

Maxima Manual

Ver. 5.29.1

Maxima is a computer algebra system, implemented in Lisp.

Maxima is derived from the Macsyma system, developed at MIT in the years 1968 through 1982 as part of Project MAC. MIT turned over a copy of the Macsyma source code to the Department of Energy in 1982; that version is now known as DOE Macsyma. A copy of DOE Macsyma was maintained by Professor William F. Schelter of the University of Texas from 1982 until his death in 2001. In 1998, Schelter obtained permission from the Department of Energy to release the DOE Macsyma source code under the GNU Public License, and in 2000 he initiated the Maxima project at SourceForge to maintain and develop DOE Macsyma, now called Maxima.

Short Contents

1	Introduction to Maxima	1
2	Bug Detection and Reporting	5
3	Help	7
4	Command Line	11
5	Data Types and Structures	29
6	Expressions	59
7	Operators	79
8	Evaluation	95
9	Simplification	105
10	Mathematical Functions	115
11	Maximas Database	133
12	Plotting	151
13	File Input and Output	173
14	Polynomials	185
15	Special Functions	207
16	Elliptic Functions	227
17	Limits	231
18	Differentiation	233
19	Integration	243
20	Equations	261
21	Differential Equations	277
22	Numerical	281
23	Matrices and Linear Algebra	289
24	Affine	309
25	itensor	311
26	ctensor	339
27	atensor	361
28	Sums, Products, and Series	365
29	Number Theory	381
30	Symmetries	393
31	Groups	407
32	Runtime Environment	409
33	Miscellaneous Options	413
34	Rules and Patterns	417
35	Sets	431
36	Function Definition	453
37	Program Flow	477
38	Debugging	489
39	asympa	495
40	augmented_lagrangian	497

41	Bernstein	499
42	bode	501
43	cobyla	503
44	contrib_ode	505
45	descriptive	511
46	diag	535
47	distrib	543
48	draw	575
49	drawdf	627
50	dynamics	631
51	ezunits	641
52	f90	655
53	finance	657
54	fractals	661
55	ggf	665
56	graphs	667
57	grobner	693
58	impdiff	699
59	interpol	701
60	lapack	707
61	lbfgs	715
62	lindstedt	721
63	linearalgebra	723
64	lsquares	735
65	minpack	743
66	makeOrders	745
67	mnewton	747
68	numericalio	749
69	opsubst	753
70	orthopoly	755
71	plotdf	765
72	romberg	771
73	simplex	775
74	simplification	777
75	solve_rec	785
76	stats	789
77	stirling	805
78	stringproc	807
79	to_poly_solve	817
80	unit	833
81	zeilberger	841
82	Indices	845
A	Function and Variable Index	847

Table of Contents

1	Introduction to Maxima.....	1
2	Bug Detection and Reporting	5
2.1	Functions and Variables for Bug Detection and Reporting	5
3	Help	7
3.1	Documentation	7
3.2	Functions and Variables for Help	7
4	Command Line	11
4.1	Introduction to Command Line	11
4.2	Functions and Variables for Command Line	11
4.3	Functions and Variables for Display	19
5	Data Types and Structures	29
5.1	Numbers	29
5.1.1	Introduction to Numbers	29
5.1.2	Functions and Variables for Numbers	29
5.2	Strings	35
5.2.1	Introduction to Strings	35
5.2.2	Functions and Variables for Strings	35
5.3	Constants	37
5.3.1	Functions and Variables for Constants	37
5.4	Lists	40
5.4.1	Introduction to Lists	40
5.4.2	Functions and Variables for Lists	40
5.5	Arrays	49
5.5.1	Functions and Variables for Arrays	49
5.6	Structures	57
5.6.1	Introduction to Structures	57
5.6.2	Functions and Variables for Structures	57
6	Expressions	59
6.1	Introduction to Expressions	59
6.2	Nouns and Verbs	59
6.3	Identifiers	60
6.4	Inequality	61
6.5	Functions and Variables for Expressions	61
7	Operators	79
7.1	Introduction to operators	79
7.2	Arithmetic operators	81
7.3	Relational operators	84
7.4	Logical operators	84
7.5	Operators for Equations	85
7.6	Assignment operators	87
7.7	User defined operators	90
8	Evaluation	95
8.1	Functions and Variables for Evaluation	95

9	Simplification	105
9.1	Functions and Variables for Simplification	105
10	Mathematical Functions	115
10.1	Functions for Numbers	115
10.2	Functions for Complex Numbers	118
10.3	Combinatorial Functions	120
10.4	Root, Exponential and Logarithmic Functions	122
10.5	Trigonometric Functions	126
10.5.1	Introduction to Trigonometric	126
10.5.2	Functions and Variables for Trigonometric	126
10.6	Random Numbers	132
11	Maximas Database	133
11.1	Introduction to Maximas Database	133
11.2	Functions and Variables for Properties	133
11.3	Functions and Variables for Facts	141
11.4	Functions and Variables for Predicates	146
12	Plotting	151
12.1	Introduction to Plotting	151
12.2	Plotting Formats	151
12.3	Functions and Variables for Plotting	152
12.4	Plotting Options	165
12.5	Gnuplot Options	169
12.6	Gnuplot_pipes Format Functions	170
13	File Input and Output	173
13.1	Comments	173
13.2	Files	173
13.3	Functions and Variables for File Input and Output	173
13.4	Functions and Variables for TeX Output	179
13.5	Functions and Variables for Fortran Output	183
14	Polynomials	185
14.1	Introduction to Polynomials	185
14.2	Functions and Variables for Polynomials	185
15	Special Functions	207
15.1	Introduction to Special Functions	207
15.2	Bessel Functions	207
15.3	Airy Functions	210
15.4	Gamma and factorial Functions	210
15.5	Exponential Integrals	220
15.6	Error Function	221
15.7	Struve Functions	222
15.8	Hypergeometric Functions	222
15.9	Parabolic Cylinder Functions	223
15.10	Functions and Variables for Special Functions	223
16	Elliptic Functions	227
16.1	Introduction to Elliptic Functions and Integrals	227
16.2	Functions and Variables for Elliptic Functions	228
16.3	Functions and Variables for Elliptic Integrals	230
17	Limits	231
17.1	Functions and Variables for Limits	231

18	Differentiation	233
18.1	Functions and Variables for Differentiation	233
19	Integration	243
19.1	Introduction to Integration	243
19.2	Functions and Variables for Integration	243
19.3	Introduction to QUADPACK	251
19.3.1	Overview	251
19.4	Functions and Variables for QUADPACK	252
20	Equations	261
20.1	Functions and Variables for Equations	261
21	Differential Equations	277
21.1	Introduction to Differential Equations	277
21.2	Functions and Variables for Differential Equations	277
22	Numerical	281
22.1	Introduction to fast Fourier transform	281
22.2	Functions and Variables for fast Fourier transform	281
22.3	Introduction to Fourier series	286
22.4	Functions and Variables for Fourier series	286
23	Matrices and Linear Algebra	289
23.1	Introduction to Matrices and Linear Algebra	289
23.1.1	Dot	289
23.1.2	Vectors	289
23.1.3	eigen	289
23.2	Functions and Variables for Matrices and Linear Algebra	290
24	Affine	309
24.1	Introduction to Affine	309
24.2	Functions and Variables for Affine	309
25	itensor	311
25.1	Introduction to itensor	311
25.1.1	New tensor notation	311
25.1.2	Indicial tensor manipulation	312
25.2	Functions and Variables for itensor	314
25.2.1	Managing indexed objects	314
25.2.2	Tensor symmetries	321
25.2.3	Indicial tensor calculus	323
25.2.4	Tensors in curved spaces	327
25.2.5	Moving frames	329
25.2.6	Torsion and nonmetricity	331
25.2.7	Exterior algebra	333
25.2.8	Exporting TeX expressions	336
25.2.9	Interfacing with ctensor	337
25.2.10	Reserved words	338

26	ctensor	339
26.1	Introduction to ctensor	339
26.2	Functions and Variables for ctensor	340
26.2.1	Initialization and setup	340
26.2.2	The tensors of curved space	343
26.2.3	Taylor series expansion	345
26.2.4	Frame fields	347
26.2.5	Algebraic classification	347
26.2.6	Torsion and nonmetricity	350
26.2.7	Miscellaneous features	350
26.2.8	Utility functions	353
26.2.9	Variables used by ctensor	357
26.2.10	Reserved names	359
26.2.11	Changes	360
27	atensor	361
27.1	Introduction to atensor	361
27.2	Functions and Variables for atensor	362
28	Sums, Products, and Series	365
28.1	Sums and Products	365
28.2	Introduction to Series	368
28.3	Functions and Variables for Series	368
28.4	Poisson series	378
29	Number Theory	381
29.1	Functions and Variables for Number Theory	381
30	Symmetries	393
30.1	Introduction to Symmetries	393
30.2	Functions and Variables for Symmetries	393
30.2.1	Changing bases	393
30.2.2	Changing representations	396
30.2.3	Groups and orbits	397
30.2.4	Partitions	400
30.2.5	Polynomials and their roots	400
30.2.6	Resolvents	401
30.2.7	Miscellaneous	406
31	Groups	407
31.1	Functions and Variables for Groups	407
32	Runtime Environment	409
32.1	Introduction for Runtime Environment	409
32.2	Interrupts	409
32.3	Functions and Variables for Runtime Environment	409
33	Miscellaneous Options	413
33.1	Introduction to Miscellaneous Options	413
33.2	Share	413
33.3	Functions and Variables for Miscellaneous Options	413
34	Rules and Patterns	417
34.1	Introduction to Rules and Patterns	417
34.2	Functions and Variables for Rules and Patterns	417

35	Sets	431
35.1	Introduction to Sets	431
35.1.1	Usage	431
35.1.2	Set Member Iteration	433
35.1.3	Bugs	433
35.1.4	Authors	434
35.2	Functions and Variables for Sets	434
36	Function Definition	453
36.1	Introduction to Function Definition	453
36.2	Function	453
36.2.1	Ordinary functions	453
36.2.2	Array functions	454
36.3	Macros	454
36.4	Functions and Variables for Function Definition	457
37	Program Flow	477
37.1	Lisp and Maxima	477
37.2	Garbage Collection	478
37.3	Introduction to Program Flow	478
37.4	Functions and Variables for Program Flow	478
38	Debugging	489
38.1	Source Level Debugging	489
38.2	Keyword Commands	490
38.3	Functions and Variables for Debugging	491
39	asympt	495
39.1	Introduction to asympt	495
39.2	Functions and variables for asympt	495
40	augmented_lagrangian	497
40.1	Functions and Variables for augmented_lagrangian	497
41	Bernstein	499
41.1	Functions and Variables for Bernstein	499
42	bode	501
42.1	Functions and Variables for bode	501
43	cobyla	503
43.1	Introduction to cobyla	503
43.2	Functions and Variables for cobyla	503
43.3	Examples for cobyla	504
44	contrib_ode	505
44.1	Introduction to contrib_ode	505
44.2	Functions and Variables for contrib_ode	507
44.3	Possible improvements to contrib_ode	509
44.4	Test cases for contrib_ode	509
44.5	References for contrib_ode	509

45	descriptive	511
45.1	Introduction to descriptive	511
45.2	Functions and Variables for data manipulation	512
45.3	Functions and Variables for descriptive statistics	516
45.4	Functions and Variables for statistical graphs	527
46	diag	535
46.1	Functions and Variables for diag	535
47	distrib	543
47.1	Introduction to distrib	543
47.2	Functions and Variables for continuous distributions	545
47.3	Functions and Variables for discrete distributions	565
48	draw	575
48.1	Introduction to draw	575
48.2	Functions and Variables for draw	575
48.2.1	Scenes	575
48.2.2	Functions	575
48.2.3	Graphics options	577
48.2.4	Graphics objects	608
48.3	Functions and Variables for pictures	620
48.4	Functions and Variables for worldmap	622
48.4.1	Variables and Functions	622
48.4.2	Graphic objects	624
49	drawdf	627
49.1	Introduction to drawdf	627
49.2	Functions and Variables for drawdf	627
49.2.1	Functions	627
50	dynamics	631
50.1	Introduction to dynamics	631
50.2	Functions and Variables for dynamics	631
51	ezunits	641
51.1	Introduction to ezunits	641
51.2	Introduction to physical_constants	642
51.3	Functions and Variables for ezunits	644
52	f90	655
52.1	Functions and Variables for f90	655
53	finance	657
53.1	Introduction to finance	657
53.2	Functions and Variables for finance	657
54	fractals	661
54.1	Introduction to fractals	661
54.2	Definitions for IFS fractals	661
54.3	Definitions for complex fractals	662
54.4	Definitions for Koch snowflakes	663
54.5	Definitions for Peano maps	663
55	ggf	665
55.1	Functions and Variables for ggf	665

56	graphs	667
56.1	Introduction to graphs	667
56.2	Functions and Variables for graphs	667
56.2.1	Building graphs	667
56.2.2	Graph properties	672
56.2.3	Modifying graphs	685
56.2.4	Reading and writing to files	687
56.2.5	Visualization	687
57	grobner	693
57.1	Introduction to grobner	693
57.1.1	Notes on the grobner package	693
57.1.2	Implementations of admissible monomial orders in grobner	693
57.2	Functions and Variables for grobner	693
57.2.1	Global switches for grobner	693
57.2.2	Simple operators in grobner	694
57.2.3	Other functions in grobner	695
57.2.4	Standard postprocessing of Groebner Bases	696
58	impdiff	699
58.1	Functions and Variables for impdiff	699
59	interpol	701
59.1	Introduction to interpol	701
59.2	Functions and Variables for interpol	701
60	lapack	707
60.1	Introduction to lapack	707
60.2	Functions and Variables for lapack	707
61	lbfgs	715
61.1	Introduction to lbfgs	715
61.2	Functions and Variables for lbfgs	715
62	lindstedt	721
62.1	Functions and Variables for lindstedt	721
63	linearalgebra	723
63.1	Introduction to linearalgebra	723
63.2	Functions and Variables for linearalgebra	724
64	lsquares	735
64.1	Introduction to lsquares	735
64.2	Functions and Variables for lsquares	735
65	minpack	743
65.1	Introduction to minpack	743
65.2	Functions and Variables for minpack	743
66	makeOrders	745
66.1	Functions and Variables for makeOrders	745
67	mnewton	747
67.1	Introduction to mnewton	747
67.2	Functions and Variables for mnewton	747

68	numericalio	749
68.1	Introduction to numericalio	749
68.1.1	Plain-text input and output	749
68.1.2	Separator flag values for input	749
68.1.3	Separator flag values for output	749
68.1.4	Binary floating-point input and output	749
68.2	Functions and Variables for plain-text input and output	750
68.3	Functions and Variables for binary input and output	751
69	opsubst	753
69.1	Functions and Variables for opsubst	753
70	orthopoly	755
70.1	Introduction to orthogonal polynomials	755
70.1.1	Getting Started with orthopoly	755
70.1.2	Limitations	757
70.1.3	Floating point Evaluation	758
70.1.4	Graphics and orthopoly	759
70.1.5	Miscellaneous Functions	760
70.1.6	Algorithms	761
70.2	Functions and Variables for orthogonal polynomials	761
71	plotdf	765
71.1	Introduction to plotdf	765
71.2	Functions and Variables for plotdf	765
72	romberg	771
72.1	Functions and Variables for romberg	771
73	simplex	775
73.1	Introduction to simplex	775
73.2	Functions and Variables for simplex	775
74	simplification	777
74.1	Introduction to simplification	777
74.2	Package absimp	777
74.3	Package facexp	777
74.4	Package functs	778
74.5	Package ineq	781
74.6	Package rducon	782
74.7	Package scifac	783
74.8	Package sqdnst	783
75	solve_rec	785
75.1	Introduction to solve_rec	785
75.2	Functions and Variables for solve_rec	785
76	stats	789
76.1	Introduction to stats	789
76.2	Functions and Variables for inference_result	789
76.3	Functions and Variables for stats	791
76.4	Functions and Variables for special distributions	802
77	stirling	805
77.1	Functions and Variables for stirling	805

78	stringproc	807
78.1	Introduction to string processing	807
78.2	Functions and Variables for input and output	808
78.3	Functions and Variables for characters	810
78.4	Functions and Variables for strings	811
79	to_poly_solve	817
79.1	Functions and Variables for to_poly_solve	817
80	unit	833
80.1	Introduction to Units	833
80.2	Functions and Variables for Units	834
81	zeilberger	841
81.1	Introduction to zeilberger	841
81.1.0.1	The indefinite summation problem	841
81.1.0.2	The definite summation problem	841
81.1.1	Verbosity levels	841
81.2	Functions and Variables for zeilberger	841
81.3	General global variables	843
81.4	Variables related to the modular test	843
82	Indices	845
Appendix A Function and Variable Index		847

1 Introduction to Maxima

Start Maxima with the command "maxima". Maxima will display version information and a prompt. End each Maxima command with a semicolon. End the session with the command "quit()". Here's a sample session:

```
[wfs@chromium]$ maxima
Maxima 5.9.1 http://maxima.sourceforge.net
Using Lisp CMU Common Lisp 19a
Distributed under the GNU Public License. See the file COPYING.
Dedicated to the memory of William Schelter.
This is a development version of Maxima. The function bug_report()
provides bug reporting information.
(%i1) factor(10!);

              8 4 2
              2 3 5 7
(%o1)
(%i2) expand ((x + y)^6);
              6      5      2 4      3 3      4 2      5      6
(%o2) y  + 6 x y  + 15 x y  + 20 x y  + 15 x y  + 6 x y  + x
(%i3) factor (x^6 - 1);

              2              2
(%o3) (x - 1) (x + 1) (x  - x + 1) (x  + x + 1)
(%i4) quit();
[wfs@chromium]$
```

Maxima can search the info pages. Use the `describe` command to show information about the command or all the commands and variables containing a string. The question mark ? (exact search) and double question mark ?? (inexact search) are abbreviations for `describe`:

```
(%i1) ?? integ
0: Functions and Variables for Elliptic Integrals
1: Functions and Variables for Integration
2: Introduction to Elliptic Functions and Integrals
3: Introduction to Integration
4: askinteger (Functions and Variables for Simplification)
5: integerp (Functions and Variables for Miscellaneous Options)
6: integer_partitions (Functions and Variables for Sets)
7: integrate (Functions and Variables for Integration)
8: integrate_use_rootsof (Functions and Variables for Integration)
9: integration_constant_counter (Functions and Variables for
  Integration)
10: nonnegintegerp (Functions and Variables for linearalgebra)
Enter space-separated numbers, 'all' or 'none': 5 4
```

```
-- Function: integerp (<expr>)
Returns 'true' if <expr> is a literal numeric integer, otherwise
'false'.
```

'integerp' returns false if its argument is a symbol, even if the argument is declared integer.

Examples:

```
(%i1) integerp (0);
(%o1) true
(%i2) integerp (1);
(%o2) true
(%i3) integerp (-17);
(%o3) true
```

```

(%i4) integerp (0.0);
(%o4)                                     false
(%i5) integerp (1.0);
(%o5)                                     false
(%i6) integerp (%pi);
(%o6)                                     false
(%i7) integerp (n);
(%o7)                                     false
(%i8) declare (n, integer);
(%o8)                                     done
(%i9) integerp (n);
(%o9)                                     false

-- Function: askinteger (<expr>, integer)
-- Function: askinteger (<expr>)
-- Function: askinteger (<expr>, even)
-- Function: askinteger (<expr>, odd)
  'askinteger (<expr>, integer)' attempts to determine from the
  'assume' database whether <expr> is an integer. 'askinteger'
  prompts the user if it cannot tell otherwise, and attempt to
  install the information in the database if possible. 'askinteger
  (<expr>)' is equivalent to 'askinteger (<expr>, integer)'.

  'askinteger (<expr>, even)' and 'askinteger (<expr>, odd)'
  likewise attempt to determine if <expr> is an even integer or odd
  integer, respectively.

```

```

(%o1)                                     true

```

To use a result in later calculations, you can assign it to a variable or refer to it by its automatically supplied label. In addition, % refers to the most recent calculated result:

```

(%i1) u: expand ((x + y)^6);
          6      5      2 4      3 3      4 2      5      6
(%o1) y  + 6 x y  + 15 x  y  + 20 x  y  + 15 x  y  + 6 x  y + x
(%i2) diff (u, x);
          5      4      2 3      3 2      4      5
(%o2) 6 y  + 30 x y  + 60 x  y  + 60 x  y  + 30 x  y + 6 x
(%i3) factor (%o2);
          5
(%o3) 6 (y + x)

```

Maxima knows about complex numbers and numerical constants:

```

(%i1) cos(%pi);
(%o1) - 1
(%i2) exp(%i*%pi);
(%o2) - 1

```

Maxima can do differential and integral calculus:

```

(%i1) u: expand ((x + y)^6);
          6      5      2 4      3 3      4 2      5      6
(%o1) y  + 6 x y  + 15 x  y  + 20 x  y  + 15 x  y  + 6 x  y + x
(%i2) diff (%o1, x);
          5      4      2 3      3 2      4      5
(%o2) 6 y  + 30 x y  + 60 x  y  + 60 x  y  + 30 x  y + 6 x
(%i3) integrate (1/(1 + x^3), x);
          2 x - 1
          2      atan(-----)
          log(x  - x + 1)      sqrt(3)      log(x + 1)
(%o3) - ----- + ----- + -----

```


6

 $\sqrt{3}$

3

Maxima can solve linear systems and cubic equations:


```
(%i1) linsolve ([3*x + 4*y = 7, 2*x + a*y = 13], [x, y]);
(%o1)          7 a - 52      25
      [x = -----, y = -----]
          3 a - 8      3 a - 8
(%i2) solve (x^3 - 3*x^2 + 5*x = 15, x);
(%o2)      [x = - sqrt(5) %i, x = sqrt(5) %i, x = 3]
```

Maxima can solve nonlinear sets of equations. Note that if you don't want a result printed, you can finish your command with \$ instead of ;.


```
(%i1) eq_1: x^2 + 3*x*y + y^2 = 0$
(%i2) eq_2: 3*x + y = 1$
(%i3) solve ([eq_1, eq_2]);
(%o3) [[y = -  $\frac{3\sqrt{5} + 7}{2}$ , x =  $\frac{\sqrt{5} + 3}{2}$ ],
      [y =  $\frac{3\sqrt{5} - 7}{2}$ , x = -  $\frac{\sqrt{5} - 3}{2}$ ]]
```

Maxima can generate plots of one or more functions:

```
(%i1) plot2d (sin(x)/x, [x, -20, 20])$
```




```
(%i2) plot2d ([atan(x), erf(x), tanh(x)], [x, -5, 5], [y, -1.5, 2])$
```



```
(%i3) plot3d (sin(sqrt(x^2 + y^2))/sqrt(x^2 + y^2),  
[x, -12, 12], [y, -12, 12])$
```

$$\sin(\sqrt{y^2+x^2})/\sqrt{y^2+x^2}$$



2 Bug Detection and Reporting

2.1 Functions and Variables for Bug Detection and Reporting

run_testsuite ([*options*]) Function

Run the Maxima test suite. Tests producing the desired answer are considered “passes,” as are tests that do not produce the desired answer, but are marked as known bugs.

run_testsuite takes the following optional keyword arguments

display_all Display all tests. Normally, the tests are not displayed, unless the test fails. (Defaults to **false**).

display_known_bugs

Displays tests that are marked as known bugs. (Default is **false**).

tests This is a single test or a list of tests that should be run. Each test can be specified by either a string or a symbol. By default, all tests are run. The complete set of tests is specified by **testsuite_files**.

time Display time information. If **true**, the time taken for each test file is displayed. If **all**, the time for each individual test is shown if **display_all** is **true**. The default is **false**, so no timing information is shown.

For example **run_testsuite(display_known_bugs = true, tests=[rtest5])** runs just test **rtest5** and displays the test that are marked as known bugs.

run_testsuite(display_all = true, tests=["rtest1", rtest1a]) will run tests **rtest1** and **rtest2**, and displays each test.

run_testsuite changes the Maxima environment. Typically a test script executes **kill** to establish a known environment (namely one without user-defined functions and variables) and then defines functions and variables appropriate to the test.

run_testsuite returns **done**.

testsuite_files Option variable

testsuite_files is the set of tests to be run by **run_testsuite**. It is a list of names of the files containing the tests to run. If some of the tests in a file are known to fail, then instead of listing the name of the file, a list containing the file name and the test numbers that fail is used.

For example, this is a part of the default set of tests:

```
["rtest13s", ["rtest14", 57, 63]]
```

This specifies the testsuite consists of the files "rtest13s" and "rtest14", but "rtest14" contains two tests that are known to fail: 57 and 63.

bug_report () Function

Prints out Maxima and Lisp version numbers, and gives a link to the Maxima project bug report web page. The version information is the same as reported by **build_info**.

When a bug is reported, it is helpful to copy the Maxima and Lisp version information into the bug report.

bug_report returns an empty string "".

build_info () Function

Returns a summary of the parameters of the Maxima build, as a Maxima structure (defined by **defstruct**). The fields of the structure are: **version**, **timestamp**, **host**, **lisp_name**, and **lisp_version**. When the pretty-printer is enabled (via **display2d**), the structure is displayed as a short table.

See also **bug_report**.

Examples:

```

(%i1) build_info ();
(%o1)
Maxima version: "5.26.0_16_gb72c64c_dirty"
Maxima build date: "2012-01-29 12:29:04"
Host type: "i686-pc-linux-gnu"
Lisp implementation type: "CMU Common Lisp"
Lisp implementation version: "CVS release-19a 19a-release-20040728 + minimal deb
(%i2) x : build_info ()$
(%i3) x@version;
(%o3)
5.26.0_16_gb72c64c_dirty
(%i4) x@timestamp;
(%o4)
2012-01-29 12:29:04
(%i5) x@host;
(%o5)
i686-pc-linux-gnu
(%i6) x@lisp_name;
(%o6)
CMU Common Lisp
(%i7) x@lisp_version;
(%o7)
CVS release-19a 19a-release-20040728 + minimal debian patches
(%i8) x;
(%o8)
Maxima version: "5.26.0_16_gb72c64c_dirty"
Maxima build date: "2012-01-29 12:29:04"
Host type: "i686-pc-linux-gnu"
Lisp implementation type: "CMU Common Lisp"
Lisp implementation version: "CVS release-19a 19a-release-20040728 + minimal deb

```

3 Help

3.1 Documentation

The Maxima on-line user's manual can be viewed in different forms. From the Maxima interactive prompt, the user's manual is viewed as plain text by the `? command` (i.e., the `describe` function). The user's manual is viewed as `info` hypertext by the `info` viewer program and as a web page by any ordinary web browser.

`example` displays examples for many Maxima functions. For example,

```
(%i1) example (integrate);
```

yields

```
(%i2) test(f):=block([u],u:integrate(f,x),ratsimp(f-diff(u,x)))
(%o2) test(f) := block([u], u : integrate(f, x),
                                ratsimp(f - diff(u, x)))

(%i3) test(sin(x))
(%o3)                                     0
(%i4) test(1/(x+1))
(%o4)                                     0
(%i5) test(1/(x^2+1))
(%o5)                                     0
```

and additional output.

3.2 Functions and Variables for Help

apropos (*string*) Function

Searches for Maxima names which have *string* appearing anywhere within them. Thus, `apropos (exp)` returns a list of all the flags and functions which have `exp` as part of their names, such as `expand`, `exp`, and `exponentialize`. Thus if you can only remember part of the name of something you can use this command to find the rest of the name. Similarly, you could say `apropos (tr_)` to find a list of many of the switches relating to the translator, most of which begin with `tr_`.

`apropos("")` returns a list with all Maxima names.

`apropos` returns the empty list `[]`, if no name is found.

Example:

Show all Maxima symbols which have "gamma" in the name:

```
(%i1) apropos("gamma");
(%o1) [%gamma, gamma, gammalim, gamma_expand, gamma_greek,
gamma_incomplete, gamma_incomplete_generalized,
gamma_incomplete_regularized, Gamma, log_gamma, makegamma,
prefer_gamma_incomplete,
gamma_incomplete_generalized_regularized]
```

demo (*filename*) Function

Evaluates Maxima expressions in *filename* and displays the results. `demo` pauses after evaluating each expression and continues after the user enters a carriage return. (If running in Xmaxima, `demo` may need to see a semicolon `;` followed by a carriage return.)

`demo` searches the list of directories `file_search_demo` to find *filename*. If the file has the suffix `dem`, the suffix may be omitted. See also `file_search`.

`demo` evaluates its argument. `demo` returns the name of the demonstration file.

Example:

```
(%i1) demo ("disol");

batching /home/wfs/maxima/share/simplification/disol.dem
At the _ prompt, type ';' followed by enter to get next demo
(%i2)                                load(disol)

-
(%i3)          exp1 : a (e (g + f) + b (d + c))
(%o3)          a (e (g + f) + b (d + c))

-
(%i4)          disolate(exp1, a, b, e)
(%t4)          d + c

(%t5)          g + f

(%o5)          a (%t5 e + %t4 b)

-
```

describe (<i>string</i>)	Function
describe (<i>string</i> , <i>exact</i>)	Function
describe (<i>string</i> , <i>inexact</i>)	Function

describe(*string*) is equivalent to **describe**(*string*, *exact*).

describe(*string*, *exact*) finds an item with title equal (case-insensitive) to *string*, if there is any such item.

describe(*string*, *inexact*) finds all documented items which contain *string* in their titles. If there is more than one such item, Maxima asks the user to select an item or items to display.

At the interactive prompt, ? foo (with a space between ? and foo) is equivalent to **describe**("foo", *exact*), and ?? foo is equivalent to **describe**("foo", *inexact*).

describe("", *inexact*) yields a list of all topics documented in the on-line manual.

describe quotes its argument. **describe** returns **true** if some documentation is found, otherwise **false**.

See also [Section 3.1 \[Documentation\]](#), page 7.

Example:

```
(%i1) ?? integ
0: Functions and Variables for Elliptic Integrals
1: Functions and Variables for Integration
2: Introduction to Elliptic Functions and Integrals
3: Introduction to Integration
4: askinteger (Functions and Variables for Simplification)
5: integerp (Functions and Variables for Miscellaneous Options)
6: integer_partitions (Functions and Variables for Sets)
7: integrate (Functions and Variables for Integration)
8: integrate_use_rootsof (Functions and Variables for
Integration)
9: integration_constant_counter (Functions and Variables for
Integration)
10: nonnegintegerp (Functions and Variables for linearalgebra)
Enter space-separated numbers, 'all' or 'none': 7 8

-- Function: integrate (<expr>, <x>)
-- Function: integrate (<expr>, <x>, <a>, <b>)
Attempts to symbolically compute the integral of <expr> with
```

respect to $\langle x \rangle$. 'integrate ($\langle \text{expr} \rangle$, $\langle x \rangle$)' is an indefinite integral, while 'integrate ($\langle \text{expr} \rangle$, $\langle x \rangle$, $\langle a \rangle$, $\langle b \rangle$)' is a definite integral, [...]

-- Option variable: integrate_use_rootsof
Default value: 'false'

When 'integrate_use_rootsof' is 'true' and the denominator of a rational function cannot be factored, 'integrate' returns the integral in a form which is a sum over the roots (not yet known) of the denominator.
[...]

In this example, items 7 and 8 were selected (output is shortened as indicated by [...]). All or none of the items could have been selected by entering **all** or **none**, which can be abbreviated **a** or **n**, respectively.

example (<i>topic</i>)	Function
example ()	Function

example (*topic*) displays some examples of *topic*, which is a symbol or a string. To get examples for operators like **if**, **do**, or **lambda** the argument must be a string, e.g. **example** ("do"). **example** is not case sensitive. Most topics are function names.

example () returns the list of all recognized topics.

The name of the file containing the examples is given by the global option variable **manual_demo**, which defaults to "manual.demo".

example quotes its argument. **example** returns **done** unless no examples are found or there is no argument, in which case **example** returns the list of all recognized topics.

Examples:

```
(%i1) example(append);
(%i2) append([x+y,0,-3.2],[2.5e+20,x])
(%o2)          [y + x, 0, - 3.2, 2.5e+20, x]
(%o2)                                     done
(%i3) example("lambda");

(%i4) lambda([x,y,z],z^2+y^2+x^2)

(%o4)          lambda([x, y, z], z2 + y2 + x2)
(%i5) %(1,2,a)

(%o5)          a2 + 5
(%i6) a+2+1
(%o6)          a + 3
(%o6)                                     done
```

manual_demo	Option variable
--------------------	-----------------

Default value: "manual.demo"

manual_demo specifies the name of the file containing the examples for the function **example**. See **example**.

4 Command Line

4.1 Introduction to Command Line

4.2 Functions and Variables for Command Line

-- System variable

-- is the input expression currently being evaluated. That is, while an input expression *expr* is being evaluated, -- is *expr*.

-- is assigned the input expression before the input is simplified or evaluated. However, the value of -- is simplified (but not evaluated) when it is displayed.

-- is recognized by **batch** and **load**. In a file processed by **batch**, -- has the same meaning as at the interactive prompt. In a file processed by **load**, -- is bound to the input expression most recently entered at the interactive prompt or in a batch file; -- is not bound to the input expressions in the file being processed. In particular, when **load** (*filename*) is called from the interactive prompt, -- is bound to **load** (*filename*) while the file is being processed.

See also _ and %.

Examples:

```
(%i1) print ("I was called as", --);
I was called as print(I was called as, --)
(%o1)          print(I was called as, --)
(%i2) foo (--);
(%o2)          foo(foo(--))
(%i3) g (x) := (print ("Current input expression =", --), 0);
(%o3) g(x) := (print("Current input expression =", --), 0)
(%i4) [aa : 1, bb : 2, cc : 3];
(%o4)          [1, 2, 3]
(%i5) (aa + bb + cc)/(dd + ee + g(x));
              cc + bb + aa
Current input expression = -----
              g(x) + ee + dd
                      6
(%o5)          -----
              ee + dd
```

- System variable

_ is the most recent input expression (e.g., %i1, %i2, %i3, ...).

_ is assigned the input expression before the input is simplified or evaluated. However, the value of _ is simplified (but not evaluated) when it is displayed.

_ is recognized by **batch** and **load**. In a file processed by **batch**, _ has the same meaning as at the interactive prompt. In a file processed by **load**, _ is bound to the input expression most recently evaluated at the interactive prompt or in a batch file; _ is not bound to the input expressions in the file being processed.

See also -- and %.

Examples:

```
(%i1) 13 + 29;
(%o1) 42
(%i2) :lisp $_
((MPLUS) 13 29)
(%i2) _;
(%o2) 42
```

```

(%i3) sin (%pi/2);
(%o3)                                     1
(%i4) :lisp $_
((%SIN) ((MQUOTIENT) $$PI 2))
(%i4) _;
(%o4)                                     1
(%i5) a: 13$
(%i6) b: 29$
(%i7) a + b;
(%o7)                                     42
(%i8) :lisp $_
((MPLUS) $A $B)
(%i8) _;
(%o8)                                     b + a
(%i9) a + b;
(%o9)                                     42
(%i10) ev (_);
(%o10)                                    42

```

%

System variable

% is the output expression (e.g., %o1, %o2, %o3, ...) most recently computed by Maxima, whether or not it was displayed.

% is recognized by `batch` and `load`. In a file processed by `batch`, **%** has the same meaning as at the interactive prompt. In a file processed by `load`, **%** is bound to the output expression most recently computed at the interactive prompt or in a batch file; **%** is not bound to output expressions in the file being processed.

See also `_`, `%%`, and `%th`.

%%

System variable

In compound statements, namely `block`, `lambda`, or `(s_1, ..., s_n)`, **%%** is the value of the previous statement.

At the first statement in a compound statement, or outside of a compound statement, **%%** is undefined.

%% is recognized by `batch` and `load`, and it has the same meaning as at the interactive prompt.

See also **%**.

Examples:

The following two examples yield the same result.

```

(%i1) block (integrate (x^5, x), ev (%%, x=2) - ev (%%, x=1));
(%o1)                                     21
--
2
(%i2) block ([prev], prev: integrate (x^5, x),
             ev (prev, x=2) - ev (prev, x=1));
(%o2)                                     21
--
2

```

A compound statement may comprise other compound statements. Whether a statement be simple or compound, **%%** is the value of the previous statement.

```

(%i3) block (block (a^n, %%*42), %%/6);
(%o3)                                     n
7 a

```

Within a compound statement, the value of `%%` may be inspected at a break prompt, which is opened by executing the `break` function. For example, entering `%%;` in the following example yields 42.

```
(%i4) block (a: 42, break ())$
```

```
Entering a Maxima break point. Type 'exit;' to resume.
```

```
_%%;
```

```
42
```

```
-
```

`%th` (*i*)

Function

The value of the *i*'th previous output expression. That is, if the next expression to be computed is the *n*'th output, `%th` (*m*) is the (*n* - *m*)'th output.

`%th` is recognized by `batch` and `load`. In a file processed by `batch`, `%th` has the same meaning as at the interactive prompt. In a file processed by `load`, `%th` refers to output expressions most recently computed at the interactive prompt or in a batch file; `%th` does not refer to output expressions in the file being processed.

See also `%` and `%%`.

Example:

`%th` is useful in `batch` files or for referring to a group of output expressions. This example sets `s` to the sum of the last five output expressions.

```
(%i1) 1;2;3;4;5;
```

```
(%o1) 1
```

```
(%o2) 2
```

```
(%o3) 3
```

```
(%o4) 4
```

```
(%o5) 5
```

```
(%i6) block (s: 0, for i:1 thru 5 do s: s + %th(i), s);
```

```
(%o6) 15
```

`?`

Special symbol

As prefix to a function or variable name, `?` signifies that the name is a Lisp name, not a Maxima name. For example, `?round` signifies the Lisp function `ROUND`. See [Section 37.1 \[Lisp and Maxima\], page 477](#) for more on this point.

The notation `? word` (a question mark followed a word, separated by whitespace) is equivalent to `describe("word")`. The question mark must occur at the beginning of an input line; otherwise it is not recognized as a request for documentation. See also `describe`.

`??`

Special symbol

The notation `?? word` (`??` followed a word, separated by whitespace) is equivalent to `describe("word", inexact)`. The question mark must occur at the beginning of an input line; otherwise it is not recognized as a request for documentation. See also `describe`.

`inchar`

Option variable

Default value: `%i`

`inchar` is the prefix of the labels of expressions entered by the user. Maxima automatically constructs a label for each input expression by concatenating `inchar` and `linenum`.

`inchar` may be assigned any string or symbol, not necessarily a single character. Because Maxima internally takes into account only the first char of the prefix, the prefixes `inchar`, `outchar`, and `linechar` should have a different first char. Otherwise some commands like `kill(inlables)` do not work as expected.

See also `labels`.

Example:

```
(%i1) inchar: "input";
(%o1)                                     input
(input2) expand((a+b)^3);
                                     3      2      2      3
(%o2)                                b  + 3 a b  + 3 a  b + a
(input3)
```

infolists

System variable

Default value: []

infolists is a list of the names of all of the information lists in Maxima. These are:**labels** All bound %i, %o, and %t labels.**values** All bound atoms which are user variables, not Maxima options or switches, created by : or :: or functional binding.**functions** All user-defined functions, created by := or **define**.**arrays** All declared and undeclared arrays, created by :, ::, or :=.**macros** All user-defined macro functions, created by ::=.**myoptions** All options ever reset by the user (whether or not they are later reset to their default values).**rules** All user-defined pattern matching and simplification rules, created by **tellsimp**, **tellsimpafter**, **defmatch**, or **defrule**.**aliases** All atoms which have a user-defined alias, created by the **alias**, **ordergreat**, **orderless** functions or by declaring the atom as a **noun** with **declare**.**dependencies** All atoms which have functional dependencies, created by the **depends** or **gradef** functions.**gradefs** All functions which have user-defined derivatives, created by the **gradef** function.**props** All atoms which have any property other than those mentioned above, such as properties established by **atvalue** or **matchdeclare**, etc., as well as properties established in the **declare** function.**let_rule_packages** All user-defined **let** rule packages plus the special package **default_let_rule_package**. (**default_let_rule_package** is the name of the rule package used when one is not explicitly set by the user.)

kill (<i>a₁</i> , ..., <i>a_n</i>)	Function
kill (<i>labels</i>)	Function
kill (<i>inlabels</i> , <i>outlabels</i> , <i>linelabels</i>)	Function
kill (<i>n</i>)	Function
kill (<i>[m, n]</i>)	Function
kill (<i>values</i> , <i>functions</i> , <i>arrays</i> , ...)	Function
kill (<i>all</i>)	Function
kill (<i>allbut</i> (<i>a₁</i> , ..., <i>a_n</i>))	Function

Removes all bindings (value, function, array, or rule) from the arguments *a₁*, ..., *a_n*. An argument *a_k* may be a symbol or a single array element. When *a_k* is a single array element, **kill** unbinds that element without affecting any other elements of the array.

Several special arguments are recognized. Different kinds of arguments may be combined, e.g., **kill** (*inlabels*, *functions*, *allbut* (*foo*, *bar*)).

kill (*labels*) unbinds all input, output, and intermediate expression labels created so far. **kill** (*inlabels*) unbinds only input labels which begin with the current value of *inchar*. Likewise, **kill** (*outlabels*) unbinds only output labels which begin with the current value of *outchar*, and **kill** (*linelabels*) unbinds only intermediate expression labels which begin with the current value of *linechar*.

kill (*n*), where *n* is an integer, unbinds the *n* most recent input and output labels.

kill (*[m, n]*) unbinds input and output labels *m* through *n*.

kill (*infolist*), where *infolist* is any item in *infolists* (such as *values*, *functions*, or *arrays*) unbinds all items in *infolist*. See also *infolists*.

kill (*all*) unbinds all items on all *infolists*. **kill** (*all*) does not reset global variables to their default values; see *reset* on this point.

kill (*allbut* (*a₁, ..., a_n*)) unbinds all items on all *infolists* except for *a₁, ..., a_n*. **kill** (*allbut* (*infolist*)) unbinds all items except for the ones on *infolist*, where *infolist* is *values*, *functions*, *arrays*, etc.

The memory taken up by a bound property is not released until all symbols are unbound from it. In particular, to release the memory taken up by the value of a symbol, one unbinds the output label which shows the bound value, as well as unbinding the symbol itself.

kill quotes its arguments. The quote-quote operator `''` defeats quotation.

kill (*symbol*) unbinds all properties of *symbol*. In contrast, the functions *remvalue*, *remfunction*, *remarray*, and *remrule* unbind a specific property.

kill always returns *done*, even if an argument has no binding.

labels (*symbol*)

Function

labels

System variable

Returns the list of input, output, or intermediate expression labels which begin with *symbol*. Typically *symbol* is the value of *inchar*, *outchar*, or *linechar*. The label character may be given with or without a percent sign, so, for example, *i* and *%i* yield the same result.

If no labels begin with *symbol*, **labels** returns an empty list.

The function **labels** quotes its argument. The quote-quote operator `''` defeats quotation. For example, **labels** (`''inchar`) returns the input labels which begin with the current input label character.

The variable **labels** is the list of input, output, and intermediate expression labels, including all previous labels if *inchar*, *outchar*, or *linechar* were redefined.

By default, Maxima displays the result of each user input expression, giving the result an output label. The output display is suppressed by terminating the input with *\$* (dollar sign) instead of *;* (semicolon). An output label is constructed and bound to the result, but not displayed, and the label may be referenced in the same way as displayed output labels. See also *%*, *%%*, and *%th*.

Intermediate expression labels can be generated by some functions. The option variable *programmode* controls whether *solve* and some other functions generate intermediate expression labels instead of returning a list of expressions. Some other functions, such as *ldisplay*, always generate intermediate expression labels.

See also *inchar*, *outchar*, *linechar*, and *infolists*.

linechar

Option variable

Default value: *%t*

linechar is the prefix of the labels of intermediate expressions generated by Maxima. Maxima constructs a label for each intermediate expression (if displayed) by concatenating *linechar* and *linenum*.

linechar may be assigned any string or symbol, not necessarily a single character. Because Maxima internally takes into account only the first char of the prefix, the prefixes

`inchar`, `outchar`, and `linechar` should have a different first char. Otherwise some commands like `kill(inlables)` do not work as expected.

Intermediate expressions might or might not be displayed. See `programmode` and `labels`.

linenum

System variable

The line number of the current pair of input and output expressions.

myoptions

System variable

Default value: `[]`

`myoptions` is the list of all options ever reset by the user, whether or not they get reset to their default value.

nolabels

Option variable

Default value: `false`

When `nolabels` is `true`, input and output result labels (`%i` and `%o`, respectively) are displayed, but the labels are not bound to results, and the labels are not appended to the `labels` list. Since labels are not bound to results, garbage collection can recover the memory taken up by the results.

Otherwise input and output result labels are bound to results, and the labels are appended to the `labels` list.

Intermediate expression labels (`%t`) are not affected by `nolabels`; whether `nolabels` is `true` or `false`, intermediate expression labels are bound and appended to the `labels` list.

See also `batch`, `load`, and `labels`.

optionset

Option variable

Default value: `false`

When `optionset` is `true`, Maxima prints out a message whenever a Maxima option is reset. This is useful if the user is doubtful of the spelling of some option and wants to make sure that the variable he assigned a value to was truly an option variable.

Example:

```
(%i1) optionset:true;
assignment: assigning to option optionset
(%o1)                                     true
(%i2) gamma_expand:true;
assignment: assigning to option gamma_expand
(%o2)                                     true
```

outchar

Option variable

Default value: `%o`

`outchar` is the prefix of the labels of expressions computed by Maxima. Maxima automatically constructs a label for each computed expression by concatenating `outchar` and `linenum`.

`outchar` may be assigned any string or symbol, not necessarily a single character. Because Maxima internally takes into account only the first char of the prefix, the prefixes `inchar`, `outchar` and `linechar` should have a different first char. Otherwise some commands like `kill(inlables)` do not work as expected.

See also `labels`.

Example:

```
(%i1) outchar: "output";
(output1)                                     output
(%i2) expand((a+b)^3);
              3      2      2      3
(output2)      b  + 3 a b  + 3 a  b  + a
(%i3)
```

playback ()	Function
playback (<i>n</i>)	Function
playback (<i>[m, n]</i>)	Function
playback (<i>[m]</i>)	Function
playback (<i>input</i>)	Function
playback (<i>slow</i>)	Function
playback (<i>time</i>)	Function
playback (<i>grind</i>)	Function

Displays input, output, and intermediate expressions, without recomputing them. **playback** only displays the expressions bound to labels; any other output (such as text printed by **print** or **describe**, or error messages) is not displayed. See also **labels**.

playback quotes its arguments. The quote-quote operator `''` defeats quotation. **playback** always returns **done**.

playback () (with no arguments) displays all input, output, and intermediate expressions generated so far. An output expression is displayed even if it was suppressed by the `$` terminator when it was originally computed.

playback (*n*) displays the most recent *n* expressions. Each input, output, and intermediate expression counts as one.

playback (*[m, n]*) displays input, output, and intermediate expressions with numbers from *m* through *n*, inclusive.

playback (*[m]*) is equivalent to **playback** (*[m, m]*); this usually prints one pair of input and output expressions.

playback (*input*) displays all input expressions generated so far.

playback (*slow*) pauses between expressions and waits for the user to press **enter**. This behavior is similar to **demo**. **playback** (*slow*) is useful in conjunction with **save** or **stringout** when creating a secondary-storage file in order to pick out useful expressions.

playback (*time*) displays the computation time for each expression.

playback (*grind*) displays input expressions in the same format as the **grind** function. Output expressions are not affected by the **grind** option. See **grind**.

Arguments may be combined, e.g., **playback** (*[5, 10], grind, time, slow*).

prompt	Option variable
---------------	-----------------

Default value: `_`

prompt is the prompt symbol of the **demo** function, **playback** (*slow*) mode, and the Maxima break loop (as invoked by **break**).

quit ()	Function
----------------	----------

Terminates the Maxima session. Note that the function must be invoked as **quit()**; or **quit()**`$`, not **quit** by itself.

To stop a lengthy computation, type **control-C**. The default action is to return to the Maxima prompt. If `*debugger-hook*` is `nil`, **control-C** opens the Lisp debugger. See also [Chapter 38 \[Debugging\]](#), page 489.

read (<i>expr_1, ..., expr_n</i>)	Function
--	----------

Prints *expr_1, ..., expr_n*, then reads one expression from the console and returns the evaluated expression. The expression is terminated with a semicolon ; or dollar sign `$`.

See also **readonly**

Example:

```
(%i1) foo: 42$
(%i2) foo: read ("foo is", foo, " -- enter new value.")$
foo is 42 -- enter new value.
(a+b)^3;
(%i3) foo;

                                     3
(%o3)                               (b + a)
```


readonly (*expr_1*, ..., *expr_n*) Function

Prints *expr_1*, ..., *expr_n*, then reads one expression from the console and returns the expression (without evaluation). The expression is terminated with a ; (semicolon) or \$ (dollar sign).

See also `read`.

Examples:

```
(%i1) aa: 7$
(%i2) foo: readonly ("Enter an expression:");
Enter an expression:
2^aa;

                                aa
(%o2)                                2
(%i3) foo: read ("Enter an expression:");
Enter an expression:
2^aa;
(%o3)                                128
```

reset () Function

Resets many global variables and options, and some other variables, to their default values.

`reset` processes the variables on the Lisp list `*variable-initial-values*`. The Lisp macro `defmvar` puts variables on this list (among other actions). Many, but not all, global variables and options are defined by `defmvar`, and some variables defined by `defmvar` are not global variables or options.

showtime Option variable

Default value: `false`

When `showtime` is `true`, the computation time and elapsed time is printed with each output expression.

The computation time is always recorded, so `time` and `playback` can display the computation time even when `showtime` is `false`.

See also `timer`.

to_lisp () Function

Enters the Lisp system under Maxima. (`to-maxima`) returns to Maxima.

Example:

Define a function and enter the Lisp system under Maxima. The definition is inspected on the property list, then the function definition is extracted, factored and stored in the variable `$result`. The variable can be used in Maxima after returning to Maxima.

```
(%i1) f(x):=x^2+x;

                                2
(%o1)                                f(x) := x  + x
(%i2) to_lisp();
Type (to-maxima) to restart, ($quit) to quit Maxima.
MAXIMA> (symbol-plist '$f)
(MPROPS (NIL MEXPR ((LAMBDA) ((MLIST) $X)
                                ((MPLUS) ((MEXPT) $X 2) $X))))
MAXIMA> (setq $result ($factor (caddr (mget '$f 'mexpr))))
((MTIMES SIMP FACTORED) $X ((MPLUS SIMP IRREDUCIBLE) 1 $X))
MAXIMA> (to-maxima)
Returning to Maxima
(%o2)                                true
(%i3) result;
(%o3)                                x (x + 1)
```


values

System variable

Initial value: []

values is a list of all bound user variables (not Maxima options or switches). The list comprises symbols bound by `:`, or `::`.

If the value of a variable is removed with the commands **kill**, **remove**, or **remvalue** the variable is deleted from **values**.

See **functions** for a list of user defined functions.

Examples:

First, **values** shows the symbols **a**, **b**, and **c**, but not **d**, it is not bound to a value, and not the user function **f**. The values are removed from the variables. **values** is the empty list.

```
(%i1) [a:99, b::a-90, c:a-b, d, f(x):= x^2];
(%o1) [99, 9, 90, d, f(x) := x^2]
(%i2) values;
(%o2) [a, b, c]
(%i3) [kill(a), remove(b,value), remvalue(c)];
(%o3) [done, done, [c]]
(%i4) values;
(%o4) []
```

4.3 Functions and Variables for Display**%edispflag**

Option variable

Default value: false

When **%edispflag** is **true**, Maxima displays **%e** to a negative exponent as a quotient. For example, **%e^{-x}** is displayed as **1/%e^x**. See also **exptdispflag**.

Example:

```
(%i1) %e^-10;
(%o1) %e^-10
(%i2) %edispflag:true$
(%i3) %e^-10;
(%o3) 1
      ----
      10
      %e
```

absboxchar

Option variable

Default value: !

absboxchar is the character used to draw absolute value signs around expressions which are more than one line tall.

Example:

```
(%i1) abs((x^3+1));
(%o1) ! 3      !
      !x  + 1!
```

disp (expr_1, expr_2, ...)

Function

is like **display** but only the value of the arguments are displayed rather than equations. This is useful for complicated arguments which don't have names or where only the value of the argument is of interest and not the name.

See also **ldisp** and **print**.

Example:

```
(%i1) b[1,2]:x-x^2$
(%i2) x:123$
(%i3) disp(x, b[1,2], sin(1.0));
```

$$x = 123$$

$$b_{1,2} = x - x^2$$

$$\sin(1.0) = .8414709848078965$$

```
(%o3) done
```

display (*expr_1*, *expr_2*, ...) Function

Displays equations whose left side is *expr_i* unevaluated, and whose right side is the value of the expression centered on the line. This function is useful in blocks and **for** statements in order to have intermediate results displayed. The arguments to **display** are usually atoms, subscripted variables, or function calls.

See also **ldisplay**, **disp**, and **ldisp**.

Example:

```
(%i1) b[1,2]:x-x^2$
(%i2) x:123$
(%i3) display(x, b[1,2], sin(1.0));
```

$$x = 123$$

$$b_{1,2} = x - x^2$$

$$\sin(1.0) = .8414709848078965$$

```
(%o3) done
```

display2d Option variable

Default value: **true**

When **display2d** is **false**, the console display is a string (1-dimensional) form rather than a display (2-dimensional) form.

See also **leftjust** to switch between a left justified and a centered display of equations.

Example:

```
(%i1) x/(x^2+1);
```

$$\frac{x}{x^2 + 1}$$

```
(%o1)
```

```
(%i2) display2d:false$
(%i3) x/(x^2+1);
(%o3) x/(x^2+1)
```

display_format_internal Option variable

Default value: **false**

When **display_format_internal** is **true**, expressions are displayed without being transformed in ways that hide the internal mathematical representation. The display then corresponds to what **inpart** returns rather than **part**.

Examples:

User	part	inpart
a-b;	a - b	a + (- 1) b
a/b;	$\frac{a}{b}$	$\frac{- 1}{a b}$
sqrt(x);	sqrt(x)	$x^{1/2}$
X*4/3;	$\frac{4 X}{3}$	$\frac{4}{3} X$

dispterm (*expr*)

Function

Displays *expr* in parts one below the other. That is, first the operator of *expr* is displayed, then each term in a sum, or factor in a product, or part of a more general expression is displayed separately. This is useful if *expr* is too large to be otherwise displayed. For example if P1, P2, ... are very large expressions then the display program may run out of storage space in trying to display P1 + P2 + ... all at once. However, **dispterm** (P1 + P2 + ...) displays P1, then below it P2, etc. When not using **dispterm**, if an exponential expression is too wide to be displayed as A^B it appears as **expt** (A, B) (or as **ncexpt** (A, B) in the case of A^^B).

Example:

```
(%i1) dispterm(2*a*sin(x)+%e^x);
```

```
+
```

```
2 a sin(x)
```

```
  x
 %e
```

```
(%o1)
```

```
done
```

expt (*a*, *b*)

Special symbol

ncexpt (*a*, *b*)

Special symbol

If an exponential expression is too wide to be displayed as a^b it appears as **expt** (*a*, *b*) (or as **ncexpt** (*a*, *b*) in the case of $a^{^b}$).

expt and **ncexpt** are not recognized in input.

exptdispflag

Option variable

Default value: **true**

When **exptdispflag** is **true**, Maxima displays expressions with negative exponents using quotients. See also **%edispflag**.

Example:

```
(%i1) exptdispflag:true;
```

```
(%o1)
```

```
true
```

```
(%i2) 10^-x;
```

```
(%o2)
```

```
  1
 ---
  x
10
```

```
(%i3) exptdispflag:false;
```

```
(%o3)
```

```
false
```

```
(%i4) 10^-x;
```

```
(%o4)          - x
          10
```

grind (*expr*) **grind**

Function
Option variable

The function **grind** prints *expr* to the console in a form suitable for input to Maxima. **grind** always returns **done**.

When *expr* is the name of a function or macro, **grind** prints the function or macro definition instead of just the name.

See also **string**, which returns a string instead of printing its output. **grind** attempts to print the expression in a manner which makes it slightly easier to read than the output of **string**.

When the variable **grind** is **true**, the output of **string** and **stringout** has the same format as that of **grind**; otherwise no attempt is made to specially format the output of those functions. The default value of the variable **grind** is **false**.

grind can also be specified as an argument of **playback**. When **grind** is present, **playback** prints input expressions in the same format as the **grind** function. Otherwise, no attempt is made to specially format input expressions.

grind evaluates its argument.

Examples:

```
(%i1) aa + 1729;
(%o1) aa + 1729
(%i2) grind (%);
aa+1729$
(%o2) done
(%i3) [aa, 1729, aa + 1729];
(%o3) [aa, 1729, aa + 1729]
(%i4) grind (%);
[aa,1729,aa+1729]$
(%o4) done
(%i5) matrix ([aa, 17], [29, bb]);
[ aa 17 ]
(%o5) [
[ 29 bb ]
]
(%i6) grind (%);
matrix([aa,17],[29,bb])$
(%o6) done
(%i7) set (aa, 17, 29, bb);
(%o7) {17, 29, aa, bb}
(%i8) grind (%);
{17,29,aa,bb}$
(%o8) done
(%i9) exp (aa / (bb + 17)^29);
aa
-----
29
(bb + 17)
(%o9) %e
(%i10) grind (%);
%e^(aa/(bb+17)^29)$
(%o10) done
(%i11) expr: expand ((aa + bb)^10);
10 9 2 8 3 7 4 6
(%o11) bb + 10 aa bb + 45 aa bb + 120 aa bb + 210 aa bb
```

```

      5 5      6 4      7 3      8 2
+ 252 aa bb + 210 aa bb + 120 aa bb + 45 aa bb
      9      10
+ 10 aa bb + aa
(%i12) grind (expr);
bb^10+10*aa*bb^9+45*aa^2*bb^8+120*aa^3*bb^7+210*aa^4*bb^6
+252*aa^5*bb^5+210*aa^6*bb^4+120*aa^7*bb^3+45*aa^8*bb^2
+10*aa^9*bb+aa^10$
(%o12) done
(%i13) string (expr);
(%o13) bb^10+10*aa*bb^9+45*aa^2*bb^8+120*aa^3*bb^7+210*aa^4*bb^6\
+252*aa^5*bb^5+210*aa^6*bb^4+120*aa^7*bb^3+45*aa^8*bb^2+10*aa^9*\
bb+aa^10
(%i14) cholesky (A):= block ([n : length (A), L : copymatrix (A),
p : makelist (0, i, 1, length (A))], for i thru n do
for j : i thru n do
(x : L[i, j], x : x - sum (L[j, k] * L[i, k], k, 1, i - 1),
if i = j then p[i] : 1 / sqrt(x) else L[j, i] : x * p[i]),
for i thru n do L[i, i] : 1 / p[i],
for i thru n do for j : i + 1 thru n do L[i, j] : 0, L)$
(%i15) grind (cholesky);
cholesky(A):=block(
[n:length(A),L:copymatrix(A),
p:makelist(0,i,1,length(A))],
for i thru n do
(for j from i thru n do
(x:L[i,j],x:x-sum(L[j,k]*L[i,k],k,1,i-1),
if i = j then p[i]:1/sqrt(x)
else L[j,i]:x*p[i])),
for i thru n do L[i,i]:1/p[i],
for i thru n do (for j from i+1 thru n do L[i,j]:0),L)$
(%o15) done
(%i16) string (fundef (cholesky));
(%o16) cholesky(A):=block([n:length(A),L:copymatrix(A),p:makelis\
t(0,i,1,length(A))],for i thru n do (for j from i thru n do (x:L\
[i,j],x:x-sum(L[j,k]*L[i,k],k,1,i-1),if i = j then p[i]:1/sqrt(x\
) else L[j,i]:x*p[i])),for i thru n do L[i,i]:1/p[i],for i thru \
n do (for j from i+1 thru n do L[i,j]:0),L)

```

ibase

Option variable

Default value: 10

ibase is the base for integers read by Maxima.

ibase may be assigned any integer between 2 and 36 (decimal), inclusive. When **ibase** is greater than 10, the numerals comprise the decimal numerals 0 through 9 plus letters of the alphabet A, B, C, ..., as needed to make **ibase** digits in all. Letters are interpreted as digits only if the first digit is 0 through 9. Uppercase and lowercase letters are not distinguished. The numerals for base 36, the largest acceptable base, comprise 0 through 9 and A through Z.

Whatever the value of **ibase**, when an integer is terminated by a decimal point, it is interpreted in base 10.

See also **obase**.

Examples:

ibase less than 10.

```

(%i1) ibase : 2 $
(%i2) obase;

```

```
(%o2) 10
(%i3) 1111111111111111;
(%o3) 65535
```

`ibase` greater than 10. Letters are interpreted as digits only if the first digit is 0 through 9.

```
(%i1) ibase : 16 $
(%i2) obase;
(%o2) 10
(%i3) 1000;
(%o3) 4096
(%i4) abcd;
(%o4) abcd
(%i5) symbolp (abcd);
(%o5) true
(%i6) 0abcd;
(%o6) 43981
(%i7) symbolp (0abcd);
(%o7) false
```

When an integer is terminated by a decimal point, it is interpreted in base 10.

```
(%i1) ibase : 36 $
(%i2) obase;
(%o2) 10
(%i3) 1234;
(%o3) 49360
(%i4) 1234.;
(%o4) 1234
```

ldisp (*expr_1*, ..., *expr_n*)

Function

Displays expressions *expr_1*, ..., *expr_n* to the console as printed output. `ldisp` assigns an intermediate expression label to each argument and returns the list of labels.

See also `disp`, `display`, and `ldisplay`.

Examples:

```
(%i1) e: (a+b)^3;
(%o1) (b + a)^3
(%i2) f: expand (e);
(%o2) b^3 + 3 a b^2 + 3 a^2 b + a^3
(%i3) ldisp (e, f);
(%t3) (b + a)^3
(%t4) b^3 + 3 a b^2 + 3 a^2 b + a^3
(%o4) [%t3, %t4]
(%i4) %t3;
(%o4) (b + a)^3
(%i5) %t4;
(%o5) b^3 + 3 a b^2 + 3 a^2 b + a^3
```

ldisplay (*expr_1*, ..., *expr_n*)

Function

Displays expressions *expr_1*, ..., *expr_n* to the console as printed output. Each expression is printed as an equation of the form *lhs* = *rhs* in which *lhs* is one of the arguments of **ldisplay** and *rhs* is its value. Typically each argument is a variable. **ldisp** assigns an intermediate expression label to each equation and returns the list of labels.

See also **display**, **disp**, and **ldisp**.

Examples:

```
(%i1) e: (a+b)^3;
(%o1)
              3
          (b + a)
(%i2) f: expand (e);
(%o2)
          3      2      2      3
      b  + 3 a b  + 3 a  b + a
(%i3) ldisplay (e, f);
(%t3)
              3
          e = (b + a)
(%t4)
          3      2      2      3
      f = b  + 3 a b  + 3 a  b + a
(%o4)
          [%t3, %t4]
(%i4) %t3;
(%o4)
              3
          e = (b + a)
(%i5) %t4;
(%o5)
          3      2      2      3
      f = b  + 3 a b  + 3 a  b + a
```

leftjust

Option variable

Default value: **false**

When **leftjust** is **true**, equations in 2D-display are drawn left justified rather than centered.

See also **display2d** to switch between 1D- and 2D-display.

Example:

```
(%i1) expand((x+1)^3);
(%o1)
          3      2
      x  + 3 x  + 3 x + 1
(%i2) leftjust:true$
(%i3) expand((x+1)^3);
          3      2
(%o3) x  + 3 x  + 3 x + 1
```

linel

Option variable

Default value: 79

linel is the assumed width (in characters) of the console display for the purpose of displaying expressions. **linel** may be assigned any value by the user, although very small or very large values may be impractical. Text printed by built-in Maxima functions, such as error messages and the output of **describe**, is not affected by **linel**.

lispdisp

Option variable

Default value: **false**

When **lispdisp** is **true**, Lisp symbols are displayed with a leading question mark ?. Otherwise, Lisp symbols are displayed with no leading mark.

Examples:

```
(%i1) lispdisp: false$
(%i2) ?foo + ?bar;
(%o2)                                foo + bar
(%i3) lispdisp: true$
(%i4) ?foo + ?bar;
(%o4)                                ?foo + ?bar
```

negsumdispflag

Option variable

Default value: `true`

When `negsumdispflag` is `true`, $x - y$ displays as $x - y$ instead of as $-y + x$. Setting it to `false` causes the special check in display for the difference of two expressions to not be done. One application is that thus $a + i*b$ and $a - i*b$ may both be displayed the same way.

obase

Option variable

Default value: 10

`obase` is the base for integers displayed by Maxima.

`obase` may be assigned any integer between 2 and 36 (decimal), inclusive. When `obase` is greater than 10, the numerals comprise the decimal numerals 0 through 9 plus capital letters of the alphabet A, B, C, . . . , as needed. A leading 0 digit is displayed if the leading digit is otherwise a letter. The numerals for base 36, the largest acceptable base, comprise 0 through 9, and A through Z.

See also `ibase`.

Examples:

```
(%i1) obase : 2;
(%o1)                                10
(%i2) 2^8 - 1;
(%o2)                                11111111
(%i3) obase : 8;
(%o3)                                10
(%i4) 8^8 - 1;
(%o4)                                77777777
(%i5) obase : 16;
(%o5)                                10
(%i6) 16^8 - 1;
(%o6)                                0FFFFFFFFF
(%i7) obase : 36;
(%o7)                                10
(%i8) 36^8 - 1;
(%o8)                                0ZZZZZZZZ
```

pformat

Option variable

Default value: `false`

When `pformat` is `true`, a ratio of integers is displayed with the solidus (forward slash) character, and an integer denominator n is displayed as a leading multiplicative term $1/n$.

Examples:

```
(%i1) pformat: false$
(%i2) 2^16/7^3;
(%o2)                                65536
                                -----
                                343
(%i3) (a+b)/8;
(%o3)                                b + a
                                -----
```



```

                                8
(%i4) pfeformat: true$
(%i5) 2^16/7^3;
(%o5)                                65536/343
(%i6) (a+b)/8;
(%o6)                                1/8 (b + a)

```

powerdisp

Option variable

Default value: `false`

When `powerdisp` is `true`, a sum is displayed with its terms in order of increasing power. Thus a polynomial is displayed as a truncated power series, with the constant term first and the highest power last.

By default, terms of a sum are displayed in order of decreasing power.

Example:

```

(%i1) powerdisp:true;
(%o1)                                true
(%i2) x^2+x^3+x^4;
                                2    3    4
(%o2) x  + x  + x
(%i3) powerdisp:false;
(%o3)                                false
(%i4) x^2+x^3+x^4;
                                4    3    2
(%o4) x  + x  + x

```

print (*expr_1*, ..., *expr_n*)

Function

Evaluates and displays *expr_1*, ..., *expr_n* one after another, from left to right, starting at the left edge of the console display.

The value returned by `print` is the value of its last argument. `print` does not generate intermediate expression labels.

See also `display`, `disp`, `ldisplay`, and `ldisp`. Those functions display one expression per line, while `print` attempts to display two or more expressions per line.

To display the contents of a file, see `printfile`.

Examples:

```

(%i1) r: print ("(a+b)^3 is", expand ((a+b)^3), "log (a^10/b) is",
               radcan (log (a^10/b)))$
                                3    2    2    3
(a+b)^3 is b  + 3 a b  + 3 a  b + a  log (a^10/b) is
                                10 log(a) - log(b)
(%i2) r;
(%o2)                                10 log(a) - log(b)
(%i3) disp ("(a+b)^3 is", expand ((a+b)^3), "log (a^10/b) is",
            radcan (log (a^10/b)))$
                                (a+b)^3 is
                                3    2    2    3
                                b  + 3 a b  + 3 a  b + a
                                log (a^10/b) is
                                10 log(a) - log(b)

```

sqrtdispflag

Option variable

Default value: `true`When `sqrtdispflag` is `false`, causes `sqrt` to display with exponent $1/2$.**stardisp**

Option variable

Default value: `false`When `stardisp` is `true`, multiplication is displayed with an asterisk `*` between operands.**ttyoff**

Option variable

Default value: `false`When `ttyoff` is `true`, output expressions are not displayed. Output expressions are still computed and assigned labels. See `labels`.Text printed by built-in Maxima functions, such as error messages and the output of `describe`, is not affected by `ttyoff`.

5 Data Types and Structures

5.1 Numbers

5.1.1 Introduction to Numbers

Complex numbers

A complex expression is specified in Maxima by adding the real part of the expression to %i times the imaginary part. Thus the roots of the equation $x^2 - 4x + 13 = 0$ are $2 + 3\%i$ and $2 - 3\%i$. Note that simplification of products of complex expressions can be effected by expanding the product. Simplification of quotients, roots, and other functions of complex expressions can usually be accomplished by using the `realpart`, `imagpart`, `rectform`, `polarform`, `abs`, `carg` functions.

5.1.2 Functions and Variables for Numbers

bfloat (*expr*) Function
 Converts all numbers and functions of numbers in *expr* to bigfloat numbers. The number of significant digits in the resulting bigfloats is specified by the global variable `fpprec`.
 When `float2bf` is `false` a warning message is printed when a floating point number is converted into a bigfloat number (since this may lead to loss of precision).

bfloatp (*expr*) Function
 Returns `true` if *expr* is a bigfloat number, otherwise `false`.

bftorat Option variable
 Default value: `false`
bftorat controls the conversion of bfloats to rational numbers. When **bftorat** is `false`, `ratepsilon` will be used to control the conversion (this results in relatively small rational numbers). When **bftorat** is `true`, the rational number generated will accurately represent the bfloat.

Note: **bftorat** has no effect on the transformation to rational numbers with the function `rationalize`.

Example:

```
(%i1) ratepsilon:1e-4;
(%o1) 1.e-4
(%i2) rat(bfloat(11111/11111)), bftorat:false;
'rat' replaced 9.99990999991B-2 by 1/10 = 1.0B-1
1
--
10
(%i3) rat(bfloat(11111/11111)), bftorat:true;
'rat' replaced 9.99990999991B-2 by 11111/11111 = 9.99990999991B-2
11111
-----
111111
```

bftrunc Option variable
 Default value: `true`
bftrunc causes trailing zeroes in non-zero bigfloat numbers not to be displayed. Thus, if **bftrunc** is `false`, `bfloat (1)` displays as `1.000000000000000B0`. Otherwise, this is displayed as `1.0B0`.

evenp (*expr*) Function
 Returns **true** if *expr* is an even integer. **false** is returned in all other cases.

float (*expr*) Function
 Converts integers, rational numbers and bigfloats in *expr* to floating point numbers. It is also an **evflag**, **float** causes non-integral rational numbers and bigfloat numbers to be converted to floating point.

float2bf Option variable
 Default value: **true**
 When **float2bf** is **false**, a warning message is printed when a floating point number is converted into a bigfloat number (since this may lead to loss of precision). The default value is **true**.

floatnump (*expr*) Function
 Returns **true** if *expr* is a floating point number, otherwise **false**.

fpprec Option variable
 Default value: 16
fpprec is the number of significant digits for arithmetic on bigfloat numbers. **fpprec** does not affect computations on ordinary floating point numbers.
 See also **bfloat** and **fpprintprec**.

fpprintprec Option variable
 Default value: 0
fpprintprec is the number of digits to print when printing an ordinary float or bigfloat number.
 For ordinary floating point numbers, when **fpprintprec** has a value between 2 and 16 (inclusive), the number of digits printed is equal to **fpprintprec**. Otherwise, **fpprintprec** is 0, or greater than 16, and the number of digits printed is 16.
 For bigfloat numbers, when **fpprintprec** has a value between 2 and **fpprec** (inclusive), the number of digits printed is equal to **fpprintprec**. Otherwise, **fpprintprec** is 0, or greater than **fpprec**, and the number of digits printed is equal to **fpprec**.
fpprintprec cannot be 1.

integerp (*expr*) Function
 Returns **true** if *expr* is a literal numeric integer, otherwise **false**.
integerp returns **false** if its argument is a symbol, even if the argument is declared integer.

Examples:

```
(%i1) integerp (0);
(%o1)                                     true
(%i2) integerp (1);
(%o2)                                     true
(%i3) integerp (-17);
(%o3)                                     true
(%i4) integerp (0.0);
(%o4)                                     false
(%i5) integerp (1.0);
(%o5)                                     false
(%i6) integerp (%pi);
(%o6)                                     false
```

```
(%i7) integerp (n);
(%o7)                                     false
(%i8) declare (n, integer);
(%o8)                                     done
(%i9) integerp (n);
(%o9)                                     false
```

m1pbranch

Option variable

Default value: **false**

m1pbranch is the principal branch for -1 to a power. Quantities such as $(-1)^{(1/3)}$ (that is, an "odd" rational exponent) and $(-1)^{(1/4)}$ (that is, an "even" rational exponent) are handled as follows:

```
domain:real

(-1)^(1/3):      -1
(-1)^(1/4):      (-1)^(1/4)

domain:complex
m1pbranch:false      m1pbranch:true
(-1)^(1/3)           1/2+%i*sqrt(3)/2
(-1)^(1/4)           sqrt(2)/2+%i*sqrt(2)/2
```

nonnegintegerp (n)

Function

Return **true** if and only if $n \geq 0$ and n is an integer.

numberp (expr)

Function

Returns **true** if *expr* is a literal integer, rational number, floating point number, or bigfloat, otherwise **false**.

numberp returns **false** if its argument is a symbol, even if the argument is a symbolic number such as **%pi** or **%i**, or declared to be **even**, **odd**, **integer**, **rational**, **irrational**, **real**, **imaginary**, or **complex**.

Examples:

```
(%i1) numberp (42);
(%o1)                                     true
(%i2) numberp (-13/19);
(%o2)                                     true
(%i3) numberp (3.14159);
(%o3)                                     true
(%i4) numberp (-1729b-4);
(%o4)                                     true
(%i5) map (numberp, [%e, %pi, %i, %phi, inf, minf]);
(%o5)      [false, false, false, false, false, false]
(%i6) declare (a, even, b, odd, c, integer, d, rational,
              e, irrational, f, real, g, imaginary, h, complex);
(%o6)                                     done
(%i7) map (numberp, [a, b, c, d, e, f, g, h]);
(%o7) [false, false, false, false, false, false, false, false]
```

numer

Option variable

numer causes some mathematical functions (including exponentiation) with numerical arguments to be evaluated in floating point. It causes variables in *expr* which have been given numerals to be replaced by their values. It also sets the **float** switch on.

See also **%enumer**.

Examples:

```
(%i1) [sqrt(2), sin(1), 1/(1+sqrt(3))];
                                     1
(%o1)      [sqrt(2), sin(1), -----]
                               sqrt(3) + 1
(%i2) [sqrt(2), sin(1), 1/(1+sqrt(3))],numer;
(%o2) [1.414213562373095, .8414709848078965, .3660254037844387]
```

numer_pbranch

Option variable

Default value: `false`

The option variable `numer_pbranch` controls the numerical evaluation of the power of a negative integer, rational, or floating point number. When `numer_pbranch` is `true` and the exponent is a floating point number or the option variable `numer` is `true` too, Maxima evaluates the numerical result using the principal branch. Otherwise a simplified, but not an evaluated result is returned.

Examples:

```
(%i1) (-2)^0.75;
(%o1) (-2)^0.75

(%i2) (-2)^0.75,numer_pbranch:true;
(%o2) 1.189207115002721*%i-1.189207115002721

(%i3) (-2)^(3/4);
(%o3) (-1)^(3/4)*2^(3/4)

(%i4) (-2)^(3/4),numer;
(%o4) 1.681792830507429*(-1)^0.75

(%i5) (-2)^(3/4),numer,numer_pbranch:true;
(%o5) 1.189207115002721*%i-1.189207115002721
```

numeval (*x₁*, *expr₁*, ..., *var_n*, *expr_n*)

Function

Declares the variables *x₁*, ..., *x_n* to have numeric values equal to *expr₁*, ..., *expr_n*. The numeric value is evaluated and substituted for the variable in any expressions in which the variable occurs if the `numer` flag is `true`. See also `ev`.

The expressions *expr₁*, ..., *expr_n* can be any expressions, not necessarily numeric.

oddp (*expr*)

Function

is `true` if *expr* is an odd integer. `false` is returned in all other cases.

ratepsilon

Option variable

Default value: `2.0e-15`

`ratepsilon` is the tolerance used in the conversion of floating point numbers to rational numbers, when the option variable `bftorat` has the value `false`. See `bftorat` for an example.

rationalize (*expr*)

Function

Convert all double floats and big floats in the Maxima expression *expr* to their exact rational equivalents. If you are not familiar with the binary representation of floating point numbers, you might be surprised that `rationalize (0.1)` does not equal `1/10`. This behavior isn't special to Maxima – the number `1/10` has a repeating, not a terminating, binary representation.

```

(%i1) rationalize (0.5);
                                     1
(%o1)                                     -
                                     2
(%i2) rationalize (0.1);
                                     1
(%o2)                                     --
                                     10
(%i3) fpprec : 5$
(%i4) rationalize (0.1b0);
                                     209715
(%o4)                                     -----
                                     2097152
(%i5) fpprec : 20$
(%i6) rationalize (0.1b0);
                                     236118324143482260685
(%o6)                                     -----
                                     2361183241434822606848
(%i7) rationalize (sin (0.1*x + 5.6));
                                     x      28
(%o7)                               sin(-- + --)
                                     10    5

```

Example use:

```

(%i1) unitfrac(r) := block([uf : [], q],
    if not(ratnump(r)) then
        error("The input to 'unitfrac' must be a rational number"),
    while r # 0 do (
        uf : cons(q : 1/ceiling(1/r), uf),
        r : r - q),
    reverse(uf))$
(%i2) unitfrac (9/10);
                                     1  1  1
(%o2)                               [-, -, --]
                                     2  3  15
(%i3) apply ("+", %);
                                     9
(%o3)                               --
                                     10
(%i4) unitfrac (-9/10);
                                     1
(%o4)                               [- 1, --]
                                     10
(%i5) apply ("+", %);
                                     9
(%o5)                               - --
                                     10
(%i6) unitfrac (36/37);
                                     1  1  1  1  1
(%o6)                               [-, -, -, --, ----]
                                     2  3  8  69  6808
(%i7) apply ("+", %);
                                     36
(%o7)                               --
                                     37

```

ratnump (*expr*)

Function

Returns **true** if *expr* is a literal integer or ratio of literal integers, otherwise **false**.

5.2 Strings

5.2.1 Introduction to Strings

Strings (quoted character sequences) are enclosed in double quote marks " for input, and displayed with or without the quote marks, depending on the global variable `stringdisp`.

Strings may contain any characters, including embedded tab, newline, and carriage return characters. The sequence `\"` is recognized as a literal double quote, and `\\` as a literal backslash. When backslash appears at the end of a line, the backslash and the line termination (either newline or carriage return and newline) are ignored, so that the string continues with the next line. No other special combinations of backslash with another character are recognized; when backslash appears before any character other than `"`, `\`, or a line termination, the backslash is ignored. There is no way to represent a special character (such as tab, newline, or carriage return) except by embedding the literal character in the string.

There is no character type in Maxima; a single character is represented as a one-character string.

The `stringproc` add-on package contains many functions for working with strings.

Examples:

```
(%i1) s_1 : "This is a string.";
(%o1)          This is a string.
(%i2) s_2 : "Embedded \"double quotes\" and backslash \\ characters.";
(%o2) Embedded "double quotes" and backslash \ characters.
(%i3) s_3 : "Embedded line termination
in this string.";
(%o3) Embedded line termination
in this string.
(%i4) s_4 : "Ignore the \
line termination \
characters in \
this string.";
(%o4) Ignore the line termination characters in this string.
(%i5) stringdisp : false;
(%o5)                                false
(%i6) s_1;
(%o6)                                This is a string.
(%i7) stringdisp : true;
(%o7)                                true
(%i8) s_1;
(%o8)                                "This is a string."
```

5.2.2 Functions and Variables for Strings

concat (*arg_1*, *arg_2*, ...)

Function

Concatenates its arguments. The arguments must evaluate to atoms. The return value is a symbol if the first argument is a symbol and a string otherwise.

`concat` evaluates its arguments. The single quote ' prevents evaluation.

```
(%i1) y: 7$
(%i2) z: 88$
(%i3) concat (y, z/2);
(%o3)                                744
(%i4) concat ('y, z/2);
(%o4)                                y44
```

A symbol constructed by `concat` may be assigned a value and appear in expressions. The `::` (double colon) assignment operator evaluates its left-hand side.

5.3 Constants

5.3.1 Functions and Variables for Constants

%e Constant
%e represents the base of the natural logarithm, also known as Euler's number. The numeric value of **%e** is the double-precision floating-point value 2.718281828459045d0.

%i Constant
%i represents the imaginary unit, $\sqrt{-1}$.

false Constant
false represents the Boolean constant of the same name. Maxima implements **false** by the value NIL in Lisp.

%gamma Constant
The Euler-Mascheroni constant, 0.5772156649015329

ind Constant
ind represents a bounded, indefinite result.
See also **limit**.
Example:

```
(%i1) limit (sin(1/x), x, 0);
(%o1) ind
```

inf Constant
inf represents real positive infinity.

infinity Constant
infinity represents complex infinity.

minf Constant
minf represents real minus (i.e., negative) infinity.

%phi Constant
%phi represents the so-called *golden mean*, $(1 + \sqrt{5})/2$. The numeric value of **%phi** is the double-precision floating-point value 1.618033988749895d0.
fibtophi expresses Fibonacci numbers **fib(n)** in terms of **%phi**.
By default, Maxima does not know the algebraic properties of **%phi**. After evaluating **tellrat(%phi^2 - %phi - 1)** and **algebraic: true**, **ratsimp** can simplify some expressions containing **%phi**.

Examples:

fibtophi expresses Fibonacci numbers **fib(n)** in terms of **%phi**.

```
(%i1) fibtophi (fib (n));
                                n          n
                                %phi  - (1 - %phi)
(%o1) -----
                                2 %phi - 1
(%i2) fib (n-1) + fib (n) - fib (n+1);
(%o2) - fib(n + 1) + fib(n) + fib(n - 1)
```

```
(%i3) fibtophi (%);
              n + 1      n + 1      n      n
      %phi      - (1 - %phi)      %phi - (1 - %phi)
(%o3) - ----- + -----
              2 %phi - 1      2 %phi - 1
              n - 1      n - 1
              %phi      - (1 - %phi)
              + -----
                  2 %phi - 1

(%i4) ratsimp (%);
(%o4) 0
```

By default, Maxima does not know the algebraic properties of %phi. After evaluating `tellrat (%phi^2 - %phi - 1)` and `algebraic: true`, `ratsimp` can simplify some expressions containing %phi.

```
(%i1) e : expand ((%phi^2 - %phi - 1) * (A + 1));
              2      2
(%o1) %phi A - %phi A - A + %phi - %phi - 1
(%i2) ratsimp (e);
              2      2
(%o2) (%phi - %phi - 1) A + %phi - %phi - 1
(%i3) tellrat (%phi^2 - %phi - 1);
              2
(%o3) [%phi - %phi - 1]
(%i4) algebraic : true;
(%o4) true
(%i5) ratsimp (e);
(%o5) 0
```

%pi Constant
 %pi represents the ratio of the perimeter of a circle to its diameter. The numeric value of %pi is the double-precision floating-point value 3.141592653589793d0.

true Constant
 true represents the Boolean constant of the same name. Maxima implements true by the value T in Lisp.

und Constant
 und represents an undefined result.
 See also `limit`.

Example:

```
(%i1) limit (x*sin(x), x, inf);
(%o1) und
```

zeroa Constant
 zeroa represents an infinitesimal above zero. zeroa can be used in expressions. `limit` simplifies expressions which contain infinitesimals.

See also `zerob` and `limit`.

Example:

`limit` simplifies expressions which contain infinitesimals:

```
(%i1) limit(zeroa);
(%o1) 0
(%i2) limit(x+zeroa);
(%o2) x
```

zerob

Constant

zerob represents an infinitesimal below zero. **zerob** can be used in expressions. **limit** simplifies expressions which contain infinitesimals.

See also **zeroa** and **limit**.

5.4 Lists

5.4.1 Introduction to Lists

Lists are the basic building block for Maxima and Lisp. All data types other than arrays, hash tables, numbers are represented as Lisp lists. These Lisp lists have the form

```
((MPLUS) $A 2)
```

to indicate an expression $a+2$. At Maxima level one would see the infix notation $a+2$. Maxima also has lists which are printed as

```
[1, 2, 7, x+y]
```

for a list with 4 elements. Internally this corresponds to a Lisp list of the form

```
((MLIST) 1 2 7 ((MPLUS) $X $Y ))
```

The flag which denotes the type field of the Maxima expression is a list itself, since after it has been through the simplifier the list would become

```
((MLIST SIMP) 1 2 7 ((MPLUS SIMP) $X $Y))
```

5.4.2 Functions and Variables for Lists

[
]

Operator
Operator

[and] mark the beginning and end, respectively, of a list.

[and] also enclose the subscripts of a list, array, hash array, or array function.

Examples:

```
(%i1) x: [a, b, c];
(%o1) [a, b, c]
(%i2) x[3];
(%o2) c
(%i3) array (y, fixnum, 3);
(%o3) y
(%i4) y[2]: %pi;
(%o4) %pi
(%i5) y[2];
(%o5) %pi
(%i6) z['foo]: 'bar;
(%o6) bar
(%i7) z['foo];
(%o7) bar
(%i8) g[k] := 1/(k^2+1);
(%o8) g_k := 1 / (k^2 + 1)
(%i9) g[10];
(%o9) 1 / 101
```

append (*list_1*, ..., *list_n*)

Function

Returns a single list of the elements of *list_1* followed by the elements of *list_2*, ...
append also works on general expressions, e.g. `append (f(a,b), f(c,d,e));` yields `f(a,b,c,d,e)`.

Do `example(append);` for an example.

assoc (*key*, *list*, *default*)

Function

assoc (*key*, *list*)

Function

This function searches for the *key* in the left hand side of the input *list* of the form $[x, y, z, \dots]$ where each of the *list* elements is an expression of a binary operand and 2 elements. For example $x=1, 2^3, [a, b]$ etc. The *key* is checked against the first operand. **assoc** returns the second operand if the *key* is found. If the *key* is not found it either returns the *default* value. *default* is optional and defaults to **false**.

cons (*expr*, *list*)

Function

Returns a new list constructed of the element *expr* as its first element, followed by the elements of *list*. **cons** also works on other expressions, e.g. **cons**(*x*, **f**(*a*, *b*, *c*)); \rightarrow **f**(*x*, *a*, *b*, *c*).

copylist (*list*)

Function

Returns a copy of the list *list*.

create_list (*form*, *x_1*, *list_1*, ..., *x_n*, *list_n*)

Function

Create a list by evaluating *form* with *x_1* bound to each element of *list_1*, and for each such binding bind *x_2* to each element of *list_2*, ... The number of elements in the result will be the product of the number of elements in each list. Each variable *x_i* must actually be a symbol – it will not be evaluated. The list arguments will be evaluated once at the beginning of the iteration.

```
(%i1) create_list (x^i, i, [1, 3, 7]);
              3      7
(%o1)          [x, x , x ]
```

With a double iteration:

```
(%i1) create_list ([i, j], i, [a, b], j, [e, f, h]);
(%o1)  [[a, e], [a, f], [a, h], [b, e], [b, f], [b, h]]
```

Instead of *list_i* two args may be supplied each of which should evaluate to a number. These will be the inclusive lower and upper bounds for the iteration.

```
(%i1) create_list ([i, j], i, [1, 2, 3], j, 1, i);
(%o1)  [[1, 1], [2, 1], [2, 2], [3, 1], [3, 2], [3, 3]]
```

Note that the limits or list for the *j* variable can depend on the current value of *i*.

delete (*expr_1*, *expr_2*)

Function

delete (*expr_1*, *expr_2*, *n*)

Function

delete(*expr_1*, *expr_2*) removes from *expr_2* any arguments of its top-level operator which are the same (as determined by "=") as *expr_1*. Note that "=" tests for formal equality, not equivalence. Note also that arguments of subexpressions are not affected.

expr_1 may be an atom or a non-atomic expression. *expr_2* may be any non-atomic expression. **delete** returns a new expression; it does not modify *expr_2*.

delete(*expr_1*, *expr_2*, *n*) removes from *expr_2* the first *n* arguments of the top-level operator which are the same as *expr_1*. If there are fewer than *n* such arguments, then all such arguments are removed.

Examples:

Removing elements from a list.

```
(%i1) delete (y, [w, x, y, z, z, y, x, w]);
(%o1)          [w, x, z, z, x, w]
```

Removing terms from a sum.

```
(%i1) delete (sin(x), x + sin(x) + y);
(%o1)          y + x
```

Removing factors from a product.

```
(%i1) delete (u - x, (u - w)*(u - x)*(u - y)*(u - z));
(%o1)          (u - w) (u - y) (u - z)
```

Removing arguments from an arbitrary expression.

```
(%i1) delete (a, foo (a, b, c, d, a));
(%o1)          foo(b, c, d)
```

Limit the number of removed arguments.

```
(%i1) delete (a, foo (a, b, a, c, d, a), 2);
(%o1)          foo(b, c, d, a)
```

Whether arguments are the same as *expr_1* is determined by "=". Arguments which are equal but not "=" are not removed.

```
(%i1) [is (equal (0, 0)), is (equal (0, 0.0)), is (equal (0, 0b0))];
rat: replaced 0.0 by 0/1 = 0.0
'rat' replaced 0.0B0 by 0/1 = 0.0B0
(%o1)          [true, true, true]
(%i2) [is (0 = 0), is (0 = 0.0), is (0 = 0b0)];
(%o2)          [true, false, false]
(%i3) delete (0, [0, 0.0, 0b0]);
(%o3)          [0.0, 0.0b0]
(%i4) is (equal ((x + y)*(x - y), x^2 - y^2));
(%o4)          true
(%i5) is ((x + y)*(x - y) = x^2 - y^2);
(%o5)          false
(%i6) delete ((x + y)*(x - y), [(x + y)*(x - y), x^2 - y^2]);
(%o6)          [x^2 - y^2]
```

eighth (*expr*)

Function

Returns the 8'th item of expression or list *expr*. See **first** for more details.

endcons (*expr*, *list*)

Function

Returns a new list consisting of the elements of *list* followed by *expr*. **endcons** also works on general expressions, e.g. **endcons**(*x*, *f*(*a*,*b*,*c*)); -> *f*(*a*,*b*,*c*,*x*).

fifth (*expr*)

Function

Returns the 5'th item of expression or list *expr*. See **first** for more details.

first (*expr*)

Function

Returns the first part of *expr* which may result in the first element of a list, the first row of a matrix, the first term of a sum, etc. Note that **first** and its related functions, **rest** and **last**, work on the form of *expr* which is displayed not the form which is typed on input. If the variable **inflag** is set to **true** however, these functions will look at the internal form of *expr*. Note that the simplifier re-orders expressions. Thus **first**(*x*+*y*) will be *x* if **inflag** is **true** and *y* if **inflag** is **false** (**first**(*y*+*x*) gives the same results). The functions **second** ... **tenth** yield the second through the tenth part of their input argument.

fourth (*expr*)

Function

Returns the 4'th item of expression or list *expr*. See **first** for more details.

join (*l*, *m*) Function

Creates a new list containing the elements of lists *l* and *m*, interspersed. The result has elements $[l[1], m[1], l[2], m[2], \dots]$. The lists *l* and *m* may contain any type of elements.

If the lists are different lengths, **join** ignores elements of the longer list.

Maxima complains if *l* or *m* is not a list.

Examples:

```
(%i1) L1: [a, sin(b), c!, d - 1];
(%o1)      [a, sin(b), c!, d - 1]
(%i2) join (L1, [1, 2, 3, 4]);
(%o2)      [a, 1, sin(b), 2, c!, 3, d - 1, 4]
(%i3) join (L1, [aa, bb, cc, dd, ee, ff]);
(%o3)      [a, aa, sin(b), bb, c!, cc, d - 1, dd]
```

last (*expr*) Function

Returns the last part (term, row, element, etc.) of the *expr*.

length (*expr*) Function

Returns (by default) the number of parts in the external (displayed) form of *expr*. For lists this is the number of elements, for matrices it is the number of rows, and for sums it is the number of terms (see **dispform**).

The **length** command is affected by the **inflag** switch. So, e.g. **length(a/(b*c))**; gives 2 if **inflag** is **false** (Assuming **exptdispflag** is **true**), but 3 if **inflag** is **true** (the internal representation is essentially $a*b^{-1}*c^{-1}$).

listarith Option variable

Default value: **true**

If **false** causes any arithmetic operations with lists to be suppressed; when **true**, list-matrix operations are contagious causing lists to be converted to matrices yielding a result which is always a matrix. However, list-list operations should return lists.

listp (*expr*) Function

Returns **true** if *expr* is a list else **false**.

makelist () Function

makelist (*expr*, *n*) Function

makelist (*expr*, *i*, *i_max*) Function

makelist (*expr*, *i*, *i_0*, *i_max*) Function

makelist (*expr*, *i*, *i_0*, *i_max*, *step*) Function

makelist (*expr*, *x*, *list*) Function

The first form, **makelist** (), creates an empty list. The second form, **makelist** (*expr*), creates a list with *expr* as its single element. **makelist** (*expr*, *n*) creates a list of *n* elements generated from *expr*.

The most general form, **makelist** (*expr*, *i*, *i_0*, *i_max*, *step*), returns the list of elements obtained when **ev** (*expr*, *i=j*) is applied to the elements *j* of the sequence: *i_0*, *i_0* + *step*, *i_0* + 2**step*, ..., with $|j|$ less than or equal to $|i_{max}|$.

The increment *step* can be a number (positive or negative) or an expression. If it is omitted, the default value 1 will be used. If both *i_0* and *step* are omitted, they will both have a default value of 1.

makelist (*expr*, *x*, *list*) returns a list, the *j*'th element of which is equal to **ev** (*expr*, $x=list[j]$) for *j* equal to 1 through **length** (*list*).

Examples:

```
(%i1) makelist (concat (x,i), i, 6);
(%o1)          [x1, x2, x3, x4, x5, x6]
(%i2) makelist (x=y, y, [a, b, c]);
(%o2)          [x = a, x = b, x = c]
(%i3) makelist (x^2, x, 3, 2*%pi, 2);
(%o3)          [9, 25]
(%i4) makelist (random(6), 4);
(%o4)          [2, 0, 2, 5]
(%i5) flatten (makelist (makelist (i^2, 3), i, 4));
(%o5)          [1, 1, 1, 4, 4, 4, 9, 9, 9, 16, 16, 16]
(%i6) flatten (makelist (makelist (i^2, i, 3), 4));
(%o6)          [1, 4, 9, 1, 4, 9, 1, 4, 9, 1, 4, 9]
```

member (*expr_1*, *expr_2*)

Function

Returns true if $\text{is}(\text{expr}_1 = a)$ for some element a in $\text{args}(\text{expr}_2)$, otherwise returns false.

expr_2 is typically a list, in which case $\text{args}(\text{expr}_2) = \text{expr}_2$ and $\text{is}(\text{expr}_1 = a)$ for some element a in *expr_2* is the test.

member does not inspect parts of the arguments of *expr_2*, so it may return false even if *expr_1* is a part of some argument of *expr_2*.

See also **elementp**.

Examples:

```
(%i1) member (8, [8, 8.0, 8b0]);
(%o1)          true
(%i2) member (8, [8.0, 8b0]);
(%o2)          false
(%i3) member (b, [a, b, c]);
(%o3)          true
(%i4) member (b, [[a, b], [b, c]]);
(%o4)          false
(%i5) member ([b, c], [[a, b], [b, c]]);
(%o5)          true
(%i6) F (1, 1/2, 1/4, 1/8);
(%o6)          1 1 1
                F(1, -, -, -)
                2 4 8
(%i7) member (1/8, %);
(%o7)          true
(%i8) member ("ab", ["aa", "ab", sin(1), a + b]);
(%o8)          true
```

ninth (*expr*)

Function

Returns the 9'th item of expression or list *expr*. See **first** for more details.

pop (*list*)

Function

pop removes the first element from the list *list* and returns this element. *list* must be a symbol, which is bound to a list and not the list itself.

If the argument *list* is not bound to a list or the list is empty, Maxima generates an error message.

See also **push** for examples.

To use this function, the additional package "basic" must be loaded first: `load("basic")`.

push (*item*, *list*)

Function

push prepends the item *item* to the list *list* and returns a copy of the new list. *list* must be a symbol, which is bound to a list and not the list itself. *item* can be any Maxima symbol or expression.

If the argument *list* is not bound to a list, Maxima generates an error message.

See also **pop** to remove the first item from a list.

load("basic") loads this function.

Examples:

```
(%i1) load ("basic")$
(%i2) l1: [];
(%o2)                                     []
(%i3) push (x, l1);
(%o3)                                     [x]
(%i4) push (x^2+y, l1);
(%o4)                                     2
                                     [y + x , x]
(%i5) a: push ("string", l1);
(%o5)                                     2
                                     [string, y + x , x]
(%i6) pop (l1);
(%o6)                                     string
(%i7) pop (l1);
(%o7)                                     2
                                     y + x
(%i8) pop (l1);
(%o8)                                     x
(%i9) l1;
(%o9)                                     []
(%i10) a;
(%o10)                                     2
                                     [string, y + x , x]
```

rest (*expr*, *n*)

Function

rest (*expr*)

Function

Returns *expr* with its first *n* elements removed if *n* is positive and its last $-n$ elements removed if *n* is negative. If *n* is 1 it may be omitted. *expr* may be a list, matrix, or other expression.

reverse (*list*)

Function

Reverses the order of the members of the *list* (not the members themselves). **reverse** also works on general expressions, e.g. **reverse**(a=b); gives b=a.

second (*expr*)

Function

Returns the 2'nd item of expression or list *expr*. See **first** for more details.

seventh (*expr*)

Function

Returns the 7'th item of expression or list *expr*. See **first** for more details.

sixth (*expr*)

Function

Returns the 6'th item of expression or list *expr*. See **first** for more details.

sort (*L*, *P*)

Function

sort (*L*)

Function

sort(*L*, *P*) sorts a list *L* according to a predicate *P* of two arguments which defines a strict weak order on the elements of *L*. If *P*(*a*, *b*) is **true**, then *a* appears before *b* in the result. If neither *P*(*a*, *b*) nor *P*(*b*, *a*) are **true**, then *a* and *b* are equivalent, and appear in the result in the same order as in the input. That is, **sort** is a stable sort.

If *P*(*a*, *b*) and *P*(*b*, *a*) are both **true** for some elements of *L*, then *P* is not a valid sort predicate, and the result is undefined. If *P*(*a*, *b*) is something other than **true** or **false**, **sort** signals an error.

The predicate may be specified as the name of a function or binary infix operator, or as a **lambda** expression. If specified as the name of an operator, the name must be enclosed in double quotes.

The sorted list is returned as a new object; the argument *L* is not modified.

sort(*L*) is equivalent to **sort**(*L*, **orderlessp**).

The default sorting order is ascending, as determined by **orderlessp**. The predicate **ordergreatp** sorts a list in descending order.

All Maxima atoms and expressions are comparable under **orderlessp** and **ordergreatp**. Operators **<** and **>** order numbers, constants, and constant expressions by magnitude. Note that **orderlessp** and **ordergreatp** do not order numbers, constants, and constant expressions by magnitude.

ordermagnitdep orders numbers, constants, and constant expressions the same as **<**, and all other elements the same as **orderlessp**.

Examples:

sort sorts a list according to a predicate of two arguments which defines a strict weak order on the elements of the list.

```
(%i1) sort ([1, a, b, 2, 3, c], 'orderlessp);
(%o1)      [1, 2, 3, a, b, c]
(%i2) sort ([1, a, b, 2, 3, c], 'ordergreatp);
(%o2)      [c, b, a, 3, 2, 1]
```

The predicate may be specified as the name of a function or binary infix operator, or as a **lambda** expression. If specified as the name of an operator, the name must be enclosed in double quotes.

```
(%i1) L : [[1, x], [3, y], [4, w], [2, z]];
(%o1)      [[1, x], [3, y], [4, w], [2, z]]
(%i2) foo (a, b) := a[1] > b[1];
(%o2)      foo(a, b) := a  > b
                        1    1
(%i3) sort (L, 'foo);
(%o3)      [[4, w], [3, y], [2, z], [1, x]]
(%i4) infix (">>");
(%o4)      >>
(%i5) a >> b := a[1] > b[1];
(%o5)      a >> b := a  > b
                        1    1
(%i6) sort (L, ">>");
(%o6)      [[4, w], [3, y], [2, z], [1, x]]
(%i7) sort (L, lambda ([a, b], a[1] > b[1]));
(%o7)      [[4, w], [3, y], [2, z], [1, x]]
```

sort(*L*) is equivalent to **sort**(*L*, **orderlessp**).

```
(%i1) L : [a, 2*b, -5, 7, 1 + %e, %pi];
(%o1)      [a, 2 b, - 5, 7, %e + 1, %pi]
(%i2) sort (L);
(%o2)      [- 5, 7, %e + 1, %pi, a, 2 b]
(%i3) sort (L, 'orderlessp);
(%o3)      [- 5, 7, %e + 1, %pi, a, 2 b]
```

The default sorting order is ascending, as determined by `orderlessp`. The predicate `ordergreatestp` sorts a list in descending order.

```
(%i1) L : [a, 2*b, -5, 7, 1 + %e, %pi];
(%o1)      [a, 2 b, - 5, 7, %e + 1, %pi]
(%i2) sort (L);
(%o2)      [- 5, 7, %e + 1, %pi, a, 2 b]
(%i3) sort (L, 'ordergreatestp);
(%o3)      [2 b, a, %pi, %e + 1, 7, - 5]
```

All Maxima atoms and expressions are comparable under `orderlessp` and `ordergreatestp`.

```
(%i1) L : [11, -17, 29b0, 9*c, 7.55, foo(x, y), -5/2, b + a];
(%o1)      [11, - 17, 2.9b1, 9 c, 7.55, foo(x, y), -  $\frac{5}{2}$ , b + a]
(%i2) sort (L, orderlessp);
(%o2)      [- 17, -  $\frac{5}{2}$ , 7.55, 11, 2.9b1, b + a, 9 c, foo(x, y)]
(%i3) sort (L, ordergreatestp);
(%o3)      [foo(x, y), 9 c, b + a, 2.9b1, 11, 7.55, -  $\frac{5}{2}$ , - 17]
```

Operators `<` and `>` order numbers, constants, and constant expressions by magnitude. Note that `orderlessp` and `ordergreatestp` do not order numbers, constants, and constant expressions by magnitude.

```
(%i1) L : [%pi, 3, 4, %e, %gamma];
(%o1)      [%pi, 3, 4, %e, %gamma]
(%i2) sort (L, ">");
(%o2)      [4, %pi, 3, %e, %gamma]
(%i3) sort (L, ordergreatestp);
(%o3)      [%pi, %gamma, %e, 4, 3]
```

`ordermagnituedep` orders numbers, constants, and constant expressions the same as `<`, and all other elements the same as `orderlessp`.

```
(%i1) L : [%i, 1+%i, 2*x, minf, inf, %e, sin(1), 0, 1, 2, 3, 1.0, 1.0b0];
(%o1) [%i, %i + 1, 2 x, minf, inf, %e, sin(1), 0, 1, 2, 3, 1.0, 1.0b0]
(%i2) sort (L, ordermagnituedep);
(%o2) [minf, 0, sin(1), 1, 1.0, 1.0b0, 2, %e, 3, inf, %i, %i + 1, 2 x]
(%i3) sort (L, orderlessp);
(%o3) [0, 1, 1.0, 2, 3, %e, %i, %i + 1, inf, minf, sin(1), 1.0b0, 2 x]
```

sublist (*list*, *p*)

Function

Returns the list of elements of *list* for which the predicate *p* returns `true`.

Example:

```
(%i1) L: [1, 2, 3, 4, 5, 6];
(%o1)      [1, 2, 3, 4, 5, 6]
(%i2) sublist (L, evenp);
(%o2)      [2, 4, 6]
```

sublist_indices (*L*, *P*)

Function

Returns the indices of the elements *x* of the list *L* for which the predicate `maybe(P(x))` returns `true`; this excludes `unknown` as well as `false`. *P* may be the name of a function or a lambda expression. *L* must be a literal list.

Examples:

```

(%i1) sublist_indices ('[a, b, b, c, 1, 2, b, 3, b],
                      lambda ([x], x='b));
(%o1)          [2, 3, 7, 9]
(%i2) sublist_indices ('[a, b, b, c, 1, 2, b, 3, b], symbolp);
(%o2)          [1, 2, 3, 4, 7, 9]
(%i3) sublist_indices ([1 > 0, 1 < 0, 2 < 1, 2 > 1, 2 > 0],
                      identity);
(%o3)          [1, 4, 5]
(%i4) assume (x < -1);
(%o4)          [x < - 1]
(%i5) map (maybe, [x > 0, x < 0, x < -2]);
(%o5)          [false, true, unknown]
(%i6) sublist_indices ([x > 0, x < 0, x < -2], identity);
(%o6)          [2]

```

unique (*L*)

Function

Returns the unique elements of the list *L*.

When all the elements of *L* are unique, **unique** returns a shallow copy of *L*, not *L* itself.

If *L* is not a list, **unique** returns *L*.

Example:

```

(%i1) unique ([1, %pi, a + b, 2, 1, %e, %pi, a + b, [1]]);
(%o1)          [1, 2, %e, %pi, [1], b + a]

```

tenth (*expr*)

Function

Returns the 10'th item of expression or list *expr*. See **first** for more details.

third (*expr*)

Function

Returns the 3'rd item of expression or list *expr*. See **first** for more details.

5.5 Arrays

5.5.1 Functions and Variables for Arrays

array (*name*, *dim_1*, ..., *dim_n*) Function
array (*name*, *type*, *dim_1*, ..., *dim_n*) Function
array (*[name_1, ..., name_m]*, *dim_1*, ..., *dim_n*) Function

Creates an *n*-dimensional array. *n* may be less than or equal to 5. The subscripts for the *i*'th dimension are the integers running from 0 to *dim_i*.

array (*name*, *dim_1*, ..., *dim_n*) creates a general array.

array (*name*, *type*, *dim_1*, ..., *dim_n*) creates an array, with elements of a specified type. *type* can be **fixnum** for integers of limited size or **flonum** for floating-point numbers.

array (*[name_1, ..., name_m]*, *dim_1*, ..., *dim_n*) creates *m* arrays, all of the same dimensions.

If the user assigns to a subscripted variable before declaring the corresponding array, an undeclared array is created. Undeclared arrays, otherwise known as hashed arrays (because hash coding is done on the subscripts), are more general than declared arrays. The user does not declare their maximum size, and they grow dynamically by hashing as more elements are assigned values. The subscripts of undeclared arrays need not even be numbers. However, unless an array is rather sparse, it is probably more efficient to declare it when possible than to leave it undeclared. The **array** function can be used to transform an undeclared array into a declared array.

arrayapply (*A*, [*i_1*, ..., *i_n*]) Function
 Evaluates *A* [*i_1*, ..., *i_n*], where *A* is an array and *i_1*, ..., *i_n* are integers.
 This is reminiscent of **apply**, except the first argument is an array instead of a function.

arrayinfo (*A*) Function

Returns information about the array *A*. The argument *A* may be a declared array, an undeclared (hashed) array, an array function, or a subscripted function.

For declared arrays, **arrayinfo** returns a list comprising the atom **declared**, the number of dimensions, and the size of each dimension. The elements of the array, both bound and unbound, are returned by **listarray**.

For undeclared arrays (hashed arrays), **arrayinfo** returns a list comprising the atom **hashed**, the number of subscripts, and the subscripts of every element which has a value. The values are returned by **listarray**.

For array functions, **arrayinfo** returns a list comprising the atom **hashed**, the number of subscripts, and any subscript values for which there are stored function values. The stored function values are returned by **listarray**.

For subscripted functions, **arrayinfo** returns a list comprising the atom **hashed**, the number of subscripts, and any subscript values for which there are lambda expressions. The lambda expressions are returned by **listarray**.

See also **listarray**.

Examples:

arrayinfo and **listarray** applied to a declared array.

```
(%i1) array (aa, 2, 3);
(%o1)                                     aa
(%i2) aa [2, 3] : %pi;
(%o2)                                     %pi
(%i3) aa [1, 2] : %e;
(%o3)                                     %e
(%i4) arrayinfo (aa);
(%o4) [declared, 2, [2, 3]]
```

```
(%i5) listarray (aa);
(%o5) [#####, #####, #####, #####, #####, #####, %e, #####,
      #####, #####, #####, %pi]
```

arrayinfo and listarray applied to an undeclared (hashed) array.

```
(%i1) bb [F00] : (a + b)^2;
(%o1) (b + a)^2
(%i2) bb [BAR] : (c - d)^3;
(%o2) (c - d)^3
(%i3) arrayinfo (bb);
(%o3) [hashed, 1, [BAR], [F00]]
(%i4) listarray (bb);
(%o4) [(c - d)^3, (b + a)^2]
```

arrayinfo and listarray applied to an array function.

```
(%i1) cc [x, y] := y / x;
(%o1) cc [x, y] := y/x
(%i2) cc [u, v];
(%o2) v/u
(%i3) cc [4, z];
(%o3) z/4
(%i4) arrayinfo (cc);
(%o4) [hashed, 2, [4, z], [u, v]]
(%i5) listarray (cc);
(%o5) [z/4, v/u]
```

arrayinfo and listarray applied to a subscripted function.

```
(%i1) dd [x] (y) := y ^ x;
(%o1) dd [x] (y) := y^x
(%i2) dd [a + b];
(%o2) lambda([y], y^(b + a))
(%i3) dd [v - u];
(%o3) lambda([y], y^(v - u))
(%i4) arrayinfo (dd);
(%o4) [hashed, 1, [b + a], [v - u]]
(%i5) listarray (dd);
(%o5) [lambda([y], y^(b + a)), lambda([y], y^(v - u))]
```

arraymake ($A, [i_1, \dots, i_n]$)

Function

Returns the expression $A[i_1, \dots, i_n]$. The result is an unevaluated array reference.

`arraymake` is reminiscent of `funmake`, except the return value is an unevaluated array reference instead of an unevaluated function call.

Examples:

```
(%i1) arraymake (A, [1]);
(%o1)          A
          1

(%i2) arraymake (A, [k]);
(%o2)          A
          k

(%i3) arraymake (A, [i, j, 3]);
(%o3)          A
          i, j, 3

(%i4) array (A, fixnum, 10);
(%o4)          A

(%i5) fillarray (A, makelist (i^2, i, 1, 11));
(%o5)          A

(%i6) arraymake (A, [5]);
(%o6)          A
          5

(%i7) '';
(%o7)          36

(%i8) L : [a, b, c, d, e];
(%o8)          [a, b, c, d, e]

(%i9) arraymake ('L, [n]);
(%o9)          L
          n

(%i10) ''; n = 3;
(%o10)          c

(%i11) A2 : make_array (fixnum, 10);
(%o11)          {Array: #(0 0 0 0 0 0 0 0 0 0)}

(%i12) fillarray (A2, [1, 2, 3, 4, 5, 6, 7, 8, 9, 10]);
(%o12)          {Array: #(1 2 3 4 5 6 7 8 9 10)}

(%i13) arraymake ('A2, [8]);
(%o13)          A2
          8

(%i14) '';
(%o14)          9
```

arrays

System variable

Default value: []

`arrays` is a list of arrays that have been allocated. These comprise arrays declared by `array`, hashed arrays constructed by implicit definition (assigning something to an array element), and array functions defined by `:=` and `define`. Arrays defined by `make_array` are not included.

See also `array`, `arrayapply`, `arrayinfo`, `arraymake`, `fillarray`, `listarray`, and `rearray`.

Examples:

```
(%i1) array (aa, 5, 7);
(%o1)          aa

(%i2) bb [F00] : (a + b)^2;
(%o2)          2
          (b + a)
```

```

(%i3) cc [x] := x/100;

(%o3)
      x
cc := ---
      x  100

(%i4) dd : make_array ('any, 7);
(%o4) {Array: #(NIL NIL NIL NIL NIL NIL NIL)}
(%i5) arrays;
(%o5) [aa, bb, cc]

```

arraysetapply (*A*, [*i*₁, ..., *i*_{*n*}], *x*) Function
 Assigns *x* to *A*[*i*₁, ..., *i*_{*n*}], where *A* is an array and *i*₁, ..., *i*_{*n*} are integers.
arraysetapply evaluates its arguments.

fillarray (*A*, *B*) Function

Fills array *A* from *B*, which is a list or an array.

If a specific type was declared for *A* when it was created, it can only be filled with elements of that same type; it is an error if an attempt is made to copy an element of a different type.

If the dimensions of the arrays *A* and *B* are different, *A* is filled in row-major order. If there are not enough elements in *B* the last element is used to fill out the rest of *A*. If there are too many, the remaining ones are ignored.

fillarray returns its first argument.

Examples:

Create an array of 9 elements and fill it from a list.

```

(%i1) array (a1, fixnum, 8);
(%o1)
      a1
(%i2) listarray (a1);
(%o2) [0, 0, 0, 0, 0, 0, 0, 0]
(%i3) fillarray (a1, [1, 2, 3, 4, 5, 6, 7, 8, 9]);
(%o3)
      a1
(%i4) listarray (a1);
(%o4) [1, 2, 3, 4, 5, 6, 7, 8, 9]

```

When there are too few elements to fill the array, the last element is repeated. When there are too many elements, the extra elements are ignored.

```

(%i1) a2 : make_array (fixnum, 8);
(%o1) {Array: #(0 0 0 0 0 0 0 0)}
(%i2) fillarray (a2, [1, 2, 3, 4, 5]);
(%o2) {Array: #(1 2 3 4 5 5 5 5)}
(%i3) fillarray (a2, [4]);
(%o3) {Array: #(4 4 4 4 4 4 4 4)}
(%i4) fillarray (a2, makelist (i, i, 1, 100));
(%o4) {Array: #(1 2 3 4 5 6 7 8)}

```

Multiple-dimension arrays are filled in row-major order.

```

(%i1) a3 : make_array (fixnum, 2, 5);
(%o1) {Array: #2A((0 0 0 0 0) (0 0 0 0 0))}
(%i2) fillarray (a3, [1, 2, 3, 4, 5, 6, 7, 8, 9, 10]);
(%o2) {Array: #2A((1 2 3 4 5) (6 7 8 9 10))}
(%i3) a4 : make_array (fixnum, 5, 2);
(%o3) {Array: #2A((0 0) (0 0) (0 0) (0 0) (0 0))}
(%i4) fillarray (a4, a3);
(%o4) {Array: #2A((1 2) (3 4) (5 6) (7 8) (9 10))}

```

listarray (A)

Function

Returns a list of the elements of the array *A*. The argument *A* may be a declared array, an undeclared (hashed) array, an array function, or a subscripted function.

Elements are listed in row-major order. That is, elements are sorted according to the first index, then according to the second index, and so on. The sorting order of index values is the same as the order established by **orderless**.

For undeclared arrays, array functions, and subscripted functions, the elements correspond to the index values returned by **arrayinfo**.

Unbound elements of declared general arrays (that is, not **fixnum** and not **flonum**) are returned as **#####**. Unbound elements of declared **fixnum** or **flonum** arrays are returned as 0 or 0.0, respectively. Unbound elements of undeclared arrays, array functions, and subscripted functions are not returned.

Examples:

listarray and **arrayinfo** applied to a declared array.

```
(%i1) array (aa, 2, 3);
(%o1)                                     aa
(%i2) aa [2, 3] : %pi;
(%o2)                                     %pi
(%i3) aa [1, 2] : %e;
(%o3)                                     %e
(%i4) listarray (aa);
(%o4) [#####, #####, #####, #####, #####, #####, %e, #####,
#####, #####, #####, %pi]
(%i5) arrayinfo (aa);
(%o5) [declared, 2, [2, 3]]
```

listarray and **arrayinfo** applied to an undeclared (hashed) array.

```
(%i1) bb [F00] : (a + b)^2;
(%o1)                                     2
                                     (b + a)
(%i2) bb [BAR] : (c - d)^3;
(%o2)                                     3
                                     (c - d)
(%i3) listarray (bb);
(%o3)                                     3          2
                                     [(c - d) , (b + a) ]
(%i4) arrayinfo (bb);
(%o4) [hashed, 1, [BAR], [F00]]
```

listarray and **arrayinfo** applied to an array function.

```
(%i1) cc [x, y] := y / x;
(%o1)                                     y
cc      := -
x, y    x
(%i2) cc [u, v];
(%o2)                                     v
-
u
(%i3) cc [4, z];
(%o3)                                     z
-
4
(%i4) listarray (cc);
(%o4)                                     z v
[-, -]
4 u
```

```

(%i5) arrayinfo (cc);
(%o5) [hashed, 2, [4, z], [u, v]]
listarray and arrayinfo applied to a subscripted function.
(%i1) dd [x] (y) := y ^ x;
(%o1) dd (y) := yx
(%i2) dd [a + b];
(%o2) lambda([y], yb + a)
(%i3) dd [v - u];
(%o3) lambda([y], yv - u)
(%i4) listarray (dd);
(%o4) [lambda([y], yb + a), lambda([y], yv - u)]
(%i5) arrayinfo (dd);
(%o5) [hashed, 1, [b + a], [v - u]]

```

make_array (*type*, *dim_1*, ..., *dim_n*) Function

Creates and returns a Lisp array. *type* may be *any*, *flonum*, *fixnum*, *hashed* or *functional*. There are *n* indices, and the *i*'th index runs from 0 to *dim_i* - 1.

The advantage of *make_array* over *array* is that the return value doesn't have a name, and once a pointer to it goes away, it will also go away. For example, if *y*: *make_array* (...) then *y* points to an object which takes up space, but after *y*: *false*, *y* no longer points to that object, so the object can be garbage collected.

Examples:

```

(%i1) A1 : make_array (fixnum, 10);
(%o1) {Array: #(0 0 0 0 0 0 0 0 0 0)}
(%i2) A1 [8] : 1729;
(%o2) 1729
(%i3) A1;
(%o3) {Array: #(0 0 0 0 0 0 0 0 1729 0)}
(%i4) A2 : make_array (flonum, 10);
(%o4) {Array: #(0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0)}
(%i5) A2 [2] : 2.718281828;
(%o5) 2.718281828
(%i6) A2;
(%o6) {Array: #(0.0 0.0 2.718281828 0.0 0.0 0.0 0.0 0.0 0.0 0.0)}
(%i7) A3 : make_array (any, 10);
(%o7) {Array: #(NIL NIL NIL NIL NIL NIL NIL NIL NIL NIL)}
(%i8) A3 [4] : x - y - z;
(%o8) - z - y + x
(%i9) A3;
(%o9) {Array: #(NIL NIL NIL NIL ((MPLUS SIMP) $X ((MTIMES SIMP) \
-1 $Y) ((MTIMES SIMP) -1 $Z))
NIL NIL NIL NIL NIL)}
(%i10) A4 : make_array (fixnum, 2, 3, 5);
(%o10) {Array: #3A(((0 0 0 0 0) (0 0 0 0 0) (0 0 0 0 0)) ((0 0 \
0 0 0) (0 0 0 0 0) (0 0 0 0 0)))}
(%i11) fillarray (A4, makelist (i, i, 1, 2*3*5));
(%o11) {Array: #3A(((1 2 3 4 5) (6 7 8 9 10) (11 12 13 14 15))
((16 17 18 19 20) (21 22 23 24 25) (26 27 28 29 30)))}

```

```
(%i12) A4 [0, 2, 1];
(%o12)                                     12
```

rearray (*A*, *dim_1*, ..., *dim_n*) Function

Changes the dimensions of an array. The new array will be filled with the elements of the old one in row-major order. If the old array was too small, the remaining elements are filled with **false**, 0.0 or 0, depending on the type of the array. The type of the array cannot be changed.

remarray (*A_1*, ..., *A_n*) Function

remarray (*all*) Function

Removes arrays and array associated functions and frees the storage occupied. The arguments may be declared arrays, undeclared (hashed) arrays, array functions, and sub-scripted functions.

remarray (*all*) removes all items in the global list **arrays**.

It may be necessary to use this function if it is desired to redefine the values in a hashed array.

remarray returns the list of arrays removed.

remarray quotes its arguments.

subvar (*x*, *i*) Function

Evaluates the subscripted expression *x*[*i*].

subvar evaluates its arguments.

arraymake (*x*, [*i*]) constructs the expression *x*[*i*], but does not evaluate it.

Examples:

```
(%i1) x : foo $
(%i2) i : 3 $
(%i3) subvar (x, i);
(%o3)                                     foo
                                           3
(%i4) foo : [aa, bb, cc, dd, ee]$
(%i5) subvar (x, i);
(%o5)                                     cc
(%i6) arraymake (x, [i]);
(%o6)                                     foo
                                           3
(%i7) ' '%;
(%o7)                                     cc
```

subvarp (*expr*) Function

Returns **true** if *expr* is a subscripted variable, for example *a*[*i*].

use_fast_arrays Option variable

If **true** then only two types of arrays are recognized:

1. The art-q array (t in Common Lisp) which may have several dimensions indexed by integers, and may hold any Lisp or Maxima object as an entry. To construct such an array, enter **a:make_array(any,3,4)**; then **a** will have as value, an array with twelve slots, and the indexing is zero based.
2. The Hash_table array which is the default type of array created if one does **b[x+1]:y^2** (and **b** is not already an array, a list, or a matrix – if it were one of these an error would be caused since **x+1** would not be a valid subscript for an art-q array, a list or a matrix). Its indices (also known as keys) may be any object. It only takes one key at a time (**b[x+1,u]:y** would ignore the **u**). Referencing is done by **b[x+1] ==> y^2**. Of course the key may be a list, e.g. **b[[x+1,u]]:y** would be valid. This is incompatible with the old Maxima hash arrays, but saves consing.

An advantage of storing the arrays as values of the symbol is that the usual conventions about local variables of a function apply to arrays as well. The Hash_table type also uses less consing and is more efficient than the old type of Maxima hashar. To obtain consistent behaviour in translated and compiled code set `translate_fast_arrays` to be `true`.

5.6 Structures

5.6.1 Introduction to Structures

Maxima provides a simple data aggregate called a structure. A structure is an expression in which arguments are identified by name (the field name) and the expression as a whole is identified by its operator (the structure name). A field value can be any expression.

A structure is defined by the **defstruct** function; the global variable **structures** is the list of user-defined structures. The function **new** creates instances of structures. The **@** operator refers to fields. **kill**(*S*) removes the structure definition *S*, and **kill**(*x@ a*) unbinds the field *a* of the structure instance *x*.

In the pretty-printing console display (with **display2d** equal to **true**), structure instances are displayed with the value of each field represented as an equation, with the field name on the left-hand side and the value on the right-hand side. (The equation is only a display construct; only the value is actually stored.) In 1-dimensional display (via **grind** or with **display2d** equal to **false**), structure instances are displayed without the field names.

There is no way to use a field name as a function name, although a field value can be a lambda expression. Nor can the values of fields be restricted to certain types; any field can be assigned any kind of expression. There is no way to make some fields accessible or inaccessible in different contexts; all fields are always visible.

5.6.2 Functions and Variables for Structures

structures

Global variable

structures is the list of user-defined structures defined by **defstruct**.

defstruct (*S*(*a₁*, . . . , *a_n*))

Function

defstruct (*S*(*a₁* = *v₁*, . . . , *a_n* = *v_n*))

Function

Define a structure, which is a list of named fields *a₁*, . . . , *a_n* associated with a symbol *S*. An instance of a structure is just an expression which has operator *S* and exactly *n* arguments. **new**(*S*) creates a new instance of structure *S*.

An argument which is just a symbol *a* specifies the name of a field. An argument which is an equation *a* = *v* specifies the field name *a* and its default value *v*. The default value can be any expression.

defstruct puts *S* on the list of user-defined structures, **structures**.

kill(*S*) removes *S* from the list of user-defined structures, and removes the structure definition.

Examples:

```
(%i1) defstruct (foo (a, b, c));
(%o1) [foo(a, b, c)]
(%i2) structures;
(%o2) [foo(a, b, c)]
(%i3) new (foo);
(%o3) foo(a, b, c)
(%i4) defstruct (bar (v, w, x = 123, y = %pi));
(%o4) [bar(v, w, x = 123, y = %pi)]
(%i5) structures;
(%o5) [foo(a, b, c), bar(v, w, x = 123, y = %pi)]
(%i6) new (bar);
(%o6) bar(v, w, x = 123, y = %pi)
(%i7) kill (foo);
(%o7) done
(%i8) structures;
(%o8) [bar(v, w, x = 123, y = %pi)]
```

new	(<i>S</i>)	Function
new	(<i>S</i> (<i>v</i> ₁ , ..., <i>v</i> _{<i>n</i>}))	Function

new creates new instances of structures.

new(*S*) creates a new instance of structure *S* in which each field is assigned its default value, if any, or no value at all if no default was specified in the structure definition.

new(*S*(*v*₁, ..., *v*_{*n*})) creates a new instance of *S* in which fields are assigned the values *v*₁, ..., *v*_{*n*}.

Examples:

```
(%i1) defstruct (foo (w, x = %e, y = 42, z));
(%o1) [foo(w, x = %e, y = 42, z)]
(%i2) new (foo);
(%o2) foo(w, x = %e, y = 42, z)
(%i3) new (foo (1, 2, 4, 8));
(%o3) foo(w = 1, x = 2, y = 4, z = 8)
```

@		Operator
----------	--	----------

@ is the structure field access operator. The expression *x@ a* refers to the value of field *a* of the structure instance *x*. The field name is not evaluated.

If the field *a* in *x* has not been assigned a value, *x@ a* evaluates to itself.

kill(*x@ a*) removes the value of field *a* in *x*.

Examples:

```
(%i1) defstruct (foo (x, y, z));
(%o1) [foo(x, y, z)]
(%i2) u : new (foo (123, a - b, %pi));
(%o2) foo(x = 123, y = a - b, z = %pi)
(%i3) u@z;
(%o3) %pi
(%i4) u@z : %e;
(%o4) %e
(%i5) u;
(%o5) foo(x = 123, y = a - b, z = %e)
(%i6) kill (u@z);
(%o6) done
(%i7) u;
(%o7) foo(x = 123, y = a - b, z)
(%i8) u@z;
(%o8) u@z
```

The field name is not evaluated.

```
(%i1) defstruct (bar (g, h));
(%o1) [bar(g, h)]
(%i2) x : new (bar);
(%o2) bar(g, h)
(%i3) x@h : 42;
(%o3) 42
(%i4) h : 123;
(%o4) 123
(%i5) x@h;
(%o5) 42
(%i6) x@h : 19;
(%o6) 19
(%i7) x;
(%o7) bar(g, h = 19)
(%i8) h;
(%o8) 123
```


6 Expressions

6.1 Introduction to Expressions

There are a number of reserved words which should not be used as variable names. Their use would cause a possibly cryptic syntax error.

integrate	next	from	diff
in	at	limit	sum
for	and	elseif	then
else	do	or	if
unless	product	while	thru
step			

Most things in Maxima are expressions. A sequence of expressions can be made into an expression by separating them by commas and putting parentheses around them. This is similar to the **C** *comma expression*.

```
(%i1) x: 3$
(%i2) (x: x+1, x: x^2);
(%o2)                                16
(%i3) (if (x > 17) then 2 else 4);
(%o3)                                4
(%i4) (if (x > 17) then x: 2 else y: 4, y+x);
(%o4)                                20
```

Even loops in Maxima are expressions, although the value they return is the not too useful done.

```
(%i1) y: (x: 1, for i from 1 thru 10 do (x: x*i))$
(%i2) y;
(%o2)                                done
```

Whereas what you really want is probably to include a third term in the *comma expression* which actually gives back the value.

```
(%i3) y: (x: 1, for i from 1 thru 10 do (x: x*i), x)$
(%i4) y;
(%o4)                                3628800
```

6.2 Nouns and Verbs

Maxima distinguishes between operators which are "nouns" and operators which are "verbs". A verb is an operator which can be executed. A noun is an operator which appears as a symbol in an expression, without being executed. By default, function names are verbs. A verb can be changed into a noun by quoting the function name or applying the **nounify** function. A noun can be changed into a verb by applying the **verbify** function. The evaluation flag **nouns** causes **ev** to evaluate nouns in an expression.

The verb form is distinguished by a leading dollar sign \$ on the corresponding Lisp symbol. In contrast, the noun form is distinguished by a leading percent sign % on the corresponding Lisp symbol. Some nouns have special display properties, such as **'integrate** and **'derivative** (returned by **diff**), but most do not. By default, the noun and verb forms of a function are identical when displayed. The global flag **noundisp** causes Maxima to display nouns with a leading quote mark '.

See also **noun**, **nouns**, **nounify**, and **verbify**.

Examples:

```
(%i1) foo (x) := x^2;
(%o1)                                2
      foo(x) := x
(%i2) foo (42);
(%o2)                                1764
```

```

(%i3) 'foo (42);
(%o3)                                foo(42)
(%i4) 'foo (42), nouns;
(%o4)                                1764
(%i5) declare (bar, noun);
(%o5)                                done
(%i6) bar (x) := x/17;

(%o6)                                x
                                ''bar(x) := --
                                17

(%i7) bar (52);
(%o7)                                bar(52)
(%i8) bar (52), nouns;
(%o8)                                52
                                --
                                17

(%i9) integrate (1/x, x, 1, 42);
(%o9)                                log(42)
(%i10) 'integrate (1/x, x, 1, 42);
(%o10)                                42
                                /
                                [ 1
                                I  - dx
                                ]  x
                                /
                                1

(%i11) ev (% , nouns);
(%o11)                                log(42)

```

6.3 Identifiers

Maxima identifiers may comprise alphabetic characters, plus the numerals 0 through 9, plus any special character preceded by the backslash \ character.

A numeral may be the first character of an identifier if it is preceded by a backslash. Numerals which are the second or later characters need not be preceded by a backslash.

Characters may be declared alphabetic by the **declare** function. If so declared, they need not be preceded by a backslash in an identifier. The alphabetic characters are initially A through Z, a through z, %, and _.

Maxima is case-sensitive. The identifiers `foo`, `F00`, and `Foo` are distinct. See [Section 37.1 \[Lisp and Maxima\], page 477](#) for more on this point.

A Maxima identifier is a Lisp symbol which begins with a dollar sign \$. Any other Lisp symbol is preceded by a question mark ? when it appears in Maxima. See [Section 37.1 \[Lisp and Maxima\], page 477](#) for more on this point.

Examples:

```

(%i1) %an_ordinary_identifier42;
(%o1)                                %an_ordinary_identifier42
(%i2) embedded\ spaces\ in\ an\ identifier;
(%o2)                                embedded spaces in an identifier
(%i3) symbolp (%);
(%o3)                                true
(%i4) [foo+bar, foo\+bar];
(%o4)                                [foo + bar, foo+bar]
(%i5) [1729, \1729];
(%o5)                                [1729, 1729]
(%i6) [symbolp (foo\+bar), symbolp (\1729)];
(%o6)                                [true, true]

```

```
(%i7) [is (foo\+bar = foo+bar), is (\1729 = 1729)];
(%o7) [false, false]
(%i8) baz~quux;
(%o8) baz~quux
(%i9) declare ("~", alphabetic);
(%o9) done
(%i10) baz~quux;
(%o10) baz~quux
(%i11) [is (foo = F00), is (F00 = Foo), is (Foo = foo)];
(%o11) [false, false, false]
(%i12) :lisp (defvar *my-lisp-variable* '$foo)
*MY-LISP-VARIABLE*
(%i12) ?\*my~-lisp~-variable\*;
(%o12) foo
```

6.4 Inequality

Maxima has the inequality operators `<`, `<=`, `>=`, `>`, `#`, and `notequal`. See `if` for a description of conditional expressions.

6.5 Functions and Variables for Expressions

alias (*new_name_1*, *old_name_1*, ..., *new_name_n*, *old_name_n*) Function
 provides an alternate name for a (user or system) function, variable, array, etc. Any even number of arguments may be used.

aliases System variable
 Default value: []
aliases is the list of atoms which have a user defined alias (set up by the `alias`, `ordergreat`, `orderless` functions or by declaring the atom a `noun` with `declare`.
)

allbut Keyword
 works with the `part` commands (i.e. `part`, `inpart`, `substpart`, `substinpart`, `dpart`, and `lpart`). For example,

```
(%i1) expr : e + d + c + b + a;
(%o1) e + d + c + b + a
(%i2) part (expr, [2, 5]);
(%o2) d + a
```

while

```
(%i1) expr : e + d + c + b + a;
(%o1) e + d + c + b + a
(%i2) part (expr, allbut (2, 5));
(%o2) e + c + b
```

`allbut` is also recognized by `kill`.

```
(%i1) [aa : 11, bb : 22, cc : 33, dd : 44, ee : 55];
(%o1) [11, 22, 33, 44, 55]
(%i2) kill (allbut (cc, dd));
(%o0) done
(%i1) [aa, bb, cc, dd];
(%o1) [aa, bb, 33, 44]
```

`kill(allbut(a_1, a_2, ...))` has the effect of `kill(all)` except that it does not kill the symbols *a_1*, *a_2*, ...

args (*expr*) Function
 Returns the list of arguments of *expr*, which may be any kind of expression other than an atom. Only the arguments of the top-level operator are extracted; subexpressions of *expr* appear as elements or subexpressions of elements of the list of arguments.
 The order of the items in the list may depend on the global flag *inflag*.
args (*expr*) is equivalent to *substpart* ("[" , *expr*, 0). See also *substpart*, and *op*.

atom (*expr*) Function
 Returns *true* if *expr* is atomic (i.e. a number, name or string) else *false*. Thus *atom*(5) is *true* while *atom*(*a*[1]) and *atom*(*sin*(*x*)) are *false* (assuming *a*[1] and *x* are unbound).

box (*expr*) Function
box (*expr*, *a*) Function
 Returns *expr* enclosed in a box. The return value is an expression with *box* as the operator and *expr* as the argument. A box is drawn on the display when *display2d* is *true*.
box (*expr*, *a*) encloses *expr* in a box labelled by the symbol *a*. The label is truncated if it is longer than the width of the box.
box evaluates its argument. However, a boxed expression does not evaluate to its content, so boxed expressions are effectively excluded from computations.
boxchar is the character used to draw the box in *box* and in the *dpart* and *lpart* functions.

Examples:

```
(%i1) box (a^2 + b^2);
                                     " 2      2"
                                     "b  + a "
                                     "          "
(%o1)
(%i2) a : 1234;
(%o2)                                1234
(%i3) b : c - d;
(%o3)                                c - d
(%i4) box (a^2 + b^2);
                                     "          2          "
(%o4)                                "(c - d)  + 1522756"
                                     "          "
(%i5) box (a^2 + b^2, term_1);
                                     term_1"          "
                                     "          2          "
(%o5)                                "(c - d)  + 1522756"
                                     "          "
(%i6) 1729 - box (1729);
                                     "          "
(%o6)                                1729 - "1729"
                                     "          "
(%i7) boxchar: "-";
(%o7)                                -
(%i8) box (sin(x) + cos(y));
                                     -----
(%o8)                                -cos(y) + sin(x)-
                                     -----
```

boxchar

Default value: "

Option variable

`boxchar` is the character used to draw the box in the `box` and in the `dpart` and `lpart` functions.

All boxes in an expression are drawn with the current value of `boxchar`; the drawing character is not stored with the box expression.

collapse (*expr*) Function

Collapses *expr* by causing all of its common (i.e., equal) subexpressions to share (i.e., use the same cells), thereby saving space. (`collapse` is a subroutine used by the `optimize` command.) Thus, calling `collapse` may be useful after loading in a `save` file. You can collapse several expressions together by using `collapse ([expr_1, ..., expr_n])`. Similarly, you can collapse the elements of the array `A` by doing `collapse (listarray ('A'))`.

disolate (*expr*, *x_1*, ..., *x_n*) Function

is similar to `isolate` (*expr*, *x*) except that it enables the user to isolate more than one variable simultaneously. This might be useful, for example, if one were attempting to change variables in a multiple integration, and that variable change involved two or more of the integration variables. This function is autoloaded from '`simplification/disol.mac`'. A demo is available by `demo("disol")$`.

dispform (*expr*) Function

dispform (*expr*, *all*) Function

Returns the external representation of *expr*.

`dispform(expr)` returns the external representation with respect to the main (top-level) operator. `dispform(expr, all)` returns the external representation with respect to all operators in *expr*.

See also `part`, `inpart`, and `inflag`.

Examples:

The internal representation of `- x` is "negative one times *x*" while the external representation is "minus *x*".

```
(%i1) - x;
(%o1)                                     - x
(%i2) ?format (true, "~S~%", %);
((MTIMES SIMP) -1 $X)
(%o2)                                     false
(%i3) dispform (- x);
(%o3)                                     - x
(%i4) ?format (true, "~S~%", %);
((MMINUS SIMP) $X)
(%o4)                                     false
```

The internal representation of `sqrt(x)` is "*x* to the power 1/2" while the external representation is "square root of *x*".

```
(%i1) sqrt (x);
(%o1)                                     sqrt(x)
(%i2) ?format (true, "~S~%", %);
((MEXPT SIMP) $X ((RAT SIMP) 1 2))
(%o2)                                     false
(%i3) dispform (sqrt (x));
(%o3)                                     sqrt(x)
(%i4) ?format (true, "~S~%", %);
((%SQRT SIMP) $X)
(%o4)                                     false
```

Use of the optional argument *all*.

```
(%i1) expr : sin (sqrt (x));
(%o1)          sin(sqrt(x))
(%i2) freeof (sqrt, expr);
(%o2)          true
(%i3) freeof (sqrt, dispform (expr));
(%o3)          true
(%i4) freeof (sqrt, dispform (expr, all));
(%o4)          false
```

dpart (*expr*, *n_1*, ..., *n_k*) Function

Selects the same subexpression as **part**, but instead of just returning that subexpression as its value, it returns the whole expression with the selected subexpression displayed inside a box. The box is actually part of the expression.

```
(%i1) dpart (x+y/z^2, 1, 2, 1);
(%o1)          y
          ----- + x
              2
          ""
          "z"
          ""
```

exptisolate Option variable

Default value: **false**

exptisolate, when **true**, causes **isolate** (*expr*, *var*) to examine exponents of atoms (such as %e) which contain *var*.

exptsubst Option variable

Default value: **false**

exptsubst, when **true**, permits substitutions such as *y* for %e^x in %e^(a x).

freeof (*x_1*, ..., *x_n*, *expr*) Function

freeof (*x_1*, *expr*) returns **true** if no subexpression of *expr* is equal to *x_1* or if *x_1* occurs only as a dummy variable in *expr*, or if *x_1* is neither the noun nor verb form of any operator in *expr*, and returns **false** otherwise.

freeof (*x_1*, ..., *x_n*, *expr*) is equivalent to **freeof** (*x_1*, *expr*) and ... and **freeof** (*x_n*, *expr*).

The arguments *x_1*, ..., *x_n* may be names of functions and variables, subscripted names, operators (enclosed in double quotes), or general expressions. **freeof** evaluates its arguments.

freeof operates only on *expr* as it stands (after simplification and evaluation) and does not attempt to determine if some equivalent expression would give a different result. In particular, simplification may yield an equivalent but different expression which comprises some different elements than the original form of *expr*.

A variable is a dummy variable in an expression if it has no binding outside of the expression. Dummy variables recognized by **freeof** are the index of a sum or product, the limit variable in **limit**, the integration variable in the definite integral form of **integrate**, the original variable in **laplace**, formal variables in **at** expressions, and arguments in **lambda** expressions.

The indefinite form of **integrate** is *not* free of its variable of integration.

Examples:

Arguments are names of functions, variables, subscripted names, operators, and expressions. **freeof** (*a*, *b*, *expr*) is equivalent to **freeof** (*a*, *expr*) and **freeof** (*b*, *expr*).

```
(%i1) expr: z^3 * cos (a[1]) * b^(c+d);
                                d + c  3
(%o1)                cos(a ) b      z
                                1

(%i2) freeof (z, expr);
(%o2)                false
(%i3) freeof (cos, expr);
(%o3)                false
(%i4) freeof (a[1], expr);
(%o4)                false
(%i5) freeof (cos (a[1]), expr);
(%o5)                false
(%i6) freeof (b^(c+d), expr);
(%o6)                false
(%i7) freeof ("^", expr);
(%o7)                false
(%i8) freeof (w, sin, a[2], sin (a[2]), b*(c+d), expr);
(%o8)                true
```

`freeof` evaluates its arguments.

```
(%i1) expr: (a+b)^5$
(%i2) c: a$
(%i3) freeof (c, expr);
(%o3)                false
```

`freeof` does not consider equivalent expressions. Simplification may yield an equivalent but different expression.

```
(%i1) expr: (a+b)^5$
(%i2) expand (expr);
          5      4      2 3      3 2      4      5
(%o2)    b  + 5 a b  + 10 a  b  + 10 a  b  + 5 a  b + a
(%i3) freeof (a+b, %);
(%o3)                true
(%i4) freeof (a+b, expr);
(%o4)                false
(%i5) exp (x);
                                x
(%o5)                %e
(%i6) freeof (exp, exp (x));
(%o6)                true
```

A summation or definite integral is free of its dummy variable. An indefinite integral is not free of its variable of integration.

```
(%i1) freeof (i, 'sum (f(i), i, 0, n));
(%o1)                true
(%i2) freeof (x, 'integrate (x^2, x, 0, 1));
(%o2)                true
(%i3) freeof (x, 'integrate (x^2, x));
(%o3)                false
```

inflag

Option variable

Default value: `false`

When `inflag` is `true`, functions for part extraction inspect the internal form of `expr`.

Note that the simplifier re-orders expressions. Thus `first (x + y)` returns `x` if `inflag` is `true` and `y` if `inflag` is `false`. (`first (y + x)` gives the same results.)

Also, setting `inflag` to `true` and calling `part` or `substpart` is the same as calling `inpart` or `substinpart`.

Functions affected by the setting of `inflag` are: `part`, `substpart`, `first`, `rest`, `last`, `length`, the `for ... in` construct, `map`, `fullmap`, `maplist`, `reveal` and `pickapart`.

inpart (*expr*, *n_1*, ..., *n_k*)

Function

is similar to `part` but works on the internal representation of the expression rather than the displayed form and thus may be faster since no formatting is done. Care should be taken with respect to the order of subexpressions in sums and products (since the order of variables in the internal form is often different from that in the displayed form) and in dealing with unary minus, subtraction, and division (since these operators are removed from the expression). `part (x+y, 0)` or `inpart (x+y, 0)` yield `+`, though in order to refer to the operator it must be enclosed in "s. For example ... if `inpart (%o9,0) = "+"` then

Examples:

```
(%i1) x + y + w*z;
(%o1)          w z + y + x
(%i2) inpart (%, 3, 2);
(%o2)          z
(%i3) part (%th (2), 1, 2);
(%o3)          z
(%i4) 'limit (f(x)^g(x+1), x, 0, minus);
(%o4)          limit f(x)
                x -> 0-
                g(x + 1)
(%i5) inpart (%, 1, 2);
(%o5)          g(x + 1)
```

isolate (*expr*, *x*)

Function

Returns *expr* with subexpressions which are sums and which do not contain *var* replaced by intermediate expression labels (these being atomic symbols like `%t1`, `%t2`, ...). This is often useful to avoid unnecessary expansion of subexpressions which don't contain the variable of interest. Since the intermediate labels are bound to the subexpressions they can all be substituted back by evaluating the expression in which they occur.

`exptisolate` (default value: `false`) if `true` will cause `isolate` to examine exponents of atoms (like `%e`) which contain *var*.

`isolate_wrt_times` if `true`, then `isolate` will also isolate with respect to products. See `isolate_wrt_times`.

Do `example (isolate)` for examples.

isolate_wrt_times

Option variable

Default value: `false`

When `isolate_wrt_times` is `true`, `isolate` will also isolate with respect to products. E.g. compare both settings of the switch on

```
(%i1) isolate_wrt_times: true$
(%i2) isolate (expand ((a+b+c)^2), c);

(%t2)          2 a

(%t3)          2 b

(%t4)          2      2
                b  + 2 a b + a
```



```

              2
(%o4)      c  + %t3 c + %t2 c + %t4
(%i4) isolate_wrt_times: false$
(%i5) isolate (expand ((a+b+c)^2), c);
              2
(%o5)      c  + 2 b c + 2 a c + %t4

```

listconstvars

Option variable

Default value: `false`

When `listconstvars` is `true`, it will cause `listofvars` to include `%e`, `%pi`, `%i`, and any variables declared constant in the list it returns if they appear in the expression `listofvars` is called on. The default is to omit these.

listdummyvars

Option variable

Default value: `true`

When `listdummyvars` is `false`, "dummy variables" in the expression will not be included in the list returned by `listofvars`. (The meaning of "dummy variables" is as given in `freeof`. "Dummy variables" are mathematical things like the index of a sum or product, the limit variable, and the definite integration variable.)

Example:

```

(%i1) listdummyvars: true$
(%i2) listofvars ('sum(f(i), i, 0, n));
(%o2)      [i, n]
(%i3) listdummyvars: false$
(%i4) listofvars ('sum(f(i), i, 0, n));
(%o4)      [n]

```

listofvars (expr)

Function

Returns a list of the variables in `expr`.

`listconstvars` if `true` causes `listofvars` to include `%e`, `%pi`, `%i`, and any variables declared constant in the list it returns if they appear in `expr`. The default is to omit these.

See also the option variable `listdummyvars` to exclude or include "dummy variables" in the list of variables.

```

(%i1) listofvars (f (x[1]+y) / g^(2+a));
(%o1)      [g, a, x , y]
              1

```

lfreeof (list, expr)

Function

For each member `m` of `list`, calls `freeof (m, expr)`. It returns `false` if any call to `freeof` does and `true` otherwise.

lpart (label, expr, n_1, ..., n_k)

Function

is similar to `dpart` but uses a labelled box. A labelled box is similar to the one produced by `dpart` but it has a name in the top line.

mainvar

Property

You may declare variables to be `mainvar`. The ordering scale for atoms is essentially: numbers < constants (e.g., `%e`, `%pi`) < scalars < other variables < mainvars. E.g., compare `expand ((X+Y)^4)` with `(declare (x, mainvar), expand ((x+y)^4))`. (Note: Care should be taken if you elect to use the above feature. E.g., if you subtract an expression in which `x` is a `mainvar` from one in which `x` isn't a `mainvar`, resimplification e.g. with `ev (expr, simp)` may be necessary if cancellation is to occur. Also, if you save an expression in which `x` is a `mainvar`, you probably should also save `x`.)

noun

Property

noun is one of the options of the **declare** command. It makes a function so declared a "noun", meaning that it won't be evaluated automatically.

Example:

```
(%i1) factor (12345678);
(%o1)
2
2 3 47 14593
(%i2) declare (factor, noun);
(%o2) done
(%i3) factor (12345678);
(%o3) factor(12345678)
(%i4) ', nouns;
(%o4)
2
2 3 47 14593
```

noundisp

Option variable

Default value: **false**

When **noundisp** is **true**, nouns display with a single quote. This switch is always **true** when displaying function definitions.

nounify (*f*)

Function

Returns the noun form of the function name *f*. This is needed if one wishes to refer to the name of a verb function as if it were a noun. Note that some verb functions will return their noun forms if they can't be evaluated for certain arguments. This is also the form returned if a function call is preceded by a quote.

See also **verbify**.

nterms (*expr*)

Function

Returns the number of terms that *expr* would have if it were fully expanded out and no cancellations or combination of terms occurred. Note that expressions like **sin** (*expr*), **sqr**t (*expr*), **exp** (*expr*), etc. count as just one term regardless of how many terms *expr* has (if it is a sum).

op (*expr*)

Function

Returns the main operator of the expression *expr*. **op** (*expr*) is equivalent to **part** (*expr*, 0).

op returns a string if the main operator is a built-in or user-defined prefix, binary or n-ary infix, postfix, matchfix, or nofix operator. Otherwise, if *expr* is a subscripted function expression, **op** returns the subscripted function; in this case the return value is not an atom. Otherwise, *expr* is an array function or ordinary function expression, and **op** returns a symbol.

op observes the value of the global flag **inflag**.

op evaluates its argument.

See also **args**.

Examples:

```
(%i1) stringdisp: true$
(%i2) op (a * b * c);
(%o2) "*"
(%i3) op (a * b + c);
(%o3) "+"
(%i4) op ('sin (a + b));
(%o4) sin
(%i5) op (a!);
```

```

(%o5)                                "!"
(%i6) op (-a);
(%o6)                                "- "
(%i7) op ([a, b, c]);
(%o7)                                "["
(%i8) op ('(if a > b then c else d));
(%o8)                                "if"
(%i9) op ('foo (a));
(%o9)                                foo
(%i10) prefix (foo);
(%o10)                               "foo"
(%i11) op (foo a);
(%o11)                               "foo"
(%i12) op (F [x, y] (a, b, c));
(%o12)                               F
                                      x, y
(%i13) op (G [u, v, w]);
(%o13)                               G

```

operatorp (*expr*, *op*) Function
operatorp (*expr*, [*op_1*, ..., *op_n*]) Function

operatorp (*expr*, *op*) returns **true** if *op* is equal to the operator of *expr*.

operatorp (*expr*, [*op_1*, ..., *op_n*]) returns **true** if some element *op_1*, ..., *op_n* is equal to the operator of *expr*.

opsubst Option variable

Default value: **true**

When **opsubst** is **false**, **subst** does not attempt to substitute into the operator of an expression. E.g., (**opsubst**: **false**, **subst** (x^2 , *r*, $r+r[0]$)) will work.

optimize (*expr*) Function

Returns an expression that produces the same value and side effects as *expr* but does so more efficiently by avoiding the recomputation of common subexpressions. **optimize** also has the side effect of "collapsing" its argument so that all common subexpressions are shared. Do **example** (**optimize**) for examples.

optimprefix Option variable

Default value: **%**

optimprefix is the prefix used for generated symbols by the **optimize** command.

ordergreat (*v_1*, ..., *v_n*) Function

orderless (*v_1*, ..., *v_n*) Function

ordergreat changes the canonical ordering of Maxima expressions such that *v_1* succeeds *v_2* succeeds ... succeeds *v_n*, and *v_n* succeeds any other symbol not mentioned as an argument.

orderless changes the canonical ordering of Maxima expressions such that *v_1* precedes *v_2* precedes ... precedes *v_n*, and *v_n* precedes any other variable not mentioned as an argument.

The order established by **ordergreat** and **orderless** is dissolved by **unorder**. **ordergreat** and **orderless** can be called only once each, unless **unorder** is called; only the last call to **ordergreat** and **orderless** has any effect.

See also **ordergreatp**.

ordergreatp (<i>expr_1</i> , <i>expr_2</i>)	Function
orderlessp (<i>expr_1</i> , <i>expr_2</i>)	Function

ordergreatp returns **true** if *expr_1* succeeds *expr_2* in the canonical ordering of Maxima expressions, and **false** otherwise.

orderlessp returns **true** if *expr_1* precedes *expr_2* in the canonical ordering of Maxima expressions, and **false** otherwise.

All Maxima atoms and expressions are comparable under **ordergreatp** and **orderlessp**, although there are isolated examples of expressions for which these predicates are not transitive; that is a bug.

The canonical ordering of atoms (symbols, literal numbers, and strings) is the following. (integers and floats) precede (bigfloats) precede (declared constants) precede (strings) precede (declared scalars) precede (first argument to **orderless**) precedes ... precedes (last argument to **orderless**) precedes (other symbols) precede (last argument to **ordergreat**) precedes ... precedes (first argument to **ordergreat**) precedes (declared main variables)

For non-atomic expressions, the canonical ordering is derived from the ordering for atoms. For the built-in **+** ***** and **^** operators, the ordering is not easily summarized. For other built-in operators and all other functions and operators, expressions are ordered by their arguments (beginning with the first argument), then by the name of the operator or function. In the case of subscripted expressions, the subscripted symbol is considered the operator and the subscript is considered an argument.

The canonical ordering of expressions is modified by the functions **ordergreat** and **orderless**, and the **mainvar**, **constant**, and **scalar** declarations.

See also **sort**.

Examples:

Ordering ordinary symbols and constants. Note that **%pi** is not ordered according to its numerical value.

```
(%i1) stringdisp : true;
(%o1)                                     true
(%i2) sort([%pi, 3b0, 3.0, x, X, "foo", 3, a, 4, "bar", 4.0, 4b0]);
(%o2) [3, 3.0, 4, 4.0, 3.0b0, 4.0b0, %pi, "bar", "foo", a, x, X]
```

Effect of **ordergreat** and **orderless** functions.

```
(%i1) sort ([M, H, K, T, E, W, G, A, P, J, S]);
(%o1)      [A, E, G, H, J, K, M, P, S, T, W]
(%i2) ordergreat (S, J);
(%o2)                                     done
(%i3) orderless (M, H);
(%o3)                                     done
(%i4) sort ([M, H, K, T, E, W, G, A, P, J, S]);
(%o4)      [M, H, A, E, G, K, P, T, W, J, S]
```

Effect of **mainvar**, **constant**, and **scalar** declarations.

```
(%i1) sort ([aa, foo, bar, bb, baz, quux, cc, dd, A1, B1, C1]);
(%o1)      [aa, bar, baz, bb, cc, dd, foo, quux, A1, B1, C1]
(%i2) declare (aa, mainvar);
(%o2)                                     done
(%i3) declare ([baz, quux], constant);
(%o3)                                     done
(%i4) declare ([A1, B1], scalar);
(%o4)                                     done
(%i5) sort ([aa, foo, bar, bb, baz, quux, cc, dd, A1, B1, C1]);
(%o5)      [baz, quux, A1, B1, bar, bb, cc, dd, foo, C1, aa]
```

Ordering non-atomic expressions.

```
(%i1) sort([1, 2, n, f(1), f(2), f(2, 1), g(1), g(1, 2), g(n),
           f(n, 1)]);
(%o1) [1, 2, f(1), g(1), g(1, 2), f(2), f(2, 1), n, g(n),
```

```

                                                    f(n, 1)]
(%i2) sort ([foo(1), X[1], X[k], foo(k), 1, k]);
(%o2)      [1, foo(1), X , k, foo(k), X ]
                1           k

```

part (*expr*, *n*₁, ..., *n*_{*k*}) Function

Returns parts of the displayed form of *expr*. It obtains the part of *expr* as specified by the indices *n*₁, ..., *n*_{*k*}. First part *n*₁ of *expr* is obtained, then part *n*₂ of that, etc. The result is part *n*_{*k*} of ... part *n*₂ of part *n*₁ of *expr*. If no indices are specified *expr* is returned.

part can be used to obtain an element of a list, a row of a matrix, etc.

If the last argument to a **part** function is a list of indices then several subexpressions are picked out, each one corresponding to an index of the list. Thus **part** (*x* + *y* + *z*, [1, 3]) is *z* + *x*.

piece holds the last expression selected when using the **part** functions. It is set during the execution of the function and thus may be referred to in the function itself as shown below.

If **partswitch** is set to **true** then **end** is returned when a selected part of an expression doesn't exist, otherwise an error message is given.

See also **inpart**, **substpart**, **substinpart**, **dpart**, and **lpart**.

Examples:

```

(%i1) part(z+2*y+a,2);
(%o1)                                     2 y
(%i2) part(z+2*y+a,[1,3]);
(%o2)                                     z + a
(%i3) part(z+2*y+a,2,1);
(%o3)                                     2

```

example (**part**) displays additional examples.

partition (*expr*, *x*) Function

Returns a list of two expressions. They are (1) the factors of *expr* (if it is a product), the terms of *expr* (if it is a sum), or the list (if it is a list) which don't contain *x* and, (2) the factors, terms, or list which do.

Examples:

```

(%i1) partition (2*a*x*f(x), x);
(%o1)          [2 a, x f(x)]
(%i2) partition (a+b, x);
(%o2)          [b + a, 0]
(%i3) partition ([a, b, f(a), c], a);
(%o3)          [[b, c], [a, f(a)]]

```

partswitch Option variable

Default value: **false**

When **partswitch** is **true**, **end** is returned when a selected part of an expression doesn't exist, otherwise an error message is given.

pickapart (*expr*, *n*) Function

Assigns intermediate expression labels to subexpressions of *expr* at depth *n*, an integer. Subexpressions at greater or lesser depths are not assigned labels. **pickapart** returns an expression in terms of intermediate expressions equivalent to the original expression *expr*.

See also **part**, **dpart**, **lpart**, **inpart**, and **reveal**.

Examples:

```
(%i1) expr: (a+b)/2 + sin (x^2)/3 - log (1 + sqrt(x+1));
```

```
(%o1)          2
              sin(x )   b + a
          - log(sqrt(x + 1) + 1) + ---- + ----
                                3       2
```

```
(%i2) pickapart (expr, 0);
```

```
(%t2)          2
              sin(x )   b + a
          - log(sqrt(x + 1) + 1) + ---- + ----
                                3       2
```

```
(%o2)          %t2
```

```
(%i3) pickapart (expr, 1);
```

```
(%t3)          - log(sqrt(x + 1) + 1)
```

```
(%t4)          2
              sin(x )
            -----
                3
```

```
(%t5)          b + a
            -----
                2
```

```
(%o5)          %t5 + %t4 + %t3
```

```
(%i5) pickapart (expr, 2);
```

```
(%t6)          log(sqrt(x + 1) + 1)
```

```
(%t7)          2
              sin(x )
```

```
(%t8)          b + a
```

```
(%o8)          %t8   %t7
            --- + --- - %t6
              2     3
```

```
(%i8) pickapart (expr, 3);
```

```
(%t9)          sqrt(x + 1) + 1
```

```
(%t10)         2
              x
```

```
(%o10)          b + a          sin(%t10)
            ----- - log(%t9) + -----
                2              3
```

```
(%i10) pickapart (expr, 4);
```

```
(%t11)          sqrt(x + 1)
```

```

              2
      sin(x )  b + a
(%o11)  ----- + ----- - log(%t11 + 1)
              3      2

(%i11) pickapart (expr, 5);

(%t12)
              x + 1

              2
      sin(x )  b + a
(%o12)  ----- + ----- - log(sqrt(%t12) + 1)
              3      2

(%i12) pickapart (expr, 6);

              2
      sin(x )  b + a
(%o12)  ----- + ----- - log(sqrt(x + 1) + 1)
              3      2

```

piece

System variable

Holds the last expression selected when using the **part** functions. It is set during the execution of the function and thus may be referred to in the function itself.

psubst (*list*, *expr*)

Function

psubst (*a*, *b*, *expr*)

Function

psubst(*a*, *b*, *expr*) is similar to **subst**. See **subst**.

In distinction from **subst** the function **psubst** makes parallel substitutions, if the first argument *list* is a list of equations.

See also **sublis** for making parallel substitutions.

Example:

The first example shows parallel substitution with **psubst**. The second example shows the result for the function **subst**, which does a serial substitution.

```

(%i4) psubst ([a^2=b, b=a], sin(a^2) + sin(b));
(%o4)
              sin(b) + sin(a)
(%i5) subst ([a^2=b, b=a], sin(a^2) + sin(b));
(%o5)
              2 sin(a)

```

rembox (*expr*, *unlabelled*)

Function

rembox (*expr*, *label*)

Function

rembox (*expr*)

Function

Removes boxes from *expr*.

rembox (*expr*, *unlabelled*) removes all unlabelled boxes from *expr*.

rembox (*expr*, *label*) removes only boxes bearing *label*.

rembox (*expr*) removes all boxes, labelled and unlabelled.

Boxes are drawn by the **box**, **dpart**, and **lpart** functions.

Examples:

```

(%i1) expr: (a*d - b*c)/h^2 + sin(%pi*x);
              a d - b c
(%o1)
              sin(%pi x) + -----
                          2
                          h
(%i2) dpart (dpart (expr, 1, 1), 2, 2);
              " " " " " " " " " "
              a d - b c
(%o2)
              sin("%pi x") + -----

```

```

              " 2"
              "h "
              ""
(%i3) expr2: lpart (BAR, lpart (FOO, %, 1), 2);
FOO" " BAR" "
" " "a d - b c"
(%o3) "sin("%pi x")" + "-----"
" " " " 2" "
" "h " "
" " "
" "
" "

(%i4) rembox (expr2, unlabelled);
BAR" "
FOO" " "a d - b c"
(%o4) "sin("%pi x")" + "-----"
" 2 "
" h "
" "

(%i5) rembox (expr2, FOO);
BAR" "
" " "a d - b c"
(%o5) sin("%pi x") + "-----"
" " "
" " 2" "
" "h " "
" " "
" "

(%i6) rembox (expr2, BAR);
FOO" "
" " "a d - b c"
(%o6) "sin("%pi x")" + -----
" " "
" " 2"
" h "
" "

(%i7) rembox (expr2);
a d - b c
(%o7) sin(%pi x) + -----
2
h

```

reveal (*expr*, *depth*)

Function

Replaces parts of *expr* at the specified integer *depth* with descriptive summaries.

- Sums and differences are replaced by `Sum(n)` where *n* is the number of operands of the sum.
- Products are replaced by `Product(n)` where *n* is the number of operands of the product.
- Exponentials are replaced by `Expt`.
- Quotients are replaced by `Quotient`.
- Unary negation is replaced by `Negterm`.
- Lists are replaced by `List(n)` where *n* is the number of elements of the list.

When *depth* is greater than or equal to the maximum depth of *expr*, `reveal (expr, depth)` returns *expr* unmodified.

`reveal` evaluates its arguments. `reveal` returns the summarized expression.

Example:

```
(%i1) e: expand ((a - b)^2)/expand ((exp(a) + exp(b))^2);
                                     2      2
                                     b  - 2 a b + a
(%o1) -----
          b + a      2 b      2 a
      2 %e      + %e      + %e
(%i2) reveal (e, 1);
(%o2) Quotient
(%i3) reveal (e, 2);
          Sum(3)
          -----
          Sum(3)
(%i4) reveal (e, 3);
          Expt + Negterm + Expt
          -----
          Product(2) + Expt + Expt
(%i5) reveal (e, 4);
          2      2
          b  - Product(3) + a
(%o5) -----
          Product(2)      Product(2)
      2 Expt + %e      + %e
(%i6) reveal (e, 5);
          2      2
          b  - 2 a b + a
(%o6) -----
          Sum(2)      2 b      2 a
      2 %e      + %e      + %e
(%i7) reveal (e, 6);
          2      2
          b  - 2 a b + a
(%o7) -----
          b + a      2 b      2 a
      2 %e      + %e      + %e
```

sublis (*list*, *expr*)

Function

Makes multiple parallel substitutions into an expression. *list* is a list of equations. The left hand side of the equations must be an atom.

The variable `sublis_apply_lambda` controls simplification after `sublis`.

See also `psubst` for making parallel substitutions.

Example:

```
(%i1) sublis ([a=b, b=a], sin(a) + cos(b));
(%o1) sin(b) + cos(a)
```

sublis_apply_lambda

Option variable

Default value: `true`

Controls whether `lambda`'s substituted are applied in simplification after `sublis` is used or whether you have to do an `ev` to get things to apply. `true` means do the application.

subnumsimp

Option variable

Default value: `false`

If **true** then the functions **subst** and **psubst** can substitute a subscripted variable **f[x]** with a number, when only the symbol **f** is given.

See also **subst**.

```
(%i1) subst(100,g,g[x]+2);

subst: cannot substitute 100 for operator g in expression g
                                         x
-- an error. To debug this try: debugmode(true);

(%i2) subst(100,g,g[x]+2),subnumsimp:true;
(%o2)                                     102
```

subst (*a*, *b*, *c*)

Function

Substitutes *a* for *b* in *c*. *b* must be an atom or a complete subexpression of *c*. For example, *x+y+z* is a complete subexpression of $2*(x+y+z)/w$ while *x+y* is not. When *b* does not have these characteristics, one may sometimes use **substpart** or **ratsubst** (see below). Alternatively, if *b* is of the form *e/f* then one could use **subst** (*a*f*, *e*, *c*) while if *b* is of the form $e^{(1/f)}$ then one could use **subst** (*a^f*, *e*, *c*). The **subst** command also discerns the x^y in x^{-y} so that **subst** (*a*, **sqrt**(*x*), $1/\text{sqrt}(x)$) yields $1/a$. *a* and *b* may also be operators of an expression enclosed in double-quotes " or they may be function names. If one wishes to substitute for the independent variable in derivative forms then the **at** function (see below) should be used.

subst is an alias for **substitute**.

The commands **subst** (*eq-1*, *expr*) or **subst** (*[eq-1, ..., eq-k]*, *expr*) are other permissible forms. The *eq-i* are equations indicating substitutions to be made. For each equation, the right side will be substituted for the left in the expression *expr*. The equations are substituted in serial from left to right in *expr*. See the functions **sublis** and **psubst** for making parallel substitutions.

exptsust if **true** permits substitutions like *y* for e^x in $e^{(a*x)}$ to take place.

When **opsubst** is **false**, **subst** will not attempt to substitute into the operator of an expression. E.g. (**opsubst: false**, **subst** (x^2 , *r*, *r+r[0]*)) will work.

Examples:

```
(%i1) subst (a, x+y, x + (x+y)^2 + y);
                                         2
(%o1)                                     y + x + a
(%i2) subst (-%i, %i, a + b*%i);
(%o2)                                     a - %i b
```

The substitution is done in serial for a list of equations. Compare this with a parallel substitution:

```
(%i3) subst([a=b, b=c], a+b);
(%o3)                                     2 c
(%i4) sublis([a=b, b=c], a+b);
(%o4)                                     c + b
```

For further examples, do **example (subst)**.

substinpart (*x*, *expr*, *n-1*, ..., *n-k*)

Function

Similar to **substpart**, but **substinpart** works on the internal representation of *expr*.

Examples:

```
(%i1) x . 'diff (f(x), x, 2);
                                         2
                                         d
(%o1)                                     x . (--- (f(x)))
                                         2
                                         dx
```

```
(%i2) substinpart (d^2, %, 2);
(%o2)

$$x^2 \cdot d$$

(%i3) substinpart (f1, f[1](x + 1), 0);
(%o3)

$$f1(x + 1)$$

```

If the last argument to a **part** function is a list of indices then several subexpressions are picked out, each one corresponding to an index of the list. Thus

```
(%i1) part (x + y + z, [1, 3]);
(%o1)

$$z + x$$

```

piece holds the value of the last expression selected when using the **part** functions. It is set during the execution of the function and thus may be referred to in the function itself as shown below. If **partswitch** is set to **true** then **end** is returned when a selected part of an expression doesn't exist, otherwise an error message is given.

```
(%i1) expr: 27*y^3 + 54*x*y^2 + 36*x^2*y + y + 8*x^3 + x + 1;
(%o1)

$$27 y^3 + 54 x y^2 + 36 x^2 y + y + 8 x^3 + x + 1$$

(%i2) part (expr, 2, [1, 3]);
(%o2)

$$54 y^2$$

(%i3) sqrt (piece/54);
(%o3)

$$\text{abs}(y)$$

(%i4) substpart (factor (piece), expr, [1, 2, 3, 5]);
(%o4)

$$(3 y + 2 x)^3 + y + x + 1$$

(%i5) expr: 1/x + y/x - 1/z;
(%o5)

$$-\frac{1}{z} + \frac{y}{x} - \frac{1}{x}$$

(%i6) substpart (xthru (piece), expr, [2, 3]);
(%o6)

$$\frac{y + 1}{x} - \frac{1}{z}$$

```

Also, setting the option **inflag** to **true** and calling **part** or **substpart** is the same as calling **inpart** or **substinpart**.

substpart (*x*, *expr*, *n₁*, ..., *n_k*) Function

Substitutes *x* for the subexpression picked out by the rest of the arguments as in **part**. It returns the new value of *expr*. *x* may be some operator to be substituted for an operator of *expr*. In some cases *x* needs to be enclosed in double-quotes " (e.g. **substpart** ("+", **a*b**, 0) yields **b + a**).

Example:

```
(%i1) 1/(x^2 + 2);
(%o1)

$$\frac{1}{x^2 + 2}$$

(%i2) substpart (3/2, %, 2, 1, 2);
(%o2)

$$\frac{3/2}{x^2 + 2}$$

(%i3) a*x + f(b, y);
(%o3)

$$a x + f(b, y)$$

(%i4) substpart ("+", %, 1, 0);
(%o4)

$$x + f(b, y) + a$$

```

Also, setting the option `inflag` to `true` and calling `part` or `substpart` is the same as calling `inpart` or `substinpart`.

symbolp (*expr*)

Function

Returns `true` if *expr* is a symbol, else `false`. In effect, `symbolp(x)` is equivalent to the predicate `atom(x)` and not `numberp(x)`.

See also [Section 6.3 \[Identifiers\]](#), page 60.

unorder ()

Function

Disables the aliasing created by the last use of the ordering commands `ordergreat` and `orderless`. `ordergreat` and `orderless` may not be used more than one time each without calling `unorder`. `unorder` does not substitute back in expressions the original symbols for the aliases introduced by `ordergreat` and `orderless`. Therefore, after execution of `unorder` the aliases appear in previous expressions.

See also `ordergreat` and `orderless`.

Examples:

`ordergreat(a)` introduces an alias for the symbol `a`. Therefore, the difference of `%o2` and `%o4` does not vanish. `unorder` does not substitute back the symbol `a` and the alias appears in the output `%o7`.

```
(%i1) unorder();
(%o1)
[]
(%i2) b*x+a^2;

                2
(%o2)      b x + a
(%i3) ordergreat(a);
(%o3)      done
(%i4) b*x+a^2;

                2
(%o4)      a  + b x
(%i5) %th(1)-%th(3);

                2    2
(%o5)      a  - a
(%i6) unorder();
(%o6)      [a]
(%i7) %th(2);

                2    2
(%o7)      _101a  - a
```

verbify (*f*)

Function

Returns the verb form of the function name *f*. See also `verb`, `noun`, and `nounify`.

Examples:

```
(%i1) verbify ('foo);
(%o1)      foo
(%i2) :lisp $%
$F00
(%i2) nounify (foo);
(%o2)      foo
(%i3) :lisp $%
%F00
```

7 Operators

7.1 Introduction to operators

It is possible to define new operators with specified precedence, to undefine existing operators, or to redefine the precedence of existing operators. An operator may be unary prefix or unary postfix, binary infix, n-ary infix, matchfix, or nofix. "Matchfix" means a pair of symbols which enclose their argument or arguments, and "nofix" means an operator which takes no arguments. As examples of the different types of operators, there are the following.

unary prefix

negation $-a$

unary postfix

factorial $a!$

binary infix

exponentiation a^b

n-ary infix addition $a + b$

matchfix list construction $[a, b]$

(There are no built-in nofix operators; for an example of such an operator, see `nofix`.)

The mechanism to define a new operator is straightforward. It is only necessary to declare a function as an operator; the operator function might or might not be defined.

An example of user-defined operators is the following. Note that the explicit function call `"dd" (a)` is equivalent to `dd a`, likewise `"<-" (a, b)` is equivalent to `a <- b`. Note also that the functions `"dd"` and `"<-"` are undefined in this example.

```
(%i1) prefix ("dd");
(%o1)                                     dd
(%i2) dd a;
(%o2)                                     dd a
(%i3) "dd" (a);
(%o3)                                     dd a
(%i4) infix ("<-");
(%o4)                                     <-
(%i5) a <- dd b;
(%o5)                                     a <- dd b
(%i6) "<-" (a, "dd" (b));
(%o6)                                     a <- dd b
```

The Maxima functions which define new operators are summarized in this table, stating the default left and right binding powers (lbp and rbp, respectively). (Binding power determines operator precedence. However, since left and right binding powers can differ, binding power is somewhat more complicated than precedence.) Some of the operation definition functions take additional arguments; see the function descriptions for details.

`prefix` rbp=180

`postfix` lbp=180

`infix` lbp=180, rbp=180

`nary` lbp=180, rbp=180

`matchfix` (binding power not applicable)

`nofix` (binding power not applicable)

For comparison, here are some built-in operators and their left and right binding powers.

Operator	lbp	rbp
:	180	20
::	180	20
:=	180	20
::=	180	20
!	160	
!!	160	
^	140	139
.	130	129
*	120	
/	120	120
+	100	100
-	100	134
=	80	80
#	80	80
>	80	80
>=	80	80
<	80	80
<=	80	80
not		70
and	65	
or	60	
,	10	
\$	-1	
;	-1	

remove and **kill** remove operator properties from an atom. **remove** ("a", op) removes only the operator properties of a. **kill** ("a") removes all properties of a, including the operator properties. Note that the name of the operator must be enclosed in quotation marks.

```
(%i1) infix ("##");
(%o1)                                     ##
(%i2) "##" (a, b) := a^b;
                                     b
(%o2)                                a ## b := a
(%i3) 5 ## 3;
(%o3)                                125
(%i4) remove ("##", op);
(%o4)                                done
(%i5) 5 ## 3;
Incorrect syntax: # is not a prefix operator
5 ##
^
(%i5) "##" (5, 3);
(%o5)                                125
(%i6) infix ("##");
(%o6)                                ##
(%i7) 5 ## 3;
(%o7)                                125
(%i8) kill ("##");
(%o8)                                done
(%i9) 5 ## 3;
Incorrect syntax: # is not a prefix operator
5 ##
^
(%i9) "##" (5, 3);
(%o9)                                ##(5, 3)
```

7.2 Arithmetic operators

+	Operator
-	Operator
*	Operator
/	Operator
^	Operator

The symbols `+` `*` `/` and `^` represent addition, multiplication, division, and exponentiation, respectively. The names of these operators are `"+"` `"*"` `"/"` and `"^"`, which may appear where the name of a function or operator is required.

The symbols `+` and `-` represent unary addition and negation, respectively, and the names of these operators are `"+"` and `"-"`, respectively.

Subtraction `a - b` is represented within Maxima as addition, `a + (- b)`. Expressions such as `a + (- b)` are displayed as subtraction. Maxima recognizes `"-"` only as the name of the unary negation operator, and not as the name of the binary subtraction operator.

Division `a / b` is represented within Maxima as multiplication, `a * b^(- 1)`. Expressions such as `a * b^(- 1)` are displayed as division. Maxima recognizes `"/"` as the name of the division operator.

Addition and multiplication are n-ary, commutative operators. Division and exponentiation are binary, noncommutative operators.

Maxima sorts the operands of commutative operators to construct a canonical representation. For internal storage, the ordering is determined by `orderlessp`. For display, the ordering for addition is determined by `ordergreatp`, and for multiplication, it is the same as the internal ordering.

Arithmetic computations are carried out on literal numbers (integers, rationals, ordinary floats, and bigfloats). Except for exponentiation, all arithmetic operations on numbers are simplified to numbers. Exponentiation is simplified to a number if either operand is an ordinary float or bigfloat or if the result is an exact integer or rational; otherwise an exponentiation may be simplified to `sqrt` or another exponentiation or left unchanged.

Floating-point contagion applies to arithmetic computations: if any operand is a bigfloat, the result is a bigfloat; otherwise, if any operand is an ordinary float, the result is an ordinary float; otherwise, the operands are rationals or integers and the result is a rational or integer.

Arithmetic computations are a simplification, not an evaluation. Thus arithmetic is carried out in quoted (but simplified) expressions.

Arithmetic operations are applied element-by-element to lists when the global flag `listarith` is `true`, and always applied element-by-element to matrices. When one operand is a list or matrix and another is an operand of some other type, the other operand is combined with each of the elements of the list or matrix.

Examples:

Addition and multiplication are n-ary, commutative operators. Maxima sorts the operands to construct a canonical representation. The names of these operators are `"+"` and `"*"`.

```
(%i1) c + g + d + a + b + e + f;
(%o1) g + f + e + d + c + b + a
(%i2) [op (%), args (%)];
(%o2) [+ , [g, f, e, d, c, b, a]]
(%i3) c * g * d * a * b * e * f;
(%o3) a b c d e f g
(%i4) [op (%), args (%)];
(%o4) [* , [a, b, c, d, e, f, g]]
(%i5) apply ("+", [a, 8, x, 2, 9, x, x, a]);
(%o5) 3 x + 2 a + 19
(%i6) apply ("*", [a, 8, x, 2, 9, x, x, a]);
(%o6) 144 a x2 3
```

Division and exponentiation are binary, noncommutative operators. The names of these operators are "/" and "^".

```
(%i1) [a / b, a ^ b];
(%o1)
      a  b
      [-, a ]
      b
(%i2) [map (op, %), map (args, %)];
(%o2) [[/, ^], [[a, b], [a, b]]]
(%i3) [apply ("/", [a, b]), apply ("^", [a, b])];
(%o3)
      a  b
      [-, a ]
      b
```

Subtraction and division are represented internally in terms of addition and multiplication, respectively.

```
(%i1) [inpart (a - b, 0), inpart (a - b, 1), inpart (a - b, 2)];
(%o1)
      +, a, - b
(%i2) [inpart (a / b, 0), inpart (a / b, 1), inpart (a / b, 2)];
(%o2)
      1
      [* , a, -]
      b
```

Computations are carried out on literal numbers. Floating-point contagion applies.

```
(%i1) 17 + b - (1/2)*29 + 11^(2/4);
(%o1)
      b + sqrt(11) + -
      2
(%i2) [17 + 29, 17 + 29.0, 17 + 29b0];
(%o2) [46, 46.0, 4.6b1]
```

Arithmetic computations are a simplification, not an evaluation.

```
(%i1) simp : false;
(%o1)
      false
(%i2) '(17 + 29*11/7 - 5^3);
(%o2)
      29 11 3
      17 + ---- - 5
      7
(%i3) simp : true;
(%o3)
      true
(%i4) '(17 + 29*11/7 - 5^3);
(%o4)
      437
      - ---
      7
```

Arithmetic is carried out element-by-element for lists (depending on `listarith`) and matrices.

```
(%i1) matrix ([a, x], [h, u]) - matrix ([1, 2], [3, 4]);
(%o1)
      [ a - 1  x - 2 ]
      [
      [ h - 3  u - 4 ]
(%i2) 5 * matrix ([a, x], [h, u]);
(%o2)
      [ 5 a  5 x ]
      [
      [ 5 h  5 u ]
(%i3) listarith : false;
(%o3)
      false
(%i4) [a, c, m, t] / [1, 7, 2, 9];
(%o4)
      [a, c, m, t]
      -----
```



```

                                [1, 7, 2, 9]
(%i5) [a, c, m, t] ^ x;
                                x
(%o5) [a, c, m, t]
(%i6) listarith : true;
(%o6) true
(%i7) [a, c, m, t] / [1, 7, 2, 9];
                                c m t
(%o7) [a, -, -, -]
                                7 2 9
(%i8) [a, c, m, t] ^ x;
                                x x x x
(%o8) [a , c , m , t ]

```

Operator

Exponentiation operator. Maxima recognizes ****** as the same operator as **^** in input, and it is displayed as **^** in 1-dimensional output, or by placing the exponent as a superscript in 2-dimensional output.

The **fortran** function displays the exponentiation operator as ******, whether it was input as ****** or **^**.

Examples:

```

(%i1) is (a**b = a^b);
(%o1) true
(%i2) x**y + x^z;
                                z y
(%o2) x + x
(%i3) string (x**y + x^z);
(%o3) x^z+x^y
(%i4) fortran (x**y + x^z);
                                x**z+x**y
(%o4) done

```

^^

Operator

Noncommutative exponentiation operator. **^^** is the exponentiation operator corresponding to noncommutative multiplication **.**, just as the ordinary exponentiation operator **^** corresponds to commutative multiplication *****.

Noncommutative exponentiation is displayed by **^^** in 1-dimensional output, and by placing the exponent as a superscript within angle brackets **< >** in 2-dimensional output.

Examples:

```

(%i1) a . a . b . b . b + a * a * a * b * b;
                                3 2 <2> <3>
(%o1) a b + a . b
(%i2) string (a . a . b . b . b + a * a * a * b * b);
(%o2) a^3*b^2+a^^2 . b^3

```

.

Operator

The dot operator, for matrix (non-commutative) multiplication. When **."** is used in this way, spaces should be left on both sides of it, e.g. **A . B**. This distinguishes it plainly from a decimal point in a floating point number.

See also **dot**, **dot0nscsimp**, **dot0simp**, **dot1simp**, **dotassoc**, **dotconstrules**, **dotdistrib**, **dotexptsimp**, **dotident**, and **dotscrules**.

7.3 Relational operators

<	Operator
<=	Operator
>=	Operator
>	Operator

The symbols < <= >= and > represent less than, less than or equal, greater than or equal, and greater than, respectively. The names of these operators are "<" "<=" ">=" and ">", which may appear where the name of a function or operator is required.

These relational operators are all binary operators; constructs such as `a < b < c` are not recognized by Maxima.

Relational expressions are evaluated to Boolean values by the functions `is` and `maybe`, and the programming constructs `if`, `while`, and `unless`. Relational expressions are not otherwise evaluated or simplified to Boolean values, although the arguments of relational expressions are evaluated (when evaluation is not otherwise prevented by quotation).

When a relational expression cannot be evaluated to `true` or `false`, the behavior of `is` and `if` are governed by the global flag `prederror`. When `prederror` is `true`, `is` and `if` trigger an error. When `prederror` is `false`, `is` returns `unknown`, and `if` returns a partially-evaluated conditional expression.

`maybe` always behaves as if `prederror` were `false`, and `while` and `unless` always behave as if `prederror` were `true`.

Relational operators do not distribute over lists or other aggregates.

See also `=`, `#`, `equal`, and `notequal`.

Examples:

Relational expressions are evaluated to Boolean values by some functions and programming constructs.

```
(%i1) [x, y, z] : [123, 456, 789];
(%o1) [123, 456, 789]
(%i2) is (x < y);
(%o2) true
(%i3) maybe (y > z);
(%o3) false
(%i4) if x >= z then 1 else 0;
(%o4) 0
(%i5) block ([S], S : 0, for i:1 while i <= 100 do S : S + i,
            return (S));
(%o5) 5050
```

Relational expressions are not otherwise evaluated or simplified to Boolean values, although the arguments of relational expressions are evaluated.

```
(%o1) [123, 456, 789]
(%i2) [x < y, y <= z, z >= y, y > z];
(%o2) [123 < 456, 456 <= 789, 789 >= 456, 456 > 789]
(%i3) map (is, %);
(%o3) [true, true, true, false]
```

7.4 Logical operators

and	Operator
------------	----------

The logical conjunction operator. `and` is an n-ary infix operator; its operands are Boolean expressions, and its result is a Boolean value.

`and` forces evaluation (like `is`) of one or more operands, and may force evaluation of all operands.

Operands are evaluated in the order in which they appear. **and** evaluates only as many of its operands as necessary to determine the result. If any operand is **false**, the result is **false** and no further operands are evaluated.

The global flag **prederror** governs the behavior of **and** when an evaluated operand cannot be determined to be **true** or **false**. **and** prints an error message when **prederror** is **true**. Otherwise, operands which do not evaluate to **true** or **false** are accepted, and the result is a Boolean expression.

and is not commutative: **a and b** might not be equal to **b and a** due to the treatment of indeterminate operands.

not

Operator

The logical negation operator. **not** is a prefix operator; its operand is a Boolean expression, and its result is a Boolean value.

not forces evaluation (like **is**) of its operand.

The global flag **prederror** governs the behavior of **not** when its operand cannot be determined to be **true** or **false**. **not** prints an error message when **prederror** is **true**. Otherwise, operands which do not evaluate to **true** or **false** are accepted, and the result is a Boolean expression.

or

Operator

The logical disjunction operator. **or** is an n-ary infix operator; its operands are Boolean expressions, and its result is a Boolean value.

or forces evaluation (like **is**) of one or more operands, and may force evaluation of all operands.

Operands are evaluated in the order in which they appear. **or** evaluates only as many of its operands as necessary to determine the result. If any operand is **true**, the result is **true** and no further operands are evaluated.

The global flag **prederror** governs the behavior of **or** when an evaluated operand cannot be determined to be **true** or **false**. **or** prints an error message when **prederror** is **true**. Otherwise, operands which do not evaluate to **true** or **false** are accepted, and the result is a Boolean expression.

or is not commutative: **a or b** might not be equal to **b or a** due to the treatment of indeterminate operands.

7.5 Operators for Equations

#

Operator

Represents the negation of syntactic equality =.

Note that because of the rules for evaluation of predicate expressions (in particular because **not expr** causes evaluation of **expr**), **not a = b** is equivalent to **is(a # b)**, instead of **a # b**.

Examples:

(%i1) a = b;	
(%o1)	a = b
(%i2) is (a = b);	
(%o2)	false
(%i3) a # b;	
(%o3)	a # b
(%i4) not a = b;	
(%o4)	true
(%i5) is (a # b);	
(%o5)	true
(%i6) is (not a = b);	
(%o6)	true

=

Operator

The equation operator.

An expression $a = b$, by itself, represents an unevaluated equation, which might or might not hold. Unevaluated equations may appear as arguments to `solve` and `algsys` or some other functions.

The function `is` evaluates $=$ to a Boolean value. `is(a = b)` evaluates $a = b$ to `true` when a and b are identical. That is, a and b are atoms which are identical, or they are not atoms and their operators are identical and their arguments are identical. Otherwise, `is(a = b)` evaluates to `false`; it never evaluates to `unknown`. When `is(a = b)` is `true`, a and b are said to be syntactically equal, in contrast to equivalent expressions, for which `is(equal(a, b))` is `true`. Expressions can be equivalent and not syntactically equal.

The negation of $=$ is represented by $\#$. As with $=$, an expression $a \# b$, by itself, is not evaluated. `is(a # b)` evaluates $a \# b$ to `true` or `false`.

In addition to `is`, some other operators evaluate $=$ and $\#$ to `true` or `false`, namely `if`, `and`, `or`, and `not`.

Note that because of the rules for evaluation of predicate expressions (in particular because `not expr` causes evaluation of `expr`), `not a = b` is equivalent to `is(a # b)`, instead of $a \# b$.

`rhs` and `lhs` return the right-hand and left-hand sides, respectively, of an equation or inequation.

See also `equal` and `notequal`.

Examples:

An expression $a = b$, by itself, represents an unevaluated equation, which might or might not hold.

```
(%i1) eq_1 : a * x - 5 * y = 17;
(%o1)          a x - 5 y = 17
(%i2) eq_2 : b * x + 3 * y = 29;
(%o2)          3 y + b x = 29
(%i3) solve ([eq_1, eq_2], [x, y]);
(%o3)          196          29 a - 17 b
          [[x = -----, y = -----]]
          5 b + 3 a          5 b + 3 a
(%i4) subst (% , [eq_1, eq_2]);
          196 a          5 (29 a - 17 b)
(%o4) [------ - ----- = 17,
          5 b + 3 a          5 b + 3 a
          196 b          3 (29 a - 17 b)
          ----- + ----- = 29]
          5 b + 3 a          5 b + 3 a
(%i5) ratsimp (%);
(%o5)          [17 = 17, 29 = 29]
```

`is(a = b)` evaluates $a = b$ to `true` when a and b are syntactically equal (that is, identical). Expressions can be equivalent and not syntactically equal.

```
(%i1) a : (x + 1) * (x - 1);
(%o1)          (x - 1) (x + 1)
(%i2) b : x^2 - 1;
(%o2)          2
          x  - 1
(%i3) [is (a = b), is (a # b)];
(%o3)          [false, true]
(%i4) [is (equal (a, b)), is (notequal (a, b))];
(%o4)          [true, false]
```

Some operators evaluate $=$ and $\#$ to `true` or `false`.

```
(%i1) if expand ((x + y)^2) = x^2 + 2 * x * y + y^2 then F00 else
BAR;
```

```
(%o1)                                F00
(%i2) eq_3 : 2 * x = 3 * x;
(%o2)                                2 x = 3 x
(%i3) eq_4 : exp (2) = %e^2;
(%o3)                                2      2
                                %e  = %e
(%i4) [eq_3 and eq_4, eq_3 or eq_4, not eq_3];
(%o4) [false, true, true]
```

Because `not expr` causes evaluation of `expr`, `not a = b` is equivalent to `is(a # b)`.

```
(%i1) [2 * x # 3 * x, not (2 * x = 3 * x)];
(%o1) [2 x # 3 x, true]
(%i2) is (2 * x # 3 * x);
(%o2) true
```

7.6 Assignment operators

:		Operator
---	--	----------

Assignment operator.

When the left-hand side is a simple variable (not subscripted), `:` evaluates its right-hand side and associates that value with the left-hand side.

When the left-hand side is a subscripted element of a list, matrix, declared Maxima array, or Lisp array, the right-hand side is assigned to that element. The subscript must name an existing element; such objects cannot be extended by naming nonexistent elements.

When the left-hand side is a subscripted element of an undeclared Maxima array, the right-hand side is assigned to that element, if it already exists, or a new element is allocated, if it does not already exist.

When the left-hand side is a list of simple and/or subscripted variables, the right-hand side must evaluate to a list, and the elements of the right-hand side are assigned to the elements of the left-hand side, in parallel.

See also `kill` and `remvalue`, which undo the association between the left-hand side and its value.

Examples:

Assignment to a simple variable.

```
(%i1) a;
(%o1) a
(%i2) a : 123;
(%o2) 123
(%i3) a;
(%o3) 123
```

Assignment to an element of a list.

```
(%i1) b : [1, 2, 3];
(%o1) [1, 2, 3]
(%i2) b[3] : 456;
(%o2) 456
(%i3) b;
(%o3) [1, 2, 456]
```

Assignment creates an undeclared array.

```
(%i1) c[99] : 789;
(%o1) 789
(%i2) c[99];
(%o2) 789
(%i3) c;
(%o3) c
```

```
(%i4) arrayinfo (c);
(%o4)          [hashed, 1, [99]]
(%i5) listarray (c);
(%o5)          [789]
```

Multiple assignment.

```
(%i1) [a, b, c] : [45, 67, 89];
(%o1)          [45, 67, 89]
(%i2) a;
(%o2)          45
(%i3) b;
(%o3)          67
(%i4) c;
(%o4)          89
```

Multiple assignment is carried out in parallel. The values of **a** and **b** are exchanged in this example.

```
(%i1) [a, b] : [33, 55];
(%o1)          [33, 55]
(%i2) [a, b] : [b, a];
(%o2)          [55, 33]
(%i3) a;
(%o3)          55
(%i4) b;
(%o4)          33
```

::

Operator

Assignment operator.

:: is the same as **:** (which see) except that **::** evaluates its left-hand side as well as its right-hand side.

Examples:

```
(%i1) x : 'foo;
(%o1)          foo
(%i2) x :: 123;
(%o2)          123
(%i3) foo;
(%o3)          123
(%i4) x : '[a, b, c];
(%o4)          [a, b, c]
(%i5) x :: [11, 22, 33];
(%o5)          [11, 22, 33]
(%i6) a;
(%o6)          11
(%i7) b;
(%o7)          22
(%i8) c;
(%o8)          33
```

::=

Operator

Macro function definition operator. **::=** defines a function (called a "macro" for historical reasons) which quotes its arguments, and the expression which it returns (called the "macro expansion") is evaluated in the context from which the macro was called. A macro function is otherwise the same as an ordinary function.

macroexpand returns a macro expansion (without evaluating it). **macroexpand (foo (x))** followed by **'%** is equivalent to **foo (x)** when **foo** is a macro function.

::= puts the name of the new macro function onto the global list **macros**. **kill**, **remove**, and **remfunction** unbind macro function definitions and remove names from **macros**.

`fundef` or `disfun` return a macro function definition or assign it to a label, respectively. Macro functions commonly contain `buildq` and `splice` expressions to construct an expression, which is then evaluated.

Examples

A macro function quotes its arguments, so message (1) shows $y - z$, not the value of $y - z$. The macro expansion (the quoted expression `'(print ("(2) x is equal to", x))`) is evaluated in the context from which the macro was called, printing message (2).

```
(%i1) x: %pi$
(%i2) y: 1234$
(%i3) z: 1729 * w$
(%i4) printq1 (x) := block (print ("(1) x is equal to", x),
    '(print ("(2) x is equal to", x)))$
(%i5) printq1 (y - z);
(1) x is equal to y - z
(2) x is equal to %pi
(%o5)                                     %pi
```

An ordinary function evaluates its arguments, so message (1) shows the value of $y - z$. The return value is not evaluated, so message (2) is not printed until the explicit evaluation `''%`.

```
(%i1) x: %pi$
(%i2) y: 1234$
(%i3) z: 1729 * w$
(%i4) printe1 (x) := block (print ("(1) x is equal to", x),
    '(print ("(2) x is equal to", x)))$
(%i5) printe1 (y - z);
(1) x is equal to 1234 - 1729 w
(%o5)                                     print((2) x is equal to, x)
(%i6) ''%;
(2) x is equal to %pi
(%o6)                                     %pi
```

`macroexpand` returns a macro expansion. `macroexpand (foo (x))` followed by `''%` is equivalent to `foo (x)` when `foo` is a macro function.

```
(%i1) x: %pi$
(%i2) y: 1234$
(%i3) z: 1729 * w$
(%i4) g (x) := buildq ([x], print ("x is equal to", x))$
(%i5) macroexpand (g (y - z));
(%o5)                                     print(x is equal to, y - z)
(%i6) ''%;
x is equal to 1234 - 1729 w
(%o6)                                     1234 - 1729 w
(%i7) g (y - z);
x is equal to 1234 - 1729 w
(%o7)                                     1234 - 1729 w
```

:=

Operator

The function definition operator. $f(x_1, \dots, x_n) := \text{expr}$ defines a function named f with arguments x_1, \dots, x_n and function body expr . `:=` never evaluates the function body (unless explicitly evaluated by quote-quote `''`). The function so defined may be an ordinary Maxima function (with arguments enclosed in parentheses) or an array function (with arguments enclosed in square brackets).

When the last or only function argument x_n is a list of one element, the function defined by `:=` accepts a variable number of arguments. Actual arguments are assigned one-to-one to formal arguments $x_1, \dots, x_{(n-1)}$, and any further actual arguments, if present, are assigned to x_n as a list.

All function definitions appear in the same namespace; defining a function **f** within another function **g** does not automatically limit the scope of **f** to **g**. However, **local(f)** makes the definition of function **f** effective only within the block or other compound expression in which **local** appears.

If some formal argument x_k is a quoted symbol, the function defined by **:=** does not evaluate the corresponding actual argument. Otherwise all actual arguments are evaluated.

See also **define** and **:=**.

Examples:

:= never evaluates the function body (unless explicitly evaluated by quote-quote).

```
(%i1) expr : cos(y) - sin(x);
(%o1) cos(y) - sin(x)
(%i2) F1 (x, y) := expr;
(%o2) F1(x, y) := expr
(%i3) F1 (a, b);
(%o3) cos(y) - sin(x)
(%i4) F2 (x, y) := 'expr;
(%o4) F2(x, y) := cos(y) - sin(x)
(%i5) F2 (a, b);
(%o5) cos(b) - sin(a)
```

The function defined by **:=** may be an ordinary Maxima function or an array function.

```
(%i1) G1 (x, y) := x.y - y.x;
(%o1) G1(x, y) := x . y - y . x
(%i2) G2 [x, y] := x.y - y.x;
(%o2) G2 := x . y - y . x
      x, y
```

When the last or only function argument x_n is a list of one element, the function defined by **:=** accepts a variable number of arguments.

```
(%i1) H ([L]) := apply ("+", L);
(%o1) H([L]) := apply("+", L)
(%i2) H (a, b, c);
(%o2) c + b + a
```

local makes a local function definition.

```
(%i1) foo (x) := 1 - x;
(%o1) foo(x) := 1 - x
(%i2) foo (100);
(%o2) - 99
(%i3) block (local (foo), foo (x) := 2 * x, foo (100));
(%o3) 200
(%i4) foo (100);
(%o4) - 99
```

7.7 User defined operators

infix (<i>op</i>)	Function
infix (<i>op</i> , <i>lbp</i> , <i>rbp</i>)	Function
infix (<i>op</i> , <i>lbp</i> , <i>rbp</i> , <i>lpos</i> , <i>rpos</i> , <i>pos</i>)	Function

Declares *op* to be an infix operator. An infix operator is a function of two arguments, with the name of the function written between the arguments. For example, the subtraction operator **-** is an infix operator.

infix (*op*) declares *op* to be an infix operator with default binding powers (left and right both equal to 180) and parts of speech (left and right both equal to **any**).

infix (*op*, *lbp*, *rbp*) declares *op* to be an infix operator with stated left and right binding powers and default parts of speech (left and right both equal to **any**).

`infix (op, lbp, rbp, lpos, rpos, pos)` declares `op` to be an infix operator with stated left and right binding powers and parts of speech `lpos`, `rpos`, and `pos` for the left operand, the right operand, and the operator result, respectively.

"Part of speech", in reference to operator declarations, means expression type. Three types are recognized: `expr`, `clause`, and `any`, indicating an algebraic expression, a Boolean expression, or any kind of expression, respectively. Maxima can detect some syntax errors by comparing the declared part of speech to an actual expression.

The precedence of `op` with respect to other operators derives from the left and right binding powers of the operators in question. If the left and right binding powers of `op` are both greater the left and right binding powers of some other operator, then `op` takes precedence over the other operator. If the binding powers are not both greater or less, some more complicated relation holds.

The associativity of `op` depends on its binding powers. Greater left binding power (`lbp`) implies an instance of `op` is evaluated before other operators to its left in an expression, while greater right binding power (`rbp`) implies an instance of `op` is evaluated before other operators to its right in an expression. Thus greater `lbp` makes `op` right-associative, while greater `rbp` makes `op` left-associative. If `lbp` is equal to `rbp`, `op` is left-associative.

See also [Section 7.1 \[Introduction to operators\]](#), page 79.

Examples:

If the left and right binding powers of `op` are both greater the left and right binding powers of some other operator, then `op` takes precedence over the other operator.

```
(%i1) :lisp (get '$+ 'lbp)
100
(%i1) :lisp (get '$+ 'rbp)
100
(%i1) infix ("##", 101, 101);
(%o1) ##
(%i2) "##"(a, b) := sconcat("(", a, ",", b, ")");
(%o2) (a ## b) := sconcat("(", a, ",", b, ")")
(%i3) 1 + a ## b + 2;
(%o3) (a,b) + 3
(%i4) infix ("##", 99, 99);
(%o4) ##
(%i5) 1 + a ## b + 2;
(%o5) (a+1,b+2)
```

Greater `lbp` makes `op` right-associative, while greater `rbp` makes `op` left-associative.

```
(%i1) infix ("##", 100, 99);
(%o1) ##
(%i2) "##"(a, b) := sconcat("(", a, ",", b, ")")$
(%i3) foo ## bar ## baz;
(%o3) (foo,(bar,baz))
(%i4) infix ("##", 100, 101);
(%o4) ##
(%i5) foo ## bar ## baz;
(%o5) ((foo,bar),baz)
```

Maxima can detect some syntax errors by comparing the declared part of speech to an actual expression.

```
(%i1) infix ("##", 100, 99, expr, expr, expr);
(%o1) ##
(%i2) if x ## y then 1 else 0;
Incorrect syntax: Found algebraic expression where logical
expression expected
if x ## y then
~
(%i2) infix ("##", 100, 99, expr, expr, clause);
```

```
(%o2)                                     ##
(%i3) if x ## y then 1 else 0;
(%o3)                                     if x ## y then 1 else 0
```

matchfix (*ldelimiter*, *rdelimiter*) Function
matchfix (*ldelimiter*, *rdelimiter*, *arg-pos*, *pos*) Function

Declares a matchfix operator with left and right delimiters *ldelimiter* and *rdelimiter*. The delimiters are specified as strings.

A "matchfix" operator is a function of any number of arguments, such that the arguments occur between matching left and right delimiters. The delimiters may be any strings, so long as the parser can distinguish the delimiters from the operands and other expressions and operators. In practice this rules out unparseable delimiters such as %, ,, \$ and ;, and may require isolating the delimiters with white space. The right delimiter can be the same or different from the left delimiter.

A left delimiter can be associated with only one right delimiter; two different matchfix operators cannot have the same left delimiter.

An existing operator may be redeclared as a matchfix operator without changing its other properties. In particular, built-in operators such as addition + can be declared matchfix, but operator functions cannot be defined for built-in operators.

The command **matchfix** (*ldelimiter*, *rdelimiter*, *arg-pos*, *pos*) declares the argument part-of-speech *arg-pos* and result part-of-speech *pos*, and the delimiters *ldelimiter* and *rdelimiter*.

"Part of speech", in reference to operator declarations, means expression type. Three types are recognized: **expr**, **clause**, and **any**, indicating an algebraic expression, a Boolean expression, or any kind of expression, respectively. Maxima can detect some syntax errors by comparing the declared part of speech to an actual expression.

The function to carry out a matchfix operation is an ordinary user-defined function. The operator function is defined in the usual way with the function definition operator **:=** or **define**. The arguments may be written between the delimiters, or with the left delimiter as a quoted string and the arguments following in parentheses. **dispfun** (*ldelimiter*) displays the function definition.

The only built-in matchfix operator is the list constructor []. Parentheses () and double-quotes " " act like matchfix operators, but are not treated as such by the Maxima parser.

matchfix evaluates its arguments. **matchfix** returns its first argument, *ldelimiter*.

Examples:

Delimiters may be almost any strings.

```
(%i1) matchfix ("@@", "~");
(%o1)                                     @@
(%i2) @@ a, b, c ~;
(%o2)                                     @@a, b, c~
(%i3) matchfix (">>", "<<");
(%o3)                                     >>
(%i4) >> a, b, c <<;
(%o4)                                     >>a, b, c<<
(%i5) matchfix ("foo", "oof");
(%o5)                                     foo
(%i6) foo a, b, c oof;
(%o6)                                     fooa, b, coof
(%i7) >> w + foo x, y oof + z << / @@ p, q ~;
                                     >>z + foox, yoof + w<<
(%o7)                                     -----
                                     @@p, q~
```

Matchfix operators are ordinary user-defined functions.

```

(%i1) matchfix ("!-", "-!");
(%o1)                                     "!"
(%i2) !- x, y -! := x/y - y/x;

(%o2)                                     x   y
                                     !-x, y-! := - - -
                                     y   x

(%i3) define (!-x, y-!, x/y - y/x);

(%o3)                                     x   y
                                     !-x, y-! := - - -
                                     y   x

(%i4) define ("!" (x, y), x/y - y/x);

(%o4)                                     x   y
                                     !-x, y-! := - - -
                                     y   x

(%i5) dispfun ("!");

(%t5)                                     x   y
                                     !-x, y-! := - - -
                                     y   x

(%o5)                                     done
(%i6) !-3, 5-!;

(%o6)                                     16
                                     - --
                                     15

(%i7) "!" (3, 5);

(%o7)                                     16
                                     - --
                                     15

```

nary (*op*) Function
nary (*op, bp, arg_pos, pos*) Function

An **nary** operator is used to denote a function of any number of arguments, each of which is separated by an occurrence of the operator, e.g. $A+B$ or $A+B+C$. The **nary**("x") function is a syntax extension function to declare x to be an **nary** operator. Functions may be declared to be **nary**. If **declare**(j,nary); is done, this tells the simplifier to simplify, e.g. $j(j(a,b), j(c,d))$ to $j(a, b, c, d)$.

See also [Section 7.1 \[Introduction to operators\]](#), page 79.

nofix (*op*) Function
nofix (*op, pos*) Function

nofix operators are used to denote functions of no arguments. The mere presence of such an operator in a command will cause the corresponding function to be evaluated. For example, when one types "exit;" to exit from a Maxima break, "exit" is behaving similar to a **nofix** operator. The function **nofix**("x") is a syntax extension function which declares x to be a **nofix** operator.

See also [Section 7.1 \[Introduction to operators\]](#), page 79.

postfix (*op*) Function
postfix (*op, lbp, lpos, pos*) Function

postfix operators like the **prefix** variety denote functions of a single argument, but in this case the argument immediately precedes an occurrence of the operator in the input string, e.g. $3!$. The **postfix**("x") function is a syntax extension function to declare x to be a **postfix** operator.

See also [Section 7.1 \[Introduction to operators\]](#), page 79.

prefix (*op*)

Function

prefix (*op, rbp, rpos, pos*)

Function

A **prefix** operator is one which signifies a function of one argument, which argument immediately follows an occurrence of the operator. **prefix("x")** is a syntax extension function to declare **x** to be a **prefix** operator.

See also [Section 7.1 \[Introduction to operators\]](#), page 79.

8 Evaluation

8.1 Functions and Variables for Evaluation

,

Operator

The single quote operator `'` prevents evaluation.

Applied to a symbol, the single quote prevents evaluation of the symbol.

Applied to a function call, the single quote prevents evaluation of the function call, although the arguments of the function are still evaluated (if evaluation is not otherwise prevented). The result is the noun form of the function call.

Applied to a parenthesized expression, the single quote prevents evaluation of all symbols and function calls in the expression. E.g., `'(f(x))` means do not evaluate the expression `f(x)`. `'f(x)` (with the single quote applied to `f` instead of `f(x)`) means return the noun form of `f` applied to `[x]`.

The single quote does not prevent simplification.

When the global flag `noundisp` is `true`, nouns display with a single quote. This switch is always `true` when displaying function definitions.

See also the quote-quote operator `''` and `nouns`.

Examples:

Applied to a symbol, the single quote prevents evaluation of the symbol.

```
(%i1) aa: 1024;
(%o1)                                     1024
(%i2) aa^2;
(%o2)                                     1048576
(%i3) 'aa^2;
(%o3)                                     2
(%i4) ''%;
(%o4)                                     1048576
```

Applied to a function call, the single quote prevents evaluation of the function call. The result is the noun form of the function call.

```
(%i1) x0: 5;
(%o1)                                     5
(%i2) x1: 7;
(%o2)                                     7
(%i3) integrate (x^2, x, x0, x1);
(%o3)                                     218
                                     ---
                                     3
(%i4) 'integrate (x^2, x, x0, x1);
(%o4)                                     7
                                     /
                                     [ 2
                                     I  x  dx
                                     ]
                                     /
                                     5
(%i5) %, nouns;
(%o5)                                     218
                                     ---
                                     3
```

Applied to a parenthesized expression, the single quote prevents evaluation of all symbols and function calls in the expression.

```
(%i1) aa: 1024;
(%o1) 1024
(%i2) bb: 19;
(%o2) 19
(%i3) sqrt(aa) + bb;
(%o3) 51
(%i4) '(sqrt(aa) + bb);
(%o4) bb + sqrt(aa)
(%i5) ''%;
(%o5) 51
```

The single quote does not prevent simplification.

```
(%i1) sin (17 * %pi) + cos (17 * %pi);
(%o1) - 1
(%i2) '(sin (17 * %pi) + cos (17 * %pi));
(%o2) - 1
```

Maxima considers floating point operations by its in-built mathematical functions to be a simplification.

```
(%i1) sin(1.0);
(%o1) .8414709848078965
(%i2) '(sin(1.0));
(%o2) .8414709848078965
```

”

Operator

The quote-quote operator `''` (two single quote marks) modifies evaluation in input expressions.

Applied to a general expression *expr*, quote-quote causes the value of *expr* to be substituted for *expr* in the input expression.

Applied to the operator of an expression, quote-quote changes the operator from a noun to a verb (if it is not already a verb).

The quote-quote operator is applied by the input parser; it is not stored as part of a parsed input expression. The quote-quote operator is always applied as soon as it is parsed, and cannot be quoted. Thus quote-quote causes evaluation when evaluation is otherwise suppressed, such as in function definitions, lambda expressions, and expressions quoted by single quote `'`.

Quote-quote is recognized by `batch` and `load`.

See also the single-quote operator `'` and `nouns`.

Examples:

Applied to a general expression *expr*, quote-quote causes the value of *expr* to be substituted for *expr* in the input expression.

```
(%i1) expand ((a + b)^3);
(%o1) b^3 + 3 a b^2 + 3 a^2 b + a^3
(%i2) [_, ''_];
(%o2) [expand((b + a)^3), b^3 + 3 a b^2 + 3 a^2 b + a^3]
(%i3) [%i1, ''%i1];
(%o3) [expand((b + a)^3), b^3 + 3 a b^2 + 3 a^2 b + a^3]
(%i4) [aa : cc, bb : dd, cc : 17, dd : 29];
(%o4) [cc, dd, 17, 29]
(%i5) foo_1 (x) := aa - bb * x;
(%o5) foo_1(x) := aa - bb x
(%i6) foo_1 (10);
(%o6) cc - 10 dd
```

```

(%i7) '';
(%o7) - 273
(%i8) ''(foo_1 (10));
(%o8) - 273
(%i9) foo_2 (x) := ''aa - ''bb * x;
(%o9) foo_2(x) := cc - dd x
(%i10) foo_2 (10);
(%o10) - 273
(%i11) [x0 : x1, x1 : x2, x2 : x3];
(%o11) [x1, x2, x3]
(%i12) x0;
(%o12) x1
(%i13) ''x0;
(%o13) x2
(%i14) '' ''x0;
(%o14) x3

```

Applied to the operator of an expression, quote-quote changes the operator from a noun to a verb (if it is not already a verb).

```

(%i1) declare (foo, noun);
(%o1) done
(%i2) foo (x) := x - 1729;
(%o2) ''foo(x) := x - 1729
(%i3) foo (100);
(%o3) foo(100)
(%i4) ''foo (100);
(%o4) - 1629

```

The quote-quote operator is applied by the input parser; it is not stored as part of a parsed input expression.

```

(%i1) [aa : bb, cc : dd, bb : 1234, dd : 5678];
(%o1) [bb, dd, 1234, 5678]
(%i2) aa + cc;
(%o2) dd + bb
(%i3) display (_, op (_), args (_));
      _ = cc + aa

      op(cc + aa) = +

      args(cc + aa) = [cc, aa]

(%o3) done
(%i4) ''(aa + cc);
(%o4) 6912
(%i5) display (_, op (_), args (_));
      _ = dd + bb

      op(dd + bb) = +

      args(dd + bb) = [dd, bb]

(%o5) done

```

Quote-quote causes evaluation when evaluation is otherwise suppressed, such as in function definitions, lambda expressions, and expressions quoted by single quote '.

```

(%i1) foo_1a (x) := ''(integrate (log (x), x));
(%o1) foo_1a(x) := x log(x) - x
(%i2) foo_1b (x) := integrate (log (x), x);
(%o2) foo_1b(x) := integrate(log(x), x)

```

```

(%i3) dispfun (foo_1a, foo_1b);
(%t3)          foo_1a(x) := x log(x) - x

(%t4)          foo_1b(x) := integrate(log(x), x)

(%o4)          [%t3, %t4]
(%i5) integrate (log (x), x);
(%o5)          x log(x) - x
(%i6) foo_2a (x) := '';
(%o6)          foo_2a(x) := x log(x) - x
(%i7) foo_2b (x) := %;
(%o7)          foo_2b(x) := %
(%i8) dispfun (foo_2a, foo_2b);
(%t8)          foo_2a(x) := x log(x) - x

(%t9)          foo_2b(x) := %

(%o9)          [%t7, %t8]
(%i10) F : lambda ([u], diff (sin (u), u));
(%o10)          lambda([u], diff(sin(u), u))
(%i11) G : lambda ([u], ''(diff (sin (u), u)));
(%o11)          lambda([u], cos(u))
(%i12) '(sum (a[k], k, 1, 3) + sum (b[k], k, 1, 3));
(%o12)          sum(b , k, 1, 3) + sum(a , k, 1, 3)
                    k                k
(%i13) '('(sum (a[k], k, 1, 3)) + ''(sum (b[k], k, 1, 3)));
(%o13)          b  + a  + b  + a  + b  + a
                    3    3    2    2    1    1

```

ev (*expr*, *arg-1*, ..., *arg-n*) Function

Evaluates the expression *expr* in the environment specified by the arguments *arg-1*, ..., *arg-n*. The arguments are switches (Boolean flags), assignments, equations, and functions. **ev** returns the result (another expression) of the evaluation.

The evaluation is carried out in steps, as follows.

1. First the environment is set up by scanning the arguments which may be any or all of the following.
 - **simp** causes *expr* to be simplified regardless of the setting of the switch **simp** which inhibits simplification if **false**.
 - **noeval** suppresses the evaluation phase of **ev** (see step (4) below). This is useful in conjunction with the other switches and in causing *expr* to be resimplified without being reevaluated.
 - **nouns** causes the evaluation of noun forms (typically unevaluated functions such as **'integrate** or **'diff**) in *expr*.
 - **expand** causes expansion.
 - **expand** (*m*, *n*) causes expansion, setting the values of **maxposex** and **maxnegex** to *m* and *n* respectively.
 - **detout** causes any matrix inverses computed in *expr* to have their determinant kept outside of the inverse rather than dividing through each element.
 - **diff** causes all differentiations indicated in *expr* to be performed.
 - **derivlist** (*x*, *y*, *z*, ...) causes only differentiations with respect to the indicated variables. See also **derivlist**.
 - **risch** causes integrals in *expr* to be evaluated using the Risch algorithm. See **risch**. The standard integration routine is invoked when using the special symbol **nouns**.
 - **float** causes non-integral rational numbers to be converted to floating point.

- **numer** causes some mathematical functions (including exponentiation) with numerical arguments to be evaluated in floating point. It causes variables in *expr* which have been given numervals to be replaced by their values. It also sets the **float** switch on.
- **pred** causes predicates (expressions which evaluate to **true** or **false**) to be evaluated.
- **eval** causes an extra post-evaluation of *expr* to occur. (See step (5) below.) **eval** may occur multiple times. For each instance of **eval**, the expression is evaluated again.
- **A** where **A** is an atom declared to be an evaluation flag **evflag** causes **A** to be bound to **true** during the evaluation of *expr*.
- **V: expression** (or alternately **V=expression**) causes **V** to be bound to the value of **expression** during the evaluation of *expr*. Note that if **V** is a Maxima option, then **expression** is used for its value during the evaluation of *expr*. If more than one argument to **ev** is of this type then the binding is done in parallel. If **V** is a non-atomic expression then a substitution rather than a binding is performed.
- **F** where **F**, a function name, has been declared to be an evaluation function **evfun** causes **F** to be applied to *expr*.
- Any other function names, e.g. **sum**, cause evaluation of occurrences of those names in *expr* as though they were verbs.
- In addition a function occurring in *expr* (say **F(x)**) may be defined locally for the purpose of this evaluation of *expr* by giving **F(x) := expression** as an argument to **ev**.
- If an atom not mentioned above or a subscripted variable or subscripted expression was given as an argument, it is evaluated and if the result is an equation or assignment then the indicated binding or substitution is performed. If the result is a list then the members of the list are treated as if they were additional arguments given to **ev**. This permits a list of equations to be given (e.g. [**X=1**, **Y=A**2**]) or a list of names of equations (e.g., [**%t1**, **%t2**] where **%t1** and **%t2** are equations) such as that returned by **solve**.

The arguments of **ev** may be given in any order with the exception of substitution equations which are handled in sequence, left to right, and evaluation functions which are composed, e.g., **ev (expr, ratsimp, realpart)** is handled as **realpart (ratsimp (expr))**.

The **simp**, **numer**, and **float** switches may also be set locally in a block, or globally in Maxima so that they will remain in effect until being reset.

If *expr* is a canonical rational expression (CRE), then the expression returned by **ev** is also a CRE, provided the **numer** and **float** switches are not both **true**.

2. During step (1), a list is made of the non-subscripted variables appearing on the left side of equations in the arguments or in the value of some arguments if the value is an equation. The variables (subscripted variables which do not have associated array functions as well as non-subscripted variables) in the expression *expr* are replaced by their global values, except for those appearing in this list. Usually, *expr* is just a label or **%** (as in **%i2** in the example below), so this step simply retrieves the expression named by the label, so that **ev** may work on it.
3. If any substitutions are indicated by the arguments, they are carried out now.
4. The resulting expression is then re-evaluated (unless one of the arguments was **noeval**) and simplified according to the arguments. Note that any function calls in *expr* will be carried out after the variables in it are evaluated and that **ev(F(x))** thus may behave like **F(ev(x))**.
5. For each instance of **eval** in the arguments, steps (3) and (4) are repeated.

Examples:

```
(%i1) sin(x) + cos(y) + (w+1)^2 + 'diff (sin(w), w);
```

```
(%o1)          cos(y) + sin(x) + -- (sin(w)) + (w + 1)
                        dw
```

```
(%i2) ev (%, numer, expand, diff, x=2, y=1);
2
```

```
(%o2)          cos(w) + w  + 2 w + 2.449599732693821
```

An alternate top level syntax has been provided for `ev`, whereby one may just type in its arguments, without the `ev()`. That is, one may write simply

```
expr, arg_1, ..., arg_n
```

This is not permitted as part of another expression, e.g., in functions, blocks, etc.

Notice the parallel binding process in the following example.

```
(%i3) programmode: false;
```

```
(%o3)          false
```

```
(%i4) x+y, x: a+y, y: 2;
```

```
(%o4)          y + a + 2
```

```
(%i5) 2*x - 3*y = 3$
```

```
(%i6) -3*x + 2*y = -4$
```

```
(%i7) solve ([%o5, %o6]);
```

```
Solution
```

```
(%t7)          y = - 1
                    5
```

```
(%t8)          x = - 6
                    5
```

```
(%o8)          [[%t7, %t8]]
```

```
(%i8) %o6, %o8;
```

```
(%o8)          - 4 = - 4
```

```
(%i9) x + 1/x > gamma (1/2);
```

```
(%o9)          x + 1
                    x
> sqrt(%pi)
```

```
(%i10) %, numer, x=1/2;
```

```
(%o10)          2.5 > 1.772453850905516
```

```
(%i11) %, pred;
```

```
(%o11)          true
```

eval

Special symbol

As an argument in a call to `ev (expr)`, `eval` causes an extra evaluation of `expr`. See `ev`.

Example:

```
(%i11) [a:b,b:c,c:d,d:e];
```

```
(%o1)          [b, c, d, e]
```

```
(%i2) a;
```

```
(%o2)          b
```

```
(%i3) ev(a);
```

```
(%o3)          c
```

```
(%i4) ev(a),eval;
```

```
(%o4)          e
```

```
(%i5) a,eval,eval;
```

```
(%o5)          e
```

evflag

Property

When a symbol `x` has the `evflag` property, the expressions `ev(expr, x)` and `expr, x` (at the interactive prompt) are equivalent to `ev(expr, x = true)`. That is, `x` is bound to `true` while `expr` is evaluated.

The expression `declare(x, evflag)` gives the `evflag` property to the variable `x`.
The flags which have the `evflag` property by default are the following:

<code>algebraic</code>	<code>cauchysum</code>	<code>demoivre</code>
<code>dotscrules</code>	<code>%emode</code>	<code>%enumer</code>
<code>exponentialize</code>	<code>exptisolate</code>	<code>factorflag</code>
<code>float</code>	<code>halfangles</code>	<code>infeval</code>
<code>isolate_wrt_times</code>	<code>keepfloat</code>	<code>letrat</code>
<code>listarith</code>	<code>logabs</code>	<code>logarc</code>
<code>logexpand</code>	<code>lognegint</code>	
<code>mipbranch</code>	<code>numer_pbranch</code>	<code>programmode</code>
<code>radexpand</code>	<code>ratalgdenom</code>	<code>ratfac</code>
<code>ratmx</code>	<code>ratsimpexpons</code>	<code>simp</code>
<code>simpproduct</code>	<code>simpsum</code>	<code>sumexpand</code>
<code>trigexpand</code>		

Examples:

```
(%i1) sin (1/2);
(%o1)
1
sin(-)
2

(%i2) sin (1/2), float;
(%o2) 0.479425538604203
(%i3) sin (1/2), float=true;
(%o3) 0.479425538604203
(%i4) simp : false;
(%o4) false
(%i5) 1 + 1;
(%o5) 1 + 1
(%i6) 1 + 1, simp;
(%o6) 2
(%i7) simp : true;
(%o7) true
(%i8) sum (1/k^2, k, 1, inf);
inf
====
\      1
>  ---
/      2
====  k
k = 1
(%i9) sum (1/k^2, k, 1, inf), simpsum;
2
%pi
----
6
(%o9)

(%i10) declare (aa, evflag);
(%o10) done
(%i11) if aa = true then YES else NO;
(%o11) NO
(%i12) if aa = true then YES else NO, aa;
(%o12) YES
```

evfun

Property

When a function F has the `evfun` property, the expressions `ev(expr, F)` and `expr, F` (at the interactive prompt) are equivalent to $F(\text{ev}(\text{expr}))$.

If two or more `evfun` functions F , G , etc., are specified, the functions are applied in the order that they are specified.

The expression `declare(F , evfun)` gives the `evfun` property to the function F . The functions which have the `evfun` property by default are the following:

<code>bfloat</code>	<code>factor</code>	<code>fullratsimp</code>
<code>logcontract</code>	<code>polarform</code>	<code>radcan</code>
<code>ratexpand</code>	<code>ratsimp</code>	<code>rectform</code>
<code>rootscontract</code>	<code>trigexpand</code>	<code>trigreduce</code>

Examples:

```
(%i1) x^3 - 1;
(%o1) 
$$x^3 - 1$$

(%i2) x^3 - 1, factor;
(%o2) 
$$(x - 1) (x^2 + x + 1)$$

(%i3) factor (x^3 - 1);
(%o3) 
$$(x - 1) (x^2 + x + 1)$$

(%i4) cos(4 * x) / sin(x)^4;
(%o4) 
$$\frac{\cos(4x)}{\sin^4(x)}$$

(%i5) cos(4 * x) / sin(x)^4, trigexpand;
(%o5) 
$$\frac{\sin^4(x) - 6 \cos^2(x) \sin^2(x) + \cos^4(x)}{\sin^4(x)}$$

(%i6) cos(4 * x) / sin(x)^4, trigexpand, ratexpand;
(%o6) 
$$-\frac{6 \cos^2(x)}{\sin^2(x)} + \frac{\cos^4(x)}{\sin^4(x)} + 1$$

(%i7) ratexpand (trigexpand (cos(4 * x) / sin(x)^4));
(%o7) 
$$-\frac{6 \cos^2(x)}{\sin^2(x)} + \frac{\cos^4(x)}{\sin^4(x)} + 1$$

(%i8) declare ([F, G], evfun);
(%o8) done
(%i9) (aa : bb, bb : cc, cc : dd);
(%o9) dd
(%i10) aa;
(%o10) bb
(%i11) aa, F;
(%o11) F(cc)
(%i12) F (aa);
(%o12) F(bb)
(%i13) F (ev (aa));
(%o13) F(cc)
(%i14) aa, F, G;
(%o14) G(F(cc))
```

```
(%i15) G (F (ev (aa)));
(%o15)          G(F(cc))
```

infeval

Option variable

Enables "infinite evaluation" mode. **ev** repeatedly evaluates an expression until it stops changing. To prevent a variable, say **X**, from being evaluated away in this mode, simply include **X='X** as an argument to **ev**. Of course expressions such as **ev (X, X=X+1, infeval)** will generate an infinite loop.

noeval

Special symbol

noeval suppresses the evaluation phase of **ev**. This is useful in conjunction with other switches and in causing expressions to be resimplified without being reevaluated.

nouns

Special symbol

nouns is an **evflag**. When used as an option to the **ev** command, **nouns** converts all "noun" forms occurring in the expression being **ev**'d to "verbs", i.e., evaluates them. See also **noun**, **nounify**, **verb**, and **verbify**.

pred

Special symbol

As an argument in a call to **ev (expr)**, **pred** causes predicates (expressions which evaluate to **true** or **false**) to be evaluated. See **ev**.

Example:

```
(%i1) 1<2;
(%o1)          1 < 2
(%i2) 1<2,pred;
(%o2)          true
```


9 Simplification

9.1 Functions and Variables for Simplification

additive

Property

If `declare(f,additive)` has been executed, then:

- (1) If `f` is univariate, whenever the simplifier encounters `f` applied to a sum, `f` will be distributed over that sum. I.e. `f(y+x)` will simplify to `f(y)+f(x)`.
- (2) If `f` is a function of 2 or more arguments, additivity is defined as additivity in the first argument to `f`, as in the case of `sum` or `integrate`, i.e. `f(h(x)+g(x),x)` will simplify to `f(h(x),x)+f(g(x),x)`. This simplification does not occur when `f` is applied to expressions of the form `sum(x[i],i,lower-limit,upper-limit)`.

Example:

```
(%i1) F3 (a + b + c);
(%o1)                                     F3(c + b + a)
(%i2) declare (F3, additive);
(%o2)                                     done
(%i3) F3 (a + b + c);
(%o3)                                     F3(c) + F3(b) + F3(a)
```

antisymmetric

Property

If `declare(h,antisymmetric)` is done, this tells the simplifier that `h` is antisymmetric. E.g. `h(x,z,y)` will simplify to `- h(x, y, z)`. That is, it will give $(-1)^n$ times the result given by `symmetric` or `commutative`, where n is the number of interchanges of two arguments necessary to convert it to that form.

Examples:

```
(%i1) S (b, a);
(%o1)                                     S(b, a)
(%i2) declare (S, symmetric);
(%o2)                                     done
(%i3) S (b, a);
(%o3)                                     S(a, b)
(%i4) S (a, c, e, d, b);
(%o4)                                     S(a, b, c, d, e)
(%i5) T (b, a);
(%o5)                                     T(b, a)
(%i6) declare (T, antisymmetric);
(%o6)                                     done
(%i7) T (b, a);
(%o7)                                     - T(a, b)
(%i8) T (a, c, e, d, b);
(%o8)                                     T(a, b, c, d, e)
```

combine (expr)

Function

Simplifies the sum `expr` by combining terms with the same denominator into a single term.

commutative

Property

If `declare(h,commutative)` is done, this tells the simplifier that `h` is a commutative function. E.g. `h(x, z, y)` will simplify to `h(x, y, z)`. This is the same as `symmetric`.

demoivre (*expr*)

Function

demoivre

Option variable

The function **demoivre** (*expr*) converts one expression without setting the global variable **demoivre**.

When the variable **demoivre** is **true**, complex exponentials are converted into equivalent expressions in terms of circular functions: **exp** ($a + b\%i$) simplifies to $e^a * (\cos(b) + \%i\sin(b))$ if b is free of $\%i$. a and b are not expanded.

The default value of **demoivre** is **false**.

exponentialize converts circular and hyperbolic functions to exponential form. **demoivre** and **exponentialize** cannot both be true at the same time.

distrib (*expr*)

Function

Distributes sums over products. It differs from **expand** in that it works at only the top level of an expression, i.e., it doesn't recurse and it is faster than **expand**. It differs from **multthru** in that it expands all sums at that level.

Examples:

```
(%i1) distrib ((a+b) * (c+d));
(%o1)          b d + a d + b c + a c
(%i2) multthru ((a+b) * (c+d));
(%o2)          (b + a) d + (b + a) c
(%i3) distrib (1/((a+b) * (c+d)));
(%o3)          1
              -----
              (b + a) (d + c)
(%i4) expand (1/((a+b) * (c+d)), 1, 0);
(%o4)          1
              -----
              b d + a d + b c + a c
```

distribute_over

Option variable

Default value: **true**

distribute_over controls the mapping of functions over bags like lists, matrices, and equations. At this time not all Maxima functions have this property. It is possible to look up this property with the command **properties**.

The mapping of functions is switched off, when setting **distribute_over** to the value **false**.

Examples:

The **sin** function maps over a list:

```
(%i1) sin([x,1,1.0]);
(%o1)          [sin(x), sin(1), .8414709848078965]
```

mod is a function with two arguments which maps over lists. Mapping over nested lists is possible too:

```
(%i2) mod([x,11,2*a],10);
(%o2)          [mod(x, 10), 1, 2 mod(a, 5)]
(%i3) mod([[x,y,z],11,2*a],10);
(%o3)          [[mod(x, 10), mod(y, 10), mod(z, 10)], 1, 2 mod(a, 5)]
```

Mapping of the **floor** function over a matrix and an equation:

```
(%i4) floor(matrix([a,b],[c,d]));
(%o4)          [ floor(a)  floor(b) ]
              [                ]
              [ floor(c)  floor(d) ]
(%i5) floor(a=b);
(%o5)          floor(a) = floor(b)
```

Functions with more than one argument map over any of the arguments or all arguments:


```
(%i6) expintegral_e([1,2],[x,y]);
(%o6) [[expintegral_e(1, x), expintegral_e(1, y)],
      [expintegral_e(2, x), expintegral_e(2, y)]]
```

Check if a function has the property `distribute_over`:

```
(%i7) properties(abs);
(%o7) [integral, distributes over bags, noun, rule, grade]
```

domain

Option variable

Default value: `real`

When `domain` is set to `complex`, `sqrt (x^2)` will remain `sqrt (x^2)` instead of returning `abs(x)`.

evenfun

Property

oddfun

Property

`declare(f, evenfun` or `declare(f, oddfun` tells Maxima to recognize the function `f` as an even or odd function.

Examples:

```
(%i1) o (- x) + o (x);
(%o1) o(x) + o(- x)
(%i2) declare (o, oddfun);
(%o2) done
(%i3) o (- x) + o (x);
(%o3) 0
(%i4) e (- x) - e (x);
(%o4) e(- x) - e(x)
(%i5) declare (e, evenfun);
(%o5) done
(%i6) e (- x) - e (x);
(%o6) 0
```

expand (expr)

Function

expand (expr, p, n)

Function

Expand expression `expr`. Products of sums and exponentiated sums are multiplied out, numerators of rational expressions which are sums are split into their respective terms, and multiplication (commutative and non-commutative) are distributed over addition at all levels of `expr`.

For polynomials one should usually use `ratexpand` which uses a more efficient algorithm. `maxnegex` and `maxposex` control the maximum negative and positive exponents, respectively, which will expand.

`expand (expr, p, n)` expands `expr`, using `p` for `maxposex` and `n` for `maxnegex`. This is useful in order to expand part but not all of an expression.

`expon` - the exponent of the largest negative power which is automatically expanded (independent of calls to `expand`). For example if `expon` is 4 then $(x+1)^{-5}$ will not be automatically expanded.

`expop` - the highest positive exponent which is automatically expanded. Thus $(x+1)^3$, when typed, will be automatically expanded only if `expop` is greater than or equal to 3. If it is desired to have $(x+1)^n$ expanded where `n` is greater than `expop` then executing `expand ((x+1)^n)` will work only if `maxposex` is not less than `n`.

`expand(expr, 0, 0)` causes a resimplification of `expr`. `expr` is not reevaluated. In distinction from `ev(expr, noeval)` a special representation (e. g. a CRE form) is removed. See also `ev`.

The `expand` flag used with `ev` causes expansion.

The file '`share/simplification/facexp.mac`' contains several related functions (in particular `facsum`, `factorfacsum` and `collectterms`, which are autoloaded) and variables

(`nextlayerfactor` and `facsum_combine`) that provide the user with the ability to structure expressions by controlled expansion. Brief function descriptions are available in 'simplification/facexp.usg'. A demo is available by doing `demo("facexp")`.

Examples:

```
(%i1) expr:(x+1)^2*(y+1)^3;

(%o1)
      2      3
      (x + 1) (y + 1)

(%i2) expand(expr);

(%o2) x2 y3 + 2 x3 y2 + y3 + 3 x2 y2 + 6 x2 y2 + 3 y2 + 3 x2 y2
      + 6 x y + 3 y + x2 + 2 x + 1

(%i3) expand(expr,2);

(%o3)
      2      3      3      3
      x (y + 1) + 2 x (y + 1) + (y + 1)

(%i4) expr:(x+1)^-2*(y+1)^3;

(%o4)
      3
      (y + 1)
      -----
      2
      (x + 1)

(%i5) expand(expr);

(%o5)
      3      2      3 y      1
      y      3 y      3 y      1
      ----- + ----- + ----- + -----
      2      2      2      2
      x + 2 x + 1 x + 2 x + 1 x + 2 x + 1 x + 2 x + 1

(%i6) expand(expr,2,2);

(%o6)
      3
      (y + 1)
      -----
      2
      x + 2 x + 1
```

Resimplify an expression without expansion:

```
(%i7) expr:(1+x)^2*sin(x);

(%o7)
      2
      (x + 1) sin(x)

(%i8) exponentialize:true;

(%o8)
      true

(%i9) expand(expr,0,0);

(%o9)
      2      %i x      - %i x
      %i (x + 1) (e  - e )
      -----
      2
```

expandwrt (*expr*, *x_1*, ..., *x_n*)

Function

Expands expression `expr` with respect to the variables `x_1`, ..., `x_n`. All products involving the variables appear explicitly. The form returned will be free of products of sums of expressions that are not free of the variables. `x_1`, ..., `x_n` may be variables, operators, or expressions.

By default, denominators are not expanded, but this can be controlled by means of the switch `expandwrt_denom`.

This function is autoloaded from 'simplification/stopex.mac'.

expandwrt_denom

Option variable

Default value: `false`

`expandwrt_denom` controls the treatment of rational expressions by `expandwrt`. If `true`, then both the numerator and denominator of the expression will be expanded according to the arguments of `expandwrt`, but if `expandwrt_denom` is `false`, then only the numerator will be expanded in that way.

expandwrt_factored (*expr*, *x_1*, ..., *x_n*)

Function

is similar to `expandwrt`, but treats expressions that are products somewhat differently. `expandwrt_factored` expands only on those factors of `expr` that contain the variables *x_1*, ..., *x_n*.

This function is autoloaded from 'simplification/stopex.mac'.

expon

Option variable

Default value: 0

`expon` is the exponent of the largest negative power which is automatically expanded (independent of calls to `expand`). For example, if `expon` is 4 then $(x+1)^{-5}$ will not be automatically expanded.

exponentialize (*expr*)

Function

exponentialize

Option variable

The function `exponentialize` (*expr*) converts circular and hyperbolic functions in *expr* to exponentials, without setting the global variable `exponentialize`.

When the variable `exponentialize` is `true`, all circular and hyperbolic functions are converted to exponential form. The default value is `false`.

`demoivre` converts complex exponentials into circular functions. `exponentialize` and `demoivre` cannot both be true at the same time.

expop

Option variable

Default value: 0

`expop` is the highest positive exponent which is automatically expanded. Thus $(x + 1)^3$, when typed, will be automatically expanded only if `expop` is greater than or equal to 3. If it is desired to have $(x + 1)^n$ expanded where *n* is greater than `expop` then executing `expand ((x + 1)^n)` will work only if `maxposex` is not less than *n*.

lassociative

Property

`declare (g, lassociative)` tells the Maxima simplifier that *g* is left-associative. E.g., `g (g (a, b), g (c, d))` will simplify to `g (g (g (a, b), c), d)`.

linear

Property

One of Maxima's operator properties. For univariate *f* so declared, "expansion" `f(x + y)` yields `f(x) + f(y)`, `f(a*x)` yields `a*f(x)` takes place where *a* is a "constant". For functions of two or more arguments, "linearity" is defined to be as in the case of `sum` or `integrate`, i.e., `f (a*x + b, x)` yields `a*f(x,x) + b*f(1,x)` for *a* and *b* free of *x*.

`linear` is equivalent to `additive` and `outative`. See also `opproperties`.

Example:

```
(%i1) 'sum (F(k) + G(k), k, 1, inf);
      inf
      ====
      \
(%o1)  > (G(k) + F(k))
      /
```

```

=====
k = 1
(%i2) declare (nounify (sum), linear);
(%o2)                                     done
(%i3) 'sum (F(k) + G(k), k, 1, inf);
      inf          inf
=====          =====
      \            \
      >      G(k) + >      F(k)
      /            /
=====          =====
      k = 1          k = 1

```

maxnegex

Option variable

Default value: 1000

maxnegex is the largest negative exponent which will be expanded by the **expand** command (see also **maxposex**).

maxposex

Option variable

Default value: 1000

maxposex is the largest exponent which will be expanded with the **expand** command (see also **maxnegex**).

multiplicative

Property

declare(f, multiplicative) tells the Maxima simplifier that **f** is multiplicative.

1. If **f** is univariate, whenever the simplifier encounters **f** applied to a product, **f** distributes over that product. E.g., **f(x*y)** simplifies to **f(x)*f(y)**.
2. If **f** is a function of 2 or more arguments, multiplicativity is defined as multiplicativity in the first argument to **f**, e.g., **f(g(x) * h(x), x)** simplifies to **f(g(x), x) * f(h(x), x)**.

This simplification does not occur when **f** is applied to expressions of the form **product(x[i], i, m, n)**.

Example:

```

(%i1) F2 (a * b * c);
(%o1)                                     F2(a b c)
(%i2) declare (F2, multiplicative);
(%o2)                                     done
(%i3) F2 (a * b * c);
(%o3)                                     F2(a) F2(b) F2(c)

```

multthru (expr)

Function

multthru (expr_1, expr_2)

Function

Multiplies a factor (which should be a sum) of *expr* by the other factors of *expr*. That is, *expr* is *f_1 f_2 ... f_n* where at least one factor, say *f_i*, is a sum of terms. Each term in that sum is multiplied by the other factors in the product. (Namely all the factors except *f_i*). **multthru** does not expand exponentiated sums. This function is the fastest way to distribute products (commutative or noncommutative) over sums. Since quotients are represented as products **multthru** can be used to divide sums by products as well.

multthru (expr_1, expr_2) multiplies each term in *expr_2* (which should be a sum or an equation) by *expr_1*. If *expr_1* is not itself a sum then this form is equivalent to **multthru (expr_1*expr_2)**.

```

(%i1) x/(x-y)^2 - 1/(x-y) - f(x)/(x-y)^3;
(%o1)

$$-\frac{1}{x-y} + \frac{x}{(x-y)^2} - \frac{f(x)}{(x-y)^3}$$

(%i2) multthru ((x-y)^3, %);
(%o2)

$$-(x-y)^2 + x(x-y) - f(x)$$

(%i3) ratexpand (%);
(%o3)

$$-y^2 + xy - f(x)$$

(%i4) ((a+b)^10*s^2 + 2*a*b*s + (a*b)^2)/(a*b*s^2);
(%o4)

$$\frac{(b+a)^{10}s^2 + 2ab s + a^2b^2}{a^2b^2s^2}$$

(%i5) multthru (%); /* note that this does not expand (b+a)^10 */
(%o5)

$$-\frac{2}{s} + \frac{ab}{s^2} + \frac{(b+a)^{10}}{a^2b^2}$$

(%i6) multthru (a.(b+c.(d+e)+f));
(%o6)

$$a \cdot f + a \cdot c \cdot (e + d) + a \cdot b$$

(%i7) expand (a.(b+c.(d+e)+f));
(%o7)

$$a \cdot f + a \cdot c \cdot e + a \cdot c \cdot d + a \cdot b$$


```

nary

Property

`declare(f, nary)` tells Maxima to recognize the function `f` as an `n`-ary function.

The `nary` declaration is not the same as calling the `nary` function. The sole effect of `declare(f, nary)` is to instruct the Maxima simplifier to flatten nested expressions, for example, to simplify `foo(x, foo(y, z))` to `foo(x, y, z)`. See also `declare`.

Example:

```

(%i1) H (H (a, b), H (c, H (d, e)));
(%o1)

$$H(H(a, b), H(c, H(d, e)))$$

(%i2) declare (H, nary);
(%o2)

$$\text{done}$$

(%i3) H (H (a, b), H (c, H (d, e)));
(%o3)

$$H(a, b, c, d, e)$$


```

negdistrib

Option variable

Default value: `true`

When `negdistrib` is `true`, `-1` distributes over an expression. E.g., `-(x + y)` becomes `- y - x`. Setting it to `false` will allow `-(x + y)` to be displayed like that. This is sometimes useful but be very careful: like the `simp` flag, this is one flag you do not want to set to `false` as a matter of course or necessarily for other than local use in your Maxima.

opproperties

System variable

`opproperties` is the list of the special operator properties recognized by the Maxima simplifier: `linear`, `additive`, `multiplicative`, `outative`, `evenfun`, `oddfun`, `commutative`, `symmetric`, `antisymmetric`, `nary`, `lassociative`, `rassociative`.

outative

Property

`declare(f, outative)` tells the Maxima simplifier that constant factors in the argument of `f` can be pulled out.

1. If `f` is univariate, whenever the simplifier encounters `f` applied to a product, that product will be partitioned into factors that are constant and factors that are not and the constant factors will be pulled out. E.g., `f(a*x)` will simplify to `a*f(x)` where `a` is a constant. Non-atomic constant factors will not be pulled out.
2. If `f` is a function of 2 or more arguments, outativity is defined as in the case of `sum` or `integrate`, i.e., `f(a*g(x), x)` will simplify to `a * f(g(x), x)` for `a` free of `x`.

`sum`, `integrate`, and `limit` are all outative.

Example:

```
(%i1) F1 (100 * x);
(%o1)                                     F1(100 x)
(%i2) declare (F1, outative);
(%o2)                                     done
(%i3) F1 (100 * x);
(%o3)                                     100 F1(x)
(%i4) declare (zz, constant);
(%o4)                                     done
(%i5) F1 (zz * y);
(%o5)                                     zz F1(y)
```

radcan (*expr*)

Function

Simplifies *expr*, which can contain logs, exponentials, and radicals, by converting it into a form which is canonical over a large class of expressions and a given ordering of variables; that is, all functionally equivalent forms are mapped into a unique form. For a somewhat larger class of expressions, `radcan` produces a regular form. Two equivalent expressions in this class do not necessarily have the same appearance, but their difference can be simplified by `radcan` to zero.

For some expressions `radcan` is quite time consuming. This is the cost of exploring certain relationships among the components of the expression for simplifications based on factoring and partial-fraction expansions of exponents.

Examples:

```
(%i1) radcan((log(x+x^2)-log(x))^a/log(1+x)^(a/2));
(%o1)                                     a/2
                                     log(x + 1)

(%i2) radcan((log(1+2*a^x+a^(2*x))/log(1+a^x)));
(%o2)                                     2

(%i3) radcan((%e^x-1)/(1+%e^(x/2)));
(%o3)                                     x/2
                                     %e      - 1
```

radexpand

Option variable

Default value: `true`

`radexpand` controls some simplifications of radicals.

When `radexpand` is `all`, causes *n*th roots of factors of a product which are powers of *n* to be pulled outside of the radical. E.g. if `radexpand` is `all`, `sqrt(16*x^2)` simplifies to `4*x`.

More particularly, consider `sqrt(x^2)`.

- If `radexpand` is `all` or `assume(x > 0)` has been executed, `sqrt(x^2)` simplifies to `x`.
- If `radexpand` is `true` and `domain` is `real` (its default), `sqrt(x^2)` simplifies to `abs(x)`.

- If `radexpand` is `false`, or `radexpand` is `true` and `domain` is `complex`, `sqrt(x^2)` is not simplified.

Note that `domain` only matters when `radexpand` is `true`.

rassociative

Property

`declare (g, rassociative)` tells the Maxima simplifier that `g` is right-associative. E.g., `g(g(a, b), g(c, d))` simplifies to `g(a, g(b, g(c, d)))`.

scsimp (*expr*, *rule_1*, ..., *rule_n*)

Function

Sequential Comparative Simplification (method due to Stoute). `scsimp` attempts to simplify *expr* according to the rules *rule_1*, ..., *rule_n*. If a smaller expression is obtained, the process repeats. Otherwise after all simplifications are tried, it returns the original answer.

`example (scsimp)` displays some examples.

simp

Option variable

Default value: `true`

`simp` enables simplification. This is the standard. `simp` is also an `evflag`, which is recognized by the function `ev`. See `ev`.

When `simp` is used as an `evflag` with a value `false`, the simplification is suppressed only during the evaluation phase of an expression. The flag can not suppress the simplification which follows the evaluation phase.

Examples:

The simplification is switched off globally. The expression `sin(1.0)` is not simplified to its numerical value. The `simp`-flag switches the simplification on.

```
(%i1) simp:false;
(%o1)                                     false
(%i2) sin(1.0);
(%o2)                                     sin(1.0)
(%i3) sin(1.0),simp;
(%o3)                                     .8414709848078965
```

The simplification is switched on again. The `simp`-flag cannot suppress the simplification completely. The output shows a simplified expression, but the variable `x` has an unsimplified expression as a value, because the assignment has occurred during the evaluation phase of the expression.

```
(%i4) simp:true;
(%o4)                                     true
(%i5) x:sin(1.0),simp:false;
(%o5)                                     .8414709848078965
(%i6) :lisp $X
((%SIN) 1.0)
```

symmetric

Property

`declare (h, symmetric)` tells the Maxima simplifier that `h` is a symmetric function. E.g., `h(x, z, y)` simplifies to `h(x, y, z)`.

`commutative` is synonymous with `symmetric`.

xthru (*expr*)

Function

Combines all terms of *expr* (which should be a sum) over a common denominator without expanding products and exponentiated sums as `ratsimp` does. `xthru` cancels common factors in the numerator and denominator of rational expressions but only if the factors are explicit.

Sometimes it is better to use `xthru` before `ratsimp` an expression in order to cause explicit factors of the gcd of the numerator and denominator to be canceled thus simplifying the expression to be `ratsimped`.

Examples:

```
(%i1) ((x+2)^20 - 2*y)/(x+y)^20 + (x+y)^(-19) - x/(x+y)^20;
```

```
(%o1)      1      20      x
      ----- + ----- - -----
      19      20      20
      (y + x)  (y + x)  (y + x)
```

```
(%i2) xthru (%);
```

```
(%o2)      20
      (x + 2) - y
      -----
      20
      (y + x)
```


10 Mathematical Functions

10.1 Functions for Numbers

abs (*z*) Function

The **abs** function represents the mathematical absolute value function and works for both numerical and symbolic values. If the argument, *z*, is a real or complex number, **abs** returns the absolute value of *z*. If possible, symbolic expressions using the absolute value function are also simplified.

Maxima can differentiate, integrate and calculate limits for expressions containing **abs**. The **abs_integrate** package further extends Maxima's ability to calculate integrals involving the **abs** function. See (%i12) in the examples below.

When applied to a list or matrix, **abs** automatically distributes over the terms. Similarly, it distributes over both sides of an equation. To alter this behaviour, see the variable **distribute_over**.

Examples:

Calculation of **abs** for real and complex numbers, including numerical constants and various infinities. The first example shows how **abs** distributes over the elements of a list.

```
(%i1) abs([-4, 0, 1, 1+%i]);
(%o1) [4, 0, 1, sqrt(2)]
```

```
(%i2) abs((1+%i)*(1-%i));
(%o2) 2
(%i3) abs(%e+%i);
(%o3) 2
```

```
(%i4) abs([inf, infinity, minf]);
(%o4) [inf, inf, inf]
```

Simplification of expressions containing **abs**:

```
(%i5) abs(x^2);
(%o5) x^2
(%i6) abs(x^3);
(%o6) x^3
(%i7) abs(abs(x));
(%o7) abs(x)
(%i8) abs(conjugate(x));
(%o8) abs(x)
```

Integrating and differentiating with the **abs** function. Note that more integrals involving the **abs** function can be performed, if the **abs_integrate** package is loaded. The last example shows the Laplace transform of **abs**: see **laplace**.

```
(%i9) diff(x*abs(x),x),expand;
(%o9) 2 abs(x)

(%i10) integrate(abs(x),x);
(%o10) x abs(x)
      -----
      2

(%i11) integrate(x*abs(x),x);
      /
```

```

(%o11)
[
  I x abs(x) dx
]
/

(%i12) load(abs_integrate)$
(%i13) integrate(x*abs(x),x);

(%o13)
      2      3
      x  abs(x)  x  signum(x)
----- - -----
      2      6

(%i14) integrate(abs(x),x,-2,%pi);

(%o14)
      2
      %pi
      ---- + 2
      2

(%i15) laplace(abs(x),x,s);

(%o15)
      1
      --
      2
      s

```

ceiling (x)

Function

When x is a real number, return the least integer that is greater than or equal to x .

If x is a constant expression ($10 * \%pi$, for example), **ceiling** evaluates x using big floating point numbers, and applies **ceiling** to the resulting big float. Because **ceiling** uses floating point evaluation, it's possible, although unlikely, that **ceiling** could return an erroneous value for constant inputs. To guard against errors, the floating point evaluation is done using three values for **fpprec**.

For non-constant inputs, **ceiling** tries to return a simplified value. Here are examples of the simplifications that **ceiling** knows about:

```

(%i1) ceiling (ceiling (x));
(%o1) ceiling(x)
(%i2) ceiling (floor (x));
(%o2) floor(x)
(%i3) declare (n, integer)$
(%i4) [ceiling (n), ceiling (abs (n)), ceiling (max (n, 6))];
(%o4) [n, abs(n), max(n, 6)]
(%i5) assume (x > 0, x < 1)$
(%i6) ceiling (x);
(%o6) 1
(%i7) tex (ceiling (a));
$$$ \left \lceil a \right \rceil $$$
(%o7) false

```

The function **ceiling** does not automatically map over lists or matrices. Finally, for all inputs that are manifestly complex, **ceiling** returns a noun form.

If the range of a function is a subset of the integers, it can be declared to be **integervalued**. Both the **ceiling** and **floor** functions can use this information; for example:

```

(%i1) declare (f, integervalued)$
(%i2) floor (f(x));
(%o2) f(x)
(%i3) ceiling (f(x) - 1);
(%o3) f(x) - 1

```

entier (*x*)

Function

Returns the largest integer less than or equal to *x* where *x* is numeric. **fix** (as in **fixnum**) is a synonym for this, so **fix**(*x*) is precisely the same.

floor (*x*)

Function

When *x* is a real number, return the largest integer that is less than or equal to *x*.

If *x* is a constant expression (`10 * %pi`, for example), **floor** evaluates *x* using big floating point numbers, and applies **floor** to the resulting big float. Because **floor** uses floating point evaluation, it's possible, although unlikely, that **floor** could return an erroneous value for constant inputs. To guard against errors, the floating point evaluation is done using three values for **fpprec**.

For non-constant inputs, **floor** tries to return a simplified value. Here are examples of the simplifications that **floor** knows about:

```
(%i1) floor (ceiling (x));
(%o1) ceiling(x)
(%i2) floor (floor (x));
(%o2) floor(x)
(%i3) declare (n, integer)$
(%i4) [floor (n), floor (abs (n)), floor (min (n, 6))];
(%o4) [n, abs(n), min(n, 6)]
(%i5) assume (x > 0, x < 1)$
(%i6) floor (x);
(%o6) 0
(%i7) tex (floor (a));
$$\left \lfloor a \right \rfloor$
(%o7) false
```

The function **floor** does not automatically map over lists or matrices. Finally, for all inputs that are manifestly complex, **floor** returns a noun form.

If the range of a function is a subset of the integers, it can be declared to be **integervalued**. Both the **ceiling** and **floor** functions can use this information; for example:

```
(%i1) declare (f, integervalued)$
(%i2) floor (f(x));
(%o2) f(x)
(%i3) ceiling (f(x) - 1);
(%o3) f(x) - 1
```

fix (*x*)

Function

A synonym for **entier** (*x*).

lmax (*L*)

Function

When *L* is a list or a set, return **apply** ('max, args (*L*)). When *L* is not a list or a set, signal an error. See also **lmin** and **max**.

lmin (*L*)

Function

When *L* is a list or a set, return **apply** ('min, args (*L*)). When *L* is not a list or a set, signal an error. See also **lmax** and **min**.

max (*x₁*, ..., *x_n*)

Function

Return a simplified value for the maximum of the expressions *x₁* through *x_n*. When **get** (**trylevel**, **maxmin**), is 2 or greater, **max** uses the simplification **max** (*e*, -*e*) --> |*e*|. When **get** (**trylevel**, **maxmin**) is 3 or greater, **max** tries to eliminate expressions that are between two other arguments; for example, **max** (*x*, 2**x*, 3**x*) --> **max** (*x*, 3**x*). To set the value of **trylevel** to 2, use **put** (**trylevel**, 2, **maxmin**).

See also **min** and **lmax**.

min (x_1, \dots, x_n) Function

Return a simplified value for the minimum of the expressions x_1 through x_n . When `get (trylevel, maxmin)`, is 2 or greater, `min` uses the simplification $\min(e, -e) \rightarrow -|e|$. When `get (trylevel, maxmin)` is 3 or greater, `min` tries to eliminate expressions that are between two other arguments; for example, $\min(x, 2*x, 3*x) \rightarrow \min(x, 3*x)$. To set the value of `trylevel` to 2, use `put (trylevel, 2, maxmin)`.

See also `max` and `lmin`.

round (x) Function

When x is a real number, returns the closest integer to x . Multiples of $1/2$ are rounded to the nearest even integer. Evaluation of x is similar to `floor` and `ceiling`.

signum (x) Function

For either real or complex numbers x , the signum function returns 0 if x is zero; for a nonzero numeric input x , the signum function returns $\text{abs}(x)/x$.

For non-numeric inputs, Maxima attempts to determine the sign of the input. When the sign is negative, zero, or positive, `signum` returns -1, 0, 1, respectively. For all other values for the sign, `signum` a simplified but equivalent form. The simplifications include reflection (`signum(-x)` gives $-\text{signum}(x)$) and multiplicative identity (`signum(x*y)` gives $\text{signum}(x) * \text{signum}(y)$).

The `signum` function distributes over a list, a matrix, or an equation. See `distribute_over`.

10.2 Functions for Complex Numbers

cabs (expr) Function

Calculates the absolute value of an expression representing a complex number. Unlike the function `abs`, the `cabs` function always decomposes its argument into a real and an imaginary part. If x and y represent real variables or expressions, the `cabs` function calculates the absolute value of $x + \%i*y$ as

$$\sqrt{y^2 + x^2}$$

The `cabs` function can use known properties like symmetry properties of complex functions to help it calculate the absolute value of an expression. If such identities exist, they can be advertised to `cabs` using function properties. The symmetries that `cabs` understands are: mirror symmetry, conjugate function and complex characteristic.

`cabs` is a verb function and is not suitable for symbolic calculations. For such calculations (including integration, differentiation and taking limits of expressions containing absolute values), use `abs`.

The result of `cabs` can include the absolute value function, `abs`, and the arc tangent, `atan2`.

When applied to a list or matrix, `cabs` automatically distributes over the terms. Similarly, it distributes over both sides of an equation.

For further ways to compute with complex numbers, see the functions `rectform`, `realpart`, `imagpart`, `carg`, `conjugate` and `polarform`.

Examples:

Examples with `sqrt` and `sin`.

```
(%i1) cabs(sqrt(1+%i*x));
(%o1) (x^2 + 1)^1/4
(%i2) cabs(sin(x+%i*y));
(%o2) sqrt(cos(x)^2 + sinh(y)^2) + sin(x) cosh(y)
```

The error function, `erf`, has mirror symmetry, which is used here in the calculation of the absolute value with a complex argument:

```
(%i3) cabs(erf(x+%i*y));
```

$$\sqrt{\frac{(\operatorname{erf}(\%i y + x) - \operatorname{erf}(\%i y - x))^2}{4} - \frac{(\operatorname{erf}(\%i y + x) + \operatorname{erf}(\%i y - x))^2}{4}}$$

```
(%o3)
```

Maxima knows complex identities for the Bessel functions, which allow it to compute the absolute value for complex arguments. Here is an example for `bessel_j`.

```
(%i4) cabs(bessel_j(1,%i));
(%o4)          abs(bessel_j(1, %i))
```

carg (z)

Function

Returns the complex argument of z . The complex argument is an angle `theta` in $(-\pi, \pi]$ such that $r \exp(i \theta) = z$ where r is the magnitude of z .

`carg` is a computational function, not a simplifying function.

See also `abs` (complex magnitude), `polarform`, `rectform`, `realpart`, and `imagpart`.

Examples:

```
(%i1) carg (1);
(%o1)          0
(%i2) carg (1 + %i);
(%o2)          %pi
              ---
              4
(%i3) carg (exp (%i));
(%o3)          1
(%i4) carg (exp (%pi * %i));
(%o4)          %pi
(%i5) carg (exp (3/2 * %pi * %i));
(%o5)          - %pi
              ---
              2
(%i6) carg (17 * exp (2 * %i));
(%o6)          2
```

conjugate (x)

Function

Returns the complex conjugate of x .

```
(%i1) declare ([aa, bb], real, cc, complex, ii, imaginary);

(%o1)          done
(%i2) conjugate (aa + bb*%i);

(%o2)          aa - %i bb
(%i3) conjugate (cc);

(%o3)          conjugate(cc)
(%i4) conjugate (ii);

(%o4)          - ii
(%i5) conjugate (xx + yy);

(%o5)          conjugate(yy) + conjugate(xx)
```

imagpart (*expr*) Function

Returns the imaginary part of the expression *expr*.

imagpart is a computational function, not a simplifying function.

See also **abs**, **carg**, **polarform**, **rectform**, and **realpart**.

polarform (*expr*) Function

Returns an expression $r \%e^{(\%i \text{ theta})}$ equivalent to *expr*, such that *r* and *theta* are purely real.

realpart (*expr*) Function

Returns the real part of *expr*. **realpart** and **imagpart** will work on expressions involving trigonometric and hyperbolic functions, as well as square root, logarithm, and exponentiation.

rectform (*expr*) Function

Returns an expression $a + b \%i$ equivalent to *expr*, such that *a* and *b* are purely real.

10.3 Combinatorial Functions

!! Operator

The double factorial operator.

For an integer, float, or rational number *n*, **n!!** evaluates to the product $n (n-2) (n-4) (n-6) \dots (n - 2 (k-1))$ where *k* is equal to **entier** (*n*/2), that is, the largest integer less than or equal to *n*/2. Note that this definition does not coincide with other published definitions for arguments which are not integers.

For an even (or odd) integer *n*, **n!!** evaluates to the product of all the consecutive even (or odd) integers from 2 (or 1) through *n* inclusive.

For an argument *n* which is not an integer, float, or rational, **n!!** yields a noun form **genfact** (*n*, *n*/2, 2).

binomial (*x*, *y*) Function

The binomial coefficient $x!/(y! (x - y)!)$. If *x* and *y* are integers, then the numerical value of the binomial coefficient is computed. If *y*, or *x - y*, is an integer, the binomial coefficient is expressed as a polynomial.

Examples:

```
(%i1) binomial (11, 7);
(%o1)                                     330
(%i2) 11! / 7! / (11 - 7)!;
(%o2)                                     330
(%i3) binomial (x, 7);
      (x - 6) (x - 5) (x - 4) (x - 3) (x - 2) (x - 1) x
(%o3) -----
                        5040
(%i4) binomial (x + 7, x);
      (x + 1) (x + 2) (x + 3) (x + 4) (x + 5) (x + 6) (x + 7)
(%o4) -----
                        5040
(%i5) binomial (11, y);
(%o5)                               binomial(11, y)
```

factcomb (*expr*) Function

Tries to combine the coefficients of factorials in *expr* with the factorials themselves by converting, for example, $(n + 1)*n!$ into $(n + 1)!$.

sumsplitfact if set to **false** will cause **minfactorial** to be applied after a **factcomb**.

factorial
!Function
Operator

Represents the factorial function. Maxima treats **factorial** (x) the same as $x!$.

For any complex number x , except for negative integers, $x!$ is defined as **gamma**($x+1$).

For an integer x , $x!$ simplifies to the product of the integers from 1 to x inclusive. $0!$ simplifies to 1. For a real or complex number in float or bigfloat precision x , $x!$ simplifies to the value of **gamma** ($x+1$). For x equal to $n/2$ where n is an odd integer, $x!$ simplifies to a rational factor times **sqrt** (**%pi**) (since **gamma** ($1/2$) is equal to **sqrt** (**%pi**)).

The option variables **factlim** and **gammalim** control the numerical evaluation of factorials for integer and rational arguments. The functions **minfactorial** and **factcomb** simplifies expressions containing factorials.

The functions **gamma**, **bffac**, and **cbffac** are varieties of the gamma function. **bffac** and **cbffac** are called internally by **gamma** to evaluate the gamma function for real and complex numbers in bigfloat precision.

makegamma substitutes **gamma** for factorials and related functions.

Maxima knows the derivative of the factorial function and the limits for specific values like negative integers.

The option variable **factorial_expand** controls the simplification of expressions like $(n+x)!$, where n is an integer.

See also **binomial**.

The factorial of an integer is simplified to an exact number unless the operand is greater than **factlim**. The factorial for real and complex numbers is evaluated in float or bigfloat precision.

```
(%i1) factlim:10;
(%o1) 10
(%i2) [0!, (7/2)!, 8!, 20!];
(%o2) [1, -----, 40320, 20!]
          105 sqrt(%pi)
          16
(%i3) [4.77!, (1.0+%i)!];
(%o3) [81.44668037931197,
      .3430658398165454 %i + .6529654964201665]
(%i4) [2.86b0!, (1.0b0+%i)!];
(%o4) [5.046635586910012b0,
      3.430658398165454b-1 %i + 6.529654964201667b-1]
```

The factorial of a known constant, or general expression is not simplified. Even so it may be possible to simplify the factorial after evaluating the operand.

```
(%i1) [(%i + 1)!, %pi!, %e!, (cos(1) + sin(1))!];
(%o1) [(%i + 1)!, %pi!, %e!, (sin(1) + cos(1))!]
(%i2) ev (%i, numer, %enumer);
(%o2) [.3430658398165454 %i + .6529654964201665,
      7.188082728976031,
      4.260820476357003, 1.227580202486819]
```

Factorials are simplified, not evaluated. Thus $x!$ may be replaced even in a quoted expression.

```
(%i1) '([0!, (7/2)!, 4.77!, 8!, 20!]);
(%o1) [1, -----, 81.44668037931199, 40320,
          105 sqrt(%pi)
          16
          2432902008176640000]
```

Maxima knows the derivative of the factorial function.

```
(%i1) diff(x!,x);
(%o1) x! psi (x + 1)
      0
```

The option variable `factorial_expand` controls expansion and simplification of expressions with the factorial function.

```
(%i1) (n+1)!/n!,factorial_expand:true;
(%o1)                                     n + 1
```

factlim

Option variable

Default value: -1

`factlim` specifies the highest factorial which is automatically expanded. If it is -1 then all integers are expanded.

factorial_expand

Option variable

Default value: false

The option variable `factorial_expand` controls the simplification of expressions like $(n+1)!$, where n is an integer. See `factorial` for an example.

genfact (x, y, z)

Function

Returns the generalized factorial, defined as $x(x-z)(x-2z)\dots(x-(y-1)z)$. Thus, for integral x , `genfact` ($x, x, 1$) = $x!$ and `genfact` ($x, x/2, 2$) = $x!!$.

minfactorial ($expr$)

Function

Examines $expr$ for occurrences of two factorials which differ by an integer. `minfactorial` then turns one into a polynomial times the other.

```
(%i1) n!/(n+2)!;
(%o1)                                     n!
                                     -----
                                     (n + 2)!

(%i2) minfactorial (%);
(%o2)                                     1
                                     -----
                                     (n + 1) (n + 2)
```

sumsplitfact

Option variable

Default value: true

When `sumsplitfact` is false, `minfactorial` is applied after a `factcomb`.

10.4 Root, Exponential and Logarithmic Functions

%e_to_numlog

Option variable

Default value: false

When true, r some rational number, and x some expression, $e^{(r \cdot \log(x))}$ will be simplified into x^r . It should be noted that the `radcan` command also does this transformation, and more complicated transformations of this ilk as well. The `logcontract` command "contracts" expressions containing `log`.

%emode

Option variable

Default value: true

When `%emode` is true, $e^{(\pi i x)}$ is simplified as follows.

$e^{(\pi i x)}$ simplifies to $\cos(\pi x) + i \sin(\pi x)$ if x is a floating point number, an integer, or a multiple of $1/2$, $1/3$, $1/4$, or $1/6$, and then further simplified.

For other numerical x , $e^{(\pi i x)}$ simplifies to $e^{(\pi i y)}$ where y is $x - 2k$ for some integer k such that $\text{abs}(y) < 1$.

When `%emode` is false, no special simplification of $e^{(\pi i x)}$ is carried out.

%enumer

Option variable

Default value: **false**When **%enumer** is **true**, **%e** is replaced by its numeric value 2.718... whenever **numer** is **true**.When **%enumer** is **false**, this substitution is carried out only if the exponent in **%e^x** evaluates to a number.See also **ev** and **numer**.**exp (x)**

Function

Represents the exponential function. Instances of **exp (x)** in input are simplified to **%e^x**; **exp** does not appear in simplified expressions.**demoivre** if **true** causes **%e^(a + b %i)** to simplify to **%e^{(a (cos(b) + %i sin(b)))}** if **b** is free of **%i**. See **demoivre**.**%emode**, when **true**, causes **%e^(%pi %i x)** to be simplified. See **%emode**.**%enumer**, when **true** causes **%e** to be replaced by 2.718... whenever **numer** is **true**. See **%enumer**.**li [s] (z)**

Function

Represents the polylogarithm function of order **s** and argument **z**, defined by the infinite series

$$\text{Li}_s(z) = \sum_{k=1}^{\infty} \frac{z^k}{k^s}$$

li [1] is $-\log(1 - z)$. **li [2]** and **li [3]** are the dilogarithm and trilogarithm functions, respectively.When the order is 1, the polylogarithm simplifies to $-\log(1 - z)$, which in turn simplifies to a numerical value if **z** is a real or complex floating point number or the **numer** evaluation flag is present.When the order is 2 or 3, the polylogarithm simplifies to a numerical value if **z** is a real floating point number or the **numer** evaluation flag is present.

Examples:

```
(%i1) assume (x > 0);
(%o1) [x > 0]
(%i2) integrate ((log (1 - t)) / t, t, 0, x);
(%o2) - li (x)
      2
(%i3) li [2] (7);
(%o3) li (7)
      2
(%i4) li [2] (7), numer;
(%o4) 1.24827317833392 - 6.113257021832577 %i
(%i5) li [3] (7);
(%o5) li (7)
      3
(%i6) li [2] (7), numer;
(%o6) 1.24827317833392 - 6.113257021832577 %i
(%i7) L : makelist (i / 4.0, i, 0, 8);
(%o7) [0.0, 0.25, 0.5, 0.75, 1.0, 1.25, 1.5, 1.75, 2.0]
(%i8) map (lambda ([x], li [2] (x)), L);
(%o8) [0, .2676526384986274, .5822405249432515,
      .9784693966661848, 1.64493407, 2.190177004178597
      - .7010261407036192 %i, 2.374395264042415
      - 1.273806203464065 %i, 2.448686757245154
      - 1.758084846201883 %i, 2.467401098097648
      - 2.177586087815347 %i]
```

```
(%i9) map (lambda ([x], li [3] (x)), L);
(%o9) [0, .2584613953442624, 0.537213192678042,
.8444258046482203, 1.2020569, 1.642866878950322
- .07821473130035025 %i, 2.060877505514697
- .2582419849982037 %i, 2.433418896388322
- .4919260182322965 %i, 2.762071904015935
- .7546938285978846 %i]
```

log (x)

Function

Represents the natural (base e) logarithm of x .

Maxima does not have a built-in function for the base 10 logarithm or other bases. $\log_{10}(x) := \log(x) / \log(10)$ is a useful definition.

Simplification and evaluation of logarithms is governed by several global flags:

logexpand

causes $\log(a^b)$ to become $b \cdot \log(a)$. If it is set to **all**, $\log(a \cdot b)$ will also simplify to $\log(a) + \log(b)$. If it is set to **super**, then $\log(a/b)$ will also simplify to $\log(a) - \log(b)$ for rational numbers a/b , $a \neq 1$. ($\log(1/b)$, for b integer, always simplifies.) If it is set to **false**, all of these simplifications will be turned off.

logsimp if **false** then no simplification of e to a power containing \log 's is done.

lognegint

if **true** implements the rule $\log(-n) \rightarrow \log(n) + i \cdot \pi$ for n a positive integer.

%e_to_numlog

when **true**, r some rational number, and x some expression, the expression $e^{(r \cdot \log(x))}$ will be simplified into x^r . It should be noted that the **radcan** command also does this transformation, and more complicated transformations of this as well. The **logcontract** command "contracts" expressions containing \log .

logabs

Option variable

Default value: **false**

When doing indefinite integration where logs are generated, e.g. **integrate**($1/x, x$), the answer is given in terms of $\log(\text{abs}(\dots))$ if **logabs** is **true**, but in terms of $\log(\dots)$ if **logabs** is **false**. For definite integration, the **logabs:true** setting is used, because here "evaluation" of the indefinite integral at the endpoints is often needed.

logarc

Option variable

logarc (expr)

Function

When the global variable **logarc** is **true**, inverse circular and hyperbolic functions are replaced by equivalent logarithmic functions. The default value of **logarc** is **false**.

The function **logarc(expr)** carries out that replacement for an expression $expr$ without setting the global variable **logarc**.

logconcoeffp

Option variable

Default value: **false**

Controls which coefficients are contracted when using **logcontract**. It may be set to the name of a predicate function of one argument. E.g. if you like to generate SQRTs, you can do **logconcoeffp: 'logconfun\$ logconfun(m) := featurep(m, integer) or ratnum(m)\$**. Then **logcontract**($1/2 \cdot \log(x)$); will give $\log(\text{sqrt}(x))$.

logcontract (*expr*)

Function

Recursively scans the expression *expr*, transforming subexpressions of the form $a_1 \log(b_1) + a_2 \log(b_2) + c$ into $\log(\text{ratsimp}(b_1^{a_1} * b_2^{a_2})) + c$

```
(%i1) 2*(a*log(x) + 2*a*log(y))$
```

```
(%i2) logcontract(%);
```

```
(%o2)          2 4
          a log(x y )
```

The declaration `declare(n, integer)` causes `logcontract(2*a*n*log(x))` to simplify to `a*log(x^(2*n))`. The coefficients that "contract" in this manner are those such as the 2 and the *n* here which satisfy `featurep(coeff, integer)`. The user can control which coefficients are contracted by setting the option `logconcoeffp` to the name of a predicate function of one argument. E.g. if you like to generate SQRTs, you can do `logconcoeffp: 'logconfun$ logconfun(m):=featurep(m, integer) or ratnum(m)$`. Then `logcontract(1/2*log(x))`; will give `log(sqrt(x))`.

logexpand

Option variable

Default value: `true`

If `true`, that is the default value, causes `log(a^b)` to become `b*log(a)`. If it is set to `all`, `log(a*b)` will also simplify to `log(a)+log(b)`. If it is set to `super`, then `log(a/b)` will also simplify to `log(a)-log(b)` for rational numbers *a/b*, *a*≠1. (`log(1/b)`, for integer *b*, always simplifies.) If it is set to `false`, all of these simplifications will be turned off.

lognegint

Option variable

Default value: `false`

If `true` implements the rule `log(-n) -> log(n)+%i*%pi` for *n* a positive integer.

logsimp

Option variable

Default value: `true`

If `false` then no simplification of `%e` to a power containing `log`'s is done.

plog (*x*)

Function

Represents the principal branch of the complex-valued natural logarithm with $-\pi < \text{carg}(x) \leq \pi$.

sqrt (*x*)

Function

The square root of *x*. It is represented internally by $x^{(1/2)}$. See also `rootscontract`.

`radexpand` if `true` will cause *n*th roots of factors of a product which are powers of *n* to be pulled outside of the radical, e.g. `sqrt(16*x^2)` will become `4*x` only if `radexpand` is `true`.

10.5 Trigonometric Functions

10.5.1 Introduction to Trigonometric

Maxima has many trigonometric functions defined. Not all trigonometric identities are programmed, but it is possible for the user to add many of them using the pattern matching capabilities of the system. The trigonometric functions defined in Maxima are: `acos`, `acosh`, `acot`, `acoth`, `acsc`, `acsch`, `asec`, `asech`, `asin`, `asinh`, `atan`, `atanh`, `cos`, `cosh`, `cot`, `coth`, `csc`, `csch`, `sec`, `sech`, `sin`, `sinh`, `tan`, and `tanh`. There are a number of commands especially for handling trigonometric functions, see `trigexpand`, `trigreduce`, and the switch `trigsign`. Two share packages extend the simplification rules built into Maxima, `ntrig` and `atrig1`. Do `describe(command)` for details.

10.5.2 Functions and Variables for Trigonometric

`%piargs`

Option variable

Default value: `true`

When `%piargs` is `true`, trigonometric functions are simplified to algebraic constants when the argument is an integer multiple of π , $\pi/2$, $\pi/3$, $\pi/4$, or $\pi/6$.

Maxima knows some identities which can be applied when π , etc., are multiplied by an integer variable (that is, a symbol declared to be integer).

Examples:

```
(%i1) %piargs : false$
(%i2) [sin (%pi), sin (%pi/2), sin (%pi/3)];
(%o2) [sin(%pi), sin(---), sin(---)]
              %pi      %pi
              2        3
(%i3) [sin (%pi/4), sin (%pi/5), sin (%pi/6)];
(%o3) [sin(---), sin(---), sin(---)]
              4        5        6
(%i4) %piargs : true$
(%i5) [sin (%pi), sin (%pi/2), sin (%pi/3)];
(%o5) [0, 1, -----]
              sqrt(3)
              2
(%i6) [sin (%pi/4), sin (%pi/5), sin (%pi/6)];
(%o6) [-----, sin(---), -]
              1      %pi  1
              sqrt(2) 5    2
(%i7) [cos (%pi/3), cos (10*%pi/3), tan (10*%pi/3),
      cos (sqrt(2)*%pi/3)];
(%o7) [-, - , sqrt(3), cos(-----)]
              1      1      sqrt(2) %pi
              2      2      3
```

Some identities are applied when π and $\pi/2$ are multiplied by an integer variable.

```
(%i1) declare (n, integer, m, even)$
(%i2) [sin (%pi * n), cos (%pi * m), sin (%pi/2 * m),
      cos (%pi/2 * m)];
(%o2) [0, 1, 0, (- 1) m/2 ]
```

`%iargs`

Option variable

Default value: `true`

When `%iargs` is `true`, trigonometric functions are simplified to hyperbolic functions when the argument is apparently a multiple of the imaginary unit i .

Even when the argument is demonstrably real, the simplification is applied; Maxima considers only whether the argument is a literal multiple of i .

Examples:

```
(%i1) %iargs : false$
(%i2) [sin (%i * x), cos (%i * x), tan (%i * x)];
(%o2) [sin(%i x), cos(%i x), tan(%i x)]
(%i3) %iargs : true$
(%i4) [sin (%i * x), cos (%i * x), tan (%i * x)];
(%o4) [%i sinh(x), cosh(x), %i tanh(x)]
```

Even when the argument is demonstrably real, the simplification is applied.

```
(%i1) declare (x, imaginary)$
(%i2) [featurep (x, imaginary), featurep (x, real)];
(%o2) [true, false]
(%i3) sin (%i * x);
(%o3) %i sinh(x)
```

acos (x)	Function
– Arc Cosine.	
acosh (x)	Function
– Hyperbolic Arc Cosine.	
acot (x)	Function
– Arc Cotangent.	
acoth (x)	Function
– Hyperbolic Arc Cotangent.	
acsc (x)	Function
– Arc Cosecant.	
acsch (x)	Function
– Hyperbolic Arc Cosecant.	
asec (x)	Function
– Arc Secant.	
asech (x)	Function
– Hyperbolic Arc Secant.	
asin (x)	Function
– Arc Sine.	
asinh (x)	Function
– Hyperbolic Arc Sine.	
atan (x)	Function
– Arc Tangent.	
atan2 (y, x)	Function
– yields the value of <code>atan(y/x)</code> in the interval $-\pi$ to π .	

atanh (*x*) Function
 – Hyperbolic Arc Tangent.

atrig1 Package
 The **atrig1** package contains several additional simplification rules for inverse trigonometric functions. Together with rules already known to Maxima, the following angles are fully implemented: 0, %pi/6, %pi/4, %pi/3, and %pi/2. Corresponding angles in the other three quadrants are also available. Do `load(atrig1);` to use them.

cos (*x*) Function
 – Cosine.

cosh (*x*) Function
 – Hyperbolic Cosine.

cot (*x*) Function
 – Cotangent.

coth (*x*) Function
 – Hyperbolic Cotangent.

csc (*x*) Function
 – Cosecant.

csch (*x*) Function
 – Hyperbolic Cosecant.

halfangles Option variable

Default value: **false**

When **halfangles** is **true**, trigonometric functions of arguments *expr*/2 are simplified to functions of *expr*.

For a real argument *x* in the interval $0 < x < 2\pi$ the sine of the half-angle simplifies to a simple formula:

$$\frac{\sqrt{1 - \cos(x)}}{\sqrt{2}}$$

A complicated factor is needed to make this formula correct for all complex arguments *z*:

$$\begin{aligned} & \frac{\text{realpart}(z)}{\text{floor}(\frac{\text{realpart}(z)}{2\pi})} \\ & (-1)^{\text{floor}(\frac{\text{realpart}(z)}{2\pi}) - \text{ceiling}(\frac{\text{realpart}(z)}{2\pi})} (1 - \text{unit_step}(-\text{imagpart}(z))) \\ & ((-1)^{\text{floor}(\frac{\text{realpart}(z)}{2\pi}) - \text{ceiling}(\frac{\text{realpart}(z)}{2\pi})} + 1)) \end{aligned}$$

Maxima knows this factor and similar factors for the functions **sin**, **cos**, **sinh**, and **cosh**. For special values of the argument *z* these factors simplify accordingly.

Examples:

```
(%i1) halfangles:false;
(%o1)                                     false
(%i2) sin(x/2);
```

```

(%o2)                                sin(-)
                                      2

(%i3) halfangles:true;
(%o3)                                true

(%i4) sin(x/2);

                                      x
                                      floor(-----)
                                      2 %pi

(%o4)                                sqrt(1 - cos(x)) (- 1)
-----
                                      sqrt(2)

(%i5) assume(x>0, x<2*%pi)$
(%i6) sin(x/2);

                                sqrt(1 - cos(x))
                                -----
                                sqrt(2)

```

ntrig Package

The **ntrig** package contains a set of simplification rules that are used to simplify trigonometric function whose arguments are of the form $f(n\pi/10)$ where f is any of the functions **sin**, **cos**, **tan**, **csc**, **sec** and **cot**.

sec (x) Function
 – Secant.

sech (x) Function
 – Hyperbolic Secant.

sin (x) Function
 – Sine.

sinh (x) Function
 – Hyperbolic Sine.

tan (x) Function
 – Tangent.

tanh (x) Function
 – Hyperbolic Tangent.

trigexpand ($expr$) Function

Expands trigonometric and hyperbolic functions of sums of angles and of multiple angles occurring in $expr$. For best results, $expr$ should be expanded. To enhance user control of simplification, this function expands only one level at a time, expanding sums of angles or multiple angles. To obtain full expansion into sines and cosines immediately, set the switch **trigexpand: true**.

trigexpand is governed by the following global flags:

trigexpand

If **true** causes expansion of all expressions containing **sin**'s and **cos**'s occurring subsequently.

halfangles

If **true** causes half-angles to be simplified away.

trigexpandplus

Controls the "sum" rule for **trigexpand**, expansion of sums (e.g. **sin**($x + y$)) will take place only if **trigexpandplus** is **true**.

trigexpandtimes

Controls the "product" rule for **trigexpand**, expansion of products (e.g. $\sin(2x)$) will take place only if **trigexpandtimes** is **true**.

Examples:

```
(%i1) x+sin(3*x)/sin(x),trigexpand=true,expand;
      2      2
(%o1) - sin (x) + 3 cos (x) + x
(%i2) trigexpand(sin(10*x+y));
(%o2) cos(10 x) sin(y) + sin(10 x) cos(y)
```

trigexpandplus

Option variable

Default value: **true**

trigexpandplus controls the "sum" rule for **trigexpand**. Thus, when the **trigexpand** command is used or the **trigexpand** switch set to **true**, expansion of sums (e.g. $\sin(x+y)$) will take place only if **trigexpandplus** is **true**.

trigexpandtimes

Option variable

Default value: **true**

trigexpandtimes controls the "product" rule for **trigexpand**. Thus, when the **trigexpand** command is used or the **trigexpand** switch set to **true**, expansion of products (e.g. $\sin(2x)$) will take place only if **trigexpandtimes** is **true**.

triginverses

Option variable

Default value: **true**

triginverses controls the simplification of the composition of trigonometric and hyperbolic functions with their inverse functions.

If **all**, both e.g. $\text{atan}(\tan(x))$ and $\tan(\text{atan}(x))$ simplify to x .

If **true**, the $\text{arcfun}(\text{fun}(x))$ simplification is turned off.

If **false**, both the $\text{arcfun}(\text{fun}(x))$ and $\text{fun}(\text{arcfun}(x))$ simplifications are turned off.

trigreduce (expr, x)

Function

trigreduce (expr)

Function

Combines products and powers of trigonometric and hyperbolic sin's and cos's of x into those of multiples of x . It also tries to eliminate these functions when they occur in denominators. If x is omitted then all variables in expr are used.

See also **poissimp**.

```
(%i1) trigreduce(-sin(x)^2+3*cos(x)^2+x);
      cos(2 x)      cos(2 x)      1      1
(%o1) ----- + 3 (----- + -) + x - -
      2      2      2      2
```

trigsign

Option variable

Default value: **true**

When **trigsign** is **true**, it permits simplification of negative arguments to trigonometric functions. E.g., $\sin(-x)$ will become $-\sin(x)$ only if **trigsign** is **true**.

trigsimp (expr)

Function

Employs the identities $\sin(x)^2 + \cos(x)^2 = 1$ and $\cosh(x)^2 - \sinh(x)^2 = 1$ to simplify expressions containing **tan**, **sec**, etc., to **sin**, **cos**, **sinh**, **cosh**.

trigreduce, **ratsimp**, and **radcan** may be able to further simplify the result.

demo ("trgsmp.dem") displays some examples of **trigsimp**.

trigrat (*expr*)

Function

Gives a canonical simplified quasilinear form of a trigonometrical expression; *expr* is a rational fraction of several **sin**, **cos** or **tan**, the arguments of them are linear forms in some variables (or kernels) and π/n (n integer) with integer coefficients. The result is a simplified fraction with numerator and denominator linear in **sin** and **cos**. Thus **trigrat** linearize always when it is possible.

```
(%i1) trigrat(sin(3*a)/sin(a+%pi/3));
```

```
(%o1)          sqrt(3) sin(2 a) + cos(2 a) - 1
```

The following example is taken from Davenport, Siret, and Tournier, *Calcul Formel*, Masson (or in English, Addison-Wesley), section 1.5.5, Morley theorem.

```
(%i1) c : %pi/3 - a - b$
```

```
(%i2) bc : sin(a)*sin(3*c)/sin(a+b);
```

$$\frac{\sin(a) \sin(3(-b - a + \frac{\pi}{3}))}{\sin(b + a)}$$

```
(%o2)
```

```
(%i3) ba : bc, c=a, a=c;
```

$$\frac{\sin(3a) \sin(b + a - \frac{\pi}{3})}{\sin(a - \frac{\pi}{3})}$$

```
(%o3)
```

```
(%i4) ac2 : ba^2 + bc^2 - 2*bc*ba*cos(b);
```

$$\sin^2(3a) \sin^2(b + a - \frac{\pi}{3}) - 2 \sin(3a) \sin(b + a - \frac{\pi}{3}) \sin(a - \frac{\pi}{3}) \cos(b)$$

```
(%o4)
```

$$\begin{aligned} & \sin^2(a - \frac{\pi}{3}) \cos(b) \\ & - (2 \sin(a) \sin(3a) \sin(3(-b - a + \frac{\pi}{3})) \cos(b) \\ & \sin(b + a - \frac{\pi}{3}) / (\sin(a - \frac{\pi}{3}) \sin(b + a)) \\ & \sin^2(a) \sin^2(3(-b - a + \frac{\pi}{3})) \\ & + \frac{\sin^2(b + a)}{\sin^2(b + a)} \end{aligned}$$

```
(%i5) trigrat(ac2);
```

```
(%o5) - (sqrt(3) sin(4 b + 4 a) - cos(4 b + 4 a)
```

```
  - 2 sqrt(3) sin(4 b + 2 a) + 2 cos(4 b + 2 a)
```

```
  - 2 sqrt(3) sin(2 b + 4 a) + 2 cos(2 b + 4 a)
```

```
  + 4 sqrt(3) sin(2 b + 2 a) - 8 cos(2 b + 2 a) - 4 cos(2 b - 2 a)
```

```
  + sqrt(3) sin(4 b) - cos(4 b) - 2 sqrt(3) sin(2 b) + 10 cos(2 b)
```

```
  + sqrt(3) sin(4 a) - cos(4 a) - 2 sqrt(3) sin(2 a) + 10 cos(2 a)
```

```
  - 9)/4
```


11 Maximas Database

11.1 Introduction to Maximas Database

11.2 Functions and Variables for Properties

alphabetic

Property

`alphabetic` is a property type recognized by `declare`. The expression `declare(s, alphabetic)` tells Maxima to recognize as alphabetic all of the characters in `s`, which must be a string.

See also [Section 6.3 \[Identifiers\]](#), page 60.

Example:

```
(%i1) xx~yy\'\'@ : 1729;
(%o1)                                     1729
(%i2) declare ("~\'@", alphabetic);
(%o2)                                     done
(%i3) xx~yy\'@ + @yy\'xx + \'xx@@yy~;
(%o3)                                     \'xx@@yy~ + @yy\'xx + 1729
(%i4) listofvars (%);
(%o4)                                     [@yy\'xx, \'xx@@yy~]
```

bindtest

Property

The command `declare(x, bindtest)` tells Maxima to trigger an error when the symbol `x` is evaluated unbound.

```
(%i1) aa + bb;
(%o1)                                     bb + aa
(%i2) declare (aa, bindtest);
(%o2)                                     done
(%i3) aa + bb;
aa unbound variable
-- an error. Quitting. To debug this try debugmode(true);
(%i4) aa : 1234;
(%o4)                                     1234
(%i5) aa + bb;
(%o5)                                     bb + 1234
```

constant

Property

`declare(a, constant)` declares `a` to be a constant. The declaration of a symbol to be constant does not prevent the assignment of a nonconstant value to the symbol.

See `constantp` and `declare`.

Example:

```
(%i1) declare(c, constant);
(%o1)                                     done
(%i2) constantp(c);
(%o2)                                     true
(%i3) c : x;
(%o3)                                     x
(%i4) constantp(c);
(%o4)                                     false
```

constantp (*expr*) Function

Returns **true** if *expr* is a constant expression, otherwise returns **false**.

An expression is considered a constant expression if its arguments are numbers (including rational numbers, as displayed with */R/*), symbolic constants such as *%pi*, *%e*, and *%i*, variables bound to a constant or declared constant by **declare**, or functions whose arguments are constant.

constantp evaluates its arguments.

See the property **constant** which declares a symbol to be constant.

Examples:

```
(%i1) constantp (7 * sin(2));
(%o1)                                     true
(%i2) constantp (rat (17/29));
(%o2)                                     true
(%i3) constantp (%pi * sin(%e));
(%o3)                                     true
(%i4) constantp (exp (x));
(%o4)                                     false
(%i5) declare (x, constant);
(%o5)                                     done
(%i6) constantp (exp (x));
(%o6)                                     true
(%i7) constantp (foo (x) + bar (%e) + baz (2));
(%o7)                                     false
(%i8)
```

declare (*a_1*, *p_1*, *a_2*, *p_2*, ...) Function

Assigns the atom or list of atoms *a_i* the property or list of properties *p_i*. When *a_i* and/or *p_i* are lists, each of the atoms gets all of the properties.

declare quotes its arguments. **declare** always returns **done**.

As noted in the description for each declaration flag, for some flags **featurep**(*object*, *feature*) returns **true** if *object* has been declared to have *feature*.

See also **features**.

declare recognizes the following properties:

additive Tells Maxima to simplify *a_i* expressions by the substitution *a_i*(*x* + *y* + *z* + ...) --> *a_i*(*x*) + *a_i*(*y*) + *a_i*(*z*) + The substitution is carried out on the first argument only.

alphabetic

Tells Maxima to recognize all characters in *a_i* (which must be a string) as alphabetic characters.

antisymmetric, commutative, symmetric

Tells Maxima to recognize *a_i* as a symmetric or antisymmetric function. **commutative** is the same as **symmetric**.

bindtest Tells Maxima to trigger an error when *a_i* is evaluated unbound.

constant Tells Maxima to consider *a_i* a symbolic constant.

even, odd Tells Maxima to recognize *a_i* as an even or odd integer variable.

evenfun, oddfun

Tells Maxima to recognize *a_i* as an odd or even function.

evflag Makes *a_i* known to the **ev** function so that *a_i* is bound to **true** during the execution of **ev** when *a_i* appears as a flag argument of **ev**. See **evflag**.

evfun Makes *a_i* known to **ev** so that the function named by *a_i* is applied when *a_i* appears as a flag argument of **ev**. See **evfun**.

feature	Tells Maxima to recognize <i>a.i</i> as the name of a feature. Other atoms may then be declared to have the <i>a.i</i> property.
increasing, decreasing	Tells Maxima to recognize <i>a.i</i> as an increasing or decreasing function.
integer, noninteger	Tells Maxima to recognize <i>a.i</i> as an integer or noninteger variable.
integervalued	Tells Maxima to recognize <i>a.i</i> as an integer-valued function.
lassociative, rassociative	Tells Maxima to recognize <i>a.i</i> as a right-associative or left-associative function.
linear	Equivalent to declaring <i>a.i</i> both outative and additive .
mainvar	Tells Maxima to consider <i>a.i</i> a "main variable". A main variable succeeds all other constants and variables in the canonical ordering of Maxima expressions, as determined by ordergreatp .
multiplicative	Tells Maxima to simplify <i>a.i</i> expressions by the substitution <i>a.i</i> (<i>x</i> * <i>y</i> * <i>z</i> * ...) --> <i>a.i</i> (<i>x</i>) * <i>a.i</i> (<i>y</i>) * <i>a.i</i> (<i>z</i>) * The substitution is carried out on the first argument only.
nary	Tells Maxima to recognize <i>a.i</i> as an n-ary function. The nary declaration is not the same as calling the nary function. The sole effect of declare (<i>foo</i> , nary) is to instruct the Maxima simplifier to flatten nested expressions, for example, to simplify <i>foo</i> (<i>x</i> , <i>foo</i> (<i>y</i> , <i>z</i>)) to <i>foo</i> (<i>x</i> , <i>y</i> , <i>z</i>).
nonarray	Tells Maxima to consider <i>a.i</i> not an array. This declaration prevents multiple evaluation of a subscripted variable name.
nonscalar	Tells Maxima to consider <i>a.i</i> a nonscalar variable. The usual application is to declare a variable as a symbolic vector or matrix.
noun	Tells Maxima to parse <i>a.i</i> as a noun. The effect of this is to replace instances of <i>a.i</i> with ' <i>a.i</i> ' or nounify (<i>a.i</i>), depending on the context.
outative	Tells Maxima to simplify <i>a.i</i> expressions by pulling constant factors out of the first argument. When <i>a.i</i> has one argument, a factor is considered constant if it is a literal or declared constant. When <i>a.i</i> has two or more arguments, a factor is considered constant if the second argument is a symbol and the factor is free of the second argument.
posfun	Tells Maxima to recognize <i>a.i</i> as a positive function.
rational, irrational	Tells Maxima to recognize <i>a.i</i> as a rational or irrational real variable.
real, imaginary, complex	Tells Maxima to recognize <i>a.i</i> as a real, pure imaginary, or complex variable.
scalar	Tells Maxima to consider <i>a.i</i> a scalar variable.

Examples of the usage of the properties are available in the documentation for each separate description of a property.

decreasing increasing

Property
Property

The commands **declare**(*f*, **decreasing**) or **declare**(*f*, **increasing**) tell Maxima to recognize the function *f* as an decreasing or increasing function.

See also **declare** for more properties.

Example:

```
(%i1) assume(a > b);
(%o1) [a > b]
(%i2) is(f(a) > f(b));
(%o2) unknown
(%i3) declare(f, increasing);
(%o3) done
(%i4) is(f(a) > f(b));
(%o4) true
```

even odd

Property
Property

`declare(a, even)` or `declare(a, odd)` tells Maxima to recognize the symbol *a* as an even or odd integer variable. The properties **even** and **odd** are not recognized by the functions `evenp`, `oddp`, and `integerp`.

See also `declare` and `askinteger`.

Example:

```
(%i1) declare(n, even);
(%o1) done
(%i2) askinteger(n, even);
(%o2) yes
(%i3) askinteger(n);
(%o3) yes
(%i4) evenp(n);
(%o4) false
```

feature

Property

Maxima understands two distinct types of features, system features and features which apply to mathematical expressions. See also **status** for information about system features. See also **features** and **featurep** for information about mathematical features.

feature itself is not the name of a function or variable.

featurep (a, f)

Function

Attempts to determine whether the object *a* has the feature *f* on the basis of the facts in the current database. If so, it returns **true**, else **false**.

Note that **featurep** returns **false** when neither *f* nor the negation of *f* can be established.

featurep evaluates its argument.

See also `declare` and `features`.

```
(%i1) declare (j, even)$
(%i2) featurep (j, integer);
(%o2) true
```

features

Declaration

Maxima recognizes certain mathematical properties of functions and variables. These are called "features".

`declare (x, foo)` gives the property *foo* to the function or variable *x*.

`declare (foo, feature)` declares a new feature *foo*. For example, `declare ([red, green, blue], feature)` declares three new features, **red**, **green**, and **blue**.

The predicate **featurep** (*x*, *foo*) returns **true** if *x* has the *foo* property, and **false** otherwise.

The infolist **features** is a list of known features. These are

integer	noninteger	even
odd	rational	irrational
real	imaginary	complex
analytic	increasing	decreasing
oddfun	evenfun	posfun
commutative	lassociative	rassociative
symmetric	antisymmetric	

plus any user-defined features.

features is a list of mathematical features. There is also a list of non-mathematical, system-dependent features. See **status**.

Example:

```
(%i1) declare (F00, feature);
(%o1)                                     done
(%i2) declare (x, F00);
(%o2)                                     done
(%i3) featurep (x, F00);
(%o3)                                     true
```

get (*a*, *i*)

Function

Retrieves the user property indicated by *i* associated with atom *a* or returns **false** if *a* doesn't have property *i*.

get evaluates its arguments.

See also **put** and **qput**.

```
(%i1) put (%e, 'transcendental, 'type);
(%o1)                                     transcendental
(%i2) put (%pi, 'transcendental, 'type)$
(%i3) put (%i, 'algebraic, 'type)$
(%i4) typeof (expr) := block ([q],
    if numberp (expr)
    then return ('algebraic),
    if not atom (expr)
    then return (maplist ('typeof, expr)),
    q: get (expr, 'type),
    if q=false
    then errcatch (error(expr,"is not numeric.")) else q)$
(%i5) typeof (2*%e + x*%pi);
x is not numeric.
(%o5) [[transcendental, []], [algebraic, transcendental]]
(%i6) typeof (2*%e + %pi);
(%o6) [transcendental, [algebraic, transcendental]]
```

integer

Property

noninteger

Property

declare(*a*, **integer**) or **declare**(*a*, **noninteger**) tells Maxima to recognize *a* as an integer or noninteger variable.

See also **declare**.

Example:

```
(%i1) declare(n, integer, x, noninteger);
(%o1)                                     done
(%i2) askinteger(n);
(%o2)                                     yes
(%i3) askinteger(x);
(%o3)                                     no
```

integervalued

Property

`declare(f, integervalued)` tells Maxima to recognize f as an integer-valued function.

See also `declare`.

Example:

```
(%i1) exp(%i)^f(x);
                                %i f(x)
(%o1)                                (%e )
(%i2) declare(f, integervalued);
(%o2)                                done
(%i3) exp(%i)^f(x);
                                %i f(x)
(%o3)                                %e
```

nonarray

Property

The command `declare(a, nonarray)` tells Maxima to consider a not an array. This declaration prevents multiple evaluation, if a is a subscripted variable.

See also `declare`.

Example:

```
(%i1) a:'b$ b:'c$ c:'d$

(%i4) a[x];
(%o4)                                d
                                x

(%i5) declare(a, nonarray);
(%o5)                                done
(%i6) a[x];
(%o6)                                a
                                x
```

nonscalar

Property

Makes atoms behave as does a list or matrix with respect to the dot operator.

See also `declare`.

nonscalarp (*expr*)

Function

Returns `true` if *expr* is a non-scalar, i.e., it contains atoms declared as non-scalars, lists, or matrices.

See also the predicate function `scalarp` and `declare`.

posfun

Property

`declare(f, posfun)` declares f to be a positive function. `is (f(x) > 0)` yields `true`.

See also `declare`.

printprops (*a*, *i*)

Function

printprops (*[a₁, ..., a_n]*, *i*)

Function

printprops (*all*, *i*)

Function

Displays the property with the indicator i associated with the atom a . a may also be a list of atoms or the atom `all` in which case all of the atoms with the given property will be used. For example, `printprops([f, g], atvalue)`. `printprops` is for properties that cannot otherwise be displayed, i.e. for `atvalue`, `atomgrad`, `gradef`, and `matchdeclare`.

properties (*a*)

Function

Returns a list of the names of all the properties associated with the atom a .

props System variable

Default value: []

props are atoms which have any property other than those explicitly mentioned in **infolists**, such as specified by **atvalue**, **matchdeclare**, etc., as well as properties specified in the **declare** function.

propvars (*prop*) Function

Returns a list of those atoms on the **props** list which have the property indicated by *prop*. Thus **propvars** (**atvalue**) returns a list of atoms which have **atvalues**.

put (*atom*, *value*, *indicator*) Function

Assigns *value* to the property (specified by *indicator*) of *atom*. *indicator* may be the name of any property, not just a system-defined property.

rem reverses the effect of **put**.

put evaluates its arguments. **put** returns *value*.

See also **qput** and **get**.

Examples:

```
(%i1) put (foo, (a+b)^5, expr);
                                     5
(%o1)                                (b + a)
(%i2) put (foo, "Hello", str);
(%o2)                                Hello
(%i3) properties (foo);
(%o3)                                [[user properties, str, expr]]
(%i4) get (foo, expr);
                                     5
(%o4)                                (b + a)
(%i5) get (foo, str);
(%o5)                                Hello
```

qput (*atom*, *value*, *indicator*) Function

Assigns *value* to the property (specified by *indicator*) of *atom*. This is the same as **put**, except that the arguments are quoted.

See also **get**.

Example:

```
(%i1) foo: aa$
(%i2) bar: bb$
(%i3) baz: cc$
(%i4) put (foo, bar, baz);
(%o4)                                bb
(%i5) properties (aa);
(%o5)                                [[user properties, cc]]
(%i6) get (aa, cc);
(%o6)                                bb
(%i7) qput (foo, bar, baz);
(%o7)                                bar
(%i8) properties (foo);
(%o8)                                [value, [user properties, baz]]
(%i9) get ('foo, 'baz);
(%o9)                                bar
```

rational Property
irrational Property

`declare(a, rational)` or `declare(a, irrational)` tells Maxima to recognize *a* as a rational or irrational real variable.

See also `declare`.

real Property
imaginary Property
complex Property

`declare(a, real)`, `declare(a, imaginary)`, or `declare(a, complex)` tells Maxima to recognize *a* as a real, pure imaginary, or complex variable.

See also `declare`.

rem (*atom*, *indicator*) Function

Removes the property indicated by *indicator* from *atom*. `rem` reverses the effect of `put`.

`rem` returns `done` if *atom* had an *indicator* property when `rem` was called, or `false` if it had no such property.

remove (*a_1*, *p_1*, ..., *a_n*, *p_n*) Function
remove ([*a_1*, ..., *a_m*], [*p_1*, ..., *p_n*], ...) Function
remove ("a", *operator*) Function
remove (*a*, *transfun*) Function
remove (*all*, *p*) Function

Removes properties associated with atoms.

`remove(a_1, p_1, ..., a_n, p_n)` removes property *p_k* from atom *a_k*.

`remove([a_1, ..., a_m], [p_1, ..., p_n], ...)` removes properties *p_1*, ..., *p_n* from atoms *a_1*, ..., *a_m*. There may be more than one pair of lists.

`remove(all, p)` removes the property *p* from all atoms which have it.

The removed properties may be system-defined properties such as `function`, `macro`, or `mode_declare`. `remove` does not remove properties defined by `put`.

A property may be `transfun` to remove the translated Lisp version of a function. After executing this, the Maxima version of the function is executed rather than the translated version.

`remove("a", operator)` or, equivalently, `remove("a", op)` removes from *a* the operator properties declared by `prefix`, `infix`, `nary`, `postfix`, `matchfix`, or `nofix`. Note that the name of the operator must be written as a quoted string.

`remove` always returns `done` whether or not an atom has a specified property. This behavior is unlike the more specific remove functions `remvalue`, `remarray`, `remfunction`, and `remrule`.

`remove` quotes its arguments.

scalar Property

`declare(a, scalar)` tells Maxima to consider *a* a scalar variable.

See also `declare`.

scalarp (*expr*) Function

Returns `true` if *expr* is a number, constant, or variable declared `scalar` with `declare`, or composed entirely of numbers, constants, and such variables, but not containing matrices or lists.

See also the predicate function `nonscalarp`.

11.3 Functions and Variables for Facts

activate (*context_1*, ..., *context_n*) Function
 Activates the contexts *context_1*, ..., *context_n*. The facts in these contexts are then available to make deductions and retrieve information. The facts in these contexts are not listed by **facts** ().

The variable **activecontexts** is the list of contexts which are active by way of the **activate** function.

activecontexts System variable
 Default value: []

activecontexts is a list of the contexts which are active by way of the **activate** function, as opposed to being active because they are subcontexts of the current context.

askinteger (*expr*, *integer*) Function
askinteger (*expr*) Function
askinteger (*expr*, *even*) Function
askinteger (*expr*, *odd*) Function

askinteger (*expr*, *integer*) attempts to determine from the **assume** database whether *expr* is an integer. **askinteger** prompts the user if it cannot tell otherwise, and attempt to install the information in the database if possible. **askinteger** (*expr*) is equivalent to **askinteger** (*expr*, *integer*).

askinteger (*expr*, *even*) and **askinteger** (*expr*, *odd*) likewise attempt to determine if *expr* is an even integer or odd integer, respectively.

asksign (*expr*) Function
 First attempts to determine whether the specified expression is positive, negative, or zero. If it cannot, it asks the user the necessary questions to complete its deduction. The user's answer is recorded in the data base for the duration of the current computation. The return value of **asksign** is one of **pos**, **neg**, or **zero**.

assume (*pred_1*, ..., *pred_n*) Function
 Adds predicates *pred_1*, ..., *pred_n* to the current context. If a predicate is inconsistent or redundant with the predicates in the current context, it is not added to the context. The context accumulates predicates from each call to **assume**.

assume returns a list whose elements are the predicates added to the context or the atoms **redundant** or **inconsistent** where applicable.

The predicates *pred_1*, ..., *pred_n* can only be expressions with the relational operators **<**, **<=**, **=**, **notequal**, **>=** and **>**. Predicates cannot be literal equality **=** or literal inequality **#** expressions, nor can they be predicate functions such as **integerp**.

Compound predicates of the form *pred_1* **and** ... **and** *pred_n* are recognized, but not *pred_1* **or** ... **or** *pred_n*. **not** *pred_k* is recognized if *pred_k* is a relational predicate. Expressions of the form **not** (*pred_1* **and** *pred_2*) and **not** (*pred_1* **or** *pred_2*) are not recognized.

Maxima's deduction mechanism is not very strong; there are many obvious consequences which cannot be determined by **is**. This is a known weakness.

assume does not handle predicates with complex numbers. If a predicate contains a complex number **assume** returns **inconsistent** or **redunant**.

assume evaluates its arguments.

See also **is**, **facts**, **forget**, **context**, and **declare**.

Examples:

```

(%i1) assume (xx > 0, yy < -1, zz >= 0);
(%o1)          [xx > 0, yy < - 1, zz >= 0]
(%i2) assume (aa < bb and bb < cc);
(%o2)          [bb > aa, cc > bb]
(%i3) facts ();
(%o3)          [xx > 0, - 1 > yy, zz >= 0, bb > aa, cc > bb]
(%i4) is (xx > yy);
(%o4)          true
(%i5) is (yy < -yy);
(%o5)          true
(%i6) is (sinh (bb - aa) > 0);
(%o6)          true
(%i7) forget (bb > aa);
(%o7)          [bb > aa]
(%i8) prederror : false;
(%o8)          false
(%i9) is (sinh (bb - aa) > 0);
(%o9)          unknown
(%i10) is (bb^2 < cc^2);
(%o10)         unknown

```

assumescalar

Option variable

Default value: **true**

assumescalar helps govern whether expressions **expr** for which **nonscalarp (expr)** is **false** are assumed to behave like scalars for certain transformations.

Let **expr** represent any expression other than a list or a matrix, and let **[1, 2, 3]** represent any list or matrix. Then **expr . [1, 2, 3]** yields **[expr, 2 expr, 3 expr]** if **assumescalar** is **true**, or **scalarp (expr)** is **true**, or **constantp (expr)** is **true**.

If **assumescalar** is **true**, such expressions will behave like scalars only for commutative operators, but not for noncommutative multiplication ..

When **assumescalar** is **false**, such expressions will behave like non-scalars.

When **assumescalar** is **all**, such expressions will behave like scalars for all the operators listed above.

assume_pos

Option variable

Default value: **false**

When **assume_pos** is **true** and the sign of a parameter **x** cannot be determined from the current context or other considerations, **sign** and **asksign (x)** return **true**. This may forestall some automatically-generated **asksign** queries, such as may arise from **integrate** or other computations.

By default, a parameter is **x** such that **symbolp (x)** or **subvarp (x)**. The class of expressions considered parameters can be modified to some extent via the variable **assume_pos_pred**.

sign and **asksign** attempt to deduce the sign of expressions from the sign of operands within the expression. For example, if **a** and **b** are both positive, then **a + b** is also positive.

However, there is no way to bypass all **asksign** queries. In particular, when the **asksign** argument is a difference **x - y** or a logarithm **log(x)**, **asksign** always requests an input from the user, even when **assume_pos** is **true** and **assume_pos_pred** is a function which returns **true** for all arguments.

assume_pos_pred

Option variable

Default value: **false**

When **assume_pos_pred** is assigned the name of a function or a lambda expression of one argument **x**, that function is called to determine whether **x** is considered a parameter for the purpose of **assume_pos**. **assume_pos_pred** is ignored when **assume_pos** is **false**.

The `assume_pos_pred` function is called by `sign` and `asksign` with an argument `x` which is either an atom, a subscripted variable, or a function call expression. If the `assume_pos_pred` function returns `true`, `x` is considered a parameter for the purpose of `assume_pos`.

By default, a parameter is `x` such that `symbolp (x)` or `subvarp (x)`.

See also `assume` and `assume_pos`.

Examples:

```
(%i1) assume_pos: true$
(%i2) assume_pos_pred: symbolp$
(%i3) sign (a);
(%o3)                                     pos
(%i4) sign (a[1]);
(%o4)                                     pnz
(%i5) assume_pos_pred: lambda ([x], display (x), true)$
(%i6) asksign (a);
                                     x = a

(%o6)                                     pos
(%i7) asksign (a[1]);
                                     x = a
                                     1

(%o7)                                     pos
(%i8) asksign (foo (a));
                                     x = foo(a)

(%o8)                                     pos
(%i9) asksign (foo (a) + bar (b));
                                     x = foo(a)

                                     x = bar(b)

(%o9)                                     pos
(%i10) asksign (log (a));
                                     x = a

Is a - 1 positive, negative, or zero?

p;
(%o10)                                     pos
(%i11) asksign (a - b);
                                     x = a

                                     x = b

                                     x = a

                                     x = b

Is b - a positive, negative, or zero?

p;
(%o11)                                     neg
```

context

Default value: `initial`

Option variable

context names the collection of facts maintained by **assume** and **forget**. **assume** adds facts to the collection named by **context**, while **forget** removes facts.

Binding **context** to a name *foo* changes the current context to *foo*. If the specified context *foo* does not yet exist, it is created automatically by a call to **newcontext**. The specified context is activated automatically.

See **contexts** for a general description of the context mechanism.

contexts

Option variable

Default value: **[initial, global]**

contexts is a list of the contexts which currently exist, including the currently active context.

The context mechanism makes it possible for a user to bind together and name a collection of facts, called a context. Once this is done, the user can have Maxima assume or forget large numbers of facts merely by activating or deactivating their context.

Any symbolic atom can be a context, and the facts contained in that context will be retained in storage until destroyed one by one by calling **forget** or destroyed as a whole by calling **kill** to destroy the context to which they belong.

Contexts exist in a hierarchy, with the root always being the context **global**, which contains information about Maxima that some functions need. When in a given context, all the facts in that context are "active" (meaning that they are used in deductions and retrievals) as are all the facts in any context which is a subcontext of the active context.

When a fresh Maxima is started up, the user is in a context called **initial**, which has **global** as a subcontext.

See also **facts**, **newcontext**, **supcontext**, **killcontext**, **activate**, **deactivate**, **assume**, and **forget**.

deactivate (*context_1*, ..., *context_n*)

Function

Deactivates the specified contexts *context_1*, ..., *context_n*.

facts (*item*)

Function

facts ()

Function

If *item* is the name of a context, **facts** (*item*) returns a list of the facts in the specified context.

If *item* is not the name of a context, **facts** (*item*) returns a list of the facts known about *item* in the current context. Facts that are active, but in a different context, are not listed.

facts () (i.e., without an argument) lists the current context.

forget (*pred_1*, ..., *pred_n*)

Function

forget (*L*)

Function

Removes predicates established by **assume**. The predicates may be expressions equivalent to (but not necessarily identical to) those previously assumed.

forget (*L*), where *L* is a list of predicates, forgets each item on the list.

is (*expr*)

Function

Attempts to determine whether the predicate *expr* is provable from the facts in the **assume** database.

If the predicate is provably **true** or **false**, **is** returns **true** or **false**, respectively. Otherwise, the return value is governed by the global flag **prederror**. When **prederror** is **true**, **is** complains with an error message. Otherwise, **is** returns **unknown**.

ev(*expr*, *pred*) (which can be written *expr*, *pred* at the interactive prompt) is equivalent to **is**(*expr*).

See also **assume**, **facts**, and **maybe**.

Examples:

is causes evaluation of predicates.

```
(%i1) %pi > %e;
(%o1)                                     %pi > %e
(%i2) is (%pi > %e);
(%o2)                                     true
```

`is` attempts to derive predicates from the `assume` database.

```
(%i1) assume (a > b);
(%o1)                                     [a > b]
(%i2) assume (b > c);
(%o2)                                     [b > c]
(%i3) is (a < b);
(%o3)                                     false
(%i4) is (a > c);
(%o4)                                     true
(%i5) is (equal (a, c));
(%o5)                                     false
```

If `is` can neither prove nor disprove a predicate from the `assume` database, the global flag `prederror` governs the behavior of `is`.

```
(%i1) assume (a > b);
(%o1)                                     [a > b]
(%i2) prederror: true$
(%i3) is (a > 0);
Maxima was unable to evaluate the predicate:
a > 0
-- an error. Quitting. To debug this try debugmode(true);
(%i4) prederror: false$
(%i5) is (a > 0);
(%o5)                                     unknown
```

killcontext (*context_1*, ..., *context_n*)

Function

Kills the contexts *context_1*, ..., *context_n*.

If one of the contexts is the current context, the new current context will become the first available subcontext of the current context which has not been killed. If the first available unkilled context is `global` then `initial` is used instead. If the `initial` context is killed, a new, empty `initial` context is created.

`killcontext` refuses to kill a context which is currently active, either because it is a subcontext of the current context, or by use of the function `activate`.

`killcontext` evaluates its arguments. `killcontext` returns `done`.

maybe (*expr*)

Function

Attempts to determine whether the predicate *expr* is provable from the facts in the `assume` database.

If the predicate is provably `true` or `false`, `maybe` returns `true` or `false`, respectively. Otherwise, `maybe` returns `unknown`.

`maybe` is functionally equivalent to `is` with `prederror: false`, but the result is computed without actually assigning a value to `prederror`.

See also `assume`, `facts`, and `is`.

Examples:

```
(%i1) maybe (x > 0);
(%o1)                                     unknown
(%i2) assume (x > 1);
(%o2)                                     [x > 1]
(%i3) maybe (x > 0);
(%o3)                                     true
```

newcontext (*name*) Function
 Creates a new, empty context, called *name*, which has **global** as its only subcontext. The newly-created context becomes the currently active context.
newcontext evaluates its argument. **newcontext** returns *name*.

sign (*expr*) Function
 Attempts to determine the sign of *expr* on the basis of the facts in the current data base. It returns one of the following answers: **pos** (positive), **neg** (negative), **zero**, **pz** (positive or zero), **nz** (negative or zero), **pn** (positive or negative), or **pnz** (positive, negative, or zero, i.e. nothing known).

supcontext (*name*, *context*) Function
supcontext (*name*) Function
 Creates a new context, called *name*, which has *context* as a subcontext. *context* must exist.
 If *context* is not specified, the current context is assumed.

11.4 Functions and Variables for Predicates

charfun (*p*) Function
 Return 0 when the predicate *p* evaluates to **false**; return 1 when the predicate evaluates to **true**. When the predicate evaluates to something other than **true** or **false** (unknown), return a noun form.
 Examples:

```
(%i1) charfun (x < 1);
(%o1) charfun(x < 1)
(%i2) subst (x = -1, %);
(%o2) 1
(%i3) e : charfun ('"and" (-1 < x, x < 1))$
(%i4) [subst (x = -1, e), subst (x = 0, e), subst (x = 1, e)];
(%o4) [0, 1, 0]
```

compare (*x*, *y*) Function
 Return a comparison operator *op* (<, <=, >, >=, =, or #) such that *is* (*x op y*) evaluates to **true**; when either *x* or *y* depends on %i and *x # y*, return **notcomparable**; when there is no such operator or Maxima isn't able to determine the operator, return **unknown**.
 Examples:

```
(%i1) compare (1, 2);
(%o1) <
(%i2) compare (1, x);
(%o2) unknown
(%i3) compare (%i, %i);
(%o3) =
(%i4) compare (%i, %i + 1);
(%o4) notcomparable
(%i5) compare (1/x, 0);
(%o5) #
(%i6) compare (x, abs(x));
(%o6) <=
```

The function **compare** doesn't try to determine whether the real domains of its arguments are nonempty; thus

```
(%i1) compare (acos (x^2 + 1), acos (x^2 + 1) + 1);
(%o1) <
```

The real domain of $\text{acos}(x^2 + 1)$ is empty.

equal (*a*, *b*)

Function

Represents equivalence, that is, equal value.

By itself, **equal** does not evaluate or simplify. The function **is** attempts to evaluate **equal** to a Boolean value. **is(equal(a, b))** returns **true** (or **false**) if and only if *a* and *b* are equal (or not equal) for all possible values of their variables, as determined by evaluating **ratsimp(a - b)**; if **ratsimp** returns 0, the two expressions are considered equivalent. Two expressions may be equivalent even if they are not syntactically equal (i.e., identical).

When **is** fails to reduce **equal** to **true** or **false**, the result is governed by the global flag **prederror**. When **prederror** is **true**, **is** complains with an error message. Otherwise, **is** returns **unknown**.

In addition to **is**, some other operators evaluate **equal** and **notequal** to **true** or **false**, namely **if**, **and**, **or**, and **not**.

The negation of **equal** is **notequal**.

Examples:

By itself, **equal** does not evaluate or simplify.

```
(%i1) equal (x^2 - 1, (x + 1) * (x - 1));
                                2
(%o1)          equal(x  - 1, (x - 1) (x + 1))
(%i2) equal (x, x + 1);
(%o2)          equal(x, x + 1)
(%i3) equal (x, y);
(%o3)          equal(x, y)
```

The function **is** attempts to evaluate **equal** to a Boolean value. **is(equal(a, b))** returns **true** when **ratsimp(a - b)** returns 0. Two expressions may be equivalent even if they are not syntactically equal (i.e., identical).

```
(%i1) ratsimp (x^2 - 1 - (x + 1) * (x - 1));
(%o1)          0
(%i2) is (equal (x^2 - 1, (x + 1) * (x - 1)));
(%o2)          true
(%i3) is (x^2 - 1 = (x + 1) * (x - 1));
(%o3)          false
(%i4) ratsimp (x - (x + 1));
(%o4)          - 1
(%i5) is (equal (x, x + 1));
(%o5)          false
(%i6) is (x = x + 1);
(%o6)          false
(%i7) ratsimp (x - y);
(%o7)          x - y
(%i8) is (equal (x, y));
(%o8)          unknown
(%i9) is (x = y);
(%o9)          false
```

When **is** fails to reduce **equal** to **true** or **false**, the result is governed by the global flag **prederror**.

```
(%i1) [aa : x^2 + 2*x + 1, bb : x^2 - 2*x - 1];
                                2          2
(%o1)          [x  + 2 x + 1, x  - 2 x - 1]
(%i2) ratsimp (aa - bb);
(%o2)          4 x + 2
(%i3) prederror : true;
(%o3)          true
(%i4) is (equal (aa, bb));
Maxima was unable to evaluate the predicate:
```

```

      2      2
equal(x  + 2 x + 1, x  - 2 x - 1)
-- an error. Quitting. To debug this try debugmode(true);
(%i5) prederror : false;
(%o5)
false
(%i6) is (equal (aa, bb));
(%o6)
unknown

```

Some operators evaluate `equal` and `notequal` to `true` or `false`.

```

(%i1) if equal (y, y - 1) then FOO else BAR;
(%o1)
BAR
(%i2) eq_1 : equal (x, x + 1);
(%o2)
equal(x, x + 1)
(%i3) eq_2 : equal (y^2 + 2*y + 1, (y + 1)^2);
(%o3)
equal(y  + 2 y + 1, (y + 1) )
(%i4) [eq_1 and eq_2, eq_1 or eq_2, not eq_1];
(%o4)
[false, true, true]

```

Because `not expr` causes evaluation of `expr`, `not equal(a, b)` is equivalent to `is(notequal(a, b))`.

```

(%i1) [notequal (2*z, 2*z - 1), not equal (2*z, 2*z - 1)];
(%o1)
[notequal(2 z, 2 z - 1), true]
(%i2) is (notequal (2*z, 2*z - 1));
(%o2)
true

```

notequal (*a*, *b*)

Function

Represents the negation of `equal(a, b)`.

Examples:

```

(%i1) equal (a, b);
(%o1)
equal(a, b)
(%i2) maybe (equal (a, b));
(%o2)
unknown
(%i3) notequal (a, b);
(%o3)
notequal(a, b)
(%i4) not equal (a, b);
(%o4)
notequal(a, b)
(%i5) maybe (notequal (a, b));
(%o5)
unknown
(%i6) assume (a > b);
(%o6)
[a > b]
(%i7) equal (a, b);
(%o7)
equal(a, b)
(%i8) maybe (equal (a, b));
(%o8)
false
(%i9) notequal (a, b);
(%o9)
notequal(a, b)
(%i10) maybe (notequal (a, b));
(%o10)
true

```

unknown (*expr*)

Function

Returns `true` if and only if `expr` contains an operator or function not recognized by the Maxima simplifier.

zeroequiv (*expr*, *v*)

Function

Tests whether the expression `expr` in the variable `v` is equivalent to zero, returning `true`, `false`, or `dontknow`.

`zeroequiv` has these restrictions:

1. Do not use functions that Maxima does not know how to differentiate and evaluate.
2. If the expression has poles on the real line, there may be errors in the result (but this is unlikely to occur).
3. If the expression contains functions which are not solutions to first order differential equations (e.g. Bessel functions) there may be incorrect results.
4. The algorithm uses evaluation at randomly chosen points for carefully selected subexpressions. This is always a somewhat hazardous business, although the algorithm tries to minimize the potential for error.

For example `zeroequiv (sin(2 * x) - 2 * sin(x) * cos(x), x)` returns `true` and `zeroequiv (%e^x + x, x)` returns `false`. On the other hand `zeroequiv (log(a * b) - log(a) - log(b), a)` returns `dontknow` because of the presence of an extra parameter `b`.

12 Plotting

12.1 Introduction to Plotting

Maxima uses an external plotting package to make the plots (see the section on Plotting formats). The plotting functions calculate a set of points and pass them to the plotting package together with a set of commands. That information can be passed to the external program either through a pipe or by calling the program with the name of a file where the data has been saved. The data file is given the name `maxout.interface`, where `interface` is the name of the plotting interface being used (gnuplot, xmaxima, mgnuplot or gnuplot_pipes).

The `maxout.interface` file, in the cases when it is used, is created in the directory specified by the system variable `maxima_tempdir`. That location can be changed; by assigning to that variable a string that represents a valid directory where Maxima can create new files.

After a plot has been created, the file `maxout.interface` can be executed again with the appropriate external program. If a Maxima plotting command fails to show anything, that file can be inspected to look for possible sources of problems.

Together with the plotting functions described in this chapter, package [Chapter 48 \[draw\]](#), [page 575](#) adds other functionalities. Note that some plotting options are named equal in both plotting contexts, but with different syntax; if you want to access the draw information related to these options, you have to type `?? opt`, where `opt` is the name of the option.

12.2 Plotting Formats

There are currently two external plotting programs that Maxima use: Gnuplot and Xmaxima. There are various different formats for those programs, which can be selected with the option `plot_format` (see the Plotting Options section).

The plotting formats are the following:

- **gnuplot** (default on Windows)

Used to launch the external program gnuplot, which must be installed in your system. All plotting commands and data are saved into the file `maxout.gnuplot`.
- **gnuplot_pipes** (default on non-Windows platforms)

This format is not available in Windows platforms. It is similar to the `gnuplot` format except that the commands are sent to gnuplot through a pipe, while the data are saved into the file `maxout.gnuplot_pipes`. A single gnuplot process is kept open and subsequent plot commands will be sent to the same process, replacing previous plots, unless the gnuplot pipe is closed with the function `gnuplot_close`. When this format is used, the function `gnuplot_replot` can be used to modify a plot that has already displayed on the screen. This format should only be used to plot to the screen; for plotting to files it is better to use the `gnuplot` format.
- **mgnuplot**

Mgnuplot is a Tk-based wrapper around gnuplot. It is included in the Maxima distribution. Mgnuplot offers a rudimentary GUI for gnuplot, but has fewer overall features than the plain gnuplot interface. Mgnuplot requires an external gnuplot installation and, in Unix systems, the Tcl/Tk system.
- **xmaxima**

Xmaxima is a Tcl/Tk graphical interface for Maxima that can also be used to display plots created when Maxima is run from the console or from other graphical interfaces. To use this format, the xmaxima program, which is distributed together with Maxima, should be installed. If Maxima is being run from xmaxima itself, this format will make the plot functions send the data and commands through the same socket used for the communication between Maxima and Xmaxima. When used from the console or from other interface, the commands and data will be saved in the file `maxout.xmaxima`, and the xmaxima program will be launched with the name of the location of that file as argument. In previous versions this format used to be called `openmath`; that old name will still be accepted as a synonym for `xmaxima`.

12.3 Functions and Variables for Plotting

contour_plot (*expr*, *x_range*, *y_range*, *options*, ...)


Function

It plots the contours (curves of equal value) of *expr* over the region *x_range* by *y_range*. Any additional arguments are treated the same as in `plot3d`.

This function only works when the plot format is either `gnuplot` or `gnuplot_pipes`. The additional package `implicit_plot` can also be used to plot contours and it works for any format. See `implicit_plot`.

Examples:


```
(%i1) contour_plot (x^2 + y^2, [x, -4, 4], [y, -4, 4])$
```



```
(%i1) F(x, y) := x^3 + y^2;
```


```
(%o1) F(x, y) := x^3 + y^2
```

```
(%i2) contour_plot (F, [u, -4, 4], [v, -4, 4])$
```



You can add any options accepted by `plot3d`; for instance, the option `legend` with a value of `false`, to remove the legend. Gnuplot chooses, by default, 3 contours to show. To increase the number of levels, it is necessary to specify a custom gnuplot preamble:

```
(%i1) contour_plot (u^3 + v^2, [u, -4, 4], [v, -4, 4],
                    [legend,false],
                    [gnuplot_preamble, "set cntrparam levels 12"])$
```



get_plot_option (*keyword*, *index*)

Function

Returns a value of the option with name *keyword*, stored in the global variable `plot_options`. A value of 1 for the index will return the keyword itself; a value of 2 turn returns the first parameter following the keyword, and so on.

See also `plot_options`, `set_plot_option` and the section on Plotting Options.

implicit_plot (*expr*, *x_range*, *y_range*)

Function

implicit_plot ([*expr_1*, ..., *expr_n*], *x_range*, *y_range*)

Function


Displays a plot of one or more expressions in implicit form. *expr* is the expression to be plotted, *x_range* the range of the horizontal axis and *y_range* the range of vertical axis. `implicit_plot` respects global setting for the Gnuplot driver set by the `set_plot_option` function. Options can also be passed to `implicit_plot` function as optional arguments.

`implicit_plot` works by tracking sign changes on the area given by *x_range* and *y_range* and can fail for complicated expressions.

`load(implicit_plot)` loads this function.

Example:

```
(%i1) implicit_plot (x^2 = y^3 - 3*y + 1, [x, -4, 4], [y, -4, 4],
                    [gnuplot_preamble, "set zeroaxis"]);
```



make_transform ([*var1*, *var2*, *var3*], *fx*, *fy*, *fz*) Function

Returns a function suitable to be used in the option **transform_xy** of **plot3d**. The three variables *var1*, *var2*, *var3* are three dummy variable names, which represent the 3 variables given by the **plot3d** command (first the two independent variables and then the function that depends on those two variables). The three functions *fx*, *fy*, *fz* must depend only on those 3 variables, and will give the corresponding x, y and z coordinates that should be plotted. There are two transformations defined by default: **polar_to_xy** and **spherical_to_xyz**. See the documentation for those two transformations.

polar_to_xy System function

It can be given as value for the **transform_xy** option of **plot3d**. Its effect will be to interpret the two independent variables in **plot3d** as the distance from the z axis and the azimuthal angle (polar coordinates), and transform them into x and y coordinates.

plot2d (*plot*, *x_range*, ..., *options*, ...) Function

plot2d ([*plot_1*, ..., *plot_n*], ..., *options*, ...) Function

plot2d ([*plot_1*, ..., *plot_n*], *x_range*, ..., *options*, ...) Function

Where *plot*, *plot_1*, ..., *plot_n* can be either expressions, function names or a list with the any of the forms: [**discrete**, [*x1*, ..., *xn*], [*y1*, ..., *yn*]], [**discrete**, [[*x1*, *y1*], ..., [*xn*, ..., *yn*]]] or [**parametric**, *x_expr*, *y_expr*, *t_range*].

Displays a plot of one or more expressions as a function of one variable or parameter.

plot2d displays one or several plots in two dimensions. When expressions or function name are used to define the plots, they should all depend on only one variable *var* and the use of *x_range* will be mandatory, to provide the name of the variable and its minimum and maximum values; the syntax for *x_range* is: [*variable*, *min*, *max*].

A plot can also be defined in the discrete or parametric forms. The discrete form is used to plot a set of points with given coordinates. A discrete plot is defined by a list starting with the keyword *discrete*, followed by one or two lists of values. If two lists are given, they must have the same length; the first list will be interpreted as the x coordinates of the points to be plotted and the second list as the y coordinates. If only one list is given after the *discrete* keyword, each element on the list should also be a list with two values that correspond to the x and y coordinates of a point.

A parametric plot is defined by a list starting with the keyword *parametric*, followed by two expressions or function names and a range for the parameter. The range for the parameter must be a list with the name of the parameter followed by its minimum and maximum values: [*param*, *min*, *max*]. The plot will show the path traced out by the point with coordinates given by the two expressions or functions, as *param* increases from *min* to *max*.

A range for the vertical axis is an optional argument with the form: [*y*, *min*, *max*] (the keyword *y* is always used for the vertical axis). If that option is used, the plot will show that exact vertical range, independently of the values reached by the plot. If the vertical range is not specified, it will be set up according to the minimum and maximum values of the second coordinate of the plot points.


All other options should also be lists, starting with a keyword and followed by one or more values. See **plot_options**.

If there are several plots to be plotted, a legend will be written to identity each of the expressions. The labels that should be used in that legend can be given with the option **legend**. If that option is not used, Maxima will create labels from the expressions or function names.

Examples:


Plot of a common function:


```
(%i1) plot2d (sin(x), [x, -%pi, %pi])$
```




If the functions grows too fast, it might be necessary to limit the values in the vertical axis using the `y` option:

```
(%i1) plot2d (sec(x), [x, -2, 2], [y, -20, 20])$
plot2d: some values were clipped.
```




The aspect of the plot might be different depending on the plotting program used. For instance, when the plot box is disabled, Xmaxima will plot the axes using arrows:

```
(%i1) plot2d ( x^2-1, [x, -3, 3], [y, -2, 10],
               [box, false], [plot_format, xmaxima])$
```



A plot with a logarithmic scale:


```
(%i1) plot2d (exp(3*s), [s, -2, 2], [logy])$
```



Plotting functions by name:


```
(%i1) F(x) := x^2 $
(%i2) :lisp (defun |$g| (x) (m* x x x))
$g
(%i2) H(x) := if x < 0 then x^4 - 1 else 1 - x^5 $
```

```
(%i3) plot2d ([F, G, H], [u, -1, 1], [y, -1.5, 1.5])$
```




A plot of the butterfly curve, defined parametrically:

```
(%i1) r: (exp(cos(t))-2*cos(4*t)-sin(t/12)^5)$
(%i2) plot2d([parametric, r*sin(t), r*cos(t),
[t, -8*%pi, 8*%pi], [nticks, 2000]])$
```




A “circle” with two turns, when plotted with only 7 points:

```
(%i1) plot2d ([parametric, cos(t), sin(t),
[t, -2*%pi, 2*%pi], [nticks, 8]])$
```




Plot of a common function together with the parametric representation of a circle. The size of the plot has been adjusted with the x and y options, to make the circle look round and not deformed as an ellipse. These values work well for the Postscript terminal used to produce this plot; you might have to adjust the values for your screen.

```
(%i1) plot2d([[parametric, cos(t), sin(t),
               [t,0,2*%pi], [nticks, 80]],
               abs(x)], [x,-2,2], [y, -1.5, 1.5])$
plot2d: some values were clipped.
```




A plot of a discrete set of points, defining x and y coordinates separately:

```
(%i1) plot2d ([discrete, [10, 20, 30, 40, 50],
                [.6, .9, 1.1, 1.3, 1.4]])$
```




The same points shown in the previous example, defining each point separately and without any lines joining the points:

```
(%i1) plot2d([discrete, [[10, .6], [20, .9], [30, 1.1],
                          [40, 1.3], [50, 1.4]]],
              [style, points])$
```




In this example, a table with three columns is saved in a file “data.txt” which is then read and the second and third column are plotted on the two axes:

```
(%i1) with_stdout ("data.txt", for x:0 thru 10 do
                                print (x, x^2, x^3))$
(%i2) data: read_matrix ("data.txt")$
(%i3) plot2d ([discrete, transpose(data)[2], transpose(data)[3]],
               [style,points], [point_type,diamond], [color,red])$
```



A plot of experimental data points together with the theoretical function that predicts the data:

```
(%i1) xy: [[10, .6], [20, .9], [30, 1.1], [40, 1.3], [50, 1.4]]$
(%i2) plot2d([[discrete, xy], 2*%pi*sqrt(1/980)], [1,0,50],
               [style, points, lines], [color, red, blue],
               [point_type, asterisk],
               [legend, "experiment", "theory"],
               [xlabel, "pendulum's length (cm)"],
               [ylabel, "period (s)"])$
```



See also the section about Plotting Options.

plot3d (*expr*, *x-range*, *y-range*, ..., *options*, ...) Function
plot3d (*[expr-1, ..., expr-n]*, *x-range*, *y-range*, ..., *options*, ...) Function


Displays a plot of one or more surfaces defined as functions of two variables or in parametric form.

The functions to be plotted may be specified as expressions or function names. The mouse can be used to rotate the plot looking at the surface from different sides.

Examples:


Plot of a common function:

```
(%i1) plot3d (2^(-u^2 + v^2), [u, -3, 3], [v, -2, 2])$
```




Use of the z option to limit a function that goes to infinity (in this case the function is minus infinity on the x and y axes); this also shows how to plot with only lines and no shading:

```
(%i1) plot3d ( log ( x^2*y^2 ), [x, -2, 2], [y, -2, 2], [z, -8, 4],
               [palette, false], [color, magenta, blue])$
```




The infinite values of z can also be avoided by choosing a grid that does not fall on any asymptotes; this example also shows how to select one of the predefined palettes, in this case the fourth one:

```
(%i1) plot3d (log (x^2*y^2), [x, -2, 2], [y, -2, 2],
               [grid, 29, 29],
               [palette, get_plot_option(palette,5)])$
```




Two surfaces in the same plot, sharing the same domain; in gnuplot the two surfaces will use the same palette:

```
(%i1) plot3d ([2^(-x^2 + y^2), 4*sin(3*(x^2+y^2))/(x^2+y^2),
               [x, -3, 3], [y, -2, 2]])$
```



The same two surfaces, but now with different domains; in xmaxima each surface will use a different palette, chosen from the list defined by the option palette:


```
(%i1) plot3d ([[2^(-x^2 + y^2), [x, -2, 2], [y, -2, 2]],
               4*sin(3*(x^2+y^2))/(x^2+y^2),
               [x, -3, 3], [y, -2, 2]], [plot_format, xmaxima])$
```



Plot of a Klein bottle, defined parametrically:


```
(%i1) expr_1:5*cos(x)*(cos(x/2)*cos(y)+sin(x/2)*sin(2*y)+3.0)-10.0$
(%i2) expr_2:-5*sin(x)*(cos(x/2)*cos(y) + sin(x/2)*sin(2*y) + 3.0)$
(%i3) expr_3: 5*(-sin(x/2)*cos(y) + cos(x/2)*sin(2*y))$
```

```
(%i4) plot3d ([expr_1, expr_2, expr_3], [x, -%pi, %pi],
             [y, -%pi, %pi], [grid, 40, 40])$
```




Plot of a spherical harmonic, using of the predefined transformations, `spherical_to_xyz`, to transform from spherical to rectangular coordinates. See the documentation for `spherical_to_xyz`.

```
(%i1) plot3d (sin(2*theta)*cos(phi), [theta, 0, %pi],
             [phi, 0, 2*%pi],
             [transform_xy, spherical_to_xyz], [grid,30,60])$
```




Use of the predefined function `polar_to_xy` to transform from cylindrical to rectangular coordinates. See the documentation for `polar_to_xy`. This example also shows how to eliminate the bounding box and the legend.


```
(%i1) plot3d (r^.33*cos(th/3), [r, 0, 1], [th, 0, 6*%pi],
             [grid, 12, 80],
             [transform_xy, polar_to_xy], [box, false],
             [legend,false])$
```



Plot of a sphere using the transformation from spherical to rectangular coordinates. In xmaxima the three axes are scaled in the same proportion, maintaining the symmetric shape of the sphere. A palette with different shades of a single color is used:


```
(%i1) plot3d ( 5, [theta, 0, %pi], [phi, 0, 2*%pi],
             [plot_format,xmaxima],
             [transform_xy, spherical_to_xyz],
             [palette,[value,0.65,0.7,0.1,0.9]])$
```



Definition of a function of two-variables using a matrix. Notice the single quote in the definition of the function, to prevent plot3d from failing when it realizes that the matrix will require integer indices.


```
(%i1) M: matrix([1, 2, 3, 4], [1, 2, 3, 2], [1, 2, 3, 4],
                [1, 2, 3, 3])$
(%i2) f(x, y) := float('M [round(x), round(y)])$
```

```
(%i3) plot3d (f(x,y), [x, 1, 4], [y, 1, 4], [grid, 4, 4])$
apply: subscript must be an integer; found: round(x)
```



By setting the elevation equal to zero, a surface can be seen as a map in which each color represents a different level. The option `colorbox` is used to show the correspondence among colors and levels, and the mesh lines are disabled to make the colors easier to see.

```
(%i1) plot3d (cos (-x^2 + y^3/4), [x, -4, 4], [y, -4, 4],
  [mesh_lines_color, false], [elevation, 0], [azimuth, 0],
  [colorbox, true], [grid, 150, 150])$
```



See also the section about Plotting Options.

plot_options

System variable

Elements of this list state the default options for plotting. If an option is present in a `plot2d` or `plot3d` call, that value takes precedence over the default option. Otherwise, the value in `plot_options` is used. Default options are assigned by `set_plot_option`. There are other local options specific to each plotting command, and not included in this list of global options.

Each element of `plot_options` is a list of two or more items. The first item is the name of the option, and the remainder comprises the value or values assigned to the option. In some cases, the assigned value is a list, which may include several items.

See also `set_plot_option`, `get_plot_option` and the section on Plotting Options.

set_plot_option (option)

Function

Accepts most of the options listed in the section Plotting Options, and saves them into the global variable `plot_options`.

`set_plot_option` evaluates its argument and returns the complete list `plot_options` (after modifying the option given).

See also `plot_options`, `get_plot_option` and the section on Plotting Options.

Example:

Modification of the `grid` values.

```
(%i1) set_plot_option ([grid, 30, 40]);
(%o1) [[t, - 3, 3], [grid, 30, 40], [transform_xy, false],
[run_viewer, true], [axes, true], [plot_format, gnuplot_pipes],
[color, blue, red, green, magenta, black, cyan],
[point_type, bullet, circle, plus, times, asterisk, box, square,
triangle, delta, wedge, nabla, diamond, lozenge],
[palette, [hue, 0.25, 0.7, 0.8, 0.5],
[hue, 0.65, 0.8, 0.9, 0.55], [hue, 0.55, 0.8, 0.9, 0.4],
[hue, 0.95, 0.7, 0.8, 0.5]], [gnuplot_term, default],
[gnuplot_out_file, false], [nticks, 29], [adapt_depth, 5],
[gnuplot_preamble, ], [gnuplot_default_term_command,
set term pop], [gnuplot_dumb_term_command, set term dumb 79 22],
[gnuplot_ps_term_command, set size 1.5, 1.5;set term postscript \
eps enhanced color solid 24], [plot_realpart, false]]
```

spherical_to_xyz

System function

It can be given as value for the `transform_xy` option of `plot3d`. Its effect will be to interpret the two independent variables and the function in `plot3d` as the spherical coordinates of a point (first, the angle with the z axis, then the angle of the xy projection with the x axis and finally the distance from the origin) and transform them into x, y and z coordinates.

12.4 Plotting Options

All options consist of a list starting with one of the keywords in this section, followed by one or more values. Most of the options can be used in any of the plotting commands (`plot2d`, `plot3d`, `contour_plot`, `implicit_plot`) or in the function `set_plot_option`. The exceptions will be specified in the following list.

adapt_depth [adapt_depth, *integer*]

Plot option

Default value: 5

The maximum number of splittings used by the adaptive plotting routine.

axes [axes, *symbol*]

Plot option

Default value: `true`

Where *symbol* can be either `true`, `false`, `x` or `y`. If `false`, no axes will be shown; if equal to `x` or `y` only the x or y axis will be shown, and if it is equal to `true`, both axes will be shown. This option is used only by `plot2d` and `implicit_plot`.

azimuth [azimuth, *number*]

Plot option

Default value: 30

A `plot3d` plot can be thought of as starting with its x and y axis in the horizontal and vertical axis, as in `plot2d`, and the z axis coming out of the paper perpendicularly. The z axis is then rotated around the x axis an angle equals to `elevation` and then the xy plane is rotated around the new z axis an angle `azimuth`. This option sets the value for the azimuth, in degrees.

See also `elevation`.

- box** [box, *symbol*] Plot option
 Default value: **true**
 If set to **true**, a bounding box will be drawn for the plot; if set to **false**, no box will be drawn.
- color** [color, *color_1*, ..., *color_n*] Plot option
 Default value: **blue, red, green, magenta, black, cyan**
 In **plot2d** and **implicit_plot**, it defines the color (or colors) for the various curves. In **plot3d**, it defines the colors used for the mesh lines of the surfaces, when no palette is being used; one side of the surface will have color *color_1* and the other *color_2* (or the same color if there is only one color).
 If there are more curves or surfaces than colors, the colors will be repeated in sequence. When using gnuplot, the colors could be: **blue, red, green, magenta, black**, or **cyan**; in xmaxima the colors can be those or a string starting with the character # and followed by six hexadecimal digits: two for the red component, two for green component and two for the blue component. If given the name of an unknown color, black will be used instead.
- colorbox** [colorbox, *symbol*] Plot option
 Default value: **false**
 Where *symbol* can be either **true** or **false**. If **true**, whenever **plot3d** uses a palette of different colors to represent the different values of *z*, a box will be shown on the right, indicating the colors used according to the scale of values of *z*. This option does not work in xmaxima.
- elevation** [elevation, *number*] Plot option
 Default value: **60**
 A **plot3d** plot can be thought of as starting with its *x* and *y* axis in the horizontal and vertical axis, as in **plot2d**, and the *z* axis coming out of the paper perpendicularly. The *z* axis is then rotated around the *x* axis an angle equals to **elevation** and then the *xy* plane is rotated around the new *z* axis an angle **azimuth**. This option sets the value for the elevation, in degrees.
 See also **azimuth**.
- grid** [grid, *integer*, *integer*] Plot option
 Default value: **30, 30**
 Sets the number of grid points to use in the *x*- and *y*-directions for three-dimensional plotting.
- legend** [legend, *string_1*, ..., *string_n*] Plot option
legend [legend, *false*] Plot option
 It specifies the labels for the plots when various plots are shown. If there are more plots than the number of labels given, they will be repeated. If given the value **false**, no legends will be shown. By default, the names of the expressions or functions will be used, or the words **discrete1**, **discrete2**, ..., for discrete sets of points. This option can not be set with **set_plot_option**.
- logx** [logx] Plot option
 Makes the horizontal axes to be scaled logarithmically. It can not be used with **set_plot_option**.
- logy** [logy] Plot option
 Makes the vertical axes to be scaled logarithmically. It can not be used with **set_plot_option**.

mesh_lines_color [mesh_lines_color, *color*] Plot option
 Default value: **black**

It sets the color used by `plot3d` to draw the mesh lines, when a palette is being used. It accepts the same colors as for the option `color` (see the list of allowed colors in `color`). It can also be given a value **false** to eliminate completely the mesh lines.

nticks [nticks, *integer*] Plot option
 Default value: 29

When plotting functions with `plot2d`, it gives the initial number of points used by the adaptive plotting routine for plotting functions. When plotting parametric functions with `plot2d` or `plot3d`, it sets the number of points that will be shown for the plot.

palette [palette, [*palette_1*], ..., [*palette_n*]] Plot option
palette [palette, *false*] Plot option

Default value: [hue, 0.25, 0.7, 0.8, 0.5], [hue, 0.65, 0.8, 0.9, 0.55], [hue, 0.55, 0.8, 0.9, 0.4], [hue, 0.95, 0.7, 0.8, 0.5]

It can consist of one palette or a list of several palettes. Each palette is a list with a keyword followed by four numbers. The first three numbers, which must be between 0 and 1, define the hue, saturation and value of a basic color to be assigned to the minimum value of *z*. The keyword specifies which of the three attributes (hue, saturation or value) will be increased according to the values of *z*. The last number indicates the increase corresponding to the maximum value of *z*. That last number can be bigger than 1 or negative; the corresponding values of the modified attribute will be rounded modulo 1.

Gnuplot only uses the first palette in the list; `xmaxima` will use the palettes in the list sequentially, when several surfaces are plotted together; if the number of palettes is exhausted, they will be repeated sequentially.

The color of the mesh lines will be given by the option `mesh_lines_color`. If `palette` is given the value **false**, the surfaces will not be shaded but represented with a mesh of curves only. In that case, the colors of the lines will be determined by the option `color`.

plot_format [plot_format, *format*] Plot option
 Default value: **gnuplot**, in Windows systems, or **gnuplot_pipes** in other systems.

Where *format* is one of the following: `gnuplot`, `xmaxima`, `mgnuplot` or `gnuplot-pipes`.

It sets the format to be used for plotting.

plot_realpart [plot_realpart, *symbol*] Plot option
 Default value: **false**

If set to **true**, the functions to be plotted will be considered as complex functions whose real value should be plotted; this is equivalent to plotting `realpart(function)`. If set to **false**, nothing will be plotted when the function does not give a real value. For instance, when *x* is negative, `log(x)` gives a complex value, with real value equal to `log(abs(x))`; if `plot_realpart` were **true**, `log(-5)` would be plotted as `log(5)`, while nothing would be plotted if `plot_realpart` were **false**.

point_type [point_type, *type_1*, ..., *type_n*] Plot option
 Default value: **bullet**, **circle**, **plus**, **times**, **asterisk**, **box**, **square**, **triangle**, **delta**, **wedge**, **nabla**, **diamond**, **lozenge**

In `gnuplot`, each set of points to be plotted with the style “points” or “linespoints” will be represented with objects taken from this list, in sequential order. If there are more sets of points than objects in this list, they will be repeated sequentially. The possible objects that can be used are: **bullet**, **circle**, **plus**, **times**, **asterisk**, **box**, **square**, **triangle**, **delta**, **wedge**, **nabla**, **diamond**, **lozenge**

- psfile** [psfile, *string*] Plot option
 Saves the plot into a Postscript file with name equal to *string*, rather than showing it in the screen. By default, the file will be created in the directory defined by the variable `maxima_tempdir`. The value of that variable can be changed to save the file in a different directory.
- run_viewer** [run_viewer, *symbol*] Plot option
 Default value: `true`
 Controls whether or not the appropriate viewer for the plot format should be run.
- style** [style, *type_1*, ..., *type_1_n*] Plot option
style [style, [*style_1*], ..., [*style_n*]] Plot option
 Default value: `lines` (will plot all sets of points joined with lines of thickness 1 and the first color given by the option `color`).
 The styles that will be used for the various functions or sets of data in a 2d plot. The word *style* must be followed by one or more styles. If there are more functions and data sets than the styles given, the styles will be repeated. Each style can be either *lines* for line segments, *points* for isolated points, *linespoints* for segments and points, or *dots* for small isolated dots. Gnuplot accepts also an *impulses* style.
 Each of the styles can be enclosed inside a list with some additional parameters. *lines* accepts one or two numbers: the width of the line and an integer that identifies a color. The default color codes are: 1: blue, 2: red, 3: magenta, 4: orange, 5: brown, 6: lime and 7: aqua. If you use Gnuplot with a terminal different than X11, those colors might be different; for example, if you use the option [*gnuplot_term*, *ps*], color index 4 will correspond to black, instead of orange.
points accepts one two or three parameters; the first parameter is the radius of the points, the second parameter is an integer that selects the color, using the same code used for *lines* and the third parameter is currently used only by Gnuplot and it corresponds to several objects instead of points. The default types of objects are: 1: filled circles, 2: open circles, 3: plus signs, 4: x, 5: *, 6: filled squares, 7: open squares, 8: filled triangles, 9: open triangles, 10: filled inverted triangles, 11: open inverted triangles, 12: filled lozenges and 13: open lozenges.
linesdots accepts up to four parameters: line width, points radius, color and type of object to replace the points.
 See also `color` and `point_type`.
- t** [t, *min*, *max*] Plot option
 Default value: `-3, 3`
 Default range for parametric plots.
- transform_xy** [transform_xy, *symbol*] Plot option
 Default value: `false`
 Where *symbol* is either `false` or the result obtained by using the function `transform_xy`. If different from `false`, it will be used to transform the 3 coordinates in plot3d.
 See `make_transform`, `polar_to_xy` and `spherical_to_xyz`.
- x** [x, *min*, *max*] Plot option
 When used as the first option in a `plot2d` command (or any of the first two in `plot3d`), it indicates that the first independent variable is x and it sets its range. It can also be used again after the first option (or after the second option in `plot3d`) to define the effective horizontal domain that will be shown in the plot.

- xlabel** [xlabel, *string*] Plot option
 Specifies the *string* that will label the first axis; if this option is not used, that label will be the name of the independent variable, when plotting functions with `plot2d` or `implicit_plot`, or the name of the first variable, when plotting surfaces with `plot3d` or contours with `contour_plot`, or the first expression in the case of a parametric plot. It can not be used with `set_plot_option`.
- y** [y, *min*, *max*] Plot option
 When used as one of the first two options in `plot3d`, it indicates that one of the independent variables is y and it sets its range. Otherwise, it defines the effective domain of the second variable that will be shown in the plot.
- ylabel** [ylabel, *string*] Plot option
 Specifies the *string* that will label the second axis; if this option is not used, that label will be “y”, when plotting functions with `plot2d` or `implicit_plot`, or the name of the second variable, when plotting surfaces with `plot3d` or contours with `contour_plot`, or the second expression in the case of a parametric plot. It can not be used with `set_plot_option`.
- z** [z, *min*, *max*] Plot option
 Used in `plot3d` to set the effective range of values of z that will be shown in the plot.
- zlabel** [zlabel, *string*] Plot option
 Specifies the *string* that will label the third axis, when using `plot3d`. If this option is not used, that label will be “z”, when plotting surfaces, or the third expression in the case of a parametric plot. It can not be used with `set_plot_option` and it will be ignored by `plot2d` and `implicit_plot`.

12.5 Gnuplot Options

There are several plot options specific to gnuplot. All of them consist of a keyword (the name of the option), followed by a string that should be a valid gnuplot command, to be passed directly to gnuplot. In most cases, there exist a corresponding plotting option that will produce a similar result and whose use is more recommended than the gnuplot specific option.

- gnuplot_term** Plot option
 Sets the output terminal type for gnuplot.
- **default** (default value)
 Gnuplot output is displayed in a separate graphical window.
 - **dumb**
 Gnuplot output is displayed in the Maxima console by an "ASCII art" approximation to graphics.
 - **ps**
 Gnuplot generates commands in the PostScript page description language. If the option `gnuplot_out_file` is set to *filename*, gnuplot writes the PostScript commands to *filename*. Otherwise, it is saved as `maxplot.ps` file.
 - any other valid gnuplot term specification
 Gnuplot can generate output in many other graphical formats such as png, jpeg, svg etc. To create plot in all these formats the `gnuplot_term` can be set to any supported gnuplot term name (symbol) or even full gnuplot term specification with any valid options (string). For example `[gnuplot_term, png]` creates output in PNG (Portable Network Graphics) format while `[gnuplot_term, "png size 1000,1000"]` creates PNG of 1000 x 1000 pixels size. If the option `gnuplot_out_file` is set to *filename*, gnuplot writes the output to *filename*. Otherwise, it is saved as `maxplot.term` file, where *term* is gnuplot terminal name.

- gnuplot_out_file** Plot option
 When used in conjunction with the `gnuplot_term` option, it can be used to save the plot in a file, in one of the graphic formats supported by Gnuplot. If you want to create a Postscript file, you can use the option `psfile` instead, which will also work in Openmath, and does the same thing with just one option.
`[gnuplot_term, png], [gnuplot_out_file, "graph3.png"]`
- gnuplot_pm3d** Plot option
 With a value of `false`, it can be used to prevent the usage of PM3D mode, which is enabled by default.
- gnuplot_preamble** Plot option
 Inserts gnuplot commands before the plot is drawn. Any valid gnuplot commands may be used. Multiple commands should be separated with a semi-colon. The example shown produces a log scale plot. The default value for `gnuplot_preamble` is the empty string `""`.
- gnuplot_curve_titles** Plot option
 This is an old option that has been replaced by `legend` described above.
- gnuplot_curve_styles** Plot option
 This is an obsolete option that has been replaced by `style`.
- gnuplot_default_term_command** Plot option
 The gnuplot command to set the terminal type for the default terminal. The default value is `"set term pop"`.
- gnuplot_dumb_term_command** Plot option
 The gnuplot command to set the terminal type for the dumb terminal. The default value is `"set term dumb 79 22"`, which makes the text output 79 characters by 22 characters.
- gnuplot_ps_term_command** Plot option
 The gnuplot command to set the terminal type for the PostScript terminal. The default value is `"set size 1.5, 1.5; set term postscript eps enhanced color solid 24"`, which sets the size to 1.5 times gnuplot's default, and the font size to 24, among other things. See the gnuplot documentation for `set term postscript` for more information.

12.6 Gnuplot_pipes Format Functions

- gnuplot_start ()** Function
 Opens the pipe to gnuplot used for plotting with the `gnuplot_pipes` format. Is not necessary to manually open the pipe before plotting.
- gnuplot_close ()** Function
 Closes the pipe to gnuplot which is used with the `gnuplot_pipes` format.
- gnuplot_restart ()** Function
 Closes the pipe to gnuplot which is used with the `gnuplot_pipes` format and opens a new pipe.

gnuplot_replot ()	Function
gnuplot_replot (s)	Function
Updates the gnuplot window. If gnuplot_replot is called with a gnuplot command in a string <i>s</i> , then <i>s</i> is sent to gnuplot before reploting the window.	
 gnuplot_reset ()	 Function
Resets the state of gnuplot used with the gnuplot_pipes format To update the gnuplot window call gnuplot_replot after gnuplot_reset .	

13 File Input and Output

13.1 Comments

A comment in Maxima input is any text between `/*` and `*/`.

The Maxima parser treats a comment as whitespace for the purpose of finding tokens in the input stream; a token always ends at a comment. An input such as `a/* foo */b` contains two tokens, `a` and `b`, and not a single token `ab`. Comments are otherwise ignored by Maxima; neither the content nor the location of comments is stored in parsed input expressions.

Comments can be nested to arbitrary depth. The `/*` and `*/` delimiters form matching pairs. There must be the same number of `/*` as there are `*/`.

Examples:

```
(%i1) /* aa is a variable of interest */ aa : 1234;
(%o1)
1234
(%i2) /* Value of bb depends on aa */ bb : aa^2;
(%o2)
1522756
(%i3) /* User-defined infix operator */ infix ("b");
(%o3)
b
(%i4) /* Parses same as a b c, not abc */ a/* foo */b/* bar */c;
(%o4)
a b c
(%i5) /* Comments /* can be nested /* to any depth */ */ */ 1 + xyz;
(%o5)
xyz + 1
```

13.2 Files

A file is simply an area on a particular storage device which contains data or text. Files on the disks are figuratively grouped into "directories". A directory is just a list of files. Commands which deal with files are:

<code>appendfile</code>	<code>batch</code>	<code>batchload</code>
<code>closefile</code>	<code>file_output_append</code>	<code>filename_merge</code>
<code>file_search</code>	<code>file_search_maxima</code>	<code>file_search_lisp</code>
<code>file_search_demo</code>	<code>file_search_usage</code>	<code>file_search_tests</code>
<code>file_type</code>	<code>file_type_lisp</code>	<code>file_type_maxima</code>
<code>load</code>	<code>load_pathname</code>	<code>loadfile</code>
<code>loadprint</code>	<code>pathname_directory</code>	<code>pathname_name</code>
<code>pathname_type</code>	<code>printfile</code>	<code>save</code>
<code>stringout</code>	<code>with_stdout</code>	<code>writefile</code>

When a file name is passed to functions like `plot2d`, `save`, or `writefile` and the file name does not include a path, Maxima stores the file in the current working directory. The current working directory depends on the system like Windows or Linux and on the installation.

13.3 Functions and Variables for File Input and Output

appendfile (*filename*) Function
 Appends a console transcript to *filename*. `appendfile` is the same as `writefile`, except that the transcript file, if it exists, is always appended.
`closefile` closes the transcript file opened by `appendfile` or `writefile`.

batch (*filename*) Function
batch (*filename*, *option*) Function
`batch(filename)` reads Maxima expressions from *filename* and evaluates them. `batch` searches for *filename* in the list `file_search_maxima`. See also `file_search`.

`batch(filename, demo)` is like `demo(filename)`. In this case `batch` searches for *filename* in the list `file_search_demo`. See `demo`.

`batch(filename, test)` is like `run_testsuite` with the option `display_all=true`. For this case `batch` searches *filename* in the list `file_search_maxima` and not in the list `file_search_tests` like `run_testsuite`. Furthermore, `run_testsuite` runs tests which are in the list `testsuite_files`. With `batch` it is possible to run any file in a test mode, which can be found in the list `file_search_maxima`. This is useful, when writing a test file.

filename comprises a sequence of Maxima expressions, each terminated with `;` or `$`. The special variable `%` and the function `%th` refer to previous results within the file. The file may include `:lisp` constructs. Spaces, tabs, and newlines in the file are ignored. A suitable input file may be created by a text editor or by the `stringout` function.

`batch` reads each input expression from *filename*, displays the input to the console, computes the corresponding output expression, and displays the output expression. Input labels are assigned to the input expressions and output labels are assigned to the output expressions. `batch` evaluates every input expression in the file unless there is an error. If user input is requested (by `asksign` or `askinteger`, for example) `batch` pauses to collect the requisite input and then continue.

It may be possible to halt `batch` by typing `control-C` at the console. The effect of `control-C` depends on the underlying Lisp implementation.

`batch` has several uses, such as to provide a reservoir for working command lines, to give error-free demonstrations, or to help organize one's thinking in solving complex problems.

`batch` evaluates its argument. `batch` returns the path of *filename* as a string, when called with no second argument or with the option `demo`. When called with the option `test`, the return value is a an empty list `[]` or a list with *filename* and the numbers of the tests which have failed.

See also `load`, `batchload`, and `demo`.

batchload (*filename*) Function

Reads Maxima expressions from *filename* and evaluates them, without displaying the input or output expressions and without assigning labels to output expressions. Printed output (such as produced by `print` or `describe`) is displayed, however.

The special variable `%` and the function `%th` refer to previous results from the interactive interpreter, not results within the file. The file cannot include `:lisp` constructs.

`batchload` returns the path of *filename*, as a string. `batchload` evaluates its argument.

See also `batch`, and `load`.

closefile () Function

Closes the transcript file opened by `writefile` or `appendfile`.

file_output_append Option variable

Default value: `false`

`file_output_append` governs whether file output functions append or truncate their output file. When `file_output_append` is `true`, such functions append to their output file. Otherwise, the output file is truncated.

`save`, `stringout`, and `with_stdout` respect `file_output_append`. Other functions which write output files do not respect `file_output_append`. In particular, plotting and translation functions always truncate their output file, and `tex` and `appendfile` always append.

filename_merge (*path*, *filename*) Function

Constructs a modified path from *path* and *filename*. If the final component of *path* is of the form `###.something`, the component is replaced with *filename.something*. Otherwise, the final component is simply replaced by *filename*.

The result is a Lisp pathname object.

file_search (<i>filename</i>)	Function
file_search (<i>filename</i> , <i>pathlist</i>)	Function

file_search searches for the file *filename* and returns the path to the file (as a string) if it can be found; otherwise **file_search** returns **false**. **file_search** (*filename*) searches in the default search directories, which are specified by the **file_search_maxima**, **file_search_lisp**, and **file_search_demo** variables.

file_search first checks if the actual name passed exists, before attempting to match it to “wildcard” file search patterns. See **file_search_maxima** concerning file search patterns.

The argument *filename* can be a path and file name, or just a file name, or, if a file search directory includes a file search pattern, just the base of the file name (without an extension). For example,

```
file_search ("/home/wfs/special/zeta.mac");
file_search ("zeta.mac");
file_search ("zeta");
```

all find the same file, assuming the file exists and **/home/wfs/special/###.mac** is in **file_search_maxima**.

file_search (*filename*, *pathlist*) searches only in the directories specified by *pathlist*, which is a list of strings. The argument *pathlist* supersedes the default search directories, so if the path list is given, **file_search** searches only the ones specified, and not any of the default search directories. Even if there is only one directory in *pathlist*, it must still be given as a one-element list.

The user may modify the default search directories. See **file_search_maxima**.

file_search is invoked by **load** with **file_search_maxima** and **file_search_lisp** as the search directories.

file_search_maxima	Option variable
file_search_lisp	Option variable
file_search_demo	Option variable
file_search_usage	Option variable
file_search_tests	Option variable

These variables specify lists of directories to be searched by **load**, **demo**, and some other Maxima functions. The default values of these variables name various directories in the Maxima installation.

The user can modify these variables, either to replace the default values or to append additional directories. For example,

```
file_search_maxima: ["/usr/local/foo/###.mac",
                    "/usr/local/bar/###.mac"]$
```

replaces the default value of **file_search_maxima**, while

```
file_search_maxima: append (file_search_maxima,
                           ["/usr/local/foo/###.mac", "/usr/local/bar/###.mac"])$
```

appends two additional directories. It may be convenient to put such an expression in the file **maxima-init.mac** so that the file search path is assigned automatically when Maxima starts. See also [Section 32.1 \[Introduction for Runtime Environment\]](#), page 409.

Multiple filename extensions and multiple paths can be specified by special “wildcard” constructions. The string **###** expands into the sought-after name, while a comma-separated list enclosed in curly braces {**foo,bar,baz**} expands into multiple strings. For example, supposing the sought-after name is **neumann**,

```
"/home/{wfs,gcj}/###.{lisp,mac}"
```

expands into **/home/wfs/neumann.lisp**, **/home/gcj/neumann.lisp**, **/home/wfs/neumann.mac**, and **/home/gcj/neumann.mac**.

file_type (*filename*)

Function

Returns a guess about the content of *filename*, based on the filename extension. *filename* need not refer to an actual file; no attempt is made to open the file and inspect the content.

The return value is a symbol, either `object`, `lisp`, or `maxima`. If the extension matches one of the values in `file_type_maxima`, `file_type` returns `maxima`. If the extension matches one of the values in `file_type_lisp`, `file_type` returns `lisp`. If none of the above, `file_type` returns `object`.

See also `pathname_type`.

See `file_type_maxima` and `file_type_lisp` for the default values.

Examples:

```
(%i2) map('file_type,
          ["test.lisp", "test.mac", "test.dem", "test.txt"]);
(%o2)      [lisp, maxima, maxima, object]
```

file_type_lisp

Option variable

Default value: `[l, lsp, lisp]`

`file_type_lisp` is a list of file extensions that maxima recognizes as denoting a Lisp source file.

See also `file_type`.

file_type_maxima

Option variable

Default value: `[mac, mc, demo, dem, dm1, dm2, dm3, dmt]`

`file_type_maxima` is a list of file extensions that maxima recognizes as denoting a Maxima source file.

See also `file_type`.

load (*filename*)

Function

Evaluates expressions in *filename*, thus bringing variables, functions, and other objects into Maxima. The binding of any existing object is clobbered by the binding recovered from *filename*. To find the file, `load` calls `file_search` with `file_search_maxima` and `file_search_lisp` as the search directories. If `load` succeeds, it returns the name of the file. Otherwise `load` prints an error message.

`load` works equally well for Lisp code and Maxima code. Files created by `save`, `translate_file`, and `compile_file`, which create Lisp code, and `stringout`, which creates Maxima code, can all be processed by `load`. `load` calls `loadfile` to load Lisp files and `batchload` to load Maxima files.

`load` does not recognize `:lisp` constructs in Maxima files, and while processing *filename*, the global variables `_`, `__`, `%`, and `%th` have whatever bindings they had when `load` was called.

See also `loadfile`, `batch`, `batchload`, and `demo`. `loadfile` processes Lisp files; `batch`, `batchload`, and `demo` process Maxima files.

See `file_search` for more detail about the file search mechanism.

`load` evaluates its argument.

load_pathname

System variable

Default value: `false`

When a file is loaded with the functions `load`, `loadfile` or `batchload` the system variable `load_pathname` is bound to the pathname of the file which is processed.

The variable `load_pathname` can be accessed from the file during the loading.

Example:

Suppose we have a batchfile `test.mac` in the directory

`"/home/dieter/workspace/mymaxima/temp/"` with the following commands

```

    print("The value of load_pathname is: ", load_pathname)$
    print("End of batchfile")$
then we get the following output
    (%i1) load("/home/dieter/workspace/mymaxima/temp/test.mac")$
    The value of load_pathname is:
           /home/dieter/workspace/mymaxima/temp/test.mac
    End of batchfile

```

loadfile (*filename*) Function

Evaluates Lisp expressions in *filename*. **loadfile** does not invoke **file_search**, so *filename* must include the file extension and as much of the path as needed to find the file.

loadfile can process files created by **save**, **translate_file**, and **compile_file**. The user may find it more convenient to use **load** instead of **loadfile**.

loadprint Option variable

Default value: **true**

loadprint tells whether to print a message when a file is loaded.

- When **loadprint** is **true**, always print a message.
- When **loadprint** is **'loadfile**, print a message only if a file is loaded by the function **loadfile**.
- When **loadprint** is **'autoload**, print a message only if a file is automatically loaded. See **setup_autoload**.
- When **loadprint** is **false**, never print a message.

pathname_directory (*pathname*) Function

pathname_name (*pathname*) Function

pathname_type (*pathname*) Function

These functions return the components of *pathname*.

Examples:

```

    (%i1) pathname_directory("/home/dieter/maxima/changelog.txt");
    (%o1) /home/dieter/maxima/
    (%i2) pathname_name("/home/dieter/maxima/changelog.txt");
    (%o2) changelog
    (%i3) pathname_type("/home/dieter/maxima/changelog.txt");
    (%o3) txt

```

printfile (*path*) Function

Prints the file named by *path* to the console. *path* may be a string or a symbol; if it is a symbol, it is converted to a string.

If *path* names a file which is accessible from the current working directory, that file is printed to the console. Otherwise, **printfile** attempts to locate the file by appending *path* to each of the elements of **file_search_usage** via **filename_merge**.

printfile returns *path* if it names an existing file, or otherwise the result of a successful filename merge.

save (*filename*, *name_1*, *name_2*, *name_3*, ...) Function

save (*filename*, *values*, *functions*, *labels*, ...) Function

save (*filename*, [*m*, *n*]) Function

save (*filename*, *name_1*=*expr_1*, ...) Function

save (*filename*, *all*) Function

save (*filename*, *name_1*=*expr_1*, *name_2*=*expr_2*, ...) Function

Stores the current values of *name_1*, *name_2*, *name_3*, ..., in *filename*. The arguments are the names of variables, functions, or other objects. If a name has no value or function associated with it, it is ignored. **save** returns *filename*.

save stores data in the form of Lisp expressions. The data stored by **save** may be recovered by **load** (*filename*). See **load**.

The global flag **file_output_append** governs whether **save** appends or truncates the output file. When **file_output_append** is **true**, **save** appends to the output file. Otherwise, **save** truncates the output file. In either case, **save** creates the file if it does not yet exist.

The special form **save** (*filename*, *values*, *functions*, *labels*, ...) stores the items named by *values*, *functions*, *labels*, etc. The names may be any specified by the variable **infolists**. *values* comprises all user-defined variables.

The special form **save** (*filename*, [*m*, *n*]) stores the values of input and output labels *m* through *n*. Note that *m* and *n* must be literal integers. Input and output labels may also be stored one by one, e.g., **save** ("foo.1", %i42, %o42). **save** (*filename*, *labels*) stores all input and output labels. When the stored labels are recovered, they clobber existing labels.

The special form **save** (*filename*, *name_1*=*expr_1*, *name_2*=*expr_2*, ...) stores the values of *expr_1*, *expr_2*, ..., with names *name_1*, *name_2*, ... It is useful to apply this form to input and output labels, e.g., **save** ("foo.1", aa=%o88). The right-hand side of the equality in this form may be any expression, which is evaluated. This form does not introduce the new names into the current Maxima environment, but only stores them in *filename*.

These special forms and the general form of **save** may be mixed at will. For example, **save** (*filename*, aa, bb, cc=42, *functions*, [11, 17]).

The special form **save** (*filename*, *all*) stores the current state of Maxima. This includes all user-defined variables, functions, arrays, etc., as well as some automatically defined items. The saved items include system variables, such as **file_search_maxima** or **showtime**, if they have been assigned new values by the user; see **myoptions**.

save evaluates *filename* and quotes all other arguments.

stringout (<i>filename</i> , <i>expr_1</i> , <i>expr_2</i> , <i>expr_3</i> , ...)	Function
stringout (<i>filename</i> , [<i>m</i> , <i>n</i>])	Function
stringout (<i>filename</i> , <i>input</i>)	Function
stringout (<i>filename</i> , <i>functions</i>)	Function
stringout (<i>filename</i> , <i>values</i>)	Function

stringout writes expressions to a file in the same form the expressions would be typed for input. The file can then be used as input for the **batch** or **demo** commands, and it may be edited for any purpose. **stringout** can be executed while **writefile** is in progress.

The global flag **file_output_append** governs whether **stringout** appends or truncates the output file. When **file_output_append** is **true**, **stringout** appends to the output file. Otherwise, **stringout** truncates the output file. In either case, **stringout** creates the file if it does not yet exist.

The general form of **stringout** writes the values of one or more expressions to the output file. Note that if an expression is a variable, only the value of the variable is written and not the name of the variable. As a useful special case, the expressions may be input labels (%i1, %i2, %i3, ...) or output labels (%o1, %o2, %o3, ...).

If **grind** is **true**, **stringout** formats the output using the **grind** format. Otherwise the **string** format is used. See **grind** and **string**.

The special form **stringout** (*filename*, [*m*, *n*]) writes the values of input labels *m* through *n*, inclusive.

The special form **stringout** (*filename*, *input*) writes all input labels to the file.

The special form **stringout** (*filename*, *functions*) writes all user-defined functions (named by the global list **functions**) to the file.

The special form **stringout** (*filename*, *values*) writes all user-assigned variables (named by the global list **values**) to the file. Each variable is printed as an assignment statement, with the name of the variable, a colon, and its value. Note that the general form of **stringout** does not print variables as assignment statements.

with_stdout (*f*, *expr_1*, *expr_2*, *expr_3*, ...) Function
with_stdout (*s*, *expr_1*, *expr_2*, *expr_3*, ...) Function

Evaluates *expr_1*, *expr_2*, *expr_3*, ... and writes any output thus generated to a file *f* or output stream *s*. The evaluated expressions are not written to the output. Output may be generated by **print**, **display**, **grind**, among other functions.

The global flag **file_output_append** governs whether **with_stdout** appends or truncates the output file *f*. When **file_output_append** is **true**, **with_stdout** appends to the output file. Otherwise, **with_stdout** truncates the output file. In either case, **with_stdout** creates the file if it does not yet exist.

with_stdout returns the value of its final argument.

See also **writefile**.

```
(%i1) with_stdout ("tmp.out", for i:5 thru 10 do
      print (i, "! yields", i!))$
(%i2) printfile ("tmp.out")$
5 ! yields 120
6 ! yields 720
7 ! yields 5040
8 ! yields 40320
9 ! yields 362880
10 ! yields 3628800
```

writefile (*filename*) Function

Begins writing a transcript of the Maxima session to *filename*. All interaction between the user and Maxima is then recorded in this file, just as it appears on the console.

As the transcript is printed in the console output format, it cannot be reloaded into Maxima. To make a file containing expressions which can be reloaded, see **save** and **stringout**. **save** stores expressions in Lisp form, while **stringout** stores expressions in Maxima form.

The effect of executing **writefile** when *filename* already exists depends on the underlying Lisp implementation; the transcript file may be clobbered, or the file may be appended. **appendfile** always appends to the transcript file.

It may be convenient to execute **playback** after **writefile** to save the display of previous interactions. As **playback** displays only the input and output variables (%i1, %o1, etc.), any output generated by a print statement in a function (as opposed to a return value) is not displayed by **playback**.

closefile closes the transcript file opened by **writefile** or **appendfile**.

13.4 Functions and Variables for TeX Output

tex (*expr*) Function
tex (*expr*, *destination*) Function
tex (*expr*, *false*) Function
tex (*label*) Function
tex (*label*, *destination*) Function
tex (*label*, *false*) Function

Prints a representation of an expression suitable for the TeX document preparation system. The result is a fragment of a document, which can be copied into a larger document but not processed by itself.

tex (*expr*) prints a TeX representation of *expr* on the console.

tex (*label*) prints a TeX representation of the expression named by *label* and assigns it an equation label (to be displayed to the left of the expression). The TeX equation label is the same as the Maxima label.

destination may be an output stream or file name. When *destination* is a file name, **tex** appends its output to the file. The functions **openw** and **opena** create output streams.

`tex (expr, false)` and `tex (label, false)` return their TeX output as a string.

`tex` evaluates its first argument after testing it to see if it is a label. Quote-quote `''` forces evaluation of the argument, thereby defeating the test and preventing the label.

See also `texput`.

Examples:

```
(%i1) integrate (1/(1+x^3), x);
                                2 x - 1
                                atan(-----)
                                sqrt(3)
                                log(x^2 - x + 1)
(%o1)  - ---- + ---- + ----
        6          sqrt(3)      3
(%i2) tex (%o1);
$$-{\log \left(x^2-x+1\right)}\over{6}}+{\{\arctan \left({2\,x-1}\over{\sqrt{3}}\right)}\over{\sqrt{3}}}+{\log \left(x+1\right)}\over{3}}\leqno{\tt (\%o1)}$$
(%o2)                                     (\%o1)
(%i3) tex (integrate (sin(x), x));
$$-\cos x$$
(%o3)                                     false
(%i4) tex (%o1, "foo.tex");
(%o4)                                     (\%o1)
```

`tex (expr, false)` returns its TeX output as a string.

```
(%i1) S : tex (x * y * z, false);
(%o1) $$x\,y\,z$$
(%i2) S;
(%o2) $$x\,y\,z$$
```

tex1 (e) Function

Returns a string which represents the TeX output for the expressions *e*. The TeX output is not enclosed in delimiters for an equation or any other environment.

Examples:

```
(%i1) tex1 (sin(x) + cos(x));
(%o1) \sin x+\cos x
```

texput (a, s)	Function
texput (a, f)	Function
texput (a, s, operator_type)	Function
texput (a, [s_1, s_2], matchfix)	Function
texput (a, [s_1, s_2, s_3], matchfix)	Function

Assign the TeX output for the atom *a*, which can be a symbol or the name of an operator.

`texput (a, s)` causes the `tex` function to interpolate the string *s* into the TeX output in place of *a*.

`texput (a, f)` causes the `tex` function to call the function *f* to generate TeX output. *f* must accept one argument, which is an expression which has operator *a*, and must return a string (the TeX output). *f* may call `tex1` to generate TeX output for the arguments of the input expression.

`texput (a, s, operator_type)`, where *operator_type* is `prefix`, `infix`, `postfix`, `nary`, or `nofix`, causes the `tex` function to interpolate *s* into the TeX output in place of *a*, and to place the interpolated text in the appropriate position.

`texput (a, [s_1, s_2], matchfix)` causes the `tex` function to interpolate *s_1* and *s_2* into the TeX output on either side of the arguments of *a*. The arguments (if more than one) are separated by commas.

Examples:

```
(%i1) texput (me,"\\mu_e");
(%o1)                                     \\mu_e
(%i2) tex (me);
$$\\mu_e$$
(%o2)                                     false
```

```
(%i1) texput (lcm, "\\mathrm{lcm}");
(%o1) \\mathrm{lcm}
(%i2) tex (lcm (a, b));
$$\\mathrm{lcm}\\left(a , b\\right)$$
(%o2) false
```

```
(%i1) texfoo (e) := block ([a, b], [a, b] : args (e),
concat("\\left[\\stackrel{" ,tex1(b),"}{" ,tex1(a),"}\\right]"))$
(%i2) texput (foo, texfoo);
(%o2)
texfoo
(%i3) tex (foo (2^x, %pi));
$$\\left[\\stackrel{\\pi}{2^x}\\right]$$
(%o3)
false
```

```
(%i1) prefix ("grad");
(%o1)
grad
(%i2) texput ("grad", " \\nabla ", prefix);
(%o2)
\\nabla
(%i3) tex (grad f);
$$ \\nabla f$$
(%o3)
false
```

```
(%i1) infix ("~");
(%o1) ~
(%i2) texput ("~", " \\times ", infix);
(%o2) \\times
(%i3) tex (a ~ b);
$$a \\times b$$
(%o3) false
```

```
(%i1) postfix ("##");
(%o1) ##
(%i2) texput ("##", "!!", postfix);
(%o2) !!
(%i3) tex (x ##);
$$x!!$$
(%o3) false
```

```
(%i1) nary ("@@");
(%o1) @@
(%i2) texput ("@@", " \\circ ", nary);
(%o2) \\circ
(%i3) tex (a @@ b @@ c @@ d);
```

```

$$$ \circ b \circ c \circ d$$$
(%o3)                                     false

```

Assign TeX output for a nofix operator.

```

(%i1) nofix ("foo");
(%o1)                                     foo
(%i2) texput ("foo", "\\mathsc{foo}", nofix);
(%o2)                                     \mathsc{foo}
(%i3) tex (foo);
$$$ \mathsc{foo}$$$
(%o3)                                     false

```

Assign TeX output for a matchfix operator.

```

(%i1) matchfix ("<<", ">>");
(%o1)                                     <<
(%i2) texput ("<<", [" \\langle ", " \\rangle "], matchfix);
(%o2)                                     [ \langle , \rangle ]
(%i3) tex (<<a>>);
$$$ \langle a \rangle $$$
(%o3)                                     false
(%i4) tex (<<a, b>>);
$$$ \langle a , b \rangle $$$
(%o4)                                     false
(%i5) texput ("<<", [" \\langle ", " \\rangle ", " \\, | \\,"],
matchfix);
(%o5)                                     [ \langle , \rangle , \, | \, ]
(%i6) tex (<<a>>);
$$$ \langle a \rangle $$$
(%o6)                                     false
(%i7) tex (<<a, b>>);
$$$ \langle a \, | \, b \rangle $$$
(%o7)                                     false

```

get_tex_environment (<i>op</i>)	Function
set_tex_environment (<i>op, before, after</i>)	Function

Customize the TeX environment output by `tex`. As maintained by these functions, the TeX environment comprises two strings: one is printed before any other TeX output, and the other is printed after.

Only the TeX environment of the top-level operator in an expression is output; TeX environments associated with other operators are ignored.

`get_tex_environment` returns the TeX environment which is applied to the operator *op*; returns the default if no other environment has been assigned.

`set_tex_environment` assigns the TeX environment for the operator *op*.

Examples:

```

(%i1) get_tex_environment (":=");
(%o1) [
\begin{verbatim}
, ;
\end{verbatim}
]
(%i2) tex (f (x) := 1 - x);

\begin{verbatim}
f(x):=1-x;
\end{verbatim}

(%o2)                                     false

```

```
(%i3) set_tex_environment (":=", "$$", "$$");
(%o3) [$$, $$]
(%i4) tex (f (x) := 1 - x);
$$f(x):=1-x$$
(%o4) false
```

get_tex_environment_default () Function
set_tex_environment_default (*before, after*) Function

Customize the TeX environment output by **tex**. As maintained by these functions, the TeX environment comprises two strings: one is printed before any other TeX output, and the other is printed after.

get_tex_environment_default returns the TeX environment which is applied to expressions for which the top-level operator has no specific TeX environment (as assigned by **set_tex_environment**).

set_tex_environment_default assigns the default TeX environment.

Examples:

```
(%i1) get_tex_environment_default ();
(%o1) [$$, $$]
(%i2) tex (f(x) + g(x));
$$g\left(x\right)+f\left(x\right)$$
(%o2) false
(%i3) set_tex_environment_default ("\\begin{equation}
", "
\\end{equation}");
(%o3) [\\begin{equation}
,
\\end{equation}]
(%i4) tex (f(x) + g(x));
\\begin{equation}
g\left(x\right)+f\left(x\right)
\\end{equation}
(%o4) false
```

13.5 Functions and Variables for Fortran Output

fortindent Option variable

Default value: 0

fortindent controls the left margin indentation of expressions printed out by the **fortran** command. 0 gives normal printout (i.e., 6 spaces), and positive values will causes the expressions to be printed farther to the right.

fortran (*expr*) Function

Prints *expr* as a Fortran statement. The output line is indented with spaces. If the line is too long, **fortran** prints continuation lines. **fortran** prints the exponentiation operator \wedge as **, and prints a complex number $a + b\%i$ in the form (a,b).

expr may be an equation. If so, **fortran** prints an assignment statement, assigning the right-hand side of the equation to the left-hand side. In particular, if the right-hand side of *expr* is the name of a matrix, then **fortran** prints an assignment statement for each element of the matrix.

If *expr* is not something recognized by **fortran**, the expression is printed in **grind** format without complaint. **fortran** does not know about lists, arrays, or functions.

fortindent controls the left margin of the printed lines. 0 is the normal margin (i.e., indented 6 spaces). Increasing **fortindent** causes expressions to be printed further to the right.

When `fortspaces` is `true`, `fortran` fills out each printed line with spaces to 80 columns. `fortran` evaluates its arguments; quoting an argument defeats evaluation. `fortran` always returns `done`.

See also the function `f90` for printing one or more expressions as a Fortran 90 program.

Examples:

```
(%i1) expr: (a + b)^12$
(%i2) fortran (expr);
      (b+a)**12
(%o2)                                     done
(%i3) fortran ('x=expr);
      x = (b+a)**12
(%o3)                                     done
(%i4) fortran ('x=expand (expr));
      x = b**12+12*a*b**11+66*a**2*b**10+220*a**3*b**9+495*a**4*b**8+792
1      *a**5*b**7+924*a**6*b**6+792*a**7*b**5+495*a**8*b**4+220*a**9*b
2      **3+66*a**10*b**2+12*a**11*b+a**12
(%o4)                                     done
(%i5) fortran ('x=7+5*%i);
      x = (7,5)
(%o5)                                     done
(%i6) fortran ('x=[1,2,3,4]);
      x = [1,2,3,4]
(%o6)                                     done
(%i7) f(x) := x^2$
(%i8) fortran (f);
      f
(%o8)                                     done
```

fortspaces

Option variable

Default value: `false`

When `fortspaces` is `true`, `fortran` fills out each printed line with spaces to 80 columns.

14 Polynomials

14.1 Introduction to Polynomials

Polynomials are stored in Maxima either in General Form or as Canonical Rational Expressions (CRE) form. The latter is a standard form, and is used internally by operations such as factor, ratsimp, and so on.

Canonical Rational Expressions constitute a kind of representation which is especially suitable for expanded polynomials and rational functions (as well as for partially factored polynomials and rational functions when RATFAC is set to `true`). In this CRE form an ordering of variables (from most to least main) is assumed for each expression. Polynomials are represented recursively by a list consisting of the main variable followed by a series of pairs of expressions, one for each term of the polynomial. The first member of each pair is the exponent of the main variable in that term and the second member is the coefficient of that term which could be a number or a polynomial in another variable again represented in this form. Thus the principal part of the CRE form of $3X^2-1$ is $(X\ 2\ 3\ 0\ -1)$ and that of $2XY+X-3$ is $(Y\ 1\ (X\ 1\ 2)\ 0\ (X\ 1\ 1\ 0\ -3))$ assuming Y is the main variable, and is $(X\ 1\ (Y\ 1\ 2\ 0\ 1)\ 0\ -3)$ assuming X is the main variable. "Main"-ness is usually determined by reverse alphabetical order. The "variables" of a CRE expression needn't be atomic. In fact any subexpression whose main operator is not $+$ $-$ $*$ $/$ or $^$ with integer power will be considered a "variable" of the expression (in CRE form) in which it occurs. For example the CRE variables of the expression $X+\text{SIN}(X+1)+2*\text{SQRT}(X)+1$ are X , $\text{SQRT}(X)$, and $\text{SIN}(X+1)$. If the user does not specify an ordering of variables by using the RATVARS function Maxima will choose an alphabetic one. In general, CRE's represent rational expressions, that is, ratios of polynomials, where the numerator and denominator have no common factors, and the denominator is positive. The internal form is essentially a pair of polynomials (the numerator and denominator) preceded by the variable ordering list. If an expression to be displayed is in CRE form or if it contains any subexpressions in CRE form, the symbol `/R/` will follow the line label. See the RAT function for converting an expression to CRE form. An extended CRE form is used for the representation of Taylor series. The notion of a rational expression is extended so that the exponents of the variables can be positive or negative rational numbers rather than just positive integers and the coefficients can themselves be rational expressions as described above rather than just polynomials. These are represented internally by a recursive polynomial form which is similar to and is a generalization of CRE form, but carries additional information such as the degree of truncation. As with CRE form, the symbol `/T/` follows the line label of such expressions.

14.2 Functions and Variables for Polynomials

algebraic

Option variable

Default value: `false`

`algebraic` must be set to `true` in order for the simplification of algebraic integers to take effect.

berlefact

Option variable

Default value: `true`

When `berlefact` is `false` then the Kronecker factoring algorithm will be used otherwise the Berlekamp algorithm, which is the default, will be used.

bezout (*p1*, *p2*, *x*)

Function

an alternative to the `resultant` command. It returns a matrix. `determinant` of this matrix is the desired resultant.

Examples:

```
(%i1) bezout(a*x+b, c*x^2+d, x);
              [ b c - a d ]
(%o1)         [          ]
              [ a      b   ]

(%i2) determinant(%);
              2      2
(%o2)         a d + b c
(%i3) resultant(a*x+b, c*x^2+d, x);
              2      2
(%o3)         a d + b c
```

bothcoef (*expr*, *x*)

Function

Returns a list whose first member is the coefficient of *x* in *expr* (as found by `ratcoef` if *expr* is in CRE form otherwise by `coeff`) and whose second member is the remaining part of *expr*. That is, $[A, B]$ where $\text{expr} = A*x + B$.

Example:

```
(%i1) islinear (expr, x) := block ([c],
      c: bothcoef (rat (expr, x), x),
      is (freeof (x, c) and c[1] # 0))$
(%i2) islinear ((r^2 - (x - r)^2)/x, x);
(%o2) true
```

coeff (*expr*, *x*, *n*)

Function

coeff (*expr*, *x*)

Function

Returns the coefficient of x^n in *expr*, where *expr* is a polynomial or a monomial term in *x*.

`coeff(expr, x^n)` is equivalent to `coeff(expr, x, n)`. `coeff(expr, x, 0)` returns the remainder of *expr* which is free of *x*. If omitted, *n* is assumed to be 1.

x may be a simple variable or a subscripted variable, or a subexpression of *expr* which comprises an operator and all of its arguments.

It may be possible to compute coefficients of expressions which are equivalent to *expr* by applying `expand` or `factor`. `coeff` itself does not apply `expand` or `factor` or any other function.

`coeff` distributes over lists, matrices, and equations.

Examples:

`coeff` returns the coefficient x^n in *expr*.

```
(%i1) coeff (b^3*a^3 + b^2*a^2 + b*a + 1, a^3);
              3
(%o1)         b
```

`coeff(expr, x^n)` is equivalent to `coeff(expr, x, n)`.

```
(%i1) coeff (c[4]*z^4 - c[3]*z^3 - c[2]*z^2 + c[1]*z, z, 3);
(%o1)         - c
              3
(%i2) coeff (c[4]*z^4 - c[3]*z^3 - c[2]*z^2 + c[1]*z, z^3);
(%o2)         - c
              3
```

`coeff(expr, x, 0)` returns the remainder of *expr* which is free of *x*.

```
(%i1) coeff (a*u + b^2*u^2 + c^3*u^3, b, 0);
              3 3
(%o1)         c u + a u
```

x may be a simple variable or a subscripted variable, or a subexpression of *expr* which comprises an operator and all of its arguments.


```
(%i1) coeff (h^4 - 2*pi*h^2 + 1, h, 2);
(%o1) - 2 %pi
(%i2) coeff (v[1]^4 - 2*pi*v[1]^2 + 1, v[1], 2);
(%o2) - 2 %pi
(%i3) coeff (sin(1+x)*sin(x) + sin(1+x)^3*sin(x)^3, sin(1+x)^3);
(%o3) sin (x)
(%i4) coeff ((d - a)^2*(b + c)^3 + (a + b)^4*(c - d), a + b, 4);
(%o4) c - d
```

`coeff` itself does not apply `expand` or `factor` or any other function.

```
(%i1) coeff (c*(a + b)^3, a);
(%o1) 0
(%i2) expand (c*(a + b)^3);
(%o2) b^3 c + 3 a b^2 c + 3 a^2 b c + a^3 c
(%i3) coeff (%, a);
(%o3) 3 b^2 c
(%i4) coeff (b^3*c + 3*a*b^2*c + 3*a^2*b*c + a^3*c, (a + b)^3);
(%o4) 0
(%i5) factor (b^3*c + 3*a*b^2*c + 3*a^2*b*c + a^3*c);
(%o5) (b + a)^3 c
(%i6) coeff (%, (a + b)^3);
(%o6) c
```

`coeff` distributes over lists, matrices, and equations.

```
(%i1) coeff ([4*a, -3*a, 2*a], a);
(%o1) [4, - 3, 2]
(%i2) coeff (matrix ([a*x, b*x], [-c*x, -d*x]), x);
(%o2) [ a b ]
[ - c - d ]
(%i3) coeff (a*u - b*v = 7*u + 3*v, u);
(%o3) a = 7
```

content (p_1, x_1, \dots, x_n)

Function

Returns a list whose first element is the greatest common divisor of the coefficients of the terms of the polynomial p_1 in the variable x_n (this is the content) and whose second element is the polynomial p_1 divided by the content.

Examples:

```
(%i1) content (2*x*y + 4*x^2*y^2, y);
(%o1) [2 x, 2 x y^2 + y]
```

denom ($expr$)

Function

Returns the denominator of the rational expression $expr$.

divide ($p_1, p_2, x_1, \dots, x_n$)

Function

computes the quotient and remainder of the polynomial p_1 divided by the polynomial p_2 , in a main polynomial variable, x_n . The other variables are as in the `ratvars` function. The result is a list whose first element is the quotient and whose second element is the remainder.

Examples:

```
(%i1) divide (x + y, x - y, x);
(%o1) [1, 2 y]
```

```
(%i2) divide (x + y, x - y);
(%o2)          [- 1, 2 x]
```

Note that y is the main variable in the second example.

eliminate ([eqn_1, ..., eqn_n], [x_1, ..., x_k]) Function
 Eliminates variables from equations (or expressions assumed equal to zero) by taking successive resultants. This returns a list of $n - k$ expressions with the k variables x_1, \dots, x_k eliminated. First x_1 is eliminated yielding $n - 1$ expressions, then x_2 is eliminated, etc. If $k = n$ then a single expression in a list is returned free of the variables x_1, \dots, x_k . In this case **solve** is called to solve the last resultant for the last variable.

Example:

```
(%i1) expr1: 2*x^2 + y*x + z;
(%o1)          2
              z + x y + 2 x
(%i2) expr2: 3*x + 5*y - z - 1;
(%o2)          - z + 5 y + 3 x - 1
(%i3) expr3: z^2 + x - y^2 + 5;
(%o3)          2      2
              z - y + x + 5
(%i4) eliminate ([expr3, expr2, expr1], [y, z]);
(%o4) [7425 x^8 - 1170 x^7 + 1299 x^6 + 12076 x^5 + 22887 x^4
      - 5154 x^3 - 1291 x^2 + 7688 x + 15376]
```

ezgcd (p_1, p_2, p_3, ...) Function
 Returns a list whose first element is the greatest common divisor of the polynomials p_1, p_2, p_3, \dots and whose remaining elements are the polynomials divided by the greatest common divisor. This always uses the **ezgcd** algorithm.

See also **gcd**, **gcdex**, **gcddivide**, and **poly_gcd**.

Examples:

The three polynomials have the greatest common divisor $2x-3$. The gcd is first calculated with the function **gcd** and then with the function **ezgcd**.

```
(%i1) p1 : 6*x^3-17*x^2+14*x-3;
(%o1)          3      2
              6 x - 17 x + 14 x - 3
(%i2) p2 : 4*x^4-14*x^3+12*x^2+2*x-3;
(%o2)          4      3      2
              4 x - 14 x + 12 x + 2 x - 3
(%i3) p3 : -8*x^3+14*x^2-x-3;
(%o3)          3      2
              - 8 x + 14 x - x - 3
(%i4) gcd(p1, gcd(p2, p3));
(%o4)          2 x - 3
(%i5) ezgcd(p1, p2, p3);
(%o5) [2 x - 3, 3 x^2 - 4 x + 1, 2 x^3 - 4 x^2 + 1, - 4 x^2 + x + 1]
```

facexpand Option variable
 Default value: **true**
facexpand controls whether the irreducible factors returned by **factor** are in expanded (the default) or recursive (normal CRE) form.

factor (*expr*)

Function

factor (*expr*, *p*)

Function

Factors the expression *expr*, containing any number of variables or functions, into factors irreducible over the integers. **factor** (*expr*, *p*) factors *expr* over the field of rationals with an element adjoined whose minimum polynomial is *p*.

factor uses **ifactors** function for factoring integers.

factorflag if **false** suppresses the factoring of integer factors of rational expressions.

dontfactor may be set to a list of variables with respect to which factoring is not to occur. (It is initially empty). Factoring also will not take place with respect to any variables which are less important (using the variable ordering assumed for CRE form) than those on the **dontfactor** list.

savefactors if **true** causes the factors of an expression which is a product of factors to be saved by certain functions in order to speed up later factorizations of expressions containing some of the same factors.

berlefact if **false** then the Kronecker factoring algorithm will be used otherwise the Berlekamp algorithm, which is the default, will be used.

intfacilim if **true** maxima will give up factorization of integers if no factor is found after trial divisions and Pollard's rho method. If set to **false** (this is the case when the user calls **factor** explicitly), complete factorization of the integer will be attempted. The user's setting of **intfacilim** is used for internal calls to **factor**. Thus, **intfacilim** may be reset to prevent Maxima from taking an inordinately long time factoring large integers.

Examples:

```
(%i1) factor (2^63 - 1);
              2
(%o1)          7  73 127 337 92737 649657
(%i2) factor (-8*y - 4*x + z^2*(2*y + x));
(%o2)          (2 y + x) (z - 2) (z + 2)
(%i3) -1 - 2*x - x^2 + y^2 + 2*x*y^2 + x^2*y^2;
              2  2      2      2      2
(%o3)          x  y  + 2 x y  + y  - x  - 2 x - 1
(%i4) block ([dontfactor: [x]], factor (%/36/(1 + 2*y + y^2)));
              2
              (x  + 2 x + 1) (y - 1)
(%o4)          -----
              36 (y + 1)
(%i5) factor (1 + %e^(3*x));
              x      2 x      x
(%o5)          (%e  + 1) (%e  - %e  + 1)
(%i6) factor (1 + x^4, a^2 - 2);
              2      2
(%o6)          (x  - a x + 1) (x  + a x + 1)
(%i7) factor (-y^2*z^2 - x*z^2 + x^2*y^2 + x^3);
              2
              - (y  + x) (z - x) (z + x)
(%o7)          (2 + x)/(3 + x)/(b + x)/(c + x)^2;
              x + 2
(%o8)          -----
              2
              (x + 3) (x + b) (x + c)
(%i9) ratsimp (%);
              4      3
(%o9) (x + 2)/(x  + (2 c + b + 3) x
              2      2      2      2
              + (c  + (2 b + 6) c + 3 b) x  + ((b + 3) c  + 6 b c) x + 3 b c )
(%i10) partfrac (% , x);
```

```

(%o10) - (c2 - 4 c - b + 6)/((c4 + (- 2 b - 6) c3
+ (b2 + 12 b + 9) c2 + (- 6 b2 - 18 b) c + 9 b2) (x + c))
- -----
      2
      (c + (- b - 3) c + 3 b) (x + c)
+ -----
      b - 2
      ((b - 3) c2 + (6 b - 2 b2) c + b3 - 3 b2) (x + b)
- -----
      1
      ((b - 3) c2 + (18 - 6 b) c + 9 b - 27) (x + 3)
(%i11) map ('factor, %);
(%o11) - ----- - -----
      2          c - 2
      c - 4 c - b + 6          (c - 3) (c - b) (x + c)2
      (c - 3) (c - b) (x + c)
+ ----- - -----
      b - 2          1
      (b - 3) (c - b) (x + b) (b - 3) (c - 3) (x + 3)
(%i12) ratsimp ((x^5 - 1)/(x - 1));
(%o12)
      4 3 2
      x + x + x + x + 1
(%i13) subst (a, x, %);
(%o13)
      4 3 2
      a + a + a + a + 1
(%i14) factor (%th(2), %);
(%o14) (x - a) (x - a) (x - a) (x + a + a + a + 1)
(%i15) factor (1 + x^12);
(%o15)
      4 8 4
      (x + 1) (x - x + 1)
(%i16) factor (1 + x^99);
(%o16) (x + 1) (x2 - x + 1) (x6 - x3 + 1)
      10 9 8 7 6 5 4 3 2
      (x - x + x - x + x - x + x - x + x - x + 1)
      20 19 17 16 14 13 11 10 9 7 6
      (x + x - x - x + x + x - x - x - x + x + x
      4 3 60 57 51 48 42 39 33
      - x - x + x + 1) (x + x - x - x + x + x - x

```

$$-x^{30} - x^{27} + x^{21} + x^{18} - x^{12} - x^9 + x^3 + 1)$$

factorflag

Option variable

Default value: `false`

When `factorflag` is `false`, suppresses the factoring of integer factors of rational expressions.

factorout (*expr*, *x_1*, *x_2*, ...)

Function

Rearranges the sum *expr* into a sum of terms of the form *f* (*x_1*, *x_2*, ...) * *g* where *g* is a product of expressions not containing any *x_i* and *f* is factored.

Note that the option variable `keepfloat` is ignored by `factorout`.

Example:

```
(%i1) expand (a*(x+1)*(x-1)*(u+1)^2);
              2 2      2      2      2
(%o1)      a u x + 2 a u x + a x - a u - 2 a u - a
(%i2) factorout(%,x);
              2
(%o2) a u (x - 1) (x + 1) + 2 a u (x - 1) (x + 1)
              + a (x - 1) (x + 1)
```

factorsum (*expr*)

Function

Tries to group terms in factors of *expr* which are sums into groups of terms such that their sum is factorable. `factorsum` can recover the result of `expand ((x + y)^2 + (z + w)^2)` but it can't recover `expand ((x + 1)^2 + (x + y)^2)` because the terms have variables in common.

Example:

```
(%i1) expand ((x + 1)*((u + v)^2 + a*(w + z)^2));
              2      2      2      2
(%o1) a x z + a z + 2 a w x z + 2 a w z + a w x + v x
              2      2      2      2
              + 2 u v x + u x + a w + v + 2 u v + u
(%i2) factorsum (%);
              2      2
(%o2)      (x + 1) (a (z + w) + (v + u) )
```

fasttimes (*p_1*, *p_2*)

Function

Returns the product of the polynomials *p_1* and *p_2* by using a special algorithm for multiplication of polynomials. *p_1* and *p_2* should be multivariate, dense, and nearly the same size. Classical multiplication is of order *n_1 n_2* where *n_1* is the degree of *p_1* and *n_2* is the degree of *p_2*. `fasttimes` is of order $\max(n_1, n_2)^{1.585}$.

fullratsimp (*expr*)

Function

`fullratsimp` repeatedly applies `ratsimp` followed by non-rational simplification to an expression until no further change occurs, and returns the result.

When non-rational expressions are involved, one call to `ratsimp` followed as is usual by non-rational ("general") simplification may not be sufficient to return a simplified result. Sometimes, more than one such call may be necessary. `fullratsimp` makes this process convenient.

`fullratsimp` (*expr*, *x_1*, ..., *x_n*) takes one or more arguments similar to `ratsimp` and `rat`.

Example:

```
(%i1) expr: (x^(a/2) + 1)^2*(x^(a/2) - 1)^2/(x^a - 1);
              a/2      2      a/2      2
              (x  - 1) (x  + 1)
(%o1)
              -----
              a
              x  - 1
(%i2) ratsimp (expr);
              2 a      a
              x  - 2 x  + 1
(%o2)
              -----
              a
              x  - 1
(%i3) fullratsimp (expr);
              a
              x  - 1
(%o3)
(%i4) rat (expr);
              a/2 4      a/2 2
              (x  ) - 2 (x  ) + 1
(%o4)/R/
              -----
              a
              x  - 1
```

fullratsubst (*a*, *b*, *c*)

Function

is the same as **ratsubst** except that it calls itself recursively on its result until that result stops changing. This function is useful when the replacement expression and the replaced expression have one or more variables in common.

fullratsubst will also accept its arguments in the format of **lratsubst**. That is, the first argument may be a single substitution equation or a list of such equations, while the second argument is the expression being processed.

load ("lrats") loads **fullratsubst** and **lratsubst**.

Examples:

- ```
(%i1) load ("lrats")$
```
- **subst** can carry out multiple substitutions. **lratsubst** is analogous to **subst**.
 

```
(%i2) subst ([a = b, c = d], a + c);
(%o2) d + b
(%i3) lratsubst ([a^2 = b, c^2 = d], (a + e)*c*(a + c));
(%o3) (d + a c) e + a d + b c
```
  - If only one substitution is desired, then a single equation may be given as first argument.
 

```
(%i4) lratsubst (a^2 = b, a^3);
(%o4) a b
```
  - **fullratsubst** is equivalent to **ratsubst** except that it recurses until its result stops changing.
 

```
(%i5) ratsubst (b*a, a^2, a^3);
 2
 a b
(%o5)
(%i6) fullratsubst (b*a, a^2, a^3);
 2
 a b
(%o6)
```
  - **fullratsubst** also accepts a list of equations or a single equation as first argument.
 

```
(%i7) fullratsubst ([a^2 = b, b^2 = c, c^2 = a], a^3*b*c);
 b
(%o7)
(%i8) fullratsubst (a^2 = b*a, a^3);
 2
 a b
(%o8)
```

- `fullratsubst` may cause an indefinite recursion.

```
(%i9) errcatch (fullratsubst (b*a^2, a^2, a^3));
```

```
*** - Lisp stack overflow. RESET
```

**gcd** ( $p_1, p_2, x_1, \dots$ )

Function

Returns the greatest common divisor of  $p_1$  and  $p_2$ . The flag `gcd` determines which algorithm is employed. Setting `gcd` to `ez`, `subres`, `red`, or `spmod` selects the `ezgcd`, `subresultant prs`, `reduced`, or `modular` algorithm, respectively. If `gcd` `false` then `gcd` ( $p_1, p_2, x$ ) always returns 1 for all  $x$ . Many functions (e.g. `ratsimp`, `factor`, etc.) cause `gcd`'s to be taken implicitly. For homogeneous polynomials it is recommended that `gcd` equal to `subres` be used. To take the `gcd` when an algebraic is present, e.g., `gcd` ( $x^2 - 2*\sqrt{2}*x + 2, x - \sqrt{2}$ ), the option variable `algebraic` must be `true` and `gcd` must not be `ez`.

The `gcd` flag, default: `spmod`, if `false` will also prevent the greatest common divisor from being taken when expressions are converted to canonical rational expression (CRE) form. This will sometimes speed the calculation if `gcd`s are not required.

See also `ezgcd`, `gcdex`, `gcddivide`, and `poly_gcd`.

Example:

```
(%i1) p1:6*x^3+19*x^2+19*x+6;
 3 2
 6 x + 19 x + 19 x + 6
(%o1)
(%i2) p2:6*x^5+13*x^4+12*x^3+13*x^2+6*x;
 5 4 3 2
 6 x + 13 x + 12 x + 13 x + 6 x
(%o2)
(%i3) gcd(p1, p2);
 2
 6 x + 13 x + 6
(%o3)
(%i4) p1/gcd(p1, p2), ratsimp;
 x + 1
(%o4)
(%i5) p2/gcd(p1, p2), ratsimp;
 3
 x + x
(%o5)
```

`ezgcd` returns a list whose first element is the greatest common divisor of the polynomials  $p_1$  and  $p_2$ , and whose remaining elements are the polynomials divided by the greatest common divisor.

```
(%i6) ezgcd(p1, p2);
 2 3
 6 x + 13 x + 6, x + 1, x + x
(%o6)
```

**gcdex** ( $f, g$ )

Function

**gcdex** ( $f, g, x$ )

Function

Returns a list  $[a, b, u]$  where  $u$  is the greatest common divisor (`gcd`) of  $f$  and  $g$ , and  $u$  is equal to  $a f + b g$ . The arguments  $f$  and  $g$  should be univariate polynomials, or else polynomials in  $x$  a supplied main variable since we need to be in a principal ideal domain for this to work. The `gcd` means the `gcd` regarding  $f$  and  $g$  as univariate polynomials with coefficients being rational functions in the other variables.

`gcdex` implements the Euclidean algorithm, where we have a sequence of  $L[i]: [a[i], b[i], r[i]]$  which are all perpendicular to  $[f, g, -1]$  and the next one is built as if  $q = \text{quotient}(r[i]/r[i+1])$  then  $L[i+2]: L[i] - q L[i+1]$ , and it terminates at  $L[i+1]$  when the remainder  $r[i+2]$  is zero.

The arguments  $f$  and  $g$  can be integers. For this case the function `igcdex` is called by `gcdex`.

See also `ezgcd`, `gcd`, `gcddivide`, and `poly_gcd`.

Examples:

```
(%i1) gcdex (x^2 + 1, x^3 + 4);
 2
 x + 4 x - 1 x + 4
(%o1)/R/ [- ----, ----, 1]
 17 17
(%i2) % . [x^2 + 1, x^3 + 4, -1];
(%o2)/R/ 0
```

Note that the gcd in the following is 1 since we work in  $k(y)[x]$ , not the  $y+1$  we would expect in  $k[y, x]$ .

```
(%i1) gcdex (x*(y + 1), y^2 - 1, x);
 1
(%o1)/R/ [0, ----, 1]
 2
 y - 1
```

**gcfactor** (*n*) Function

Factors the Gaussian integer *n* over the Gaussian integers, i.e., numbers of the form  $a + b\%i$  where *a* and *b* are rational integers (i.e., ordinary integers). Factors are normalized by making *a* and *b* non-negative.

**gfactor** (*expr*) Function

Factors the polynomial *expr* over the Gaussian integers (that is, the integers with the imaginary unit *%i* adjoined). This is like **factor** (*expr*,  $a^2+1$ ) where *a* is *%i*.

Example:

```
(%i1) gfactor (x^4 - 1);
(%o1) (x - 1) (x + 1) (x - %i) (x + %i)
```

**gfactorsum** (*expr*) Function

is similar to **factorsum** but applies **gfactor** instead of **factor**.

**hipow** (*expr*, *x*) Function

Returns the highest explicit exponent of *x* in *expr*. *x* may be a variable or a general expression. If *x* does not appear in *expr*, **hipow** returns 0.

**hipow** does not consider expressions equivalent to *expr*. In particular, **hipow** does not expand *expr*, so **hipow** (*expr*, *x*) and **hipow** (**expand** (*expr*, *x*)) may yield different results.

Examples:

```
(%i1) hipow (y^3 * x^2 + x * y^4, x);
(%o1) 2
(%i2) hipow ((x + y)^5, x);
(%o2) 1
(%i3) hipow (expand ((x + y)^5), x);
(%o3) 5
(%i4) hipow ((x + y)^5, x + y);
(%o4) 5
(%i5) hipow (expand ((x + y)^5), x + y);
(%o5) 0
```

**intfaclim** Option variable

Default value: true

If **true**, maxima will give up factorization of integers if no factor is found after trial divisions and Pollard's rho method and factorization will not be complete.

When **intfaclim** is **false** (this is the case when the user calls **factor** explicitly), complete factorization will be attempted. **intfaclim** is set to **false** when factors are computed in **divisors**, **divsum** and **totient**.

Internal calls to **factor** respect the user-specified value of **intfaclim**. Setting **intfaclim** to **true** may reduce the time spent factoring large integers.



**keepfloat**

Option variable

Default value: `false`

When `keepfloat` is `true`, prevents floating point numbers from being rationalized when expressions which contain them are converted to canonical rational expression (CRE) form.

Note that the function `solve` and those functions calling it (`eigenvalues`, for example) currently ignore this flag, converting floating point numbers anyway.

Examples:

```
(%i1) rat(x/2.0);

'rat' replaced 0.5 by 1/2 = 0.5
(%o1)/R/
x
-
2

(%i2) rat(x/2.0), keepfloat;

(%o2)/R/
0.5 x

solve ignores keepfloat:
(%i3) solve(1.0-x,x), keepfloat;

'rat' replaced 1.0 by 1/1 = 1.0
(%o3)
[x = 1]
```

**lopow** (*expr*, *x*)

Function

Returns the lowest exponent of *x* which explicitly appears in *expr*. Thus

```
(%i1) lopow ((x+y)^2 + (x+y)^a, x+y);
(%o1)
min(a, 2)
```

**lratsubst** (*L*, *expr*)

Function

is analogous to `subst` (*L*, *expr*) except that it uses `ratsubst` instead of `subst`.

The first argument of `lratsubst` is an equation or a list of equations identical in format to that accepted by `subst`. The substitutions are made in the order given by the list of equations, that is, from left to right.

`load ("lrats")` loads `fullratsubst` and `lratsubst`.

Examples:

- ```
(%i1) load ("lrats")$
```
- `subst` can carry out multiple substitutions. `lratsubst` is analogous to `subst`.


```
(%i2) subst ([a = b, c = d], a + c);
(%o2)
d + b
(%i3) lratsubst ([a^2 = b, c^2 = d], (a + e)*c*(a + c));
(%o3)
(d + a c) e + a d + b c
```
 - If only one substitution is desired, then a single equation may be given as first argument.


```
(%i4) lratsubst (a^2 = b, a^3);
(%o4)
a b
```

modulus

Option variable

Default value: `false`

When `modulus` is a positive number *p*, operations on rational numbers (as returned by `rat` and related functions) are carried out modulo *p*, using the so-called "balanced" modulus system in which *n* modulo *p* is defined as an integer *k* in $[-(p-1)/2, \dots, 0, \dots, (p-1)/2]$ when *p* is odd, or $[-(p/2 - 1), \dots, 0, \dots, p/2]$ when *p* is even, such that *a* *p* + *k* equals *n* for some integer *a*.

If *expr* is already in canonical rational expression (CRE) form when *modulus* is reset, then you may need to re-rat *expr*, e.g., `expr: rat (ratdisrep (expr))`, in order to get correct results.

Typically *modulus* is set to a prime number. If *modulus* is set to a positive non-prime integer, this setting is accepted, but a warning message is displayed. Maxima signals an error, when zero or a negative integer is assigned to *modulus*.

Examples:

```
(%i1) modulus:7;
(%o1)
7
(%i2) polymod([0,1,2,3,4,5,6,7]);
(%o2) [0, 1, 2, 3, - 3, - 2, - 1, 0]
(%i3) modulus:false;
(%o3) false
(%i4) poly:x^6+x^2+1;
(%o4)
6      2
x  + x  + 1
(%i5) factor(poly);
(%o5)
6      2
x  + x  + 1
(%i6) modulus:13;
(%o6)
13
(%i7) factor(poly);
(%o7)
2      4      2
(x  + 6) (x  - 6 x  - 2)
(%i8) polymod(%);
(%o8)
6      2
x  + x  + 1
```

num (*expr*) Function
Returns the numerator of *expr* if it is a ratio. If *expr* is not a ratio, *expr* is returned.
num evaluates its argument.

polydecomp (*p*, *x*) Function
Decomposes the polynomial *p* in the variable *x* into the functional composition of polynomials in *x*. *polydecomp* returns a list [*p*₁, ..., *p*_{*n*}] such that

$$\text{lambda}([x], p_1)(\text{lambda}([x], p_2)(\dots(\text{lambda}([x], p_n)(x))\dots))$$

is equal to *p*. The degree of *p*_{*i*} is greater than 1 for *i* less than *n*.

Such a decomposition is not unique.

Examples:

```
(%i1) polydecomp (x^210, x);
(%o1)
7      5      3      2
[x , x , x , x ]
(%i2) p : expand (subst (x^3 - x - 1, x, x^2 - a));
(%o2)
6      4      3      2
x  - 2 x  - 2 x  + x  + 2 x - a + 1
(%i3) polydecomp (p, x);
(%o3)
2      3
[x  - a, x  - x - 1]
```

The following function composes *L* = [*e*₁, ..., *e*_{*n*}] as functions in *x*; it is the inverse of *polydecomp*:

```
compose (L, x) :=
  block ([r : x], for e in L do r : subst (e, x, r), r) $
```

Re-express above example using *compose*:

```
(%i3) polydecomp (compose ([x^2 - a, x^3 - x - 1], x), x);
```

```
(%o3) [x^2 - a, x^3 - x - 1]
```

Note that though `compose (polydecomp (p, x), x)` always returns p (unexpanded), `polydecomp (compose ([p_1, ..., p_n], x), x)` does *not* necessarily return $[p_1, \dots, p_n]$:

```
(%i4) polydecomp (compose ([x^2 + 2*x + 3, x^2], x), x);
```

```
(%o4) [x^2 + 2, x^2 + 1]
```

```
(%i5) polydecomp (compose ([x^2 + x + 1, x^2 + x + 1], x), x);
```

```
(%o5) [-----, -----, 2 x + 1]
        4          2
```

polymod (p)

Function

polymod (p, m)

Function

Converts the polynomial p to a modular representation with respect to the current modulus which is the value of the variable `modulus`.

`polymod (p, m)` specifies a modulus m to be used instead of the current value of `modulus`.

See `modulus`.

powers ($expr, x$)

Function

Gives the powers of x occurring in $expr$.

`load (powers)` loads this function.

quotient (p_1, p_2)

Function

quotient ($p_1, p_2, x_1, \dots, x_n$)

Function

Returns the polynomial p_1 divided by the polynomial p_2 . The arguments x_1, \dots, x_n are interpreted as in `ratvars`.

`quotient` returns the first element of the two-element list returned by `divide`.

rat ($expr$)

Function

rat ($expr, x_1, \dots, x_n$)

Function

Converts $expr$ to canonical rational expression (CRE) form by expanding and combining all terms over a common denominator and cancelling out the greatest common divisor of the numerator and denominator, as well as converting floating point numbers to rational numbers within a tolerance of `ratepsilon`. The variables are ordered according to the x_1, \dots, x_n , if specified, as in `ratvars`.

`rat` does not generally simplify functions other than addition $+$, subtraction $-$, multiplication $*$, division $/$, and exponentiation to an integer power, whereas `ratsimp` does handle those cases. Note that atoms (numbers and variables) in CRE form are not the same as they are in the general form. For example, `rat(x)-x` yields `rat(0)` which has a different internal representation than 0.

When `ratfac` is `true`, `rat` yields a partially factored form for CRE. During rational operations the expression is maintained as fully factored as possible without an actual call to the factor package. This should always save space and may save some time in some computations. The numerator and denominator are still made relatively prime (e.g. `rat ((x^2 - 1)^4/(x + 1)^2)` yields $(x - 1)^4 (x + 1)^2$), but the factors within each part may not be relatively prime.

`ratprint` if `false` suppresses the printout of the message informing the user of the conversion of floating point numbers to rational numbers.

`keepfloat` if `true` prevents floating point numbers from being converted to rational numbers.

See also `ratexpand` and `ratsimp`.

Examples:

```
(%i1) ((x - 2*y)^4/(x^2 - 4*y^2)^2 + 1)*(y + a)*(2*y + x) /
      (4*y^2 + x^2);
```

```
(%o1)
      (y + a) (2 y + x) (x - 2 y)^4
      ----- + 1)
      2      2 2
      (x - 4 y )
      -----
      2      2
      4 y + x
```

```
(%i2) rat (% , y, a, x);
```

```
(%o2)/R/
      2 a + 2 y
      -----
      x + 2 y
```

ratalgdenom

Option variable

Default value: `true`

When `ratalgdenom` is `true`, allows rationalization of denominators with respect to radicals to take effect. `ratalgdenom` has an effect only when canonical rational expressions (CRE) are used in algebraic mode.

ratcoef (*expr*, *x*, *n*)

Function

ratcoef (*expr*, *x*)

Function

Returns the coefficient of the expression x^n in the expression *expr*. If omitted, *n* is assumed to be 1.

The return value is free (except possibly in a non-rational sense) of the variables in *x*. If no coefficient of this type exists, 0 is returned.

`ratcoef` expands and rationally simplifies its first argument and thus it may produce answers different from those of `coeff` which is purely syntactic. Thus `ratcoef ((x + 1)/y + x, x)` returns $(y + 1)/y$ whereas `coeff` returns 1.

`ratcoef (expr, x, 0)`, viewing *expr* as a sum, returns a sum of those terms which do not contain *x*. Therefore if *x* occurs to any negative powers, `ratcoef` should not be used.

Since *expr* is rationally simplified before it is examined, coefficients may not appear quite the way they were envisioned.

Example:

```
(%i1) s: a*x + b*x + 5$
```

```
(%i2) ratcoef (s, a + b);
```

```
(%o2) x
```

ratdenom (*expr*)

Function

Returns the denominator of *expr*, after coercing *expr* to a canonical rational expression (CRE). The return value is a CRE.

expr is coerced to a CRE by `rat` if it is not already a CRE. This conversion may change the form of *expr* by putting all terms over a common denominator.

`denom` is similar, but returns an ordinary expression instead of a CRE. Also, `denom` does not attempt to place all terms over a common denominator, and thus some expressions which are considered ratios by `ratdenom` are not considered ratios by `denom`.

ratdenomdivide

Option variable

Default value: `true`

When `ratdenomdivide` is `true`, `ratexpand` expands a ratio in which the numerator is a sum into a sum of ratios, all having a common denominator. Otherwise, `ratexpand`

collapses a sum of ratios into a single ratio, the numerator of which is the sum of the numerators of each ratio.

Examples:

```
(%i1) expr: (x^2 + x + 1)/(y^2 + 7);
```

$$\frac{x^2 + x + 1}{y^2 + 7}$$

```
(%o1)
```

```
(%i2) ratdenomdivide: true$
```

```
(%i3) ratexpand (expr);
```

$$\frac{x^2}{y^2 + 7} + \frac{x}{y^2 + 7} + \frac{1}{y^2 + 7}$$

```
(%o3)
```

```
(%i4) ratdenomdivide: false$
```

```
(%i5) ratexpand (expr);
```

$$\frac{x^2 + x + 1}{y^2 + 7}$$

```
(%o5)
```

```
(%i6) expr2: a^2/(b^2 + 3) + b/(b^2 + 3);
```

$$\frac{b^2}{b^2 + 3} + \frac{a}{b^2 + 3}$$

```
(%o6)
```

```
(%i7) ratexpand (expr2);
```

$$\frac{b^2 + a}{b^2 + 3}$$

```
(%o7)
```

ratdiff (*expr*, *x*) Function

Differentiates the rational expression *expr* with respect to *x*. *expr* must be a ratio of polynomials or a polynomial in *x*. The argument *x* may be a variable or a subexpression of *expr*.

The result is equivalent to **diff**, although perhaps in a different form. **ratdiff** may be faster than **diff**, for rational expressions.

ratdiff returns a canonical rational expression (CRE) if *expr* is a CRE. Otherwise, **ratdiff** returns a general expression.

ratdiff considers only the dependence of *expr* on *x*, and ignores any dependencies established by **depends**.

Example:

```
(%i1) expr: (4*x^3 + 10*x - 11)/(x^5 + 5);
```

$$\frac{4x^3 + 10x - 11}{x^5 + 5}$$

```
(%o1)
```

```
(%i2) ratdiff (expr, x);
```

$$8x^7 + 40x^5 - 55x^4 - 60x^2 - 50$$

```
(%o2)          - -----
                10      5
                x  + 10 x  + 25
(%i3) expr: f(x)^3 - f(x)^2 + 7;
                3      2
                f (x) - f (x) + 7
(%i4) ratdiff (expr, f(x));
                2
                3 f (x) - 2 f(x)
(%i5) expr: (a + b)^3 + (a + b)^2;
                3      2
                (b + a)  + (b + a)
(%i6) ratdiff (expr, a + b);
                2      2
                3 b  + (6 a + 2) b + 3 a  + 2 a
(%o6)
```

ratdisrep (*expr*) Function

Returns its argument as a general expression. If *expr* is a general expression, it is returned unchanged.

Typically **ratdisrep** is called to convert a canonical rational expression (CRE) into a general expression. This is sometimes convenient if one wishes to stop the "contagion", or use rational functions in non-rational contexts.

See also **totaldisrep**.

ratexpand (*expr*) Function
ratexpand Option variable

Expands *expr* by multiplying out products of sums and exponentiated sums, combining fractions over a common denominator, cancelling the greatest common divisor of the numerator and denominator, then splitting the numerator (if a sum) into its respective terms divided by the denominator.

The return value of **ratexpand** is a general expression, even if *expr* is a canonical rational expression (CRE).

The switch **ratexpand** if **true** will cause CRE expressions to be fully expanded when they are converted back to general form or displayed, while if it is **false** then they will be put into a recursive form. See also **ratsimp**.

When **ratdenomdivide** is **true**, **ratexpand** expands a ratio in which the numerator is a sum into a sum of ratios, all having a common denominator. Otherwise, **ratexpand** collapses a sum of ratios into a single ratio, the numerator of which is the sum of the numerators of each ratio.

When **keepfloat** is **true**, prevents floating point numbers from being rationalized when expressions which contain them are converted to canonical rational expression (CRE) form.

Examples:

```
(%i1) ratexpand ((2*x - 3*y)^3);
                3      2      2      3
                - 27 y  + 54 x y  - 36 x  y + 8 x
(%i2) expr: (x - 1)/(x + 1)^2 + 1/(x - 1);
                x - 1      1
                ----- + -----
                2      x - 1
                (x + 1)
(%i3) expand (expr);
                x      1      1
                ----- - ----- + -----
                2      2      x - 1
                x  + 2 x + 1  x  + 2 x + 1
(%o3)
```

```
(%i4) ratexpand (expr);
```

$$\frac{x^2}{x^3 + x^2 - x - 1} + \frac{x^2}{x^3 + x^2 - x - 1}$$

```
(%o4)
```

ratfac

Option variable

Default value: **false**

When **ratfac** is **true**, canonical rational expressions (CRE) are manipulated in a partially factored form.

During rational operations the expression is maintained as fully factored as possible without calling **factor**. This should always save space and may save time in some computations. The numerator and denominator are made relatively prime, for example **rat** $((x^2 - 1)^4 / (x + 1)^2)$ yields $(x - 1)^4 (x + 1)^2$, but the factors within each part may not be relatively prime.

In the **ctensr** (Component Tensor Manipulation) package, Ricci, Einstein, Riemann, and Weyl tensors and the scalar curvature are factored automatically when **ratfac** is **true**. *ratfac should only be set for cases where the tensorial components are known to consist of few terms.*

The **ratfac** and **ratweight** schemes are incompatible and may not both be used at the same time.

ratnumber (*expr*)

Function

Returns the numerator of *expr*, after coercing *expr* to a canonical rational expression (CRE). The return value is a CRE.

expr is coerced to a CRE by **rat** if it is not already a CRE. This conversion may change the form of *expr* by putting all terms over a common denominator.

num is similar, but returns an ordinary expression instead of a CRE. Also, **num** does not attempt to place all terms over a common denominator, and thus some expressions which are considered ratios by **ratnumber** are not considered ratios by **num**.

ratp (*expr*)

Function

Returns **true** if *expr* is a canonical rational expression (CRE) or extended CRE, otherwise **false**.

CRE are created by **rat** and related functions. Extended CRE are created by **taylor** and related functions.

ratprint

Option variable

Default value: **true**

When **ratprint** is **true**, a message informing the user of the conversion of floating point numbers to rational numbers is displayed.

ratsimp (*expr*)

Function

ratsimp (*expr*, *x_1*, ..., *x_n*)

Function

Simplifies the expression *expr* and all of its subexpressions, including the arguments to non-rational functions. The result is returned as the quotient of two polynomials in a recursive form, that is, the coefficients of the main variable are polynomials in the other variables. Variables may include non-rational functions (e.g., **sin** $(x^2 + 1)$) and the arguments to any such functions are also rationally simplified.

ratsimp (*expr*, *x_1*, ..., *x_n*) enables rational simplification with the specification of variable ordering as in **ratvars**.

When **ratsimpexpons** is **true**, **ratsimp** is applied to the exponents of expressions during simplification.

See also `ratexpand`. Note that `ratsimp` is affected by some of the flags which affect `ratexpand`.

Examples:

```
(%i1) sin (x/(x^2 + x)) = exp ((log(x) + 1)^2 - log(x)^2);
                                     2      2
(%o1)      sin(-----) = %e
                x      (log(x) + 1)  - log (x)
                2
                x  + x
(%i2) ratsimp (%);
                                     1      2
(%o2)      sin(-----) = %e x
                x + 1
(%i3) ((x - 1)^(3/2) - (x + 1)*sqrt(x - 1))/sqrt((x - 1)*(x + 1));
                                     3/2
                (x - 1)  - sqrt(x - 1) (x + 1)
(%o3)      -----
                sqrt((x - 1) (x + 1))
(%i4) ratsimp (%);
                2 sqrt(x - 1)
(%o4)      - ----
                2
                sqrt(x  - 1)
(%i5) x^(a + 1/a), ratsimpexpons: true;
                2
                a  + 1
                -----
                a
(%o5)      x
```

ratsimpexpons

Option variable

Default value: `false`

When `ratsimpexpons` is `true`, `ratsimp` is applied to the exponents of expressions during simplification.

radsubstflag

Option variable

Default value: `false`

`radsubstflag`, if `true`, permits `ratsubst` to make substitutions such as `u` for `sqrt (x)` in `x`.

ratsubst (a, b, c)

Function

Substitutes `a` for `b` in `c` and returns the resulting expression. `b` may be a sum, product, power, etc.

`ratsubst` knows something of the meaning of expressions whereas `subst` does a purely syntactic substitution. Thus `subst (a, x + y, x + y + z)` returns `x + y + z` whereas `ratsubst` returns `z + a`.

When `radsubstflag` is `true`, `ratsubst` makes substitutions for radicals in expressions which don't explicitly contain them.

`ratsubst` ignores the value `true` of the option variable `keepfloat`.

Examples:

```
(%i1) ratsubst (a, x*y^2, x^4*y^3 + x^4*y^8);
                3      4
(%o1)      a x  y  + a
(%i2) cos(x)^4 + cos(x)^3 + cos(x)^2 + cos(x) + 1;
```



```

              4          3          2
(%o2)      cos (x) + cos (x) + cos (x) + cos(x) + 1
(%i3) ratsubst (1 - sin(x)^2, cos(x)^2, %);
              4          2          2
(%o3)      sin (x) - 3 sin (x) + cos(x) (2 - sin (x)) + 3
(%i4) ratsubst (1 - cos(x)^2, sin(x)^2, sin(x)^4);
              4          2
(%o4)      cos (x) - 2 cos (x) + 1
(%i5) radsubstflag: false$
(%i6) ratsubst (u, sqrt(x), x);
(%o6)      x
(%i7) radsubstflag: true$
(%i8) ratsubst (u, sqrt(x), x);
              2
(%o8)      u

```

ratvars (x_1, \dots, x_n)

Function

ratvars ()

Function

ratvars

System variable

Declares main variables x_1, \dots, x_n for rational expressions. x_n , if present in a rational expression, is considered the main variable. Otherwise, $x_{[n-1]}$ is considered the main variable if present, and so on through the preceding variables to x_1 , which is considered the main variable only if none of the succeeding variables are present.

If a variable in a rational expression is not present in the **ratvars** list, it is given a lower priority than x_1 .

The arguments to **ratvars** can be either variables or non-rational functions such as $\sin(x)$.

The variable **ratvars** is a list of the arguments of the function **ratvars** when it was called most recently. Each call to the function **ratvars** resets the list. **ratvars** () clears the list.

ratvarswitch

Option variable

Default value: **true**

Maxima keeps an internal list in the Lisp variable **VARLIST** of the main variables for rational expressions. If **ratvarswitch** is **true**, every evaluation starts with a fresh list **VARLIST**. This is the default behavior. Otherwise, the main variables from previous evaluations are not removed from the internal list **VARLIST**.

The main variables, which are declared with the function **ratvars** are not affected by the option variable **ratvarswitch**.

Examples:

If **ratvarswitch** is **true**, every evaluation starts with a fresh list **VARLIST**.

```

(%i1) ratvarswitch:true$

(%i2) rat(2*x+y^2);
              2
(%o2)/R/      y  + 2 x
(%i3) :lisp varlist
($X $Y)

(%i3) rat(2*a+b^2);
              2
(%o3)/R/      b  + 2 a

(%i4) :lisp varlist
($A $B)

```

If **ratvarswitch** is **false**, the main variables from the last evaluation are still present.

```
(%i4) ratvarswitch:false$

(%i5) rat(2*x+y^2);
                                2
                                y  + 2 x
(%o5)/R/

(%i6) :lisp varlist
($X $Y)

(%i6) rat(2*a+b^2);
                                2
                                b  + 2 a
(%o6)/R/

(%i7) :lisp varlist
($A $B $X $Y)
```

ratweight ($x_1, w_1, \dots, x_n, w_n$) Function
ratweight () Function

Assigns a weight w_i to the variable x_i . This causes a term to be replaced by 0 if its weight exceeds the value of the variable `ratwtlvl` (default yields no truncation). The weight of a term is the sum of the products of the weight of a variable in the term times its power. For example, the weight of $3 x_1^2 x_2$ is $2 w_1 + w_2$. Truncation according to `ratwtlvl` is carried out only when multiplying or exponentiating canonical rational expressions (CRE).

`ratweight` () returns the cumulative list of weight assignments.

Note: The `ratfac` and `ratweight` schemes are incompatible and may not both be used at the same time.

Examples:

```
(%i1) ratweight (a, 1, b, 1);
(%o1) [a, 1, b, 1]
(%i2) expr1: rat(a + b + 1)$
(%i3) expr1^2;
                                2          2
                                b  + (2 a + 2) b + a  + 2 a + 1
(%o3)/R/

(%i4) ratwtlvl: 1$
(%i5) expr1^2;
                                2 b + 2 a + 1
(%o5)/R/
```

ratweights System variable

Default value: []

`ratweights` is the list of weights assigned by `ratweight`. The list is cumulative: each call to `ratweight` places additional items in the list.

`kill (ratweights)` and `save (ratweights)` both work as expected.

ratwtlvl Option variable

Default value: false

`ratwtlvl` is used in combination with the `ratweight` function to control the truncation of canonical rational expressions (CRE). For the default value of `false`, no truncation occurs.

remainder (p_1, p_2) Function
remainder ($p_1, p_2, x_1, \dots, x_n$) Function

Returns the remainder of the polynomial p_1 divided by the polynomial p_2 . The arguments x_1, \dots, x_n are interpreted as in `ratvars`.

`remainder` returns the second element of the two-element list returned by `divide`.

resultant (*p-1*, *p-2*, *x*)

Function

The function **resultant** computes the resultant of the two polynomials *p-1* and *p-2*, eliminating the variable *x*. The resultant is a determinant of the coefficients of *x* in *p-1* and *p-2*, which equals zero if and only if *p-1* and *p-2* have a non-constant factor in common.

If *p-1* or *p-2* can be factored, it may be desirable to call **factor** before calling **resultant**. The option variable **resultant** controls which algorithm will be used to compute the resultant. See the option variable **resultant**.

The function **bezout** takes the same arguments as **resultant** and returns a matrix. The determinant of the return value is the desired resultant.

Examples:

```
(%i1) resultant(2*x^2+3*x+1, 2*x^2+x+1, x);
(%o1)
8
(%i2) resultant(x+1, x+1, x);
(%o2)
0
(%i3) resultant((x+1)*x, (x+1), x);
(%o3)
0
(%i4) resultant(a*x^2+b*x+1, c*x + 2, x);
(%o4)
2
c - 2 b c + 4 a
(%i5) bezout(a*x^2+b*x+1, c*x+2, x);
(%o5)
[ 2 a 2 b - c ]
[
[ c 2 ]
(%i6) determinant(%);
(%o6)
4 a - (2 b - c) c
```

resultant

Option variable

Default value: **subres**

The option variable **resultant** controls which algorithm will be used to compute the resultant with the function **resultant**. The possible values are:

subres for the subresultant polynomial remainder sequence (PRS) algorithm,
mod for the modular resultant algorithm, and
red for the reduced polynomial remainder sequence (PRS) algorithm.

On most problems the default value **subres** should be best. On some large degree univariate or bivariate problems **mod** may be better.

savefactors

Option variable

Default value: **false**

When **savefactors** is **true**, causes the factors of an expression which is a product of factors to be saved by certain functions in order to speed up later factorizations of expressions containing some of the same factors.

showratvars (*expr*)

Function

Returns a list of the canonical rational expression (CRE) variables in expression *expr*. See also **ratvars**.

sqfr (*expr*)

Function

is similar to **factor** except that the polynomial factors are "square-free." That is, they have factors only of degree one. This algorithm, which is also used by the first stage of **factor**, utilizes the fact that a polynomial has in common with its *n*'th derivative all

its factors of degree greater than n . Thus by taking greatest common divisors with the polynomial of the derivatives with respect to each variable in the polynomial, all factors of degree greater than 1 can be found.

Example:

```
(%i1) sqfr (4*x^4 + 4*x^3 - 3*x^2 - 4*x - 1);
              2      2
(%o1)          (2 x + 1) (x  - 1)
```

tellrat (p_1, \dots, p_n)

Function

tellrat ()

Function

Adds to the ring of algebraic integers known to Maxima the elements which are the solutions of the polynomials p_1, \dots, p_n . Each argument p_i is a polynomial with integer coefficients.

tellrat (x) effectively means substitute 0 for x in rational functions.

tellrat () returns a list of the current substitutions.

algebraic must be set to **true** in order for the simplification of algebraic integers to take effect.

Maxima initially knows about the imaginary unit **%i** and all roots of integers.

There is a command **untellrat** which takes kernels and removes **tellrat** properties.

When **tellrat**'ing a multivariate polynomial, e.g., **tellrat** ($x^2 - y^2$), there would be an ambiguity as to whether to substitute y^2 for x^2 or vice versa. Maxima picks a particular ordering, but if the user wants to specify which, e.g. **tellrat** ($y^2 = x^2$) provides a syntax which says replace y^2 by x^2 .

Examples:

```
(%i1) 10*(%i + 1)/(%i + 3^(1/3));
              10 (%i + 1)
(%o1) -----
              1/3
              %i + 3
(%i2) ev (ratdisrep (rat(%)), algebraic);
              2/3      1/3      2/3      1/3
(%o2) (4 3 - 2 3 - 4) %i + 2 3 + 4 3 - 2
(%i3) tellrat (1 + a + a^2);
              2
(%o3) [a + a + 1]
(%i4) 1/(a*sqrt(2) - 1) + a/(sqrt(3) + sqrt(2));
              1              a
(%o4) ----- + -----
              sqrt(2) a - 1  sqrt(3) + sqrt(2)
(%i5) ev (ratdisrep (rat(%)), algebraic);
              (7 sqrt(3) - 10 sqrt(2) + 2) a - 2 sqrt(2) - 1
(%o5) -----
              7
(%i6) tellrat (y^2 = x^2);
              2      2      2
(%o6) [y - x , a + a + 1]
```

totaldisrep ($expr$)

Function

Converts every subexpression of $expr$ from canonical rational expressions (CRE) to general form and returns the result. If $expr$ is itself in CRE form then **totaldisrep** is identical to **ratdisrep**.

totaldisrep may be useful for **ratdisrepping** expressions such as equations, lists, matrices, etc., which have some subexpressions in CRE form.

untellrat (x_1, \dots, x_n)

Function

Removes **tellrat** properties from x_1, \dots, x_n .

15 Special Functions

15.1 Introduction to Special Functions

Special function notation follows:

bessel_j (index, expr)	Bessel function, 1st kind
bessel_y (index, expr)	Bessel function, 2nd kind
bessel_i (index, expr)	Modified Bessel function, 1st kind
bessel_k (index, expr)	Modified Bessel function, 2nd kind
hankel_1 (v,z)	Hankel function of the 1st kind
hankel_2 (v,z)	Hankel function of the 2nd kind
struve_h (v,z)	Struve H function
struve_l (v,z)	Struve L function
assoc_legendre_p[v,u] (z)	Legendre function of degree v and order u
assoc_legendre_q[v,u] (z)	Legendre function, 2nd kind
%f[p,q] ([], [], expr)	Generalized Hypergeometric function
gamma()	Gamma function
gammagreek(a,z)	Incomplete gamma function
gammaincomplete(a,z)	Tail of incomplete gamma function
hypergeometric(l1, l2, z)	Hypergeometric function
slommel	
%m[u,k] (z)	Whittaker function, 1st kind
%w[u,k] (z)	Whittaker function, 2nd kind
erfc (z)	Complement of the erf function
expintegral_e (v,z)	Exponential integral E
expintegral_e1 (z)	Exponential integral E1
expintegral_ei (z)	Exponential integral Ei
expintegral_li (z)	Logarithmic integral Li
expintegral_si (z)	Exponential integral Si
expintegral_ci (z)	Exponential integral Ci
expintegral_shi (z)	Exponential integral Shi
expintegral_chi (z)	Exponential integral Chi
kelliptic (z)	Complete elliptic integral of the first kind (K)
parabolic_cylinder_d (v,z)	Parabolic cylinder D function

15.2 Bessel Functions

bessel_j (v, z)

Function

The Bessel function of the first kind of order v and argument z .

bessel_j is defined as

$$\sum_{k=0}^{\infty} \frac{(-1)^k \left(\frac{z}{2}\right)^{v+2k}}{k! \Gamma(v+k+1)}$$

although the infinite series is not used for computations.

bessel_y (*v*, *z*)

Function

The Bessel function of the second kind of order *v* and argument *z*.

bessel_y is defined as

$$\frac{\cos(\pi v) J_v(z) - J_{-v}(z)}{\sin(\pi v)}$$

when *v* is not an integer. When *v* is an integer *n*, the limit as *v* approaches *n* is taken.

bessel_i (*v*, *z*)

Function

The modified Bessel function of the first kind of order *v* and argument *z*.

bessel_i is defined as

$$\sum_{k=0}^{\infty} \frac{1}{k! \Gamma(v+k+1)} \left(\frac{z}{2}\right)^{v+2k}$$

although the infinite series is not used for computations.

bessel_k (*v*, *z*)

Function

The modified Bessel function of the second kind of order *v* and argument *z*.

bessel_k is defined as

$$\frac{\pi \csc(\pi v) (I_{-v}(z) - I_v(z))}{2}$$

when *v* is not an integer. If *v* is an integer *n*, then the limit as *v* approaches *n* is taken.

hankel_1 (*v*, *z*)

Function

The Hankel function of the first kind of order *v* and argument *z* (A&S 9.1.3). **hankel_1** is defined as

$$\text{bessel_j}(v, z) + \%i * \text{bessel_y}(v, z)$$

Maxima evaluates **hankel_1** numerically for a real order *v* and complex argument *z* in float precision. The numerical evaluation in bigfloat precision and for a complex order *v* is not supported.

When **besselexpand** is **true**, **hankel_1** is expanded in terms of elementary functions when the order *v* is half of an odd integer. See **besselexpand**.

Maxima knows the derivative of **hankel_1** wrt the argument *z*.

Examples:

Numerical evaluation:

```
(%i1) hankel_1(1,0.5);
(%o1) .2422684576748738 - 1.471472392670243 %i
(%i2) hankel_1(1,0.5+%i);
(%o2) - .2558287994862166 %i - 0.239575601883016
```

A complex order *v* is not supported. Maxima returns a noun form:

```
(%i3) hankel_1(%i,0.5+%i);
(%o3) hankel_1(%i, %i + 0.5)
```

Expansion of **hankel_1** when **besselexpand** is **true**:

```
(%i4) hankel_1(1/2,z),besselexpand:true;
(%o4) 
$$\frac{\sqrt{2} \sin(z) - \sqrt{2} \%i \cos(z)}{\sqrt{\pi} \sqrt{z}}$$

```

Derivative of **hankel_1** wrt the argument *z*. The derivative wrt the order *v* is not supported. Maxima returns a noun form:

```
(%i5) diff(hankel_1(v,z),z);
      hankel_1(v - 1, z) - hankel_1(v + 1, z)
(%o5) -----
      2

(%i6) diff(hankel_1(v,z),v);
      d
(%o6)  -- (hankel_1(v, z))
      dv
```

hankel_2 (*v*, *z*)

Function

The Hankel function of the second kind of order *v* and argument *z* (A&S 9.1.4). **hankel_2** is defined as

$$\text{bessel_j}(v, z) - \%i * \text{bessel_y}(v, z)$$

Maxima evaluates **hankel_2** numerically for a real order *v* and complex argument *z* in float precision. The numerical evaluation in bigfloat precision and for a complex order *v* is not supported.

When **besselexpand** is true, **hankel_2** is expanded in terms of elementary functions when the order *v* is half of an odd integer. See **besselexpand**.

Maxima knows the derivative of **hankel_2** wrt the argument *z*.

For examples see **hankel_1**.

besselexpand

Option variable

Default value: **false**

Controls expansion of the Bessel functions when the order is half of an odd integer. In this case, the Bessel functions can be expanded in terms of other elementary functions. When **besselexpand** is true, the Bessel function is expanded.

```
(%i1) besselexpand: false$
(%i2) bessel_j (3/2, z);
      3
(%o2)  bessel_j(-, z)
      2

(%i3) besselexpand: true$
(%i4) bessel_j (3/2, z);
      sin(z)  cos(z)
      sqrt(2) sqrt(z) (----- - -----)
      2      z
      z
(%o4)  -----
      sqrt(%pi)
```

scaled_bessel_i (*v*, *z*)

Function

The scaled modified Bessel function of the first kind of order *v* and argument *z*. That is, $\text{scaled_bessel}_i(v, z) = \exp(-\text{abs}(z)) * \text{bessel}_i(v, z)$. This function is particularly useful for calculating bessel_i for large *z*, which is large. However, maxima does not otherwise know much about this function. For symbolic work, it is probably preferable to work with the expression $\exp(-\text{abs}(z)) * \text{bessel}_i(v, z)$.

scaled_bessel_i0 (*z*)

Function

Identical to **scaled_bessel_i**(0, *z*).

scaled_bessel_i1 (*z*)

Function

Identical to **scaled_bessel_i**(1, *z*).

%s [*u*, *v*] (*z*)

Function

Lommel's little $s[u, v](z)$ function. Probably Gradshteyn & Ryzhik 8.570.1.

15.3 Airy Functions

The Airy functions $\text{Ai}(x)$ and $\text{Bi}(x)$ are defined in Abramowitz and Stegun, *Handbook of Mathematical Functions*, Section 10.4.

$y = \text{Ai}(x)$ and $y = \text{Bi}(x)$ are two linearly independent solutions of the Airy differential equation $\text{diff}(y(x), x, 2) - x y(x) = 0$.

If the argument x is a real or complex floating point number, the numerical value of the function is returned.

airy_ai (x) Function

The Airy function $\text{Ai}(x)$. (A&S 10.4.2)

The derivative $\text{diff}(\text{airy_ai}(x), x)$ is $\text{airy_dai}(x)$.

See also `airy_bi`, `airy_dai`, `airy_dbi`.

airy_dai (x) Function

The derivative of the Airy function Ai `airy_ai`(x).

See `airy_ai`.

airy_bi (x) Function

The Airy function $\text{Bi}(x)$. (A&S 10.4.3)

The derivative $\text{diff}(\text{airy_bi}(x), x)$ is $\text{airy_dbi}(x)$.

See `airy_ai`, `airy_dbi`.

airy_dbi (x) Function

The derivative of the Airy Bi function `airy_bi`(x).

See `airy_ai` and `airy_bi`.

15.4 Gamma and factorial Functions

The gamma function and the related beta, psi and incomplete gamma functions are defined in Abramowitz and Stegun, *Handbook of Mathematical Functions*, Chapter 6.

bffac ($expr, n$) Function

Bigfloat version of the factorial (shifted gamma) function. The second argument is how many digits to retain and return, it's a good idea to request a couple of extra.

bfpsi ($n, z, fpprec$) Function

bfpsi0 ($z, fpprec$) Function

bfpsi is the polygamma function of real argument z and integer order n . **bfpsi0** is the digamma function. **bfpsi0** ($z, fpprec$) is equivalent to **bfpsi** ($0, z, fpprec$).

These functions return bigfloat values. *fpprec* is the bigfloat precision of the return value.

cbffac ($z, fpprec$) Function

Complex bigfloat factorial.

`load("bffac")` loads this function.

gamma (z) Function

The basic definition of the gamma function (A&S 6.1.1) is

$$\Gamma(z) = \int_0^{\infty} t^{z-1} e^{-t} dt$$

Maxima simplifies `gamma` for positive integer and positive and negative rational numbers. For half integral values the result is a rational number times `sqrt(%pi)`. The simplification for integer values is controlled by `factlim`. For integers greater than `factlim` the numerical result of the factorial function, which is used to calculate `gamma`, will overflow. The simplification for rational numbers is controlled by `gammalim` to avoid internal overflow. See `factlim` and `gammalim`.

For negative integers `gamma` is not defined.

Maxima can evaluate `gamma` numerically for real and complex values in float and bigfloat precision.

`gamma` has mirror symmetry.

When `gamma_expand` is `true`, Maxima expands `gamma` for arguments `z+n` and `z-n` where `n` is an integer.

Maxima knows the derivative of `gamma`.

Examples:

Simplification for integer, half integral, and rational numbers:

```
(%i1) map('gamma, [1,2,3,4,5,6,7,8,9]);
(%o1) [1, 1, 2, 6, 24, 120, 720, 5040, 40320]
(%i2) map('gamma, [1/2,3/2,5/2,7/2]);
(%o2) [sqrt(%pi),  $\frac{\sqrt{\pi}}{2}$ ,  $\frac{3\sqrt{\pi}}{4}$ ,  $\frac{15\sqrt{\pi}}{8}$ ]
(%i3) map('gamma, [2/3,5/3,7/3]);
(%o3) [gamma(-),  $\frac{2\gamma(-)}{3}$ ,  $\frac{4\gamma(-)}{9}$ ]
```

Numerical evaluation for real and complex values:

```
(%i4) map('gamma, [2.5,2.5b0]);
(%o4) [1.329340388179137, 1.3293403881791370205b0]
(%i5) map('gamma, [1.0+%i,1.0b0+%i]);
(%o5) [0.498015668118356 - .1549498283018107 %i,
4.9801566811835604272b-1 - 1.5494982830181068513b-1 %i]
```

`gamma` has mirror symmetry:

```
(%i6) declare(z,complex)$
(%i7) conjugate(gamma(z));
(%o7) gamma(conjugate(z))
```

Maxima expands `gamma(z+n)` and `gamma(z-n)`, when `gamma_expand` is `true`:

```
(%i8) gamma_expand:true$
(%i9) [gamma(z+1),gamma(z-1),gamma(z+2)/gamma(z+1)];
(%o9) [z gamma(z),  $\frac{\gamma(z)}{z-1}$ , z + 1]
```

The derivative of `gamma`:

```
(%i10) diff(gamma(z),z);
(%o10)  $\psi(z) \gamma(z)$ 
```

See also `makegamma`.

The Euler-Mascheroni constant is `%gamma`.

log_gamma (z)

The natural logarithm of the gamma function.

Function

gamma_greek (*a*, *z*)

Function

The lower incomplete gamma function (A&S 6.5.2):

$$\gamma(a, z) = \int_0^z t^{a-1} e^{-t} dt$$

See also **gamma_incomplete** (upper incomplete gamma function).

gamma_incomplete (*a*, *z*)

Function

The incomplete upper gamma function A&S 6.5.3:

$$\Gamma(a, z) = \int_z^\infty t^{a-1} e^{-t} dt$$

See also **gamma_expand** for controlling how **gamma_incomplete** is expressed in terms of elementary functions and **erfc**.

Also see the related functions **gamma_incomplete_regularized** and **gamma_incomplete_generalized**.

gamma_incomplete_regularized (*a*, *z*)

Function

The regularized incomplete upper gamma function A&S 6.5.1:

$$Q(a, z) = \frac{\Gamma(a, z)}{\Gamma(a)}$$

See also **gamma_expand** for controlling how **gamma_incomplete** is expressed in terms of elementary functions and **erfc**.

Also see **gamma_incomplete**.

gamma_incomplete_generalized (*a*, *z1*, *z1*)

Function

The generalized incomplete gamma function.

$$\Gamma(a, z_1, z_2) = \int_{z_1}^{z_2} t^{a-1} e^{-t} dt$$

Also see **gamma_incomplete** and **gamma_incomplete_regularized**.

gamma_expand

Option variable

Default value: **false**

gamma_expand controls expansion of **gamma_incomplete**. When **gamma_expand** is **true**, **gamma_incomplete(v,z)** is expanded in terms of **z**, **exp(z)**, and **erfc(z)** when possible.

```
(%i1) gamma_incomplete(2,z);
(%o1)                                     gamma_incomplete(2, z)
(%i2) gamma_expand:true;
(%o2)                                     true
(%i3) gamma_incomplete(2,z);
(%o3)                                     - z
      (z + 1) %e
(%i4) gamma_incomplete(3/2,z);
(%o4)                                     - z      sqrt(%pi) erfc(sqrt(z))
      sqrt(z) %e      + -----
                          2
```

gammalim

Option variable

Default value: 1000000

gammalim controls simplification of the gamma function for integral and rational number arguments. If the absolute value of the argument is not greater than **gammalim**, then simplification will occur. Note that the **factlim** switch controls simplification of the result of **gamma** of an integer argument as well.

makegamma (*expr*)

Function

Transforms instances of binomial, factorial, and beta functions in *expr* into gamma functions.

See also **makefact**.

beta (*a*, *b*)

Function

The beta function is defined as $\text{gamma}(a) \text{gamma}(b) / \text{gamma}(a+b)$ (A&S 6.2.1).

Maxima simplifies the beta function for positive integers and rational numbers, which sum to an integer. When **beta_args_sum_to_integer** is true, Maxima simplifies also general expressions which sum to an integer.

For *a* or *b* equal to zero the beta function is not defined.

In general the beta function is not defined for negative integers as an argument. The exception is for $a=-n$, *n* a positive integer and *b* a positive integer with $b \leq n$, it is possible to define an analytic continuation. Maxima gives for this case a result.

When **beta_expand** is true, expressions like **beta(a+n,b)** and **beta(a-n,b)** or **beta(a,b+n)** and **beta(a,b-n)** with *n* an integer are simplified.

Maxima can evaluate the beta function for real and complex values in float and bigfloat precision. For numerical evaluation Maxima uses **log_gamma**:

$$- \log_{\text{gamma}}(b + a) + \log_{\text{gamma}}(b) + \log_{\text{gamma}}(a)$$

%e

Maxima knows that the beta function is symmetric and has mirror symmetry.

Maxima knows the derivatives of the beta function with respect to *a* or *b*.

To express the beta function as a ratio of gamma functions see **makegamma**.

Examples:

Simplification, when one of the arguments is an integer:

```
(%i1) [beta(2,3),beta(2,1/3),beta(2,a)];
(%o1) [1/12, 9/4, 1/(a(a+1))]
```

Simplification for two rational numbers as arguments which sum to an integer:

```
(%i2) [beta(1/2,5/2),beta(1/3,2/3),beta(1/4,3/4)];
(%o2) [3/8 %pi, 2/8 %pi, sqrt(2)/sqrt(3) %pi]
```

When setting **beta_args_sum_to_integer** to true more general expression are simplified, when the sum of the arguments is an integer:

```
(%i3) beta_args_sum_to_integer:true$
(%i4) beta(a+1,-a+2);
(%o4) %pi (a - 1) a / (2 sin(%pi (2 - a)))
```

The possible results, when one of the arguments is a negative integer:

```
(%i5) [beta(-3,1),beta(-3,2),beta(-3,3)];
(%o5) [-1/3, -1/6, -1/3]
```

beta(a+n,b) or **beta(a-n)** with *n* an integer simplifies when **beta_expand** is true:

```
(%i6) beta_expand:true$
(%i7) [beta(a+1,b),beta(a-1,b),beta(a+1,b)/beta(a,b+1)];
(%o7) [a beta(a, b) / (b + a), beta(a, b) / (a - 1), a / b]
```

Beta is not defined, when one of the arguments is zero:

```
(%i7) beta(0,b);
beta: expected nonzero arguments; found 0, b
-- an error. To debug this try debugmode(true);
```

Numerical evaluation for real and complex arguments in float or bigfloat precision:

```
(%i8) beta(2.5,2.3);
(%o8) .08694748611299981

(%i9) beta(2.5,1.4+%i);
(%o9) 0.0640144950796695 - .1502078053286415 %i

(%i10) beta(2.5b0,2.3b0);
(%o10) 8.694748611299969b-2

(%i11) beta(2.5b0,1.4b0+%i);
(%o11) 6.401449507966944b-2 - 1.502078053286415b-1 %i
```

Beta is symmetric and has mirror symmetry:

```
(%i14) beta(a,b)-beta(b,a);
(%o14) 0
(%i15) declare(a,complex,b,complex)$
(%i16) conjugate(beta(a,b));
(%o16) beta(conjugate(a), conjugate(b))
```

The derivative of the beta function wrt a:

```
(%i17) diff(beta(a,b),a);
(%o17) - beta(a, b) (psi (b + a) - psi (a))
0 0
```

beta_incomplete (*a*, *b*, *z*)

Function

The basic definition of the incomplete beta function (A&S 6.6.1) is

$$\frac{z}{\int_0^z (1-t)^{b-1} t^{a-1} dt}$$

This definition is possible for $\text{realpart}(a) > 0$ and $\text{realpart}(b) > 0$ and $\text{abs}(z) < 1$. For other values the incomplete beta function can be defined through a generalized hypergeometric function:

$$\text{gamma}(a) \text{ hypergeometric_generalized}([a, 1 - b], [a + 1], z) z$$

(See functions.wolfram.com for a complete definition of the incomplete beta function.)

For negative integers $a = -n$ and positive integers $b = m$ with $m \leq n$ the incomplete beta function is defined through

$$z^{n-1} \sum_{k=0}^{m-1} \frac{(1-m)^k}{k! (n-k)} z^k$$

Maxima uses this definition to simplify **beta_incomplete** for *a* a negative integer.

For *a* a positive integer, **beta_incomplete** simplifies for any argument *b* and *z* and for *b* a positive integer for any argument *a* and *z*, with the exception of *a* a negative integer.

For $z = 0$ and $\text{realpart}(a) > 0$, **beta_incomplete** has the specific value zero. For $z=1$ and $\text{realpart}(b) > 0$, **beta_incomplete** simplifies to the beta function **beta(a,b)**.

Maxima evaluates `beta_incomplete` numerically for real and complex values in float or bigfloat precision. For the numerical evaluation an expansion of the incomplete beta function in continued fractions is used.

When the option variable `beta_expand` is `true`, Maxima expands expressions like `beta_incomplete(a+n,b,z)` and `beta_incomplete(a-n,b,z)` where `n` is a positive integer.

Maxima knows the derivatives of `beta_incomplete` with respect to the variables `a`, `b` and `z` and the integral with respect to the variable `z`.

Examples:

Simplification for `a` a positive integer:

```
(%i1) beta_incomplete(2,b,z);
```

$$\frac{1 - (1 - z)^b}{b(b + 1)}$$

```
(%o1)
```

Simplification for `b` a positive integer:

```
(%i2) beta_incomplete(a,2,z);
```

$$\frac{(a(1 - z) + 1)z^a}{a(a + 1)}$$

```
(%o2)
```

Simplification for `a` and `b` a positive integer:

```
(%i3) beta_incomplete(3,2,z);
```

$$\frac{(3(1 - z) + 1)z^3}{12}$$

```
(%o3)
```

`a` is a negative integer and `b ≤ (-a)`, Maxima simplifies:

```
(%i4) beta_incomplete(-3,1,z);
```

$$-\frac{1}{3z^3}$$

```
(%o4)
```

For the specific values `z = 0` and `z = 1`, Maxima simplifies:

```
(%i5) assume(a>0,b>0)$
(%i6) beta_incomplete(a,b,0);
(%o6) 0
(%i7) beta_incomplete(a,b,1);
(%o7) beta(a, b)
```

Numerical evaluation in float or bigfloat precision:

```
(%i8) beta_incomplete(0.25,0.50,0.9);
(%o8) 4.594959440269333
(%i9) fpprec:25$
(%i10) beta_incomplete(0.25,0.50,0.9b0);
(%o10) 4.594959440269324086971203b0
```

For `abs(z) > 1` `beta_incomplete` returns a complex result:

```
(%i11) beta_incomplete(0.25,0.50,1.7);
(%o11) 5.244115108584249 - 1.45518047787844 %i
```

Results for more general complex arguments:

```
(%i14) beta_incomplete(0.25+%i,1.0+%i,1.7+%i);
(%o14) 2.726960675662536 - .3831175704269199 %i
(%i15) beta_incomplete(1/2,5/4*%i,2.8+%i);
(%o15) 13.04649635168716 %i - 5.802067956270001
(%i16)
```

Expansion, when `beta_expand` is `true`:

```
(%i23) beta_incomplete(a+1,b,z),beta_expand:true;
```

```
(%o23)
```

$$\frac{a \operatorname{beta_incomplete}(a, b, z) (1-z)^b z^a}{b+a}$$

```
(%i24) beta_incomplete(a-1,b,z),beta_expand:true;
```

```
(%o24)
```

$$\frac{\operatorname{beta_incomplete}(a, b, z) (-b-a+1) (1-z)^b z^{a-1}}{1-a}$$

Derivative and integral for `beta_incomplete`:

```
(%i34) diff(beta_incomplete(a, b, z), z);
```

```
(%o34)
```

$$(1-z)^{b-1} z^{a-1}$$

```
(%i35) integrate(beta_incomplete(a, b, z), z);
```

```
(%o35)
```

$$\frac{(1-z)^b z^a}{b+a} + \operatorname{beta_incomplete}(a, b, z) z - \frac{a \operatorname{beta_incomplete}(a, b, z)}{b+a}$$

```
(%i36) factor(diff(% , z));
```

```
(%o36)
```

$$\operatorname{beta_incomplete}(a, b, z)$$

beta_incomplete_regularized (*a*, *b*, *z*)

Function

The regularized incomplete beta function A&S 6.6.2, defined as

$$\operatorname{beta_incomplete_regularized}(a, b, z) = \frac{\operatorname{beta_incomplete}(a, b, z)}{\operatorname{beta}(a, b)}$$

As for `beta_incomplete` this definition is not complete. See functions.wolfram.com for a complete definition of `beta_incomplete_regularized`.

`beta_incomplete_regularized` simplifies *a* or *b* a positive integer.

For $z=0$ and $\operatorname{realpart}(a) > 0$, `beta_incomplete_regularized` has the specific value 0. For $z=1$ and $\operatorname{realpart}(b) > 0$, `beta_incomplete_regularized` simplifies to 1.

Maxima can evaluate `beta_incomplete_regularized` for real and complex arguments in float and bigfloat precision.

When `beta_expand` is true, Maxima expands `beta_incomplete_regularized` for arguments $a+n$ or $a-n$, where *n* is an integer.

Maxima knows the derivatives of `beta_incomplete_regularized` with respect to the variables *a*, *b*, and *z* and the integral with respect to the variable *z*.

Examples:

Simplification for *a* or *b* a positive integer:

```
(%i1) beta_incomplete_regularized(2,b,z);
```

```
(%o1)
```

$$1 - (1-z)^b (b z + 1)$$

```
(%i2) beta_incomplete_regularized(a,2,z);
```

```
(%o2)
```

$$(a(1-z) + 1) z^a$$

```
(%i3) beta_incomplete_regularized(3,2,z);
```

```
(%o3) (3 (1 - z) + 1) z3
```

For the specific values $z = 0$ and $z = 1$, Maxima simplifies:

```
(%i4) assume(a>0,b>0)$
(%i5) beta_incomplete_regularized(a,b,0);
(%o5) 0
(%i6) beta_incomplete_regularized(a,b,1);
(%o6) 1
```

Numerical evaluation for real and complex arguments in float and bigfloat precision:

```
(%i7) beta_incomplete_regularized(0.12,0.43,0.9);
(%o7) .9114011367359802
(%i8) fpprec:32$
(%i9) beta_incomplete_regularized(0.12,0.43,0.9b0);
(%o9) 9.1140113673598075519946998779975b-1
(%i10) beta_incomplete_regularized(1+%i,3/3,1.5*i);
(%o10) .2865367499935403 %i - 0.122995963334684
(%i11) fpprec:20$
(%i12) beta_incomplete_regularized(1+%i,3/3,1.5b0*i);
(%o12) 2.8653674999354036142b-1 %i - 1.2299596333468400163b-1
```

Expansion, when `beta_expand` is true:

```
(%i13) beta_incomplete_regularized(a+1,b,z);
(%o13) beta_incomplete_regularized(a, b, z) -  $\frac{(1-z)^b z^a}{a \beta(a, b)}$ 
(%i14) beta_incomplete_regularized(a-1,b,z);
(%o14) beta_incomplete_regularized(a, b, z) -  $\frac{(1-z)^b z^{a-1}}{\beta(a, b) (b+a-1)}$ 
```

The derivative and the integral wrt z :

```
(%i15) diff(beta_incomplete_regularized(a,b,z),z);
(%o15)  $\frac{(1-z)^{b-1} z^{a-1}}{\beta(a, b)}$ 
(%i16) integrate(beta_incomplete_regularized(a,b,z),z);
(%o16) beta_incomplete_regularized(a, b, z) z -  $\frac{a (\beta(a, b) \frac{(1-z)^b z^a}{a \beta(a, b)} - \frac{1}{b+a})}{b+a}$ 
```

beta_incomplete_generalized ($a, b, z1, z2$)

Function

The basic definition of the generalized incomplete beta function is

$$\frac{z_2}{\int_{z_1}^{z_2} \frac{(1-t)^{b-1} t^{a-1}}{t} dt}$$

Maxima simplifies `beta_incomplete_regularized` for a and b a positive integer.

For $\text{realpart}(a) > 0$ and $z1 = 0$ or $z2 = 0$, Maxima simplifies `beta_incomplete_generalized` to `beta_incomplete`. For $\text{realpart}(b) > 0$ and $z1 = 1$ or $z2 = 1$, Maxima simplifies to an expression with `beta` and `beta_incomplete`.

Maxima evaluates `beta_incomplete_regularized` for real and complex values in float and bigfloat precision.

When `beta_expand` is true, Maxima expands `beta_incomplete_generalized` for $a + n$ and $a - n$, n a positive integer.

Maxima knows the derivative of `beta_incomplete_generalized` with respect to the variables a , b , $z1$, and $z2$ and the integrals with respect to the variables $z1$ and $z2$.

Examples:

Maxima simplifies `beta_incomplete_generalized` for a and b a positive integer:

```
(%i1) beta_incomplete_generalized(2,b,z1,z2);
              b              b
      (1 - z1) (b z1 + 1) - (1 - z2) (b z2 + 1)
(%o1) -----
              b (b + 1)
(%i2) beta_incomplete_generalized(a,2,z1,z2);
              a              a
      (a (1 - z2) + 1) z2 - (a (1 - z1) + 1) z1
(%o2) -----
              a (a + 1)
(%i3) beta_incomplete_generalized(3,2,z1,z2);
              2      2      2      2
      (1 - z1) (3 z1 + 2 z1 + 1) - (1 - z2) (3 z2 + 2 z2 + 1)
(%o3) -----
              12
```

Simplification for specific values $z1 = 0$, $z2 = 0$, $z1 = 1$, or $z2 = 1$:

```
(%i4) assume(a > 0, b > 0)$
(%i5) beta_incomplete_generalized(a,b,z1,0);
(%o5) - beta_incomplete(a, b, z1)

(%i6) beta_incomplete_generalized(a,b,0,z2);
(%o6) - beta_incomplete(a, b, z2)

(%i7) beta_incomplete_generalized(a,b,z1,1);
(%o7) beta(a, b) - beta_incomplete(a, b, z1)

(%i8) beta_incomplete_generalized(a,b,1,z2);
(%o8) beta_incomplete(a, b, z2) - beta(a, b)
```

Numerical evaluation for real arguments in float or bigfloat precision:

```
(%i9) beta_incomplete_generalized(1/2,3/2,0.25,0.31);
(%o9) .09638178086368676

(%i10) fpprec:32$
(%i10) beta_incomplete_generalized(1/2,3/2,0.25,0.31b0);
(%o10) 9.6381780863686935309170054689964b-2
```

Numerical evaluation for complex arguments in float or bigfloat precision:

```
(%i11) beta_incomplete_generalized(1/2+%i,3/2+%i,0.25,0.31);
(%o11) - .09625463003205376 %i - .003323847735353769

(%i12) fpprec:20$
(%i13) beta_incomplete_generalized(1/2+%i,3/2+%i,0.25,0.31b0);
(%o13) - 9.6254630032054178691b-2 %i - 3.3238477353543591914b-3
```

Expansion for $a + n$ or $a - n$, n a positive integer, when `beta_expand` is true:


```
(%i14) beta_expand:true$

(%i15) beta_incomplete_generalized(a+1,b,z1,z2);

      b   a           b   a
(1 - z1) z1 - (1 - z2) z2
(%o15) -----
      b + a
      a beta_incomplete_generalized(a, b, z1, z2)
      + -----
                        b + a
(%i16) beta_incomplete_generalized(a-1,b,z1,z2);

      beta_incomplete_generalized(a, b, z1, z2) (- b - a + 1)
(%o16) -----
                        1 - a
                        b   a - 1           b   a - 1
(1 - z2) z2 - (1 - z1) z1
      - -----
                        1 - a

Derivative wrt the variable z1 and integrals wrt z1 and z2:
(%i17) diff(beta_incomplete_generalized(a,b,z1,z2),z1);
      b - 1   a - 1
      - (1 - z1) z1
(%o17)
(%i18) integrate(beta_incomplete_generalized(a,b,z1,z2),z1);
(%o18) beta_incomplete_generalized(a, b, z1, z2) z1
      + beta_incomplete(a + 1, b, z1)
(%i19) integrate(beta_incomplete_generalized(a,b,z1,z2),z2);
(%o19) beta_incomplete_generalized(a, b, z1, z2) z2
      - beta_incomplete(a + 1, b, z2)
```

beta_expand

Option variable

Default value: false

When **beta_expand** is true, **beta(a,b)** and related functions are expanded for arguments like $a + n$ or $a - n$, where n is an integer.

beta_args_sum_to_integer

Option variable

Default value: false

When **beta_args_sum_to_integer** is true, Maxima simplifies **beta(a,b)**, when the arguments a and b sum to an integer.

psi [n](x)

Function

The derivative of $\log(\text{gamma}(x))$ of order $n+1$. Thus, **psi[0](x)** is the first derivative, **psi[1](x)** is the second derivative, etc.

Maxima does not know how, in general, to compute a numerical value of **psi**, but it can compute some exact values for rational args. Several variables control what range of rational args **psi** will return an exact value, if possible. See **maxpsiposint**, **maxpsinegint**, **maxpsifracnum**, and **maxpsifracdenom**. That is, x must lie between **maxpsinegint** and **maxpsiposint**. If the absolute value of the fractional part of x is rational and has a numerator less than **maxpsifracnum** and has a denominator less than **maxpsifracdenom**, **psi** will return an exact value.

The function **bfpsi** in the **bfac** package can compute numerical values.

maxpsiposint

Option variable

Default value: 20

maxpsiposint is the largest positive value for which **psi[n](x)** will try to compute an exact value.

maxpsinegint

Option variable

Default value: -10

maxpsinegint is the most negative value for which **psi**[*n*](*x*) will try to compute an exact value. That is if *x* is less than **maxnegint**, **psi**[*n*](*x*) will not return simplified answer, even if it could.

maxpsifracnum

Option variable

Default value: 6

Let *x* be a rational number less than one of the form *p/q*. If *p* is greater than **maxpsifracnum**, then **psi**[*n*](*x*) will not try to return a simplified value.

maxpsifracdenom

Option variable

Default value: 6

Let *x* be a rational number less than one of the form *p/q*. If *q* is greater than **maxpsifracdenom**, then **psi**[*n*](*x*) will not try to return a simplified value.

makefact (*expr*)

Function

Transforms instances of binomial, gamma, and beta functions in *expr* into factorials.

See also **makegamma**.

numfactor (*expr*)

Function

Returns the numerical factor multiplying the expression *expr*, which should be a single term.

content returns the greatest common divisor (gcd) of all terms in a sum.

```
(%i1) gamma (7/2);
(%o1)
15 sqrt(%pi)
-----
8
(%i2) numfactor (%);
15
--
8
```

15.5 Exponential Integrals

The Exponential Integral and related functions are defined in Abramowitz and Stegun, *Handbook of Mathematical Functions*, Chapter 5

expintegral_e1 (*z*)

Function

The Exponential Integral $E_1(z)$ (A&S 5.1.1)

expintegral_ei (*z*)

Function

The Exponential Integral $E_i(z)$ (A&S 5.1.2)

expintegral_li (*z*)

Function

The Exponential Integral $Li(z)$ (A&S 5.1.3)

expintegral_e (*n*,*z*)

Function

The Exponential Integral $E_n(z)$ (A&S 5.1.4)

expintegral_si (*z*)

Function

The Exponential Integral $Si(z)$ (A&S 5.2.1)

expintegral_ci (*z*)

Function

The Exponential Integral $Ci(z)$ (A&S 5.2.2)

expintegral_shi (*z*) Function
 The Exponential Integral Shi(*z*) (A&S 5.2.3)

expintegral_chi (*z*) Function
 The Exponential Integral Chi(*z*) (A&S 5.2.4)

expintrep Option variable
 Default value: false
 Change the representation of the Exponential Integral to gamma_incomplete, expintegral_e1, expintegral_ei, expintegral_li, expintegral_trig, expintegral_hyp

expintexpand Option variable
 Default value: false
 Expand the Exponential Integral $E[n](z)$ for half integral values in terms of Erfc or Erf and for positive integers in terms of Ei

15.6 Error Function

The Error function and related functions are defined in Abramowitz and Stegun, *Handbook of Mathematical Functions*, Chapter 7

erf (*z*) Function
 The Error Function erf(*z*) (A&S 7.1.1)
 See also flag **erfflag**.

erfc (*z*) Function
 The Complementary Error Function erfc(*z*) (A&S 7.1.2)
 $\text{erfc}(z) = 1 - \text{erf}(z)$

erfi (*z*) Function
 The Imaginary Error Function.
 $\text{erfi}(z) = -i * \text{erf}(i * z)$

erf_generalized (*z1,z2*) Function
 Generalized Error function Erf(*z1,z2*)

fresnel_c (*z*) Function
 The Fresnel Integral $C(z) = \int_0^z \cos((\pi/2)t^2) dt$. (A&S 7.3.1)
 The simplification fresnel_c(-*x*) = -fresnel_c(*x*) is applied when flag **trigsig** is true.
 The simplification fresnel_c(*i***x*) = *i**fresnel_c(*x*) is applied when flag **%iargs** is true.
 See flags **erf_representation** and **hypergeometric_representation**.

fresnel_s (*z*) Function
 The Fresnel Integral $S(z) = \int_0^z \sin((\pi/2)t^2) dt$. (A&S 7.3.2)
 The simplification fresnel_s(-*x*) = -fresnel_s(*x*) is applied when flag **trigsig** is true.
 The simplification fresnel_s(*i***x*) = *i**fresnel_s(*x*) is applied when flag **%iargs** is true.
 See flags **erf_representation** and **hypergeometric_representation**.

erf_representation Option variable
 Default value: false
 When T erfc, erfi, erf_generalized, fresnel_s and fresnel_c are transformed to erf.

hypergeometric_representation Option variable
 Default value: false
 Enables transformation to a Hypergeometric representation for fresnel_s and fresnel_c

15.7 Struve Functions

The Struve functions are defined in Abramowitz and Stegun, *Handbook of Mathematical Functions*, Chapter 12.

struve_h (<i>v</i> , <i>z</i>)	Function
The Struve Function H of order <i>v</i> and argument <i>z</i> . (A&S 12.1.1)	
struve_l (<i>v</i> , <i>z</i>)	Function
The Modified Struve Function L of order <i>v</i> and argument <i>z</i> . (A&S 12.2.1)	

15.8 Hypergeometric Functions

The Hypergeometric Functions are defined in Abramowitz and Stegun, *Handbook of Mathematical Functions*, Chapters 13 and 15.

Maxima has very limited knowledge of these functions. They can be returned from function `hgfred`.

%m [<i>k</i> , <i>u</i>] (<i>z</i>)	Function
Whittaker M function $M[k,u](z) = \exp(-z/2) * z^{(1/2+u)} * M(1/2+u-k, 1+2*u, z)$. (A&S 13.1.32)	
%w [<i>k</i> , <i>u</i>] (<i>z</i>)	Function
Whittaker W function. (A&S 13.1.33)	
%f [<i>p</i> , <i>q</i>] ([<i>a</i>],[<i>b</i>], <i>z</i>)	Function
The ${}_pF_q(a_1, a_2, \dots, a_p; b_1, b_2, \dots, b_q; z)$ hypergeometric function, where a a list of length p and b a list of length q .	

hypergeometric ([<i>a1</i> , ..., <i>ap</i>],[<i>b1</i> , ..., <i>bq</i>], <i>x</i>)	Function
The hypergeometric function. Unlike Maxima's %f hypergeometric function, the function hypergeometric is a simplifying function; also, hypergeometric supports complex double and big floating point evaluation. For the Gauss hypergeometric function, that is $p = 2$ and $q = 1$, floating point evaluation outside the unit circle is supported, but in general, it is not supported.	

When the option variable `expand_hypergeometric` is true (default is false) and one of the arguments **a1** through **ap** is a negative integer (a polynomial case), **hypergeometric** returns an expanded polynomial.

Examples:

```
(%i1) hypergeometric([], [], x);
(%o1) %e^x
```

Polynomial cases automatically expand when `expand_hypergeometric` is true:

```
(%i2) hypergeometric([-3], [7], x);
(%o2) hypergeometric([-3], [7], x)
```

```
(%i3) hypergeometric([-3], [7], x), expand_hypergeometric : true;
(%o3) -x^3/504+3*x^2/56-3*x/7+1
```

Both double float and big float evaluation is supported:

```
(%i4) hypergeometric([5.1], [7.1 + %i], 0.42);
(%o4) 1.346250786375334 - 0.0559061414208204 %i
(%i5) hypergeometric([5,6], [8], 5.7 - %i);
(%o5) .007375824009774946 - .001049813688578674 %i
(%i6) hypergeometric([5,6], [8], 5.7b0 - %i), fpprec : 30;
(%o6) 7.37582400977494674506442010824b-3
      - 1.04981368857867315858055393376b-3 %i
```

15.9 Parabolic Cylinder Functions

The Parabolic Cylinder Functions are defined in Abramowitz and Stegun, *Handbook of Mathematical Functions*, Chapter 19.

Maxima has very limited knowledge of these functions. They can be returned from function `hgfired`.

parabolic_cylinder_d (v, z) Function
 The parabolic cylinder function `parabolic_cylinder_d(v,z)`. (A&S 19.3.1)

15.10 Functions and Variables for Special Functions

specint ($\exp(-s*t) * \text{expr}, t$) Function
 Compute the Laplace transform of expr with respect to the variable t . The integrand expr may contain special functions.

The following special functions are handled by `specint`: incomplete gamma function, error functions (but not the error function `erfi`, it is easy to transform `erfi` e.g. to the error function `erf`), exponential integrals, bessel functions (including products of bessel functions), hankel functions, hermite and the laguerre polynomials.

Furthermore, `specint` can handle the hypergeometric function `%f[p,q]([],[],z)`, the whittaker function of the first kind `%m[u,k](z)` and of the second kind `%w[u,k](z)`.

The result may be in terms of special functions and can include unsimplified hypergeomtric functions.

When `laplace` fails to find a Laplace transform, `specint` is called. Because `laplace` knows more general rules for Laplace transforms, it is preferable to use `laplace` and not `specint`.

`demo(hypgeo)` displays several examples of Laplace transforms computed by `specint`.

Examples:

```
(%i1) assume (p > 0, a > 0)$
(%i2) specint (t^(1/2) * exp(-a*t/4) * exp(-p*t), t);
                                sqrt(%pi)
(%o2)  -----
                                a 3/2
                                2 (p + -)
                                4
(%i3) specint (t^(1/2) * bessel_j(1, 2 * a^(1/2) * t^(1/2))
              * exp(-p*t), t);
                                - a/p
                                sqrt(a) %e
(%o3)  -----
                                2
                                p
```

Examples for exponential integrals:

```
(%i4) assume(s>0,a>0,s-a>0)$
(%i5) ratsimp(specint(%e^(a*t)
                    *(log(a)+expintegral_e1(a*t))*%e^(-s*t),t));
                                log(s)
(%o5)  -----
                                s - a
(%i6) logarc:true$
(%i7) gamma_expand:true$
radcan(specint((cos(t)*expintegral_si(t)
```

```

                                -sin(t)*expintegral_ci(t))*%e^(-s*t),t));
                                log(s)
(%o8)  -----
                                2
                                s  + 1
ratsimp(specint((2*t*log(a)+2/a*sin(a*t)
                                -2*t*expintegral_ci(a*t))*%e^(-s*t),t));
                                2    2
                                log(s  + a )
(%o9)  -----
                                2
                                s

```

Results when using the expansion of `gamma_incomplete` and when changing the representation to `expintegral_e1`:

```

(%i10) assume(s>0)$
(%i11) specint(1/sqrt(%pi*t)*unit_step(t-k)*%e^(-s*t),t);
                                1
                                gamma_incomplete(-, k s)
                                2
(%o11)  -----
                                sqrt(%pi) sqrt(s)

(%i12) gamma_expand:true$
(%i13) specint(1/sqrt(%pi*t)*unit_step(t-k)*%e^(-s*t),t);
                                erfc(sqrt(k) sqrt(s))
(%o13)  -----
                                sqrt(s)

(%i14) expintrep:expintegral_e1$
(%i15) ratsimp(specint(1/(t+a)^2*%e^(-s*t),t));
                                a s
                                a s %e    expintegral_e1(a s) - 1
(%o15)  -----
                                a

```

hgfred (*a*, *b*, *t*)

Function

Simplify the generalized hypergeometric function in terms of other, simpler, forms. *a* is a list of numerator parameters and *b* is a list of the denominator parameters.

If `hgfred` cannot simplify the hypergeometric function, it returns an expression of the form `%f[p,q]([a],[b],x)` where *p* is the number of elements in *a*, and *q* is the number of elements in *b*. This is the usual `pFq` generalized hypergeometric function.

```

(%i1) assume(not(equal(z,0)));
(%o1) [notequal(z, 0)]
(%i2) hgfred([v+1/2],[2*v+1],2*%i*z);
                                v/2
                                4    bessel_j(v, z) gamma(v + 1) %e    %i z
(%o2)  -----
                                v
                                z

(%i3) hgfred([1,1],[2],z);
                                log(1 - z)
(%o3)  -----
                                z

(%i4) hgfred([a,a+1/2],[3/2],z^2);

```

$$\begin{array}{l}
 (\%o4) \qquad \frac{(z+1)^{1-2a} - (1-z)^{1-2a}}{2(1-2a)z}
 \end{array}$$

It can be beneficial to load orthopoly too as the following example shows. Note that L is the generalized Laguerre polynomial.

```
(%i5) load(orthopoly)$
(%i6) hgfred([-2],[a],z);
```

$$\begin{array}{l}
 (\%o6) \qquad \frac{(a-1)^2 L_2(z)}{a(a+1)}
 \end{array}$$

```
(%i7) ev(%);
```

$$\begin{array}{l}
 (\%o7) \qquad \frac{z^2}{a(a+1)} - \frac{2z}{a} + 1
 \end{array}$$

lambert_w (z) Function
 The principal branch of Lambert's W function $W(z)$, the solution of $z = W(z) * \exp(W(z))$. (DLMF 4.13)

generalized_lambert_w (k, z) Function
 The k -th branch of Lambert's W function $W(z)$, the solution of $z = W(z) * \exp(W(z))$. (DLMF 4.13)
 The principal branch, denoted $W_p(z)$ in DLMF, is `lambert_w(z) = generalized_lambert_w(0,z)`.
 The other branch with real values, denoted $W_m(z)$ in DLMF, is `generalized_lambert_w(-1,z)`.

nzeta (z) Function
 The Plasma Dispersion Function `nzeta(z) = %i*sqrt(%pi)*exp(-z^2)*(1-erf(-%i*z))`

nzetar (z) Function
 Returns `realpart(nzeta(z))`.

nzetai (z) Function
 Returns `imagpart(nzeta(z))`.

16 Elliptic Functions

16.1 Introduction to Elliptic Functions and Integrals

Maxima includes support for Jacobian elliptic functions and for complete and incomplete elliptic integrals. This includes symbolic manipulation of these functions and numerical evaluation as well. Definitions of these functions and many of their properties can be found in Abramowitz and Stegun, Chapter 16–17. As much as possible, we use the definitions and relationships given there.

In particular, all elliptic functions and integrals use the parameter m instead of the modulus k or the modular angle α . This is one area where we differ from Abramowitz and Stegun who use the modular angle for the elliptic functions. The following relationships are true:

$$m = k^2$$

and

$$k = \sin \alpha$$

The elliptic functions and integrals are primarily intended to support symbolic computation. Therefore, most of derivatives of the functions and integrals are known. However, if floating-point values are given, a floating-point result is returned.

Support for most of the other properties of elliptic functions and integrals other than derivatives has not yet been written.

Some examples of elliptic functions:

```
(%i1) jacobi_sn (u, m);
(%o1)          jacobi_sn(u, m)
(%i2) jacobi_sn (u, 1);
(%o2)          tanh(u)
(%i3) jacobi_sn (u, 0);
(%o3)          sin(u)
(%i4) diff (jacobi_sn (u, m), u);
(%o4)          jacobi_cn(u, m) jacobi_dn(u, m)
(%i5) diff (jacobi_sn (u, m), m);
(%o5) jacobi_cn(u, m) jacobi_dn(u, m)
```

$$\frac{\text{elliptic_e}(\text{asin}(\text{jacobi_sn}(u, m)), m)}{(u - \frac{\text{jacobi_cn}(u, m) \text{jacobi_sn}(u, m)}{2(1 - m)})/(2m)}$$

Some examples of elliptic integrals:

```
(%i1) elliptic_f (phi, m);
(%o1)          elliptic_f(phi, m)
(%i2) elliptic_f (phi, 0);
(%o2)          phi
(%i3) elliptic_f (phi, 1);
(%o3)          log(tan(--- + ---))
                        phi   %pi
                        2     4
(%i4) elliptic_e (phi, 1);
(%o4)          sin(phi)
(%i5) elliptic_e (phi, 0);
```

```

(%o5)                                phi
(%i6) elliptic_kc (1/2);
                                1
                                elliptic_kc(-)
                                2
(%i7) makegamma (%);
                                2 1
                                gamma (-)
                                4
(%o7) -----
                                4 sqrt(%pi)
(%i8) diff (elliptic_f (phi, m), phi);
                                1
(%o8) -----
                                2
                                sqrt(1 - m sin (phi))
(%i9) diff (elliptic_f (phi, m), m);
                                elliptic_e(phi, m) - (1 - m) elliptic_f(phi, m)
(%o9) (-----)
                                m

                                cos(phi) sin(phi)
                                - -----)/(2 (1 - m))
                                2
                                sqrt(1 - m sin (phi))

```

Support for elliptic functions and integrals was written by Raymond Toy. It is placed under the terms of the General Public License (GPL) that governs the distribution of Maxima.

16.2 Functions and Variables for Elliptic Functions

jacobi_sn (<i>u</i> , <i>m</i>)	Function
The Jacobian elliptic function $sn(u, m)$.	
jacobi_cn (<i>u</i> , <i>m</i>)	Function
The Jacobian elliptic function $cn(u, m)$.	
jacobi_dn (<i>u</i> , <i>m</i>)	Function
The Jacobian elliptic function $dn(u, m)$.	
jacobi_ns (<i>u</i> , <i>m</i>)	Function
The Jacobian elliptic function $ns(u, m) = 1/sn(u, m)$.	
jacobi_sc (<i>u</i> , <i>m</i>)	Function
The Jacobian elliptic function $sc(u, m) = sn(u, m)/cn(u, m)$.	
jacobi_sd (<i>u</i> , <i>m</i>)	Function
The Jacobian elliptic function $sd(u, m) = sn(u, m)/dn(u, m)$.	
jacobi_nc (<i>u</i> , <i>m</i>)	Function
The Jacobian elliptic function $nc(u, m) = 1/cn(u, m)$.	
jacobi_cs (<i>u</i> , <i>m</i>)	Function
The Jacobian elliptic function $cs(u, m) = cn(u, m)/sn(u, m)$.	
jacobi_cd (<i>u</i> , <i>m</i>)	Function
The Jacobian elliptic function $cd(u, m) = cn(u, m)/dn(u, m)$.	

jacobi_nd (u, m)	Function
The Jacobian elliptic function $nc(u, m) = 1/cn(u, m)$.	
jacobi_ds (u, m)	Function
The Jacobian elliptic function $ds(u, m) = dn(u, m)/sn(u, m)$.	
jacobi_dc (u, m)	Function
The Jacobian elliptic function $dc(u, m) = dn(u, m)/cn(u, m)$.	
inverse_jacobi_sn (u, m)	Function
The inverse of the Jacobian elliptic function $sn(u, m)$.	
inverse_jacobi_cn (u, m)	Function
The inverse of the Jacobian elliptic function $cn(u, m)$.	
inverse_jacobi_dn (u, m)	Function
The inverse of the Jacobian elliptic function $dn(u, m)$.	
inverse_jacobi_ns (u, m)	Function
The inverse of the Jacobian elliptic function $ns(u, m)$.	
inverse_jacobi_sc (u, m)	Function
The inverse of the Jacobian elliptic function $sc(u, m)$.	
inverse_jacobi_sd (u, m)	Function
The inverse of the Jacobian elliptic function $sd(u, m)$.	
inverse_jacobi_nc (u, m)	Function
The inverse of the Jacobian elliptic function $nc(u, m)$.	
inverse_jacobi_cs (u, m)	Function
The inverse of the Jacobian elliptic function $cs(u, m)$.	
inverse_jacobi_cd (u, m)	Function
The inverse of the Jacobian elliptic function $cd(u, m)$.	
inverse_jacobi_nd (u, m)	Function
The inverse of the Jacobian elliptic function $nc(u, m)$.	
inverse_jacobi_ds (u, m)	Function
The inverse of the Jacobian elliptic function $ds(u, m)$.	
inverse_jacobi_dc (u, m)	Function
The inverse of the Jacobian elliptic function $dc(u, m)$.	

16.3 Functions and Variables for Elliptic Integrals

elliptic_f (*phi*, *m*)

Function

The incomplete elliptic integral of the first kind, defined as

$$\int_0^\phi \frac{d\theta}{\sqrt{1 - m \sin^2 \theta}}$$

See also [\[elliptic_e\]](#), page 230 and [\[elliptic_kc\]](#), page 230.

elliptic_e (*phi*, *m*)

Function

The incomplete elliptic integral of the second kind, defined as

$$\int_0^\phi \sqrt{1 - m \sin^2 \theta} d\theta$$

See also [\[elliptic_e\]](#), page 230 and [\[elliptic_ec\]](#), page 230.

elliptic_eu (*u*, *m*)

Function

The incomplete elliptic integral of the second kind, defined as

$$\int_0^u \operatorname{dn}(v, m) dv = \int_0^\tau \sqrt{\frac{1 - mt^2}{1 - t^2}} dt$$

where $\tau = \operatorname{sn}(u, m)$.

This is related to *elliptic_e* by

$$E(u, m) = E(\phi, m)$$

where $\phi = \sin^{-1} \operatorname{sn}(u, m)$.

See also [\[elliptic_e\]](#), page 230.

elliptic_pi (*n*, *phi*, *m*)

Function

The incomplete elliptic integral of the third kind, defined as

$$\int_0^\phi \frac{d\theta}{(1 - n \sin^2 \theta) \sqrt{1 - m \sin^2 \theta}}$$

Only the derivative with respect to *phi* is known by Maxima.

elliptic_kc (*m*)

Function

The complete elliptic integral of the first kind, defined as

$$\int_0^{\frac{\pi}{2}} \frac{d\theta}{\sqrt{1 - m \sin^2 \theta}}$$

For certain values of *m*, the value of the integral is known in terms of *Gamma* functions. Use **makegamma** to evaluate them.

elliptic_ec (*m*)

Function

The complete elliptic integral of the second kind, defined as

$$\int_0^{\frac{\pi}{2}} \sqrt{1 - m \sin^2 \theta} d\theta$$

For certain values of *m*, the value of the integral is known in terms of *Gamma* functions. Use **makegamma** to evaluate them.

17 Limits

17.1 Functions and Variables for Limits

lhospitallim

Option variable

Default: 4

lhospitallim is the maximum number of times L'Hospital's rule is used in **limit**. This prevents infinite looping in cases like **limit (cot(x)/csc(x), x, 0)**.

limit (*expr*, *x*, *val*, *dir*)

Function

limit (*expr*, *x*, *val*)

Function

limit (*expr*)

Function

Computes the limit of *expr* as the real variable *x* approaches the value *val* from the direction *dir*. *dir* may have the value **plus** for a limit from above, **minus** for a limit from below, or may be omitted (implying a two-sided limit is to be computed).

limit uses the following special symbols: **inf** (positive infinity) and **minf** (negative infinity). On output it may also use **und** (undefined), **ind** (indefinite but bounded) and **infinity** (complex infinity).

infinity (complex infinity) is returned when the limit of the absolute value of the expression is positive infinity, but the limit of the expression itself is not positive infinity or negative infinity. This includes cases where the limit of the complex argument is a constant, as in **limit(log(x), x, minf)**, cases where the complex argument oscillates, as in **limit((-2)^x, x, inf)**, and cases where the complex argument is different for either side of a two-sided limit, as in **limit(1/x, x, 0)** and **limit(log(x), x, 0)**.

lhospitallim is the maximum number of times L'Hospital's rule is used in **limit**. This prevents infinite looping in cases like **limit (cot(x)/csc(x), x, 0)**.

tlimswitch when true will allow the **limit** command to use Taylor series expansion when necessary.

limsubst prevents **limit** from attempting substitutions on unknown forms. This is to avoid bugs like **limit (f(n)/f(n+1), n, inf)** giving 1. Setting **limsubst** to **true** will allow such substitutions.

limit with one argument is often called upon to simplify constant expressions, for example, **limit (inf-1)**.

example (limit) displays some examples.

For the method see Wang, P., "Evaluation of Definite Integrals by Symbolic Manipulation", Ph.D. thesis, MAC TR-92, October 1971.

limsubst

Option variable

Default value: false

prevents **limit** from attempting substitutions on unknown forms. This is to avoid bugs like **limit (f(n)/f(n+1), n, inf)** giving 1. Setting **limsubst** to **true** will allow such substitutions.

tlimit (*expr*, *x*, *val*, *dir*)

Function

tlimit (*expr*, *x*, *val*)

Function

tlimit (*expr*)

Function

Take the limit of the Taylor series expansion of **expr** in *x* at *val* from direction *dir*.

tlimswitch

Option variable

Default value: `true`

When `tlimswitch` is `true`, the `limit` command will use a Taylor series expansion if the limit of the input expression cannot be computed directly. This allows evaluation of limits such as `limit(x/(x-1)-1/log(x),x,1,plus)`. When `tlimswitch` is `false` and the limit of input expression cannot be computed directly, `limit` will return an unevaluated limit expression.

18 Differentiation

18.1 Functions and Variables for Differentiation

antid (*expr*, *x*, *u(x)*)

Function

Returns a two-element list, such that an antiderivative of *expr* with respect to *x* can be constructed from the list. The expression *expr* may contain an unknown function *u* and its derivatives.

Let *L*, a list of two elements, be the return value of **antid**. Then *L*[1] + 'integrate (*L*[2], *x*) is an antiderivative of *expr* with respect to *x*.

When **antid** succeeds entirely, the second element of the return value is zero. Otherwise, the second element is nonzero, and the first element is nonzero or zero. If **antid** cannot make any progress, the first element is zero and the second nonzero.

`load ("antid")` loads this function. The **antid** package also defines the functions **nonzeroandfreeof** and **linear**.

antid is related to **antidiff** as follows. Let *L*, a list of two elements, be the return value of **antid**. Then the return value of **antidiff** is equal to *L*[1] + 'integrate (*L*[2], *x*) where *x* is the variable of integration.

Examples:

```
(%i1) load ("antid")$
(%i2) expr: exp (z(x)) * diff (z(x), x) * y(x);
                                z(x)  d
(%o2)          y(x) %e      (--- (z(x)))
                                dx
(%i3) a1: antid (expr, x, z(x));
                                z(x)  z(x)  d
(%o3)          [y(x) %e      , - %e      (--- (y(x)))]
                                dx
(%i4) a2: antidiff (expr, x, z(x));
                                /
                                z(x)  [  z(x)  d
(%o4)          y(x) %e      - I %e      (--- (y(x))) dx
                                ]      dx
                                /
(%i5) a2 - (first(a1) + 'integrate (second (a1), x));
(%o5)          0
(%i6) antid (expr, x, y(x));
                                z(x)  d
(%o6)          [0, y(x) %e      (--- (z(x)))]
                                dx
(%i7) antidiff (expr, x, y(x));
                                /
                                [  z(x)  d
(%o7)          I y(x) %e      (--- (z(x))) dx
                                ]      dx
                                /
```

antidiff (*expr*, *x*, *u(x)*)

Function

Returns an antiderivative of *expr* with respect to *x*. The expression *expr* may contain an unknown function *u* and its derivatives.

When **antidiff** succeeds entirely, the resulting expression is free of integral signs (that is, free of the **integrate** noun). Otherwise, **antidiff** returns an expression which is partly or entirely within an integral sign. If **antidiff** cannot make any progress, the return value is entirely within an integral sign.

`load ("antid")` loads this function. The `antid` package also defines the functions `nonzeroandfreeof` and `linear`.

`antidiff` is related to `antid` as follows. Let L , a list of two elements, be the return value of `antid`. Then the return value of `antidiff` is equal to $L[1] + \text{'integrate}(L[2], x)$ where x is the variable of integration.

Examples:

```
(%i1) load ("antid")$
(%i2) expr: exp (z(x)) * diff (z(x), x) * y(x);
(%o2)
      z(x) d
      y(x) %e  (--- (z(x)))
              dx
(%i3) a1: antid (expr, x, z(x));
(%o3)
      z(x)      z(x) d
      [y(x) %e  , - %e  (--- (y(x)))]
              dx
(%i4) a2: antidiff (expr, x, z(x));
(%o4)
      z(x)      [ z(x) d
      y(x) %e  - I %e  (--- (y(x))) dx
              ]
              dx
(%i5) a2 - (first (a1) + 'integrate (second (a1), x));
(%o5)
      0
(%i6) antid (expr, x, y(x));
(%o6)
      z(x) d
      [0, y(x) %e  (--- (z(x)))]
              dx
(%i7) antidiff (expr, x, y(x));
(%o7)
      [ z(x) d
      I y(x) %e  (--- (z(x))) dx
      ]
      dx
      /
```

at (*expr*, [*eqn_1*, ..., *eqn_n*])

Function

at (*expr*, *eqn*)

Function

Evaluates the expression *expr* with the variables assuming the values as specified for them in the list of equations [*eqn_1*, ..., *eqn_n*] or the single equation *eqn*.

If a subexpression depends on any of the variables for which a value is specified but there is no `atvalue` specified and it can't be otherwise evaluated, then a noun form of the `at` is returned which displays in a two-dimensional form.

`at` carries out multiple substitutions in parallel.

See also `atvalue`. For other functions which carry out substitutions, see also `subst` and `ev`.

Examples:

```
(%i1) atvalue (f(x,y), [x = 0, y = 1], a^2);
(%o1)
      a
      2
(%i2) atvalue ('diff (f(x,y), x), x = 0, 1 + y);
(%o2)
      @2 + 1
(%i3) printprops (all, atvalue);
      !
      d
      --- (f(@1, @2))!
      d@1
      !
      = @2 + 1
```



```

!@1 = 0

2
f(0, 1) = a

(%o3) done
(%i4) diff (4*f(x, y)^2 - u(x, y)^2, x);
      d      d
(%o4) 8 f(x, y) (--- (f(x, y))) - 2 u(x, y) (--- (u(x, y)))
      dx      dx
(%i5) at (% , [x = 0, y = 1]);

2      d      !
(%o5) 16 a - 2 u(0, 1) (--- (u(x, y)))!
      dx      !
              !x = 0, y = 1

```

atomgrad

Property

atomgrad is the atomic gradient property of an expression. This property is assigned by **gradef**.

atvalue (*expr*, [*x*₁ = *a*₁, ..., *x*_{*m*} = *a*_{*m*}], *c*)

Function

atvalue (*expr*, *x*₁ = *a*₁, *c*)

Function

Assigns the value *c* to *expr* at the point *x* = *a*. Typically boundary values are established by this mechanism.

expr is a function evaluation, *f*(*x*₁, ..., *x*_{*m*}), or a derivative, **diff** (*f*(*x*₁, ..., *x*_{*m*}), *x*₁, *n*₁, ..., *x*_{*n*}, *n*_{*n*}) in which the function arguments explicitly appear. *n*_{*i*} is the order of differentiation with respect to *x*_{*i*}.

The point at which the **atvalue** is established is given by the list of equations [*x*₁ = *a*₁, ..., *x*_{*m*} = *a*_{*m*}]. If there is a single variable *x*₁, the sole equation may be given without enclosing it in a list.

printprops (*[f*₁, *f*₂, ...], **atvalue**) displays the **atvalues** of the functions *f*₁, *f*₂, ... as specified by calls to **atvalue**. **printprops** (*f*, **atvalue**) displays the **atvalues** of one function *f*. **printprops** (**all**, **atvalue**) displays the **atvalues** of all functions for which **atvalues** are defined.

The symbols @1, @2, ... represent the variables *x*₁, *x*₂, ... when **atvalues** are displayed. **atvalue** evaluates its arguments. **atvalue** returns *c*, the **atvalue**.

Examples:

```

(%i1) atvalue (f(x,y), [x = 0, y = 1], a^2);
      2
(%o1) a
(%i2) atvalue ('diff (f(x,y), x), x = 0, 1 + y);
      @2 + 1
(%o2)
(%i3) printprops (all, atvalue);
      !
      d      !
      --- (f(@1, @2))! = @2 + 1
      d@1      !
              !@1 = 0

2
f(0, 1) = a

(%o3) done
(%i4) diff (4*f(x,y)^2 - u(x,y)^2, x);

```

```
(%o4) 8 f(x, y) (--- (f(x, y))) - 2 u(x, y) (--- (u(x, y)))
          dx                      dx
(%i5) at (% , [x = 0, y = 1]);
          !
          2          d          !
(%o5) 16 a - 2 u(0, 1) (--- (u(x, y)))!
          dx          !
          !x = 0, y = 1
```

cartan

Function

The exterior calculus of differential forms is a basic tool of differential geometry developed by Elie Cartan and has important applications in the theory of partial differential equations. The **cartan** package implements the functions **ext_diff** and **lie_diff**, along with the operators **~** (wedge product) and **|** (contraction of a form with a vector.) Type **demo (tensor)** to see a brief description of these commands along with examples.

cartan was implemented by F.B. Estabrook and H.D. Wahlquist.

del (x)

Function

del (x) represents the differential of the variable x .

diff returns an expression containing **del** if an independent variable is not specified. In this case, the return value is the so-called "total differential".

Examples:

```
(%i1) diff (log (x));
          del(x)
(%o1) -----
          x

(%i2) diff (exp (x*y));
          x y          x y
(%o2) x %e del(y) + y %e del(x)
(%i3) diff (x*y*z);
(%o3) x y del(z) + x z del(y) + y z del(x)
```

delta (t)

Function

The Dirac Delta function.

Currently only **laplace** knows about the **delta** function.

Example:

```
(%i1) laplace (delta (t - a) * sin(b*t), t, s);
Is a positive, negative, or zero?

P;
          - a s
(%o1) sin(a b) %e
```

dependencies

System variable

Default value: []

dependencies is the list of atoms which have functional dependencies, assigned by **depends** or **gradef**. The **dependencies** list is cumulative: each call to **depends** or **gradef** appends additional items.

See **depends** and **gradef**.

depends (*f₁*, *x₁*, ..., *f_n*, *x_n*)

Function

Declares functional dependencies among variables for the purpose of computing derivatives. In the absence of declared dependence, `diff (f, x)` yields zero. If `depends (f, x)` is declared, `diff (f, x)` yields a symbolic derivative (that is, a `diff` noun).

Each argument *f₁*, *x₁*, etc., can be the name of a variable or array, or a list of names. Every element of *f_i* (perhaps just a single element) is declared to depend on every element of *x_i* (perhaps just a single element). If some *f_i* is the name of an array or contains the name of an array, all elements of the array depend on *x_i*.

`diff` recognizes indirect dependencies established by `depends` and applies the chain rule in these cases.

`remove (f, dependency)` removes all dependencies declared for *f*.

`depends` returns a list of the dependencies established. The dependencies are appended to the global variable `dependencies`. `depends` evaluates its arguments.

`diff` is the only Maxima command which recognizes dependencies established by `depends`. Other functions (`integrate`, `laplace`, etc.) only recognize dependencies explicitly represented by their arguments. For example, `integrate` does not recognize the dependence of *f* on *x* unless explicitly represented as `integrate (f(x), x)`.

```
(%i1) depends ([f, g], x);
(%o1) [f(x), g(x)]
(%i2) depends ([r, s], [u, v, w]);
(%o2) [r(u, v, w), s(u, v, w)]
(%i3) depends (u, t);
(%o3) [u(t)]
(%i4) dependencies;
(%o4) [f(x), g(x), r(u, v, w), s(u, v, w), u(t)]
(%i5) diff (r.s, u);

(%o5)      dr      ds
      -- . s + r . --
      du      du

(%i6) diff (r.s, t);

(%o6)      dr du      ds du
      -- -- . s + r . -- --
      du dt      du dt

(%i7) remove (r, dependency);
(%o7) done
(%i8) diff (r.s, t);

(%o8)      ds du
      r . -- --
      du dt
```

derivabbrev

Option variable

Default value: `false`

When `derivabbrev` is `true`, symbolic derivatives (that is, `diff` nouns) are displayed as subscripts. Otherwise, derivatives are displayed in the Leibniz notation dy/dx .

derivdegree (*expr*, *y*, *x*)

Function

Returns the highest degree of the derivative of the dependent variable *y* with respect to the independent variable *x* occurring in *expr*.

Example:

```
(%i1) 'diff (y, x, 2) + 'diff (y, z, 3) + 'diff (y, x) * x^2;
(%o1)      3      2
      d y   d y   2 dy
      --- + --- + x ---
      3      2      dx
```


$g(\mathbf{x})$

For the tensor package, the following modifications have been incorporated:

(1) The derivatives of any indexed objects in *expr* will have the variables x_i appended as additional arguments. Then all the derivative indices will be sorted.

(2) The x_i may be integers from 1 up to the value of the variable **dimension** [default value: 4]. This will cause the differentiation to be carried out with respect to the x_i 'th member of the list **coordinates** which should be set to a list of the names of the coordinates, e.g., [x, y, z, t]. If **coordinates** is bound to an atomic variable, then that variable subscripted by x_i will be used for the variable of differentiation. This permits an array of coordinate names or subscripted names like X[1], X[2], ... to be used. If **coordinates** has not been assigned a value, then the variables will be treated as in (1) above.

diff

Special symbol

When **diff** is present as an **evflag** in call to **ev**, all differentiations indicated in **expr** are carried out.

dscalar (*f*)

Function

Applies the scalar d'Alembertian to the scalar function *f*.

load ("ctensor") loads this function.

express (*expr*)

Function

Expands differential operator nouns into expressions in terms of partial derivatives. **express** recognizes the operators **grad**, **div**, **curl**, **laplacian**. **express** also expands the cross product \sim .

Symbolic derivatives (that is, **diff** nouns) in the return value of **express** may be evaluated by including **diff** in the **ev** function call or command line. In this context, **diff** acts as an **evfun**.

load ("vect") loads this function.

Examples:

```
(%i1) load ("vect")$
(%i2) grad (x^2 + y^2 + z^2);

(%o2)
      2      2      2
      grad (z  + y  + x )
(%i3) express (%);
      d      2      2      2      d      2      2      2      d      2      2      2
(%o3) [-- (z  + y  + x ), -- (z  + y  + x ), -- (z  + y  + x )]
      dx      dy      dz
(%i4) ev (% , diff);
(%o4)
      [2 x, 2 y, 2 z]
(%i5) div ([x^2, y^2, z^2]);

(%o5)
      2      2      2
      div [x , y , z ]
(%i6) express (%);
      d      2      d      2      d      2
(%o6) -- (z ) + -- (y ) + -- (x )
      dz      dy      dx
(%i7) ev (% , diff);
(%o7)
      2 z + 2 y + 2 x
(%i8) curl ([x^2, y^2, z^2]);

(%o8)
      2      2      2
      curl [x , y , z ]
(%i9) express (%);
      d      2      d      2      d      2      d      2      d      2
(%o9) [-- (z ) - -- (y ), -- (x ) - -- (z ), -- (y ) - -- (x )]
```

```

      dy      dz      dz      dx      dx      dy
(%i10) ev (%, diff);
(%o10) [0, 0, 0]
(%i11) laplacian (x^2 * y^2 * z^2);
      2 2 2
(%o11) laplacian (x y z )
(%i12) express (%);
      2      2      2
      d      2 2 2      d      2 2 2      d      2 2 2
(%o12) --- (x y z ) + --- (x y z ) + --- (x y z )
      2      2      2
      dz      dy      dx
(%i13) ev (%, diff);
      2 2      2 2      2 2
(%o13) 2 y z + 2 x z + 2 x y
(%i14) [a, b, c] ~ [x, y, z];
(%o14) [a, b, c] ~ [x, y, z]
(%i15) express (%);
(%o15) [b z - c y, c x - a z, a y - b x]

```

gradef ($f(x_1, \dots, x_n), g_1, \dots, g_m$)

Function

gradef (a, x, expr)

Function

Defines the partial derivatives (i.e., the components of the gradient) of the function f or variable a .

gradef ($f(x_1, \dots, x_n), g_1, \dots, g_m$) defines df/dx_i as g_i , where g_i is an expression; g_i may be a function call, but not the name of a function. The number of partial derivatives m may be less than the number of arguments n , in which case derivatives are defined with respect to x_1 through x_m only.

gradef (a, x, expr) defines the derivative of variable a with respect to x as expr . This also establishes the dependence of a on x (via **depends** (a, x)).

The first argument $f(x_1, \dots, x_n)$ or a is quoted, but the remaining arguments g_1, \dots, g_m are evaluated. **gradef** returns the function or variable for which the partial derivatives are defined.

gradef can redefine the derivatives of Maxima's built-in functions. For example, **gradef** (**sin**(x), **sqrt** ($1 - \sin(x)^2$)) redefines the derivative of **sin**.

gradef cannot define partial derivatives for a subscripted function.

printprops ($[f_1, \dots, f_n], \text{gradef}$) displays the partial derivatives of the functions f_1, \dots, f_n , as defined by **gradef**.

printprops ($[a_n, \dots, a_n], \text{atomgrad}$) displays the partial derivatives of the variables a_n, \dots, a_n , as defined by **gradef**.

gradefs is the list of the functions for which partial derivatives have been defined by **gradef**. **gradefs** does not include any variables for which partial derivatives have been defined by **gradef**.

Gradients are needed when, for example, a function is not known explicitly but its first derivatives are and it is desired to obtain higher order derivatives.

gradefs

System variable

Default value: []

gradefs is the list of the functions for which partial derivatives have been defined by **gradef**. **gradefs** does not include any variables for which partial derivatives have been defined by **gradef**.

laplace (*expr*, *t*, *s*)

Function

Attempts to compute the Laplace transform of *expr* with respect to the variable *t* and transform parameter *s*.

laplace recognizes in *expr* the functions **delta**, **exp**, **log**, **sin**, **cos**, **sinh**, **cosh**, and **erf**, as well as **derivative**, **integrate**, **sum**, and **ilt**. If **laplace** fails to find a transform the function **specint** is called. **specint** can find the laplace transform for expressions with special functions like the bessel functions **bessel_j**, **bessel_i**, ... and can handle the **unit_step** function. See also **specint**.

If **specint** cannot find a solution too, a noun **laplace** is returned.

expr may also be a linear, constant coefficient differential equation in which case **atvalue** of the dependent variable is used. The required **atvalue** may be supplied either before or after the transform is computed. Since the initial conditions must be specified at zero, if one has boundary conditions imposed elsewhere he can impose these on the general solution and eliminate the constants by solving the general solution for them and substituting their values back.

laplace recognizes convolution integrals of the form **integrate** (*f*(*x*) * *g*(*t* - *x*), *x*, 0, *t*); other kinds of convolutions are not recognized.

Functional relations must be explicitly represented in *expr*; implicit relations, established by **depends**, are not recognized. That is, if *f* depends on *x* and *y*, *f* (*x*, *y*) must appear in *expr*.

See also **ilt**, the inverse Laplace transform.

Examples:

```
(%i1) laplace (exp (2*t + a) * sin(t) * t, t, s);
              a
              %e  (2 s - 4)
(%o1)  -----
              2      2
              (s  - 4 s + 5)
(%i2) laplace ('diff (f (x), x), x, s);
(%o2)  s laplace(f(x), x, s) - f(0)
(%i3) diff (diff (delta (t), t), t);
              2
              d
              --- (delta(t))
              2
              dt
(%i4) laplace (%, t, s);
              !
              d      !      2
(%o4)  - -- (delta(t))!      + s  - delta(0) s
              dt      !
              !t = 0
(%i5) assume(a>0)$
(%i6) laplace(gamma_incomplete(a,t),t,s),gamma_expand:true;
              - a - 1
              gamma(a)  gamma(a) s
(%o6)  ----- - -----
              s          1      a
              (- + 1)
              s
(%i7) factor(laplace(gamma_incomplete(1/2,t),t,s));
              s + 1
              sqrt(%pi) (sqrt(s) sqrt(-----) - 1)
              s
(%o7)  -----
              3/2      s + 1
```

```

                                s      sqrt(-----)
                                s
(%i8) assume(exp(%pi*s)>1)$
(%i9) laplace(sum((-1)^n*unit_step(t-n*%pi)*sin(t),n,0,inf),t,s),
      simpsum;
                                %i                                %i
      ----- - -----
      (s + %i) (1 - %e- %pi s) (s - %i) (1 - %e- %pi s)
(%o9) -----
                                2
(%i9) factor(%);
                                %pi s
                                %e
(%o9) -----
      (s - %i) (s + %i) (%e%pi s - 1)

```


19 Integration

19.1 Introduction to Integration

Maxima has several routines for handling integration. The `integrate` function makes use of most of them. There is also the `antid` package, which handles an unspecified function (and its derivatives, of course). For numerical uses, there is a set of adaptive integrators from QUADPACK, named `quad_qag`, `quad_qags`, etc., which are described under the heading QUADPACK. Hypergeometric functions are being worked on, see `specint` for details. Generally speaking, Maxima only handles integrals which are integrable in terms of the "elementary functions" (rational functions, trigonometrics, logs, exponentials, radicals, etc.) and a few extensions (error function, dilogarithm). It does not handle integrals in terms of unknown functions such as $g(x)$ and $h(x)$.

19.2 Functions and Variables for Integration

changevar (*expr*, *f(x,y)*, *y*, *x*) Function
 Makes the change of variable given by $f(x,y) = 0$ in all integrals occurring in *expr* with integration with respect to *x*. The new variable is *y*.

```
(%i1) assume(a > 0)$
(%i2) 'integrate (%e**sqrt(a*y), y, 0, 4);
      4
      /
      [  sqrt(a) sqrt(y)
(%o2)  I  %e                                dy
      ]
      /
      0
(%i3) changevar (%, y-z^2/a, z, y);
      0
      /
      [                                abs(z)
      2 I                                z %e                                dz
      ]
      /
      - 2 sqrt(a)
(%o3)  - -----
              a
```

An expression containing a noun form, such as the instances of `'integrate` above, may be evaluated by `ev` with the `nouns` flag. For example, the expression returned by `changevar` above may be evaluated by `ev (%o3, nouns)`.

`changevar` may also be used to changes in the indices of a sum or product. However, it must be realized that when a change is made in a sum or product, this change must be a shift, i.e., $i = j + \dots$, not a higher degree function. E.g.,

```
(%i4) sum (a[i]*x^(i-2), i, 0, inf);
      inf
      ====
      \      i - 2
      >      a  x
      /      i
      ====
      i = 0
```

```
(%i5) changevar (%, i-2-n, n, i);
      inf
      ====
      \
      >      a      x      n
      /      n + 2
      ====
      n = - 2
```

dblint (*f*, *r*, *s*, *a*, *b*)

Function

A double-integral routine which was written in top-level Maxima and then translated and compiled to machine code. Use `load (dblint)` to access this package. It uses the Simpson's rule method in both the *x* and *y* directions to calculate

$$\int_a^b \int_{r(x)}^{s(x)} f(x, y) dy dx.$$

The function *f* must be a translated or compiled function of two variables, and *r* and *s* must each be a translated or compiled function of one variable, while *a* and *b* must be floating point numbers. The routine has two global variables which determine the number of divisions of the *x* and *y* intervals: `dblint_x` and `dblint_y`, both of which are initially 10, and can be changed independently to other integer values (there are `2*dblint_x+1` points computed in the *x* direction, and `2*dblint_y+1` in the *y* direction). The routine subdivides the *X* axis and then for each value of *X* it first computes *r*(*x*) and *s*(*x*); then the *Y* axis between *r*(*x*) and *s*(*x*) is subdivided and the integral along the *Y* axis is performed using Simpson's rule; then the integral along the *X* axis is done using Simpson's rule with the function values being the *Y*-integrals. This procedure may be numerically unstable for a great variety of reasons, but is reasonably fast: avoid using it on highly oscillatory functions and functions with singularities (poles or branch points in the region). The *Y* integrals depend on how far apart *r*(*x*) and *s*(*x*) are, so if the distance *s*(*x*) - *r*(*x*) varies rapidly with *X*, there may be substantial errors arising from truncation with different step-sizes in the various *Y* integrals. One can increase `dblint_x` and `dblint_y` in an effort to improve the coverage of the region, at the expense of computation time. The function values are not saved, so if the function is very time-consuming, you will have to wait for re-computation if you change anything (sorry). It is required that the functions *f*, *r*, and *s* be either translated or compiled prior to calling `dblint`. This will result in orders of magnitude speed improvement over interpreted code in many cases!

`demo (dblint)` executes a demonstration of `dblint` applied to an example problem.

defint (*expr*, *x*, *a*, *b*)

Function

Attempts to compute a definite integral. `defint` is called by `integrate` when limits of integration are specified, i.e., when `integrate` is called as `integrate (expr, x, a, b)`. Thus from the user's point of view, it is sufficient to call `integrate`.

`defint` returns a symbolic expression, either the computed integral or the noun form of the integral. See `quad_qag` and related functions for numerical approximation of definite integrals.

erfflag

Option variable

Default value: `true`

When `erfflag` is `false`, prevents `risch` from introducing the `erf` function in the answer if there were none in the integrand to begin with.

ilt (*expr*, *s*, *t*)

Function

Computes the inverse Laplace transform of *expr* with respect to *s* and parameter *t*. *expr* must be a ratio of polynomials whose denominator has only linear and quadratic factors. By using the functions `laplace` and `ilt` together with the `solve` or `linsolve` functions the user can solve a single differential or convolution integral equation or a set of them.

```
(%i1) 'integrate (sinh(a*x)*f(t-x), x, 0, t) + b*f(t) = t**2;
```

$$\int_0^t f(t-x) \sinh(ax) dx + b f(t) = t^2$$

```
(%o1)
```

```
(%i2) laplace (% , t, s);
```

$$b \operatorname{laplace}(f(t), t, s) + \frac{a \operatorname{laplace}(f(t), t, s)}{s^2 - a^2} = \frac{t^2}{s^3}$$

```
(%o2)
```

```
(%i3) linsolve ([%], ['laplace(f(t), t, s)]);
```

$$[\operatorname{laplace}(f(t), t, s) = \frac{2 s^2 - 2 a^2}{b s^5 + (a - a^2 b) s^3}]$$

```
(%o3)
```

```
(%i4) ilt (rhs (first (%)), s, t);
```

Is $a b (a b - 1)$ positive, negative, or zero?

```
pos;
```

$$2 \cosh\left(\frac{\sqrt{a b (a b - 1)} t}{b}\right) - \frac{a t^2}{a^3 b^2 - 2 a^2 b + a} + \frac{2}{a^3 b^2 - 2 a^2 b + a}$$

```
(%o4)
```

intanalysis

Option variable

Default value: **true**

When **true**, definite integration tries to find poles in the integrand in the interval of integration. If there are, then the integral is evaluated appropriately as a principal value integral. If **intanalysis** is **false**, this check is not performed and integration is done assuming there are no poles.

See also **ldefint**.

Examples:

Maxima can solve the following integrals, when **intanalysis** is set to **false**:

```
(%i1) integrate(1/(sqrt(x)+1),x,0,1);
```

$$\int_0^1 \frac{1}{\sqrt{x} + 1} dx$$

```
(%o1)
```

```
(%i2) integrate(1/(sqrt(x)+1),x,0,1),intanalysis:false;
```

$$2 - 2 \log(2)$$

```
(%o2)
```

```
(%i3) integrate(cos(a)/sqrt((tan(a))^2 +1),a,-%pi/2,%pi/2);
The number 1 isn't in the domain of atanh
-- an error. To debug this try: debugmode(true);

(%i4) intanalysis:false$
(%i5) integrate(cos(a)/sqrt((tan(a))^2+1),a,-%pi/2,%pi/2);
                                     %pi
(%o5)                               ---
                                     2
```

integrate (*expr*, *x*)

Function

integrate (*expr*, *x*, *a*, *b*)

Function

Attempts to symbolically compute the integral of *expr* with respect to *x*. **integrate** (*expr*, *x*) is an indefinite integral, while **integrate** (*expr*, *x*, *a*, *b*) is a definite integral, with limits of integration *a* and *b*. The limits should not contain *x*, although **integrate** does not enforce this restriction. *a* need not be less than *b*. If *b* is equal to *a*, **integrate** returns zero.

See **quad_qag** and related functions for numerical approximation of definite integrals. See **residue** for computation of residues (complex integration). See **antid** for an alternative means of computing indefinite integrals.

The integral (an expression free of **integrate**) is returned if **integrate** succeeds. Otherwise the return value is the noun form of the integral (the quoted operator '**integrate**') or an expression containing one or more noun forms. The noun form of **integrate** is displayed with an integral sign.

In some circumstances it is useful to construct a noun form by hand, by quoting **integrate** with a single quote, e.g., '**integrate** (*expr*, *x*)'. For example, the integral may depend on some parameters which are not yet computed. The noun may be applied to its arguments by **ev** (*i*, **nouns**) where *i* is the noun form of interest.

integrate handles definite integrals separately from indefinite, and employs a range of heuristics to handle each case. Special cases of definite integrals include limits of integration equal to zero or infinity (**inf** or **minf**), trigonometric functions with limits of integration equal to zero and **%pi** or 2 **%pi**, rational functions, integrals related to the definitions of the **beta** and **psi** functions, and some logarithmic and trigonometric integrals. Processing rational functions may include computation of residues. If an applicable special case is not found, an attempt will be made to compute the indefinite integral and evaluate it at the limits of integration. This may include taking a limit as a limit of integration goes to infinity or negative infinity; see also **ldefint**.

Special cases of indefinite integrals include trigonometric functions, exponential and logarithmic functions, and rational functions. **integrate** may also make use of a short table of elementary integrals.

integrate may carry out a change of variable if the integrand has the form **f(g(x)) * diff(g(x), x)**. **integrate** attempts to find a subexpression **g(x)** such that the derivative of **g(x)** divides the integrand. This search may make use of derivatives defined by the **gradef** function. See also **changevar** and **antid**.

If none of the preceding heuristics find the indefinite integral, the Risch algorithm is executed. The flag **risch** may be set as an **evflag**, in a call to **ev** or on the command line, e.g., **ev (integrate (expr, x), risch)** or **integrate (expr, x), risch**. If **risch** is present, **integrate** calls the **risch** function without attempting heuristics first. See also **risch**.

integrate works only with functional relations represented explicitly with the **f(x)** notation. **integrate** does not respect implicit dependencies established by the **depends** function.

integrate may need to know some property of a parameter in the integrand. **integrate** will first consult the **assume** database, and, if the variable of interest is not there,

`integrate` will ask the user. Depending on the question, suitable responses are `yes`; or `no`;, or `pos`;, `zero`;, or `neg`;

`integrate` is not, by default, declared to be linear. See `declare` and `linear`.

`integrate` attempts integration by parts only in a few special cases.

Examples:

- Elementary indefinite and definite integrals.

```
(%i1) integrate (sin(x)^3, x);
              3
              cos (x)
(%o1)  ----- - cos(x)
              3
(%i2) integrate (x/ sqrt (b^2 - x^2), x);
              2      2
              - sqrt(b  - x )
(%o2)  -----
              2
(%i3) integrate (cos(x)^2 * exp(x), x, 0, %pi);
              %pi
              3 %e      3
              ----- -
              5      5
(%o3)  -----
              5      5
(%i4) integrate (x^2 * exp(-x^2), x, minf, inf);
              sqrt(%pi)
(%o4)  -----
              2
```

- Use of `assume` and interactive query.

```
(%i1) assume (a > 1)$
(%i2) integrate (x**a/(x+1)**(5/2), x, 0, inf);
      2 a + 2
Is  -----  an integer?
      5

no;
Is  2 a - 3  positive, negative, or zero?

neg;

              3
(%o2)  beta(a + 1, - - a)
              2
```

- Change of variable. There are two changes of variable in this example: one using a derivative established by `gradef`, and one using the derivation `diff(r(x))` of an unspecified function `r(x)`.

```
(%i3) gradef (q(x), sin(x**2));
(%o3)  q(x)
(%i4) diff (log (q (r (x))), x);
              d      2
              (-- (r(x))) sin(r (x))
              dx
(%o4)  -----
              q(r(x))

(%i5) integrate (%, x);
(%o5)  log(q(r(x)))
```

- Return value contains the `'integrate` noun form. In this example, Maxima can extract one factor of the denominator of a rational function, but cannot factor the remainder or otherwise find its integral. `grind` shows the noun form `'integrate` in the result. See also `integrate_use_rootsof` for more on integrals of rational functions.

```
(%i1) expand ((x-4) * (x^3+2*x+1));
              4      3      2
(%o1)          x  - 4 x  + 2 x  - 7 x - 4
(%i2) integrate (1/%, x);
              /  2
              [ x  + 4 x + 18
              I ----- dx
              ]  3
              log(x - 4) / x  + 2 x + 1
(%o2)          ----- - -----
              73          73
(%i3) grind (%);
log(x-4)/73-(integrate((x^2+4*x+18)/(x^3+2*x+1),x))/73$
```

- Defining a function in terms of an integral. The body of a function is not evaluated when the function is defined. Thus the body of `f_1` in this example contains the noun form of `integrate`. The quote-quote operator `''` causes the integral to be evaluated, and the result becomes the body of `f_2`.

```
(%i1) f_1 (a) := integrate (x^3, x, 1, a);
              3
(%o1)          f_1(a) := integrate(x , x, 1, a)
(%i2) ev (f_1 (7), nouns);
(%o2)          600
(%i3) /* Note parentheses around integrate(...) here */
      f_2 (a) := ''(integrate (x^3, x, 1, a));
              4
              a      1
(%o3)          f_2(a) := -- - -
              4      4
(%i4) f_2 (7);
(%o4)          600
```

integration_constant

System variable

Default value: %c

When a constant of integration is introduced by indefinite integration of an equation, the name of the constant is constructed by concatenating `integration_constant` and `integration_constant_counter`.

`integration_constant` may be assigned any symbol.

Examples:

```
(%i1) integrate (x^2 = 1, x);
              3
              x
(%o1)          -- = x + %c1
              3
(%i2) integration_constant : 'k;
(%o2)          k
(%i3) integrate (x^2 = 1, x);
              3
              x
(%o3)          -- = x + k2
              3
```

integration_constant_counter

System variable

Default value: 0

When a constant of integration is introduced by indefinite integration of an equation, the name of the constant is constructed by concatenating `integration_constant` and `integration_constant_counter`.

`integration_constant_counter` is incremented before constructing the next integration constant.

Examples:

```
(%i1) integrate (x^2 = 1, x);
              3
              x
(%o1)  ----- = x + %c1
              3
(%i2) integrate (x^2 = 1, x);
              3
              x
(%o2)  ----- = x + %c2
              3
(%i3) integrate (x^2 = 1, x);
              3
              x
(%o3)  ----- = x + %c3
              3
(%i4) reset (integration_constant_counter);
(%o4)  [integration_constant_counter]
(%i5) integrate (x^2 = 1, x);
              3
              x
(%o5)  ----- = x + %c1
              3
```

`integrate_use_rootsof`

Option variable

Default value: `false`

When `integrate_use_rootsof` is `true` and the denominator of a rational function cannot be factored, `integrate` returns the integral in a form which is a sum over the roots (not yet known) of the denominator.

For example, with `integrate_use_rootsof` set to `false`, `integrate` returns an unsolved integral of a rational function in noun form:

```
(%i1) integrate_use_rootsof: false$
(%i2) integrate (1/(1+x+x^5), x);
      /  2
      [ x  - 4 x + 5
      I ----- dx
      ]  3    2
      / x  - x  + 1      2      5 atan(-----)
                        log(x  + x + 1)      sqrt(3)
(%o2)  ----- - ----- + -----
              7              14              7 sqrt(3)
```

Now we set the flag to be `true` and the unsolved part of the integral will be expressed as a summation over the roots of the denominator of the rational function:

```
(%i3) integrate_use_rootsof: true$
```

```
(%i4) integrate (1/(1+x+x^5), x);
====
\      2
  (%r4  - 4 %r4 + 5) log(x - %r4)
> -----
/
====
      2
      3 %r4  - 2 %r4
      3      2
      %r4 in rootsof(x  - x  + 1)
(%o4) -----
      7

      2 x + 1
      2      5 atan(-----)
      log(x  + x + 1)      sqrt(3)
- ----- + -----
      14      7 sqrt(3)
```

Alternatively the user may compute the roots of the denominator separately, and then express the integrand in terms of these roots, e.g., $1/((x - a)*(x - b)*(x - c))$ or $1/((x^2 - (a+b)*x + a*b)*(x - c))$ if the denominator is a cubic polynomial. Sometimes this will help Maxima obtain a more useful result.

ldefint (*expr*, *x*, *a*, *b*)

Function

Attempts to compute the definite integral of *expr* by using **limit** to evaluate the indefinite integral of *expr* with respect to *x* at the upper limit *b* and at the lower limit *a*. If it fails to compute the definite integral, **ldefint** returns an expression containing limits as noun forms.

ldefint is not called from **integrate**, so executing **ldefint** (*expr*, *x*, *a*, *b*) may yield a different result than **integrate** (*expr*, *x*, *a*, *b*). **ldefint** always uses the same method to evaluate the definite integral, while **integrate** may employ various heuristics and may recognize some special cases.

potential (*givengradient*)

Function

The calculation makes use of the global variable **potentialzeroloc**[0] which must be **nonlist** or of the form

```
[indeterminatej=expressionj, indeterminatek=expressionk, ...]
```

the former being equivalent to the **nonlist** expression for all right-hand sides in the latter. The indicated right-hand sides are used as the lower limit of integration. The success of the integrations may depend upon their values and order. **potentialzeroloc** is initially set to 0.

residue (*expr*, *z*, *z_0*)

Function

Computes the residue in the complex plane of the expression *expr* when the variable *z* assumes the value *z_0*. The residue is the coefficient of $(z - z_0)^{-1}$ in the Laurent series for *expr*.

```
(%i1) residue (s/(s**2+a**2), s, a%i);
      1
(%o1)  -
      2
      a
(%i2) residue (sin(a*x)/x**4, x, 0);
      3
      a
(%o2)  - --
      6
```


risch (*expr*, *x*)

Function

Integrates *expr* with respect to *x* using the transcendental case of the Risch algorithm. (The algebraic case of the Risch algorithm has not been implemented.) This currently handles the cases of nested exponentials and logarithms which the main part of **integrate** can't do. **integrate** will automatically apply **risch** if given these cases.

erfflag, if **false**, prevents **risch** from introducing the **erf** function in the answer if there were none in the integrand to begin with.

```
(%i1) risch (x^2*erf(x), x);
```

$$\frac{\frac{3}{2}\pi x^3 \operatorname{erf}(x) + (\sqrt{\pi} x^2 + \sqrt{\pi}) e^{-x^2}}{3\pi}$$

```
(%o1)
```

```
(%i2) diff(%, x), ratsimp;
```

$$x^2 \operatorname{erf}(x)$$

```
(%o2)
```

tldefint (*expr*, *x*, *a*, *b*)

Function

Equivalent to **ldefint** with **tlimswitch** set to **true**.

19.3 Introduction to QUADPACK

QUADPACK is a collection of functions for the numerical computation of one-dimensional definite integrals. It originated from a joint project of R. Piessens¹, E. de Doncker², C. Ueberhuber³, and D. Kahaner⁴.

The QUADPACK library included in Maxima is an automatic translation (via the program **f2c1**) of the Fortran source code of QUADPACK as it appears in the SLATEC Common Mathematical Library, Version 4.1⁵. The SLATEC library is dated July 1993, but the QUADPACK functions were written some years before. There is another version of QUADPACK at Netlib⁶; it is not clear how that version differs from the SLATEC version.

The QUADPACK functions included in Maxima are all automatic, in the sense that these functions attempt to compute a result to a specified accuracy, requiring an unspecified number of function evaluations. Maxima's Lisp translation of QUADPACK also includes some non-automatic functions, but they are not exposed at the Maxima level.

Further information about QUADPACK can be found in the QUADPACK book⁷.

19.3.1 Overview

quad_qag Integration of a general function over a finite interval. **quad_qag** implements a simple globally adaptive integrator using the strategy of Aind (Piessens, 1973). The caller may choose among 6 pairs of Gauss-Kronrod quadrature formulae for the rule evaluation component. The high-degree rules are suitable for strongly oscillating integrands.

quad_qags

Integration of a general function over a finite interval. **quad_qags** implements globally adaptive interval subdivision with extrapolation (de Doncker, 1978) by the Epsilon algorithm (Wynn, 1956).

¹ Applied Mathematics and Programming Division, K.U. Leuven

² Applied Mathematics and Programming Division, K.U. Leuven

³ Institut für Mathematik, T.U. Wien

⁴ National Bureau of Standards, Washington, D.C., U.S.A

⁵ <http://www.netlib.org/slatec>

⁶ <http://www.netlib.org/quadpack>

⁷ R. Piessens, E. de Doncker-Kapenga, C.W. Ueberhuber, and D.K. Kahaner. *QUADPACK: A Subroutine Package for Automatic Integration*. Berlin: Springer-Verlag, 1983, ISBN 0387125531.

quad_qagi

Integration of a general function over an infinite or semi-infinite interval. The interval is mapped onto a finite interval and then the same strategy as in **quad_qags** is applied.

quad_qawo

Integration of $\cos(\omega x) f(x)$ or $\sin(\omega x) f(x)$ over a finite interval, where ω is a constant. The rule evaluation component is based on the modified Clenshaw-Curtis technique. **quad_qawo** applies adaptive subdivision with extrapolation, similar to **quad_qags**.

quad_qawf

Calculates a Fourier cosine or Fourier sine transform on a semi-infinite interval. The same approach as in **quad_qawo** is applied on successive finite intervals, and convergence acceleration by means of the Epsilon algorithm (Wynn, 1956) is applied to the series of the integral contributions.

quad_qaws

Integration of $w(x) f(x)$ over a finite interval $[a, b]$, where w is a function of the form $(x - a)^\alpha (b - x)^\beta v(x)$ and $v(x)$ is 1 or $\log(x - a)$ or $\log(b - x)$ or $\log(x - a) \log(b - x)$, and $\alpha > -1$ and $\beta > -1$.

A globally adaptive subdivision strategy is applied, with modified Clenshaw-Curtis integration on the subintervals which contain a or b .

quad_qawc

Computes the Cauchy principal value of $f(x)/(x - c)$ over a finite interval (a, b) and specified c . The strategy is globally adaptive, and modified Clenshaw-Curtis integration is used on the subranges which contain the point $x = c$.

quad_qagp

Basically the same as **quad_qags** but points of singularity or discontinuity of the integrand must be supplied. This makes it easier for the integrator to produce a good solution.

19.4 Functions and Variables for QUADPACK

quad_qag ($f(x)$, x , a , b , key , [$epsrel$, $epsabs$, $limit$])

Function

quad_qag (f , x , a , b , key , [$epsrel$, $epsabs$, $limit$])

Function

Integration of a general function over a finite interval. **quad_qag** implements a simple globally adaptive integrator using the strategy of Aind (Piessens, 1973). The caller may choose among 6 pairs of Gauss-Kronrod quadrature formulae for the rule evaluation component. The high-degree rules are suitable for strongly oscillating integrands.

quad_qag computes the integral

$$\int_a^b f(x) dx$$

The function to be integrated is $f(x)$, with dependent variable x , and the function is to be integrated between the limits a and b . key is the integrator to be used and should be an integer between 1 and 6, inclusive. The value of key selects the order of the Gauss-Kronrod integration rule. High-order rules are suitable for strongly oscillating integrands.

The integrand may be specified as the name of a Maxima or Lisp function or operator, a Maxima lambda expression, or a general Maxima expression.

The numerical integration is done adaptively by subdividing the integration region into sub-intervals until the desired accuracy is achieved.

The keyword arguments are optional and may be specified in any order. They all take the form **key=val**. The keyword arguments are:

epsrel Desired relative error of approximation. Default is 1d-8.

epsabs Desired absolute error of approximation. Default is 0.
limit Size of internal work array. *limit* is the maximum number of subintervals to use. Default is 200.

quad_qag returns a list of four elements:
 an approximation to the integral,
 the estimated absolute error of the approximation,
 the number integrand evaluations,
 an error code.

The error code (fourth element of the return value) can have the values:

0 if no problems were encountered;
 1 if too many sub-intervals were done;
 2 if excessive roundoff error is detected;
 3 if extremely bad integrand behavior occurs;
 6 if the input is invalid.

Examples:

```
(%i1) quad_qag (x^(1/2)*log(1/x), x, 0, 1, 3, 'epsrel=5d-8);
(%o1)      [.4444444444492108, 3.1700968502883E-9, 961, 0]
(%i2) integrate (x^(1/2)*log(1/x), x, 0, 1);
4
-
9
```

quad_qags (<i>f(x)</i> , <i>x</i> , <i>a</i> , <i>b</i> , [<i>epsrel</i> , <i>epsabs</i> , <i>limit</i>])	Function
quad_qags (<i>f</i> , <i>x</i> , <i>a</i> , <i>b</i> , [<i>epsrel</i> , <i>epsabs</i> , <i>limit</i>])	Function

Integration of a general function over a finite interval. **quad_qags** implements globally adaptive interval subdivision with extrapolation (de Doncker, 1978) by the Epsilon algorithm (Wynn, 1956).

quad_qags computes the integral

$$\int_a^b f(x) dx$$

The function to be integrated is $f(x)$, with dependent variable x , and the function is to be integrated between the limits a and b .

The integrand may be specified as the name of a Maxima or Lisp function or operator, a Maxima lambda expression, or a general Maxima expression.

The keyword arguments are optional and may be specified in any order. They all take the form **key=val**. The keyword arguments are:

epsrel Desired relative error of approximation. Default is 1d-8.
epsabs Desired absolute error of approximation. Default is 0.
limit Size of internal work array. *limit* is the maximum number of subintervals to use. Default is 200.

quad_qags returns a list of four elements:
 an approximation to the integral,
 the estimated absolute error of the approximation,
 the number integrand evaluations,
 an error code.

The error code (fourth element of the return value) can have the values:

- 0 no problems were encountered;
- 1 too many sub-intervals were done;
- 2 excessive roundoff error is detected;
- 3 extremely bad integrand behavior occurs;
- 4 failed to converge
- 5 integral is probably divergent or slowly convergent
- 6 if the input is invalid.

Examples:

```
(%i1) quad_qags (x^(1/2)*log(1/x), x, 0, 1, 'epsrel=1d-10);
(%o1) [.4444444444444448, 1.11022302462516E-15, 315, 0]
```

Note that `quad_qags` is more accurate and efficient than `quad_qag` for this integrand.

quad_qagi ($f(x)$, x , a , b , [$epsrel$, $epsabs$, $limit$]) Function
quad_qagi (f , x , a , b , [$epsrel$, $epsabs$, $limit$]) Function

Integration of a general function over an infinite or semi-infinite interval. The interval is mapped onto a finite interval and then the same strategy as in `quad_qags` is applied.

`quad_qagi` evaluates one of the following integrals

$$\int_a^{\infty} f(x) dx$$

$$\int_{\infty}^a f(x) dx$$

$$\int_{-\infty}^{\infty} f(x) dx$$

using the Quadpack QAGI routine. The function to be integrated is $f(x)$, with dependent variable x , and the function is to be integrated over an infinite range.

The integrand may be specified as the name of a Maxima or Lisp function or operator, a Maxima lambda expression, or a general Maxima expression.

One of the limits of integration must be infinity. If not, then `quad_qagi` will just return the noun form.

The keyword arguments are optional and may be specified in any order. They all take the form **key=val**. The keyword arguments are:

epsrel Desired relative error of approximation. Default is 1d-8.

epsabs Desired absolute error of approximation. Default is 0.

limit Size of internal work array. *limit* is the maximum number of subintervals to use. Default is 200.

`quad_qagi` returns a list of four elements:

- an approximation to the integral,
- the estimated absolute error of the approximation,
- the number integrand evaluations,
- an error code.

The error code (fourth element of the return value) can have the values:

- 0 no problems were encountered;
- 1 too many sub-intervals were done;
- 2 excessive roundoff error is detected;

- 3 extremely bad integrand behavior occurs;
- 4 failed to converge
- 5 integral is probably divergent or slowly convergent
- 6 if the input is invalid.

Examples:

```
(%i1) quad_qagi (x^2*exp(-4*x), x, 0, inf, 'epsrel=1d-8);
(%o1)          [0.03125, 2.95916102995002E-11, 105, 0]
(%i2) integrate (x^2*exp(-4*x), x, 0, inf);
1
--
32
```

quad_qawc ($f(x)$, x , c , a , b , [$epsrel$, $epsabs$, $limit$]) Function
quad_qawc (f , x , c , a , b , [$epsrel$, $epsabs$, $limit$]) Function

Computes the Cauchy principal value of $f(x)/(x - c)$ over a finite interval. The strategy is globally adaptive, and modified Clenshaw-Curtis integration is used on the subranges which contain the point $x = c$.

quad_qawc computes the Cauchy principal value of

$$\int_a^b \frac{f(x)}{x - c} dx$$

using the Quadpack QAWC routine. The function to be integrated is $f(x)/(x - c)$, with dependent variable x , and the function is to be integrated over the interval a to b .

The integrand may be specified as the name of a Maxima or Lisp function or operator, a Maxima lambda expression, or a general Maxima expression.

The keyword arguments are optional and may be specified in any order. They all take the form **key=val**. The keyword arguments are:

- epsrel** Desired relative error of approximation. Default is 1d-8.
- epsabs** Desired absolute error of approximation. Default is 0.
- limit** Size of internal work array. *limit* is the maximum number of subintervals to use. Default is 200.

quad_qawc returns a list of four elements:

- an approximation to the integral,
- the estimated absolute error of the approximation,
- the number integrand evaluations,
- an error code.

The error code (fourth element of the return value) can have the values:

- 0 no problems were encountered;
- 1 too many sub-intervals were done;
- 2 excessive roundoff error is detected;
- 3 extremely bad integrand behavior occurs;
- 6 if the input is invalid.

Examples:

```
(%i1) quad_qawc (2^(-5)*((x-1)^2+4^(-5))^-1), x, 2, 0, 5,
'epsrel=1d-7);
(%o1)          [- 3.130120337415925, 1.306830140249558E-8, 495, 0]
```

```
(%i2) integrate (2^(-alpha)*(((x-1)^2 + 4^(-alpha))*(x-2))^-1),
x, 0, 5);
Principal Value
```

$$\begin{aligned}
& \frac{\alpha^4 \log\left(\frac{\alpha^9}{64^4} + \frac{\alpha^9}{64^4}\right)}{\alpha^2 + 2} \\
& - \frac{\frac{3\alpha^2}{2^4} \operatorname{atan}\left(4^{\frac{\alpha}{2}}\right) - \frac{3\alpha^2}{2^4} \operatorname{atan}\left(4^{\frac{\alpha}{2}}\right) \alpha}{\alpha^2 + 2} / 2
\end{aligned}$$

```
(%o2) (-----)
alpha
2 4      + 2

3 alpha      3 alpha
-----      -----
2      alpha/2      2      alpha/2
2 4      atan(4 4      )      2 4      atan(4 4      )      alpha
-----      -----      -----) / 2
alpha      alpha
2 4      + 2      2 4      + 2

(%i3) ev (%, alpha=5, numer);
(%o3) - 3.130120337415917
```

quad_qawf ($f(x)$, x , a , ω , trig , [epsabs , limit , maxp1 , limlst]) Function
quad_qawf (f , x , a , ω , trig , [epsabs , limit , maxp1 , limlst]) Function

Calculates a Fourier cosine or Fourier sine transform on a semi-infinite interval using the Quadpack QAWF function. The same approach as in **quad_qawo** is applied on successive finite intervals, and convergence acceleration by means of the Epsilon algorithm (Wynn, 1956) is applied to the series of the integral contributions.

quad_qawf computes the integral

$$\int_a^\infty f(x) w(x) dx$$

The weight function w is selected by trig :

cos $w(x) = \cos(\omega x)$

sin $w(x) = \sin(\omega x)$

The integrand may be specified as the name of a Maxima or Lisp function or operator, a Maxima lambda expression, or a general Maxima expression.

The keyword arguments are optional and may be specified in any order. They all take the form **key=val**. The keyword arguments are:

epsabs Desired absolute error of approximation. Default is 1d-10.

limit Size of internal work array. $(\text{limit} - \text{limlst})/2$ is the maximum number of subintervals to use. Default is 200.

maxp1 Maximum number of Chebyshev moments. Must be greater than 0. Default is 100.

limlst Upper bound on the number of cycles. Must be greater than or equal to 3. Default is 10.

quad_qawf returns a list of four elements:

- an approximation to the integral,
- the estimated absolute error of the approximation,
- the number integrand evaluations,
- an error code.

The error code (fourth element of the return value) can have the values:

- 0 no problems were encountered;
- 1 too many sub-intervals were done;
- 2 excessive roundoff error is detected;
- 3 extremely bad integrand behavior occurs;
- 6 if the input is invalid.

Examples:

```
(%i1) quad_qawf (exp(-x^2), x, 0, 1, 'cos, 'epsabs=1d-9);
(%o1)  [.6901942235215714, 2.84846300257552E-11, 215, 0]
(%i2) integrate (exp(-x^2)*cos(x), x, 0, inf);
          - 1/4
          %e      sqrt(%pi)
(%o2)  -----
          2
(%i3) ev (% , numer);
(%o3)  .6901942235215714
```

quad_qawo ($f(x)$, x , a , b , ω , trig , [epsrel , epsabs , limit , maxp1 , limlst]) Function
quad_qawo (f , x , a , b , ω , trig , [epsrel , epsabs , limit , maxp1 , limlst]) Function

Integration of $\cos(\omega x) f(x)$ or $\sin(\omega x) f(x)$ over a finite interval, where ω is a constant.

The rule evaluation component is based on the modified Clenshaw-Curtis technique. **quad_qawo** applies adaptive subdivision with extrapolation, similar to **quad_qags**.

quad_qawo computes the integral using the Quadpack QAWO routine:

$$\int_a^b f(x) w(x) dx$$

The weight function w is selected by *trig*:

cos $w(x) = \cos(\omega x)$

sin $w(x) = \sin(\omega x)$

The integrand may be specified as the name of a Maxima or Lisp function or operator, a Maxima lambda expression, or a general Maxima expression.

The keyword arguments are optional and may be specified in any order. They all take the form **key=val**. The keyword arguments are:

epsrel Desired relative error of approximation. Default is 1d-8.

epsabs Desired absolute error of approximation. Default is 0.

limit Size of internal work array. $\text{limit}/2$ is the maximum number of subintervals to use. Default is 200.

maxp1 Maximum number of Chebyshev moments. Must be greater than 0. Default is 100.

limlst Upper bound on the number of cycles. Must be greater than or equal to 3. Default is 10.

quad_qawo returns a list of four elements:

- an approximation to the integral,
- the estimated absolute error of the approximation,
- the number integrand evaluations,
- an error code.

The error code (fourth element of the return value) can have the values:

- 0 no problems were encountered;
- 1 too many sub-intervals were done;
- 2 excessive roundoff error is detected;
- 3 extremely bad integrand behavior occurs;
- 6 if the input is invalid.

Examples:

```
(%i1) quad_qawo (x^(-1/2)*exp(-2^(-2)*x), x, 1d-8, 20*2^2, 1, cos);
(%o1) [1.376043389877692, 4.72710759424899E-11, 765, 0]
(%i2) rectform (integrate (x^(-1/2)*exp(-2^(-alpha)*x) * cos(x),
      x, 0, inf));
      alpha/2 - 1/2          2 alpha
      sqrt(%pi) 2          sqrt(sqrt(2  + 1) + 1)
(%o2) -----
      2 alpha
      sqrt(2  + 1)
(%i3) ev (% , alpha=2, numer);
(%o3) 1.376043390090716
```

quad_qaws ($f(x)$, x , a , b , α , β , $wfun$, [ϵ_{srel} , ϵ_{sabs} , $limit$]) Function
quad_qaws (f , x , a , b , α , β , $wfun$, [ϵ_{srel} , ϵ_{sabs} , $limit$]) Function

Integration of $w(x)f(x)$ over a finite interval, where $w(x)$ is a certain algebraic or logarithmic function. A globally adaptive subdivision strategy is applied, with modified Clenshaw-Curtis integration on the subintervals which contain the endpoints of the interval of integration.

quad_qaws computes the integral using the Quadpack QAWS routine:

$$\int_a^b f(x) w(x) dx$$

The weight function w is selected by $wfun$:

- 1 $w(x) = (x - a)^\alpha (b - x)^\beta$
- 2 $w(x) = (x - a)^\alpha (b - x)^\beta \log(x - a)$
- 3 $w(x) = (x - a)^\alpha (b - x)^\beta \log(b - x)$
- 4 $w(x) = (x - a)^\alpha (b - x)^\beta \log(x - a) \log(b - x)$

The integrand may be specified as the name of a Maxima or Lisp function or operator, a Maxima lambda expression, or a general Maxima expression.

The keyword arguments are optional and may be specified in any order. They all take the form **key=val**. The keyword arguments are:

- epsrel* Desired relative error of approximation. Default is 1d-8.
- epsabs* Desired absolute error of approximation. Default is 0.
- limit* Size of internal work array. *limit* is the maximum number of subintervals to use. Default is 200.

quad_qaws returns a list of four elements:

- an approximation to the integral,
- the estimated absolute error of the approximation,
- the number integrand evaluations,
- an error code.

The error code (fourth element of the return value) can have the values:

- 0 no problems were encountered;
- 1 too many sub-intervals were done;
- 2 excessive roundoff error is detected;
- 3 extremely bad integrand behavior occurs;
- 6 if the input is invalid.

Examples:

```
(%i1) quad_qaws (1/(x+1+2^(-4)), x, -1, 1, -0.5, -0.5, 1,
               'epsabs=1d-9);
(%o1)      [8.750097361672832, 1.24321522715422E-10, 170, 0]
(%i2) integrate ((1-x*x)^(-1/2)/(x+1+2^(-alpha)), x, -1, 1);
      alpha
Is  4 2      - 1  positive, negative, or zero?

pos;

      alpha      alpha
      2 %pi 2      sqrt(2 2      + 1)
(%o2)  -----
      alpha
      4 2      + 2

(%i3) ev (% , alpha=4, numer);
(%o3)      8.750097361672829
```

quad_qagp ($f(x)$, x , a , b , $points$, [$epsrel$, $epsabs$, $limit$]) Function
quad_qagp (f , x , a , b , $points$, [$epsrel$, $epsabs$, $limit$]) Function

Integration of a general function over a finite interval. **quad_qagp** implements globally adaptive interval subdivision with extrapolation (de Doncker, 1978) by the Epsilon algorithm (Wynn, 1956).

quad_qagp computes the integral

$$\int_a^b f(x) dx$$

The function to be integrated is $f(x)$, with dependent variable x , and the function is to be integrated between the limits a and b .

The integrand may be specified as the name of a Maxima or Lisp function or operator, a Maxima lambda expression, or a general Maxima expression.

To help the integrator, the user must supply a list of points where the integrand is singular or discontinuous.

The keyword arguments are optional and may be specified in any order. They all take the form **key=val**. The keyword arguments are:

- epsrel** Desired relative error of approximation. Default is 1d-8.
- epsabs** Desired absolute error of approximation. Default is 0.
- limit** Size of internal work array. *limit* is the maximum number of subintervals to use. Default is 200.

quad_qagp returns a list of four elements:

- an approximation to the integral,
- the estimated absolute error of the approximation,
- the number integrand evaluations,
- an error code.

The error code (fourth element of the return value) can have the values:

- 0 no problems were encountered;
- 1 too many sub-intervals were done;
- 2 excessive roundoff error is detected;
- 3 extremely bad integrand behavior occurs;
- 4 failed to converge
- 5 integral is probably divergent or slowly convergent
- 6 if the input is invalid.

Examples:

```
(%i1) quad_qagp(x^3*log(abs((x^2-1)*(x^2-2))),x,0,3,[1,sqrt(2)]);
(%o1) [52.74074838347143, 2.6247632689546663e-7, 1029, 0]
(%i2) quad_qags(x^3*log(abs((x^2-1)*(x^2-2))), x, 0, 3);
(%o2) [52.74074847951494, 4.088443219529836e-7, 1869, 0]
```

The integrand has singularities at 1 and $\sqrt{2}$ so we supply these points to `quad_qagp`. We also note that `quad_qagp` is more accurate and more efficient than `quad_qags`.

quad_control (*parameter*, [*value*]) Function

Control error handling for quadpack. The parameter should be one of the following symbols:

current_error

The current error number

control Controls if messages are printed or not. If it is set to zero or less, messages are suppressed.

max_message

The maximum number of times any message is to be printed.

If *value* is not given, then the current value of the *parameter* is returned. If *value* is given, the value of *parameter* is set to the given value.

20 Equations

20.1 Functions and Variables for Equations

`%rnum_list`

System variable

Default value: `[]`

`%rnum_list` is the list of variables introduced in solutions by `solve` and `algsys`. `%r` variables are added to `%rnum_list` in the order they are created. This is convenient for doing substitutions into the solution later on. It's recommended to use this list rather than doing `concat ('%r, j)`.

```
(%i1) solve ([x + y = 3], [x,y]);
(%o1)          [[x = 3 - %r1, y = %r1]]
(%i2) %rnum_list;
(%o2)          [%r1]
(%i3) sol : solve ([x + 2*y + 3*z = 4], [x,y,z]);
(%o3)          [[x = - 2 %r3 - 3 %r2 + 4, y = %r3, z = %r2]]
(%i4) %rnum_list;
(%o4)          [%r2, %r3]
(%i5) for i : 1 thru length (%rnum_list) do
      sol : subst (t[i], %rnum_list[i], sol)$
(%i6) sol;
(%o6)          [[x = - 2 t2 - 3 t1 + 4, y = t2, z = t1]]
```

`algepsilon`

Option variable

Default value: `10^8``algepsilon` is used by `algsys`.

`algexact`

Option variable

Default value: `false``algexact` affects the behavior of `algsys` as follows:

If `algexact` is `true`, `algsys` always calls `solve` and then uses `realroots` on `solve`'s failures.

If `algexact` is `false`, `solve` is called only if the eliminant was not univariate, or if it was a quadratic or biquadratic.

Thus `algexact: true` does not guarantee only exact solutions, just that `algsys` will first try as hard as it can to give exact solutions, and only yield approximations when all else fails.

`algsys` (`[expr_1, ..., expr_m], [x_1, ..., x_n]`)

Function

`algsys` (`[eqn_1, ..., eqn_m], [x_1, ..., x_n]`)

Function

Solves the simultaneous polynomials `expr_1, ..., expr_m` or polynomial equations `eqn_1, ..., eqn_m` for the variables `x_1, ..., x_n`. An expression `expr` is equivalent to an equation `expr = 0`. There may be more equations than variables or vice versa.

`algsys` returns a list of solutions, with each solution given as a list of equations stating values of the variables `x_1, ..., x_n` which satisfy the system of equations. If `algsys` cannot find a solution, an empty list `[]` is returned.

The symbols `%r1, %r2, ...`, are introduced as needed to represent arbitrary parameters in the solution; these variables are also appended to the list `%rnum_list`.

The method is as follows:

1. First the equations are factored and split into subsystems.

2. For each subsystem S_i , an equation E and a variable x are selected. The variable is chosen to have lowest nonzero degree. Then the resultant of E and E_j with respect to x is computed for each of the remaining equations E_j in the subsystem S_i . This yields a new subsystem S_i' in one fewer variables, as x has been eliminated. The process now returns to (1).
3. Eventually, a subsystem consisting of a single equation is obtained. If the equation is multivariate and no approximations in the form of floating point numbers have been introduced, then `solve` is called to find an exact solution.

In some cases, `solve` is not be able to find a solution, or if it does the solution may be a very large expression.

If the equation is univariate and is either linear, quadratic, or biquadratic, then again `solve` is called if no approximations have been introduced. If approximations have been introduced or the equation is not univariate and neither linear, quadratic, or biquadratic, then if the switch `realonly` is `true`, the function `realroots` is called to find the real-valued solutions. If `realonly` is `false`, then `allroots` is called which looks for real and complex-valued solutions.

If `algsys` produces a solution which has fewer significant digits than required, the user can change the value of `algepsilon` to a higher value.

If `algebraexact` is set to `true`, `solve` will always be called.

4. Finally, the solutions obtained in step (3) are substituted into previous levels and the solution process returns to (1).

When `algsys` encounters a multivariate equation which contains floating point approximations (usually due to its failing to find exact solutions at an earlier stage), then it does not attempt to apply exact methods to such equations and instead prints the message: "algsys cannot solve - system too complicated."

Interactions with `radcan` can produce large or complicated expressions. In that case, it may be possible to isolate parts of the result with `pickapart` or `reveal`.

Occasionally, `radcan` may introduce an imaginary unit `%i` into a solution which is actually real-valued.

Examples:

```
(%i1) e1: 2*x*(1 - a1) - 2*(x - 1)*a2;
(%o1)          2 (1 - a1) x - 2 a2 (x - 1)
(%i2) e2: a2 - a1;
(%o2)          a2 - a1
(%i3) e3: a1*(-y - x^2 + 1);
(%o3)          a1 (- y - x^2 + 1)
(%i4) e4: a2*(y - (x - 1)^2);
(%o4)          a2 (y - (x - 1)^2)
(%i5) algsys ([e1, e2, e3, e4], [x, y, a1, a2]);
(%o5) [[x = 0, y = %r1, a1 = 0, a2 = 0],

[x = 1, y = 0, a1 = 1, a2 = 1]]
(%i6) e1: x^2 - y^2;
(%o6)          x^2 - y^2
(%i7) e2: -1 - y + 2*y^2 - x + x^2;
(%o7)          2 y^2 - y - x + x^2 - 1
(%i8) algsys ([e1, e2], [x, y]);
(%o8) [[x = - ----, y = ----],
          sqrt(3)      sqrt(3)]
```

$$[x = \frac{1}{\sqrt{3}}, y = -\frac{1}{\sqrt{3}}], [x = -\frac{1}{3}, y = -\frac{1}{3}], [x = 1, y = 1]]$$

allroots (*expr*)

Function

allroots (*eqn*)

Function

Computes numerical approximations of the real and complex roots of the polynomial *expr* or polynomial equation *eqn* of one variable.

The flag **polyfactor** when **true** causes **allroots** to factor the polynomial over the real numbers if the polynomial is real, or over the complex numbers, if the polynomial is complex.

allroots may give inaccurate results in case of multiple roots. If the polynomial is real, **allroots** (*%i*p*) may yield more accurate approximations than **allroots** (*p*), as **allroots** invokes a different algorithm in that case.

allroots rejects non-polynomials. It requires that the numerator after **rat**'ing should be a polynomial, and it requires that the denominator be at most a complex number. As a result of this **allroots** will always return an equivalent (but factored) expression, if **polyfactor** is **true**.

For complex polynomials an algorithm by Jenkins and Traub is used (Algorithm 419, *Comm. ACM*, vol. 15, (1972), p. 97). For real polynomials the algorithm used is due to Jenkins (Algorithm 493, *ACM TOMS*, vol. 1, (1975), p.178).

Examples:

```
(%i1) eqn: (1 + 2*x)^3 = 13.5*(1 + x^5);
              3          5
(%o1)          (2 x + 1) = 13.5 (x + 1)
(%i2) soln: allroots (eqn);
(%o2) [x = .8296749902129361, x = - 1.015755543828121,
x = .9659625152196369 %i - .4069597231924075,
x = - .9659625152196369 %i - .4069597231924075, x = 1.0]
(%i3) for e in soln
      do (e2: subst (e, eqn), disp (expand (lhs(e2) - rhs(e2))));
          - 3.5527136788005E-15
          - 5.32907051820075E-15
          4.44089209850063E-15 %i - 4.88498130835069E-15
          - 4.44089209850063E-15 %i - 4.88498130835069E-15
          3.5527136788005E-15
(%o3) done
(%i4) polyfactor: true$
(%i5) allroots (eqn);
(%o5) - 13.5 (x - 1.0) (x - .8296749902129361)
              2
(x + 1.015755543828121) (x + .8139194463848151 x
+ 1.098699797110288)
```

bfallroots (*expr*) Function
bfallroots (*eqn*) Function

Computes numerical approximations of the real and complex roots of the polynomial *expr* or polynomial equation *eqn* of one variable.

In all respects, **bfallroots** is identical to **allroots** except that **bfallroots** computes the roots using bigfloats. See **allroots** for more information.

backsubst Option variable

Default value: **true**

When **backsubst** is **false**, prevents back substitution in **linsolve** after the equations have been triangularized. This may be helpful in very big problems where back substitution would cause the generation of extremely large expressions.

```
(%i1) eq1 : x + y + z = 6$
(%i2) eq2 : x - y + z = 2$
(%i3) eq3 : x + y - z = 0$
(%i4) backsubst : false$
(%i5) linsolve ([eq1, eq2, eq3], [x,y,z]);
(%o5)          [x = z - y, y = 2, z = 3]
(%i6) backsubst : true$
(%i7) linsolve ([eq1, eq2, eq3], [x,y,z]);
(%o7)          [x = 1, y = 2, z = 3]
```

breakup Option variable

Default value: **true**

When **breakup** is **true**, **solve** expresses solutions of cubic and quartic equations in terms of common subexpressions, which are assigned to intermediate expression labels (%t1, %t2, etc.). Otherwise, common subexpressions are not identified.

breakup: true has an effect only when **programmode** is **false**.

Examples:

```
(%i1) programmode: false$
(%i2) breakup: true$
(%i3) solve (x^3 + x^2 - 1);
```

```
(%t3)          sqrt(23)      25 1/3
      (----- + ---)
          6 sqrt(3)      54
```

Solution:

```
(%t4)          sqrt(3) %i      1
      x = (- ---- - -) %t3 + ---- - -
              2          2          9 %t3      3
```

```
(%t5)          sqrt(3) %i      1
      x = (---- - -) %t3 + ---- - -
              2          2          9 %t3      3
```

```
(%t6)          1      1
      x = %t3 + ---- - -
              9 %t3      3
```

```
(%o6)          [%t4, %t5, %t6]
```

```
(%i6) breakup: false$
(%i7) solve (x^3 + x^2 - 1);
Solution:
```

```
(%t7) x = 
$$\frac{\frac{\sqrt{3}}{2} \frac{i}{2} - \frac{1}{2}}{\sqrt{23} \frac{25}{6} \sqrt{3} \frac{1}{54}} + \left( \frac{\sqrt{23}}{6 \sqrt{3}} + \frac{25}{54} \right)^{1/3}$$

```

```
(%t8) x = 
$$\left( \frac{\sqrt{23}}{6 \sqrt{3}} + \frac{25}{54} \right)^{1/3} \left( -\frac{\sqrt{3}}{2} \frac{i}{2} - \frac{1}{3} \right) - \frac{1}{3}$$

```

```
(%t9) x = 
$$\left( \frac{\sqrt{23}}{6 \sqrt{3}} + \frac{25}{54} \right)^{1/3} + \frac{\frac{\sqrt{3}}{2} \frac{i}{2} - \frac{1}{2}}{\sqrt{23} \frac{25}{6} \sqrt{3} \frac{1}{54}} - \frac{1}{3}$$

```

```
(%o9) [%t7, %t8, %t9]
```

dimension (*eqn*) Function
dimension (*eqn_1, ..., eqn_n*) Function

dimen is a package for dimensional analysis. `load ("dimen")` loads this package. `demo ("dimen")` displays a short demonstration.

dispflag Option variable
 Default value: `true`

If set to `false` within a `block` will inhibit the display of output generated by the solve functions called from within the `block`. Termination of the `block` with a dollar sign, `$`, sets `dispflag` to `false`.

funcsolve (*eqn, g(t)*) Function

Returns `[g(t) = ...]` or `[]`, depending on whether or not there exists a rational function $g(t)$ satisfying *eqn*, which must be a first order, linear polynomial in (for this case) $g(t)$ and $g(t+1)$

```
(%i1) eqn: (n + 1)*f(n) - (n + 3)*f(n + 1)/(n + 1) =
          (n - 1)/(n + 2);
(%o1)      (n + 1) f(n) - 
$$\frac{(n + 3) f(n + 1)}{n + 1} = \frac{n - 1}{n + 2}$$

(%i2) funcsolve (eqn, f(n));
```

Dependent equations eliminated: (4 3)

$$f(n) = \frac{n}{(n+1)(n+2)}$$

Warning: this is a very rudimentary implementation – many safety checks and obvious generalizations are missing.

globalsolve

Option variable

Default value: false

When `globalsolve` is `true`, solved-for variables are assigned the solution values found by `linsolve`, and by `solve` when solving two or more linear equations.

When `globalsolve` is `false`, solutions found by `linsolve` and by `solve` when solving two or more linear equations are expressed as equations, and the solved-for variables are not assigned.

When solving anything other than two or more linear equations, `solve` ignores `globalsolve`. Other functions which solve equations (e.g., `algsys`) always ignore `globalsolve`.

Examples:

```
(%i1) globalsolve: true$
(%i2) solve ([x + 3*y = 2, 2*x - y = 5], [x, y]);
Solution
```

$$x = -\frac{17}{7}$$

$$y = -\frac{1}{7}$$

```
(%o3) [[%t2, %t3]]
```

```
(%i3) x;
```

$$-\frac{17}{7}$$

```
(%i4) y;
```

$$-\frac{1}{7}$$

```
(%i5) globalsolve: false$
```

```
(%i6) kill (x, y)$
```

```
(%i7) solve ([x + 3*y = 2, 2*x - y = 5], [x, y]);
Solution
```

$$x = -\frac{17}{7}$$

$$y = -\frac{1}{7}$$

```
(%o8) [[%t7, %t8]]
```

```
(%i8) x;
```

$$x$$

```
(%i9) y;
```

$$y$$

ieqn (*ie, unk, tech, n, guess*)

Function

inteqn is a package for solving integral equations. `load ("inteqn")` loads this package.

ie is the integral equation; *unk* is the unknown function; *tech* is the technique to be tried from those given above (*tech* = **first** means: try the first technique which finds a solution; *tech* = **all** means: try all applicable techniques); *n* is the maximum number of terms to take for **taylor**, **neumann**, **firstkindseries**, or **fredseries** (it is also the maximum depth of recursion for the differentiation method); *guess* is the initial guess for **neumann** or **firstkindseries**.

Default values for the 2nd thru 5th parameters are:

unk: $p(x)$, where p is the first function encountered in an integrand which is unknown to Maxima and x is the variable which occurs as an argument to the first occurrence of p found outside of an integral in the case of **secondkind** equations, or is the only other variable besides the variable of integration in **firstkind** equations. If the attempt to search for x fails, the user will be asked to supply the independent variable.

tech: **first**

n: 1

guess: **none** which will cause **neumann** and **firstkindseries** to use $f(x)$ as an initial guess.

ieqnprint

Option variable

Default value: **true**

ieqnprint governs the behavior of the result returned by the **ieqn** command. When **ieqnprint** is **false**, the lists returned by the **ieqn** function are of the form

$[solution, technique\ used, nterms, flag]$

where *flag* is absent if the solution is exact.

Otherwise, it is the word **approximate** or **incomplete** corresponding to an inexact or non-closed form solution, respectively. If a series method was used, *nterms* gives the number of terms taken (which could be less than the n given to **ieqn** if an error prevented generation of further terms).

lhs (*expr*)

Function

Returns the left-hand side (that is, the first argument) of the expression *expr*, when the operator of *expr* is one of the relational operators **<** **<=** **#** **equal** **notequal** **>=** **>**, one of the assignment operators **:=** **::=** **:** **::**, or a user-defined binary infix operator, as declared by **infix**.

When *expr* is an atom or its operator is something other than the ones listed above, **lhs** returns *expr*.

See also **rhs**.

Examples:

```
(%i1) e: aa + bb = cc;
(%o1)                                     bb + aa = cc
(%i2) lhs (e);
(%o2)                                     bb + aa
(%i3) rhs (e);
(%o3)                                     cc
(%i4) [lhs (aa < bb), lhs (aa <= bb), lhs (aa >= bb),
      lhs (aa > bb)];
(%o4) [aa, aa, aa, aa]
(%i5) [lhs (aa = bb), lhs (aa # bb), lhs (equal (aa, bb)),
      lhs (notequal (aa, bb))];
(%o5) [aa, aa, aa, aa]
(%i6) e1: '(foo(x) := 2*x);
(%o6)                                     foo(x) := 2 x
(%i7) e2: '(bar(y) ::= 3*y);
```

```

(%o7)                                bar(y) ::= 3 y
(%i8) e3: '(x : y);
(%o8)                                x : y
(%i9) e4: '(x :: y);
(%o9)                                x :: y
(%i10) [lhs (e1), lhs (e2), lhs (e3), lhs (e4)];
(%o10) [foo(x), bar(y), x, x]
(%i11) infix ("["");
(%o11)                                ][
(%i12) lhs (aa) [ bb);
(%o12)                                aa

```

linsolve ([*expr_1*, ..., *expr_m*], [*x_1*, ..., *x_n*]) Function

Solves the list of simultaneous linear equations for the list of variables. The expressions must each be polynomials in the variables and may be equations.

When **globalsolve** is **true**, each solved-for variable is bound to its value in the solution of the equations.

When **backsubst** is **false**, **linsolve** does not carry out back substitution after the equations have been triangularized. This may be necessary in very big problems where back substitution would cause the generation of extremely large expressions.

When **linsolve_params** is **true**, **linsolve** also generates the **%r** symbols used to represent arbitrary parameters described in the manual under **algsys**. Otherwise, **linsolve** solves an under-determined system of equations with some variables expressed in terms of others.

When **programmode** is **false**, **linsolve** displays the solution with intermediate expression (**%t**) labels, and returns the list of labels.

```

(%i1) e1: x + z = y;
(%o1)                                z + x = y
(%i2) e2: 2*a*x - y = 2*a^2;
(%o2)                                2 a x - y = 2 a
(%i3) e3: y - 2*z = 2;
(%o3)                                y - 2 z = 2
(%i4) [globalsolve: false, programmode: true];
(%o4)                                [false, true]
(%i5) linsolve ([e1, e2, e3], [x, y, z]);
(%o5)                                [x = a + 1, y = 2 a, z = a - 1]
(%i6) [globalsolve: false, programmode: false];
(%o6)                                [false, false]
(%i7) linsolve ([e1, e2, e3], [x, y, z]);
Solution

(%t7)                                z = a - 1

(%t8)                                y = 2 a

(%t9)                                x = a + 1
(%o9)                                [%t7, %t8, %t9]
(%i9) ',',;
(%o9)                                [z = a - 1, y = 2 a, x = a + 1]
(%i10) [globalsolve: true, programmode: false];
(%o10)                                [true, false]
(%i11) linsolve ([e1, e2, e3], [x, y, z]);
Solution

(%t11)                                z : a - 1

```

```

(%t12)                y : 2 a

(%t13)                x : a + 1
(%o13)                [%t11, %t12, %t13]
(%i13) ' ';
(%o13)                [z : a - 1, y : 2 a, x : a + 1]
(%i14) [x, y, z];
(%o14)                [a + 1, 2 a, a - 1]
(%i15) [globalsolve: true, programmode: true];
(%o15)                [true, true]
(%i16) linsolve ([e1, e2, e3], '[x, y, z]);
(%o16)                [x : a + 1, y : 2 a, z : a - 1]
(%i17) [x, y, z];
(%o17)                [a + 1, 2 a, a - 1]

```

linsolvewarn

Option variable

Default value: `true`

When `linsolvewarn` is `true`, `linsolve` prints a message "Dependent equations eliminated".

linsolve_params

Option variable

Default value: `true`

When `linsolve_params` is `true`, `linsolve` also generates the `%r` symbols used to represent arbitrary parameters described in the manual under `algsys`. Otherwise, `linsolve` solves an under-determined system of equations with some variables expressed in terms of others.

multiplicities

System variable

Default value: `not_set_yet`

`multiplicities` is set to a list of the multiplicities of the individual solutions returned by `solve` or `realroots`.

nroots (*p*, *low*, *high*)

Function

Returns the number of real roots of the real univariate polynomial *p* in the half-open interval [*low*, *high*]. The endpoints of the interval may be `minf` or `inf`.

`nroots` uses the method of Sturm sequences.

```

(%i1) p: x^10 - 2*x^4 + 1/2$
(%i2) nroots (p, -6, 9.1);
(%o2)                4

```

nthroot (*p*, *n*)

Function

where *p* is a polynomial with integer coefficients and *n* is a positive integer returns *q*, a polynomial over the integers, such that $q^n = p$ or prints an error message indicating that *p* is not a perfect *n*th power. This routine is much faster than `factor` or even `sqfr`.

polyfactor

Option variable

Default value: `false`

The option variable `polyfactor` when `true` causes `allroots` and `bfallroots` to factor the polynomial over the real numbers if the polynomial is real, or over the complex numbers, if the polynomial is complex.

See `allroots` for an example.

programmode

Option variable

Default value: `true`

When `programmode` is `true`, `solve`, `realroots`, `allroots`, and `linsolve` return solutions as elements in a list. (Except when `backsubst` is set to `false`, in which case `programmode: false` is assumed.)

When `programmode` is `false`, `solve`, etc. create intermediate expression labels `%t1`, `t2`, etc., and assign the solutions to them.

realonly

Option variable

Default value: `false`

When `realonly` is `true`, `algsys` returns only those solutions which are free of `%i`.

realroots (*expr*, *bound*)

Function

realroots (*eqn*, *bound*)

Function

realroots (*expr*)

Function

realroots (*eqn*)

Function

Computes rational approximations of the real roots of the polynomial *expr* or polynomial equation *eqn* of one variable, to within a tolerance of *bound*. Coefficients of *expr* or *eqn* must be literal numbers; symbol constants such as `%pi` are rejected.

`realroots` assigns the multiplicities of the roots it finds to the global variable `multiplicities`.

`realroots` constructs a Sturm sequence to bracket each root, and then applies bisection to refine the approximations. All coefficients are converted to rational equivalents before searching for roots, and computations are carried out by exact rational arithmetic. Even if some coefficients are floating-point numbers, the results are rational (unless coerced to floats by the `float` or `numer` flags).

When *bound* is less than 1, all integer roots are found exactly. When *bound* is unspecified, it is assumed equal to the global variable `rootsepsilon`.

When the global variable `programmode` is `true`, `realroots` returns a list of the form `[x = x_1, x = x_2, ...]`. When `programmode` is `false`, `realroots` creates intermediate expression labels `%t1`, `%t2`, ..., assigns the results to them, and returns the list of labels.

Examples:

```
(%i1) realroots (-1 - x + x^5, 5e-6);
                                612003
(%o1)                        [x = -----]
                                524288

(%i2) ev (%[1], float);
(%o2)                        x = 1.167303085327148
(%i3) ev (-1 - x + x^5, %);
(%o3)                        - 7.396496210176905E-6
(%i1) realroots (expand ((1 - x)^5 * (2 - x)^3 * (3 - x)), 1e-20);
(%o1)                        [x = 1, x = 2, x = 3]
(%i2) multiplicities;
(%o2)                        [5, 3, 1]
```

rhs (*expr*)

Function

Returns the right-hand side (that is, the second argument) of the expression *expr*, when the operator of *expr* is one of the relational operators `<` `<=` `#` `equal` `notequal` `>=` `>`, one of the assignment operators `:=` `::=` `:` `::`, or a user-defined binary infix operator, as declared by `infix`.

When *expr* is an atom or its operator is something other than the ones listed above, `rhs` returns 0.

See also `lhs`.

Examples:

```

(%i1) e: aa + bb = cc;
(%o1)                                     bb + aa = cc
(%i2) lhs (e);
(%o2)                                     bb + aa
(%i3) rhs (e);
(%o3)                                     cc
(%i4) [rhs (aa < bb), rhs (aa <= bb), rhs (aa >= bb),
      rhs (aa > bb)];
(%o4) [bb, bb, bb, bb]
(%i5) [rhs (aa = bb), rhs (aa # bb), rhs (equal (aa, bb)),
      rhs (notequal (aa, bb))];
(%o5) [bb, bb, bb, bb]
(%i6) e1: '(foo(x) := 2*x);
(%o6)                                     foo(x) := 2 x
(%i7) e2: '(bar(y) ::= 3*y);
(%o7)                                     bar(y) ::= 3 y
(%i8) e3: '(x : y);
(%o8)                                     x : y
(%i9) e4: '(x :: y);
(%o9)                                     x :: y
(%i10) [rhs (e1), rhs (e2), rhs (e3), rhs (e4)];
(%o10) [2 x, 3 y, y, y]
(%i11) infix ("["");
(%o11)                                     ][
(%i12) rhs (aa ][ bb);
(%o12)                                     bb

```

rootsconmode

Option variable

Default value: **true**

rootsconmode governs the behavior of the **rootscontract** command. See **rootscontract** for details.

rootscontract (expr)

Function

Converts products of roots into roots of products. For example, **rootscontract** (**sqrt(x)*y^(3/2)**) yields **sqrt(x*y³)**.

When **radexpand** is **true** and **domain** is **real**, **rootscontract** converts **abs** into **sqrt**, e.g., **rootscontract** (**abs(x)*sqrt(y)**) yields **sqrt(x²*y)**.

There is an option **rootsconmode** affecting **rootscontract** as follows:

Problem	Value of rootsconmode	Result of applying rootscontract
$x^{(1/2)}y^{(3/2)}$	false	$(xy^3)^{(1/2)}$
$x^{(1/2)}y^{(1/4)}$	false	$x^{(1/2)}y^{(1/4)}$
$x^{(1/2)}y^{(1/4)}$	true	$(xy^{(1/2)})^{(1/2)}$
$x^{(1/2)}y^{(1/3)}$	true	$x^{(1/2)}y^{(1/3)}$
$x^{(1/2)}y^{(1/4)}$	all	$(x^2y)^{(1/4)}$
$x^{(1/2)}y^{(1/3)}$	all	$(x^3y^2)^{(1/6)}$

When **rootsconmode** is **false**, **rootscontract** contracts only with respect to rational number exponents whose denominators are the same. The key to the **rootsconmode: true** examples is simply that 2 divides into 4 but not into 3. **rootsconmode: all** involves taking the least common multiple of the denominators of the exponents.

rootscontract uses **ratsimp** in a manner similar to **logcontract**.

Examples:

```

(%i1) rootsconmode: false$
(%i2) rootscontract (x^(1/2)*y^(3/2));
              3
(%o2)          sqrt(x y )
(%i3) rootscontract (x^(1/2)*y^(1/4));
              1/4
(%o3)          sqrt(x) y
(%i4) rootsconmode: true$
(%i5) rootscontract (x^(1/2)*y^(1/4));
(%o5)          sqrt(x sqrt(y))
(%i6) rootscontract (x^(1/2)*y^(1/3));
              1/3
(%o6)          sqrt(x) y
(%i7) rootsconmode: all$
(%i8) rootscontract (x^(1/2)*y^(1/4));
              2 1/4
(%o8)          (x y )
(%i9) rootscontract (x^(1/2)*y^(1/3));
              3 2 1/6
(%o9)          (x y )
(%i10) rootsconmode: false$
(%i11) rootscontract (sqrt(sqrt(x) + sqrt(1 + x))
              *sqrt(sqrt(1 + x) - sqrt(x)));
(%o11)          1
(%i12) rootsconmode: true$
(%i13) rootscontract (sqrt(5+sqrt(5)) - 5^(1/4)*sqrt(1+sqrt(5)));
(%o13)          0

```

rootsepsilon

Option variable

Default value: 1.0e-7

rootsepsilon is the tolerance which establishes the confidence interval for the roots found by the **realroots** function.

solve (*expr*, *x*)

Function

solve (*expr*)

Function

solve ([*eqn_1*, ..., *eqn_n*], [*x_1*, ..., *x_n*])

Function

Solves the algebraic equation *expr* for the variable *x* and returns a list of solution equations in *x*. If *expr* is not an equation, the equation *expr* = 0 is assumed in its place. *x* may be a function (e.g. *f(x)*), or other non-atomic expression except a sum or product. *x* may be omitted if *expr* contains only one variable. *expr* may be a rational expression, and may contain trigonometric functions, exponentials, etc.

The following method is used:

Let *E* be the expression and *X* be the variable. If *E* is linear in *X* then it is trivially solved for *X*. Otherwise if *E* is of the form *A***X*^{*N*} + *B* then the result is (-*B*/*A*)^{1/*N*} times the *N*'th roots of unity.

If *E* is not linear in *X* then the gcd of the exponents of *X* in *E* (say *N*) is divided into the exponents and the multiplicity of the roots is multiplied by *N*. Then **solve** is called again on the result. If *E* factors then **solve** is called on each of the factors. Finally **solve** will use the quadratic, cubic, or quartic formulas where necessary.

In the case where *E* is a polynomial in some function of the variable to be solved for, say *F(X)*, then it is first solved for *F(X)* (call the result *C*), then the equation *F(X)*=*C* can be solved for *X* provided the inverse of the function *F* is known.

breakup if **false** will cause **solve** to express the solutions of cubic or quartic equations as single expressions rather than as made up of several common subexpressions which is the default.

multiplicities - will be set to a list of the multiplicities of the individual solutions returned by **solve**, **realroots**, or **allroots**. Try **apropos (solve)** for the switches which affect **solve**. **describe** may then be used on the individual switch names if their purpose is not clear.

solve (*eqn_1*, ..., *eqn_n*), [*x_1*, ..., *x_n*]) solves a system of simultaneous (linear or non-linear) polynomial equations by calling **linsolve** or **algsys** and returns a list of the solution lists in the variables. In the case of **linsolve** this list would contain a single list of solutions. It takes two lists as arguments. The first list represents the equations to be solved; the second list is a list of the unknowns to be determined. If the total number of variables in the equations is equal to the number of equations, the second argument-list may be omitted.

When **programmode** is **false**, **solve** displays solutions with intermediate expression (%t) labels, and returns the list of labels.

When **globalsolve** is **true** and the problem is to solve two or more linear equations, each solved-for variable is bound to its value in the solution of the equations.

Examples:

```
(%i1) solve (asin (cos (3*x))*(f(x) - 1), x);
```

```
solve: using arc-trig functions to get a solution.
Some solutions will be lost.
```

```
(%o1) [x = ---, f(x) = 1]
          %pi
          6
```

```
(%i2) ev (solve (5^f(x) = 125, f(x)), solveradcan);
          log(125)
```

```
(%o2) [f(x) = -----]
          log(5)
```

```
(%i3) [4*x^2 - y^2 = 12, x*y - x = 2];
          2      2
```

```
(%o3) [4 x  - y  = 12, x y - x = 2]
```

```
(%i4) solve (%, [x, y]);
```

```
(%o4) [[x = 2, y = 2], [x = .5202594388652008 %i
- .1331240357358706, y = .07678378523787788
- 3.608003221870287 %i], [x = - .5202594388652008 %i
- .1331240357358706, y = 3.608003221870287 %i
+ .07678378523787788], [x = - 1.733751846381093,
y = - .1535675710019696]]
```

```
(%i5) solve (1 + a*x + x^3, x);
```

```
(%o5) [x = (-
          sqrt(3) %i      1      sqrt(4 a  + 27)      1 1/3
          ----- - -) (-
          2              2              6 sqrt(3)      2
```

```

          sqrt(3) %i      1
          (----- - -) a
          2              2
- -----, x =
          3
          sqrt(4 a  + 27)      1 1/3
          3 (----- - -)
          6 sqrt(3)      2
```

```

sqrt(3) %i 1 sqrt(4 a + 27) 1 1/3
(----- - -) (----- - -)
2 2 6 sqrt(3) 2

sqrt(3) %i 1
(- ---- - -) a
2 2

- ----, x =
3
sqrt(4 a + 27) 1 1/3
3 (----- - -)
6 sqrt(3) 2

3
sqrt(4 a + 27) 1 1/3 a
(----- - -) - ----]
6 sqrt(3) 2 3
sqrt(4 a + 27) 1 1/3
3 (----- - -)
6 sqrt(3) 2

(%i6) solve (x^3 - 1);
sqrt(3) %i - 1 sqrt(3) %i + 1
(%o6) [x = ----, x = - ----, x = 1]
2 2

(%i7) solve (x^6 - 1);
sqrt(3) %i + 1 sqrt(3) %i - 1
(%o7) [x = ----, x = ----, x = - 1,
2 2

x = - ----, x = - ----, x = 1]
2 2

(%i8) ev (x^6 - 1, %[1]);
6
(sqrt(3) %i + 1)
(%o8) ---- - 1
64

(%i9) expand (%);
0
(%o9)
2
x - 1
(%o10)
(%i11) solve (%, x);
[x = - 1, x = 1]
(%o11)
(%i12) ev (%th(2), %[1]);
0
(%o12)

```

The symbols %r are used to denote arbitrary constants in a solution.

```
(%i1) solve([x+y=1, 2*x+2*y=2], [x, y]);
```

```
solve: dependent equations eliminated: (2)
```

```
(%o1) [[x = 1 - %r1, y = %r1]]
```

See `algsys` and `%rnum_list` for more information.

solvedecomposes

Option variable

Default value: `true`

When `solvedecomposes` is `true`, `solve` calls `polydecomp` if asked to solve polynomials.

solveexplicit

Option variable

Default value: `false`

When `solveexplicit` is `true`, inhibits `solve` from returning implicit solutions, that is, solutions of the form $F(x) = 0$ where F is some function.

solvefactors

Option variable

Default value: `true`

When `solvefactors` is `false`, `solve` does not try to factor the expression. The `false` setting may be desired in some cases where factoring is not necessary.

solvenullwarn

Option variable

Default value: `true`

When `solvenullwarn` is `true`, `solve` prints a warning message if called with either a null equation list or a null variable list. For example, `solve([], [])` would print two warning messages and return `[]`.

solveradcan

Option variable

Default value: `false`

When `solveradcan` is `true`, `solve` calls `radcan` which makes `solve` slower but will allow certain problems containing exponentials and logarithms to be solved.

solvetricwarn

Option variable

Default value: `true`

When `solvetricwarn` is `true`, `solve` may print a message saying that it is using inverse trigonometric functions to solve the equation, and thereby losing solutions.

21 Differential Equations

21.1 Introduction to Differential Equations

This section describes the functions available in Maxima to obtain analytic solutions for some specific types of first and second-order equations. To obtain a numerical solution for a system of differential equations, see the additional package `dynamics`. For graphical representations in phase space, see the additional package `plotdf`.

21.2 Functions and Variables for Differential Equations

bc2 (*solution*, *xval1*, *yval1*, *xval2*, *yval2*) Function
 Solves a boundary value problem for a second order differential equation. Here: *solution* is a general solution to the equation, as found by `ode2`; *xval1* specifies the value of the independent variable in a first point, in the form $x = x1$, and *yval1* gives the value of the dependent variable in that point, in the form $y = y1$. The expressions *xval2* and *yval2* give the values for these variables at a second point, using the same form.
 See `ode2` for an example of its usage.

desolve (*eqn*, *x*) Function
desolve ([*eqn_1*, ..., *eqn_n*], [*x_1*, ..., *x_n*]) Function

The function `desolve` solves systems of linear ordinary differential equations using Laplace transform. Here the *eqn*'s are differential equations in the dependent variables x_1, \dots, x_n . The functional dependence of x_1, \dots, x_n on an independent variable, for instance x , must be explicitly indicated in the variables and its derivatives. For example, this would not be the correct way to define two equations:

```
eqn_1: 'diff(f,x,2) = sin(x) + 'diff(g,x);
eqn_2: 'diff(f,x) + x^2 - f = 2*'diff(g,x,2);
```

The correct way would be:

```
eqn_1: 'diff(f(x),x,2) = sin(x) + 'diff(g(x),x);
eqn_2: 'diff(f(x),x) + x^2 - f(x) = 2*'diff(g(x),x,2);
```

The call to the function `desolve` would then be

```
desolve([eqn_1, eqn_2], [f(x),g(x)]);
```

If initial conditions at $x=0$ are known, they can be supplied before calling `desolve` by using `atvalue`.

```
(%i1) 'diff(f(x),x)='diff(g(x),x)+sin(x);
      d          d
(%o1)  -- (f(x)) = -- (g(x)) + sin(x)
      dx          dx
(%i2) 'diff(g(x),x,2)='diff(f(x),x)-cos(x);
      2
      d          d
(%o2)  --- (g(x)) = -- (f(x)) - cos(x)
      2          dx
      dx
(%i3) atvalue('diff(g(x),x),x=0,a);
(%o3)  a
(%i4) atvalue(f(x),x=0,1);
(%o4)  1
(%i5) desolve([%o1,%o2],[f(x),g(x)]);
      x
(%o5) [f(x) = a %e  - a + 1, g(x) =
```

```

                                x
                                cos(x) + a %e  - a + g(0) - 1]
(%i6) [%o1,%o2],%o5,diff;

                                x      x      x      x
(%o6)  [a %e  = a %e , a %e  - cos(x) = a %e  - cos(x)]

```

If `desolve` cannot obtain a solution, it returns `false`.

ic1 (*solution, xval, yval*) Function

Solves initial value problems for first order differential equations. Here *solution* is a general solution to the equation, as found by `ode2`, *xval* gives an initial value for the independent variable in the form $x = x0$, and *yval* gives the initial value for the dependent variable in the form $y = y0$.

See `ode2` for an example of its usage.

ic2 (*solution, xval, yval, dval*) Function

Solves initial value problems for second-order differential equations. Here *solution* is a general solution to the equation, as found by `ode2`, *xval* gives the initial value for the independent variable in the form $x = x0$, *yval* gives the initial value of the dependent variable in the form $y = y0$, and *dval* gives the initial value for the first derivative of the dependent variable with respect to independent variable, in the form $\text{diff}(y,x) = dy0$ (`diff` does not have to be quoted).

See `ode2` for an example of its usage.

ode2 (*eqn, dvar, ivar*) Function

The function `ode2` solves an ordinary differential equation (ODE) of first or second order. It takes three arguments: an ODE given by *eqn*, the dependent variable *dvar*, and the independent variable *ivar*. When successful, it returns either an explicit or implicit solution for the dependent variable. `%c` is used to represent the integration constant in the case of first-order equations, and `%k1` and `%k2` the constants for second-order equations. The dependence of the dependent variable on the independent variable does not have to be written explicitly, as in the case of `desolve`, but the independent variable must always be given as the third argument.

If `ode2` cannot obtain a solution for whatever reason, it returns `false`, after perhaps printing out an error message. The methods implemented for first order equations in the order in which they are tested are: linear, separable, exact - perhaps requiring an integrating factor, homogeneous, Bernoulli's equation, and a generalized homogeneous method. The types of second-order equations which can be solved are: constant coefficients, exact, linear homogeneous with non-constant coefficients which can be transformed to constant coefficients, the Euler or equi-dimensional equation, equations solvable by the method of variation of parameters, and equations which are free of either the independent or of the dependent variable so that they can be reduced to two first order linear equations to be solved sequentially.

In the course of solving ODE's, several variables are set purely for informational purposes: `method` denotes the method of solution used (e.g., `linear`), `intfactor` denotes any integrating factor used, `odeindex` denotes the index for Bernoulli's method or for the generalized homogeneous method, and `yp` denotes the particular solution for the variation of parameters technique.

In order to solve initial value problems (IVP) functions `ic1` and `ic2` are available for first and second order equations, and to solve second-order boundary value problems (BVP) the function `bc2` can be used.

Example:

```

(%i1) x^2*'diff(y,x) + 3*y*x = sin(x)/x;
                                2 dy          sin(x)
(%o1)  x  -- + 3 x y = -----
                                dx          x

```

```
(%i2) ode2(%,y,x);
```

$$(\%o2) \quad y = \frac{\%c - \cos(x)}{x^3}$$

```
(%i3) ic1(%o2,x=%pi,y=0);
```

$$(\%o3) \quad y = -\frac{\cos(x) + 1}{x^3}$$

```
(%i4) 'diff(y,x,2) + y*'diff(y,x)^3 = 0;
```

$$(\%o4) \quad \frac{d^2 y}{dx^2} + y \left(\frac{dy}{dx} \right)^3 = 0$$

```
(%i5) ode2(%,y,x);
```

$$(\%o5) \quad \frac{y^3 + 6 \%k1 y}{6} = x + \%k2$$

```
(%i6) ratsimp(ic2(%o5,x=0,y=0,'diff(y,x)=2));
```

$$(\%o6) \quad -\frac{2 y^3 - 3 y}{6} = x$$

```
(%i7) bc2(%o5,x=0,y=1,x=1,y=3);
```

$$(\%o7) \quad \frac{y^3 - 10 y}{6} = x - \frac{3}{2}$$

22 Numerical

22.1 Introduction to fast Fourier transform

The `fft` package comprises functions for the numerical (not symbolic) computation of the fast Fourier transform.

22.2 Functions and Variables for fast Fourier transform

polartorect (*r*, *t*) Function

Translates complex values of the form $r e^{i t}$ to the form $a + b i$, where r is the magnitude and t is the phase. r and t are 1-dimensional arrays of the same size. The array size need not be a power of 2.

The original values of the input arrays are replaced by the real and imaginary parts, a and b , on return. The outputs are calculated as

```
a = r cos(t)
b = r sin(t)
```

`polartorect` is the inverse function of `recttopolar`.

`load(fft)` loads this function. See also `fft`.

recttopolar (*a*, *b*) Function

Translates complex values of the form $a + b i$ to the form $r e^{i t}$, where a is the real part and b is the imaginary part. a and b are 1-dimensional arrays of the same size. The array size need not be a power of 2.

The original values of the input arrays are replaced by the magnitude and angle, r and t , on return. The outputs are calculated as

```
r = sqrt(a^2 + b^2)
t = atan2(b, a)
```

The computed angle is in the range $-\pi$ to π .

`recttopolar` is the inverse function of `polartorect`.

`load(fft)` loads this function. See also `fft`.

inverse_fft (*y*) Function

Computes the inverse complex fast Fourier transform. y is a list or array (named or unnamed) which contains the data to transform. The number of elements must be a power of 2. The elements must be literal numbers (integers, rationals, floats, or bigfloats) or symbolic constants, or expressions $a + b i$ where a and b are literal numbers or symbolic constants.

`inverse_fft` returns a new object of the same type as y , which is not modified. Results are always computed as floats or expressions $a + b i$ where a and b are floats.

The inverse discrete Fourier transform is defined as follows. Let x be the output of the inverse transform. Then for j from 0 through $n - 1$,

$$x[j] = \sum(y[k] \exp(+2 i \pi j k / n), k, 0, n - 1)$$

`load(fft)` loads this function.

See also `fft` (forward transform), `recttopolar`, and `polartorect`.

Examples:

Real data.

```
(%i1) load (fft) $
(%i2) fpprintprec : 4 $
(%i3) L : [1, 2, 3, 4, -1, -2, -3, -4] $
(%i4) L1 : inverse_fft (L);
(%o4) [0.0, 14.49 %i - .8284, 0.0, 2.485 %i + 4.828, 0.0,
      4.828 - 2.485 %i, 0.0, - 14.49 %i - .8284]
(%i5) L2 : fft (L1);
(%o5) [1.0, 2.0 - 2.168L-19 %i, 3.0 - 7.525L-20 %i,
      4.0 - 4.256L-19 %i, - 1.0, 2.168L-19 %i - 2.0,
      7.525L-20 %i - 3.0, 4.256L-19 %i - 4.0]
(%i6) lmax (abs (L2 - L));
(%o6) 3.545L-16
```

Complex data.

```
(%i1) load (fft) $
(%i2) fpprintprec : 4 $
(%i3) L : [1, 1 + %i, 1 - %i, -1, -1, 1 - %i, 1 + %i, 1] $
(%i4) L1 : inverse_fft (L);
(%o4) [4.0, 2.711L-19 %i + 4.0, 2.0 %i - 2.0,
      - 2.828 %i - 2.828, 0.0, 5.421L-20 %i + 4.0, - 2.0 %i - 2.0,
      2.828 %i + 2.828]
(%i5) L2 : fft (L1);
(%o5) [4.066E-20 %i + 1.0, 1.0 %i + 1.0, 1.0 - 1.0 %i,
      1.55L-19 %i - 1.0, - 4.066E-20 %i - 1.0, 1.0 - 1.0 %i,
      1.0 %i + 1.0, 1.0 - 7.368L-20 %i]
(%i6) lmax (abs (L2 - L));
(%o6) 6.841L-17
```

fft (x)

Function

Computes the complex fast Fourier transform. x is a list or array (named or unnamed) which contains the data to transform. The number of elements must be a power of 2. The elements must be literal numbers (integers, rationals, floats, or bigfloats) or symbolic constants, or expressions $a + b\%i$ where a and b are literal numbers or symbolic constants.

fft returns a new object of the same type as x , which is not modified. Results are always computed as floats or expressions $a + b\%i$ where a and b are floats.

The discrete Fourier transform is defined as follows. Let y be the output of the transform. Then for k from 0 through $n - 1$,

$$y[k] = (1/n) \sum(x[j] \exp(-2 \%i \%pi j k / n), j, 0, n - 1)$$

When the data x are real, real coefficients a and b can be computed such that

$$x[j] = \sum(a[k] * \cos(2 \%pi * j * k / n) + b[k] * \sin(2 \%pi * j * k / n), k, 0, n/2)$$

with

$$\begin{aligned} a[0] &= \text{realpart} (y[0]) \\ b[0] &= 0 \end{aligned}$$

and, for k from 1 through $n/2 - 1$,

$$\begin{aligned} a[k] &= \text{realpart} (y[k] + y[n - k]) \\ b[k] &= \text{imagpart} (y[n - k] - y[k]) \end{aligned}$$

and

$$\begin{aligned} a[n/2] &= \text{realpart} (y[n/2]) \\ b[n/2] &= 0 \end{aligned}$$

load(fft) loads this function.

See also **inverse_fft** (inverse transform), **recttopolar**, and **polartorect**.

Examples:

Real data.


```
(%i1) load (fft) $
(%i2) fpprintprec : 4 $
(%i3) L : [1, 2, 3, 4, -1, -2, -3, -4] $
(%i4) L1 : fft (L);
(%o4) [0.0, - 1.811 %i - .1036, 0.0, .6036 - .3107 %i, 0.0,
      .3107 %i + .6036, 0.0, 1.811 %i - .1036]
(%i5) L2 : inverse_fft (L1);
(%o5) [1.0, 2.168L-19 %i + 2.0, 7.525L-20 %i + 3.0,
      4.256L-19 %i + 4.0, - 1.0, - 2.168L-19 %i - 2.0,
      - 7.525L-20 %i - 3.0, - 4.256L-19 %i - 4.0]
(%i6) lmax (abs (L2 - L));
(%o6) 3.545L-16
```

Complex data.

```
(%i1) load (fft) $
(%i2) fpprintprec : 4 $
(%i3) L : [1, 1 + %i, 1 - %i, -1, -1, 1 - %i, 1 + %i, 1] $
(%i4) L1 : fft (L);
(%o4) [0.5, .3536 %i + .3536, - 0.25 %i - 0.25,
      0.5 - 6.776L-21 %i, 0.0, - .3536 %i - .3536, 0.25 %i - 0.25,
      0.5 - 3.388L-20 %i]
(%i5) L2 : inverse_fft (L1);
(%o5) [1.0 - 4.066E-20 %i, 1.0 %i + 1.0, 1.0 - 1.0 %i,
      - 1.008L-19 %i - 1.0, 4.066E-20 %i - 1.0, 1.0 - 1.0 %i,
      1.0 %i + 1.0, 1.947L-20 %i + 1.0]
(%i6) lmax (abs (L2 - L));
(%o6) 6.83L-17
```

Computation of sine and cosine coefficients.

```
(%i1) load (fft) $
(%i2) fpprintprec : 4 $
(%i3) L : [1, 2, 3, 4, 5, 6, 7, 8] $
(%i4) n : length (L) $
(%i5) x : make_array (any, n) $
(%i6) fillarray (x, L) $
(%i7) y : fft (x) $
(%i8) a : make_array (any, n/2 + 1) $
(%i9) b : make_array (any, n/2 + 1) $
(%i10) a[0] : realpart (y[0]) $
(%i11) b[0] : 0 $
(%i12) for k : 1 thru n/2 - 1 do
      (a[k] : realpart (y[k] + y[n - k]),
       b[k] : imagpart (y[n - k] - y[k]));
(%o12) done
(%i13) a[n/2] : y[n/2] $
(%i14) b[n/2] : 0 $
(%i15) listarray (a);
(%o15) [4.5, - 1.0, - 1.0, - 1.0, - 0.5]
(%i16) listarray (b);
(%o16) [0, - 2.414, - 1.0, - .4142, 0]
(%i17) f(j) := sum (a[k]*cos(2*%pi*j*k/n) + b[k]*sin(2*%pi*j*k/n),
      k, 0, n/2) $
(%i18) makelist (float (f (j)), j, 0, n - 1);
(%o18) [1.0, 2.0, 3.0, 4.0, 5.0, 6.0, 7.0, 8.0]
```

horner (*expr*, *x*) Function
horner (*expr*) Function

Returns a rearranged representation of *expr* as in Horner's rule, using *x* as the main variable if it is specified. *x* may be omitted in which case the main variable of the canonical rational expression form of *expr* is used.

horner sometimes improves stability if *expr* is to be numerically evaluated. It is also useful if Maxima is used to generate programs to be run in Fortran. See also **stringout**.

```
(%i1) expr: 1e-155*x^2 - 5.5*x + 5.2e155;
      2
(%o1)      1.0E-155 x  - 5.5 x + 5.2E+155
(%i2) expr2: horner (%i1, x), keepfloat: true;
(%o2)      (1.0E-155 x - 5.5) x + 5.2E+155
(%i3) ev (expr, x=1e155);
Maxima encountered a Lisp error:

floating point overflow

Automatically continuing.
To reenale the Lisp debugger set *debugger-hook* to nil.
(%i4) ev (expr2, x=1e155);
(%o4)      7.0E+154
```

find_root (*expr*, *x*, *a*, *b*, [*abserr*, *relerr*]) Function
find_root (*f*, *a*, *b*, [*abserr*, *relerr*]) Function
bf_find_root (*expr*, *x*, *a*, *b*, [*abserr*, *relerr*]) Function
bf_find_root (*f*, *a*, *b*, [*abserr*, *relerr*]) Function
find_root_error Option variable
find_root_abs Option variable
find_root_rel Option variable

Finds a root of the expression *expr* or the function *f* over the closed interval [*a*, *b*]. The expression *expr* may be an equation, in which case **find_root** seeks a root of **lhs**(*expr*) - **rhs**(*expr*).

Given that Maxima can evaluate *expr* or *f* over [*a*, *b*] and that *expr* or *f* is continuous, **find_root** is guaranteed to find the root, or one of the roots if there is more than one.

find_root initially applies binary search. If the function in question appears to be smooth enough, **find_root** applies linear interpolation instead.

bf_find_root is a bigfloat version of **find_root**. The function is computed using bigfloat arithmetic and a bigfloat result is returned. Otherwise, **bf_find_root** is identical to **find_root**, and the following description is equally applicable to **bf_find_root**.

The accuracy of **find_root** is governed by **abserr** and **relerr**, which are optional keyword arguments to **find_root**. These keyword arguments take the form **key=val**. The keyword arguments are

abserr Desired absolute error of function value at root. Default is **find_root_abs**.

relerr Desired relative error of root. Default is **find_root_rel**.

find_root stops when the function in question evaluates to something less than or equal to **abserr**, or if successive approximants *x*₀, *x*₁ differ by no more than **relerr** * **max**(**abs**(*x*₀), **abs**(*x*₁)). The default values of **find_root_abs** and **find_root_rel** are both zero.

find_root expects the function in question to have a different sign at the endpoints of the search interval. When the function evaluates to a number at both endpoints and these numbers have the same sign, the behavior of **find_root** is governed by **find_root_error**. When **find_root_error** is **true**, **find_root** prints an error message. Otherwise **find_root** returns the value of **find_root_error**. The default value of **find_root_error** is **true**.

If f evaluates to something other than a number at any step in the search algorithm, `find_root` returns a partially-evaluated `find_root` expression.

The order of a and b is ignored; the region in which a root is sought is $[min(a, b), max(a, b)]$.

Examples:

```
(%i1) f(x) := sin(x) - x/2;
(%o1)

$$f(x) := \sin(x) - \frac{x}{2}$$

(%i2) find_root (sin(x) - x/2, x, 0.1, %pi);
(%o2) 1.895494267033981
(%i3) find_root (sin(x) = x/2, x, 0.1, %pi);
(%o3) 1.895494267033981
(%i4) find_root (f(x), x, 0.1, %pi);
(%o4) 1.895494267033981
(%i5) find_root (f, 0.1, %pi);
(%o5) 1.895494267033981
(%i6) find_root (exp(x) = y, x, 0, 100);
(%o6)

$$\text{find\_root}(\%e^x = y, x, 0.0, 100.0)$$

(%i7) find_root (exp(x) = y, x, 0, 100), y = 10;
(%o7) 2.302585092994046
(%i8) log (10.0);
(%o8) 2.302585092994046
(%i9) fpprec:32;
(%o9) 32
(%i10) bf_find_root (exp(x) = y, x, 0, 100), y = 10;
(%o10) 2.3025850929940456840179914546844b0
(%i11) log(10b0);
(%o11) 2.3025850929940456840179914546844b0
```

newton (expr, x, x.0, eps)

Function

Returns an approximate solution of $expr = 0$ by Newton's method, considering $expr$ to be a function of one variable, x . The search begins with $x = x.0$ and proceeds until $abs(expr) < eps$ (with $expr$ evaluated at the current value of x).

`newton` allows undefined variables to appear in $expr$, so long as the termination test $abs(expr) < eps$ evaluates to `true` or `false`. Thus it is not necessary that $expr$ evaluate to a number.

`load(newton1)` loads this function.

See also `realroots`, `allroots`, `find_root`, and `mnewton`.

Examples:

```
(%i1) load (newton1);
(%o1) /usr/share/maxima/5.10.0cvs/share/numeric/newton1.mac
(%i2) newton (cos (u), u, 1, 1/100);
(%o2) 1.570675277161251
(%i3) ev (cos (u), u = %);
(%o3) 1.2104963335033528E-4
(%i4) assume (a > 0);
(%o4) [a > 0]
(%i5) newton (x^2 - a^2, x, a/2, a^2/100);
(%o5) 1.00030487804878 a
(%i6) ev (x^2 - a^2, x = %);
(%o6) 6.098490481853958E-4 a
```

22.3 Introduction to Fourier series

The `fourie` package comprises functions for the symbolic computation of Fourier series. There are functions in the `fourie` package to calculate Fourier integral coefficients and some functions for manipulation of expressions.

22.4 Functions and Variables for Fourier series

- equalp** (*x*, *y*) Function
 Returns `true` if `equal (x, y)` otherwise `false` (doesn't give an error message like `equal (x, y)` would do in this case).
- remfun** (*f*, *expr*) Function
remfun (*f*, *expr*, *x*) Function
`remfun (f, expr)` replaces all occurrences of *f* (*arg*) by *arg* in *expr*.
`remfun (f, expr, x)` replaces all occurrences of *f* (*arg*) by *arg* in *expr* only if *arg* contains the variable *x*.
- funp** (*f*, *expr*) Function
funp (*f*, *expr*, *x*) Function
`funp (f, expr)` returns `true` if *expr* contains the function *f*.
`funp (f, expr, x)` returns `true` if *expr* contains the function *f* and the variable *x* is somewhere in the argument of one of the instances of *f*.
- absint** (*f*, *x*, *halfplane*) Function
absint (*f*, *x*) Function
absint (*f*, *x*, *a*, *b*) Function
`absint (f, x, halfplane)` returns the indefinite integral of *f* with respect to *x* in the given halfplane (`pos`, `neg`, or `both`). *f* may contain expressions of the form `abs (x)`, `abs (sin (x))`, `abs (a) * exp (-abs (b) * abs (x))`.
`absint (f, x)` is equivalent to `absint (f, x, pos)`.
`absint (f, x, a, b)` returns the definite integral of *f* with respect to *x* from *a* to *b*. *f* may include absolute values.
- fourier** (*f*, *x*, *p*) Function
 Returns a list of the Fourier coefficients of *f*(*x*) defined on the interval `[-p, p]`.
- foursimp** (*l*) Function
 Simplifies `sin (n %pi)` to 0 if `sinnpiflag` is `true` and `cos (n %pi)` to `(-1)^n` if `cosnpiflag` is `true`.
- sinnpiflag** Option variable
 Default value: `true`
 See `foursimp`.
- cosnpiflag** Option variable
 Default value: `true`
 See `foursimp`.
- fourexpand** (*l*, *x*, *p*, *limit*) Function
 Constructs and returns the Fourier series from the list of Fourier coefficients *l* up through *limit* terms (*limit* may be `inf`). *x* and *p* have same meaning as in `fourier`.

fourcos (f, x, p)	Function
Returns the Fourier cosine coefficients for $f(x)$ defined on $[0, p]$.	
foursin (f, x, p)	Function
Returns the Fourier sine coefficients for $f(x)$ defined on $[0, p]$.	
totalfourier (f, x, p)	Function
Returns <code>fourexpend (foursimp (fourier (f, x, p)), x, p, 'inf)</code> .	
fourint (f, x)	Function
Constructs and returns a list of the Fourier integral coefficients of $f(x)$ defined on <code>[minf, inf]</code> .	
fourintcos (f, x)	Function
Returns the Fourier cosine integral coefficients for $f(x)$ on <code>[0, inf]</code> .	
fourintsin (f, x)	Function
Returns the Fourier sine integral coefficients for $f(x)$ on <code>[0, inf]</code> .	

23 Matrices and Linear Algebra

23.1 Introduction to Matrices and Linear Algebra

23.1.1 Dot

The operator `.` represents noncommutative multiplication and scalar product. When the operands are 1-column or 1-row matrices `a` and `b`, the expression `a.b` is equivalent to `sum(a[i]*b[i], i, 1, length(a))`. If `a` and `b` are not complex, this is the scalar product, also called the inner product or dot product, of `a` and `b`. The scalar product is defined as `conjugate(a).b` when `a` and `b` are complex; `innerproduct` in the `eigen` package provides the complex scalar product.

When the operands are more general matrices, the product is the matrix product `a` and `b`. The number of rows of `b` must equal the number of columns of `a`, and the result has number of rows equal to the number of rows of `a` and number of columns equal to the number of columns of `b`.

To distinguish `.` as an arithmetic operator from the decimal point in a floating point number, it may be necessary to leave spaces on either side. For example, `5.e3` is 5000.0 but `5 . e3` is 5 times `e3`.

There are several flags which govern the simplification of expressions involving `.`, namely `dot0nscsimp`, `dot0simp`, `dot1simp`, `dotassoc`, `dotconstrules`, `dotdistrib`, `dotexptsimp`, `dotident`, and `dotscrules`.

23.1.2 Vectors

`vect` is a package of functions for vector analysis. `load ("vect")` loads this package, and `demo ("vect")` displays a demonstration.

The vector analysis package can combine and simplify symbolic expressions including dot products and cross products, together with the gradient, divergence, curl, and Laplacian operators. The distribution of these operators over sums or products is governed by several flags, as are various other expansions, including expansion into components in any specific orthogonal coordinate systems. There are also functions for deriving the scalar or vector potential of a field.

The `vect` package contains these functions: `vectorsimp`, `scalefactors`, `express`, `potential`, and `vectorpotential`.

By default the `vect` package does not declare the dot operator to be a commutative operator. To get a commutative dot operator `.`, the command `declare(".", commutative)` must be executed.

23.1.3 eigen

The package `eigen` contains several functions devoted to the symbolic computation of eigenvalues and eigenvectors. Maxima loads the package automatically if one of the functions `eigenvalues` or `eigenvectors` is invoked. The package may be loaded explicitly as `load ("eigen")`.

`demo ("eigen")` displays a demonstration of the capabilities of this package. `batch ("eigen")` executes the same demonstration, but without the user prompt between successive computations.

The functions in the `eigen` package are:
`innerproduct`, `unitvector`, `columnvector`, `gramschmidt`, `eigenvalues`,
`eigenvectors`, `uniteigenvectors`, and `similaritytransform`.

23.2 Functions and Variables for Matrices and Linear Algebra

addcol ($M, list_1, \dots, list_n$) Function
 Appends the column(s) given by the one or more lists (or matrices) onto the matrix M .

addrow ($M, list_1, \dots, list_n$) Function
 Appends the row(s) given by the one or more lists (or matrices) onto the matrix M .

adjoint (M) Function
 Returns the adjoint of the matrix M . The adjoint matrix is the transpose of the matrix of cofactors of M .

augcoefmatrix ($[eqn_1, \dots, eqn_m], [x_1, \dots, x_n]$) Function
 Returns the augmented coefficient matrix for the variables x_1, \dots, x_n of the system of linear equations eqn_1, \dots, eqn_m . This is the coefficient matrix with a column adjoined for the constant terms in each equation (i.e., those terms not dependent upon x_1, \dots, x_n).

```
(%i1) m: [2*x - (a - 1)*y = 5*b, c + b*y + a*x = 0]$
(%i2) augcoefmatrix (m, [x, y]);
          [ 2   1 - a   - 5 b ]
(%o2)      [
          [ a      b      c   ]
```

cauchy_matrix ($[x_1, x_2, \dots, x_m], [y_1, y_2, \dots, y_n]$) Function
cauchy_matrix ($[x_1, x_2, \dots, x_n]$) Function

Returns a n by m Cauchy matrix with the elements $a[i,j] = 1/(x_i + y_j)$. The second argument of **cauchy_matrix** is optional. For this case the elements of the Cauchy matrix are $a[i,j] = 1/(x_i + x_j)$.

Remark: In the literature the Cauchy matrix can be found defined in two forms. A second definition is $a[i,j] = 1/(x_i - y_j)$.

Examples:

```
(%i1) cauchy_matrix([x1,x2],[y1,y2]);
          [    1          1      ]
          [ -----  ----- ]
          [ y1 + x1  y2 + x1 ]
(%o1)      [
          [    1          1      ]
          [ -----  ----- ]
          [ y1 + x2  y2 + x2 ]

(%i2) cauchy_matrix([x1,x2]);
          [    1          1      ]
          [ ----  ----- ]
          [ 2 x1    x2 + x1 ]
(%o2)      [
          [    1          1      ]
          [ -----  ---- ]
          [ x2 + x1    2 x2 ]
```

charpoly (M, x) Function
 Returns the characteristic polynomial for the matrix M with respect to variable x . That is, **determinant** ($M - \text{diagmatrix}(\text{length}(M), x)$).


```
(%i1) a: matrix ([3, 1], [2, 4]);
                                [ 3  1 ]
(%o1)                                [    ]
                                [ 2  4 ]
(%i2) expand (charpoly (a, lambda));
                                2
(%o2)                lambda  - 7 lambda + 10
(%i3) (programmode: true, solve (%));
(%o3)                [lambda = 5, lambda = 2]
(%i4) matrix ([x1], [x2]);
                                [ x1 ]
(%o4)                                [    ]
                                [ x2 ]
(%i5) ev (a . % - lambda*%, %th(2)[1]);
                                [ x2 - 2 x1 ]
(%o5)                                [    ]
                                [ 2 x1 - x2 ]
(%i6) %[1, 1] = 0;
(%o6)                x2 - 2 x1 = 0
(%i7) x2^2 + x1^2 = 1;
                                2      2
(%o7)                x2  + x1  = 1
(%i8) solve ([%th(2), %], [x1, x2]);
                                1      2
(%o8) [[x1 = - ----, x2 = - ----],
                                sqrt(5)    sqrt(5)]
```

$$[x1 = -\frac{1}{\sqrt{5}}, x2 = -\frac{2}{\sqrt{5}}]$$

coefmatrix (*eqn_1*, ..., *eqn_m*], [*x_1*, ..., *x_n*]) Function
 Returns the coefficient matrix for the variables *x_1*, ..., *x_n* of the system of linear equations *eqn_1*, ..., *eqn_m*.

```
(%i1) coefmatrix([2*x-(a-1)*y+5*b = 0, b*y+a*x = 3], [x,y]);
                                [ 2  1 - a ]
(%o1)                                [    ]
                                [ a    b  ]
```

col (*M*, *i*) Function
 Returns the *i*'th column of the matrix *M*. The return value is a matrix.

columnvector (*L*) Function

covect (*L*) Function

Returns a matrix of one column and **length** (*L*) rows, containing the elements of the list *L*.

covect is a synonym for **columnvector**.

load ("eigen") loads this function.

This is useful if you want to use parts of the outputs of the functions in this package in matrix calculations.

Example:

```
(%i1) load ("eigen")$
Warning - you are redefining the Macsyma function eigenvalues
Warning - you are redefining the Macsyma function eigenvectors
```

```
(%i2) columnvector ([aa, bb, cc, dd]);
      [ aa ]
      [   ]
      [ bb ]
(%o2)  [   ]
      [ cc ]
      [   ]
      [ dd ]
```

copymatrix (*M*)

Function

Returns a copy of the matrix *M*. This is the only way to make a copy aside from copying *M* element by element.

Note that an assignment of one matrix to another, as in `m2: m1`, does not copy *m1*. An assignment `m2 [i,j]: x` or `setelmx(x, i, j, m2)` also modifies *m1* [i,j]. Creating a copy with **copymatrix** and then using assignment creates a separate, modified copy.

determinant (*M*)

Function

Computes the determinant of *M* by a method similar to Gaussian elimination.

The form of the result depends upon the setting of the switch **ratmx**.

There is a special routine for computing sparse determinants which is called when the switches **ratmx** and **sparse** are both **true**.

detout

Option variable

Default value: **false**

When **detout** is **true**, the determinant of a matrix whose inverse is computed is factored out of the inverse.

For this switch to have an effect **doallmxops** and **doscmxops** should be **false** (see their descriptions). Alternatively this switch can be given to **ev** which causes the other two to be set correctly.

Example:

```
(%i1) m: matrix ([a, b], [c, d]);
      [ a  b ]
(%o1)  [      ]
      [ c  d ]

(%i2) detout: true$
(%i3) doallmxops: false$
(%i4) doscmxops: false$
(%i5) invert (m);
      [  d  - b ]
      [          ]
      [ - c   a ]
(%o5) -----
      a d - b c
```

diagmatrix (*n*, *x*)

Function

Returns a diagonal matrix of size *n* by *n* with the diagonal elements all equal to *x*. **diagmatrix** (*n*, 1) returns an identity matrix (same as **ident** (*n*)).

n must evaluate to an integer, otherwise **diagmatrix** complains with an error message.

x can be any kind of expression, including another matrix. If *x* is a matrix, it is not copied; all diagonal elements refer to the same instance, *x*.

doallmxops

Option variable

Default value: `true`

When `doallmxops` is `true`, all operations relating to matrices are carried out. When it is `false` then the setting of the individual `dot` switches govern which operations are performed.

domxexpt

Option variable

Default value: `true`

When `domxexpt` is `true`, a matrix exponential, `exp (M)` where M is a matrix, is interpreted as a matrix with element $[i,j]$ equal to `exp (m[i,j])`. Otherwise `exp (M)` evaluates to `exp (ev(M))`.

`domxexpt` affects all expressions of the form $base^{power}$ where *base* is an expression assumed scalar or constant, and *power* is a list or matrix.

Example:

```
(%i1) m: matrix ([1, %i], [a+b, %pi]);
              [ 1      %i ]
(%o1)          [          ]
              [ b + a  %pi ]

(%i2) domxexpt: false$
(%i3) (1 - c)^m;
              [ 1      %i ]
              [          ]
              [ b + a  %pi ]

(%o3)          (1 - c)
(%i4) domxexpt: true$
(%i5) (1 - c)^m;
              [          %i ]
              [ 1 - c      (1 - c) ]
(%o5)          [          ]
              [          %pi ]
              [ (1 - c)      (1 - c) ]
```

domxmxops

Option variable

Default value: `true`

When `domxmxops` is `true`, all matrix-matrix or matrix-list operations are carried out (but not scalar-matrix operations); if this switch is `false` such operations are not carried out.

domxnctimes

Option variable

Default value: `false`

When `domxnctimes` is `true`, non-commutative products of matrices are carried out.

dontfactor

Option variable

Default value: `[]`

`dontfactor` may be set to a list of variables with respect to which factoring is not to occur. (The list is initially empty.) Factoring also will not take place with respect to any variables which are less important, according the variable ordering assumed for canonical rational expression (CRE) form, than those on the `dontfactor` list.

doscmxops

Option variable

Default value: `false`

When `doscmxops` is `true`, scalar-matrix operations are carried out.

- doscmxplus** Option variable
 Default value: `false`
 When `doscmxplus` is `true`, scalar-matrix operations yield a matrix result. This switch is not subsumed under `doallmxops`.
- dot0nscsimp** Option variable
 Default value: `true`
 When `dot0nscsimp` is `true`, a non-commutative product of zero and a nonscalar term is simplified to a commutative product.
- dot0simp** Option variable
 Default value: `true`
 When `dot0simp` is `true`, a non-commutative product of zero and a scalar term is simplified to a commutative product.
- dot1simp** Option variable
 Default value: `true`
 When `dot1simp` is `true`, a non-commutative product of one and another term is simplified to a commutative product.
- dotassoc** Option variable
 Default value: `true`
 When `dotassoc` is `true`, an expression $(A.B).C$ simplifies to $A.(B.C)$.
- dotconstrules** Option variable
 Default value: `true`
 When `dotconstrules` is `true`, a non-commutative product of a constant and another term is simplified to a commutative product. Turning on this flag effectively turns on `dot0simp`, `dot0nscsimp`, and `dot1simp` as well.
- dotdistrib** Option variable
 Default value: `false`
 When `dotdistrib` is `true`, an expression $A.(B + C)$ simplifies to $A.B + A.C$.
- dotexptsimp** Option variable
 Default value: `true`
 When `dotexptsimp` is `true`, an expression $A.A$ simplifies to $A^{^2}$.
- dotident** Option variable
 Default value: 1
`dotident` is the value returned by $X^{^0}$.
- dotscrules** Option variable
 Default value: `false`
 When `dotscrules` is `true`, an expression $A.SC$ or $SC.A$ simplifies to $SC*A$ and $A.(SC*B)$ simplifies to $SC*(A.B)$.

echelon (*M*)

Function

Returns the echelon form of the matrix *M*, as produced by Gaussian elimination. The echelon form is computed from *M* by elementary row operations such that the first non-zero element in each row in the resulting matrix is one and the column elements under the first one in each row are all zero.

triangularize also carries out Gaussian elimination, but it does not normalize the leading non-zero element in each row.

lu_factor and **cholesky** are other functions which yield triangularized matrices.

```
(%i1) M: matrix ([3, 7, aa, bb], [-1, 8, 5, 2], [9, 2, 11, 4]);
          [ 3  7  aa  bb ]
          [          ]
(%o1)      [ - 1  8  5  2 ]
          [          ]
          [ 9  2  11  4 ]

(%i2) echelon (M);
          [ 1  - 8  - 5      - 2      ]
          [          ]
          [          28      11      ]
          [ 0   1  --      --      ]
(%o2)      [          37      37      ]
          [          ]
          [          37 bb - 119 ]
          [ 0   0   1  ----- ]
          [          37 aa - 313 ]
```

eigenvalues (*M*)

Function

eivals (*M*)

Function

Returns a list of two lists containing the eigenvalues of the matrix *M*. The first sublist of the return value is the list of eigenvalues of the matrix, and the second sublist is the list of the multiplicities of the eigenvalues in the corresponding order.

eivals is a synonym for **eigenvalues**.

eigenvalues calls the function **solve** to find the roots of the characteristic polynomial of the matrix. Sometimes **solve** may not be able to find the roots of the polynomial; in that case some other functions in this package (except **innerproduct**, **unitvector**, **columnvector** and **gramschmidt**) will not work.

In some cases the eigenvalues found by **solve** may be complicated expressions. (This may happen when **solve** returns a not-so-obviously real expression for an eigenvalue which is known to be real.) It may be possible to simplify the eigenvalues using some other functions.

The package **eigen.mac** is loaded automatically when **eigenvalues** or **eigenvectors** is referenced. If **eigen.mac** is not already loaded, **load ("eigen")** loads it. After loading, all functions and variables in the package are available.

eigenvectors (*M*)

Function

eivects (*M*)

Function

Computes eigenvectors of the matrix *M*. The return value is a list of two elements. The first is a list of the eigenvalues of *M* and a list of the multiplicities of the eigenvalues. The second is a list of lists of eigenvectors. There is one list of eigenvectors for each eigenvalue. There may be one or more eigenvectors in each list.

eivects is a synonym for **eigenvectors**.

The package **eigen.mac** is loaded automatically when **eigenvalues** or **eigenvectors** is referenced. If **eigen.mac** is not already loaded, **load ("eigen")** loads it. After loading, all functions and variables in the package are available.

The flags that affect this function are:

`nondiagonalizable` is set to `true` or `false` depending on whether the matrix is nondiagonalizable or diagonalizable after `eigenvectors` returns.

`hermitianmatrix` when `true`, causes the degenerate eigenvectors of the Hermitian matrix to be orthogonalized using the Gram-Schmidt algorithm.

`knoweigvals` when `true` causes the `eigen` package to assume the eigenvalues of the matrix are known to the user and stored under the global name `listeigvals`. `listeigvals` should be set to a list similar to the output `eigenvalues`.

The function `algsys` is used here to solve for the eigenvectors. Sometimes if the eigenvalues are messy, `algsys` may not be able to find a solution. In some cases, it may be possible to simplify the eigenvalues by first finding them using `eigenvalues` command and then using other functions to reduce them to something simpler. Following simplification, `eigenvectors` can be called again with the `knoweigvals` flag set to `true`.

See also `eigenvalues`.

Examples:

A matrix which has just one eigenvector per eigenvalue.

```
(%i1) M1 : matrix ([11, -1], [1, 7]);
              [ 11  - 1 ]
(%o1)          [          ]
              [ 1    7  ]

(%i2) [vals, vecs] : eigenvectors (M1);
(%o2) [[[9 - sqrt(3), sqrt(3) + 9], [1, 1]],
        [[1, sqrt(3) + 2]], [[1, 2 - sqrt(3)]]]

(%i3) for i thru length (vals[1]) do disp (val[i] = vals[1][i],
      mult[i] = vals[2][i], vec[i] = vecs[i]);
      val  = 9 - sqrt(3)
      1

      mult  = 1
      1

      vec  = [[1, sqrt(3) + 2]]
      1

      val  = sqrt(3) + 9
      2

      mult  = 1
      2

      vec  = [[1, 2 - sqrt(3)]]
      2

(%o3) done
```

A matrix which has two eigenvectors for one eigenvalue (namely 2).

```
(%i1) M1 : matrix ([0, 1, 0, 0], [0, 0, 0, 0], [0, 0, 2, 0],
      [0, 0, 0, 2]);
              [ 0  1  0  0 ]
              [          ]
              [ 0  0  0  0 ]
(%o1)          [          ]
              [ 0  0  2  0 ]
              [          ]
              [ 0  0  0  2 ]

(%i2) [vals, vecs] : eigenvectors (M1);
(%o2) [[[0, 2], [2, 2]], [[1, 0, 0, 0]],
```

```

                                [[0, 0, 1, 0], [0, 0, 0, 1]]]
(%i3) for i thru length (vals[1]) do disp (val[i] = vals[1][i],
      mult[i] = vals[2][i], vec[i] = vecs[i]);
      val  = 0
      1

      mult  = 2
      1

      vec  = [[1, 0, 0, 0]]
      1

      val  = 2
      2

      mult  = 2
      2

      vec  = [[0, 0, 1, 0], [0, 0, 0, 1]]
      2

(%o3)                                     done

```

ematrix (m, n, x, i, j) Function
 Returns an m by n matrix, all elements of which are zero except for the $[i, j]$ element which is x .

entermatrix (m, n) Function
 Returns an m by n matrix, reading the elements interactively.
 If n is equal to m , Maxima prompts for the type of the matrix (diagonal, symmetric, anti-symmetric, or general) and for each element. Each response is terminated by a semicolon ; or dollar sign \$.
 If n is not equal to m , Maxima prompts for each element.
 The elements may be any expressions, which are evaluated. **entermatrix** evaluates its arguments.

```

(%i1) n: 3$
(%i2) m: entermatrix (n, n)$

Is the matrix  1. Diagonal  2. Symmetric  3. Antisymmetric
4. General
Answer 1, 2, 3 or 4 :
1$
Row 1 Column 1:
(a+b)^n$
Row 2 Column 2:
(a+b)^(n+1)$
Row 3 Column 3:
(a+b)^(n+2)$

Matrix entered.
(%i3) m;
      [
      [ (b + a)3      0      0      ]
      [
(%o3)      [
              4
      ]

```

$$\begin{bmatrix} 0 & (b + a) & 0 \\ & & \\ & & 5 \\ 0 & 0 & (b + a) \end{bmatrix}$$
genmatrix (*a*, *i_2*, *j_2*, *i_1*, *j_1*)

Function

genmatrix (*a*, *i_2*, *j_2*, *i_1*)

Function

genmatrix (*a*, *i_2*, *j_2*)

Function

Returns a matrix generated from *a*, taking element *a*[*i_1*, *j_1*] as the upper-left element and *a*[*i_2*, *j_2*] as the lower-right element of the matrix. Here *a* is a declared array (created by **array** but not by **make_array**) or an undeclared array, or an array function, or a lambda expression of two arguments. (An array function is created like other functions with **:=** or **define**, but arguments are enclosed in square brackets instead of parentheses.)

If *j_1* is omitted, it is assumed equal to *i_1*. If both *j_1* and *i_1* are omitted, both are assumed equal to 1.

If a selected element *i*,*j* of the array is undefined, the matrix will contain a symbolic element *a*[*i*,*j*].

Examples:

```
(%i1) h [i, j] := 1 / (i + j - 1);
                                1
(%o1)      h      := -----
           i, j    i + j - 1
(%i2) genmatrix (h, 3, 3);
      [ 1 1 ]
      [ 1 - - ]
      [ 2 3 ]
      [      ]
      [ 1 1 1 ]
      [ - - - ]
      [ 2 3 4 ]
      [      ]
      [ 1 1 1 ]
      [ - - - ]
      [ 3 4 5 ]
(%i3) array (a, fixnum, 2, 2);
(%o3)      a
(%i4) a [1, 1] : %e;
(%o4)      %e
(%i5) a [2, 2] : %pi;
(%o5)      %pi
(%i6) genmatrix (a, 2, 2);
      [ %e 0 ]
(%o6)      [      ]
      [ 0 %pi ]
(%i7) genmatrix (lambda ([i, j], j - i), 3, 3);
      [ 0 1 2 ]
      [      ]
      [ - 1 0 1 ]
      [      ]
      [ - 2 - 1 0 ]
(%i8) genmatrix (B, 2, 2);
      [ B      B ]
      [ 1, 1 1, 2 ]
(%o8)      [      ]
      [ B      B ]
      [ 2, 1 2, 2 ]
```


gramschmidt (*x*)

Function

gramschmidt (*x*, *F*)

Function

Carries out the Gram-Schmidt orthogonalization algorithm on *x*, which is either a matrix or a list of lists. *x* is not modified by **gramschmidt**. The inner product employed by **gramschmidt** is *F*, if present, otherwise the inner product is the function **innerproduct**.

If *x* is a matrix, the algorithm is applied to the rows of *x*. If *x* is a list of lists, the algorithm is applied to the sublists, which must have equal numbers of elements. In either case, the return value is a list of lists, the sublists of which are orthogonal and span the same space as *x*. If the dimension of the span of *x* is less than the number of rows or sublists, some sublists of the return value are zero.

factor is called at each stage of the algorithm to simplify intermediate results. As a consequence, the return value may contain factored integers.

load(eigen) loads this function.

Example:

Gram-Schmidt algorithm using default inner product function.

```
(%i1) load (eigen)$
(%i2) x: matrix ([1, 2, 3], [9, 18, 30], [12, 48, 60]);
          [ 1  2  3 ]
          [          ]
(%o2)      [ 9  18 30 ]
          [          ]
          [ 12 48 60 ]
(%i3) y: gramshmidt (x);
          2      2      4      3
          3      3  3 5      2 3 2 3
(%o3)  [[1, 2, 3], [- ---, - --, ---], [- ----, ----, 0]]
          2 7      7      2 7      5      5
(%i4) map (innerproduct, [y[1], y[2], y[3]], [y[2], y[3], y[1]]);
(%o4)      [0, 0, 0]
```

Gram-Schmidt algorithm using a specified inner product function.

```
(%i1) load (eigen)$
(%i2) ip (f, g) := integrate (f * g, u, a, b);
(%o2)      ip(f, g) := integrate(f g, u, a, b)
(%i3) y : gramshmidt([1, sin(u), cos(u)], ip), a= -%pi/2, b=%pi/2;
          %pi cos(u) - 2
(%o3)      [1, sin(u), -----]
          %pi
(%i4) map (ip, [y[1], y[2], y[3]], [y[2], y[3], y[1]]),
          a= -%pi/2, b=%pi/2;
(%o4)      [0, 0, 0]
```

ident (*n*)

Function

Returns an *n* by *n* identity matrix.

innerproduct (*x*, *y*)

Function

inprod (*x*, *y*)

Function

Returns the inner product (also called the scalar product or dot product) of *x* and *y*, which are lists of equal length, or both 1-column or 1-row matrices of equal length. The return value is **conjugate**(*x*) . *y*, where . is the noncommutative multiplication operator.

load ("eigen") loads this function.

inprod is a synonym for **innerproduct**.

invert (*M*)

Function

Returns the inverse of the matrix *M*. The inverse is computed by the adjoint method.

This allows a user to compute the inverse of a matrix with bfloat entries or polynomials with floating point coefficients without converting to cre-form.

Cofactors are computed by the **determinant** function, so if **ratmx** is **false** the inverse is computed without changing the representation of the elements.

The current implementation is inefficient for matrices of high order.

When **detout** is **true**, the determinant is factored out of the inverse.

The elements of the inverse are not automatically expanded. If *M* has polynomial elements, better appearing output can be generated by **expand**(**invert**(*m*)), **detout**. If it is desirable to then divide through by the determinant this can be accomplished by **xthru**(%) or alternatively from scratch by

```
expand (adjoint (m)) / expand (determinant (m))
invert (m) := adjoint (m) / determinant (m)
```

See ^^ (noncommutative exponent) for another method of inverting a matrix.

list_matrix_entries (*M*)

Function

Returns a list containing the elements of the matrix *M*.

Example:

```
(%i1) list_matrix_entries(matrix([a,b],[c,d]));
(%o1) [a, b, c, d]
```

lmxchar

Option variable

Default value: [

lmxchar is the character displayed as the left delimiter of a matrix. See also **rmxchar**.

Example:

```
(%i1) lmxchar: "|" $
(%i2) matrix ([a, b, c], [d, e, f], [g, h, i]);
              | a  b  c |
              |      |
(%o2)         | d  e  f |
              |      |
              | g  h  i |
```

matrix (*row_1*, ..., *row_n*)

Function

Returns a rectangular matrix which has the rows *row_1*, ..., *row_n*. Each row is a list of expressions. All rows must be the same length.

The operations + (addition), - (subtraction), * (multiplication), and / (division), are carried out element by element when the operands are two matrices, a scalar and a matrix, or a matrix and a scalar. The operation ^ (exponentiation, equivalently **) is carried out element by element if the operands are a scalar and a matrix or a matrix and a scalar, but not if the operands are two matrices. All operations are normally carried out in full, including . (noncommutative multiplication).

Matrix multiplication is represented by the noncommutative multiplication operator .. The corresponding noncommutative exponentiation operator is ^^.. For a matrix *A*, *A*..*A* = *A*^^2 and *A*^^-1 is the inverse of *A*, if it exists.

There are switches for controlling simplification of expressions involving dot and matrix-list operations. These are **doallmxops**, **domxexpt**, **dommxops**, **doscmxops**, and **doscmxplus**.

There are additional options which are related to matrices. These are: **lmxchar**, **rmxchar**, **ratmx**, **listarith**, **detout**, **scalarmatrix** and **sparse**.

There are a number of functions which take matrices as arguments or yield matrices as return values. See `eigenvalues`, `eigenvectors`, `determinant`, `charpoly`, `genmatrix`, `addcol`, `addrow`, `copymatrix`, `transpose`, `echelon`, and `rank`.

Examples:

- Construction of matrices from lists.

```
(%i1) x: matrix ([17, 3], [-8, 11]);
              [ 17   3 ]
(%o1)         [         ]
              [ - 8  11 ]
(%i2) y: matrix ([%pi, %e], [a, b]);
              [ %pi  %e ]
(%o2)         [         ]
              [  a   b  ]
```

- Addition, element by element.

```
(%i3) x + y;
              [ %pi + 17  %e + 3 ]
(%o3)         [         ]
              [  a - 8    b + 11 ]
```

- Subtraction, element by element.

```
(%i4) x - y;
              [ 17 - %pi  3 - %e ]
(%o4)         [         ]
              [ - a - 8    11 - b ]
```

- Multiplication, element by element.

```
(%i5) x * y;
              [ 17 %pi  3 %e ]
(%o5)         [         ]
              [ - 8 a   11 b ]
```

- Division, element by element.

```
(%i6) x / y;
              [ 17      - 1 ]
              [ ---  3 %e   ]
              [ %pi      ]
(%o6)         [         ]
              [  8      11   ]
              [ - -      --   ]
              [  a      b    ]
```

- Matrix to a scalar exponent, element by element.

```
(%i7) x ^ 3;
              [ 4913    27 ]
(%o7)         [         ]
              [ - 512  1331 ]
```

- Scalar base to a matrix exponent, element by element.

```
(%i8) exp(y);
              [ %pi  %e ]
              [ %e   %e ]
(%o8)         [         ]
              [  a    b  ]
              [ %e   %e ]
```

- Matrix base to a matrix exponent. This is not carried out element by element.

```
(%i9) x ^ y;
              [ %pi  %e ]
              [         ]
```

```

                                [ a  b ]
                                [ 17  3 ]
(%o9)                          [      ]
                                [ - 8  11 ]
• Noncommutative matrix multiplication.
(%i10) x . y;
                                [ 3 a + 17 %pi  3 b + 17 %e ]
(%o10)                          [      ]
                                [ 11 a - 8 %pi  11 b - 8 %e ]
(%i11) y . x;
                                [ 17 %pi - 8 %e  3 %pi + 11 %e ]
(%o11)                          [      ]
                                [ 17 a - 8 b      11 b + 3 a ]
• Noncommutative matrix exponentiation. A scalar base b to a matrix power M is
  carried out element by element and so b^^m is the same as b^m.
(%i12) x ^^ 3;
                                [ 3833  1719 ]
(%o12)                          [      ]
                                [ - 4584  395 ]
(%i13) %e ^^ y;
                                [ %pi  %e ]
                                [ %e  %e ]
(%o13)                          [      ]
                                [ a  b ]
                                [ %e  %e ]
• A matrix raised to a -1 exponent with noncommutative exponentiation is the matrix
  inverse, if it exists.
(%i14) x ^^ -1;
                                [ 11  3 ]
                                [ --- - --- ]
                                [ 211  211 ]
(%o14)                          [      ]
                                [ 8  17 ]
                                [ --- --- ]
                                [ 211  211 ]
(%i15) x . (x ^^ -1);
                                [ 1  0 ]
(%o15)                          [      ]
                                [ 0  1 ]

```

matrixmap (*f*, *M*)

Function

Returns a matrix with element *i*,*j* equal to *f*(*M*[*i*,*j*]).See also `map`, `fullmap`, `fullmap1`, and `apply`.**matrixp** (*expr*)

Function

Returns `true` if *expr* is a matrix, otherwise `false`.**matrix_element_add**

Option variable

Default value: `+`

`matrix_element_add` is the operation invoked in place of addition in a matrix multiplication. `matrix_element_add` can be assigned any n-ary operator (that is, a function which handles any number of arguments). The assigned value may be the name of an operator enclosed in quote marks, the name of a function, or a lambda expression.

See also `matrix_element_mult` and `matrix_element_transpose`.

Example:

```
(%i1) matrix_element_add: "*" $
(%i2) matrix_element_mult: "^" $
(%i3) aa: matrix ([a, b, c], [d, e, f]);
          [ a  b  c ]
(%o3)      [
          [ d  e  f ]
(%i4) bb: matrix ([u, v, w], [x, y, z]);
          [ u  v  w ]
(%o4)      [
          [ x  y  z ]
(%i5) aa . transpose (bb);
          [ u  v  w  x  y  z ]
          [ a  b  c  a  b  c ]
(%o5)      [
          [ u  v  w  x  y  z ]
          [ d  e  f  d  e  f ]
```

matrix_element_mult

Option variable

Default value: *

`matrix_element_mult` is the operation invoked in place of multiplication in a matrix multiplication. `matrix_element_mult` can be assigned any binary operator. The assigned value may be the name of an operator enclosed in quote marks, the name of a function, or a lambda expression.

The dot operator `.` is a useful choice in some contexts.

See also `matrix_element_add` and `matrix_element_transpose`.

Example:

```
(%i1) matrix_element_add: lambda ([x], sqrt (apply ("+", x))) $
(%i2) matrix_element_mult: lambda ([x, y], (x - y)^2) $
(%i3) [a, b, c] . [x, y, z];
          2          2          2
(%o3)      sqrt((c - z) + (b - y) + (a - x) )
(%i4) aa: matrix ([a, b, c], [d, e, f]);
          [ a  b  c ]
(%o4)      [
          [ d  e  f ]
(%i5) bb: matrix ([u, v, w], [x, y, z]);
          [ u  v  w ]
(%o5)      [
          [ x  y  z ]
(%i6) aa . transpose (bb);
          [          2          2          2 ]
          [ sqrt((c - w) + (b - v) + (a - u) ) ]
(%o6) Col 1 = [
          [          2          2          2 ]
          [ sqrt((f - w) + (e - v) + (d - u) ) ]

          [          2          2          2 ]
          [ sqrt((c - z) + (b - y) + (a - x) ) ]
Col 2 = [
          [          2          2          2 ]
          [ sqrt((f - z) + (e - y) + (d - x) ) ]
```

matrix_element_transpose

Option variable

Default value: false

`matrix_element_transpose` is the operation applied to each element of a matrix when it is transposed. `matrix_element_mult` can be assigned any unary operator. The assigned value may be the name of an operator enclosed in quote marks, the name of a function, or a lambda expression.

When `matrix_element_transpose` equals `transpose`, the `transpose` function is applied to every element. When `matrix_element_transpose` equals `nonscalars`, the `transpose` function is applied to every nonscalar element. If some element is an atom, the `nonscalars` option applies `transpose` only if the atom is declared nonscalar, while the `transpose` option always applies `transpose`.

The default value, `false`, means no operation is applied.

See also `matrix_element_add` and `matrix_element_mult`.

Examples:

```
(%i1) declare (a, nonscalar)$
(%i2) transpose ([a, b]);
          [ transpose(a) ]
(%o2)      [              ]
          [      b      ]
(%i3) matrix_element_transpose: nonscalars$
(%i4) transpose ([a, b]);
          [ transpose(a) ]
(%o4)      [              ]
          [      b      ]
(%i5) matrix_element_transpose: transpose$
(%i6) transpose ([a, b]);
          [ transpose(a) ]
(%o6)      [              ]
          [ transpose(b) ]
(%i7) matrix_element_transpose: lambda ([x], realpart(x)
- %i*imagpart(x))$
(%i8) m: matrix ([1 + 5*i, 3 - 2*i], [7*i, 11]);
          [ 5 %i + 1  3 - 2 %i ]
(%o8)      [              ]
          [ 7 %i      11      ]
(%i9) transpose (m);
          [ 1 - 5 %i  - 7 %i ]
(%o9)      [              ]
          [ 2 %i + 3    11    ]
```

mattrace (*M*)

Function

Returns the trace (that is, the sum of the elements on the main diagonal) of the square matrix *M*.

`mattrace` is called by `ncharpoly`, an alternative to Maxima's `charpoly`.

`load ("nchrpl")` loads this function.

minor (*M*, *i*, *j*)

Function

Returns the *i*, *j* minor of the matrix *M*. That is, *M* with row *i* and column *j* removed.

ncharpoly (*M*, *x*)

Function

Returns the characteristic polynomial of the matrix *M* with respect to *x*. This is an alternative to Maxima's `charpoly`.

`ncharpoly` works by computing traces of powers of the given matrix, which are known to be equal to sums of powers of the roots of the characteristic polynomial. From these quantities the symmetric functions of the roots can be calculated, which are nothing more than the coefficients of the characteristic polynomial. `charpoly` works by forming the

determinant of $x * \text{ident } [n] - a$. Thus `ncharpoly` wins, for example, in the case of large dense matrices filled with integers, since it avoids polynomial arithmetic altogether. `load ("nchrpl")` loads this file.

newdet (*M*) Function
 Computes the determinant of the matrix *M* by the Johnson-Gentleman tree minor algorithm. `newdet` returns the result in CRE form.

permanent (*M*) Function
 Computes the permanent of the matrix *M* by the Johnson-Gentleman tree minor algorithm. A permanent is like a determinant but with no sign changes. `permanent` returns the result in CRE form.
 See also `newdet`.

rank (*M*) Function
 Computes the rank of the matrix *M*. That is, the order of the largest non-singular subdeterminant of *M*.
rank may return the wrong answer if it cannot determine that a matrix element that is equivalent to zero is indeed so.

ratmx Option variable
 Default value: `false`
 When `ratmx` is `false`, determinant and matrix addition, subtraction, and multiplication are performed in the representation of the matrix elements and cause the result of matrix inversion to be left in general representation.
 When `ratmx` is `true`, the 4 operations mentioned above are performed in CRE form and the result of matrix inverse is in CRE form. Note that this may cause the elements to be expanded (depending on the setting of `ratfac`) which might not always be desired.

row (*M*, *i*) Function
 Returns the *i*'th row of the matrix *M*. The return value is a matrix.

rmxchar Option variable
 Default value: `]`
`rmxchar` is the character drawn on the right-hand side of a matrix.
 See also `lmxchar`.

scalarmatrixp Option variable
 Default value: `true`
 When `scalarmatrixp` is `true`, then whenever a 1 x 1 matrix is produced as a result of computing the dot product of matrices it is simplified to a scalar, namely the sole element of the matrix.
 When `scalarmatrixp` is `all`, then all 1 x 1 matrices are simplified to scalars.
 When `scalarmatrixp` is `false`, 1 x 1 matrices are not simplified to scalars.

scalefactors (*coordinatetransform*) Function
 Here the argument *coordinatetransform* evaluates to the form `[[expression1, expression2, ...], indeterminate1, indeterminate2, ...]`, where the variables *indeterminate1*, *indeterminate2*, etc. are the curvilinear coordinate variables and where a set of rectangular Cartesian components is given in terms of the curvilinear coordinates by `[expression1, expression2, ...]`. `coordinates` is set to the vector

[*indeterminate1*, *indeterminate2*, ...], and *dimension* is set to the length of this vector. *SF*[1], *SF*[2], ..., *SF*[*DIMENSION*] are set to the coordinate scale factors, and *sfprod* is set to the product of these scale factors. Initially, *coordinates* is [*X*, *Y*, *Z*], *dimension* is 3, and *SF*[1]=*SF*[2]=*SF*[3]=*SFPROD*=1, corresponding to 3-dimensional rectangular Cartesian coordinates. To expand an expression into physical components in the current coordinate system, there is a function with usage of the form

setelmx (*x*, *i*, *j*, *M*) Function

Assigns *x* to the (*i*, *j*)'th element of the matrix *M*, and returns the altered matrix.

M [*i*, *j*]: *x* has the same effect, but returns *x* instead of *M*.

similaritytransform (*M*) Function

simtran (*M*) Function

similaritytransform computes a similarity transform of the matrix *M*. It returns a list which is the output of the **uniteigenvectors** command. In addition if the flag **nondiagonalizable** is **false** two global matrices **leftmatrix** and **rightmatrix** are computed. These matrices have the property that **leftmatrix** . *M* . **rightmatrix** is a diagonal matrix with the eigenvalues of *M* on the diagonal. If **nondiagonalizable** is **true** the left and right matrices are not computed.

If the flag **hermitianmatrix** is **true** then **leftmatrix** is the complex conjugate of the transpose of **rightmatrix**. Otherwise **leftmatrix** is the inverse of **rightmatrix**.

rightmatrix is the matrix the columns of which are the unit eigenvectors of *M*. The other flags (see **eigenvalues** and **eigenvectors**) have the same effects since **similaritytransform** calls the other functions in the package in order to be able to form **rightmatrix**.

load ("eigen") loads this function.

simtran is a synonym for **similaritytransform**.

sparse Option variable

Default value: **false**

When **sparse** is **true**, and if **ratmx** is **true**, then **determinant** will use special routines for computing sparse determinants.

submatrix (*i-1*, ..., *i-m*, *M*, *j-1*, ..., *j-n*) Function

submatrix (*i-1*, ..., *i-m*, *M*) Function

submatrix (*M*, *j-1*, ..., *j-n*) Function

Returns a new matrix composed of the matrix *M* with rows *i-1*, ..., *i-m* deleted, and columns *j-1*, ..., *j-n* deleted.

transpose (*M*) Function

Returns the transpose of *M*.

If *M* is a matrix, the return value is another matrix *N* such that *N*[*i*,*j*] = *M*[*j*,*i*].

If *M* is a list, the return value is a matrix *N* of **length** (*m*) rows and 1 column, such that *N*[*i*,1] = *M*[*i*].

Otherwise *M* is a symbol, and the return value is a noun expression '**transpose** (*M*)'.

triangularize (*M*) Function

Returns the upper triangular form of the matrix *M*, as produced by Gaussian elimination. The return value is the same as **echelon**, except that the leading nonzero coefficient in each row is not normalized to 1.

lu_factor and **cholesky** are other functions which yield triangularized matrices.


```
(%i1) M: matrix ([3, 7, aa, bb], [-1, 8, 5, 2], [9, 2, 11, 4]);
          [ 3  7  aa  bb ]
          [          ]
(%o1)      [ - 1  8  5  2 ]
          [          ]
          [ 9  2  11  4 ]
(%i2) triangularize (M);
          [ - 1  8          5          2          ]
          [          ]
(%o2)      [ 0  - 74      - 56          - 22      ]
          [          ]
          [ 0  0      626 - 74 aa  238 - 74 bb ]
```

uniteigenvectors (*M*)

Function

ueivects (*M*)

Function

Computes unit eigenvectors of the matrix *M*. The return value is a list of lists, the first sublist of which is the output of the **eigenvalues** command, and the other sublists of which are the unit eigenvectors of the matrix corresponding to those eigenvalues respectively.

The flags mentioned in the description of the **eigenvectors** command have the same effects in this one as well.

When **knowneigvects** is **true**, the **eigen** package assumes that the eigenvectors of the matrix are known to the user and are stored under the global name **listeigvects**. **listeigvects** should be set to a list similar to the output of the **eigenvectors** command.

If **knowneigvects** is set to **true** and the list of eigenvectors is given the setting of the flag **nondiagonalizable** may not be correct. If that is the case please set it to the correct value. The author assumes that the user knows what he is doing and will not try to diagonalize a matrix the eigenvectors of which do not span the vector space of the appropriate dimension.

load ("eigen") loads this function.

ueivects is a synonym for **uniteigenvectors**.

unitvector (*x*)

Function

uvect (*x*)

Function

Returns $x/\text{norm}(x)$; this is a unit vector in the same direction as *x*.

load ("eigen") loads this function.

uvect is a synonym for **unitvector**.

vectorpotential (*gencurl*)

Function

Returns the vector potential of a given curl vector, in the current coordinate system. **potentialzeroloc** has a similar role as for **potential**, but the order of the left-hand sides of the equations must be a cyclic permutation of the coordinate variables.

vectorsimp (*expr*)

Function

Applies simplifications and expansions according to the following global flags:

expandall, **expanddot**, **expanddotplus**, **expandcross**, **expandcrossplus**,
expandcrosscross, **expandgrad**, **expandgradplus**, **expandgradprod**,
expanddiv, **expanddivplus**, **expanddivprod**, **expandcurl**, **expandcurlplus**,
expandcurlcurl, **expandlaplacian**, **expandlaplacianplus**,
and **expandlaplacianprod**.

All these flags have default value **false**. The **plus** suffix refers to employing additivity or distributivity. The **prod** suffix refers to the expansion for an operand that is any kind of product.

expandcrosscross

Simplifies $p (q r)$ to $(p.r) * q - (p.q) * r$.

expandcurlcurl

Simplifies $curlcurlp$ to $graddivp + divgradp$.

expandlaplaciantodivgrad

Simplifies $laplacianp$ to $divgradp$.

expandcross

Enables **expandcrossplus** and **expandcrosscross**.

expandplus

Enables **expanddotplus**, **expandcrossplus**, **expandgradplus**, **expanddivplus**, **expandcurlplus**, and **expandlaplacianplus**.

expandprod

Enables **expandgradprod**, **expanddivprod**, and **expandlaplacianprod**.

These flags have all been declared **evflag**.

vect_cross

Option variable

Default value: **false**

When **vect_cross** is **true**, it allows $\text{DIFF}(X \sim Y, T)$ to work where \sim is defined in **SHARE;VECT** (where **VECT_CROSS** is set to **true**, anyway.)

zeromatrix (m, n)

Function

Returns an m by n matrix, all elements of which are zero.

24 Affine

24.1 Introduction to Affine

`affine` is a package to work with groups of polynomials.

24.2 Functions and Variables for Affine

fast_linsolve (*[expr_1, ..., expr_m], [x_1, ..., x_n]*) Function

Solves the simultaneous linear equations *expr_1, ..., expr_m* for the variables *x_1, ..., x_n*. Each *expr_i* may be an equation or a general expression; if given as a general expression, it is treated as an equation of the form *expr_i* = 0.

The return value is a list of equations of the form *[x_1 = a_1, ..., x_n = a_n]* where *a_1, ..., a_n* are all free of *x_1, ..., x_n*.

`fast_linsolve` is faster than `linsolve` for system of equations which are sparse.

`load(affine)` loads this function.

grobner_basis (*[expr_1, ..., expr_m]*) Function

Returns a Groebner basis for the equations *expr_1, ..., expr_m*. The function `polysimp` can then be used to simplify other functions relative to the equations.

```
grobner_basis ([3*x^2+1, y*x])$
```

```
polysimp (y^2*x + x^3*9 + 2) ==> -3*x + 2
```

`polysimp(f)` yields 0 if and only if *f* is in the ideal generated by *expr_1, ..., expr_m*, that is, if and only if *f* is a polynomial combination of the elements of *expr_1, ..., expr_m*.

`load(affine)` loads this function.

set_up_dot_simplifications (*eqns, check_through_degree*) Function

set_up_dot_simplifications (*eqns*) Function

The *eqns* are polynomial equations in non commutative variables. The value of `current_variables` is the list of variables used for computing degrees. The equations must be homogeneous, in order for the procedure to terminate.

If you have checked overlapping simplifications in `dot_simplifications` above the degree of *f*, then the following is true: `dotsimp(f)` yields 0 if and only if *f* is in the ideal generated by the equations, i.e., if and only if *f* is a polynomial combination of the elements of the equations.

The degree is that returned by `nc_degree`. This in turn is influenced by the weights of individual variables.

`load(affine)` loads this function.

declare_weights (*x_1, w_1, ..., x_n, w_n*) Function

Assigns weights *w_1, ..., w_n* to *x_1, ..., x_n*, respectively. These are the weights used in computing `nc_degree`.

`load(affine)` loads this function.

nc_degree (*p*) Function

Returns the degree of a noncommutative polynomial *p*. See `declare_weights`.

`load(affine)` loads this function.

dotsimp (*f*) Function

Returns 0 if and only if *f* is in the ideal generated by the equations, i.e., if and only if *f* is a polynomial combination of the elements of the equations.

`load(affine)` loads this function.

fast_central_elements ($[x_1, \dots, x_n], n$) Function

If `set_up_dot_simplifications` has been previously done, finds the central polynomials in the variables x_1, \dots, x_n in the given degree, n .

For example:

```
set_up_dot_simplifications ([y.x + x.y], 3);
fast_central_elements ([x, y], 2);
[y.y, x.x];
```

`load(affine)` loads this function.

check_overlaps (n, add_to_simps) Function

Checks the overlaps thru degree n , making sure that you have sufficient simplification rules in each degree, for `dotsimp` to work correctly. This process can be speeded up if you know before hand what the dimension of the space of monomials is. If it is of finite global dimension, then `hilbert` should be used. If you don't know the monomial dimensions, do not specify a `rank_function`. An optional third argument `reset`, `false` says don't bother to query about resetting things.

`load(affine)` loads this function.

mono ($[x_1, \dots, x_n], n$) Function

Returns the list of independent monomials relative to the current dot simplifications of degree n in the variables x_1, \dots, x_n .

`load(affine)` loads this function.

monomial_dimensions (n) Function

Compute the Hilbert series through degree n for the current algebra.

`load(affine)` loads this function.

extract_linear_equations ($[p_1, \dots, p_n], [m_1, \dots, m_n]$) Function

Makes a list of the coefficients of the noncommutative polynomials p_1, \dots, p_n of the noncommutative monomials m_1, \dots, m_n . The coefficients should be scalars. Use `list_nc_monomials` to build the list of monomials.

`load(affine)` loads this function.

list_nc_monomials ($[p_1, \dots, p_n]$) Function

list_nc_monomials (p) Function

Returns a list of the non commutative monomials occurring in a polynomial p or a list of polynomials p_1, \dots, p_n .

`load(affine)` loads this function.

all_dotsimp_denoms Option variable

Default value: `false`

When `all_dotsimp_denoms` is a list, the denominators encountered by `dotsimp` are appended to the list. `all_dotsimp_denoms` may be initialized to an empty list `[]` before calling `dotsimp`.

By default, denominators are not collected by `dotsimp`.

25 itensor

25.1 Introduction to itensor

Maxima implements symbolic tensor manipulation of two distinct types: component tensor manipulation (**ctensor** package) and indicial tensor manipulation (**itensor** package).

Nota bene: Please see the note on 'new tensor notation' below.

Component tensor manipulation means that geometrical tensor objects are represented as arrays or matrices. Tensor operations such as contraction or covariant differentiation are carried out by actually summing over repeated (dummy) indices with **do** statements. That is, one explicitly performs operations on the appropriate tensor components stored in an array or matrix.

Indicial tensor manipulation is implemented by representing tensors as functions of their covariant, contravariant and derivative indices. Tensor operations such as contraction or covariant differentiation are performed by manipulating the indices themselves rather than the components to which they correspond.

These two approaches to the treatment of differential, algebraic and analytic processes in the context of Riemannian geometry have various advantages and disadvantages which reveal themselves only through the particular nature and difficulty of the user's problem. However, one should keep in mind the following characteristics of the two implementations:

The representation of tensors and tensor operations explicitly in terms of their components makes **ctensor** easy to use. Specification of the metric and the computation of the induced tensors and invariants is straightforward. Although all of Maxima's powerful simplification capacity is at hand, a complex metric with intricate functional and coordinate dependencies can easily lead to expressions whose size is excessive and whose structure is hidden. In addition, many calculations involve intermediate expressions which swell causing programs to terminate before completion. Through experience, a user can avoid many of these difficulties.

Because of the special way in which tensors and tensor operations are represented in terms of symbolic operations on their indices, expressions which in the component representation would be unmanageable can sometimes be greatly simplified by using the special routines for symmetrical objects in **itensor**. In this way the structure of a large expression may be more transparent. On the other hand, because of the the special indicial representation in **itensor**, in some cases the user may find difficulty with the specification of the metric, function definition, and the evaluation of differentiated "indexed" objects.

The **itensor** package can carry out differentiation with respect to an indexed variable, which allows one to use the package when dealing with Lagrangian and Hamiltonian formalisms. As it is possible to differentiate a field Lagrangian with respect to an (indexed) field variable, one can use Maxima to derive the corresponding Euler-Lagrange equations in indicial form. These equations can be translated into component tensor (**ctensor**) programs using the **ic_convert** function, allowing us to solve the field equations in a particular coordinate representation, or to recast the equations of motion in Hamiltonian form. See **einhil.dem** and **bradic.dem** for two comprehensive examples. The first, **einhil.dem**, uses the Einstein-Hilbert action to derive the Einstein field tensor in the homogeneous and isotropic case (Friedmann equations) and the spherically symmetric, static case (Schwarzschild solution.) The second, **bradic.dem**, demonstrates how to compute the Friedmann equations from the action of Brans-Dicke gravity theory, and also derives the Hamiltonian associated with the theory's scalar field.

25.1.1 New tensor notation

Earlier versions of the **itensor** package in Maxima used a notation that sometimes led to incorrect index ordering. Consider the following, for instance:

```
(%i2) imetric(g);
(%o2)
(%i3) ishow(g([],[j,k])*g([],[i,l])*a([i,j],[l]))$
          i l j k
(%t3)
          g g a
```

```

                                i j
(%i4) ishow(contract(%))$
                                k l
                                a
(%t4)

```

This result is incorrect unless **a** happens to be a symmetric tensor. The reason why this happens is that although **itensor** correctly maintains the order within the set of covariant and contravariant indices, once an index is raised or lowered, its position relative to the other set of indices is lost.

To avoid this problem, a new notation has been developed that remains fully compatible with the existing notation and can be used interchangeably. In this notation, contravariant indices are inserted in the appropriate positions in the covariant index list, but with a minus sign prepended. Functions like **contract** and **ishow** are now aware of this new index notation and can process tensors appropriately.

In this new notation, the previous example yields a correct result:

```

                                i l      j k
(%i5) ishow(g([-j,-k],[])*g([-i,-l],[])*a([i,j],[]))$
                                g      a      g
                                i j
                                i j
(%i6) ishow(contract(%))$
                                l k
                                a
(%t6)

```

Presently, the only code that makes use of this notation is the **lc2kdt** function. Through this notation, it achieves consistent results as it applies the metric tensor to resolve Levi-Civita symbols without resorting to numeric indices.

Since this code is brand new, it probably contains bugs. While it has been tested to make sure that it doesn't break anything using the "old" tensor notation, there is a considerable chance that "new" tensors will fail to interoperate with certain functions or features. These bugs will be fixed as they are encountered... until then, caveat emptor!

25.1.2 Indicial tensor manipulation

The indicial tensor manipulation package may be loaded by **load(itensor)**. Demos are also available: try **demo(tensor)**.

In **itensor** a tensor is represented as an "indexed object". This is a function of 3 groups of indices which represent the covariant, contravariant and derivative indices. The covariant indices are specified by a list as the first argument to the indexed object, and the contravariant indices by a list as the second argument. If the indexed object lacks either of these groups of indices then the empty list **[]** is given as the corresponding argument. Thus, **g([a,b],[c])** represents an indexed object called **g** which has two covariant indices (**a,b**), one contravariant index (**c**) and no derivative indices.

The derivative indices, if they are present, are appended as additional arguments to the symbolic function representing the tensor. They can be explicitly specified by the user or be created in the process of differentiation with respect to some coordinate variable. Since ordinary differentiation is commutative, the derivative indices are sorted alphanumerically, unless **iframe_flag** is set to **true**, indicating that a frame metric is being used. This canonical ordering makes it possible for Maxima to recognize that, for example, **t([a],[b],i,j)** is the same as **t([a],[b],j,i)**. Differentiation of an indexed object with respect to some coordinate whose index does not appear as an argument to the indexed object would normally yield zero. This is because Maxima would not know that the tensor represented by the indexed object might depend implicitly on the corresponding coordinate. By modifying the existing Maxima function **diff** in **itensor**, Maxima now assumes that all indexed objects depend on any variable of differentiation unless otherwise stated. This makes it possible for the summation convention to be extended to derivative indices. It should be noted that **itensor** does not possess the capabilities of raising derivative indices, and so they are always treated as covariant.

The following functions are available in the tensor package for manipulating indexed objects. At present, with respect to the simplification routines, it is assumed that indexed objects do

not by default possess symmetry properties. This can be overridden by setting the variable `allsym[false]` to `true`, which will result in treating all indexed objects completely symmetric in their lists of covariant indices and symmetric in their lists of contravariant indices.

The `itensor` package generally treats tensors as opaque objects. Tensorial equations are manipulated based on algebraic rules, specifically symmetry and contraction rules. In addition, the `itensor` package understands covariant differentiation, curvature, and torsion. Calculations can be performed relative to a metric of moving frame, depending on the setting of the `iframe_flag` variable.

A sample session below demonstrates how to load the `itensor` package, specify the name of the metric, and perform some simple calculations.

```
(%i1) load(itensor);
(%o1)      /share/tensor/itensor.lisp
(%i2) imetric(g);
(%o2)
done
(%i3) components(g([i,j],[ ]),p([i,j],[ ])*e([ ],[ ]))$
(%i4) ishow(g([k,l],[ ]))$
(%t4)

$$e \quad p$$


$$k \quad l$$

(%i5) ishow(diff(v([i],[ ]),t))$
(%t5)
0
(%i6) depends(v,t);
(%o6)
[v(t)]
(%i7) ishow(diff(v([i],[ ]),t))$
(%t7)

$$\frac{d}{dt} (v_i)$$

(%i8) ishow(idiff(v([i],[ ]),j))$
(%t8)

$$v_{i,j}$$

(%i9) ishow(extdiff(v([i],[ ]),j))$
(%t9)

$$\frac{v_{j,i} - v_{i,j}}{2}$$

(%i10) ishow(liediff(v,w([i],[ ])))$
(%t10)

$$\frac{v_{i,\%3} w_{\%3} + v_{\%3,i} w_{\%3}}{2}$$

(%i11) ishow(covdiff(v([i],[ ]),j))$
(%t11)

$$\frac{v_{i,j} - v_{j,i} \text{chr2}}{\%4}$$

(%i12) ishow(ev(% ,ichr2))$
(%t12)

$$\frac{v_{i,j} - (g_{i,j} v_{\%4} (e_{j,\%5,i} p_{\%5,i} + e_{i,j,\%5} p_{\%5,j} - e_{i,j,\%5} p_{\%5,i} - e_{\%5,i,j} p_{\%5,j} + e_{i,\%5,j} p_{\%5,j} + e_{j,i,\%5} p_{\%5,i}))/2}{\%4 \ \%5}$$

(%i13) iframe_flag:true;
(%o13)
true
(%i14) ishow(covdiff(v([i],[ ]),j))$
(%t14)

$$\frac{v_{i,j} - v_{j,i} \text{icc2}}{\%6}$$

(%i15) ishow(ev(% ,icc2))$
```

```

(%t15)

$$\frac{v_{i,j} - v_{i,j}^{ifc2}}{i,j}$$

(%i16) ishow(radcan(ev(% , ifc2, ifc1)))$
(%t16) - (ifg

$$\frac{v_{i,j}^{ifb}}{i,j} + \frac{v_{i,j}^{ifb}}{i,j} - 2 \frac{v_{i,j}}{i,j}$$


$$- \frac{ifg_{i,j}^{ifb}}{i,j} )/2$$

(%i17) ishow(canform(s([i,j],[ ])-s([j,i])))$
(%t17)

$$s_{i,j} - s_{j,i}$$

(%i18) decsym(s,2,0,[sym(all)],[]);
(%o18) done
(%i19) ishow(canform(s([i,j],[ ])-s([j,i])))$
(%t19) 0
(%i20) ishow(canform(a([i,j],[ ])+a([j,i])))$
(%t20)

$$a_{j,i} + a_{i,j}$$

(%i21) decsym(a,2,0,[anti(all)],[]);
(%o21) done
(%i22) ishow(canform(a([i,j],[ ])+a([j,i])))$
(%t22) 0

```

25.2 Functions and Variables for itensor

25.2.1 Managing indexed objects

dispcon (*tensor_1, tensor_2, ...*) Function
dispcon (*all*) Function

Displays the contraction properties of its arguments as were given to **defcon**. **dispcon** (*all*) displays all the contraction properties which were defined.

entertensor (*name*) Function
 is a function which, by prompting, allows one to create an indexed object called *name* with any number of tensorial and derivative indices. Either a single index or a list of indices (which may be null) is acceptable input (see the example under **covdiff**).

changenname (*old, new, expr*) Function
 will change the name of all indexed objects called *old* to *new* in *expr*. *old* may be either a symbol or a list of the form [*name, m, n*] in which case only those indexed objects called *name* with *m* covariant and *n* contravariant indices will be renamed to *new*.

listoftens Function
 Lists all tensors in a tensorial expression, complete with their indices. E.g.,

```

(%i6) ishow(a([i,j],[k])*b([u],[ ],v)+c([x,y],[ ])*d([ ],[ ])*e)$
(%t6)

$$d_{x,y}^k + a_{i,j} b_{u,v}$$

(%i7) ishow(listoftens(%))$
(%t7)

$$[a_{i,j}, b_{u,v}, c_{x,y}^k, d_{x,y}^k]$$


```


$$i \ j \quad u, v \quad x \ y$$
ishow (*expr*)

Function

displays *expr* with the indexed objects in it shown having their covariant indices as subscripts and contravariant indices as superscripts. The derivative indices are displayed as subscripts, separated from the covariant indices by a comma (see the examples throughout this document).

indices (*expr*)

Function

Returns a list of two elements. The first is a list of the free indices in *expr* (those that occur only once). The second is the list of the dummy indices in *expr* (those that occur exactly twice) as the following example demonstrates.

```
(%i1) load(itensor);
(%o1)      /share/tensor/itensor.lisp
(%i2) ishow(a([i,j],[k,l],m,n)*b([k,o],[j,m,p],q,r))$
              k l      j m p
(%t2)      a      b
              i j,m n k o,q r
(%i3) indices(%);
(%o3)      [[l, p, i, n, o, q, r], [k, j, m]]
```

A tensor product containing the same index more than twice is syntactically illegal. **indices** attempts to deal with these expressions in a reasonable manner; however, when it is called to operate upon such an illegal expression, its behavior should be considered undefined.

rename (*expr*)

Function

rename (*expr*, *count*)

Function

Returns an expression equivalent to *expr* but with the dummy indices in each term chosen from the set [%1, %2, ...], if the optional second argument is omitted. Otherwise, the dummy indices are indexed beginning at the value of *count*. Each dummy index in a product will be different. For a sum, **rename** will operate upon each term in the sum resetting the counter with each term. In this way **rename** can serve as a tensorial simplifier. In addition, the indices will be sorted alphanumerically (if **allsym** is **true**) with respect to covariant or contravariant indices depending upon the value of **flipflag**. If **flipflag** is **false** then the indices will be renamed according to the order of the contravariant indices. If **flipflag** is **true** the renaming will occur according to the order of the covariant indices. It often happens that the combined effect of the two renamings will reduce an expression more than either one by itself.

```
(%i1) load(itensor);
(%o1)      /share/tensor/itensor.lisp
(%i2) allsym:true;
(%o2)      true
(%i3) g([],[%4,%5])*g([],[%6,%7])*ichr2([%1,%4],[%3])*
ichr2([%2,%3],[u])*ichr2([%5,%6],[%1])*ichr2([%7,r],[%2])-
g([],[%4,%5])*g([],[%6,%7])*ichr2([%1,%2],[u])*
ichr2([%3,%5],[%1])*ichr2([%4,%6],[%3])*ichr2([%7,r],[%2]),noeval$
(%i4) expr:ishow(%)$
              %4 %5 %6 %7      %3      u      %1      %2
(%t4) g      g      ichr2      ichr2      ichr2      ichr2
              %1 %4      %2 %3      %5 %6      %7 r

              %4 %5 %6 %7      u      %1      %3      %2
- g      g      ichr2      ichr2      ichr2      ichr2
              %1 %2      %3 %5      %4 %6      %7 r
```

```

(%i5) flipflag:true;
(%o5) true
(%i6) ishow(rename(expr))$
      %2 %5 %6 %7 %4 u %1 %3
(%t6) g g ichr2 ichr2 ichr2 ichr2
      %1 %2 %3 %4 %5 %6 %7 r

      %4 %5 %6 %7 u %1 %3 %2
- g g ichr2 ichr2 ichr2 ichr2
      %1 %2 %3 %4 %5 %6 %7 r

(%i7) flipflag:false;
(%o7) false
(%i8) rename(%th(2));
(%o8) 0
(%i9) ishow(rename(expr))$
      %1 %2 %3 %4 %5 %6 %7 u
(%t9) g g ichr2 ichr2 ichr2 ichr2
      %1 %6 %2 %3 %4 r %5 %7

      %1 %2 %3 %4 %6 %5 %7 u
- g g ichr2 ichr2 ichr2 ichr2
      %1 %3 %2 %6 %4 r %5 %7

```

show (*expr*) Function
 Displays *expr* with the indexed objects in it shown having covariant indices as subscripts, contravariant indices as superscripts. The derivative indices are displayed as subscripts, separated from the covariant indices by a comma.

flipflag Option variable
 Default: **false**. If **false** then the indices will be renamed according to the order of the contravariant indices, otherwise according to the order of the covariant indices.
 If **flipflag** is **false** then **rename** forms a list of the contravariant indices as they are encountered from left to right (if **true** then of the covariant indices). The first dummy index in the list is renamed to %1, the next to %2, etc. Then sorting occurs after the **rename**-ing (see the example under **rename**).

defcon (*tensor_1*) Function
defcon (*tensor_1*, *tensor_2*, *tensor_3*) Function
 gives *tensor_1* the property that the contraction of a product of *tensor_1* and *tensor_2* results in *tensor_3* with the appropriate indices. If only one argument, *tensor_1*, is given, then the contraction of the product of *tensor_1* with any indexed object having the appropriate indices (say *my_tensor*) will yield an indexed object with that name, i.e. *my_tensor*, and with a new set of indices reflecting the contractions performed. For example, if *imetric*:*g*, then **defcon**(*g*) will implement the raising and lowering of indices through contraction with the metric tensor. More than one **defcon** can be given for the same indexed object; the latest one given which applies in a particular contraction will be used. **contractions** is a list of those indexed objects which have been given contraction properties with **defcon**.

remcon (*tensor_1*, ..., *tensor_n*) Function
remcon (*all*) Function
 removes all the contraction properties from the *tensor_1*, ..., *tensor_n*. **remcon**(*all*) removes all contraction properties from all indexed objects.

contract (*expr*) Function
 Carries out the tensorial contractions in *expr* which may be any combination of sums and products. This function uses the information given to the **defcon** function. For best

results, `expr` should be fully expanded. `ratexpand` is the fastest way to expand products and powers of sums if there are no variables in the denominators of the terms. The `gcd` switch should be `false` if GCD cancellations are unnecessary.

indexed_tensor (*tensor*)

Function

Must be executed before assigning components to a *tensor* for which a built in value already exists as with `ichr1`, `ichr2`, `icurvature`. See the example under `icurvature`.

components (*tensor*, *expr*)

Function

permits one to assign an indicial value to an expression *expr* giving the values of the components of *tensor*. These are automatically substituted for the tensor whenever it occurs with all of its indices. The tensor must be of the form $t([\dots],[\dots])$ where either list may be empty. *expr* can be any indexed expression involving other objects with the same free indices as *tensor*. When used to assign values to the metric tensor wherein the components contain dummy indices one must be careful to define these indices to avoid the generation of multiple dummy indices. Removal of this assignment is given to the function `remcomps`.

It is important to keep in mind that `components` cares only about the valence of a tensor, not about any particular index ordering. Thus assigning components to, say, $x([i,-j],[\])$, $x([-j,i],[\])$, or $x([i],[j])$ all produce the same result, namely components being assigned to a tensor named *x* with valence (1,1).

Components can be assigned to an indexed expression in four ways, two of which involve the use of the `components` command:

1) As an indexed expression. For instance:

```
(%i2) components(g([\ ],[i,j]),e([\ ],[i])*p([\ ],[j]))$
(%i3) ishow(g([\ ],[i,j]))$

(%t3)
          i  j
        e  p
```

2) As a matrix:

```
(%i5) lg:-ident(4)$lg[1,1]:1$lg;
          [ 1  0  0  0 ]
          [
          [ 0 - 1  0  0 ]
(%o5)      [
          [ 0  0 - 1  0 ]
          [
          [ 0  0  0 - 1 ]

(%i6) components(g([i,j],[\ ]),lg);
(%o6)
done
(%i7) ishow(g([i,j],[\ ]))$
(%t7)
          g
          i j

(%i8) g([1,1],[\ ]);
(%o8)
1
(%i9) g([4,4],[\ ]);
(%o9)
- 1
```

3) As a function. You can use a Maxima function to specify the components of a tensor based on its indices. For instance, the following code assigns `kdelta` to *h* if *h* has the same number of covariant and contravariant indices and no derivative indices, and *g* otherwise:

```
(%i4) h(l1,l2,[l3]):=if length(l1)=length(l2) and length(l3)=0
then kdelta(l1,l2) else apply(g,append([l1,l2], l3))$
(%i5) ishow(h([i],[j]))$
```

j


```

[
[      r
[ sqrt(-----)  0      0      0
[      r - 2 m
[
[
[      0      r      0      0
(%t5)  g      =
[      0      0  r sin(theta)  0
[
[
[      r - 2 m
[      0      0      0      sqrt(-----)
[      r
(%o5)
false

```

The `showcomps` command can also display components of a tensor of rank higher than 2.

idummy () Function
 Increments **icounter** and returns as its value an index of the form %n where n is a positive integer. This guarantees that dummy indices which are needed in forming expressions will not conflict with indices already in use (see the example under **indices**).

idummyx	Option variable
Default value: %	
Is the prefix for dummy indices (see the example under indices).	

icounter	Option variable
Default value: 1	
Determines the numerical suffix to be used in generating the next dummy index in the tensor package. The prefix is determined by the option <code>idummy</code> (default: %).	

kdelta (*L1*, *L2*) Function

is the generalized Kronecker delta function defined in the **itensor** package with *L1* the list of covariant indices and *L2* the list of contravariant indices. **kdelta**([i],[j]) returns the ordinary Kronecker delta. The command **ev**(*expr*,**kdelta**) causes the evaluation of an expression containing **kdelta**([],[]) to the dimension of the manifold.

In what amounts to an abuse of this notation, **itensor** also allows **kdelta** to have 2 covariant and no contravariant, or 2 contravariant and no covariant indices, in effect providing a co(ntra)variant "unit matrix" capability. This is strictly considered a programming aid and not meant to imply that **kdelta**([i,j],[]) is a valid tensorial object.

kdels (<i>L1</i> , <i>L2</i>)	Function
Symmetrized Kronecker delta, used in some calculations. For instance:	

```
(%i1) load(itensor);
(%o1) /share/tensor/itensor.lisp
(%i2) kdelta([1,2],[2,1]);
(%o2)  $\delta_{12} - \delta_{21}$ 
(%i3) kdels([1,2],[2,1]);
(%o3)  $\delta_{12} + \delta_{21}$ 
(%i4) ishow(kdelta([a,b],[c,d]))$
(%t4)  $\delta_{a,c} \delta_{b,d} - \delta_{a,d} \delta_{b,c}$ 
(%i4) ishow(kdels([a,b],[c,d]))$
(%t4)  $\delta_{a,c} \delta_{b,d} + \delta_{a,d} \delta_{b,c}$ 
```

levi_civita (*L*)

Function

is the permutation (or Levi-Civita) tensor which yields 1 if the list *L* consists of an even permutation of integers, -1 if it consists of an odd permutation, and 0 if some indices in *L* are repeated.

lc2kdt (*expr*)

Function

Simplifies expressions containing the Levi-Civita symbol, converting these to Kronecker-delta expressions when possible. The main difference between this function and simply evaluating the Levi-Civita symbol is that direct evaluation often results in Kronecker expressions containing numerical indices. This is often undesirable as it prevents further simplification. The **lc2kdt** function avoids this problem, yielding expressions that are more easily simplified with **rename** or **contract**.

```
(%i1) load(itensor);
(%o1) /share/tensor/itensor.lisp
(%i2) expr:ishow('levi_civita([], [i,j])
      *'levi_civita([k,l], [])*a([j],[k]))$
      i j k
      levi_civita a levi_civita
      j k l
(%t2)
(%i3) ishow(ev(expr,levi_civita))$
      i j k 1 2
      kdelta a kdelta
      1 2 j k l
(%t3)
(%i4) ishow(ev(%,kdelta))$
      i j j i k
      (kdelta kdelta - kdelta kdelta) a
      1 2 1 2 j
      1 2 2 1
      (kdelta kdelta - kdelta kdelta)
      k l k l
(%i5) ishow(lc2kdt(expr))$
      k i j k j i
      a kdelta kdelta - a kdelta kdelta
      j k l j k l
(%t5)
(%i6) ishow(contract(expand(%)))$
      i i
      a - a kdelta
      1 1
(%t6)
```

The **lc2kdt** function sometimes makes use of the metric tensor. If the metric tensor was not defined previously with **imetric**, this results in an error.

```
(%i7) expr:ishow('levi_civita([], [i,j])
      *'levi_civita([], [k,l])*a([j,k], []))$
      i j k l
      levi_civita levi_civita a
      j k
(%t7)
(%i8) ishow(lc2kdt(expr))$
Maxima encountered a Lisp error:

Error in $IMETRIC [or a callee]:
$IMETRIC [or a callee] requires less than two arguments.

Automatically continuing.
To reenble the Lisp debugger set *debugger-hook* to nil.
```

```
(%i9) imetric(g);
(%o9)
done
(%i10) ishow(lc2kdt(expr))$
      %3 i      k      %4 j      1      %3 i      1      %4 j
(%t10) (g      kdelta      g      kdelta      - g      kdelta      g
      %3      %4      %3
      k
      kdelta      ) a
      %4      j k
(%i11) ishow(contract(expand(%)))$
      1 i      1 i      j
(%t11)      a      - g      a
      j
```

lc_l

Function

Simplification rule used for expressions containing the unevaluated Levi-Civita symbol (`levi_civita`). Along with `lc_u`, it can be used to simplify many expressions more efficiently than the evaluation of `levi_civita`. For example:

```
(%i1) load(itensor);
(%o1) /share/tensor/itensor.lisp
(%i2) e11:ishow('levi_civita([i,j,k],[[]])*a([],[i])*a([],[j]))$
      i j
      a a levi_civita
      i j k
(%i3) e12:ishow('levi_civita([],[i,j,k])*a([i])*a([j]))$
      i j k
      levi_civita      a a
      i j
(%i4) canform(contract(expand(applyb1(e11,lc_l,lc_u))))$
(%t4) 0
(%i5) canform(contract(expand(applyb1(e12,lc_l,lc_u))))$
(%t5) 0
```

lc_u

Function

Simplification rule used for expressions containing the unevaluated Levi-Civita symbol (`levi_civita`). Along with `lc_l`, it can be used to simplify many expressions more efficiently than the evaluation of `levi_civita`. For details, see `lc_l`.

canten (*expr*)

Function

Simplifies *expr* by renaming (see `rename`) and permuting dummy indices. `rename` is restricted to sums of tensor products in which no derivatives are present. As such it is limited and should only be used if `canform` is not capable of carrying out the required simplification.

The `canten` function returns a mathematically correct result only if its argument is an expression that is fully symmetric in its indices. For this reason, `canten` returns an error if `allsym` is not set to `true`.

concan (*expr*)

Function

Similar to `canten` but also performs index contraction.

25.2.2 Tensor symmetries

allsym

Option variable

Default: **false**. if **true** then all indexed objects are assumed symmetric in all of their covariant and contravariant indices. If **false** then no symmetries of any kind are assumed in these indices. Derivative indices are always taken to be symmetric unless **iframe_flag** is set to **true**.

decsym (*tensor*, *m*, *n*, [*cov_1*, *cov_2*, ...], [*contr_1*, *contr_2*, ...])

Function

Declares symmetry properties for *tensor* of *m* covariant and *n* contravariant indices. The *cov_i* and *contr_i* are pseudofunctions expressing symmetry relations among the covariant and contravariant indices respectively. These are of the form **symoper**(*index_1*, *index_2*, ...) where **symoper** is one of **sym**, **anti** or **cyc** and the *index_i* are integers indicating the position of the index in the *tensor*. This will declare *tensor* to be symmetric, antisymmetric or cyclic respectively in the *index_i*. **symoper**(**all**) is also an allowable form which indicates all indices obey the symmetry condition. For example, given an object **b** with 5 covariant indices, **decsym(b,5,3,[sym(1,2),anti(3,4)],[cyc(all)])** declares **b** symmetric in its first and second and antisymmetric in its third and fourth covariant indices, and cyclic in all of its contravariant indices. Either list of symmetry declarations may be null. The function which performs the simplifications is **canform** as the example below illustrates.

```
(%i1) load(itensor);
(%o1) /share/tensor/itensor.lisp
(%i2) expr:contract( expand( a([i1, j1, k1], [])
      *kdels([i, j, k], [i1, j1, k1])))$
(%i3) ishow(expr)$
(%t3)      a      + a      + a      + a      + a      + a
           k j i    k i j    j k i    j i k    i k j    i j k
(%i4) decsym(a,3,0,[sym(all)],[]);
(%o4)                                           done
(%i5) ishow(canform(expr))$
(%t5)                                           6 a
                                           i j k

(%i6) remsym(a,3,0);
(%o6)                                           done
(%i7) decsym(a,3,0,[anti(all)],[]);
(%o7)                                           done
(%i8) ishow(canform(expr))$
(%t8)                                           0
(%i9) remsym(a,3,0);
(%o9)                                           done
(%i10) decsym(a,3,0,[cyc(all)],[]);
(%o10)                                          done
(%i11) ishow(canform(expr))$
(%t11)      3 a      + 3 a
           i k j      i j k

(%i12) dispSYM(a,3,0);
(%o12)      [[cyc, [[1, 2, 3]], []]]
```

remsym (*tensor*, *m*, *n*)

Function

Removes all symmetry properties from *tensor* which has *m* covariant indices and *n* contravariant indices.

canform (*expr*)

Function

canform (*expr*, *rename*)

Function

Simplifies *expr* by renaming dummy indices and reordering all indices as dictated by symmetry conditions imposed on them. If **allsym** is **true** then all indices are assumed

symmetric, otherwise symmetry information provided by **decsym** declarations will be used. The dummy indices are renamed in the same manner as in the **rename** function. When **canform** is applied to a large expression the calculation may take a considerable amount of time. This time can be shortened by calling **rename** on the expression first. Also see the example under **decsym**. Note: **canform** may not be able to reduce an expression completely to its simplest form although it will always return a mathematically correct result.

The optional second parameter *rename*, if set to **false**, suppresses renaming.

25.2.3 Indicial tensor calculus

diff (*expr*, *v_1*, [*n_1*, [*v_2*, *n_2*] ...]) Function

is the usual Maxima differentiation function which has been expanded in its abilities for **itensor**. It takes the derivative of *expr* with respect to *v_1* *n_1* times, with respect to *v_2* *n_2* times, etc. For the tensor package, the function has been modified so that the *v_i* may be integers from 1 up to the value of the variable **dim**. This will cause the differentiation to be carried out with respect to the *v_i*th member of the list **vect_coords**. If **vect_coords** is bound to an atomic variable, then that variable subscripted by *v_i* will be used for the variable of differentiation. This permits an array of coordinate names or subscripted names like **x[1]**, **x[2]**, ... to be used.

A further extension adds the ability to **diff** to compute derivatives with respect to an indexed variable. In particular, the tensor package knows how to differentiate expressions containing combinations of the metric tensor and its derivatives with respect to the metric tensor and its first and second derivatives. This capability is particularly useful when considering Lagrangian formulations of a gravitational theory, allowing one to derive the Einstein tensor and field equations from the action principle.

idiff (*expr*, *v_1*, [*n_1*, [*v_2*, *n_2*] ...]) Function

Indicial differentiation. Unlike **diff**, which differentiates with respect to an independent variable, **idiff** can be used to differentiate with respect to a coordinate. For an indexed object, this amounts to appending the *v_i* as derivative indices. Subsequently, derivative indices will be sorted, unless **iframe_flag** is set to **true**.

idiff can also differentiate the determinant of the metric tensor. Thus, if **imetric** has been bound to **G** then **idiff(determinant(g),k)** will return **2 * determinant(g) * ichr2([%i,k],[%i])** where the dummy index *%i* is chosen appropriately.

liediff (*v*, *ten*) Function

Computes the Lie-derivative of the tensorial expression *ten* with respect to the vector field *v*. *ten* should be any indexed tensor expression; *v* should be the name (without indices) of a vector field. For example:

```
(%i1) load(itensor);
(%o1)      /share/tensor/itensor.lisp
(%i2) ishow(liediff(v,a([i,j],[k],1)))$
      k      %2      %2      %2
(%t2) b      (v      a      + v      a      + v      a      )
      ,1      i j,%2      ,j i %2      ,i %2 j
              %1 k      %1 k      %1 k
              + (v      b      - b      v      + v      b      ) a
              ,%1 1      ,1 ,%1      ,1 ,%1      i j
```

rediff (*ten*) Function

Evaluates all occurrences of the **idiff** command in the tensorial expression *ten*.

undiff (*expr*)

Function

Returns an expression equivalent to *expr* but with all derivatives of indexed objects replaced by the noun form of the **idiff** function. Its arguments would yield that indexed object if the differentiation were carried out. This is useful when it is desired to replace a differentiated indexed object with some function definition resulting in *expr* and then carry out the differentiation by saying **ev**(*expr*, **idiff**).

evundiff (*expr*)

Function

Equivalent to the execution of **undiff**, followed by **ev** and **rediff**.

The point of this operation is to easily evaluate expressions that cannot be directly evaluated in derivative form. For instance, the following causes an error:

```
(%i1) load(itensor);
(%o1)      /share/tensor/itensor.lisp
(%i2) icurvature([i,j,k],[l],m);
Maxima encountered a Lisp error:
```

```
Error in $ICURVATURE [or a callee]:
$ICURVATURE [or a callee] requires less than three arguments.
```

Automatically continuing.

To reenale the Lisp debugger set **debugger-hook** to nil.

However, if **icurvature** is entered in noun form, it can be evaluated using **evundiff**:

```
(%i3) ishow('icurvature([i,j,k],[l],m))$
                                     1
(%t3)                               icurvature
                                     i j k,m

(%i4) ishow(evundiff(%))$
                                     1      1      %1      1      %1
(%t4) - ichr2      - ichr2      ichr2      - ichr2      ichr2
          i k,j m      %1 j      i k,m      %1 j,m      i k

          1      1      %1      1      %1
      + ichr2      + ichr2      ichr2      + ichr2      ichr2
          i j,k m      %1 k      i j,m      %1 k,m      i j
```

Note: In earlier versions of Maxima, derivative forms of the Christoffel-symbols also could not be evaluated. This has been fixed now, so **evundiff** is no longer necessary for expressions like this:

```
(%i5) imetric(g);
(%o5)                                     done
(%i6) ishow(ichr2([i,j],[k],1))$
      k %3
      g      (g      - g      + g      )
          j %3,i 1      i j,%3 1      i %3,j 1
(%t6) -----
                      2

                      k %3
                      g      (g      - g      + g      )
                      ,1      j %3,i      i j,%3      i %3,j
      + -----
                      2
```

flush (*expr*, *tensor_1*, *tensor_2*, ...)

Function

Set to zero, in *expr*, all occurrences of the *tensor_i* that have no derivative indices.

flushd (*expr*, *tensor_1*, *tensor_2*, ...)

Function

Set to zero, in *expr*, all occurrences of the *tensor_i* that have derivative indices.

flushnd (*expr*, *tensor*, *n*)

Function

Set to zero, in *expr*, all occurrences of the differentiated object *tensor* that have *n* or more derivative indices as the following example demonstrates.

```
(%i1) load(itensor);
(%o1)      /share/tensor/itensor.lisp
(%i2) ishow(a([i],[J,r],k,r)+a([i],[j,r,s],k,r,s))$
              J r      j r s
(%t2)      a      + a
              i,k r    i,k r s
(%i3) ishow(flushnd(%,a,3))$
              J r
(%t3)      a
              i,k r
```

coord (*tensor_1*, *tensor_2*, ...)

Function

Gives *tensor_i* the coordinate differentiation property that the derivative of contravariant vector whose name is one of the *tensor_i* yields a Kronecker delta. For example, if **coord**(*x*) has been done then **idiff**(*x*([],[i]),*j*) gives **kdelta**([i],[j]). **coord** is a list of all indexed objects having this property.

remcoord (*tensor_1*, *tensor_2*, ...)

Function

remcoord (*all*)

Function

Removes the coordinate differentiation property from the *tensor_i* that was established by the function **coord**. **remcoord**(*all*) removes this property from all indexed objects.

makebox (*expr*)

Function

Display *expr* in the same manner as **show**; however, any tensor d'Alembertian occurring in *expr* will be indicated using the symbol \square . For example, $\square p([m],[n])$ represents $g([i],[j]) * p([m],[n],i,j)$.

conmetderiv (*expr*, *tensor*)

Function

Simplifies expressions containing ordinary derivatives of both covariant and contravariant forms of the metric tensor (the current restriction). For example, **conmetderiv** can relate the derivative of the contravariant metric tensor with the Christoffel symbols as seen from the following:

```
(%i1) load(itensor);
(%o1)      /share/tensor/itensor.lisp
(%i2) ishow(g([],[a,b],c))$
              a b
(%t2)      g
              ,c
(%i3) ishow(conmetderiv(%,g))$
              %1 b      a      %1 a      b
(%t3)      - g      ichr2      - g      ichr2
              %1 c      %1 c      %1 c
```

simplmetderiv (*expr*)

Function

simplmetderiv (*expr*[, *stop*])

Function

Simplifies expressions containing products of the derivatives of the metric tensor. Specifically, **simplmetderiv** recognizes two identities:

$$g_{,d}^{ab} g_{bc}^{ab} + g_{bc,d}^{ab} g^{ab} = (g_{bc,d}^{ab} g^{ab}) = (kdelta_{c,d}^a) = 0$$

hence

$$g_{,d}^{ab} g_{bc} = - g_{bc,d}^{ab} g$$

and

$$g_{,j}^{ab} g_{ab,i} = g_{,i}^{ab} g_{ab,j}$$

which follows from the symmetries of the Christoffel symbols.

The `simplmetderiv` function takes one optional parameter which, when present, causes the function to stop after the first successful substitution in a product expression. The `simplmetderiv` function also makes use of the global variable `flipflag` which determines how to apply a “canonical” ordering to the product indices.

Put together, these capabilities can be used to achieve powerful simplifications that are difficult or impossible to accomplish otherwise. This is demonstrated through the following example that explicitly uses the partial simplification features of `simplmetderiv` to obtain a contractible expression:

```
(%i1) load(itensor);
(%o1)      /share/tensor/itensor.lisp
(%i2) imetric(g);
(%o2)
done
(%i3) ishow(g([], [a,b])*g([], [b,c])*g([a,b], [], d)*g([b,c], [], e))$
          a b  b c
          g   g   g   g
          a b,d b c,e
(%t3)
(%i4) ishow(canform(%))$

errexpl has improper indices
-- an error.  Quitting.  To debug this try debugmode(true);
(%i5) ishow(simplmetderiv(%))$
          a b  b c
          g   g   g   g
          a b,d b c,e
(%t5)
(%i6) flipflag:not flipflag;
(%o6)
true
(%i7) ishow(simplmetderiv(%th(2)))$
          a b  b c
          g   g   g   g
          ,d  ,e  a b  b c
(%t7)
(%i8) flipflag:not flipflag;
(%o8)
false
(%i9) ishow(simplmetderiv(%th(2), stop))$
          a b  b c
          - g   g   g   g
          ,e  a b,d b c
(%t9)
(%i10) ishow(contract(%))$
          b c
          - g   g
          ,e  c b,d
(%t10)
```

See also `weyl.dem` for an example that uses `simpmetderiv` and `conmetderiv` together to simplify contractions of the Weyl tensor.

flush1deriv (*expr*, *tensor*) Function
Set to zero, in *expr*, all occurrences of *tensor* that have exactly one derivative index.

25.2.4 Tensors in curved spaces

imetric (*g*) Function
imetric System variable

Specifies the metric by assigning the variable `imetric:g` in addition, the contraction properties of the metric *g* are set up by executing the commands `defcon(g)`, `defcon(g, g, kdelta)`. The variable `imetric` (unbound by default), is bound to the metric, assigned by the `imetric(g)` command.

idim (*n*) Function
Sets the dimensions of the metric. Also initializes the antisymmetry properties of the Levi-Civita symbols for the given dimension.

ichr1 ([*i*, *j*, *k*]) Function
Yields the Christoffel symbol of the first kind via the definition

$$(g_{ik,j} + g_{jk,i} - g_{ij,k})/2.$$

To evaluate the Christoffel symbols for a particular metric, the variable `imetric` must be assigned a name as in the example under `chr2`.

ichr2 ([*i*, *j*], [*k*]) Function
Yields the Christoffel symbol of the second kind defined by the relation

$$\text{ichr2}([i,j],[k]) = g^{ks} (g_{is,j} + g_{js,i} - g_{ij,s})/2$$

icurvature ([*i*, *j*, *k*], [*h*]) Function
Yields the Riemann curvature tensor in terms of the Christoffel symbols of the second kind (`ichr2`). The following notation is used:

$$\begin{aligned} \text{icurvature}_{ijk}^h &= -\text{ichr2}_{ik,j}^h - \text{ichr2}_{ij,k}^h + \text{ichr2}_{ij,k}^h + \text{ichr2}_{ik,j}^h \\ &\quad + \text{ichr2}_{ij,k}^h - \text{ichr2}_{ik,j}^h \end{aligned}$$

covdiff (*expr*, *v_1*, *v_2*, ...) Function
Yields the covariant derivative of *expr* with respect to the variables *v_i* in terms of the Christoffel symbols of the second kind (`ichr2`). In order to evaluate these, one should use `ev(expr,ichr2)`.

```
(%i1) load(itensor);
(%o1)      /share/tensor/itensor.lisp
(%i2) entertensor()$
Enter tensor name: a;
Enter a list of the covariant indices: [i,j];
Enter a list of the contravariant indices: [k];
Enter a list of the derivative indices: [];
```

k

```

(%t2)
a
i j
(%i3) ishow(covdiff(%s))$
k %1 k %1 k
(%t3) - a ichr2 - a ichr2 + a
i %1 j s %1 j i s i j,s
k %1
+ ichr2 a
%1 s i j
(%i4) imetric:g;
(%o4) g
(%i5) ishow(ev(%th(2),ichr2))$
%1 %4 k
g a (g - g + g )
i %1 s %4,j j s,%4 j %4,s
(%t5) - -----
2
%1 %3 k
g a (g - g + g )
%1 j s %3,i i s,%3 i %3,s
- -----
2
k %2 %1
g a (g - g + g )
i j s %2,%1 %1 s,%2 %1 %2,s
+ ----- + a
2 i j,s
(%i6)

```

lorentz_gauge (*expr*) Function
Imposes the Lorentz condition by substituting 0 for all indexed objects in *expr* that have a derivative index identical to a contravariant index.

igeodesic_coords (*expr*, *name*) Function
Causes undifferentiated Christoffel symbols and first derivatives of the metric tensor vanish in *expr*. The *name* in the **igeodesic_coords** function refers to the metric *name* (if it appears in *expr*) while the connection coefficients must be called with the names *ichr1* and/or *ichr2*. The following example demonstrates the verification of the cyclic identity satisfied by the Riemann curvature tensor using the **igeodesic_coords** function.

```

(%i1) load(itensor);
(%o1) /share/tensor/itensor.lisp
(%i2) ishow(icurvature([r,s,t],[u]))$
u u %1 u
(%t2) - ichr2 - ichr2 ichr2 + ichr2
r t,s %1 s r t r s,t
u %1
+ ichr2 ichr2
%1 t r s
(%i3) ishow(igeodesic_coords(%s,ichr2))$
u u
(%t3) ichr2 - ichr2
r s,t r t,s
(%i4) ishow(igeodesic_coords(icurvature([r,s,t],[u]),ichr2)+
igeodesic_coords(icurvature([s,t,r],[u]),ichr2)+

```

```

            igeodesic_coords(icurvature([t,r,s],[u]),ichr2))$
            u          u          u          u
(%t4) - ichr2      + ichr2      + ichr2      - ichr2
            t s,r      t r,s      s t,r      s r,t

            u          u
            - ichr2      + ichr2
            r t,s      r s,t

(%i5) canform(%);
(%o5) 0

```

25.2.5 Moving frames

Maxima now has the ability to perform calculations using moving frames. These can be orthonormal frames (tetrads, vielbeins) or an arbitrary frame.

To use frames, you must first set `iframe_flag` to `true`. This causes the Christoffel-symbols, `ichr1` and `ichr2`, to be replaced by the more general frame connection coefficients `icc1` and `icc2` in calculations. Specifically, the behavior of `covdiff` and `icurvature` is changed.

The frame is defined by two tensors: the inverse frame field (`ifri`, the dual basis tetrad), and the frame metric `ifg`. The frame metric is the identity matrix for orthonormal frames, or the Lorentz metric for orthonormal frames in Minkowski spacetime. The inverse frame field defines the frame base (unit vectors). Contraction properties are defined for the frame field and the frame metric.

When `iframe_flag` is true, many `itensor` expressions use the frame metric `ifg` instead of the metric defined by `imetric` for raising and lowering indices.

IMPORTANT: Setting the variable `iframe_flag` to `true` does NOT undefine the contraction properties of a metric defined by a call to `defcon` or `imetric`. If a frame field is used, it is best to define the metric by assigning its name to the variable `imetric` and NOT invoke the `imetric` function.

Maxima uses these two tensors to define the frame coefficients (`ifc1` and `ifc2`) which form part of the connection coefficients (`icc1` and `icc2`), as the following example demonstrates:

```

(%i1) load(itensor);
(%o1) /share/tensor/itensor.lisp
(%i2) iframe_flag:true;
(%o2) true
(%i3) ishow(covdiff(v([],[i]),j))$
            i          i          %1
(%t3)      v  + icc2      v
            ,j          %1 j

(%i4) ishow(ev(%,icc2))$
            %1          i          i
(%t4)      v  ifc2      + v
            %1 j          ,j

(%i5) ishow(ev(%,ifc2))$
            %1          i %2          i
(%t5)      v  ifg      ifc1      + v
            %1 j %2          ,j

(%i6) ishow(ev(%,ifc1))$
            %1          i %2
            v  ifg      (ifb      - ifb      + ifb      )
            j %2 %1          %2 %1 j          %1 j %2          i
(%t6)      ----- + v
            2
(%i7) ishow(ifb([a,b,c]))$

```

$$(\%t7) \quad \left(\text{ifri}_{a \%3, \%4} - \text{ifri}_{a \%4, \%3} \right) \text{ifr}_{b \%3} \text{ifr}_{c \%4}$$

An alternate method is used to compute the frame bracket (`ifb`) if the `iframe_bracket_form` flag is set to `false`:

$$(\%i8) \text{ block}([\text{iframe_bracket_form}:\text{false}], \text{ishow}(\text{ifb}([a, b, c])))\$$$

$$(\%t8) \quad \text{ifri}_{a \%5} \left(\text{ifr}_{b \%6} \text{ifr}_{c \%5} - \text{ifr}_{b \%5} \text{ifr}_{c \%6} \right)$$

iframes () Function
 Since in this version of Maxima, contraction identities for `ifr` and `ifri` are always defined, as is the frame bracket (`ifb`), this function does nothing.

ifb Variable
 The frame bracket. The contribution of the frame metric to the connection coefficients is expressed using the frame bracket:

$$\text{ifc1}_{abc} = \frac{-\text{ifb}_{cab} + \text{ifb}_{bca} + \text{ifb}_{abc}}{2}$$

The frame bracket itself is defined in terms of the frame field and frame metric. Two alternate methods of computation are used depending on the value of `frame_bracket_form`. If `true` (the default) or if the `itorsion_flag` is `true`:

$$\text{ifb}_{abc} = \text{ifr}_{ab}^d \text{ifr}_{bc}^e \left(\text{ifri}_{a d, e} - \text{ifri}_{a e, d} - \text{ifri}_{a f} \text{itr}_{d e}^f \right)$$

Otherwise:

$$\text{ifb}_{abc} = \left(\text{ifr}_{ab}^e \text{ifr}_{c, e}^d - \text{ifr}_{b, e}^d \text{ifr}_{ac}^e \right) \text{ifri}_{ad}$$

icc1 Variable
 Connection coefficients of the first kind. In `itensor`, defined as

$$\text{icc1}_{abc} = \text{ichr1}_{abc} - \text{ikt1}_{abc} - \text{inmc1}_{abc}$$

In this expression, if `iframe_flag` is `true`, the Christoffel-symbol `ichr1` is replaced with the frame connection coefficient `ifc1`. If `itorsion_flag` is `false`, `ikt1` will be omitted. It is also omitted if a frame base is used, as the torsion is already calculated as part of the frame bracket. Lastly, if `inonmet_flag` is `false`, `inmc1` will not be present.

icc2 Variable
 Connection coefficients of the second kind. In `itensor`, defined as

$$\text{icc2}_{ab}^c = \text{ichr2}_{ab}^c - \text{ikt2}_{ab}^c - \text{inmc2}_{ab}^c$$

In this expression, if `iframe_flag` is true, the Christoffel-symbol `ichr2` is replaced with the frame connection coefficient `ifc2`. If `itorsion_flag` is false, `ikt2` will be omitted. It is also omitted if a frame base is used, as the torsion is already calculated as part of the frame bracket. Lastly, if `inonmet_flag` is false, `inmc2` will not be present.

ifc1

Variable

Frame coefficient of the first kind (also known as Ricci-rotation coefficients.) This tensor represents the contribution of the frame metric to the connection coefficient of the first kind. Defined as:

$$\text{ifc1}_{abc} = \frac{-\text{ifb}_{cab} + \text{ifb}_{bca} + \text{ifb}_{abc}}{2}$$

ifc2

Variable

Frame coefficient of the second kind. This tensor represents the contribution of the frame metric to the connection coefficient of the second kind. Defined as a permutation of the frame bracket (`ifb`) with the appropriate indices raised and lowered as necessary:

$$\text{ifc2}_{ab}^c = \text{ifg}_{cd}^c \text{ifc1}_{abd}$$

ifr

Variable

The frame field. Contracts with the inverse frame field (`ifri`) to form the frame metric (`ifg`).

ifri

Variable

The inverse frame field. Specifies the frame base (dual basis vectors). Along with the frame metric, it forms the basis of all calculations based on frames.

ifg

Variable

The frame metric. Defaults to `kdelta`, but can be changed using `components`.

ifgi

Variable

The inverse frame metric. Contracts with the frame metric (`ifg`) to `kdelta`.

iframe_bracket_form

Option variable

Default value: `true`

Specifies how the frame bracket (`ifb`) is computed.

25.2.6 Torsion and nonmetricity

Maxima can now take into account torsion and nonmetricity. When the flag `itorsion_flag` is set to `true`, the contribution of torsion is added to the connection coefficients. Similarly, when the flag `inonmet_flag` is true, nonmetricity components are included.

inm

Variable

The nonmetricity vector. Conformal nonmetricity is defined through the covariant derivative of the metric tensor. Normally zero, the metric tensor's covariant derivative will evaluate to the following when `inonmet_flag` is set to `true`:

$$g_{ij;k} = -g_{ij} \text{ inm}_k$$

inmc1

Variable

Covariant permutation of the nonmetricity vector components. Defined as

$$\text{inmc1}_{abc} = \frac{g_{ab} \text{ inm}_c - \text{inm}_a g_{bc} - g_{ac} \text{ inm}_b}{2}$$

(Substitute `ifg` in place of `g` if a frame metric is used.)

inmc2

Variable

Contravariant permutation of the nonmetricity vector components. Used in the connection coefficients if `inonmet_flag` is `true`. Defined as:

$$\text{inmc2}_{ab}^c = \frac{-\text{inm}_a^c \text{ kdelta}_{cb} - \text{ kdelta}_{ab}^c \text{ inm}_b + g_{ab}^c \text{ inm}_d^d}{2}$$

(Substitute `ifg` in place of `g` if a frame metric is used.)

ikt1

Variable

Covariant permutation of the torsion tensor (also known as contorsion). Defined as:

$$\text{ikt1}_{abc} = \frac{-g_{ad} \text{ itr}_{cb} - g_{bd} \text{ itr}_{ca} - \text{itr}_{ab} g_{cd}}{2}$$

(Substitute `ifg` in place of `g` if a frame metric is used.)

ikt2

Variable

Contravariant permutation of the torsion tensor (also known as contorsion). Defined as:

$$\text{ikt2}_{ab}^c = g_{ab}^c \text{ ikt1}_{abd}$$

(Substitute `ifg` in place of `g` if a frame metric is used.)

itr

Variable

The torsion tensor. For a metric with torsion, repeated covariant differentiation on a scalar function will not commute, as demonstrated by the following example:

```

(%i1) load(itensor);
(%o1) /share/tensor/itensor.lisp
(%i2) imetric:g;
(%o2)
(%i3) covdiff( covdiff( f( [], []), i), j)
          - covdiff( covdiff( f( [], []), j), i)$
(%i4) ishow(%)$
          %4 %2
          f  ichr2 - f  ichr2
          ,%4   j i  ,%2   i j
(%t4)
(%i5) canform(%);
(%o5) 0
(%i6) itorsion_flag:true;
(%o6) true
(%i7) covdiff( covdiff( f( [], []), i), j)
          - covdiff( covdiff( f( [], []), j), i)$
(%i8) ishow(%)$
          %8 %6
          f  icc2 - f  icc2 - f  + f
          ,%8   j i  ,%6   i j  ,j i  ,i j
(%t8)
(%i9) ishow(canform(%))$
          %1 %1
          f  icc2 - f  icc2
          ,%1   j i  ,%1   i j
(%t9)
(%i10) ishow(canform(ev(%,icc2)))$
          %1 %1
          f  ikt2 - f  ikt2
          ,%1   i j  ,%1   j i
(%t10)
(%i11) ishow(canform(ev(%,ikt2)))$
          %2 %1 %2 %1
          f  g  ikt1 - f  g  ikt1
          ,%2   i j %1 ,%2   j i %1
(%t11)
(%i12) ishow(factor(canform(rename(expand(ev(%,ikt1))))))$
          %3 %2 %1 %1
          f  g  g  (itr - itr )
          ,%3   %2 %1   j i   i j
(%t12)
          -----
          2
(%i13) decsym(itr,2,1,[anti(all)],[]);
(%o13) done
(%i14) defcon(g,g,kdelta);
(%o14) done
(%i15) subst(g,nounify(g),%th(3))$
(%i16) ishow(canform(contract(%)))$
          %1
          - f  itr
          ,%1   i j

```

25.2.7 Exterior algebra

The `itensor` package can perform operations on totally antisymmetric covariant tensor fields. A totally antisymmetric tensor field of rank (0,L) corresponds with a differential L-form. On these objects, a multiplication operation known as the exterior product, or wedge product, is defined.

Unfortunately, not all authors agree on the definition of the wedge product. Some authors prefer a definition that corresponds with the notion of antisymmetrization: in these works, the wedge product of two vector fields, for instance, would be defined as

$$a_i \wedge a_j = \frac{a_i a_j - a_j a_i}{2}$$

More generally, the product of a p-form and a q-form would be defined as

$$A_{i_1 \dots i_p} \wedge B_{j_1 \dots j_q} = \frac{1}{(p+q)!} D_{i_1 \dots i_p j_1 \dots j_q}^{k_1 \dots k_p l_1 \dots l_q} A_{k_1 \dots k_p} B_{l_1 \dots l_q}$$

where D stands for the Kronecker-delta.

Other authors, however, prefer a “geometric” definition that corresponds with the notion of the volume element:

$$a_i \wedge a_j = a_i a_j - a_j a_i$$

and, in the general case

$$A_{i_1 \dots i_p} \wedge B_{j_1 \dots j_q} = \frac{1}{p! q!} D_{i_1 \dots i_p j_1 \dots j_q}^{k_1 \dots k_p l_1 \dots l_q} A_{k_1 \dots k_p} B_{l_1 \dots l_q}$$

Since `itensor` is a tensor algebra package, the first of these two definitions appears to be the more natural one. Many applications, however, utilize the second definition. To resolve this dilemma, a flag has been implemented that controls the behavior of the wedge product: if `igeowedge_flag` is `false` (the default), the first, “tensorial” definition is used, otherwise the second, “geometric” definition will be applied.

~

Operator

The wedge product operator is denoted by the tilde `~`. This is a binary operator. Its arguments should be expressions involving scalars, covariant tensors of rank one, or covariant tensors of rank 1 that have been declared antisymmetric in all covariant indices.

The behavior of the wedge product operator is controlled by the `igeowedge_flag` flag, as in the following example:

```
(%i1) load(itensor);
(%o1) /share/tensor/itensor.lisp
(%i2) ishow(a([i])~b([j]))$
      a  b  - b  a
      i  j   i  j
      -----
              2
(%t2)
(%i3) decsym(a,2,0,[anti(all)],[]);
(%o3) done
(%i4) ishow(a([i,j])~b([k]))$
      a  b  + b  a  - a  b
      i  j  k   i  j  k   i  k  j
      -----
              3
(%t4)
(%i5) igeowedge_flag:true;
(%o5) true
(%i6) ishow(a([i])~b([j]))$
      a  b  - b  a
      i  j   i  j
(%t6)
(%i7) ishow(a([i,j])~b([k]))$
      a  b  + b  a  - a  b
      i  j  k   i  j  k   i  k  j
(%t7)
```

|

Operator

The vertical bar | denotes the "contraction with a vector" binary operation. When a totally antisymmetric covariant tensor is contracted with a contravariant vector, the result is the same regardless which index was used for the contraction. Thus, it is possible to define the contraction operation in an index-free manner.

In the `itensor` package, contraction with a vector is always carried out with respect to the first index in the literal sorting order. This ensures better simplification of expressions involving the | operator. For instance:

```
(%i1) load(itensor);
(%o1) /share/tensor/itensor.lisp
(%i2) decsym(a,2,0,[anti(all)],[]);
(%o2) done
(%i3) ishow(a([i,j],[])|v)$
(%t3)

$$v^i a_{ij}$$

(%i4) ishow(a([j,i],[])|v)$
(%t4)

$$-v^i a_{ji}$$

```

Note that it is essential that the tensors used with the | operator be declared totally antisymmetric in their covariant indices. Otherwise, the results will be incorrect.

extdiff (expr, i)

Function

Computes the exterior derivative of `expr` with respect to the index `i`. The exterior derivative is formally defined as the wedge product of the partial derivative operator and a differential form. As such, this operation is also controlled by the setting of `igeowedge_flag`. For instance:

```
(%i1) load(itensor);
(%o1) /share/tensor/itensor.lisp
(%i2) ishow(extdiff(v([i]),j))$
(%t2)

$$\frac{v_{j,i} - v_{i,j}}{2}$$

(%i3) decsym(a,2,0,[anti(all)],[]);
(%o3) done
(%i4) ishow(extdiff(a([i,j]),k))$
(%t4)

$$\frac{a_{jk,i} - a_{ik,j} + a_{ij,k}}{3}$$

(%i5) igeowedge_flag:true;
(%o5) true
(%i6) ishow(extdiff(v([i]),j))$
(%t6)

$$v_{j,i} - v_{i,j}$$

(%i7) ishow(extdiff(a([i,j]),k))$
(%t7)

$$-(a_{kj,i} - a_{ki,j} + a_{ji,k})$$

```

hodge (expr)

Function

Compute the Hodge-dual of `expr`. For instance:

```
(%i1) load(itensor);
```

```

(%o1)      /share/tensor/itensor.lisp
(%i2) imetric(g);
(%o2)                                     done
(%i3) idim(4);
(%o3)                                     done
(%i4) icounter:100;
(%o4)                                     100
(%i5) decsym(A,3,0,[anti(all)],[])$

(%i6) ishow(A([i,j,k],[]))$
(%t6)
      A
      i j k
(%i7) ishow(canform(hodge(%)))$
      %1 %2 %3 %4
      levi_civita
      g
      %1 %102 A %2 %3 %4
      -----
      6
(%i8) ishow(canform(hodge(%)))$
      %1 %2 %3 %8 %4 %5 %6 %7
(%t8) levi_civita levi_civita g
      %1 %106
      g %2 %107 g %3 %108 g %4 %8 A %5 %6 %7 /6

(%i9) lc2kdt(%)$

(%i10) %,kdelta$

(%i11) ishow(canform(contract(expand(%))))$
(%t11)
      - A
      %106 %107 %108

```

igeowedge_flag

Option variable

Default value: `false`

Controls the behavior of the wedge product and exterior derivative. When set to `false` (the default), the notion of differential forms will correspond with that of a totally anti-symmetric covariant tensor field. When set to `true`, differential forms will agree with the notion of the volume element.

25.2.8 Exporting TeX expressions

The `itensor` package provides limited support for exporting tensor expressions to TeX. Since `itensor` expressions appear as function calls, the regular Maxima `tex` command will not produce the expected output. You can try instead the `tentex` command, which attempts to translate tensor expressions into appropriately indexed TeX objects.

tentex (expr)

Function

To use the `tentex` function, you must first load `tentex`, as in the following example:

```

(%i1) load(itensor);
(%o1)      /share/tensor/itensor.lisp
(%i2) load(tentex);
(%o2)      /share/tensor/tentex.lisp
(%i3) idummyx:m;
(%o3)                                     m
(%i4) ishow(icurvature([j,k,l],[i]))$
      m1 i m1 i i

```

```
(%t4)      ichr2      ichr2      - ichr2      ichr2      - ichr2
           j k        m1 l        j l        m1 k        j l,k
                                           i
                                           + ichr2
                                           j k,l

(%i5) tentex(%)$
$$\Gamma_{j\backslash,k}^{m_1}\backslash,\Gamma_{l\backslash,m_1}^{i}-\Gamma_{j\backslash,l}^{m_1}\backslash,
\Gamma_{k\backslash,m_1}^{i}-\Gamma_{j\backslash,l,k}^{i}+\Gamma_{j\backslash,k,l}^{i}$$
```

Note the use of the `idummyx` assignment, to avoid the appearance of the percent sign in the TeX expression, which may lead to compile errors.

NB: This version of the `tentex` function is somewhat experimental.

25.2.9 Interfacing with ctensor

The `itensor` package has the ability to generate Maxima code that can then be executed in the context of the `ctensor` package. The function that performs this task is `ic_convert`.

`ic_convert` (*eqn*)

Function

Converts the `itensor` equation *eqn* to a `ctensor` assignment statement. Implied sums over dummy indices are made explicit while indexed objects are transformed into arrays (the array subscripts are in the order of covariant followed by contravariant indices of the indexed objects). The derivative of an indexed object will be replaced by the noun form of `diff` taken with respect to `ct_coords` subscripted by the derivative index. The Christoffel symbols `ichr1` and `ichr2` will be translated to `lcs` and `mcs`, respectively and if `metricconvert` is `true` then all occurrences of the metric with two covariant (contravariant) indices will be renamed to `lg` (`ug`). In addition, `do` loops will be introduced summing over all free indices so that the transformed assignment statement can be evaluated by just doing `ev`. The following examples demonstrate the features of this function.

```
(%i1) load(itensor);
(%o1)      /share/tensor/itensor.lisp
(%i2) eqn:ishow(t([i,j],[k])=f([],[l,m])*g([l,m],[i])*a([i],[m],j)
      *b([i],[l,k]))$

(%t2)
           k      m      l k
      t      = f a      b      g
      i j      ,j i      l m

(%i3) ic_convert(eqn);
(%o3) for i thru dim do (for j thru dim do (
      for k thru dim do
      t      : f sum(sum(diff(a , ct_coords ) b
      i, j, k      m      j      i, l, k

      g      , l, 1, dim), m, 1, dim)))
      l, m
(%i4) imetric(g);
(%o4)
done
(%i5) metricconvert:true;
(%o5)
true
(%i6) ic_convert(eqn);
(%o6) for i thru dim do (for j thru dim do (
      for k thru dim do
      t      : f sum(sum(diff(a , ct_coords ) b
      i, j, k      m      j      i, l, k

      lg      , l, 1, dim), m, 1, dim)))
      l, m
```

25.2.10 Reserved words

The following Maxima words are used by the `itensor` package internally and should not be redefined:

Keyword	Comments

<code>indices2()</code>	Internal version of <code>indices()</code>
<code>conti</code>	Lists contravariant indices
<code>covi</code>	Lists covariant indices of a indexed object
<code>deri</code>	Lists derivative indices of an indexed object
<code>name</code>	Returns the name of an indexed object
<code>concan</code>	
<code>irpmon</code>	
<code>lc0</code>	
<code>_lc2kdt0</code>	
<code>_lcprod</code>	
<code>_extlc</code>	

26 ctensor

26.1 Introduction to ctensor

`ctensor` is a component tensor manipulation package. To use the `ctensor` package, type `load(ctensor)`. To begin an interactive session with `ctensor`, type `csetup()`. You are first asked to specify the dimension of the manifold. If the dimension is 2, 3 or 4 then the list of coordinates defaults to `[x,y]`, `[x,y,z]` or `[x,y,z,t]` respectively. These names may be changed by assigning a new list of coordinates to the variable `ct_coords` (described below) and the user is queried about this. Care must be taken to avoid the coordinate names conflicting with other object definitions.

Next, the user enters the metric either directly or from a file by specifying its ordinal position. The metric is stored in the matrix `lg`. Finally, the metric inverse is computed and stored in the matrix `ug`. One has the option of carrying out all calculations in a power series.

A sample protocol is begun below for the static, spherically symmetric metric (standard coordinates) which will be applied to the problem of deriving Einstein's vacuum equations (which lead to the Schwarzschild solution) as an example. Many of the functions in `ctensor` will be displayed for the standard metric as examples.

```
(%i1) load(ctensor);
(%o1)      /share/tensor/ctensor.mac
(%i2) csetup();
Enter the dimension of the coordinate system:
4;
Do you wish to change the coordinate names?
n;
Do you want to
1. Enter a new metric?

2. Enter a metric from a file?

3. Approximate a metric with a Taylor series?
1;

Is the matrix  1. Diagonal  2. Symmetric  3. Antisymmetric  4. General
Answer 1, 2, 3 or 4
1;
Row 1 Column 1:
a;
Row 2 Column 2:
x^2;
Row 3 Column 3:
x^2*sin(y)^2;
Row 4 Column 4:
-d;

Matrix entered.
Enter functional dependencies with the DEPENDS function or 'N' if none
depends([a,d],x);
Do you wish to see the metric?
y;
```

```
[ a  0      0      0 ]
[                ]
[      2      ]
[ 0  x      0      0 ]
[                ]
```

```

[      2      2      ]
[ 0  0  x  sin (y)  0  ]
[      ]
[ 0  0      0      - d ]

(%o2)
done
(%i3) christof(mcs);

mcs      a
      x
1, 1, 1  = ---
      2 a

mcs      1
      = -
1, 2, 2  x

mcs      1
      = -
1, 3, 3  x

mcs      d
      x
1, 4, 4  = ---
      2 d

mcs      x
      = - -
2, 2, 1  a

mcs      cos(y)
      = -----
2, 3, 3  sin(y)

mcs      2
      x sin (y)
3, 3, 1  = - ----
      a

mcs      = - cos(y) sin(y)
3, 3, 2

mcs      d
      x
4, 4, 1  = ---
      2 a

(%o11)
done

```

26.2 Functions and Variables for ctensor

26.2.1 Initialization and setup

csetup ()

Function

A function in the **ctensor** (component tensor) package which initializes the package and allows the user to enter a metric interactively. See **ctensor** for more details.

cmetric (*dis*)

Function

cmetric ()

Function

A function in the **ctensor** (component tensor) package that computes the metric inverse and sets up the package for further calculations.

If **cframe_flag** is **false**, the function computes the inverse metric **ug** from the (user-defined) matrix **lg**. The metric determinant is also computed and stored in the variable **gdet**. Furthermore, the package determines if the metric is diagonal and sets the value of **diagmetric** accordingly. If the optional argument *dis* is present and not equal to **false**, the user is prompted to see the metric inverse.

If **cframe_flag** is **true**, the function expects that the values of **fri** (the inverse frame matrix) and **lfg** (the frame metric) are defined. From these, the frame matrix **fr** and the inverse frame metric **ufg** are computed.

ct_coordsys (*coordinate_system, extra_arg*)

Function

ct_coordsys (*coordinate_system*)

Function

Sets up a predefined coordinate system and metric. The argument *coordinate_system* can be one of the following symbols:

SYMBOL	Dim	Coordinates	Description/comments
cartesian2d	2	[x,y]	Cartesian 2D coordinate system
polar	2	[r,phi]	Polar coordinate system
elliptic	2	[u,v]	Elliptic coord. system
confocalelliptic	2	[u,v]	Confocal elliptic coordinates
bipolar	2	[u,v]	Bipolar coord. system
parabolic	2	[u,v]	Parabolic coord. system
cartesian3d	3	[x,y,z]	Cartesian 3D coordinate system
polarcylindrical	3	[r,theta,z]	Polar 2D with cylindrical z
ellipticcylindrical	3	[u,v,z]	Elliptic 2D with cylindrical z
confocalellipsoidal	3	[u,v,w]	Confocal ellipsoidal
bipolarcylindrical	3	[u,v,z]	Bipolar 2D with cylindrical z
paraboliccylindrical	3	[u,v,z]	Parabolic 2D with cylindrical z
paraboloidal	3	[u,v,phi]	Paraboloidal coords.
conical	3	[u,v,w]	Conical coordinates
toroidal	3	[u,v,phi]	Toroidal coordinates
spherical	3	[r,theta,phi]	Spherical coord. system
oblatespheroidal	3	[u,v,phi]	Oblate spheroidal coordinates
oblatespheroidalsqrt	3	[u,v,phi]	
prolatespheroidal	3	[u,v,phi]	Prolate spheroidal coordinates
prolatespheroidalsqrt	3	[u,v,phi]	
ellipsoidal	3	[r,theta,phi]	Ellipsoidal coordinates
cartesian4d	4	[x,y,z,t]	Cartesian 4D coordinate system
spherical4d	4	[r,theta,eta,phi]	Spherical 4D coordinate system
exterior schwarzschild	4	[t,r,theta,phi]	Schwarzschild metric
interior schwarzschild	4	[t,z,u,v]	Interior Schwarzschild metric

```
kerr_newman      4  [t,r,theta,phi]  Charged axially
                                   symmetric metric
```

`coordinate_system` can also be a list of transformation functions, followed by a list containing the coordinate variables. For instance, you can specify a spherical metric as follows:

```
(%i1) load(ctensor);
(%o1)      /share/tensor/ctensor.mac
(%i2) ct_coordsys([r*cos(theta)*cos(phi),r*cos(theta)*sin(phi),
r*sin(theta),[r,theta,phi]]);
(%o2)                                     done
(%i3) lg:trigsimp(lg);
                                     [ 1  0      0      ]
                                     [      ]
                                     [      2      ]
(%o3)                                     [ 0  r      0      ]
                                     [      ]
                                     [      2  2      ]
                                     [ 0  0  r  cos(theta) ]

(%i4) ct_coords;
(%o4)                                     [r, theta, phi]
(%i5) dim;
(%o5)                                     3
```

Transformation functions can also be used when `cframe_flag` is true:

```
(%i1) load(ctensor);
(%o1)      /share/tensor/ctensor.mac
(%i2) cframe_flag:true;
(%o2)                                     true
(%i3) ct_coordsys([r*cos(theta)*cos(phi),r*cos(theta)*sin(phi),
r*sin(theta),[r,theta,phi]]);
(%o3)                                     done
(%i4) fri;
(%o4)
[cos(phi)cos(theta) -cos(phi) r sin(theta) -sin(phi) r cos(theta)]
[      ]
[sin(phi)cos(theta) -sin(phi) r sin(theta)  cos(phi) r cos(theta)]
[      ]
[   sin(theta)           r cos(theta)           0           ]

(%i5) cmetric();
(%o5)                                     false
(%i6) lg:trigsimp(lg);
                                     [ 1  0      0      ]
                                     [      ]
                                     [      2      ]
(%o6)                                     [ 0  r      0      ]
                                     [      ]
                                     [      2  2      ]
                                     [ 0  0  r  cos(theta) ]
```

The optional argument *extra_arg* can be any one of the following:

`cylindrical` tells `ct_coordsys` to attach an additional cylindrical coordinate.

`minkowski` tells `ct_coordsys` to attach an additional coordinate with negative metric signature.

all tells `ct_coordsys` to call `cmetric` and `christof(false)` after setting up the metric. If the global variable `verbose` is set to `true`, `ct_coordsys` displays the values of `dim`, `ct_coords`, and either `lg` or `lfg` and `fri`, depending on the value of `cframe_flag`.

init_ctensor ()

Function

Initializes the `ctensor` package.

The `init_ctensor` function reinitializes the `ctensor` package. It removes all arrays and matrices used by `ctensor`, resets all flags, resets `dim` to 4, and resets the frame metric to the Lorentz-frame.

26.2.2 The tensors of curved space

The main purpose of the `ctensor` package is to compute the tensors of curved space(time), most notably the tensors used in general relativity.

When a metric base is used, `ctensor` can compute the following tensors:

```
lg -- ug
 |   \
lcs -- mcs -- ric -- uric
      |       \    \
      |         tracer - ein -- lein
      |         /
      |        riem -- lriem -- weyl
              |
             uriem
```

`ctensor` can also work using moving frames. When `cframe_flag` is set to `true`, the following tensors can be calculated:

```

lfg -- ufg
  \
fri -- fr -- lcs -- mcs -- lriem -- ric -- uric
    \                | \      \      \
      lg -- ug        |  weyl  tracer - ein -- lein
                      ||
                      | riem
                      |
                      \uriem

```

christof (*dis*)

Function

A function in the `ctensor` (component tensor) package. It computes the Christoffel symbols of both kinds. The argument `dis` determines which results are to be immediately displayed. The Christoffel symbols of the first and second kinds are stored in the arrays `lcs[i,j,k]` and `mcs[i,j,k]` respectively and defined to be symmetric in the first two indices. If the argument to `christof` is `lcs` or `mcs` then the unique non-zero values of `lcs[i,j,k]` or `mcs[i,j,k]`, respectively, will be displayed. If the argument is `all` then the unique non-zero values of `lcs[i,j,k]` and `mcs[i,j,k]` will be displayed. If the argument is `false` then the display of the elements will not occur. The array elements `mcs[i,j,k]` are defined in such a manner that the final index is contravariant.

ricci (*dis*)

Function

A function in the `ctensor` (component tensor) package. `ricci` computes the covariant (symmetric) components `ric[i,j]` of the Ricci tensor. If the argument `dis` is `true`, then the non-zero components are displayed.

uricci (*dis*) Function

This function first computes the covariant components `ric[i,j]` of the Ricci tensor. Then the mixed Ricci tensor is computed using the contravariant metric tensor. If the value of the argument *dis* is `true`, then these mixed components, `uric[i,j]` (the index *i* is covariant and the index *j* is contravariant), will be displayed directly. Otherwise, `ricci(false)` will simply compute the entries of the array `uric[i,j]` without displaying the results.

scurvature () Function

Returns the scalar curvature (obtained by contracting the Ricci tensor) of the Riemannian manifold with the given metric.

einstein (*dis*) Function

A function in the `ctensor` (component tensor) package. `einstein` computes the mixed Einstein tensor after the Christoffel symbols and Ricci tensor have been obtained (with the functions `christof` and `ricci`). If the argument *dis* is `true`, then the non-zero values of the mixed Einstein tensor `ein[i,j]` will be displayed where *j* is the contravariant index. The variable `rateinstein` will cause the rational simplification on these components. If `ratfac` is `true` then the components will also be factored.

leinstein (*dis*) Function

Covariant Einstein-tensor. `leinstein` stores the values of the covariant Einstein tensor in the array `lein`. The covariant Einstein-tensor is computed from the mixed Einstein tensor `ein` by multiplying it with the metric tensor. If the argument *dis* is `true`, then the non-zero values of the covariant Einstein tensor are displayed.

riemann (*dis*) Function

A function in the `ctensor` (component tensor) package. `riemann` computes the Riemann curvature tensor from the given metric and the corresponding Christoffel symbols. The following index conventions are used:

$$R[i,j,k,l] = R \begin{matrix} l \\ ijk \end{matrix} = \begin{matrix} _l \\ ij,k \end{matrix} - \begin{matrix} _l \\ ik,j \end{matrix} + \begin{matrix} _l \\ mk \end{matrix} \begin{matrix} _m \\ ij \end{matrix} - \begin{matrix} _l \\ mj \end{matrix} \begin{matrix} _m \\ ik \end{matrix}$$

This notation is consistent with the notation used by the `itensor` package and its `icurvature` function. If the optional argument *dis* is `true`, the unique non-zero components `riem[i,j,k,l]` will be displayed. As with the Einstein tensor, various switches set by the user control the simplification of the components of the Riemann tensor. If `ratriemann` is `true`, then rational simplification will be done. If `ratfac` is `true` then each of the components will also be factored.

If the variable `cframe_flag` is `false`, the Riemann tensor is computed directly from the Christoffel-symbols. If `cframe_flag` is `true`, the covariant Riemann-tensor is computed first from the frame field coefficients.

lriemann (*dis*) Function

Covariant Riemann-tensor (`lriem[]`).

Computes the covariant Riemann-tensor as the array `lriem`. If the argument *dis* is `true`, unique non-zero values are displayed.

If the variable `cframe_flag` is `true`, the covariant Riemann tensor is computed directly from the frame field coefficients. Otherwise, the (3,1) Riemann tensor is computed first.

For information on index ordering, see `riemann`.

uriemann (*dis*) Function

Computes the contravariant components of the Riemann curvature tensor as array elements `uriem[i,j,k,l]`. These are displayed if *dis* is `true`.

rinvariant () Function

Forms the Kretschmann-invariant (**kinvariant**) obtained by contracting the tensors

`lriem[i,j,k,l]*urien[i,j,k,l]`.

This object is not automatically simplified since it can be very large.

weyl (*dis*) Function

Computes the Weyl conformal tensor. If the argument *dis* is **true**, the non-zero components `weyl[i,j,k,l]` will be displayed to the user. Otherwise, these components will simply be computed and stored. If the switch **ratweyl** is set to **true**, then the components will be rationally simplified; if **ratfac** is **true** then the results will be factored as well.

26.2.3 Taylor series expansion

The **ctensor** package has the ability to truncate results by assuming that they are Taylor-series approximations. This behavior is controlled by the **ctayswitch** variable; when set to true, **ctensor** makes use internally of the function **ctaylor** when simplifying results.

The **ctaylor** function is invoked by the following **ctensor** functions:

Function	Comments

<code>christof()</code>	For mcs only
<code>ricci()</code>	
<code>uricci()</code>	
<code>einstein()</code>	
<code>riemann()</code>	
<code>weyl()</code>	
<code>checkdiv()</code>	

ctaylor () Function

The **ctaylor** function truncates its argument by converting it to a Taylor-series using **taylor**, and then calling **ratdisrep**. This has the combined effect of dropping terms higher order in the expansion variable **ctayvar**. The order of terms that should be dropped is defined by **ctaypov**; the point around which the series expansion is carried out is specified in **ctaypt**.

As an example, consider a simple metric that is a perturbation of the Minkowski metric. Without further restrictions, even a diagonal metric produces expressions for the Einstein tensor that are far too complex:

```
(%i1) load(ctensor);
(%o1)      /share/tensor/ctensor.mac
(%i2) ratfac:true;
(%o2)                                     true
(%i3) derivabbrev:true;
(%o3)                                     true
(%i4) ct_coords:[t,r,theta,phi];
(%o4)      [t, r, theta, phi]
(%i5) lg:matrix([-1,0,0,0],[0,1,0,0],[0,0,r^2,0],
               [0,0,0,r^2*sin(theta)^2]);
               [ - 1  0  0          0          ]
               [                                     ]
               [  0   1  0          0          ]
               [                                     ]
               [                                     ]
(%o5)      [                                     ]
               [          2          ]
               [  0   0   r          0          ]
               [                                     ]
               [                                     ]
               [          2    2          ]
```

```

[ 0 0 0 r sin(theta) ]
(%i6) h:matrix([h11,0,0,0],[0,h22,0,0],[0,0,h33,0],[0,0,0,h44]);
[ h11 0 0 0 ]
[      ]
[ 0 h22 0 0 ]
(%o6) [      ]
[ 0 0 h33 0 ]
[      ]
[ 0 0 0 h44 ]

(%i7) depends(l,r);
(%o7) [l(r)]
(%i8) lg:lg+l*h;
[ h11 l - 1 0 0 0 ]
[      ]
[ 0 h22 l + 1 0 0 ]
[      ]
(%o8) [      ]
[ 0 0 r^2 + h33 l 0 ]
[      ]
[      ]
[ 0 0 0 r^2 sin^2(theta) + h44 l ]

(%i9) cmetric(false);
(%o9) done
(%i10) einstein(false);
(%o10) done
(%i11) ntermst(ein);
[[1, 1], 62]
[[1, 2], 0]
[[1, 3], 0]
[[1, 4], 0]
[[2, 1], 0]
[[2, 2], 24]
[[2, 3], 0]
[[2, 4], 0]
[[3, 1], 0]
[[3, 2], 0]
[[3, 3], 46]
[[3, 4], 0]
[[4, 1], 0]
[[4, 2], 0]
[[4, 3], 0]
[[4, 4], 46]
(%o12) done

```

However, if we recompute this example as an approximation that is linear in the variable l , we get much simpler expressions:

```

(%i14) ctayswitch:true;
(%o14) true
(%i15) ctayvar:l;
(%o15) l
(%i16) ctaypov:1;
(%o16) 1
(%i17) ctaypt:0;
(%o17) 0
(%i18) christof(false);

```



```

(%o18)                                     done
(%i19) ricci(false);
(%o19)                                     done
(%i20) einstein(false);
(%o20)                                     done
(%i21) ntermst(ein);
[[1, 1], 6]
[[1, 2], 0]
[[1, 3], 0]
[[1, 4], 0]
[[2, 1], 0]
[[2, 2], 13]
[[2, 3], 2]
[[2, 4], 0]
[[3, 1], 0]
[[3, 2], 2]
[[3, 3], 9]
[[3, 4], 0]
[[4, 1], 0]
[[4, 2], 0]
[[4, 3], 0]
[[4, 4], 9]
(%o21)                                     done
(%i22) ratsimp(ein[1,1]);
(%o22) - (((h11 h22 - h11 ) (1 ) ) r - 2 h33 l r ) sin (theta)
          2      2 4      2      2
          r      r      r r
          - 2 h44 l r - h33 h44 (1 ) )/(4 r sin (theta))
          2      2      4      2
          r r      r      r

```

This capability can be useful, for instance, when working in the weak field limit far from a gravitational source.

26.2.4 Frame fields

When the variable `cframe_flag` is set to true, the `ctensor` package performs its calculations using a moving frame.

frame_bracket (*fr*, *fri*, *diagframe*)

Function

The frame bracket (`fb[]`).

Computes the frame bracket according to the following definition:

$$fb_{ab}^c = (ifri_{d,e}^c - ifri_{e,d}^c) ifr_a^d ifr_b^e$$

26.2.5 Algebraic classification

A new feature (as of November, 2004) of `ctensor` is its ability to compute the Petrov classification of a 4-dimensional spacetime metric. For a demonstration of this capability, see the file `share/tensor/petrov.dem`.

nptetrad ()

Function

Computes a Newman-Penrose null tetrad (**np**) and its raised-index counterpart (**npⁱ**). See **petrov** for an example.

The null tetrad is constructed on the assumption that a four-dimensional orthonormal frame metric with metric signature $(-,+,+,+)$ is being used. The components of the null tetrad are related to the inverse frame matrix as follows:

$$\begin{aligned} np_1 &= (f_{r1} + f_{t1}) / \sqrt{2} \\ np_2 &= (f_{r1} - f_{t1}) / \sqrt{2} \\ np_3 &= (f_{r3} + i f_{t3}) / \sqrt{2} \\ np_4 &= (f_{r3} - i f_{t3}) / \sqrt{2} \end{aligned}$$

psi (dis)

Function

Computes the five Newman-Penrose coefficients **psi[0]...psi[4]**. If **dis** is set to **true**, the coefficients are displayed. See **petrov** for an example.

These coefficients are computed from the Weyl-tensor in a coordinate base. If a frame base is used, the Weyl-tensor is first converted to a coordinate base, which can be a computationally expensive procedure. For this reason, in some cases it may be more advantageous to use a coordinate base in the first place before the Weyl tensor is computed. Note however, that constructing a Newman-Penrose null tetrad requires a frame base. Therefore, a meaningful computation sequence may begin with a frame base, which is then used to compute **lg** (computed automatically by **cmetric** and then **ug**). At this point, you can switch back to a coordinate base by setting **cframe_flag** to false before beginning to compute the Christoffel symbols. Changing to a frame base at a later stage could yield inconsistent results, as you may end up with a mixed bag of tensors, some computed in a frame base, some in a coordinate base, with no means to distinguish between the two.

petrov ()

Function

Computes the Petrov classification of the metric characterized by **psi[0]...psi[4]**.

For example, the following demonstrates how to obtain the Petrov-classification of the Kerr metric:

```
(%i1) load(ctensor);
(%o1) /share/tensor/ctensor.mac
(%i2) (cframe_flag:true,gcd:spmod,ctrgsimp:true,ratfac:true);
(%o2) true
(%i3) ct_coordsys(exterior schwarzschild,all);
(%o3) done
(%i4) ug:invert(lg)$
(%i5) weyl(false);
(%o5) done
(%i6) nptetrad(true);
(%t6) np =
```

$$\begin{bmatrix} \sqrt{r-2m} & \sqrt{r} & 0 & 0 \\ -\frac{\sqrt{2}\sqrt{r}}{\sqrt{2}\sqrt{r-2m}} & \frac{\sqrt{2}\sqrt{r-2m}}{\sqrt{2}\sqrt{r}} & 0 & 0 \\ \sqrt{r-2m} & \sqrt{r} & 0 & 0 \\ \sqrt{r-2m} & \sqrt{r} & 0 & 0 \end{bmatrix}$$

```

[----- - ----- 0 0 ]
[sqrt(2) sqrt(r) sqrt(2) sqrt(r - 2 m) ]
[ ]
[ r %i r sin(theta) ]
[ 0 0 ----- ]
[ sqrt(2) sqrt(2) ]
[ ]
[ r %i r sin(theta) ]
[ 0 0 ----- ]
[ sqrt(2) sqrt(2) ]

(%t7) np1 = matrix([- sqrt(r) sqrt(r - 2 m)
                    sqrt(2) sqrt(r - 2 m) sqrt(2) sqrt(r), 0, 0],

                    sqrt(r) sqrt(r - 2 m)
[- -----, - -----, 0, 0],
  sqrt(2) sqrt(r - 2 m) sqrt(2) sqrt(r)

1 %i
[0, 0, -----, -----],
  sqrt(2) r sqrt(2) r sin(theta)

1 %i
[0, 0, -----, - -----])
  sqrt(2) r sqrt(2) r sin(theta)

(%o7) done
(%i7) psi(true);
(%t8) psi = 0
      0

(%t9) psi = 0
      1

(%t10) psi = --
        2 3
        r

(%t11) psi = 0
        3

(%t12) psi = 0
        4
(%o12) done
(%i12) petrov();
(%o12) D

```

The Petrov classification function is based on the algorithm published in "Classifying geometries in general relativity: III Classification in practice" by Pollney, Skea, and d'Inverno, *Class. Quant. Grav.* 17 2885-2902 (2000). Except for some simple test cases, the implementation is untested as of December 19, 2004, and is likely to contain errors.

26.2.6 Torsion and nonmetricity

`ctensor` has the ability to compute and include torsion and nonmetricity coefficients in the connection coefficients.

The torsion coefficients are calculated from a user-supplied tensor `tr`, which should be a rank (2,1) tensor. From this, the torsion coefficients `kt` are computed according to the following formulae:

$$kt_{ijk} = \frac{-g_{im} tr_{kj}^m - g_{jm} tr_{ki}^m - tr_{ij}^m g_{km}}{2}$$

$$kt_{ij}^k = g_{km} kt_{ijm}$$

Note that only the mixed-index tensor is calculated and stored in the array `kt`.

The nonmetricity coefficients are calculated from the user-supplied nonmetricity vector `nm`. From this, the nonmetricity coefficients `nmc` are computed as follows:

$$nmc_{ij}^k = \frac{-nm_i^k D_j - D_i^k nm_j + g_{nm}^k nm_m g_{ij}}{2}$$

where `D` stands for the Kronecker-delta.

When `ctorsion_flag` is set to `true`, the values of `kt` are subtracted from the mixed-indexed connection coefficients computed by `christof` and stored in `mcs`. Similarly, if `cnonmet_flag` is set to `true`, the values of `nmc` are subtracted from the mixed-indexed connection coefficients.

If necessary, `christof` calls the functions `contortion` and `nonmetricity` in order to compute `kt` and `nm`.

contortion (*tr*) Function
Computes the (2,1) contortion coefficients from the torsion tensor *tr*.

nonmetricity (*nm*) Function
Computes the (2,1) nonmetricity coefficients from the nonmetricity vector *nm*.

26.2.7 Miscellaneous features

ctransform (*M*) Function
A function in the `ctensor` (component tensor) package which will perform a coordinate transformation upon an arbitrary square symmetric matrix *M*. The user must input the functions which define the transformation. (Formerly called `transform`.)

findde (*A*, *n*) Function
returns a list of the unique differential equations (expressions) corresponding to the elements of the *n* dimensional square array *A*. Presently, *n* may be 2 or 3. `deindex` is a global list containing the indices of *A* corresponding to these unique differential equations. For the Einstein tensor (`ein`), which is a two dimensional array, if computed for the metric in the example below, `findde` gives the following independent differential equations:

```

(%i1) load(ctensor);
(%o1) /share/tensor/ctensor.mac
(%i2) derivabbrev:true;
(%o2) true
(%i3) dim:4;
(%o3) 4
(%i4) lg:matrix([a, 0, 0, 0], [ 0, x^2, 0, 0],
                [0, 0, x^2*sin(y)^2, 0], [0,0,0,-d]);
                [ a  0      0      0 ]
                [      ]
                [      2      ]
                [ 0  x      0      0 ]
(%o4)          [      ]
                [      2      2      ]
                [ 0  0  x  sin (y)  0 ]
                [      ]
                [ 0  0      0      - d ]

(%i5) depends([a,d],x);
(%o5) [a(x), d(x)]
(%i6) ct_coords:[x,y,z,t];
(%o6) [x, y, z, t]
(%i7) cmetric();
(%o7) done
(%i8) einstein(false);
(%o8) done
(%i9) findde(ein,2);
(%o9) [d x - a d + d, 2 a d d x - a (d ) x - a d d x
      x          x x          x          x x
      + 2 a d d - 2 a d , a x + a - a]
      x          x          x

(%i10) deindex;
(%o10) [[1, 1], [2, 2], [4, 4]]

```

cograd ()

Function

Computes the covariant gradient of a scalar function allowing the user to choose the corresponding vector name as the example under **contragrad** illustrates.

contragrad ()

Function

Computes the contravariant gradient of a scalar function allowing the user to choose the corresponding vector name as the example below for the Schwarzschild metric illustrates:

```

(%i1) load(ctensor);
(%o1) /share/tensor/ctensor.mac
(%i2) derivabbrev:true;
(%o2) true
(%i3) ct_coordsys(exterior schwarzschild,all);
(%o3) done
(%i4) depends(f,r);
(%o4) [f(r)]
(%i5) cograd(f,g1);
(%o5) done
(%i6) listarray(g1);
(%o6) [0, f , 0, 0]
      r
(%i7) contragrad(f,g2);

```

```
(%o7) done
(%i8) listarray(g2);

      f  r - 2 f  m
      r      r
(%o8) [0, -----, 0, 0]
      r
```

dscalar () Function
 computes the tensor d'Alembertian of the scalar function once dependencies have been declared upon the function. For example:

```
(%i1) load(ctensor);
(%o1) /share/tensor/ctensor.mac
(%i2) derivabbrev:true;
(%o2) true
(%i3) ct_coordsys(exterior Schwarzschild,all);
(%o3) done
(%i4) depends(p,r);
(%o4) [p(r)]
(%i5) factor(dscalar(p));

      2
      p  r - 2 m p  r + 2 p  r - 2 m p
      r r      r r      r      r
(%o5) -----
      2
      r
```

checkdiv () Function
 computes the covariant divergence of the mixed second rank tensor (whose first index must be covariant) by printing the corresponding n components of the vector field (the divergence) where $n = \text{dim}$. If the argument to the function is g then the divergence of the Einstein tensor will be formed and must be zero. In addition, the divergence (vector) is given the array name `div`.

cgeodesic (dis) Function
 A function in the `ctensor` (component tensor) package. `cgeodesic` computes the geodesic equations of motion for a given metric. They are stored in the array `geod[i]`. If the argument `dis` is `true` then these equations are displayed.

bdvac (f) Function
 generates the covariant components of the vacuum field equations of the Brans- Dicke gravitational theory. The scalar field is specified by the argument f , which should be a (quoted) function name with functional dependencies, e.g., '`p(x)`'.
 The components of the second rank covariant field tensor are represented by the array `bd`.

invariant1 () Function
 generates the mixed Euler- Lagrange tensor (field equations) for the invariant density of R^2 . The field equations are the components of an array named `inv1`.

invariant2 () Function
 *** NOT YET IMPLEMENTED ***
 generates the mixed Euler- Lagrange tensor (field equations) for the invariant density of `ric[i,j]*uriem[i,j]`. The field equations are the components of an array named `inv2`.

bimetric () Function
 *** NOT YET IMPLEMENTED ***
 generates the field equations of Rosen's bimetric theory. The field equations are the components of an array named `rosen`.

26.2.8 Utility functions

diagmatrixp (*M*)

Function

Returns **true** if *M* is a diagonal matrix or (2D) array.

symmetricp (*M*)

Function

Returns **true** if *M* is a symmetric matrix or (2D) array.

ntermst (*f*)

Function

gives the user a quick picture of the "size" of the doubly subscripted tensor (array) *f*. It prints two element lists where the second element corresponds to NTERMS of the components specified by the first elements. In this way, it is possible to quickly find the non-zero expressions and attempt simplification.

cdisplay (*ten*)

Function

displays all the elements of the tensor *ten*, as represented by a multidimensional array. Tensors of rank 0 and 1, as well as other types of variables, are displayed as with **ldisplay**. Tensors of rank 2 are displayed as 2-dimensional matrices, while tensors of higher rank are displayed as a list of 2-dimensional matrices. For instance, the Riemann-tensor of the Schwarzschild metric can be viewed as:

```
(%i1) load(ctensor);
(%o1)      /share/tensor/ctensor.mac
(%i2) ratfac:true;
(%o2)                                     true
(%i3) ct_coordsys(exteriorschwarzschild,all);
(%o3)                                     done
(%i4) riemann(false);
(%o4)                                     done
(%i5) cdisplay(riem);
```

$$\text{riem}_{1,1} = \begin{bmatrix} 0 & 0 & 0 & 0 \\ 0 & -\frac{3m(r-2m)}{r^4} + \frac{m}{r^3} - \frac{2m}{r^4} & 0 & 0 \\ 0 & 0 & \frac{m(r-2m)}{r^4} & 0 \\ 0 & 0 & 0 & -\frac{m(r-2m)}{r^4} \end{bmatrix}$$

$$\text{riem}_{1,2} = \begin{bmatrix} 0 & \frac{2m(r-2m)}{r^4} & 0 & 0 \\ 0 & 0 & 0 & 0 \\ 0 & 0 & 0 & 0 \\ 0 & 0 & 0 & 0 \end{bmatrix}$$

$$\text{riem}_{2,3} = \begin{bmatrix} & 2 & & \\ & r & (r - 2m) & \\ & & & \\ [0 & 0 & 0 & 0] \\ & & & \\ [0 & 0 & 0 & 0] \end{bmatrix}$$

$$\text{riem}_{2,4} = \begin{bmatrix} [0 & 0 & 0 & 0] \\ [& & &] \\ [& m & &] \\ [0 & 0 & 0 & \frac{m}{r}] \\ & 2 & & \\ & r & (r - 2m) & \\ & & & \\ [0 & 0 & 0 & 0] \\ & & & \\ [0 & 0 & 0 & 0] \end{bmatrix}$$

$$\text{riem}_{3,1} = \begin{bmatrix} [0 & 0 & 0 & 0] \\ [& & &] \\ [0 & 0 & 0 & 0] \\ [& & &] \\ [m & & &] \\ [- & 0 & 0 & 0] \\ [r & & &] \\ [& & &] \\ [0 & 0 & 0 & 0] \end{bmatrix}$$

$$\text{riem}_{3,2} = \begin{bmatrix} [0 & 0 & 0 & 0] \\ [& & &] \\ [0 & 0 & 0 & 0] \\ [& & &] \\ [m & & &] \\ [0 & - & 0 & 0] \\ [r & & &] \\ [& & &] \\ [0 & 0 & 0 & 0] \end{bmatrix}$$

$$\text{riem}_{3,3} = \begin{bmatrix} [m & & &] \\ [- & - & 0 & 0] \\ [r & & &] \\ [& & &] \\ [m & & &] \\ [0 & - & 0 & 0] \\ [r & & &] \\ [& & &] \\ [0 & 0 & 0 & 0] \\ [& & &] \\ [0 & 0 & 0 & \frac{2m-r}{r} + 1] \\ [& & &] \end{bmatrix}$$

$$\begin{bmatrix} [0 & 0 & 0 & 0] \\ [& & &] \\ [0 & 0 & 0 & 0] \\ [& & &] \end{bmatrix}$$

$$\begin{aligned}
 \text{riem}_{3,4} &= \begin{bmatrix} 2m \\ 0 & 0 & 0 & -\frac{1}{r} \\ 0 & 0 & 0 & 0 \end{bmatrix} \\
 \text{riem}_{4,1} &= \begin{bmatrix} 0 & 0 & 0 & 0 \\ 0 & 0 & 0 & 0 \\ 0 & 0 & 0 & 0 \\ m \sin^2(\theta) & -\frac{m \sin(\theta)}{r} & 0 & 0 \end{bmatrix} \\
 \text{riem}_{4,2} &= \begin{bmatrix} 0 & 0 & 0 & 0 \\ 0 & 0 & 0 & 0 \\ 0 & 0 & 0 & 0 \\ 0 & \frac{m \sin^2(\theta)}{r} & 0 & 0 \end{bmatrix} \\
 \text{riem}_{4,3} &= \begin{bmatrix} 0 & 0 & 0 & 0 \\ 0 & 0 & 0 & 0 \\ 0 & 0 & 0 & 0 \\ 0 & 0 & -\frac{2m \sin(\theta)}{r} & 0 \end{bmatrix} \\
 \text{riem}_{4,4} &= \begin{bmatrix} m \sin^2(\theta) & -\frac{m \sin(\theta)}{r} & 0 & 0 \\ 0 & -\frac{m \sin^2(\theta)}{r} & 0 & 0 \\ 0 & 0 & \frac{2m \sin^2(\theta)}{r} & 0 \\ 0 & 0 & 0 & 0 \end{bmatrix}
 \end{aligned}$$

(%o5)

done

deleten (L, n)

Function

Returns a new list consisting of L with the n 'th element deleted.

26.2.9 Variables used by ctensor

dim

Option variable

Default value: 4

An option in the **ctensor** (component tensor) package. **dim** is the dimension of the manifold with the default 4. The command **dim: n** will reset the dimension to any other value **n**.

diagmetric

Option variable

Default value: **false**

An option in the **ctensor** (component tensor) package. If **diagmetric** is **true** special routines compute all geometrical objects (which contain the metric tensor explicitly) by taking into consideration the diagonality of the metric. Reduced run times will, of course, result. Note: this option is set automatically by **csetup** if a diagonal metric is specified.

ctrgsimp

Option variable

Causes trigonometric simplifications to be used when tensors are computed. Presently, **ctrgsimp** affects only computations involving a moving frame.

cframe_flag

Option variable

Causes computations to be performed relative to a moving frame as opposed to a holonomic metric. The frame is defined by the inverse frame array **fri** and the frame metric **lfg**. For computations using a Cartesian frame, **lfg** should be the unit matrix of the appropriate dimension; for computations in a Lorentz frame, **lfg** should have the appropriate signature.

ctorsion_flag

Option variable

Causes the contortion tensor to be included in the computation of the connection coefficients. The contortion tensor itself is computed by **contortion** from the user-supplied tensor **tr**.

cnonmet_flag

Option variable

Causes the nonmetricity coefficients to be included in the computation of the connection coefficients. The nonmetricity coefficients are computed from the user-supplied nonmetricity vector **nm** by the function **nonmetricity**.

ctayswitch

Option variable

If set to **true**, causes some **ctensor** computations to be carried out using Taylor-series expansions. Presently, **christof**, **ricci**, **uricci**, **einstein**, and **weyl** take into account this setting.

ctayvar

Option variable

Variable used for Taylor-series expansion if **ctayswitch** is set to **true**.

ctaypov

Option variable

Maximum power used in Taylor-series expansion when **ctayswitch** is set to **true**.

ctaypt

Option variable

Point around which Taylor-series expansion is carried out when **ctayswitch** is set to **true**.

gdet	System variable
The determinant of the metric tensor <code>lg</code> . Computed by <code>cmetric</code> when <code>cframe_flag</code> is set to <code>false</code> .	
ratchristof	Option variable
Causes rational simplification to be applied by <code>christof</code> .	
rateinstein	Option variable
Default value: <code>true</code> If <code>true</code> rational simplification will be performed on the non-zero components of Einstein tensors; if <code>ratfac</code> is <code>true</code> then the components will also be factored.	
ratriemann	Option variable
Default value: <code>true</code> One of the switches which controls simplification of Riemann tensors; if <code>true</code> , then rational simplification will be done; if <code>ratfac</code> is <code>true</code> then each of the components will also be factored.	
ratweyl	Option variable
Default value: <code>true</code> If <code>true</code> , this switch causes the <code>weyl</code> function to apply rational simplification to the values of the Weyl tensor. If <code>ratfac</code> is <code>true</code> , then the components will also be factored.	
lfg	Variable
The covariant frame metric. By default, it is initialized to the 4-dimensional Lorentz frame with signature $(+,+,+,-)$. Used when <code>cframe_flag</code> is <code>true</code> .	
ufg	Variable
The inverse frame metric. Computed from <code>lfg</code> when <code>cmetric</code> is called while <code>cframe_flag</code> is set to <code>true</code> .	
riem	Variable
The (3,1) Riemann tensor. Computed when the function <code>riemann</code> is invoked. For information about index ordering, see the description of <code>riemann</code> . If <code>cframe_flag</code> is <code>true</code> , <code>riem</code> is computed from the covariant Riemann-tensor <code>lriem</code> .	
lriem	Variable
The covariant Riemann tensor. Computed by <code>lriemann</code> .	
uriem	Variable
The contravariant Riemann tensor. Computed by <code>uriemann</code> .	
ric	Variable
The mixed Ricci-tensor. Computed by <code>ricci</code> .	
uric	Variable
The contravariant Ricci-tensor. Computed by <code>uricci</code> .	
lg	Variable
The metric tensor. This tensor must be specified (as a <code>dim</code> by <code>dim</code> matrix) before other computations can be performed.	
ug	Variable
The inverse of the metric tensor. Computed by <code>cmetric</code> .	

weyl	The Weyl tensor. Computed by <code>weyl</code> .	Variable
fb	Frame bracket coefficients, as computed by <code>frame_bracket</code> .	Variable
kinvariant	The Kretschmann invariant. Computed by <code>rinvariant</code> .	Variable
np	A Newman-Penrose null tetrad. Computed by <code>nptetrad</code> .	Variable
npi	The raised-index Newman-Penrose null tetrad. Computed by <code>nptetrad</code> . Defined as <code>ug.np</code> . The product <code>np.transpose(npi)</code> is constant: <pre>(%i39) trigsimp(np.transpose(npi)); [0 - 1 0 0] [] [- 1 0 0 0] [] [0 0 0 1] [] [0 0 1 0]</pre>	Variable
tr	User-supplied rank-3 tensor representing torsion. Used by <code>contortion</code> .	Variable
kt	The contortion tensor, computed from <code>tr</code> by <code>contortion</code> .	Variable
nm	User-supplied nonmetricity vector. Used by <code>nonmetricity</code> .	Variable
nmc	The nonmetricity coefficients, computed from <code>nm</code> by <code>nonmetricity</code> .	Variable
tensorkill	Variable indicating if the tensor package has been initialized. Set and used by <code>csetup</code> , reset by <code>init_ctensor</code> .	System variable
ct_coords	Default value: <code>[]</code> An option in the <code>ctensor</code> (component tensor) package. <code>ct_coords</code> contains a list of coordinates. While normally defined when the function <code>csetup</code> is called, one may redefine the coordinates with the assignment <code>ct_coords: [j1, j2, ..., jn]</code> where the <code>j</code> 's are the new coordinate names. See also <code>csetup</code> .	Option variable

26.2.10 Reserved names

The following names are used internally by the `ctensor` package and should not be redefined:

Name	Description
<code>_lg()</code>	Evaluates to <code>lfg</code> if frame metric used, <code>lg</code> otherwise
<code>_ug()</code>	Evaluates to <code>ufg</code> if frame metric used, <code>ug</code> otherwise
<code>cleanup()</code>	Removes items from the deindex list
<code>contract4()</code>	Used by <code>psi()</code>

<code>filemet()</code>	Used by <code>csetup()</code> when reading the metric from a file
<code>findde1()</code>	Used by <code>findde()</code>
<code>findde2()</code>	Used by <code>findde()</code>
<code>findde3()</code>	Used by <code>findde()</code>
<code>kdelt()</code>	Kronecker-delta (not generalized)
<code>newmet()</code>	Used by <code>csetup()</code> for setting up a metric interactively
<code>setflags()</code>	Used by <code>init_ctensor()</code>
<code>readvalue()</code>	
<code>resimp()</code>	
<code>sermet()</code>	Used by <code>csetup()</code> for entering a metric as Taylor-series
<code>txyzsum()</code>	
<code>tmetric()</code>	Frame metric, used by <code>cmetric()</code> when <code>cframe_flag:true</code>
<code>triemann()</code>	Riemann-tensor in frame base, used when <code>cframe_flag:true</code>
<code>tr Ricci()</code>	Ricci-tensor in frame base, used when <code>cframe_flag:true</code>
<code>trrc()</code>	Ricci rotation coefficients, used by <code>christof()</code>
<code>yesp()</code>	

26.2.11 Changes

In November, 2004, the `ctensor` package was extensively rewritten. Many functions and variables have been renamed in order to make the package compatible with the commercial version of Macsyma.

New Name	Old Name	Description

<code>ctaylor()</code>	<code>DLGTAYLOR()</code>	Taylor-series expansion of an expression
<code>lgeod[]</code>	<code>EM</code>	Geodesic equations
<code>ein[]</code>	<code>G[]</code>	Mixed Einstein-tensor
<code>ric[]</code>	<code>LR[]</code>	Mixed Ricci-tensor
<code>ricci()</code>	<code>LRICCOM()</code>	Compute the mixed Ricci-tensor
<code>ctaypov</code>	<code>MINP</code>	Maximum power in Taylor-series expansion
<code>cgeodesic()</code>	<code>MOTION</code>	Compute geodesic equations
<code>ct_coords</code>	<code>OMEGA</code>	Metric coordinates
<code>ctayvar</code>	<code>PARAM</code>	Taylor-series expansion variable
<code>lriem[]</code>	<code>R[]</code>	Covariant Riemann-tensor
<code>uriemann()</code>	<code>RAISERIEMANN()</code>	Compute the contravariant Riemann-tensor
<code>ratriemann</code>	<code>RATRIEMAN</code>	Rational simplif. of the Riemann-tensor
<code>uric[]</code>	<code>RICCI[]</code>	Contravariant Ricci-tensor
<code>ur Ricci()</code>	<code>RICCOM()</code>	Compute the contravariant Ricci-tensor
<code>cmetric()</code>	<code>SETMETRIC()</code>	Set up the metric
<code>ctaypt</code>	<code>TAYPT</code>	Point for Taylor-series expansion
<code>ctayswitch</code>	<code>TAYSWITCH</code>	Taylor-series setting switch
<code>csetup()</code>	<code>TSETUP()</code>	Start interactive setup session
<code>ctransform()</code>	<code>TTRANSFORM()</code>	Interactive coordinate transformation
<code>uriem[]</code>	<code>UR[]</code>	Contravariant Riemann-tensor
<code>weyl[]</code>	<code>W[]</code>	(3,1) Weyl-tensor

27 atensor

27.1 Introduction to atensor

atensor is an algebraic tensor manipulation package. To use **atensor**, type `load(atensor)`, followed by a call to the `init_atensor` function.

The essence of **atensor** is a set of simplification rules for the noncommutative (dot) product operator ("`.`"). **atensor** recognizes several algebra types; the corresponding simplification rules are put into effect when the `init_atensor` function is called.

The capabilities of **atensor** can be demonstrated by defining the algebra of quaternions as a Clifford-algebra $Cl(0,2)$ with two basis vectors. The three quaternionic imaginary units are then the two basis vectors and their product, i.e.:

$$\begin{array}{ccccc} i & = & v & & j & = & v & & k & = & v & & . & v \\ & & 1 & & 2 & & 1 & & 2 \end{array}$$

Although the **atensor** package has a built-in definition for the quaternion algebra, it is not used in this example, in which we endeavour to build the quaternion multiplication table as a matrix:

```
(%i1) load(atensor);
(%o1)      /share/tensor/atensor.mac
(%i2) init_atensor(clifford,0,0,2);
(%o2)
(%i3) atensimp(v[1].v[1]);
(%o3)
(%i4) atensimp((v[1].v[2]).(v[1].v[2]));
(%o4)
(%i5) q:zeromatrix(4,4);
(%o5)
[ 0  0  0  0 ]
[
[ 0  0  0  0 ]
[
[ 0  0  0  0 ]
[
[ 0  0  0  0 ]
[
[ 0  0  0  0 ]

(%i6) q[1,1]:1;
(%o6)
1
(%i7) for i thru adim do q[1,i+1]:q[i+1,1]:v[i];
(%o7)
done
(%i8) q[1,4]:q[4,1]:v[1].v[2];
(%o8)
v . v
1 2
(%i9) for i from 2 thru 4 do for j from 2 thru 4 do
q[i,j]:atensimp(q[i,1].q[1,j]);
(%o9)
done
(%i10) q;
(%o10)
[ 1      v      v      v . v ]
[      1      2      1 2 ]
[
[ v      - 1      v . v      - v ]
[ 1      1 2      2 ]
[
[ v      - v . v      - 1      v ]
[ 2      1 2      1 ]
[
[ v . v      v      - v      - 1 ]
[ 1 2      2      1 ]
```

`atensor` recognizes as base vectors indexed symbols, where the symbol is that stored in `asymbol` and the index runs between 1 and `adim`. For indexed symbols, and indexed symbols only, the bilinear forms `sf`, `af`, and `av` are evaluated. The evaluation substitutes the value of `aform[i,j]` in place of `fun(v[i],v[j])` where `v` represents the value of `asymbol` and `fun` is either `af` or `sf`; or, it substitutes `v[aform[i,j]]` in place of `av(v[i],v[j])`.

Needless to say, the functions `sf`, `af` and `av` can be redefined.

When the `atensor` package is loaded, the following flags are set:

```
dotsrules:true;
dotdistrib:true;
dotexptsimp:false;
```

If you wish to experiment with a nonassociative algebra, you may also consider setting `dotassoc` to `false`. In this case, however, `atensimp` will not always be able to obtain the desired simplifications.

27.2 Functions and Variables for `atensor`

init_atensor (<i>alg_type</i> , <i>opt_dims</i>)	Function
init_atensor (<i>alg_type</i>)	Function

Initializes the `atensor` package with the specified algebra type. *alg_type* can be one of the following:

universal: The universal algebra has no commutation rules.

grassmann: The Grassman algebra is defined by the commutation relation $u.v + v.u = 0$.

clifford: The Clifford algebra is defined by the commutation relation $u.v + v.u = -2*sf(u,v)$ where `sf` is a symmetric scalar-valued function. For this algebra, *opt_dims* can be up to three nonnegative integers, representing the number of positive, degenerate, and negative dimensions of the algebra, respectively. If any *opt_dims* values are supplied, `atensor` will configure the values of `adim` and `aform` appropriately. Otherwise, `adim` will default to 0 and `aform` will not be defined.

symmetric: The symmetric algebra is defined by the commutation relation $u.v - v.u = 0$.

symplectic: The symplectic algebra is defined by the commutation relation $u.v - v.u = 2*af(u,v)$ where `af` is an antisymmetric scalar-valued function. For the symplectic algebra, *opt_dims* can be up to two nonnegative integers, representing the nondegenerate and degenerate dimensions, respectively. If any *opt_dims* values are supplied, `atensor` will configure the values of `adim` and `aform` appropriately. Otherwise, `adim` will default to 0 and `aform` will not be defined.

lie_envelop: The algebra of the Lie envelope is defined by the commutation relation $u.v - v.u = 2*av(u,v)$ where `av` is an antisymmetric function.

The `init_atensor` function also recognizes several predefined algebra types:

complex implements the algebra of complex numbers as the Clifford algebra $Cl(0,1)$. The call `init_atensor(complex)` is equivalent to `init_atensor(clifford,0,0,1)`.

quaternion implements the algebra of quaternions. The call `init_atensor(quaternion)` is equivalent to `init_atensor(clifford,0,0,2)`.

pauli implements the algebra of Pauli-spinors as the Clifford-algebra $Cl(3,0)$. A call to `init_atensor(pauli)` is equivalent to `init_atensor(clifford,3)`.

dirac implements the algebra of Dirac-spinors as the Clifford-algebra $Cl(3,1)$. A call to `init_atensor(dirac)` is equivalent to `init_atensor(clifford,3,0,1)`.

atensimp (<i>expr</i>)	Function
---------------------------------	----------

Simplifies an algebraic tensor expression *expr* according to the rules configured by a call to `init_atensor`. Simplification includes recursive application of commutation relations and resolving calls to `sf`, `af`, and `av` where applicable. A safeguard is used to ensure that the function always terminates, even for complex expressions.

- alg_type** Function
 The algebra type. Valid values are `universal`, `grassmann`, `clifford`, `symmetric`, `symplectic` and `lie_envelop`.
- adim** Variable
 Default value: 0
 The dimensionality of the algebra. `atensor` uses the value of `adim` to determine if an indexed object is a valid base vector. See `abasep`.
- aform** Variable
 Default value: `ident(3)`
 Default values for the bilinear forms `sf`, `af`, and `av`. The default is the identity matrix `ident(3)`.
- asymbol** Variable
 Default value: `v`
 The symbol for base vectors.
- sf** (*u*, *v*) Function
 A symmetric scalar function that is used in commutation relations. The default implementation checks if both arguments are base vectors using `abasep` and if that is the case, substitutes the corresponding value from the matrix `aform`.
- af** (*u*, *v*) Function
 An antisymmetric scalar function that is used in commutation relations. The default implementation checks if both arguments are base vectors using `abasep` and if that is the case, substitutes the corresponding value from the matrix `aform`.
- av** (*u*, *v*) Function
 An antisymmetric function that is used in commutation relations. The default implementation checks if both arguments are base vectors using `abasep` and if that is the case, substitutes the corresponding value from the matrix `aform`.
 For instance:
- ```
(%i1) load(atensor);
(%o1) /share/tensor/atensor.mac
(%i2) adim:3;
(%o2)
(%i3) aform:matrix([0,3,-2],[-3,0,1],[2,-1,0]);
 [0 3 -2]
 []
(%o3) [-3 0 1]
 []
 [2 -1 0]

(%i4) asymbol:x;
(%o4)
 x
(%i5) av(x[1],x[2]);
(%o5)
 x
 3
```
- abasep** (*v*) Function  
 Checks if its argument is an `atensor` base vector. That is, if it is an indexed symbol, with the symbol being the same as the value of `asymbol`, and the index having a numeric value between 1 and `adim`.



## 28 Sums, Products, and Series

### 28.1 Sums and Products

#### **bashindices** (*expr*)

Function

Transforms the expression *expr* by giving each summation and product a unique index. This gives **changevar** greater precision when it is working with summations or products. The form of the unique index is *jnumber*. The quantity *number* is determined by referring to **gensumnum**, which can be changed by the user. For example, **gensumnum:0\$** resets it.

#### **lsum** (*expr*, *x*, *L*)

Function

Represents the sum of *expr* for each element *x* in *L*. A noun form 'lsum is returned if the argument *L* does not evaluate to a list.

Examples:

```
(%i1) lsum (x^i, i, [1, 2, 7]);
 7 2
(%o1) x + x + x
(%i2) lsum (i^2, i, rootsof (x^3 - 1));
=====
\ 2
> i
/
=====
 3
i in rootsof(x - 1)
```

#### **intosum** (*expr*)

Function

Moves multiplicative factors outside a summation to inside. If the index is used in the outside expression, then the function tries to find a reasonable index, the same as it does for **sumcontract**. This is essentially the reverse idea of the **outative** property of summations, but note that it does not remove this property, it only bypasses it.

In some cases, a **scanmap** (**multthru**, *expr*) may be necessary before the **intosum**.

#### **product** (*expr*, *i*, *i\_0*, *i\_1*)

Function

Represents a product of the values of *expr* as the index *i* varies from *i\_0* to *i\_1*. The noun form 'product is displayed as an uppercase letter pi.

**product** evaluates *expr* and lower and upper limits *i\_0* and *i\_1*, **product** quotes (does not evaluate) the index *i*.

If the upper and lower limits differ by an integer, *expr* is evaluated for each value of the index *i*, and the result is an explicit product.

Otherwise, the range of the index is indefinite. Some rules are applied to simplify the product. When the global variable **simpproduct** is **true**, additional rules are applied. In some cases, simplification yields a result which is not a product; otherwise, the result is a noun form 'product.

See also **nouns** and **evflag**.

Examples:

```
(%i1) product (x + i*(i+1)/2, i, 1, 4);
(%o1) (x + 1) (x + 3) (x + 6) (x + 10)
(%i2) product (i^2, i, 1, 7);
(%o2) 25401600
(%i3) product (a[i], i, 1, 7);
(%o3) a a a a a a a
```

```

 1 2 3 4 5 6 7
(%i4) product (a(i), i, 1, 7);
(%o4) a(1) a(2) a(3) a(4) a(5) a(6) a(7)
(%i5) product (a(i), i, 1, n);
 n
 /===\
 ! !
 ! ! a(i)
 ! !
 i = 1
(%i6) product (k, k, 1, n);
 n
 /===\
 ! !
 ! ! k
 ! !
 k = 1
(%i7) product (k, k, 1, n), simpproduct;
(%o7) n!
(%i8) product (integrate (x^k, x, 0, 1), k, 1, n);
 n
 /===\
 ! ! 1
 ! ! -----
 ! ! k + 1
 k = 1
(%i9) product (if k <= 5 then a^k else b^k, k, 1, 10);
 15 40
(%o9) a b

```

**simpsum**

Option variable

Default value: `false`

When `simpsum` is `true`, the result of a `sum` is simplified. This simplification may sometimes be able to produce a closed form. If `simpsum` is `false` or if the quoted form `'sum` is used, the value is a sum noun form which is a representation of the sigma notation used in mathematics.

**sum** (*expr*, *i*, *i\_0*, *i\_1*)

Function

Represents a summation of the values of *expr* as the index *i* varies from *i\_0* to *i\_1*. The noun form `'sum` is displayed as an uppercase letter sigma.

`sum` evaluates its summand *expr* and lower and upper limits *i\_0* and *i\_1*, `sum` quotes (does not evaluate) the index *i*.

If the upper and lower limits differ by an integer, the summand *expr* is evaluated for each value of the summation index *i*, and the result is an explicit sum.

Otherwise, the range of the index is indefinite. Some rules are applied to simplify the summation. When the global variable `simpsum` is `true`, additional rules are applied. In some cases, simplification yields a result which is not a summation; otherwise, the result is a noun form `'sum`.

When the `evflag` (evaluation flag) `cauchysum` is `true`, a product of summations is expressed as a Cauchy product, in which the index of the inner summation is a function of the index of the outer one, rather than varying independently.

The global variable `genindex` is the alphabetic prefix used to generate the next index of summation, when an automatically generated index is needed.

`gensumnum` is the numeric suffix used to generate the next index of summation, when an automatically generated index is needed. When `gensumnum` is `false`, an automatically-generated index is only `genindex` with no numeric suffix.

See also `sumcontract`, `intosum`, `bashindices`, `niceindices`, `nouns`, `evflag`, and `zeilberger`.

Examples:

```
(%i1) sum (i^2, i, 1, 7);
(%o1) 140
(%i2) sum (a[i], i, 1, 7);
(%o2)

$$a_7 + a_6 + a_5 + a_4 + a_3 + a_2 + a_1$$

(%i3) sum (a(i), i, 1, 7);
(%o3) a(7) + a(6) + a(5) + a(4) + a(3) + a(2) + a(1)
(%i4) sum (a(i), i, 1, n);
(%o4)

$$\sum_{i=1}^n a(i)$$

(%i5) sum (2^i + i^2, i, 0, n);
(%o5)

$$\sum_{i=0}^n (2^i + i^2)$$

(%i6) sum (2^i + i^2, i, 0, n), simpsum;
(%o6)

$$\frac{n+1}{2} + \frac{2n^2 + 3n + n}{6} - 1$$

(%i7) sum (1/3^i, i, 1, inf);
(%o7)

$$\sum_{i=1}^{\infty} \frac{1}{3^i}$$

(%i8) sum (1/3^i, i, 1, inf), simpsum;
(%o8)

$$\frac{1}{2}$$

(%i9) sum (i^2, i, 1, 4) * sum (1/i^2, i, 1, inf);
(%o9)

$$30 \sum_{i=1}^{\infty} \frac{1}{i^2}$$

(%i10) sum (i^2, i, 1, 4) * sum (1/i^2, i, 1, inf), simpsum;
(%o10)

$$\frac{5}{2} \pi^2$$

(%i11) sum (integrate (x^k, x, 0, 1), k, 1, n);
(%o11)

$$\sum_{k=1}^n \int_0^1 x^k dx$$

```

```

====
\ 1
> -----
/ k + 1
====
k = 1
(%i12) sum (if k <= 5 then a^k else b^k, k, 1, 10);
 10 9 8 7 6 5 4 3 2
(%o12) b + b + b + b + b + a + a + a + a + a

```

**sumcontract** (*expr*)

Function

Combines all sums of an addition that have upper and lower bounds that differ by constants. The result is an expression containing one summation for each set of such summations added to all appropriate extra terms that had to be extracted to form this sum. **sumcontract** combines all compatible sums and uses one of the indices from one of the sums if it can, and then try to form a reasonable index if it cannot use any supplied.

It may be necessary to do an **intosum** (*expr*) before the **sumcontract**.

**sumexpand**

Option variable

Default value: **false**

When **sumexpand** is **true**, products of sums and exponentiated sums simplify to nested sums.

See also **cauchysum**.

Examples:

```

(%i1) sumexpand: true$
(%i2) sum (f (i), i, 0, m) * sum (g (j), j, 0, n);
 m n
 ==== ====
 \ \
 > > f(i1) g(i2)
 / /
 ==== ====
 i1 = 0 i2 = 0
(%i3) sum (f (i), i, 0, m)^2;
 m m
 ==== ====
 \ \
 > > f(i3) f(i4)
 / /
 ==== ====
 i3 = 0 i4 = 0

```

## 28.2 Introduction to Series

Maxima contains functions **taylor** and **powerseries** for finding the series of differentiable functions. It also has tools such as **nusum** capable of finding the closed form of some series. Operations such as addition and multiplication work as usual on series. This section presents the global variables which control the expansion.

## 28.3 Functions and Variables for Series

**cauchysum**

Option variable

Default value: **false**

When multiplying together sums with `inf` as their upper limit, if `sumexpand` is `true` and `cauchysum` is `true` then the Cauchy product will be used rather than the usual product. In the Cauchy product the index of the inner summation is a function of the index of the outer one rather than varying independently.

Example:

```
(%i1) sumexpand: false$
(%i2) cauchysum: false$
(%i3) s: sum (f(i), i, 0, inf) * sum (g(j), j, 0, inf);
 inf inf
 ==== ====
 \ \
 (> f(i)) > g(j)
 / /
 ==== ====
 i = 0 j = 0

(%i4) sumexpand: true$
(%i5) cauchysum: true$
(%i6) ''s;
 inf i1
 ==== ====
 \ \
 > > g(i1 - i2) f(i2)
 / /
 ==== ====
 i1 = 0 i2 = 0
```

**deftaylor** ( $f_1(x_1)$ ,  $expr_1$ , ...,  $f_n(x_n)$ ,  $expr_n$ ) Function

For each function  $f_i$  of one variable  $x_i$ , **deftaylor** defines  $expr_i$  as the Taylor series about zero.  $expr_i$  is typically a polynomial in  $x_i$  or a summation; more general expressions are accepted by **deftaylor** without complaint.

**powerseries** ( $f_i(x_i)$ ,  $x_i$ , 0) returns the series defined by **deftaylor**.

**deftaylor** returns a list of the functions  $f_1$ , ...,  $f_n$ . **deftaylor** evaluates its arguments.

Example:

```
(%i1) deftaylor (f(x), x^2 + sum(x^i/(2^i*i!^2), i, 4, inf));
(%o1) [f]
(%i2) powerseries (f(x), x, 0);
 inf
 ====
 \ i1
 > x 2
 / ----- + x
 / i1 2
 / 2 i1!
 / i1 = 4
 /
 / 2 3 4
 / x 3073 x 12817 x
 / 2 18432 307200
 /
 / 1 + x + --- + ----- + ----- + . . .
 / 2 18432 307200
```

**maxtayorder**

Option variable

Default value: `true`

When **maxtayorder** is `true`, then during algebraic manipulation of (truncated) Taylor series, **taylor** tries to retain as many terms as are known to be correct.

**niceindices** (*expr*)

Function

Renames the indices of sums and products in *expr*. **niceindices** attempts to rename each index to the value of **niceindicespref**[1], unless that name appears in the summand or multiplicand, in which case **niceindices** tries the succeeding elements of **niceindicespref** in turn, until an unused variable is found. If the entire list is exhausted, additional indices are constructed by appending integers to the value of **niceindicespref**[1], e.g., *i0*, *i1*, *i2*, ...

**niceindices** returns an expression. **niceindices** evaluates its argument.

Example:

```
(%i1) niceindicespref;
(%o1) [i, j, k, l, m, n]
(%i2) product (sum (f (foo + i*j*bar), foo, 1, inf), bar, 1, inf);
 inf inf
 /====\ =====
 ! ! \
(%o2) ! ! > f(bar i j + foo)
 ! ! /
 bar = 1 =====
 foo = 1
(%i3) niceindices (%);
 inf inf
 /====\ =====
 ! ! \
(%o3) ! ! > f(i j l + k)
 ! ! /
 l = 1 =====
 k = 1
```

**niceindicespref**

Option variable

Default value: [i, j, k, l, m, n]

**niceindicespref** is the list from which **niceindices** takes the names of indices for sums and products.

The elements of **niceindicespref** are typically names of variables, although that is not enforced by **niceindices**.

Example:

```
(%i1) niceindicespref: [p, q, r, s, t, u]$
(%i2) product (sum (f (foo + i*j*bar), foo, 1, inf), bar, 1, inf);
 inf inf
 /====\ =====
 ! ! \
(%o2) ! ! > f(bar i j + foo)
 ! ! /
 bar = 1 =====
 foo = 1
(%i3) niceindices (%);
 inf inf
 /====\ =====
 ! ! \
(%o3) ! ! > f(i j q + p)
 ! ! /
 q = 1 =====
 p = 1
```



**nusum** (*expr*, *x*, *i\_0*, *i\_1*)

Function

Carries out indefinite hypergeometric summation of *expr* with respect to *x* using a decision procedure due to R.W. Gosper. *expr* and the result must be expressible as products of integer powers, factorials, binomials, and rational functions.

The terms "definite" and "indefinite summation" are used analogously to "definite" and "indefinite integration". To sum indefinitely means to give a symbolic result for the sum over intervals of variable length, not just e.g. 0 to inf. Thus, since there is no formula for the general partial sum of the binomial series, **nusum** can't do it.

**nusum** and **unsum** know a little about sums and differences of finite products. See also **unsum**.

Examples:

```
(%i1) nusum (n*n!, n, 0, n);
```

Dependent equations eliminated: (1)

```
(%o1) (n + 1)! - 1
```

```
(%i2) nusum (n^4*4^n/binomial(2*n,n), n, 0, n);
```

```
(%o2) -----
 4 3 2 n
 2 (n + 1) (63 n + 112 n + 18 n - 22 n + 3) 4 2
 693 binomial(2 n, n) 3 11 7
```

```
(%i3) unsum (% , n);
```

```
(%o3) -----
 4 n
 n 4
 binomial(2 n, n)
```

```
(%i4) unsum (prod (i^2, i, 1, n), n);
```

```
(%o4) -----
 n - 1
 /===\
 ! ! 2
 (! ! i) (n - 1) (n + 1)
 ! !
 i = 1
```

```
(%i5) nusum (% , n, 1, n);
```

Dependent equations eliminated: (2 3)

```
(%o5) -----
 n
 /===\
 ! ! 2
 ! ! i - 1
 ! !
 i = 1
```

**pade** (*taylor\_series*, *numer\_deg\_bound*, *denom\_deg\_bound*)

Function

Returns a list of all rational functions which have the given Taylor series expansion where the sum of the degrees of the numerator and the denominator is less than or equal to the truncation level of the power series, i.e. are "best" approximants, and which additionally satisfy the specified degree bounds.

*taylor\_series* is a univariate Taylor series. *numer\_deg\_bound* and *denom\_deg\_bound* are positive integers specifying degree bounds on the numerator and denominator.

*taylor\_series* can also be a Laurent series, and the degree bounds can be **inf** which causes all rational functions whose total degree is less than or equal to the length of the power series to be returned. Total degree is defined as *numer\_deg\_bound* + *denom\_deg\_bound*. Length of a power series is defined as "truncation level" + 1 - min(0, "order of series").

```
(%i1) taylor (1 + x + x^2 + x^3, x, 0, 3);
```

```

(%o1)/T/
 2 3
 1 + x + x + x + . . .
(%i2) pade (% , 1, 1);

(%o2)
 1
 [- ----]
 x - 1
(%i3) t: taylor(-(83787*x^10 - 45552*x^9 - 187296*x^8
 + 387072*x^7 + 86016*x^6 - 1507328*x^5
 + 1966080*x^4 + 4194304*x^3 - 25165824*x^2
 + 67108864*x - 134217728)
 /134217728, x, 0, 10);
 2 3 4 5 6 7
 x 3 x x 15 x 23 x 21 x 189 x
(%o3)/T/ 1 - - + ---- - - - - - + ---- - ---- - ----
 2 16 32 1024 2048 32768 65536

 8 9 10
 5853 x 2847 x 83787 x
 + ---- + ---- - ---- + . . .
 4194304 8388608 134217728
(%i4) pade (t, 4, 4);
(%o4)
 []

```

There is no rational function of degree 4 numerator/denominator, with this power series expansion. You must in general have degree of the numerator and degree of the denominator adding up to at least the degree of the power series, in order to have enough unknown coefficients to solve.

```

(%i5) pade (t, 5, 5);
(%o5) [- (520256329 x^5 - 96719020632 x^4 - 489651410240 x^3
 - 1619100813312 x^2 - 2176885157888 x - 2386516803584)
 / (47041365435 x^5 + 381702613848 x^4 + 1360678489152 x^3
 + 2856700692480 x^2 + 3370143559680 x + 2386516803584)]

```

### **powerseries** (expr, x, a)

Function

Returns the general form of the power series expansion for *expr* in the variable *x* about the point *a* (which may be *inf* for infinity):

```

 inf
 ====
 \
 > b (x - a)^n
 / n
 ====
 n = 0

```

If **powerseries** is unable to expand *expr*, **taylor** may give the first several terms of the series.

When **verbose** is true, **powerseries** prints progress messages.

```

(%i1) verbose: true$
(%i2) powerseries (log(sin(x)/x), x, 0);
can't expand

```

```

log(sin(x))
so we'll try again after applying the rule:
 d
 / -- (sin(x))
 [dx
log(sin(x)) = i ----- dx
] sin(x)
 /
in the first simplification we have returned:
 /
 [
 i cot(x) dx - log(x)
]
 /

inf
====
\ i1 2 i1 2 i1
(- 1) 2 bern(2 i1) x
> -----
/ i1 (2 i1)!
====
i1 = 1
(2) -----
 2

```

psexpand

Option variable

Default value: `false`

When `psexpand` is `true`, an extended rational function expression is displayed fully expanded. The switch `ratexpand` has the same effect.

When `psexpand` is `false`, a multivariate expression is displayed just as in the rational function package.

When `psexpand` is `multi`, then terms with the same total degree in the variables are grouped together.

```
revert (expr, x)
```

Function

```

revert2 (expr, x, n)

```

Function

These functions return the reversion of *expr*, a Taylor series about zero in the variable *x*. **revert** returns a polynomial of degree equal to the highest power in *expr*. **revert2** returns a polynomial of degree *n*, which may be greater than, equal to, or less than the degree of *expr*.

`load ("revert")` loads these functions.

Examples:

```
(%i1) load ("revert")$
(%i2) t: taylor (exp(x) - 1, x, 0, 6);

 2 3 4 5 6
 x x x x x
(%o2)/T/ x + -- + -- + -- + --- + --- + . . .
 2 6 24 120 720

(%i3) revert (t, x);

 6 5 4 3 2
 10 x - 12 x + 15 x - 20 x + 30 x - 60 x
(%o3)/R/ - ----
 60

(%i4) ratexpand (%);

 6 5 4 3 2
 x x x x x
```

```
(%o4)
 - -- + -- - -- + -- - -- + x
 6 5 4 3 2
(%i5) taylor (log(x+1), x, 0, 6);
 2 3 4 5 6
 x x x x x
(%o5)/T/ x - -- + -- - -- + -- - -- + . . .
 2 3 4 5 6
(%i6) ratsimp (revert (t, x) - taylor (log(x+1), x, 0, 6));
(%o6)
 0
(%i7) revert2 (t, x, 4);
 4 3 2
 x x x
(%o7) - -- + -- - -- + x
 4 3 2
```

|                                                                                                                                                                                                       |          |
|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|
| <b>taylor</b> ( <i>expr</i> , <i>x</i> , <i>a</i> , <i>n</i> )                                                                                                                                        | Function |
| <b>taylor</b> ( <i>expr</i> , [ <i>x</i> <sub>1</sub> , <i>x</i> <sub>2</sub> , ...], <i>a</i> , <i>n</i> )                                                                                           | Function |
| <b>taylor</b> ( <i>expr</i> , [ <i>x</i> , <i>a</i> , <i>n</i> , 'asympt])                                                                                                                            | Function |
| <b>taylor</b> ( <i>expr</i> , [ <i>x</i> <sub>1</sub> , <i>x</i> <sub>2</sub> , ...], [ <i>a</i> <sub>1</sub> , <i>a</i> <sub>2</sub> , ...], [ <i>n</i> <sub>1</sub> , <i>n</i> <sub>2</sub> , ...]) | Function |
| <b>taylor</b> ( <i>expr</i> , [ <i>x</i> <sub>1</sub> , <i>a</i> <sub>1</sub> , <i>n</i> <sub>1</sub> ], [ <i>x</i> <sub>2</sub> , <i>a</i> <sub>2</sub> , <i>n</i> <sub>2</sub> ], ...)              | Function |

**taylor** (*expr*, *x*, *a*, *n*) expands the expression *expr* in a truncated Taylor or Laurent series in the variable *x* around the point *a*, containing terms through  $(x - a)^n$ .

If *expr* is of the form  $f(x)/g(x)$  and  $g(x)$  has no terms up to degree *n* then **taylor** attempts to expand  $g(x)$  up to degree  $2n$ . If there are still no nonzero terms, **taylor** doubles the degree of the expansion of  $g(x)$  so long as the degree of the expansion is less than or equal to  $n \cdot 2^{\text{taylordepth}}$ .

**taylor** (*expr*, [*x*<sub>1</sub>, *x*<sub>2</sub>, ...], *a*, *n*) returns a truncated power series of degree *n* in all variables *x*<sub>1</sub>, *x*<sub>2</sub>, ... about the point (*a*, *a*, ...).

**taylor** (*expr*, [*x*<sub>1</sub>, *a*<sub>1</sub>, *n*<sub>1</sub>], [*x*<sub>2</sub>, *a*<sub>2</sub>, *n*<sub>2</sub>], ...) returns a truncated power series in the variables *x*<sub>1</sub>, *x*<sub>2</sub>, ... about the point (*a*<sub>1</sub>, *a*<sub>2</sub>, ...), truncated at *n*<sub>1</sub>, *n*<sub>2</sub>, ...

**taylor** (*expr*, [*x*<sub>1</sub>, *x*<sub>2</sub>, ...], [*a*<sub>1</sub>, *a*<sub>2</sub>, ...], [*n*<sub>1</sub>, *n*<sub>2</sub>, ...]) returns a truncated power series in the variables *x*<sub>1</sub>, *x*<sub>2</sub>, ... about the point (*a*<sub>1</sub>, *a*<sub>2</sub>, ...), truncated at *n*<sub>1</sub>, *n*<sub>2</sub>, ...

**taylor** (*expr*, [*x*, *a*, *n*, 'asympt]) returns an expansion of *expr* in negative powers of  $x - a$ . The highest order term is  $(x - a)^{-n}$ .

When **maxtayorder** is **true**, then during algebraic manipulation of (truncated) Taylor series, **taylor** tries to retain as many terms as are known to be correct.

When **psexpand** is **true**, an extended rational function expression is displayed fully expanded. The switch **ratexpand** has the same effect. When **psexpand** is **false**, a multivariate expression is displayed just as in the rational function package. When **psexpand** is **multi**, then terms with the same total degree in the variables are grouped together.

See also the **taylor\_logexpand** switch for controlling expansion.

Examples:

```
(%i1) taylor (sqrt (sin(x) + a*x + 1), x, 0, 3);
 2 2
 (a + 1) x (a + 2 a + 1) x
(%o1)/T/ 1 + ----- - -----
 2 8
 3 2 3
 (3 a + 9 a + 9 a - 1) x
 + ----- + . . .
 48
(%i2) %^2;
```

```

(%o2)/T/

$$1 + (a + 1)x - \frac{x^6}{6} + \dots$$

(%i3) taylor (sqrt (x + 1), x, 0, 5);

$$1 + \frac{x}{2} - \frac{x^2}{8} + \frac{x^3}{16} - \frac{5x^4}{128} + \frac{7x^5}{256} + \dots$$

(%o3)/T/
(%i4) %^2;
(%o4)/T/

$$1 + x + \dots$$

(%i5) product ((1 + x^i)^2.5, i, 1, inf)/(1 + x^2);

$$\frac{\prod_{i=1}^{\infty} (x^i + 1)^{2.5}}{(1 + x^2)}$$

(%o5)

$$\frac{x^2 + 1}{2}$$

(%i6) ev (taylor(%, x, 0, 3), keepfloat);

$$1 + 2.5x + 3.375x^2 + 6.5625x^3 + \dots$$

(%o6)/T/
(%i7) taylor (1/log (x + 1), x, 0, 3);

$$-\frac{1}{x} + \frac{1}{2} - \frac{x}{12} + \frac{x^2}{24} - \frac{19x^3}{720} + \dots$$

(%o7)/T/
(%i8) taylor (cos(x) - sec(x), x, 0, 5);

$$-x^2 - \frac{x^4}{6} + \dots$$

(%o8)/T/
(%i9) taylor ((cos(x) - sec(x))^3, x, 0, 5);

$$0 + \dots$$

(%o9)/T/
(%i10) taylor (1/(cos(x) - sec(x))^3, x, 0, 5);

$$\frac{1}{x^6} + \frac{1}{2x^4} + \frac{11}{120x^2} - \frac{347}{15120} - \frac{6767x}{604800} - \frac{15377x^2}{7983360} + \dots$$

(%o10)/T/
(%i11) taylor (sqrt (1 - k^2*sin(x)^2), x, 0, 6);

$$1 - \frac{k^2x^2}{2} - \frac{(3k^2 - 4k^4)x^4}{24} - \frac{(45k^6 - 60k^4 + 16k^2)x^6}{720} + \dots$$

(%o11)/T/

```

```

 2 2 3 2 3
 (n - n) x (n - 3 n + 2 n) x
(%o12)/T/ 1 + n x + ----- + -----
 2 6

 4 3 2 4
 (n - 6 n + 11 n - 6 n) x
 + ----- + . . .
 24
(%i13) taylor (sin (y + x), x, 0, 3, y, 0, 3);
 3 2
 y y
(%o13)/T/ y - -- + . . . + (1 - -- + . . .) x
 6 2

 3 2
 y y 2 1 y 3
 + (- - + -- + . . .) x + (- - + -- + . . .) x + . . .
 2 12 6 12
(%i14) taylor (sin (y + x), [x, y], 0, 3);
 3 2 2 3
 x + 3 y x + 3 y x + y
(%o14)/T/ y + x - ----- + . . .
 6

 6
(%i15) taylor (1/sin (y + x), x, 0, 3, y, 0, 3);
 1 y 1 1 1 2
 - + - + . . . + (- -- + - + . . .) x + (-- + . . .) x
 y 6 2 6 3
 y

 1 3
 + (- -- + . . .) x + . . .
 4
 y
(%i16) taylor (1/sin (y + x), [x, y], 0, 3);
 3 2 2 3
 x + y 7 x + 21 y x + 21 y x + 7 y
(%o16)/T/ ----- + ----- + ----- + . . .
 x + y 6 360

```

**taylordepth**

Option variable

Default value: 3

If there are still no nonzero terms, **taylor** doubles the degree of the expansion of  $g(x)$  so long as the degree of the expansion is less than or equal to  $n^{2\text{taylordepth}}$ .

**taylorinfo** (*expr*)

Function

Returns information about the Taylor series *expr*. The return value is a list of lists. Each list comprises the name of a variable, the point of expansion, and the degree of the expansion.

**taylorinfo** returns **false** if *expr* is not a Taylor series.

Example:

```

(%i1) taylor ((1 - y^2)/(1 - x), x, 0, 3, [y, a, inf]);
 2 2
(%o1)/T/ - (y - a) - 2 a (y - a) + (1 - a)

```

```

 2 2
+ (1 - a - 2 a (y - a) - (y - a)) x
 2 2 2
+ (1 - a - 2 a (y - a) - (y - a)) x
 2 2 3
+ (1 - a - 2 a (y - a) - (y - a)) x + . . .
(%i2) taylorinfo(%);
(%o2) [[y, a, inf], [x, 0, 3]]

```

**taylorp** (*expr*) Function

Returns **true** if *expr* is a Taylor series, and **false** otherwise.

**taylor\_logexpand** Option variable

Default value: **true**

**taylor\_logexpand** controls expansions of logarithms in **taylor** series.

When **taylor\_logexpand** is **true**, all logarithms are expanded fully so that zero-recognition problems involving logarithmic identities do not disturb the expansion process. However, this scheme is not always mathematically correct since it ignores branch information.

When **taylor\_logexpand** is set to **false**, then the only expansion of logarithms that occur is that necessary to obtain a formal power series.

**taylor\_order\_coefficients** Option variable

Default value: **true**

**taylor\_order\_coefficients** controls the ordering of coefficients in a Taylor series.

When **taylor\_order\_coefficients** is **true**, coefficients of **taylor** series are ordered canonically.

**taylor\_simplifier** (*expr*) Function

Simplifies coefficients of the power series *expr*. **taylor** calls this function.

**taylor\_truncate\_polynomials** Option variable

Default value: **true**

When **taylor\_truncate\_polynomials** is **true**, polynomials are truncated based upon the input truncation levels.

Otherwise, polynomials input to **taylor** are considered to have infinite precision.

**taytorat** (*expr*) Function

Converts *expr* from **taylor** form to canonical rational expression (CRE) form. The effect is the same as **rat** (**ratdisrep** (*expr*)), but faster.

**trunc** (*expr*) Function

Annotates the internal representation of the general expression *expr* so that it is displayed as if its sums were truncated Taylor series. *expr* is not otherwise modified.

Example:

```

(%i1) expr: x^2 + x + 1;
(%o1) 2
 x + x + 1
(%i2) trunc (expr);
(%o2) 2
 1 + x + x + . . .
(%i3) is (expr = trunc (expr));
(%o3) true

```

**unsum** (*f*, *n*)

Function

Returns the first backward difference  $f(n) - f(n - 1)$ . Thus **unsum** in a sense is the inverse of **sum**.

See also **nusum**.

Examples:

```
(%i1) g(p) := p*4^n/binomial(2*n,n);
 n
 p 4
(%o1) g(p) := -----
 binomial(2 n, n)

(%i2) g(n^4);
 4 n
 n 4
(%o2) -----
 binomial(2 n, n)

(%i3) nusum (% , n, 0, n);
 4 3 2 n
2 (n + 1) (63 n + 112 n + 18 n - 22 n + 3) 4 2
(%o3) ----- - -----
 693 binomial(2 n, n) 3 11 7

(%i4) unsum (% , n);
 4 n
 n 4
(%o4) -----
 binomial(2 n, n)
```

**verbose**

Option variable

Default value: **false**

When **verbose** is **true**, **powerseries** prints progress messages.

**28.4 Poisson series****intopois** (*a*)

Function

Converts *a* into a Poisson encoding.

**outofpois** (*a*)

Function

Converts *a* from Poisson encoding to general representation. If *a* is not in Poisson form, **outofpois** carries out the conversion, i.e., the return value is **outofpois** (**intopois** (*a*)). This function is thus a canonical simplifier for sums of powers of sine and cosine terms of a particular type.

**poisdiff** (*a*, *b*)

Function

Differentiates *a* with respect to *b*. *b* must occur only in the trig arguments or only in the coefficients.

**poisexpt** (*a*, *b*)

Function

Functionally identical to **intopois** ( $a^b$ ). *b* must be a positive integer.

**poisint** (*a*, *b*)

Function

Integrates in a similarly restricted sense (to **poisdiff**). Non-periodic terms in *b* are dropped if *b* is in the trig arguments.



**poislim**

Option variable

Default value: 5

**poislim** determines the domain of the coefficients in the arguments of the trig functions. The initial value of 5 corresponds to the interval  $[-2^{(5-1)+1}, 2^{(5-1)}]$ , or  $[-15, 16]$ , but it can be set to  $[-2^{(n-1)+1}, 2^{(n-1)}]$ .

**poismap** (*series*, *sinfn*, *cosfn*)

Function

will map the functions *sinfn* on the sine terms and *cosfn* on the cosine terms of the Poisson series given. *sinfn* and *cosfn* are functions of two arguments which are a coefficient and a trigonometric part of a term in series respectively.

**poisplus** (*a*, *b*)

Function

Is functionally identical to **intopois** (*a* + *b*).

**poissimp** (*a*)

Function

Converts *a* into a Poisson series for *a* in general representation.

**poisson**

Special symbol

The symbol /P/ follows the line label of Poisson series expressions.

**poissubst** (*a*, *b*, *c*)

Function

Substitutes *a* for *b* in *c*. *c* is a Poisson series.

(1) Where *B* is a variable *u*, *v*, *w*, *x*, *y*, or *z*, then *a* must be an expression linear in those variables (e.g.,  $6*u + 4*v$ ).

(2) Where *b* is other than those variables, then *a* must also be free of those variables, and furthermore, free of sines or cosines.

**poissubst** (*a*, *b*, *c*, *d*, *n*) is a special type of substitution which operates on *a* and *b* as in type (1) above, but where *d* is a Poisson series, expands **cos**(*d*) and **sin**(*d*) to order *n* so as to provide the result of substituting *a* + *d* for *b* in *c*. The idea is that *d* is an expansion in terms of a small parameter. For example, **poissubst** (*u*, *v*, **cos**(*v*), %e, 3) yields  $\cos(u)*(1 - \%e^{2/2}) - \sin(u)*(\%e - \%e^{3/6})$ .

**poistimes** (*a*, *b*)

Function

Is functionally identical to **intopois** (*a*\**b*).

**poistrim** ()

Function

is a reserved function name which (if the user has defined it) gets applied during Poisson multiplication. It is a predicate function of 6 arguments which are the coefficients of the *u*, *v*, ..., *z* in a term. Terms for which **poistrim** is **true** (for the coefficients of that term) are eliminated during multiplication.

**printpois** (*a*)

Function

Prints a Poisson series in a readable format. In common with **outofpois**, it will convert *a* into a Poisson encoding first, if necessary.



## 29 Number Theory

### 29.1 Functions and Variables for Number Theory

**bern** (*n*) Function

Returns the *n*'th Bernoulli number for integer *n*. Bernoulli numbers equal to zero are suppressed if **zerobern** is **false**.

See also **burn**.

```
(%i1) zerobern: true$
(%i2) map (bern, [0, 1, 2, 3, 4, 5, 6, 7, 8]);
 1 1 1 1 1
(%o2) [1, - -, -, 0, - --, 0, --, 0, - --]
 2 6 30 42 30
(%i3) zerobern: false$
(%i4) map (bern, [0, 1, 2, 3, 4, 5, 6, 7, 8]);
 1 1 1 5 691 7 3617 43867
(%o4) [1, - -, -, - --, --, - ----, -, - ----, -----]
 2 6 30 66 2730 6 510 798
```

**bernpoly** (*x*, *n*) Function

Returns the *n*'th Bernoulli polynomial in the variable *x*.

**bfzeta** (*s*, *n*) Function

Returns the Riemann zeta function for the argument *s*. The return value is a big float (bfloat); *n* is the number of digits in the return value.

**bfhzeta** (*s*, *h*, *n*) Function

Returns the Hurwitz zeta function for the arguments *s* and *h*. The return value is a big float (bfloat); *n* is the number of digits in the return value.

The Hurwitz zeta function is defined as

$$\zeta(s, h) = \sum_{k=0}^{\infty} \frac{1}{(k+h)^s}$$

**load** ("bffac") loads this function.

**burn** (*n*) Function

Returns a rational number, which is an approximation of the *n*'th Bernoulli number for integer *n*. **burn** exploits the observation that (rational) Bernoulli numbers can be approximated by (transcendental) zetas with tolerable efficiency:

$$B(2n) = \frac{(-1)^{n-1} \frac{1-2n}{2} \text{zeta}(2n)}{(2n)! \pi^{2n}}$$

**burn** may be more efficient than **bern** for large, isolated *n* as **bern** computes all the Bernoulli numbers up to index *n* before returning. **burn** invokes the approximation for even integers *n* > 255. For odd integers and *n* ≤ 255 the function **bern** is called.

**load** ("bffac") loads this function. See also **bern**.

**chinese** ( $[r_1, \dots, r_n], [m_1, \dots, m_n]$ ) Function

Solves the system of congruences  $x = r_1 \bmod m_1, \dots, x = r_n \bmod m_n$ . The remainders  $r_n$  may be arbitrary integers while the moduli  $m_n$  have to be positive and pairwise coprime integers.

```
(%i1) mods : [1000, 1001, 1003, 1007];
(%o1) [1000, 1001, 1003, 1007]
(%i2) lreduce('gcd, mods);
(%o2) 1
(%i3) x : random(apply("*", mods));
(%o3) 685124877004
(%i4) rems : map(lambda([z], mod(x, z)), mods);
(%o4) [4, 568, 54, 624]
(%i5) chinese(rems, mods);
(%o5) 685124877004
(%i6) chinese([1, 2], [3, n]);
(%o6) chinese([1, 2], [3, n])
(%i7) %, n = 4;
(%o7) 10
```

**cf** (*expr*) Function

Computes a continued fraction approximation. *expr* is an expression comprising continued fractions, square roots of integers, and literal real numbers (integers, rational numbers, ordinary floats, and bigfloats). **cf** computes exact expansions for rational numbers, but expansions are truncated at **ratepsilon** for ordinary floats and  $10^{(-\text{fpprec})}$  for bigfloats. Operands in the expression may be combined with arithmetic operators. Maxima does not know about operations on continued fractions outside of **cf**.

**cf** evaluates its arguments after binding **listarith** to **false**. **cf** returns a continued fraction, represented as a list.

A continued fraction  $a + 1/(b + 1/(c + \dots))$  is represented by the list  $[a, b, c, \dots]$ . The list elements  $a, b, c, \dots$  must evaluate to integers. *expr* may also contain **sqrt** (*n*) where *n* is an integer. In this case **cf** will give as many terms of the continued fraction as the value of the variable **cflength** times the period.

A continued fraction can be evaluated to a number by evaluating the arithmetic representation returned by **cfdisrep**. See also **cfexpand** for another way to evaluate a continued fraction.

See also **cfdisrep**, **cfexpand**, and **cflength**.

Examples:

- expr* is an expression comprising continued fractions and square roots of integers.

```
(%i1) cf ([5, 3, 1]*[11, 9, 7] + [3, 7]/[4, 3, 2]);
(%o1) [59, 17, 2, 1, 1, 1, 27]
(%i2) cf ((3/17)*[1, -2, 5]/sqrt(11) + (8/13));
(%o2) [0, 1, 1, 1, 1, 3, 2, 1, 4, 1, 9, 1, 9, 2]
```

- cflength** controls how many periods of the continued fraction are computed for algebraic, irrational numbers.

```
(%i1) cflength: 1$
(%i2) cf ((1 + sqrt(5))/2);
(%o2) [1, 1, 1, 1, 1, 2]
(%i3) cflength: 2$
(%i4) cf ((1 + sqrt(5))/2);
(%o4) [1, 1, 1, 1, 1, 1, 1, 2]
(%i5) cflength: 3$
(%i6) cf ((1 + sqrt(5))/2);
(%o6) [1, 1, 1, 1, 1, 1, 1, 1, 1, 1, 2]
```

- A continued fraction can be evaluated by evaluating the arithmetic representation returned by **cfdisrep**.

```
(%i1) cflength: 3$
(%i2) cfdisrep (cf (sqrt (3)))$
(%i3) ev (%, number);
(%o3) 1.731707317073171
```

- Maxima does not know about operations on continued fractions outside of `cf`.

```
(%i1) cf ([1,1,1,1,1,2] * 3);
(%o1) [4, 1, 5, 2]
(%i2) cf ([1,1,1,1,1,2]) * 3;
(%o2) [3, 3, 3, 3, 3, 6]
```

**cfdisrep** (*list*)

Function

Constructs and returns an ordinary arithmetic expression of the form  $a + 1/(b + 1/(c + \dots))$  from the list representation of a continued fraction  $[a, b, c, \dots]$ .

```
(%i1) cf ([1, 2, -3] + [1, -2, 1]);
(%o1) [1, 1, 1, 2]
(%i2) cfdisrep (%);
(%o2) 1 + 1/(1 + 1/(1 + 1/2))
```

**cfexpand** (*x*)

Function

Returns a matrix of the numerators and denominators of the last (column 1) and next-to-last (column 2) convergents of the continued fraction *x*.

```
(%i1) cf (rat (ev (%pi, number)));
'rat' replaced 3.141592653589793 by 103993/33102 =3.141592653011902
(%o1) [3, 7, 15, 1, 292]
(%i2) cfexpand (%);
(%o2) [103993 355]
 [33102 113]
(%i3) %[1,1]/[%2,1], numer;
(%o3) 3.141592653011902
```

**cflength**

Option variable

Default value: 1

`cflength` controls the number of terms of the continued fraction the function `cf` will give, as the value `cflength` times the period. Thus the default is to give one period.

```
(%i1) cflength: 1$
(%i2) cf ((1 + sqrt(5))/2);
(%o2) [1, 1, 1, 1, 2]
(%i3) cflength: 2$
(%i4) cf ((1 + sqrt(5))/2);
(%o4) [1, 1, 1, 1, 1, 1, 2]
(%i5) cflength: 3$
(%i6) cf ((1 + sqrt(5))/2);
(%o6) [1, 1, 1, 1, 1, 1, 1, 1, 2]
```

**divsum** (*n*, *k*)

Function

**divsum** (*n*)

Function

**divsum** (*n*, *k*) returns the sum of the divisors of *n* raised to the *k*'th power.

**divsum** (*n*) returns the sum of the divisors of *n*.

```
(%i1) divsum (12);
(%o1) 28
(%i2) 1 + 2 + 3 + 4 + 6 + 12;
(%o2) 28
(%i3) divsum (12, 2);
(%o3) 210
(%i4) 1^2 + 2^2 + 3^2 + 4^2 + 6^2 + 12^2;
(%o4) 210
```

**euler** (*n*)

Function

Returns the *n*'th Euler number for nonnegative integer *n*.

For the Euler-Mascheroni constant, see **%gamma**.

```
(%i1) map (euler, [0, 1, 2, 3, 4, 5, 6, 7, 8, 9, 10]);
(%o1) [1, 0, - 1, 0, 5, 0, - 61, 0, 1385, 0, - 50521]
```

**factors\_only**

Option variable

Default value: **false**

Controls the value returned by **ifactors**. . The default **false** causes **ifactors** to provide information about multiplicities of the computed prime factors. If **factors\_only** is set to **true**, **ifactors** returns nothing more than a list of prime factors.

Example: See **ifactors**. .

**fib** (*n*)

Function

Returns the *n*'th Fibonacci number. **fib**(0) equal to 0 and **fib**(1) equal to 1, and **fib**(-*n*) equal to  $(-1)^{(n+1)} * \text{fib}(n)$ .

After calling **fib**, **prevfib** is equal to **fib** (*x* - 1), the Fibonacci number preceding the last one computed.

```
(%i1) map (fib, [0, 1, 2, 3, 4, 5, 6, 7, 8, 9, 10]);
(%o1) [0, 1, 1, 2, 3, 5, 8, 13, 21, 34, 55]
```

**fibtophi** (*expr*)

Function

Expresses Fibonacci numbers in *expr* in terms of the constant **%phi**, which is  $(1 + \sqrt{5})/2$ , approximately 1.61803399.

Examples:

```
(%i1) fibtophi (fib (n));
(%o1)
$$\frac{\%phi^n - (1 - \%phi)^n}{2 \%phi - 1}$$

(%i2) fib (n-1) + fib (n) - fib (n+1);
(%o2) - fib(n + 1) + fib(n) + fib(n - 1)
(%i3) fibtophi (%);
(%o3)
$$- \frac{\%phi^{n+1} - (1 - \%phi)^{n+1}}{2 \%phi - 1} + \frac{\%phi^n - (1 - \%phi)^n}{2 \%phi - 1} + \frac{\%phi^{n-1} - (1 - \%phi)^{n-1}}{2 \%phi - 1}$$

```

```

 2 %phi - 1
(%i4) ratsimp (%);
(%o4) 0

```

**ifactors** (*n*)

Function

For a positive integer  $n$  returns the factorization of  $n$ . If  $n=p_1^{e_1} \dots p_k^{e_k}$  is the decomposition of  $n$  into prime factors, `ifactors` returns `[[p1, e1], ..., [pk, ek]]`.

Factorization methods used are trial divisions by primes up to 9973, Pollard's rho and p-1 method and elliptic curves.

The value returned by `ifactors` is controlled by the option variable `factors_only`. The default `false` causes `ifactors` to provide information about the multiplicities of the computed prime factors. If `factors_only` is set to `true`, `ifactors` simply returns the list of prime factors.

```

(%i1) ifactors(51575319651600);
(%o1) [[2, 4], [3, 2], [5, 2], [1583, 1], [9050207, 1]]
(%i2) apply("?", map(lambda([u], u[1]^u[2]), %));
(%o2) 51575319651600
(%i3) ifactors(51575319651600), factors_only : true;
(%o3) [2, 3, 5, 1583, 9050207]

```

**igcdex** (*n*, *k*)

Function

Returns a list `[a, b, u]` where  $u$  is the greatest common divisor of  $n$  and  $k$ , and  $u$  is equal to  $a n + b k$ . The arguments  $n$  and  $k$  must be integers.

`igcdex` implements the Euclidean algorithm. See also `gcdex`.

The command `load(gcdex)` loads the function.

Examples:

```

(%i1) load(gcdex)$
(%i2) igcdex(30,18);
(%o2) [- 1, 2, 6]
(%i3) igcdex(1526757668, 7835626735736);
(%o3) [845922341123, - 164826435, 4]
(%i4) igcdex(fib(20), fib(21));
(%o4) [4181, - 2584, 1]

```

**inrt** (*x*, *n*)

Function

Returns the integer  $n$ 'th root of the absolute value of  $x$ .

```

(%i1) 1: [1, 2, 3, 4, 5, 6, 7, 8, 9, 10, 11, 12]$
(%i2) map (lambda ([a], inrt (10^a, 3)), 1);
(%o2) [2, 4, 10, 21, 46, 100, 215, 464, 1000, 2154, 4641, 10000]

```

**inv\_mod** (*n*, *m*)

Function

Computes the inverse of  $n$  modulo  $m$ . `inv_mod (n,m)` returns `false`, if  $n$  is a zero divisor modulo  $m$ .

```

(%i1) inv_mod(3, 41);
(%o1) 14
(%i2) ratsimp(3^-1), modulus=41;
(%o2) 14
(%i3) inv_mod(3, 42);
(%o3) false

```

**isqrt** (*x*)

Function

Returns the "integer square root" of the absolute value of  $x$ , which is an integer.

**jacobi** (*p*, *q*)

Function

Returns the Jacobi symbol of *p* and *q*.

```
(%i1) l: [1, 2, 3, 4, 5, 6, 7, 8, 9, 10, 11, 12]$
(%i2) map (lambda ([a], jacobi (a, 9)), l);
(%o2) [1, 1, 0, 1, 1, 0, 1, 1, 0, 1, 1, 0]
```

**lcm** (*expr\_1*, ..., *expr\_n*)

Function

Returns the least common multiple of its arguments. The arguments may be general expressions as well as integers.

load ("functs") loads this function.

**mod** (*x*, *y*)

Function

If *x* and *y* are real numbers and *y* is nonzero, return  $x - y * \text{floor}(x / y)$ . Further for all real *x*, we have  $\text{mod}(x, 0) = x$ . For a discussion of the definition  $\text{mod}(x, 0) = x$ , see Section 3.4, of "Concrete Mathematics," by Graham, Knuth, and Patashnik. The function  $\text{mod}(x, 1)$  is a sawtooth function with period 1 with  $\text{mod}(1, 1) = 0$  and  $\text{mod}(0, 1) = 0$ .

To find the principal argument (a number in the interval  $(-\pi, \pi]$ ) of a complex number, use the function  $x \mapsto \pi - \text{mod}(\pi - x, 2\pi)$ , where *x* is an argument.

When *x* and *y* are constant expressions ( $10 * \pi$ , for example), **mod** uses the same big float evaluation scheme that **floor** and **ceiling** uses. Again, it's possible, although unlikely, that **mod** could return an erroneous value in such cases.

For nonnumerical arguments *x* or *y*, **mod** knows several simplification rules:

```
(%i1) mod (x, 0);
(%o1) x
(%i2) mod (a*x, a*y);
(%o2) a mod(x, y)
(%i3) mod (0, x);
(%o3) 0
```

**next\_prime** (*n*)

Function

Returns the smallest prime bigger than *n*.

```
(%i1) next_prime(27);
(%o1) 29
```

**partfrac** (*expr*, *var*)

Function

Expands the expression *expr* in partial fractions with respect to the main variable *var*. **partfrac** does a complete partial fraction decomposition. The algorithm employed is based on the fact that the denominators of the partial fraction expansion (the factors of the original denominator) are relatively prime. The numerators can be written as linear combinations of denominators, and the expansion falls out.

```
(%i1) 1/(1+x)^2 - 2/(1+x) + 2/(2+x);
(%o1) 2 2 1
 ----- - ----- + -----
 x + 2 x + 1 (x + 1)^2

(%i2) ratsimp (%);
(%o2) x
 - -----
 3 2
 x + 4 x + 5 x + 2

(%i3) partfrac (% , x);
(%o3) 2 2 1
 ----- - ----- + -----
 x + 2 x + 1 (x + 1)^2
```



**power\_mod** (*a*, *n*, *m*)

Function

Uses a modular algorithm to compute  $a^n \bmod m$  where *a* and *n* are integers and *m* is a positive integer. If *n* is negative, `inv_mod` is used to find the modular inverse.

```
(%i1) power_mod(3, 15, 5);
(%o1) 2
(%i2) mod(3^15,5);
(%o2) 2
(%i3) power_mod(2, -1, 5);
(%o3) 3
(%i4) inv_mod(2,5);
(%o4) 3
```

**primep** (*n*)

Function

Primality test. If `primep` (*n*) returns `false`, *n* is a composite number and if it returns `true`, *n* is a prime number with very high probability.

For *n* less than 341550071728321 a deterministic version of Miller-Rabin's test is used. If `primep` (*n*) returns `true`, then *n* is a prime number.

For *n* bigger than 341550071728321 `primep` uses `primep_number_of_tests` Miller-Rabin's pseudo-primality tests and one Lucas pseudo-primality test. The probability that a non-prime *n* will pass one Miller-Rabin test is less than 1/4. Using the default value 25 for `primep_number_of_tests`, the probability of *n* being composite is much smaller than  $10^{-15}$ .

**primep\_number\_of\_tests**

Option variable

Default value: 25

Number of Miller-Rabin's tests used in `primep`.

**prev\_prime** (*n*)

Function

Returns the greatest prime smaller than *n*.

```
(%i1) prev_prime(27);
(%o1) 23
```

**qunit** (*n*)

Function

Returns the principal unit of the real quadratic number field `sqrt` (*n*) where *n* is an integer, i.e., the element whose norm is unity. This amounts to solving Pell's equation  $a^2 - n b^2 = 1$ .

```
(%i1) qunit (17);
(%o1) sqrt(17) + 4
(%i2) expand (% * (sqrt(17) - 4));
(%o2) 1
```

**totient** (*n*)

Function

Returns the number of integers less than or equal to *n* which are relatively prime to *n*.

**zerobern**

Option variable

Default value: `true`

When `zerobern` is `false`, `bern` excludes the Bernoulli numbers and `euler` excludes the Euler numbers which are equal to zero. See `bern` and `euler`.

**zeta** (*n*)

Function

Returns the Riemann zeta function. If *n* is a negative integer, 0, or a positive even integer, the Riemann zeta function simplifies to an exact value. For a positive even integer the option variable `zeta%pi` has to be `true` in addition (See `zeta%pi`). For a floating point or bigfloat number the Riemann zeta function is evaluated numerically. Maxima returns a noun form `zeta` (*n*) for all other arguments, including rational noninteger, and complex arguments, or for even integers, if `zeta%pi` has the value `false`.

`zeta(1)` is undefined, but Maxima knows the limit `limit(zeta(x), x, 1)` from above and below.

The Riemann zeta function distributes over lists, matrices, and equations.

See also `bfzeta` and `zeta%pi`.

Examples:

```
(%i1) zeta([-2, -1, 0, 0.5, 2, 3, 1+%i]);
(%o1) [0, - --, - --, - 1.460354508809586, ----, zeta(3),
 12 2 %pi 6
 zeta(%i + 1)]

(%i2) limit(zeta(x), x, 1, plus);
(%o2) inf
(%i3) limit(zeta(x), x, 1, minus);
(%o3) minf
```

**zeta%pi**

Option variable

Default value: `true`

When `zeta%pi` is `true`, `zeta` returns an expression proportional to  $\pi^n$  for even integer *n*. Otherwise, `zeta` returns a noun form `zeta` (*n*) for even integer *n*.

Examples:

```
(%i1) zeta%pi: true$
(%i2) zeta (4);
(%o2) 4
 %pi

 90

(%i3) zeta%pi: false$
(%i4) zeta (4);
(%o4) zeta(4)
```

**zn\_log** (*a*, *g*, *n*)

Function

**zn\_log** (*a*, *g*, *n*, [[*p1*, *e1*], ..., [*pk*, *ek*]])

Function

Computes the discrete logarithm. Let  $(\mathbb{Z}/n\mathbb{Z})^*$  be a cyclic group, *g* a primitive root modulo *n* and let *a* be a member of this group. `zn_log` (*a*, *g*, *n*) then solves the congruence  $g^x = a \pmod n$ .

The applied algorithm needs a prime factorization of `totient(n)`. This factorization might be time consuming as well and in some cases it can be useful to factor first and then to pass the list of factors to `zn_log` as the fourth argument. The list must be of the same form as the list returned by `ifactors(totient(n))` using the default option `factors_only : false`.

The algorithm uses a Pohlig-Hellman-reduction and Pollard's Rho-method for discrete logarithms. The run time of `zn_log` primarily depends on the bitlength of the totient's greatest prime factor.

See also `zn_primroot`, `zn_order`, `ifactors`, `totient`.

Examples:

`zn_log` (*a*, *g*, *n*) solves the congruence  $g^x = a \pmod n$ .

```

(%i1) n : 22$
(%i2) g : zn_primroot(n);
(%o2) 7
(%i3) ord_7 : zn_order(7, n);
(%o3) 10
(%i4) powers_7 : makelist(power_mod(g, x, n), x, 0, ord_7 - 1);
(%o4) [1, 7, 5, 13, 3, 21, 15, 17, 9, 19]
(%i5) zn_log(21, g, n);
(%o5) 5
(%i6) map(lambda([x], zn_log(x, g, n)), powers_7);
(%o6) [0, 1, 2, 3, 4, 5, 6, 7, 8, 9]

```

The optional fourth argument must be of the same form as the list returned by `ifactors(totient(n))`. The run time primarily depends on the bitlength of the totient's greatest prime factor.

```

(%i1) (p : 2^127-1, primep(p));
(%o1) true
(%i2) ifs : ifactors(p - 1)$
(%i3) g : zn_primroot(p, ifs);
(%o3) 43
(%i4) a : power_mod(g, 1234567890, p)$
(%i5) zn_log(a, g, p, ifs);
(%o5) 1234567890
(%i6) time(%o5);
(%o6) [1.204]
(%i7) f_max : last(ifs);
(%o7) [77158673929, 1]
(%i8) slength(printf(false, "~b", f_max[1]));
(%o8) 37

```

|                                                                                                      |          |
|------------------------------------------------------------------------------------------------------|----------|
| <b>zn_order</b> ( <i>x</i> , <i>n</i> )                                                              | Function |
| <b>zn_order</b> ( <i>x</i> , <i>n</i> , [[ <i>p1</i> , <i>e1</i> ], ..., [ <i>pk</i> , <i>ek</i> ]]) | Function |

Returns the order of *x* if it is a unit of the finite group  $(\mathbb{Z}/n\mathbb{Z})^*$  or returns **false**. *x* is a unit modulo *n* if it is coprime to *n*.

The applied algorithm needs a prime factorization of `totient(n)`. This factorization might be time consuming in some cases and it can be useful to factor first and then to pass the list of factors to `zn_log` as the third argument. The list must be of the same form as the list returned by `ifactors(totient(n))` using the default option `factors_only : false`.

See also `zn_primroot`, `ifactors`, `totient`.

Examples:

`zn_order` computes the order of the unit *x* in  $(\mathbb{Z}/n\mathbb{Z})^*$ .

```

(%i1) n : 22$
(%i2) g : zn_primroot(n);
(%o2) 7
(%i3) units_22 : sublist(makelist(i,i,1,21), lambda([x], gcd(x, n) = 1));
(%o3) [1, 3, 5, 7, 9, 13, 15, 17, 19, 21]
(%i4) (ord_7 : zn_order(7, n)) = totient(n);
(%o4) 10 = 10
(%i5) powers_7 : makelist(power_mod(g,i,n), i,0,ord_7 - 1);
(%o5) [1, 7, 5, 13, 3, 21, 15, 17, 9, 19]
(%i6) map(lambda([x], zn_order(x, n)), powers_7);
(%o6) [1, 10, 5, 10, 5, 2, 5, 10, 5, 10]
(%i7) map(lambda([x], ord_7/gcd(x, ord_7)), makelist(i, i,0,ord_7 - 1));
(%o7) [1, 10, 5, 10, 5, 2, 5, 10, 5, 10]
(%i8) totient(totient(n));

```

```
(%o8) 4
```

The optional third argument must be of the same form as the list returned by `ifactors(totient(n))`.

```
(%i1) (p : 2^142 + 217, primep(p));
(%o1) true
(%i2) ifs : ifactors(totient(p))$
(%i3) g : zn_primroot(p, ifs);
(%o3) 3
(%i4) is((ord_3 : zn_order(g, p, ifs)) = totient(p));
(%o4) true
(%i5) map(lambda([x], ord_3/zn_order(x, p, ifs)), makelist(i,i,2,15));
(%o5) [22, 1, 44, 10, 5, 2, 22, 2, 8, 2, 1, 1, 20, 1]
```

**zn\_primroot** (*n*) Function

**zn\_primroot** (*n*, [[*p1*, *e1*], ..., [*pk*, *ek*]]) Function

If the multiplicative group  $(\mathbb{Z}/n\mathbb{Z})^*$  is cyclic, `zn_primroot` computes the smallest primitive root modulo *n*.  $(\mathbb{Z}/n\mathbb{Z})^*$  is cyclic if *n* is equal to 2, 4,  $p^k$  or  $2 \cdot p^k$ , where *p* is prime and greater than 2 and *k* is a natural number. `zn_primroot` performs an according pretest if the option variable `zn_primroot_pretest` (default: `false`) is set to `true`. In any case the computation is limited by the upper bound `zn_primroot_limit`.

If  $(\mathbb{Z}/n\mathbb{Z})^*$  is not cyclic or if there is no primitive root up to `zn_primroot_limit`, `zn_primroot` returns `false`.

The applied algorithm needs a prime factorization of `totient(n)`. This factorization might be time consuming in some cases and it can be useful to factor first and then to pass the list of factors to `zn_log` as an additional argument. The list must be of the same form as the list returned by `ifactors(totient(n))` using the default option `factors_only : false`.

See also `zn_primroot_p`, `zn_order`, `ifactors`, `totient`.

Examples:

`zn_primroot` computes the smallest primitive root modulo *n* or returns `false`.

```
(%i1) n : 14$
(%i2) g : zn_primroot(n);
(%o2) 3
(%i3) zn_order(g, n) = totient(n);
(%o3) 6 = 6
(%i4) n : 15$
(%i5) zn_primroot(n);
(%o5) false
```

The optional second argument must be of the same form as the list returned by `ifactors(totient(n))`.

```
(%i1) (p : 2^142 + 217, primep(p));
(%o1) true
(%i2) ifs : ifactors(totient(p))$
(%i3) g : zn_primroot(p, ifs);
(%o3) 3
(%i4) [time(%o2), time(%o3)];
(%o4) [[15.556972], [0.004]]
(%i5) is(zn_order(g, p, ifs) = p - 1);
(%o5) true
(%i6) n : 2^142 + 216$
(%i7) ifs : ifactors(totient(n))$
(%i8) zn_primroot(n, ifs),
 zn_primroot_limit : 200, zn_primroot_verbose : true;
'zn_primroot' stopped at zn_primroot_limit = 200
(%o8) false
```

**zn\_primroot\_limit**

Option variable

Default value: 1000

If `zn_primroot.` cannot find a primitive root, it stops at this upper bound. If the option variable `zn_primroot_verbose.` (default: `false`) is set to `true`, a message will be printed when `zn_primroot_limit` is reached.

**zn\_primroot\_p** (*x*, *n*)

Function

**zn\_primroot\_p** (*x*, *n*, [[*p1*, *e1*], ..., [*pk*, *ek*]])

Function

Checks whether *x* is a primitive root in the multiplicative group  $(\mathbb{Z}/n\mathbb{Z})^*$ .

The applied algorithm needs a prime factorization of `totient(n)`. This factorization might be time consuming and in case `zn_primroot_p` will be consecutively applied to a list of candidates it can be useful to factor first and then to pass the list of factors to `zn_log` as a third argument. The list must be of the same form as the list returned by `ifactors(totient(n))` using the default option `factors_only : false`.

See also `zn_primroot`, `zn_order`, `ifactors`, `totient`.

Examples:

`zn_primroot_p` as a predicate function.

```
(%i1) n : 14$
(%i2) units_14 : sublist(makelist(i,i,1,13), lambda([i], gcd(i, n) = 1));
(%o2)
 [1, 3, 5, 9, 11, 13]
(%i3) zn_primroot_p(13, n);
(%o3)
 false
(%i4) sublist(units_14, lambda([x], zn_primroot_p(x, n)));
(%o4)
 [3, 5]
(%i5) map(lambda([x], zn_order(x, n)), units_14);
(%o5)
 [1, 6, 6, 3, 3, 2]
```

The optional third argument must be of the same form as the list returned by `ifactors(totient(n))`.

```
(%i1) (p : 2^142 + 217, primep(p));
(%o1)
 true
(%i2) ifs : ifactors(totient(p))$
(%i3) sublist(makelist(i,i,1,50), lambda([x], zn_primroot_p(x, p, ifs)));
(%o3)
 [3, 12, 13, 15, 21, 24, 26, 27, 29, 33, 38, 42, 48]
(%i4) [time(%o2), time(%o3)];
(%o4)
 [[7.748484], [0.036002]]
```

**zn\_primroot\_pretest**

Option variable

Default value: `false`

The multiplicative group  $(\mathbb{Z}/n\mathbb{Z})^*$  is cyclic if *n* is equal to 2, 4,  $p^k$  or  $2 \cdot p^k$ , where *p* is prime and greater than 2 and *k* is a natural number.

`zn_primroot_pretest` controls whether `zn_primroot.` will check if one of these cases occur before it computes the smallest primitive root. Only if `zn_primroot_pretest` is set to `true` this pretest will be performed.

**zn\_primroot\_verbose**

Option variable

Default value: `false`

Controls whether `zn_primroot.` prints a message when reaching `zn_primroot_limit.`



## 30 Symmetries

### 30.1 Introduction to Symmetries

`sym` is a package for working with symmetric groups of polynomials.

It was written for Macsyma-Symbolics by Annick Valibouze<sup>1</sup>. The algorithms are described in the following papers:

1. Fonctions symétriques et changements de bases<sup>2</sup>. Annick Valibouze. EUROCAL'87 (Leipzig, 1987), 323–332, Lecture Notes in Comput. Sci 378. Springer, Berlin, 1989.
2. Résolvantes et fonctions symétriques<sup>3</sup>. Annick Valibouze. Proceedings of the ACM-SIGSAM 1989 International Symposium on Symbolic and Algebraic Computation, ISSAC'89 (Portland, Oregon). ACM Press, 390–399, 1989.
3. Symbolic computation with symmetric polynomials, an extension to Macsyma<sup>4</sup>. Annick Valibouze. Computers and Mathematics (MIT, USA, June 13–17, 1989), Springer-Verlag, New York Berlin, 308–320, 1989.
4. Théorie de Galois Constructive. Annick Valibouze. Mémoire d'habilitation à diriger les recherches (HDR), Université P. et M. Curie (Paris VI), 1994.

### 30.2 Functions and Variables for Symmetries

#### 30.2.1 Changing bases

**comp2pui** (*n*, *L*) Function  
implements passing from the complete symmetric functions given in the list *L* to the elementary symmetric functions from 0 to *n*. If the list *L* contains fewer than *n*+1 elements, it will be completed with formal values of the type *h1*, *h2*, etc. If the first element of the list *L* exists, it specifies the size of the alphabet, otherwise the size is set to *n*.

```
(%i1) comp2pui (3, [4, g]);
 2
 2
(%o1) [4, g, 2 h2 - g , 3 h3 - g h2 + g (g - 2 h2)]
```

**ele2pui** (*m*, *L*) Function  
goes from the elementary symmetric functions to the complete functions. Similar to `comp2ele` and `comp2pui`.  
Other functions for changing bases: `comp2ele`.

**ele2comp** (*m*, *L*) Function  
Goes from the elementary symmetric functions to the complete functions. Similar to `comp2ele` and `comp2pui`.  
Other functions for changing bases: `comp2ele`.

**elem** (*ele*, *sym*, *lvar*) Function  
decomposes the symmetric polynomial *sym*, in the variables contained in the list *lvar*, in terms of the elementary symmetric functions given in the list *ele*. If the first element of *ele* is given, it will be the size of the alphabet, otherwise the size will be the degree of the polynomial *sym*. If values are missing in the list *ele*, formal values of the type *e1*, *e2*, etc. will be added. The polynomial *sym* may be given in three different forms: contracted (`elem` should then be 1, its default value), partitioned (`elem` should be 3), or extended

<sup>1</sup> [www-calfor.lip6.fr/~avb](http://www-calfor.lip6.fr/~avb)

<sup>2</sup> [www.stix.polytechnique.fr/publications/1984-1994.html](http://www.stix.polytechnique.fr/publications/1984-1994.html)

<sup>3</sup> [www-calfor.lip6.fr/~avb/DonneesTelechargeables/MesArticles/issac89ACMValibouze.pdf](http://www-calfor.lip6.fr/~avb/DonneesTelechargeables/MesArticles/issac89ACMValibouze.pdf)

<sup>4</sup> [www.stix.polytechnique.fr/publications/1984-1994.html](http://www.stix.polytechnique.fr/publications/1984-1994.html)

(i.e. the entire polynomial, and `elem` should then be 2). The function `pui` is used in the same way.

On an alphabet of size 3 with `e1`, the first elementary symmetric function, with value 7, the symmetric polynomial in 3 variables whose contracted form (which here depends on only two of its variables) is  $x^4 - 2xy$  decomposes as follows in elementary symmetric functions:

```
(%i1) elem ([3, 7], x^4 - 2*x*y, [x, y]);
(%o1) 7 (e3 - 7 e2 + 7 (49 - e2)) + 21 e3

+ (- 2 (49 - e2) - 2) e2

(%i2) ratsimp (%);
(%o2) 28 e3 + 2 e2^2 - 198 e2 + 2401
```

Other functions for changing bases: `comp2ele`.

### **mon2schur** (*L*)

Function

The list *L* represents the Schur function  $S_L$ : we have  $L = [i_1, i_2, \dots, i_q]$ , with  $i_1 \leq i_2 \leq \dots \leq i_q$ . The Schur function  $S_{i_1, i_2, \dots, i_q}$  is the minor of the infinite matrix  $h_{i-j}$ ,  $i \geq 1, j \geq 1$ , consisting of the  $q$  first rows and the columns  $i_1 + 1, i_2 + 2, \dots, i_q + q$ .

This Schur function can be written in terms of monomials by using `treinat` and `kostka`. The form returned is a symmetric polynomial in a contracted representation in the variables  $x_1, x_2, \dots$ .

```
(%i1) mon2schur ([1, 1, 1]);
(%o1) x1 x2 x3

(%i2) mon2schur ([3]);
(%o2) x1^2 x2^3 + x1^3 x2^2 + x1^3 x2^3

(%i3) mon2schur ([1, 2]);
(%o3) 2 x1^2 x2 x3 + x1^2 x2^2 + x1^3 x2^2
```

which means that for 3 variables this gives:

$$2 x_1^2 x_2 x_3 + x_1^2 x_2^2 + x_2^2 x_1^2 + x_1^2 x_3^2 + x_3^2 x_1^2 + x_2^2 x_3^2 + x_3^2 x_2^2$$

Other functions for changing bases: `comp2ele`.

### **multi\_elem** (*Lelem*, *multi\_pc*, *Lvar*)

Function

decomposes a multi-symmetric polynomial in the multi-contracted form *multi\_pc* in the groups of variables contained in the list of lists *Lvar* in terms of the elementary symmetric functions contained in *Lelem*.

```
(%i1) multi_elem ([[2, e1, e2], [2, f1, f2]], a*x + a^2 + x^3,
[[x, y], [a, b]]);
(%o1) - 2 f2 + f1 (f1 + e1) - 3 e1 e2 + e1^3

(%i2) ratsimp (%);
(%o2) - 2 f2 + f1^2 + e1 f1 - 3 e1 e2 + e1^3
```

Other functions for changing bases: `comp2ele`.

### **multi\_pui**

Function

is to the function `pui` what the function `multi_elem` is to the function `elem`.

```
(%i1) multi_pui ([[2, p1, p2], [2, t1, t2]], a*x + a^2 + x^3,
[[x, y], [a, b]]);
(%o1) t2 + p1 t1 + (3 p1 p2 t1) / 2 - (p1^3) / 2
```



**pui** (*L*, *sym*, *lvar*)

Function

decomposes the symmetric polynomial *sym*, in the variables in the list *lvar*, in terms of the power functions in the list *L*. If the first element of *L* is given, it will be the size of the alphabet, otherwise the size will be the degree of the polynomial *sym*. If values are missing in the list *L*, formal values of the type *p1*, *p2*, etc. will be added. The polynomial *sym* may be given in three different forms: contracted (**elem** should then be 1, its default value), partitioned (**elem** should be 3), or extended (i.e. the entire polynomial, and **elem** should then be 2). The function **pui** is used in the same way.

```
(%i1) pui;
(%o1)
1
(%i2) pui ([3, a, b], u*x*y*z, [x, y, z]);
2
a (a - b) u (a b - p3) u
(%o2) ----- - -----
6 3
(%i3) ratsimp (%);
3
(2 p3 - 3 a b + a) u
(%o3) -----
6
```

Other functions for changing bases: **comp2ele**.

**pui2comp** (*n*, *lpui*)

Function

renders the list of the first *n* complete functions (with the length first) in terms of the power functions given in the list *lpui*. If the list *lpui* is empty, the cardinal is *n*, otherwise it is its first element (as in **comp2ele** and **comp2pui**).

```
(%i1) pui2comp (2, []);
2
p2 + p1
(%o1) [2, p1, -----]
2
(%i2) pui2comp (3, [2, a1]);
2
a1 (p2 + a1)
2 p3 + ----- + a1 p2
2
p2 + a1
(%o2) [2, a1, -----, -----]
2 3
(%i3) ratsimp (%);
2 3
p2 + a1 2 p3 + 3 a1 p2 + a1
(%o3) [2, a1, -----, -----]
2 6
```

Other functions for changing bases: **comp2ele**.

**pui2ele** (*n*, *lpui*)

Function

effects the passage from power functions to the elementary symmetric functions. If the flag **pui2ele** is **girard**, it will return the list of elementary symmetric functions from 1 to *n*, and if the flag is **close**, it will return the *n*-th elementary symmetric function.

Other functions for changing bases: **comp2ele**.

**pui2educ** (*n*, *lpui*)

Function

*lpui* is a list whose first element is an integer *m*. **pui2educ** gives the first *n* power functions in terms of the first *m*.

```
(%i1) puireduc (3, [2]);
```

$$[2, p_1, p_2, p_1 p_2 - \frac{p_1^2 (p_1^2 - p_2)}{2}]$$

```
(%i2) ratsimp (%);
```

$$[2, p_1, p_2, \frac{3 p_1^3 p_2 - p_1^3}{2}]$$
**schur2comp** (*P*, *Lvar*)

Function

*P* is a polynomial in the variables of the list *Lvar*. Each of these variables represents a complete symmetric function. In *Lvar* the *i*-th complete symmetric function is represented by the concatenation of the letter *h* and the integer *i*: *hi*. This function expresses *P* in terms of Schur functions.

```
(%i1) schur2comp (h1*h2 - h3, [h1, h2, h3]);
```

$$s_{1, 2}$$

```
(%i2) schur2comp (a*h3, [h3]);
```

$$s_3 a$$
**30.2.2 Changing representations****cont2part** (*pc*, *lvar*)

Function

returns the partitioned polynomial associated to the contracted form *pc* whose variables are in *lvar*.

```
(%i1) pc: 2*a^3*b*x^4*y + x^5;
```

$$2 a^3 b x^4 y + x^5$$

```
(%i2) cont2part (pc, [x, y]);
```

$$[[1, 5, 0], [2 a^3 b, 4, 1]]$$
**contract** (*psym*, *lvar*)

Function

returns a contracted form (i.e. a monomial orbit under the action of the symmetric group) of the polynomial *psym* in the variables contained in the list *lvar*. The function **explode** performs the inverse operation. The function **tcontract** tests the symmetry of the polynomial.

```
(%i1) psym: explode (2*a^3*b*x^4*y, [x, y, z]);
```

$$2 a^3 b y z^4 + 2 a^3 b x z^4 + 2 a^3 b y z^3 + 2 a^3 b x z^3 + 2 a^3 b x y^4 + 2 a^3 b x^4 y$$

```
(%i2) contract (psym, [x, y, z]);
```

$$2 a^3 b x^4 y$$
**explode** (*pc*, *lvar*)

Function

returns the symmetric polynomial associated with the contracted form *pc*. The list *lvar* contains the variables.

```
(%i1) explode (a*x + 1, [x, y, z]);
```

$$a z + a y + a x + 1$$

**part2cont** (*ppart*, *lvar*)

Function

goes from the partitioned form to the contracted form of a symmetric polynomial. The contracted form is rendered with the variables in *lvar*.

```
(%i1) part2cont ([[2*a^3*b, 4, 1]], [x, y]);
 3 4
(%o1) 2 a b x y
```

**partpol** (*psym*, *lvar*)

Function

*psym* is a symmetric polynomial in the variables of the list *lvar*. This function returns its partitioned representation.

```
(%i1) partpol (-a*(x + y) + 3*x*y, [x, y]);
(%o1) [[3, 1, 1], [- a, 1, 0]]
```

**tcontract** (*pol*, *lvar*)

Function

tests if the polynomial *pol* is symmetric in the variables of the list *lvar*. If so, it returns a contracted representation like the function **contract**.

**tpartpol** (*pol*, *lvar*)

Function

tests if the polynomial *pol* is symmetric in the variables of the list *lvar*. If so, it returns its partitioned representation like the function **partpol**.

**30.2.3 Groups and orbits****direct** (*[p-1, ..., p-n]*, *y*, *f*, *[lvar-1, ..., lvar-n]*)

Function

calculates the direct image (see M. Giusti, D. Lazard et A. Valibouze, ISSAC 1988, Rome) associated to the function *f*, in the lists of variables *lvar-1, ..., lvar-n*, and in the polynomials *p-1, ..., p-n* in a variable *y*. The arity of the function *f* is important for the calculation. Thus, if the expression for *f* does not depend on some variable, it is useless to include this variable, and not including it will also considerably reduce the amount of computation.

```
(%i1) direct ([z^2 - e1*z + e2, z^2 - f1*z + f2],
 z, b*v + a*u, [[u, v], [a, b]]);
 2
(%o1) y - e1 f1 y
 2 2 2 2
 - 4 e2 f2 - (e1 - 2 e2) (f1 - 2 f2) + e1 f1
 + -----
 2
(%i2) ratsimp (%);
 2 2 2
(%o2) y - e1 f1 y + (e1 - 4 e2) f2 + e2 f1
```

```
(%i3) ratsimp (direct ([z^3-e1*z^2+e2*z-e3,z^2 - f1*z + f2],
 z, b*v + a*u, [[u, v], [a, b]]));
(%o3) y^6 - 2 e1 f1 y^5 + ((2 e1^2 - 6 e2) f2 + (2 e2 + e1^2) f1^2) y^4
+ ((9 e3 + 5 e1 e2 - 2 e1^3) f1 f2 + (- 2 e3 - 2 e1 e2) f1^3) y^3
+ ((9 e2^2 - 6 e1^2 e2 + e1^4) f2^2
+ (- 9 e1 e3 - 6 e2^2 + 3 e1^2 e2) f1^2 f2 + (2 e1 e3 + e2^2) f1^4) y^2
+ ((9 e1^2 - 27 e2) e3 + 3 e1 e2^2 - e1^3 e2) f1 f2^2
+ ((15 e2^2 - 2 e1^2) e3 - e1^2 e2^2) f1^3 f2 - 2 e2 e3 f1^5) y
+ (- 27 e3^2 + (18 e1 e2 - 4 e1^3) e3 - 4 e2^3 + e1^2 e2^2) f2^3
+ (27 e3^2 + (e1^3 - 9 e1 e2) e3 + e2^3) f1^2 f2^2
+ (e1 e2 e3 - 9 e3^2) f1^4 f2 + e3^2 f1^6
```

Finding the polynomial whose roots are the sums  $a + u$  where  $a$  is a root of  $z^2 - e_1 z + e_2$  and  $u$  is a root of  $z^2 - f_1 z + f_2$ .

```
(%i1) ratsimp (direct ([z^2 - e1*z + e2, z^2 - f1*z + f2],
 z, a + u, [[u], [a]]));
(%o1) y^4 + (- 2 f1 - 2 e1) y^3 + (2 f2 + f1^2 + 3 e1 f1 + 2 e2
+ e1^2) y^2 + ((- 2 f1 - 2 e1) f2 - e1 f1^2 + (- 2 e2 - e1^2) f1
- 2 e1 e2) y + f2^2 + (e1 f1 - 2 e2 + e1^2) f2 + e2 f1^2 + e1 e2 f1
+ e2^2
```

`direct` accepts two flags: `elementaires` and `puissances` (default) which allow decomposing the symmetric polynomials appearing in the calculation into elementary symmetric functions, or power functions, respectively.

Functions of `sym` used in this function:

`multi_orbit` (so `orbit`), `pui_direct`, `multi_elem` (so `elem`), `multi_pui` (so `pui`), `pui2ele`, `ele2pui` (if the flag `direct` is in `puissances`).

**multi\_orbit** ( $P$ , [ $lvar_1$ ,  $lvar_2$ , ...,  $lvar_p$ ]) Function  
 $P$  is a polynomial in the set of variables contained in the lists  $lvar_1$ ,  $lvar_2$ , ...,  $lvar_p$ . This function returns the orbit of the polynomial  $P$  under the action of the product of the symmetric groups of the sets of variables represented in these  $p$  lists.

```
(%i1) multi_orbit (a*x + b*y, [[x, y], [a, b]]);
(%o1) [b y + a x, a y + b x]
```

```
(%i2) multi_orbit (x + y + 2*a, [[x, y], [a, b, c]]);
(%o2) [y + x + 2 c, y + x + 2 b, y + x + 2 a]
```

Also see: `orbit` for the action of a single symmetric group.

**multsym** (*ppart\_1*, *ppart\_2*, *n*) Function  
 returns the product of the two symmetric polynomials in  $n$  variables by working only modulo the action of the symmetric group of order  $n$ . The polynomials are in their partitioned form.

Given the 2 symmetric polynomials in  $x, y$ :  $3*(x + y) + 2*x*y$  and  $5*(x^2 + y^2)$  whose partitioned forms are  $[[3, 1], [2, 1, 1]]$  and  $[[5, 2]]$ , their product will be

```
(%i1) multsym ([[3, 1], [2, 1, 1]], [[5, 2]], 2);
(%o1) [[10, 3, 1], [15, 3, 0], [15, 2, 1]]
```

that is  $10*(x^3*y + y^3*x) + 15*(x^2*y + y^2*x) + 15*(x^3 + y^3)$ .

Functions for changing the representations of a symmetric polynomial:

`contract`, `cont2part`, `explode`, `part2cont`, `partpol`, `tcontract`, `tpartpol`.

**orbit** (*P*, *lvar*) Function  
 computes the orbit of the polynomial  $P$  in the variables in the list *lvar* under the action of the symmetric group of the set of variables in the list *lvar*.

```
(%i1) orbit (a*x + b*y, [x, y]);
(%o1) [a y + b x, b y + a x]
(%i2) orbit (2*x + x^2, [x, y]);
(%o2) [y^2 + 2 y, x^2 + 2 x]
```

See also `multi_orbit` for the action of a product of symmetric groups on a polynomial.

**pui\_direct** (*orbite*, [*lvar\_1*, ..., *lvar\_n*], [*d\_1*, *d\_2*, ..., *d\_n*]) Function

Let  $f$  be a polynomial in  $n$  blocks of variables  $lvar_1, \dots, lvar_n$ . Let  $c_i$  be the number of variables in  $lvar_i$ , and  $SC$  be the product of  $n$  symmetric groups of degree  $c_1, \dots, c_n$ . This group acts naturally on  $f$ . The list *orbite* is the orbit, denoted  $SC(f)$ , of the function  $f$  under the action of  $SC$ . (This list may be obtained by the function `multi_orbit`.) The  $d_i$  are integers s.t.  $c_1 \leq d_1, c_2 \leq d_2, \dots, c_n \leq d_n$ .

Let  $SD$  be the product of the symmetric groups  $S_{d_1} \times S_{d_2} \times \dots \times S_{d_n}$ . The function `pui_direct` returns the first  $n$  power functions of  $SD(f)$  deduced from the power functions of  $SC(f)$ , where  $n$  is the size of  $SD(f)$ .

The result is in multi-contracted form w.r.t.  $SD$ , i.e. only one element is kept per orbit, under the action of  $SD$ .

```
(%i1) 1: [[x, y], [a, b]];
(%o1) [[x, y], [a, b]]
(%i2) pui_direct (multi_orbit (a*x + b*y, 1), 1, [2, 2]);
(%o2) [a x, 4 a b x y + a x^2]
(%i3) pui_direct (multi_orbit (a*x + b*y, 1), 1, [3, 2]);
(%o3) [2 a x, 4 a b x y + 2 a x^2, 3 a b x y + 2 a x^3,
 12 a^2 b x y + 4 a^3 b x y + 2 a^4 x^2,
 10 a^3 b x y + 5 a^4 b x y + 2 a^5 x^2,
 40 a^3 b x y + 15 a^4 b x y + 6 a^5 b x y + 2 a^6 x^2]
```

```
(%i4) pui_direct ([y + x + 2*c, y + x + 2*b, y + x + 2*a],
 [[x, y], [a, b, c]], [2, 3]);
(%o4) [3 x + 2 a, 6 x y + 3 x2 + 4 a x + 4 a2,
 9 x2 y + 12 a x y + 3 x3 + 6 a x2 + 12 a2 x + 8 a3]
```

### 30.2.4 Partitions

**kostka** (*part\_1*, *part\_2*) Function  
 written by P. Esperet, calculates the Kostka number of the partition *part\_1* and *part\_2*.

```
(%i1) kostka ([3, 3, 3], [2, 2, 1, 1, 1]);
(%o1) 6
```

**lgtreillis** (*n*, *m*) Function  
 returns the list of partitions of weight *n* and length *m*.

```
(%i1) lgtreillis (4, 2);
(%o1) [[3, 1], [2, 2]]
```

Also see: `ltreillis`, `treillis` and `treinat`.

**ltreillis** (*n*, *m*) Function  
 returns the list of partitions of weight *n* and length less than or equal to *m*.

```
(%i1) ltreillis (4, 2);
(%o1) [[4, 0], [3, 1], [2, 2]]
```

Also see: `lgtreillis`, `treillis` and `treinat`.

**treillis** (*n*) Function  
 returns all partitions of weight *n*.

```
(%i1) treillis (4);
(%o1) [[4], [3, 1], [2, 2], [2, 1, 1], [1, 1, 1, 1]]
```

See also: `lgtreillis`, `ltreillis` and `treinat`.

**treinat** (*part*) Function  
 retruns the list of partitions inferior to the partition *part* w.r.t. the natural order.

```
(%i1) treinat ([5]);
(%o1) [[5]]
(%i2) treinat ([1, 1, 1, 1, 1]);
(%o2) [[5], [4, 1], [3, 2], [3, 1, 1], [2, 2, 1], [2, 1, 1, 1],
 [1, 1, 1, 1, 1]]
(%i3) treinat ([3, 2]);
(%o3) [[5], [4, 1], [3, 2]]
```

See also: `lgtreillis`, `ltreillis` and `treillis`.

### 30.2.5 Polynomials and their roots

**ele2polynome** (*L*, *z*) Function  
 returns the polynomial in *z* s.t. the elementary symmetric functions of its roots are in the list *L* = [*e\_1*, ..., *e\_n*], where *n* is the degree of the polynomial and *e\_i* the *i*-th elementary symmetric function.

```
(%i1) ele2polynome ([2, e1, e2], z);
 2
(%o1) z - e1 z + e2
(%i2) polynome2ele (x^7 - 14*x^5 + 56*x^3 - 56*x + 22, x);
(%o2) [7, 0, - 14, 0, 56, 0, - 56, - 22]
(%i3) ele2polynome ([7, 0, -14, 0, 56, 0, -56, -22], x);
 7 5 3
(%o3) x - 14 x + 56 x - 56 x + 22
```

The inverse: `polynome2ele (P, z)`.

Also see: `polynome2ele`, `pui2polynome`.

### **polynome2ele** (*P*, *x*)

Function

gives the list  $l = [n, e_1, \dots, e_n]$  where  $n$  is the degree of the polynomial  $P$  in the variable  $x$  and  $e_i$  is the  $i$ -th elementary symmetric function of the roots of  $P$ .

```
(%i1) polynome2ele (x^7 - 14*x^5 + 56*x^3 - 56*x + 22, x);
(%o1) [7, 0, - 14, 0, 56, 0, - 56, - 22]
(%i2) ele2polynome ([7, 0, -14, 0, 56, 0, -56, -22], x);
 7 5 3
(%o2) x - 14 x + 56 x - 56 x + 22
```

The inverse: `ele2polynome (l, x)`

### **prodrac** (*L*, *k*)

Function

$L$  is a list containing the elementary symmetric functions on a set  $A$ . `prodrac` returns the polynomial whose roots are the  $k$  by  $k$  products of the elements of  $A$ .

Also see `somrac`.

### **pui2polynome** (*x*, *lpui*)

Function

calculates the polynomial in  $x$  whose power functions of the roots are given in the list *lpui*.

```
(%i1) pui;
(%o1) 1
(%i2) kill(labels);
(%o2) done
(%i1) polynome2ele (x^3 - 4*x^2 + 5*x - 1, x);
(%o1) [3, 4, 5, 1]
(%i2) ele2pui (3, %);
(%o2) [3, 4, 6, 7]
(%i3) pui2polynome (x, %);
 3 2
(%o3) x - 4 x + 5 x - 1
```

See also: `polynome2ele`, `ele2polynome`.

### **somrac** (*L*, *k*)

Function

The list  $L$  contains elementary symmetric functions of a polynomial  $P$ . The function computes the polynomial whose roots are the  $k$  by  $k$  distinct sums of the roots of  $P$ .

Also see `prodrac`.

## 30.2.6 Resolvents

### **resolvante** (*P*, *x*, *f*, [*x*<sub>1</sub>, ..., *x*<sub>*d*</sub>])

Function

calculates the resolvent of the polynomial  $P$  in  $x$  of degree  $n \geq d$  by the function  $f$  expressed in the variables  $x_1, \dots, x_d$ . For efficiency of computation it is important to not include in the list  $[x_1, \dots, x_d]$  variables which do not appear in the transformation function  $f$ .

To increase the efficiency of the computation one may set flags in **resolvante** so as to use appropriate algorithms:

If the function  $f$  is unitary:

- A polynomial in a single variable,
- linear,
- alternating,
- a sum,
- symmetric,
- a product,
- the function of the Cayley resolvent (usable up to degree 5)

$$(x_1x_2 + x_2x_3 + x_3x_4 + x_4x_5 + x_5x_1 - (x_1x_3 + x_3x_5 + x_5x_2 + x_2x_4 + x_4x_1))^2$$

general,

the flag of **resolvante** may be, respectively:

- unitaire,
- lineaire,
- alternee,
- somme,
- produit,
- cayley,
- generale.

```
(%i1) resolvante: unitaire$
(%i2) resolvante (x^7 - 14*x^5 + 56*x^3 - 56*x + 22, x, x^3 - 1,
[x]);

" resolvante unitaire " [7, 0, 28, 0, 168, 0, 1120, - 154, 7840,
- 2772, 56448, - 33880,

413952, - 352352, 3076668, - 3363360, 23114112, - 30494464,

175230832, - 267412992, 1338886528, - 2292126760]
3 6 3 9 6 3
[x - 1, x - 2 x + 1, x - 3 x + 3 x - 1,

12 9 6 3 15 12 9 6 3
x - 4 x + 6 x - 4 x + 1, x - 5 x + 10 x - 10 x + 5 x

- 1, x - 6 x + 15 x - 20 x + 15 x - 6 x + 1,

21 18 15 12 9 6 3
x - 7 x + 21 x - 35 x + 35 x - 21 x + 7 x - 1]
[- 7, 1127, - 6139, 431767, - 5472047, 201692519, - 3603982011]
7 6 5 4 3 2
(%o2) y + 7 y - 539 y - 1841 y + 51443 y + 315133 y

+ 376999 y + 125253

(%i3) resolvante: lineaire$
```



```
(%i4) resolvante (x^4 - 1, x, x1 + 2*x2 + 3*x3, [x1, x2, x3]);

" resolvante lineaire "
 24 20 16 12 8
(%o4) y + 80 y + 7520 y + 1107200 y + 49475840 y
 4
 + 344489984 y + 655360000
(%i5) resolvante: general$
(%i6) resolvante (x^4 - 1, x, x1 + 2*x2 + 3*x3, [x1, x2, x3]);

" resolvante generale "
 24 20 16 12 8
(%o6) y + 80 y + 7520 y + 1107200 y + 49475840 y
 4
 + 344489984 y + 655360000
(%i7) resolvante (x^4 - 1, x, x1 + 2*x2 + 3*x3, [x1, x2, x3, x4]);

" resolvante generale "
 24 20 16 12 8
(%o7) y + 80 y + 7520 y + 1107200 y + 49475840 y
 4
 + 344489984 y + 655360000
(%i8) direct ([x^4 - 1], x, x1 + 2*x2 + 3*x3, [[x1, x2, x3]]);
 24 20 16 12 8
(%o8) y + 80 y + 7520 y + 1107200 y + 49475840 y
 4
 + 344489984 y + 655360000
(%i9) resolvante :lineaire$
(%i10) resolvante (x^4 - 1, x, x1 + x2 + x3, [x1, x2, x3]);

" resolvante lineaire "
 4
(%o10) y - 1
(%i11) resolvante: symetrique$
(%i12) resolvante (x^4 - 1, x, x1 + x2 + x3, [x1, x2, x3]);

" resolvante symetrique "
 4
(%o12) y - 1
(%i13) resolvante (x^4 + x + 1, x, x1 - x2, [x1, x2]);

" resolvante symetrique "
 6 2
(%o13) y - 4 y - 1
(%i14) resolvante: alternee$
(%i15) resolvante (x^4 + x + 1, x, x1 - x2, [x1, x2]);

" resolvante alternee "
 12 8 6 4 2
(%o15) y + 8 y + 26 y - 112 y + 216 y + 229
(%i16) resolvante: produit$
```

```
(%i17) resolvante (x^7 - 7*x + 3, x, x1*x2*x3, [x1, x2, x3]);

" resolvante produit "
 35 33 29 28 27 26
(%o17) y - 7 y - 1029 y + 135 y + 7203 y - 756 y
 24 23 22 21 20
+ 1323 y + 352947 y - 46305 y - 2463339 y + 324135 y
 19 18 17 15
- 30618 y - 453789 y - 40246444 y + 282225202 y
 14 12 11 10
- 44274492 y + 155098503 y + 12252303 y + 2893401 y
 9 8 7 6
- 171532242 y + 6751269 y + 2657205 y - 94517766 y
 5 3
- 3720087 y + 26040609 y + 14348907
(%i18) resolvante: symetrique$
(%i19) resolvante (x^7 - 7*x + 3, x, x1*x2*x3, [x1, x2, x3]);

" resolvante symetrique "
 35 33 29 28 27 26
(%o19) y - 7 y - 1029 y + 135 y + 7203 y - 756 y
 24 23 22 21 20
+ 1323 y + 352947 y - 46305 y - 2463339 y + 324135 y
 19 18 17 15
- 30618 y - 453789 y - 40246444 y + 282225202 y
 14 12 11 10
- 44274492 y + 155098503 y + 12252303 y + 2893401 y
 9 8 7 6
- 171532242 y + 6751269 y + 2657205 y - 94517766 y
 5 3
- 3720087 y + 26040609 y + 14348907
(%i20) resolvante: cayley$
(%i21) resolvante (x^5 - 4*x^2 + x + 1, x, a, []);

" resolvante de Cayley "
 6 5 4 3 2
(%o21) x - 40 x + 4080 x - 92928 x + 3772160 x + 37880832 x
 + 93392896
```

For the Cayley resolvent, the 2 last arguments are neutral and the input polynomial must necessarily be of degree 5.

See also:

resolvante\_bipartite, resolvante\_produit\_sym,  
 resolvante\_unitaire, resolvante\_alterneel, resolvante\_klein,  
 resolvante\_klein3, resolvante\_vierer, resolvante\_diedrale.

**resolvante\_alternee1** ( $P, x$ ) Function  
 calculates the transformation  $P(x)$  of degree  $n$  by the function  $\prod_{1 \leq i < j \leq n-1} (x_i - x_j)$ .

See also:

resolvante\_produit\_sym, resolvante\_unitaire,  
 resolvante, resolvante\_klein, resolvante\_klein3,  
 resolvante\_vierer, resolvante\_diedrale, resolvante\_bipartite.

**resolvante\_bipartite** ( $P, x$ ) Function  
 calculates the transformation of  $P(x)$  of even degree  $n$  by the function  $x_1 x_2 \cdots x_{n/2} + x_{n/2+1} \cdots x_n$ .

```
(%i1) resolvante_bipartite (x^6 + 108, x);
 10 8 6 4
(%o1) y - 972 y + 314928 y - 34012224 y
```

See also:

resolvante\_produit\_sym, resolvante\_unitaire,  
 resolvante, resolvante\_klein, resolvante\_klein3,  
 resolvante\_vierer, resolvante\_diedrale, resolvante\_alternee1.

**resolvante\_diedrale** ( $P, x$ ) Function  
 calculates the transformation of  $P(x)$  by the function  $x_1 x_2 + x_3 x_4$ .

```
(%i1) resolvante_diedrale (x^5 - 3*x^4 + 1, x);
 15 12 11 10 9 8 7
(%o1) x - 21 x - 81 x - 21 x + 207 x + 1134 x + 2331 x
 6 5 4 3 2
 - 945 x - 4970 x - 18333 x - 29079 x - 20745 x - 25326 x
 - 697
```

See also:

resolvante\_produit\_sym, resolvante\_unitaire,  
 resolvante\_alternee1, resolvante\_klein, resolvante\_klein3,  
 resolvante\_vierer, resolvante.

**resolvante\_klein** ( $P, x$ ) Function  
 calculates the transformation of  $P(x)$  by the function  $x_1 x_2 x_4 + x_4$ .

See also:

resolvante\_produit\_sym, resolvante\_unitaire,  
 resolvante\_alternee1, resolvante, resolvante\_klein3,  
 resolvante\_vierer, resolvante\_diedrale.

**resolvante\_klein3** ( $P, x$ ) Function  
 calculates the transformation of  $P(x)$  by the function  $x_1 x_2 x_4 + x_4$ .

See also:

resolvante\_produit\_sym, resolvante\_unitaire,  
 resolvante\_alternee1, resolvante\_klein, resolvante,  
 resolvante\_vierer, resolvante\_diedrale.

**resolvante\_produit\_sym** ( $P, x$ ) Function  
 calculates the list of all product resolvents of the polynomial  $P(x)$ .

```
(%i1) resolvante_produit_sym (x^5 + 3*x^4 + 2*x - 1, x);
 5 4 10 8 7 6 5
(%o1) [y + 3 y + 2 y - 1, y - 2 y - 21 y - 31 y - 14 y
 4 3 2 10 8 7 6 5 4
 - y + 14 y + 3 y + 1, y + 3 y + 14 y - y - 14 y - 31 y
 3 2 5 4
 - 21 y - 2 y + 1, y - 2 y - 3 y - 1, y - 1]
(%i2) resolvante: produit$
(%i3) resolvante (x^5 + 3*x^4 + 2*x - 1, x, a*b*c, [a, b, c]);

" resolvante produit "
 10 8 7 6 5 4 3 2
(%o3) y + 3 y + 14 y - y - 14 y - 31 y - 21 y - 2 y + 1
```

See also:

resolvante, resolvante\_unitaire,  
 resolvante\_alternee1, resolvante\_klein,  
 resolvante\_klein3, resolvante\_vierer,  
 resolvante\_diedrale.

### resolvante\_unitaire ( $P, Q, x$ )

Function

computes the resolvent of the polynomial  $P(x)$  by the polynomial  $Q(x)$ .

See also:

resolvante\_produit\_sym, resolvante,  
 resolvante\_alternee1, resolvante\_klein, resolvante\_klein3,  
 resolvante\_vierer, resolvante\_diedrale.

### resolvante\_vierer ( $P, x$ )

Function

computes the transformation of  $P(x)$  by the function  $x_1 x_2 - x_3 x_4$ .

See also:

resolvante\_produit\_sym, resolvante\_unitaire,  
 resolvante\_alternee1, resolvante\_klein, resolvante\_klein3,  
 resolvante, resolvante\_diedrale.

## 30.2.7 Miscellaneous

### multinomial ( $r, part$ )

Function

where  $r$  is the weight of the partition  $part$ . This function returns the associate multinomial coefficient: if the parts of  $part$  are  $i_1, i_2, \dots, i_k$ , the result is  $r!/(i_1! i_2! \dots i_k!)$ .

### permut ( $L$ )

Function

returns the list of permutations of the list  $L$ .

## 31 Groups

### 31.1 Functions and Variables for Groups

**todd\_coxeter** (*relations*, *subgroup*)

Function

**todd\_coxeter** (*relations*)

Function

Find the order of  $G/H$  where  $G$  is the Free Group modulo *relations*, and  $H$  is the subgroup of  $G$  generated by *subgroup*. *subgroup* is an optional argument, defaulting to  $[]$ . In doing this it produces a multiplication table for the right action of  $G$  on  $G/H$ , where the cosets are enumerated  $[H, Hg_2, Hg_3, \dots]$ . This can be seen internally in the variable `todd_coxeter_state`.

Example:

```
(%i1) symet(n):=create_list(
 if (j - i) = 1 then (p(i,j))<3> else
 if (not i = j) then (p(i,j))<2> else
 p(i,i) , j, 1, n-1, i, 1, j);

(%o1) symet(n) := create_list(if j - i = 1 then p(i, j)
 else (if not i = j then p(i, j)
 else p(i, i)), j, 1, n - 1,
 i, 1, j)
(%i2) p(i,j) := concat(x,i).concat(x,j);
(%o2) p(i, j) := concat(x, i) . concat(x, j)
(%i3) symet(5);
(%o3) [x1<2>, (x1 . x2)<3>, x2<2>, (x1 . x3)<2>, (x2 . x3)<3>,
 x3<2>, (x1 . x4)<2>, (x2 . x4)<2>, (x3 . x4)<3>, x4<2>]
(%i4) todd_coxeter(%o3);

Rows tried 426
(%o4) 120
(%i5) todd_coxeter(%o3,[x1]);

Rows tried 213
(%o5) 60
(%i6) todd_coxeter(%o3,[x1,x2]);

Rows tried 71
(%o6) 20
```



## 32 Runtime Environment

### 32.1 Introduction for Runtime Environment

`maxima-init.mac` is a file which is loaded automatically when Maxima starts. You can use `maxima-init.mac` to customize your Maxima environment. `maxima-init.mac`, if it exists, is typically placed in the directory named by `maxima_userdir`, although it can be in any directory searched by the function `file_search`.

Here is an example `maxima-init.mac` file:

```
setup_autoload ("specfun.mac", ultraspherical, assoc_legendre_p);
showtime:all;
```

In this example, `setup_autoload` tells Maxima to load the specified file (`specfun.mac`) if any of the functions (`ultraspherical`, `assoc_legendre_p`) are called but not yet defined. Thus you needn't remember to load the file before calling the functions.

The statement `showtime: all` tells Maxima to set the `showtime` variable. The `maxima-init.mac` file can contain any other assignments or other Maxima statements.

### 32.2 Interrupts

The user can stop a time-consuming computation with the `^C` (control-C) character. The default action is to stop the computation and print another user prompt. In this case, it is not possible to restart a stopped computation.

If the Lisp variable `*debugger-hook*` is set to `nil`, by executing

```
:lisp (setq *debugger-hook* nil)
```

then upon receiving `^C`, Maxima will enter the Lisp debugger, and the user may use the debugger to inspect the Lisp environment. The stopped computation can be restarted by entering `continue` in the Lisp debugger. The means of returning to Maxima from the Lisp debugger (other than running the computation to completion) is different for each version of Lisp.

On Unix systems, the character `^Z` (control-Z) causes Maxima to stop altogether, and control is returned to the shell prompt. The `fg` command causes Maxima to resume from the point at which it was stopped.

### 32.3 Functions and Variables for Runtime Environment

#### **maxima\_tempdir**

System variable

`maxima_tempdir` names the directory in which Maxima creates some temporary files. In particular, temporary files for plotting are created in `maxima_tempdir`.

The initial value of `maxima_tempdir` is the user's home directory, if Maxima can locate it; otherwise Maxima makes a guess about a suitable directory.

`maxima_tempdir` may be assigned a string which names a directory.

#### **maxima\_userdir**

System variable

`maxima_userdir` names a directory which Maxima searches to find Maxima and Lisp files. (Maxima searches some other directories as well; `file_search_maxima` and `file_search_lisp` are the complete lists.)

The initial value of `maxima_userdir` is a subdirectory of the user's home directory, if Maxima can locate it; otherwise Maxima makes a guess about a suitable directory.

`maxima_userdir` may be assigned a string which names a directory. However, assigning to `maxima_userdir` does not automatically change `file_search_maxima` and `file_search_lisp`; those variables must be changed separately.

**room** () Function  
**room** (*true*) Function  
**room** (*false*) Function

Prints out a description of the state of storage and stack management in Maxima. **room** calls the Lisp function of the same name.

- **room** () prints out a moderate description.
- **room** (*true*) prints out a verbose description.
- **room** (*false*) prints out a terse description.

**sstatus** (*keyword*, *item*) Function

When *keyword* is the symbol **feature**, *item* is put on the list of system features. After **sstatus** (*keyword*, *item*) is executed, **status** (**feature**, *item*) returns **true**. If *keyword* is the symbol **nofeature**, *item* is deleted from the list of system features. This can be useful for package writers, to keep track of what features they have loaded in.

See also **status**.

**status** (*feature*) Function

**status** (*feature*, *item*) Function

Returns information about the presence or absence of certain system-dependent features.

- **status** (*feature*) returns a list of system features. These include Lisp version, operating system type, etc. The list may vary from one Lisp type to another.
- **status** (*feature*, *item*) returns **true** if *item* is on the list of items returned by **status** (*feature*) and **false** otherwise. **status** quotes the argument *item*. The quote-quote operator **''** defeats quotation. A feature whose name contains a special character, such as a hyphen, must be given as a string argument. For example, **status** (*feature*, "ansi-cl").

See also **sstatus**.

The variable **features** contains a list of features which apply to mathematical expressions. See **features** and **featurep** for more information.

**system** (*command*) Function

Executes *command* as a separate process. The command is passed to the default shell for execution. **system** is not supported by all operating systems, but generally exists in Unix and Unix-like environments.

Supposing **\_hist.out** is a list of frequencies which you wish to plot as a bar graph using **xgraph**.

```
(%i1) (with_stdout("_hist.out",
 for i:1 thru length(hist) do (
 print(i,hist[i]))),
 system("xgraph -bar -brw .7 -nl < _hist.out"));
```

In order to make the plot be done in the background (returning control to Maxima) and remove the temporary file after it is done do:

```
system("(xgraph -bar -brw .7 -nl < _hist.out; rm -f _hist.out)&")
```

**time** (%o1, %o2, %o3, ...) Function

Returns a list of the times, in seconds, taken to compute the output lines %o1, %o2, %o3, ... The time returned is Maxima's estimate of the internal computation time, not the elapsed time. **time** can only be applied to output line variables; for any other variables, **time** returns **unknown**.

Set **showtime**: **true** to make Maxima print out the computation time and elapsed time with each output line.



**timedate ()** Function  
**timedate (T)** Function

**timedate()** with no argument returns a string representing the current time and date. The string has the format `YYYY-MM-DD HH:MM:SS[+|-]ZZ:ZZ`, where the fields are year, month, day, hours, minutes, seconds, and time zone offset in hours and minutes.

**timedate(T)** returns the time *T* as a string with the format `YYYY-MM-DD HH:MM:SS[+|-]ZZ:ZZ`. *T* is interpreted as the number of seconds since midnight, January 1, 1900, as returned by **absolute\_real\_time**.

Example:

**timedate** with no argument returns a string representing the current time and date.

```
(%i1) d : timedate ();
(%o1) 2010-06-08 04:08:09+01:00
(%i2) print ("timedate reports current time", d) $
timedate reports current time 2010-06-08 04:08:09+01:00
```

**timedate** with an argument returns a string representing the argument.

```
(%i1) timedate (0);
(%o1) 1900-01-01 01:00:00+01:00
(%i2) timedate (absolute_real_time () - 7*24*3600);
(%o2) 2010-06-01 04:19:51+01:00
```

**absolute\_real\_time ()** Function

Returns the number of seconds since midnight, January 1, 1900 UTC. The return value is an integer.

See also **elapsed\_real\_time** and **elapsed\_run\_time**.

Example:

```
(%i1) absolute_real_time ();
(%o1) 3385045277
(%i2) 1900 + absolute_real_time () / (365.25 * 24 * 3600);
(%o2) 2007.265612087104
```

**elapsed\_real\_time ()** Function

Returns the number of seconds (including fractions of a second) since Maxima was most recently started or restarted. The return value is a floating-point number.

See also **absolute\_real\_time** and **elapsed\_run\_time**.

Example:

```
(%i1) elapsed_real_time ();
(%o1) 2.559324
(%i2) expand ((a + b)^500)$
(%i3) elapsed_real_time ();
(%o3) 7.552087
```

**elapsed\_run\_time ()** Function

Returns an estimate of the number of seconds (including fractions of a second) which Maxima has spent in computations since Maxima was most recently started or restarted. The return value is a floating-point number.

See also **absolute\_real\_time** and **elapsed\_real\_time**.

Example:

```
(%i1) elapsed_run_time ();
(%o1) 0.04
(%i2) expand ((a + b)^500)$
(%i3) elapsed_run_time ();
(%o3) 1.26
```



## 33 Miscellaneous Options

### 33.1 Introduction to Miscellaneous Options

In this section various options are discussed which have a global effect on the operation of Maxima. Also various lists such as the list of all user defined functions, are discussed.

### 33.2 Share

The Maxima "share" directory contains programs and other files of interest to Maxima users, but not part of the core implementation of Maxima. These programs are typically loaded via `load` or `setup_autoload`.

`:lisp *maxima-sharedir*` displays the location of the share directory within the user's file system.

`printfile ("share.usg")` prints an out-of-date list of share packages. Users may find it more informative to browse the share directory using a file system browser.

### 33.3 Functions and Variables for Miscellaneous Options

#### **askexp**

System variable

When `asksign` is called, `askexp` is the expression `asksign` is testing.

At one time, it was possible for a user to inspect `askexp` by entering a Maxima break with control-A.

#### **genindex**

Option variable

Default value: `i`

`genindex` is the alphabetic prefix used to generate the next variable of summation when necessary.

#### **gensumnum**

Option variable

Default value: `0`

`gensumnum` is the numeric suffix used to generate the next variable of summation. If it is set to `false` then the index will consist only of `genindex` with no numeric suffix.

#### **gensym** ()

Function

#### **gensym** (x)

Function

`gensym()` creates and returns a fresh symbol.

The name of the new-symbol is the concatenation of a prefix, which defaults to "g", and a suffix, which is the decimal representation of a number that defaults to the value of a Lisp internal counter.

If `x` is supplied, and is a string, then that string is used as a prefix instead of "g" for this call to `gensym` only.

If `x` is supplied, and is an integer, then that integer, instead of the value of the internal Lisp integer, is used as the suffix for this call to `gensym` only.

If and only if no explicit suffix is supplied, the Lisp internal integer is incremented after it is used.

Examples:

```
(%i1) gensym();
(%o1) g887
(%i2) gensym("new");
(%o2) new888
(%i3) gensym(123);
(%o3) g123
```

**packagefile**

Option variable

Default value: `false`

Package designers who use `save` or `translate` to create packages (files) for others to use may want to set `packagefile: true` to prevent information from being added to Maxima's information-lists (e.g. `values`, `functions`) except where necessary when the file is loaded in. In this way, the contents of the package will not get in the user's way when he adds his own data. Note that this will not solve the problem of possible name conflicts. Also note that the flag simply affects what is output to the package file. Setting the flag to `true` is also useful for creating Maxima init files.

**remvalue** (*name\_1*, ..., *name\_n*)

Function

**remvalue** (*all*)

Function

Removes the values of user variables *name\_1*, ..., *name\_n* (which can be subscripted) from the system.

`remvalue (all)` removes the values of all variables in `values`, the list of all variables given names by the user (as opposed to those which are automatically assigned by Maxima).

See also `values`.

**rncombine** (*expr*)

Function

Transforms *expr* by combining all terms of *expr* that have identical denominators or denominators that differ from each other by numerical factors only. This is slightly different from the behavior of `combine`, which collects terms that have identical denominators.

Setting `pformat: true` and using `combine` yields results similar to those that can be obtained with `rncombine`, but `rncombine` takes the additional step of cross-multiplying numerical denominator factors. This results in neater forms, and the possibility of recognizing some cancellations.

`load(rncomb)` loads this function.

**setup\_autoload** (*filename*, *function\_1*, ..., *function\_n*)

Function

Specifies that if any of *function\_1*, ..., *function\_n* are referenced and not yet defined, *filename* is loaded via `load`. *filename* usually contains definitions for the functions specified, although that is not enforced.

`setup_autoload` does not work for array functions.

`setup_autoload` quotes its arguments.

Example:

```
(%i1) legendre_p (1, %pi);
(%o1) legendre_p(1, %pi)
(%i2) setup_autoload ("specfun.mac", legendre_p, ultraspherical);
(%o2) done
(%i3) ultraspherical (2, 1/2, %pi);
Warning - you are redefining the Macsyma function ultraspherical
Warning - you are redefining the Macsyma function legendre_p
2
3 (%pi - 1)
(%o3) ----- + 3 (%pi - 1) + 1
 2
(%i4) legendre_p (1, %pi);
(%o4) %pi
(%i5) legendre_q (1, %pi);
 %pi + 1
 %pi log(-----)
 1 - %pi
(%o5) ----- - 1
 2
```

|                                                                       |          |
|-----------------------------------------------------------------------|----------|
| <b>tcl_output</b> ( <i>list</i> , <i>i0</i> , <i>skip</i> )           | Function |
| <b>tcl_output</b> ( <i>list</i> , <i>i0</i> )                         | Function |
| <b>tcl_output</b> ([ <i>list_1</i> , ..., <i>list_n</i> ], <i>i</i> ) | Function |

Prints elements of a list enclosed by curly braces { }, suitable as part of a program in the Tcl/Tk language.

**tcl\_output** (*list*, *i0*, *skip*) prints *list*, beginning with element *i0* and printing elements *i0* + *skip*, *i0* + 2 *skip*, etc.

**tcl\_output** (*list*, *i0*) is equivalent to **tcl\_output** (*list*, *i0*, 2).

**tcl\_output** ([*list\_1*, ..., *list\_n*], *i*) prints the *i*'th elements of *list\_1*, ..., *list\_n*.

Examples:

```
(%i1) tcl_output ([1, 2, 3, 4, 5, 6], 1, 3)$
```

```
{1.000000000 4.000000000
}
```

```
(%i2) tcl_output ([1, 2, 3, 4, 5, 6], 2, 3)$
```

```
{2.000000000 5.000000000
}
```

```
(%i3) tcl_output ([3/7, 5/9, 11/13, 13/17], 1)$
```

```
{{(RAT SIMP) 3 7} {(RAT SIMP) 11 13}
}
```

```
(%i4) tcl_output ([x1, y1, x2, y2, x3, y3], 2)$
```

```
{$Y1 $Y2 $Y3
}
```

```
(%i5) tcl_output ([[1, 2, 3], [11, 22, 33]], 1)$
```

```
{SIMP 1.000000000 11.000000000
}
```



## 34 Rules and Patterns

### 34.1 Introduction to Rules and Patterns

This section describes user-defined pattern matching and simplification rules. There are two groups of functions which implement somewhat different pattern matching schemes. In one group are `tellsimp`, `tellsimpafter`, `defmatch`, `defrule`, `apply1`, `applyb1`, and `apply2`. In the other group are `let` and `letsimp`. Both schemes define patterns in terms of pattern variables declared by `matchdeclare`.

Pattern-matching rules defined by `tellsimp` and `tellsimpafter` are applied automatically by the Maxima simplifier. Rules defined by `defmatch`, `defrule`, and `let` are applied by an explicit function call.

There are additional mechanisms for rules applied to polynomials by `tellrat`, and for commutative and noncommutative algebra in `affine` package.

### 34.2 Functions and Variables for Rules and Patterns

**apply1** (*expr*, *rule\_1*, ..., *rule\_n*) Function

Repeatedly applies *rule\_1* to *expr* until it fails, then repeatedly applies the same rule to all subexpressions of *expr*, left to right, until *rule\_1* has failed on all subexpressions. Call the result of transforming *expr* in this manner *expr\_2*. Then *rule\_2* is applied in the same fashion starting at the top of *expr\_2*. When *rule\_n* fails on the final subexpression, the result is returned.

`maxapplydepth` is the depth of the deepest subexpressions processed by `apply1` and `apply2`.

See also `applyb1`, `apply2`, and `let`.

**apply2** (*expr*, *rule\_1*, ..., *rule\_n*) Function

If *rule\_1* fails on a given subexpression, then *rule\_2* is repeatedly applied, etc. Only if all rules fail on a given subexpression is the whole set of rules repeatedly applied to the next subexpression. If one of the rules succeeds, then the same subexpression is reprocessed, starting with the first rule.

`maxapplydepth` is the depth of the deepest subexpressions processed by `apply1` and `apply2`.

See also `apply1` and `let`.

**applyb1** (*expr*, *rule\_1*, ..., *rule\_n*) Function

Repeatedly applies *rule\_1* to the deepest subexpression of *expr* until it fails, then repeatedly applies the same rule one level higher (i.e., larger subexpressions), until *rule\_1* has failed on the top-level expression. Then *rule\_2* is applied in the same fashion to the result of *rule\_1*. After *rule\_n* has been applied to the top-level expression, the result is returned.

`applyb1` is similar to `apply1` but works from the bottom up instead of from the top down.

`maxapplyheight` is the maximum height which `applyb1` reaches before giving up.

See also `apply1`, `apply2`, and `let`.

**current\_let\_rule\_package** Option variable

Default value: `default_let_rule_package`

`current_let_rule_package` is the name of the rule package that is used by functions in the `let` package (`letsimp`, etc.) if no other rule package is specified. This variable may be assigned the name of any rule package defined via the `let` command.

If a call such as `letsimp (expr, rule_pkg_name)` is made, the rule package `rule_pkg_name` is used for that function call only, and the value of `current_let_rule_package` is not changed.

**default\_let\_rule\_package**

Option variable

Default value: `default_let_rule_package`

`default_let_rule_package` is the name of the rule package used when one is not explicitly set by the user with `let` or by changing the value of `current_let_rule_package`.

**defmatch** (*progname*, *pattern*, *x\_1*, ..., *x\_n*)

Function

**defmatch** (*progname*, *pattern*)

Function

Defines a function *progname*(*expr*, *x\_1*, ..., *x\_n*) which tests *expr* to see if it matches *pattern*.

*pattern* is an expression containing the pattern arguments *x\_1*, ..., *x\_n* (if any) and some pattern variables (if any). The pattern arguments are given explicitly as arguments to `defmatch` while the pattern variables are declared by the `matchdeclare` function. Any variable not declared as a pattern variable in `matchdeclare` or as a pattern argument in `defmatch` matches only itself.

The first argument to the created function *progname* is an expression to be matched against the pattern and the other arguments are the actual arguments which correspond to the dummy variables *x\_1*, ..., *x\_n* in the pattern.

If the match is successful, *progname* returns a list of equations whose left sides are the pattern arguments and pattern variables, and whose right sides are the subexpressions which the pattern arguments and variables matched. The pattern variables, but not the pattern arguments, are assigned the subexpressions they match. If the match fails, *progname* returns `false`.

A literal pattern (that is, a pattern which contains neither pattern arguments nor pattern variables) returns `true` if the match succeeds.

See also `matchdeclare`, `defrule`, `tellsimp`, and `tellsimpafter`.

Examples:

Define a function `linearp(expr, x)` which tests *expr* to see if it is of the form  $a*x + b$  such that *a* and *b* do not contain *x* and *a* is nonzero. This match function matches expressions which are linear in any variable, because the pattern argument *x* is given to `defmatch`.

```
(%i1) matchdeclare (a, lambda ([e], e#0 and freeof(x, e)), b,
 freeof(x));
(%o1) done
(%i2) defmatch (linearp, a*x + b, x);
(%o2) linearp
(%i3) linearp (3*z + (y + 1)*z + y^2, z);
 2
(%o3) [b = y , a = y + 4, x = z]
(%i4) a;
(%o4) y + 4
(%i5) b;
 2
(%o5) y
(%i6) x;
(%o6) x
```

Define a function `linearp(expr)` which tests *expr* to see if it is of the form  $a*x + b$  such that *a* and *b* do not contain *x* and *a* is nonzero. This match function only matches expressions linear in *x*, not any other variable, because no pattern argument is given to `defmatch`.

```
(%i1) matchdeclare (a, lambda ([e], e#0 and freeof(x, e)), b,
 freeof(x));
(%o1) done
(%i2) defmatch (linearp, a*x + b);
(%o2) linearp
(%i3) linearp (3*z + (y + 1)*z + y^2);
```



```

(%o3) false
(%i4) linearp (3*x + (y + 1)*x + y^2);
 2
(%o4) [b = y , a = y + 4]
Define a function checklimits(expr) which tests expr to see if it is a definite integral.
(%i1) matchdeclare ([a, f], true);
(%o1) done
(%i2) constinterval (l, h) := constantp (h - l);
(%o2) constinterval(l, h) := constantp(h - l)
(%i3) matchdeclare (b, constinterval (a));
(%o3) done
(%i4) matchdeclare (x, atom);
(%o4) done
(%i5) simp : false;
(%o5) false
(%i6) defmatch (checklimits, 'integrate (f, x, a, b));
(%o6) checklimits
(%i7) simp : true;
(%o7) true
(%i8) 'integrate (sin(t), t, %pi + x, 2*%pi + x);
 x + 2 %pi
 /
 [
(%o8) I sin(t) dt
]
 /
 x + %pi
(%i9) checklimits (%);
(%o9) [b = x + 2 %pi, a = x + %pi, x = t, f = sin(t)]

```

|                                                                          |          |
|--------------------------------------------------------------------------|----------|
| <b>defrule</b> ( <i>rulename</i> , <i>pattern</i> , <i>replacement</i> ) | Function |
|--------------------------------------------------------------------------|----------|

Defines and names a replacement rule for the given pattern. If the rule named *rulename* is applied to an expression (by `apply1`, `applyb1`, or `apply2`), every subexpression matching the pattern will be replaced by the replacement. All variables in the replacement which have been assigned values by the pattern match are assigned those values in the replacement which is then simplified.

The rules themselves can be treated as functions which transform an expression by one operation of the pattern match and replacement. If the match fails, the rule function returns `false`.

|                                                                   |          |
|-------------------------------------------------------------------|----------|
| <b>disprule</b> ( <i>rulename_1</i> , . . . , <i>rulename_2</i> ) | Function |
| <b>disprule</b> ( <i>all</i> )                                    | Function |

Display rules with the names *rulename\_1*, ..., *rulename\_n*, as returned by **defrule**, **tellsimp**, or **tellsimpafter**, or a pattern defined by **defmatch**. Each rule is displayed with an intermediate expression label (%t).

`disprule (all)` displays all rules.

**disprule** quotes its arguments. **disprule** returns the list of intermediate expression labels corresponding to the displayed rules.

See also `letrules`, which displays rules defined by `let`.

Examples:

```
(%i1) tellsimpafter (foo (x, y), bar (x) + baz (y));
(%o1) [foorule1, false]
(%i2) tellsimpafter (x + y, special_add (x, y));
(%o2) [+rule1, simplus]
```

```

(%i3) defmatch (quux, mumble (x));
(%o3)
 quux
(%i4) disprule (foorule1, "+rule1", quux);
(%t4) foorule1 : foo(x, y) -> baz(y) + bar(x)

(%t5) +rule1 : y + x -> special_add(x, y)

(%t6) quux : mumble(x) -> []

(%o6) [%t4, %t5, %t6]
(%i6) ' ';
(%o6) [foorule1 : foo(x, y) -> baz(y) + bar(x),
 +rule1 : y + x -> special_add(x, y), quux : mumble(x) -> []]

```

**let** (*prod*, *repl*, *predname*, *arg\_1*, ..., *arg\_n*) Function

**let** ([*prod*, *repl*, *predname*, *arg\_1*, ..., *arg\_n*], *package\_name*) Function

Defines a substitution rule for **letsimp** such that *prod* is replaced by *repl*. *prod* is a product of positive or negative powers of the following terms:

- Atoms which **letsimp** will search for literally unless previous to calling **letsimp** the **matchdeclare** function is used to associate a predicate with the atom. In this case **letsimp** will match the atom to any term of a product satisfying the predicate.
- Kernels such as **sin(x)**, **n!**, **f(x,y)**, etc. As with atoms above **letsimp** will look for a literal match unless **matchdeclare** is used to associate a predicate with the argument of the kernel.

A term to a positive power will only match a term having at least that power. A term to a negative power on the other hand will only match a term with a power at least as negative. In the case of negative powers in *prod* the switch **letrat** must be set to **true**. See also **letrat**.

If a predicate is included in the **let** function followed by a list of arguments, a tentative match (i.e. one that would be accepted if the predicate were omitted) is accepted only if **predname** (*arg\_1'*, ..., *arg\_n'*) evaluates to **true** where *arg\_i'* is the value matched to *arg\_i*. The *arg\_i* may be the name of any atom or the argument of any kernel appearing in *prod*. *repl* may be any rational expression. If any of the atoms or arguments from *prod* appear in *repl* the appropriate substitutions are made.

The global flag **letrat** controls the simplification of quotients by **letsimp**. When **letrat** is **false**, **letsimp** simplifies the numerator and denominator of *expr* separately, and does not simplify the quotient. Substitutions such as **n!/n** goes to **(n-1)!** then fail. When **letrat** is **true**, then the numerator, denominator, and the quotient are simplified in that order.

These substitution functions allow you to work with several rule packages at once. Each rule package can contain any number of **let** rules and is referenced by a user-defined name. The command **let** ([*prod*, *repl*, *predname*, *arg\_1*, ..., *arg\_n*], *package\_name*) adds the rule *predname* to the rule package *package\_name*. The command **letsimp** (*expr*, *package\_name*) applies the rules in *package\_name*. **letsimp** (*expr*, *package\_name1*, *package\_name2*, ...) is equivalent to **letsimp** (*expr*, *package\_name1*) followed by **letsimp** (%, *package\_name2*), ...

**current\_let\_rule\_package** is the name of the rule package that is presently being used. This variable may be assigned the name of any rule package defined via the **let** command. Whenever any of the functions comprising the **let** package are called with no package name, the package named by **current\_let\_rule\_package** is used. If a call such as **letsimp** (*expr*, *rule\_pkg\_name*) is made, the rule package *rule\_pkg\_name* is used for that **letsimp** command only, and **current\_let\_rule\_package** is not changed. If not otherwise specified, **current\_let\_rule\_package** defaults to **default\_let\_rule\_package**.

```

(%i1) matchdeclare ([a, a1, a2], true)$
(%i2) oneless (x, y) := is (x = y-1)$
(%i3) let (a1*a2!, a1!, oneless, a2, a1);

```

```

(%o3) a1 a2! --> a1! where oneless(a2, a1)
(%i4) letrat: true$
(%i5) let (a1!/a1, (a1-1)!);
 a1!
(%o5) --- --> (a1 - 1)!
 a1
(%i6) letsimp (n*m!*(n-1)!/m);
(%o6) (m - 1)! n!
(%i7) let (sin(a)^2, 1 - cos(a)^2);
 2 2
(%o7) sin (a) --> 1 - cos (a)
(%i8) letsimp (sin(x)^4);
 4 2
(%o8) cos (x) - 2 cos (x) + 1

```

**letrat**

Option variable

Default value: false

When `letrat` is false, `letsimp` simplifies the numerator and denominator of a ratio separately, and does not simplify the quotient.

When `letrat` is true, the numerator, denominator, and their quotient are simplified in that order.

```

(%i1) matchdeclare (n, true)$
(%i2) let (n!/n, (n-1)!);
 n!
(%o2) -- --> (n - 1)!
 n
(%i3) letrat: false$
(%i4) letsimp (a!/a);
 a!
(%o4) --
 a
(%i5) letrat: true$
(%i6) letsimp (a!/a);
(%o6) (a - 1)!

```

**letrules ()**

Function

**letrules (package\_name)**

Function

Displays the rules in a rule package. `letrules ()` displays the rules in the current rule package. `letrules (package_name)` displays the rules in `package_name`.

The current rule package is named by `current_let_rule_package`. If not otherwise specified, `current_let_rule_package` defaults to `default_let_rule_package`.

See also `disprule`, which displays rules defined by `tellsimp` and `tellsimpafter`.

**letsimp (expr)**

Function

**letsimp (expr, package\_name)**

Function

**letsimp (expr, package\_name\_1, ..., package\_name\_n)**

Function

Repeatedly applies the substitution rules defined by `let` until no further change is made to `expr`.

`letsimp (expr)` uses the rules from `current_let_rule_package`.

`letsimp (expr, package_name)` uses the rules from `package_name` without changing `current_let_rule_package`.

`letsimp (expr, package_name_1, ..., package_name_n)` is equivalent to `letsimp (expr, package_name_1, followed by letsimp (% , package_name_2), and so on.`

**let\_rule\_packages**

Option variable

Default value: `[default_let_rule_package]`

`let_rule_packages` is a list of all user-defined let rule packages plus the default package `default_let_rule_package`.

**matchdeclare** (*a<sub>1</sub>*, *pred<sub>1</sub>*, ..., *a<sub>n</sub>*, *pred<sub>n</sub>*)

Function

Associates a predicate *pred<sub>k</sub>* with a variable or list of variables *a<sub>k</sub>* so that *a<sub>k</sub>* matches expressions for which the predicate returns anything other than **false**.

A predicate is the name of a function, or a lambda expression, or a function call or lambda call missing the last argument, or **true** or **all**. Any expression matches **true** or **all**. If the predicate is specified as a function call or lambda call, the expression to be tested is appended to the list of arguments; the arguments are evaluated at the time the match is evaluated. Otherwise, the predicate is specified as a function name or lambda expression, and the expression to be tested is the sole argument. A predicate function need not be defined when **matchdeclare** is called; the predicate is not evaluated until a match is attempted.

A predicate may return a Boolean expression as well as **true** or **false**. Boolean expressions are evaluated by **is** within the constructed rule function, so it is not necessary to call **is** within the predicate.

If an expression satisfies a match predicate, the match variable is assigned the expression, except for match variables which are operands of addition **+** or multiplication **\***. Only addition and multiplication are handled specially; other n-ary operators (both built-in and user-defined) are treated like ordinary functions.

In the case of addition and multiplication, the match variable may be assigned a single expression which satisfies the match predicate, or a sum or product (respectively) of such expressions. Such multiple-term matching is greedy: predicates are evaluated in the order in which their associated variables appear in the match pattern, and a term which satisfies more than one predicate is taken by the first predicate which it satisfies. Each predicate is tested against all operands of the sum or product before the next predicate is evaluated. In addition, if 0 or 1 (respectively) satisfies a match predicate, and there are no other terms which satisfy the predicate, 0 or 1 is assigned to the match variable associated with the predicate.

The algorithm for processing addition and multiplication patterns makes some match results (for example, a pattern in which a "match anything" variable appears) dependent on the ordering of terms in the match pattern and in the expression to be matched. However, if all match predicates are mutually exclusive, the match result is insensitive to ordering, as one match predicate cannot accept terms matched by another.

Calling **matchdeclare** with a variable *a* as an argument changes the **matchdeclare** property for *a*, if one was already declared; only the most recent **matchdeclare** is in effect when a rule is defined. Later changes to the **matchdeclare** property (via **matchdeclare** or **remove**) do not affect existing rules.

**propvars** (**matchdeclare**) returns the list of all variables for which there is a **matchdeclare** property. **printprops** (*a*, **matchdeclare**) returns the predicate for variable *a*. **printprops** (**all**, **matchdeclare**) returns the list of predicates for all **matchdeclare** variables. **remove** (*a*, **matchdeclare**) removes the **matchdeclare** property from *a*.

The functions **defmatch**, **defrule**, **tellsimp**, **tellsimpafter**, and **let** construct rules which test expressions against patterns.

**matchdeclare** quotes its arguments. **matchdeclare** always returns **done**.

Examples:

A predicate is the name of a function, or a lambda expression, or a function call or lambda call missing the last argument, or **true** or **all**.

```
(%i1) matchdeclare (aa, integerp);
(%o1) done
(%i2) matchdeclare (bb, lambda ([x], x > 0));
```

```

(%o2) done
(%i3) matchdeclare (cc, freeof (%e, %pi, %i));
(%o3) done
(%i4) matchdeclare (dd, lambda ([x, y], gcd (x, y) = 1) (1728));
(%o4) done
(%i5) matchdeclare (ee, true);
(%o5) done
(%i6) matchdeclare (ff, all);
(%o6) done

```

If an expression satisfies a match predicate, the match variable is assigned the expression.

```

(%i1) matchdeclare (aa, integerp, bb, atom);
(%o1) done
(%i2) defrule (r1, bb^aa, ["integer" = aa, "atom" = bb]);
 aa
(%o2) r1 : bb -> [integer = aa, atom = bb]
(%i3) r1 (%pi^8);
(%o3) [integer = 8, atom = %pi]

```

In the case of addition and multiplication, the match variable may be assigned a single expression which satisfies the match predicate, or a sum or product (respectively) of such expressions.

```

(%i1) matchdeclare (aa, atom, bb, lambda ([x], not atom(x)));
(%o1) done
(%i2) defrule (r1, aa + bb, ["all atoms" = aa, "all nonatoms" =
 bb]);
bb + aa partitions 'sum'
(%o2) r1 : bb + aa -> [all atoms = aa, all nonatoms = bb]
(%i3) r1 (8 + a*b + sin(x));
(%o3) [all atoms = 8, all nonatoms = sin(x) + a b]
(%i4) defrule (r2, aa * bb, ["all atoms" = aa, "all nonatoms" =
 bb]);
bb aa partitions 'product'
(%o4) r2 : aa bb -> [all atoms = aa, all nonatoms = bb]
(%i5) r2 (8 * (a + b) * sin(x));
(%o5) [all atoms = 8, all nonatoms = (b + a) sin(x)]

```

When matching arguments of + and \*, if all match predicates are mutually exclusive, the match result is insensitive to ordering, as one match predicate cannot accept terms matched by another.

```

(%i1) matchdeclare (aa, atom, bb, lambda ([x], not atom(x)));
(%o1) done
(%i2) defrule (r1, aa + bb, ["all atoms" = aa, "all nonatoms" =
 bb]);
bb + aa partitions 'sum'
(%o2) r1 : bb + aa -> [all atoms = aa, all nonatoms = bb]
(%i3) r1 (8 + a*b + %pi + sin(x) - c + 2^n);
 n
(%o3) [all atoms = %pi + 8, all nonatoms = sin(x) + 2 - c + a b]
(%i4) defrule (r2, aa * bb, ["all atoms" = aa, "all nonatoms" =
 bb]);
bb aa partitions 'product'
(%o4) r2 : aa bb -> [all atoms = aa, all nonatoms = bb]
(%i5) r2 (8 * (a + b) * %pi * sin(x) / c * 2^n);
 n
 (b + a) 2 sin(x)
(%o5) [all atoms = 8 %pi, all nonatoms = -----]
 c

```

The functions `propvars` and `printprops` return information about match variables.

```
(%i1) matchdeclare ([aa, bb, cc], atom, [dd, ee], integerp);
(%o1) done
(%i2) matchdeclare (ff, floatnump, gg, lambda ([x], x > 100));
(%o2) done
(%i3) propvars (matchdeclare);
(%o3) [aa, bb, cc, dd, ee, ff, gg]
(%i4) printprops (ee, matchdeclare);
(%o4) [integerp(ee)]
(%i5) printprops (gg, matchdeclare);
(%o5) [lambda([x], x > 100, gg)]
(%i6) printprops (all, matchdeclare);
(%o6) [lambda([x], x > 100, gg), floatnump(ff), integerp(ee),
integerp(dd), atom(cc), atom(bb), atom(aa)]
```

**maxapplydepth**

Option variable

Default value: 10000

**maxapplydepth** is the maximum depth to which **apply1** and **apply2** will delve.**maxapplyheight**

Option variable

Default value: 10000

**maxapplyheight** is the maximum height to which **applyb1** will reach before giving up.**remlet** (*prod*, *name*)

Function

**remlet** ()

Function

**remlet** (*all*)

Function

**remlet** (*all*, *name*)

Function

Deletes the substitution rule, *prod* → *repl*, most recently defined by the **let** function. If *name* is supplied the rule is deleted from the rule package *name*.

**remlet**() and **remlet**(*all*) delete all substitution rules from the current rule package. If the name of a rule package is supplied, e.g. **remlet** (*all*, *name*), the rule package *name* is also deleted.

If a substitution is to be changed using the same product, **remlet** need not be called, just redefine the substitution using the same product (literally) with the **let** function and the new replacement and/or predicate name. Should **remlet** (*prod*) now be called the original substitution rule is revived.

See also **remrule**, which removes a rule defined by **tellsimp** or **tellsimpafter**.

**remrule** (*op*, *rulename*)

Function

**remrule** (*op*, *all*)

Function

Removes rules defined by **tellsimp** or **tellsimpafter**.

**remrule** (*op*, *rulename*) removes the rule with the name *rulename* from the operator *op*. When *op* is a built-in or user-defined operator (as defined by **infix**, **prefix**, etc.), *op* and *rulename* must be enclosed in double quote marks.

**remrule** (*op*, *all*) removes all rules for the operator *op*.

See also **remlet**, which removes a rule defined by **let**.

Examples:

```
(%i1) tellsimp (foo (aa, bb), bb - aa);
(%o1) [foorule1, false]
(%i2) tellsimpafter (aa + bb, special_add (aa, bb));
(%o2) [+rule1, simplus]
(%i3) infix ("@@");
(%o3) @@
(%i4) tellsimp (aa @@ bb, bb/aa);
```

```

(%o4) [@@rule1, false]
(%i5) tellsimpafter (quux (%pi, %e), %pi - %e);
(%o5) [quuxrule1, false]
(%i6) tellsimpafter (quux (%e, %pi), %pi + %e);
(%o6) [quuxrule2, quuxrule1, false]
(%i7) [foo (aa, bb), aa + bb, aa @@ bb, quux (%pi, %e),
 quux (%e, %pi)];

 bb
(%o7) [bb - aa, special_add(aa, bb), --, %pi - %e, %pi + %e]
 aa

(%i8) remrule (foo, foerule1);
(%o8) foo
(%i9) remrule ("+", ?\+rule1);
(%o9) +
(%i10) remrule ("@", ?\@@rule1);
(%o10) @@
(%i11) remrule (quux, all);
(%o11) quux
(%i12) [foo (aa, bb), aa + bb, aa @@ bb, quux (%pi, %e),
 quux (%e, %pi)];
(%o12) [foo(aa, bb), bb + aa, aa @@ bb, quux(%pi, %e),
 quux(%e, %pi)]

```

**tellsimp** (*pattern, replacement*)

Function

is similar to `tellsimpafter` but places new information before old so that it is applied before the built-in simplification rules.

`tellsimp` is used when it is important to modify the expression before the simplifier works on it, for instance if the simplifier "knows" something about the expression, but what it returns is not to your liking. If the simplifier "knows" something about the main operator of the expression, but is simply not doing enough for you, you probably want to use `tellsimpafter`.

The pattern may not be a sum, product, single variable, or number.

The system variable `rules` is the list of rules defined by `defrule`, `defmatch`, `tellsimp`, and `tellsimpafter`.

Examples:

```

(%i1) matchdeclare (x, freeof (%i));
(%o1) done
(%i2) %iargs: false$
(%i3) tellsimp (sin(%i*x), %i*sinh(x));
(%o3) [sinrule1, simp-%sin]
(%i4) trigexpand (sin (%i*y + x));
(%o4) sin(x) cos(%i y) + %i cos(x) sinh(y)
(%i5) %iargs:true$
(%i6) errcatch(0^0);
0
0 has been generated
(%o6) []
(%i7) ev (tellsimp (0^0, 1), simp: false);
(%o7) [^rule1, simpexpt]
(%i8) 0^0;
(%o8) 1
(%i9) remrule ("^", %th(2)[1]);
(%o9) ^
(%i10) tellsimp (sin(x)^2, 1 - cos(x)^2);
(%o10) [^rule2, simpexpt]

```



```

(%i11) (1 + sin(x))^2;

(%o11)

$$(\sin(x) + 1)^2$$

(%i12) expand (%);

(%o12)

$$2 \sin(x) - \cos^2(x) + 2$$

(%i13) sin(x)^2;

(%o13)

$$1 - \cos^2(x)$$

(%i14) kill (rules);
(%o14) done
(%i15) matchdeclare (a, true);
(%o15) done
(%i16) tellsimp (sin(a)^2, 1 - cos(a)^2);
(%o16) [^rule3, simpexpt]
(%i17) sin(y)^2;

(%o17)

$$1 - \cos^2(y)$$


```

### **tellsimpafter** (*pattern*, *replacement*)

Function

Defines a simplification rule which the Maxima simplifier applies after built-in simplification rules. *pattern* is an expression, comprising pattern variables (declared by **matchdeclare**) and other atoms and operators, considered literals for the purpose of pattern matching. *replacement* is substituted for an actual expression which matches *pattern*; pattern variables in *replacement* are assigned the values matched in the actual expression.

*pattern* may be any nonatomic expression in which the main operator is not a pattern variable; the simplification rule is associated with the main operator. The names of functions (with one exception, described below), lists, and arrays may appear in *pattern* as the main operator only as literals (not pattern variables); this rules out expressions such as **aa**(*x*) and **bb**[*y*] as patterns, if **aa** and **bb** are pattern variables. Names of functions, lists, and arrays which are pattern variables may appear as operators other than the main operator in *pattern*.

There is one exception to the above rule concerning names of functions. The name of a subscripted function in an expression such as **aa**[*x*](*y*) may be a pattern variable, because the main operator is not **aa** but rather the Lisp atom **mqapply**. This is a consequence of the representation of expressions involving subscripted functions.

Simplification rules are applied after evaluation (if not suppressed through quotation or the flag **noeval**). Rules established by **tellsimpafter** are applied in the order they were defined, and after any built-in rules. Rules are applied bottom-up, that is, applied first to subexpressions before application to the whole expression. It may be necessary to repeatedly simplify a result (for example, via the quote-quote operator **''** or the flag **infeval**) to ensure that all rules are applied.

Pattern variables are treated as local variables in simplification rules. Once a rule is defined, the value of a pattern variable does not affect the rule, and is not affected by the rule. An assignment to a pattern variable which results from a successful rule match does not affect the current assignment (or lack of it) of the pattern variable. However, as with all atoms in Maxima, the properties of pattern variables (as declared by **put** and related functions) are global.

The rule constructed by **tellsimpafter** is named after the main operator of *pattern*. Rules for built-in operators, and user-defined operators defined by **infix**, **prefix**, **postfix**, **matchfix**, and **nofix**, have names which are Lisp identifiers. Rules for other functions have names which are Maxima identifiers.

The treatment of noun and verb forms is slightly confused. If a rule is defined for a noun (or verb) form and a rule for the corresponding verb (or noun) form already exists, the newly-defined rule applies to both forms (noun and verb). If a rule for the corresponding



verb (or noun) form does not exist, the newly-defined rule applies only to the noun (or verb) form.

The rule constructed by `tellsimpafter` is an ordinary Lisp function. If the name of the rule is `$foorule1`, the construct `:lisp (trace $foorule1)` traces the function, and `:lisp (symbol-function '$foorule1)` displays its definition.

`tellsimpafter` quotes its arguments. `tellsimpafter` returns the list of rules for the main operator of *pattern*, including the newly established rule.

See also `matchdeclare`, `defmatch`, `defrule`, `tellsimp`, `let`, `kill`, `remrule`, and `clear_rules`.

Examples:

*pattern* may be any nonatomic expression in which the main operator is not a pattern variable.

```
(%i1) matchdeclare (aa, atom, [ll, mm], listp, xx, true)$
(%i2) tellsimpafter (sin (ll), map (sin, ll));
(%o2) [sinrule1, simp-%sin]
(%i3) sin ([1/6, 1/4, 1/3, 1/2, 1]*%pi);
(%o3) [-, -----, -----, 1, 0]
 2 2 2
(%i4) tellsimpafter (ll^mm, map ("^", ll, mm));
(%o4) [^rule1, simpexpt]
(%i5) [a, b, c]^[1, 2, 3];
(%o5) [a, b , c]
 2 3
(%i6) tellsimpafter (foo (aa (xx)), aa (foo (xx)));
(%o6) [foorule1, false]
(%i7) foo (bar (u - v));
(%o7) bar(foo(u - v))
```

Rules are applied in the order they were defined. If two rules can match an expression, the rule which was defined first is applied.

```
(%i1) matchdeclare (aa, integerp);
(%o1) done
(%i2) tellsimpafter (foo (aa), bar_1 (aa));
(%o2) [foorule1, false]
(%i3) tellsimpafter (foo (aa), bar_2 (aa));
(%o3) [foorule2, foorule1, false]
(%i4) foo (42);
(%o4) bar_1(42)
```

Pattern variables are treated as local variables in simplification rules. (Compare to `defmatch`, which treats pattern variables as global variables.)

```
(%i1) matchdeclare (aa, integerp, bb, atom);
(%o1) done
(%i2) tellsimpafter (foo(aa, bb), bar('aa=aa, 'bb=bb));
(%o2) [foorule1, false]
(%i3) bb: 12345;
(%o3) 12345
(%i4) foo (42, %e);
(%o4) bar(aa = 42, bb = %e)
(%i5) bb;
(%o5) 12345
```

As with all atoms, properties of pattern variables are global even though values are local. In this example, an assignment property is declared via `define_variable`. This is a property of the atom `bb` throughout Maxima.

```
(%i1) matchdeclare (aa, integerp, bb, atom);
(%o1) done
```

```
(%i2) tellsimpafter (foo(aa, bb), bar('aa=aa, 'bb=bb));
(%o2) [foorule1, false]
(%i3) foo (42, %e);
(%o3) bar(aa = 42, bb = %e)
(%i4) define_variable (bb, true, boolean);
(%o4) true
(%i5) foo (42, %e);
Error: bb was declared mode boolean, has value: %e
-- an error. Quitting. To debug this try debugmode(true);
```

Rules are named after main operators. Names of rules for built-in and user-defined operators are Lisp identifiers, while names for other functions are Maxima identifiers.

```
(%i1) tellsimpafter (foo (%pi + %e), 3*%pi);
(%o1) [foorule1, false]
(%i2) tellsimpafter (foo (%pi * %e), 17*%e);
(%o2) [foorule2, foorule1, false]
(%i3) tellsimpafter (foo (%i ^ %e), -42*%i);
(%o3) [foorule3, foorule2, foorule1, false]
(%i4) tellsimpafter (foo (9) + foo (13), quux (22));
(%o4) [+rule1, simplus]
(%i5) tellsimpafter (foo (9) * foo (13), blurf (22));
(%o5) [*rule1, simptimes]
(%i6) tellsimpafter (foo (9) ^ foo (13), mumble (22));
(%o6) [^rule1, simpexpt]
(%i7) rules;
(%o7) [foorule1, foorule2, foorule3, +rule1, *rule1, ^rule1]
(%i8) foorule_name: first (%o1);
(%o8) foorule1
(%i9) plusrule_name: first (%o4);
(%o9) +rule1
(%i10) remrule (foo, foorule1);
(%o10) foo
(%i11) remrule ("^", ?\^rule1);
(%o11) ^
(%i12) rules;
(%o12) [foorule2, foorule3, +rule1, *rule1]
```

A worked example: anticommutative multiplication.

```
(%i1) gt (i, j) := integerp(j) and i < j;
(%o1) gt(i, j) := integerp(j) and i < j
(%i2) matchdeclare (i, integerp, j, gt(i));
(%o2) done
(%i3) tellsimpafter (s[i]^2, 1);
(%o3) [^^rule1, simpncexpt]
(%i4) tellsimpafter (s[i] . s[j], -s[j] . s[i]);
(%o4) [.rule1, simpnct]
(%i5) s[1] . (s[1] + s[2]);
(%o5) s1 . (s2 + s1)
(%i6) expand (%);
(%o6) 1 - s2 . s1
(%i7) factor (expand (sum (s[i], i, 0, 9)^5));
(%o7) 100 (s9 + s8 + s7 + s6 + s5 + s4 + s3 + s2 + s1 + s0)
```

**clear\_rules ()**

Function

Executes `kill (rules)` and then resets the next rule number to 1 for addition `+`, multiplication `*`, and exponentiation `^`.



## 35 Sets

### 35.1 Introduction to Sets

Maxima provides set functions, such as intersection and union, for finite sets that are defined by explicit enumeration. Maxima treats lists and sets as distinct objects. This feature makes it possible to work with sets that have members that are either lists or sets.

In addition to functions for finite sets, Maxima provides some functions related to combinatorics; these include the Stirling numbers of the first and second kind, the Bell numbers, multinomial coefficients, partitions of nonnegative integers, and a few others. Maxima also defines a Kronecker delta function.

#### 35.1.1 Usage

To construct a set with members  $a_1, \dots, a_n$ , write `set(a_1, ..., a_n)` or `{a_1, ..., a_n}`; to construct the empty set, write `set()` or `{}`. In input, `set(...)` and `{ ... }` are equivalent. Sets are always displayed with curly braces.

If a member is listed more than once, simplification eliminates the redundant member.

```
(%i1) set();
(%o1) {}
(%i2) set(a, b, a);
(%o2) {a, b}
(%i3) set(a, set(b));
(%o3) {a, {b}}
(%i4) set(a, [b]);
(%o4) {a, [b]}
(%i5) {};
(%o5) {}
(%i6) {a, b, a};
(%o6) {a, b}
(%i7) {a, {b}};
(%o7) {a, {b}}
(%i8) {a, [b]};
(%o8) {a, [b]}
```

Two would-be elements  $x$  and  $y$  are redundant (i.e., considered the same for the purpose of set construction) if and only if `is(x = y)` yields `true`. Note that `is(equal(x, y))` can yield `true` while `is(x = y)` yields `false`; in that case the elements  $x$  and  $y$  are considered distinct.

```
(%i1) x: a/c + b/c;
(%o1)
$$\frac{b}{c} + \frac{a}{c}$$

(%i2) y: a/c + b/c;
(%o2)
$$\frac{b}{c} + \frac{a}{c}$$

(%i3) z: (a + b)/c;
(%o3)
$$\frac{b + a}{c}$$

(%i4) is (x = y);
(%o4) true
(%i5) is (y = z);
(%o5) false
(%i6) is (equal (y, z));
(%o6) true
```

```
(%i7) y - z;
```

$$-\frac{b+a}{c} + \frac{b}{c} + \frac{a}{c}$$

```
(%o7)
```

```
(%i8) ratsimp (%);
```

$$0$$

```
(%o8)
```

```
(%i9) {x, y, z};
```

$$\left\{-\frac{b+a}{c}, \frac{b}{c} + \frac{a}{c}\right\}$$

```
(%o9)
```

To construct a set from the elements of a list, use **setify**.

```
(%i1) setify ([b, a]);
```

$$\{a, b\}$$

```
(%o1)
```

Set members  $x$  and  $y$  are equal provided **is**( $x = y$ ) evaluates to **true**. Thus **rat**( $x$ ) and  $x$  are equal as set members; consequently,

```
(%i1) {x, rat(x)};
```

$$\{x\}$$

```
(%o1)
```

Further, since **is**(( $x - 1$ )\*( $x + 1$ ) =  $x^2 - 1$ ) evaluates to **false**, ( $x - 1$ )\*( $x + 1$ ) and  $x^2 - 1$  are distinct set members; thus

```
(%i1) {(x - 1)*(x + 1), x^2 - 1};
```

$$\{(x - 1)(x + 1), x^2 - 1\}$$

```
(%o1)
```

To reduce this set to a singleton set, apply **rat** to each set member:

```
(%i1) {(x - 1)*(x + 1), x^2 - 1};
```

$$\{(x - 1)(x + 1), x^2 - 1\}$$

```
(%o1)
```

```
(%i2) map (rat, %);
```

$$\{x^2 - 1\}$$

```
(%o2)/R/
```

To remove redundancies from other sets, you may need to use other simplification functions. Here is an example that uses **trigsimp**:

```
(%i1) {1, cos(x)^2 + sin(x)^2};
```

$$\{1, \sin^2(x) + \cos^2(x)\}$$

```
(%o1)
```

```
(%i2) map (trigsimp, %);
```

$$\{1\}$$

```
(%o2)
```

A set is simplified when its members are non-redundant and sorted. The current version of the set functions uses the Maxima function **orderlessp** to order sets; however, *future versions of the set functions might use a different ordering function*.

Some operations on sets, such as substitution, automatically force a re-simplification; for example,

```
(%i1) s: {a, b, c} $
```

```
(%i2) subst (c=a, s);
```

$$\{a, b\}$$

```
(%o2)
```

```
(%i3) subst ([a=x, b=x, c=x], s);
```

$$\{x\}$$

```
(%o3)
```

```
(%i4) map (lambda ([x], x^2), set (-1, 0, 1));
```

$$\{0, 1\}$$

```
(%o4)
```

Maxima treats lists and sets as distinct objects; functions such as **union** and **intersection** complain if any argument is not a set. If you need to apply a set function to a list, use the **setify** function to convert it to a set. Thus

```
(%i1) union ([1, 2], {a, b});
```

Function union expects a set, instead found [1,2]  
 -- an error. Quitting. To debug this try debugmode(true);

```
(%i2) union (setify ([1, 2]), {a, b});
(%o2) {1, 2, a, b}
```

To extract all set elements of a set *s* that satisfy a predicate *f*, use `subset(s, f)`. (A *predicate* is a boolean-valued function.) For example, to find the equations in a given set that do not depend on a variable *z*, use

```
(%i1) subset ({x + y + z, x - y + 4, x + y - 5},
 lambda ([e], freeof (z, e)));
(%o1) {- y + x + 4, y + x - 5}
```

The section [Section 35.2 \[Functions and Variables for Sets\]](#), page 434 has a complete list of the set functions in Maxima.

### 35.1.2 Set Member Iteration

There two ways to to iterate over set members. One way is the use `map`; for example:

```
(%i1) map (f, {a, b, c});
(%o1) {f(a), f(b), f(c)}
```

The other way is to use `for x in s do`

```
(%i1) s: {a, b, c};
(%o1) {a, b, c}
(%i2) for si in s do print (concat (si, 1));
a1
b1
c1
(%o2) done
```

The Maxima functions `first` and `rest` work correctly on sets. Applied to a set, `first` returns the first displayed element of a set; which element that is may be implementation-dependent. If *s* is a set, then `rest(s)` is equivalent to `disjoin(first(s), s)`. Currently, there are other Maxima functions that work correctly on sets. In future versions of the set functions, `first` and `rest` may function differently or not at all.

### 35.1.3 Bugs

The set functions use the Maxima function `orderlessp` to order set members and the (Lisp-level) function `like` to test for set member equality. Both of these functions have known bugs that may manifest if you attempt to use sets with members that are lists or matrices that contain expressions in canonical rational expression (CRE) form. An example is

```
(%i1) {[x], [rat (x)]};
Maxima encountered a Lisp error:
```

```
The value #:X1440 is not of type LIST.
```

```
Automatically continuing.
```

```
To reenable the Lisp debugger set *debugger-hook* to nil.
```

This expression causes Maxima to halt with an error (the error message depends on which version of Lisp your Maxima uses). Another example is

```
(%i1) setify ([[rat(a)], [rat(b)]]);
Maxima encountered a Lisp error:
```

```
The value #:A1440 is not of type LIST.
```

```
Automatically continuing.
```

```
To reenable the Lisp debugger set *debugger-hook* to nil.
```

These bugs are caused by bugs in `orderlessp` and `like`; they are not caused by bugs in the set functions. To illustrate, try the expressions

```
(%i1) orderlessp ([rat(a)], [rat(b)]);
Maxima encountered a Lisp error:
```

```
The value #:B1441 is not of type LIST.
```

```
Automatically continuing.
To reenble the Lisp debugger set *debugger-hook* to nil.
(%i2) is ([rat(a)] = [rat(a)]);
(%o2) false
```

Until these bugs are fixed, do not construct sets with members that are lists or matrices containing expressions in CRE form; a set with a member in CRE form, however, shouldn't be a problem:

```
(%i1) {x, rat (x)};
(%o1) {x}
```

Maxima's `orderlessp` has another bug that can cause problems with set functions, namely that the ordering predicate `orderlessp` is not transitive. The simplest known example that shows this is

```
(%i1) q: x^2$
(%i2) r: (x + 1)^2$
(%i3) s: x*(x + 2)$
(%i4) orderlessp (q, r);
(%o4) true
(%i5) orderlessp (r, s);
(%o5) true
(%i6) orderlessp (q, s);
(%o6) false
```

This bug can cause trouble with all set functions as well as with Maxima functions in general. It is probable, but not certain, that this bug can be avoided if all set members are either in CRE form or have been simplified using `ratsimp`.

Maxima's `orderless` and `ordergreat` mechanisms are incompatible with the set functions. If you need to use either `orderless` or `ordergreat`, call those functions before constructing any sets, and do not call `unorder`.

If you find something that you think might be a set function bug, please report it to the Maxima bug database. See `bug_report`.

### 35.1.4 Authors

Stavros Macrakis of Cambridge, Massachusetts and Barton Willis of the University of Nebraska at Kearney (UNK) wrote the Maxima set functions and their documentation.

## 35.2 Functions and Variables for Sets

### `adjoin (x, a)`

Function

Returns the union of the set `a` with `{x}`.

`adjoin` complains if `a` is not a literal set.

`adjoin(x, a)` and `union(set(x), a)` are equivalent; however, `adjoin` may be somewhat faster than `union`.

See also `disjoin`.

Examples:

```
(%i1) adjoin (c, {a, b});
(%o1) {a, b, c}
(%i2) adjoin (a, {a, b});
(%o2) {a, b}
```



**belln** (*n*)

Function

Represents the  $n$ -th Bell number. **belln**(*n*) is the number of partitions of a set with  $n$  members.

For nonnegative integers  $n$ , **belln**( $n$ ) simplifies to the  $n$ -th Bell number. **belln** does not simplify for any other arguments.

**belln** distributes over equations, lists, matrices, and sets.

Examples:

**belln** applied to nonnegative integers.

```
(%i1) makelist (belln (i), i, 0, 6);
(%o1) [1, 1, 2, 5, 15, 52, 203]
(%i2) is (cardinality (set_partitions ({})) = belln (0));
(%o2) true
(%i3) is (cardinality (set_partitions ({1, 2, 3, 4, 5, 6})) =
 belln (6));
(%o3) true
```

**belln** applied to arguments which are not nonnegative integers.

```
(%i1) [belln (x), belln (sqrt(3)), belln (-9)];
(%o1) [belln(x), belln(sqrt(3)), belln(- 9)]
```

**cardinality** (*a*)

Function

Returns the number of distinct elements of the set  $a$ .

**cardinality** ignores redundant elements even when simplification is disabled.

Examples:

```
(%i1) cardinality ({});
(%o1) 0
(%i2) cardinality ({a, a, b, c});
(%o2) 3
(%i3) simp : false;
(%o3) false
(%i4) cardinality ({a, a, b, c});
(%o4) 3
```

**cartesian\_product** ( $b_1, \dots, b_n$ )

Function

Returns a set of lists of the form  $[x_1, \dots, x_n]$ , where  $x_1, \dots, x_n$  are elements of the sets  $b_1, \dots, b_n$ , respectively.

**cartesian\_product** complains if any argument is not a literal set.

Examples:

```
(%i1) cartesian_product ({0, 1});
(%o1) {[0], [1]}
(%i2) cartesian_product ({0, 1}, {0, 1});
(%o2) {[0, 0], [0, 1], [1, 0], [1, 1]}
(%i3) cartesian_product ({x}, {y}, {z});
(%o3) {[x, y, z]}
(%i4) cartesian_product ({x}, {-1, 0, 1});
(%o4) {[x, - 1], [x, 0], [x, 1]}
```

**disjoin** ( $x, a$ )

Function

Returns the set  $a$  without the member  $x$ . If  $x$  is not a member of  $a$ , return  $a$  unchanged.

**disjoin** complains if  $a$  is not a literal set.

**disjoin**( $x, a$ ), **delete**( $x, a$ ), and **setdifference**( $a, \text{set}(x)$ ) are all equivalent. Of these, **disjoin** is generally faster than the others.

Examples:

```
(%i1) disjoint (a, {a, b, c, d});
(%o1) {b, c, d}
(%i2) disjoint (a + b, {5, z, a + b, %pi});
(%o2) {5, %pi, z}
(%i3) disjoint (a - b, {5, z, a + b, %pi});
(%o3) {5, %pi, b + a, z}
```

**disjointp** (*a*, *b*)

Function

Returns **true** if and only if the sets *a* and *b* are disjoint.

**disjointp** complains if either *a* or *b* is not a literal set.

Examples:

```
(%i1) disjointp ({a, b, c}, {1, 2, 3});
(%o1) true
(%i2) disjointp ({a, b, 3}, {1, 2, 3});
(%o2) false
```

**divisors** (*n*)

Function

Represents the set of divisors of *n*.

**divisors**(*n*) simplifies to a set of integers when *n* is a nonzero integer. The set of divisors includes the members 1 and *n*. The divisors of a negative integer are the divisors of its absolute value.

**divisors** distributes over equations, lists, matrices, and sets.

Examples:

We can verify that 28 is a perfect number: the sum of its divisors (except for itself) is 28.

```
(%i1) s: divisors(28);
(%o1) {1, 2, 4, 7, 14, 28}
(%i2) lreduce ("+", args(s)) - 28;
(%o2) 28
```

**divisors** is a simplifying function. Substituting 8 for *a* in **divisors**(*a*) yields the divisors without reevaluating **divisors**(8).

```
(%i1) divisors (a);
(%o1) divisors(a)
(%i2) subst (8, a, %);
(%o2) {1, 2, 4, 8}
```

**divisors** distributes over equations, lists, matrices, and sets.

```
(%i1) divisors (a = b);
(%o1) divisors(a) = divisors(b)
(%i2) divisors ([a, b, c]);
(%o2) [divisors(a), divisors(b), divisors(c)]
(%i3) divisors (matrix ([a, b], [c, d]));
(%o3) [[divisors(a) divisors(b)]
 [divisors(c) divisors(d)]]
(%i4) divisors ({a, b, c});
(%o4) {divisors(a), divisors(b), divisors(c)}
```

**elementp** (*x*, *a*)

Function

Returns **true** if and only if *x* is a member of the set *a*.

**elementp** complains if *a* is not a literal set.

Examples:

```
(%i1) elementp (sin(1), {sin(1), sin(2), sin(3)});
(%o1) true
(%i2) elementp (sin(1), {cos(1), cos(2), cos(3)});
(%o2) false
```

**empty** (*a*)

Function

Return **true** if and only if *a* is the empty set or the empty list.

Examples:

```
(%i1) map (empty, [{}, []]);
(%o1) [true, true]
(%i2) map (empty, [a + b, {}, %pi]);
(%o2) [false, false, false]
```

**equiv\_classes** (*s*, *F*)

Function

Returns a set of the equivalence classes of the set *s* with respect to the equivalence relation *F*.

*F* is a function of two variables defined on the Cartesian product of *s* with *s*. The return value of *F* is either **true** or **false**, or an expression *expr* such that **is**(*expr*) is either **true** or **false**.

When *F* is not an equivalence relation, **equiv\_classes** accepts it without complaint, but the result is generally incorrect in that case.

Examples:

The equivalence relation is a lambda expression which returns **true** or **false**.

```
(%i1) equiv_classes ({1, 1.0, 2, 2.0, 3, 3.0},
 lambda ([x, y], is (equal (x, y))));
(%o1) {{1, 1.0}, {2, 2.0}, {3, 3.0}}
```

The equivalence relation is the name of a relational function which is evaluates to **true** or **false**.

```
(%i1) equiv_classes ({1, 1.0, 2, 2.0, 3, 3.0}, equal);
(%o1) {{1, 1.0}, {2, 2.0}, {3, 3.0}}
```

The equivalence classes are numbers which differ by a multiple of 3.

```
(%i1) equiv_classes ({1, 2, 3, 4, 5, 6, 7},
 lambda ([x, y], remainder (x - y, 3) = 0));
(%o1) {{1, 4, 7}, {2, 5}, {3, 6}}
```

**every** (*f*, *s*)

Function

**every** (*f*, *L*<sub>1</sub>, ..., *L*<sub>*n*</sub>)

Function

Returns **true** if the predicate *f* is **true** for all given arguments.

Given one set as the second argument, **every**(*f*, *s*) returns **true** if **is**(*f*(*a*<sub>*i*</sub>)) returns **true** for all *a*<sub>*i*</sub> in *s*. **every** may or may not evaluate *f* for all *a*<sub>*i*</sub> in *s*. Since sets are unordered, **every** may evaluate *f*(*a*<sub>*i*</sub>) in any order.

Given one or more lists as arguments, **every**(*f*, *L*<sub>1</sub>, ..., *L*<sub>*n*</sub>) returns **true** if **is**(*f*(*x*<sub>1</sub>, ..., *x*<sub>*n*</sub>)) returns **true** for all *x*<sub>1</sub>, ..., *x*<sub>*n*</sub> in *L*<sub>1</sub>, ..., *L*<sub>*n*</sub>, respectively. **every** may or may not evaluate *f* for every combination *x*<sub>1</sub>, ..., *x*<sub>*n*</sub>. **every** evaluates lists in the order of increasing index.

Given an empty set {} or empty lists [] as arguments, **every** returns **false**.

When the global flag **maperror** is **true**, all lists *L*<sub>1</sub>, ..., *L*<sub>*n*</sub> must have equal lengths. When **maperror** is **false**, list arguments are effectively truncated to the length of the shortest list.

Return values of the predicate *f* which evaluate (via **is**) to something other than **true** or **false** are governed by the global flag **prederror**. When **prederror** is **true**, such values are treated as **false**, and the return value from **every** is **false**. When **prederror** is **false**, such values are treated as **unknown**, and the return value from **every** is **unknown**.

Examples:

**every** applied to a single set. The predicate is a function of one argument.

```
(%i1) every (integerp, {1, 2, 3, 4, 5, 6});
(%o1) true
(%i2) every (atom, {1, 2, sin(3), 4, 5 + y, 6});
(%o2) false
```

`every` applied to two lists. The predicate is a function of two arguments.

```
(%i1) every ("=", [a, b, c], [a, b, c]);
(%o1) true
(%i2) every ("#", [a, b, c], [a, b, c]);
(%o2) false
```

Return values of the predicate  $f$  which evaluate to something other than `true` or `false` are governed by the global flag `prederror`.

```
(%i1) prederror : false;
(%o1) false
(%i2) map (lambda ([a, b], is (a < b)), [x, y, z],
 [x^2, y^2, z^2]);
(%o2) [unknown, unknown, unknown]
(%i3) every ("<", [x, y, z], [x^2, y^2, z^2]);
(%o3) unknown
(%i4) prederror : true;
(%o4) true
(%i5) every ("<", [x, y, z], [x^2, y^2, z^2]);
(%o5) false
```

**extremal\_subset** ( $s, f, \max$ )

Function

**extremal\_subset** ( $s, f, \min$ )

Function

Returns the subset of  $s$  for which the function  $f$  takes on maximum or minimum values.

`extremal_subset( $s, f, \max$ )` returns the subset of the set or list  $s$  for which the real-valued function  $f$  takes on its maximum value.

`extremal_subset( $s, f, \min$ )` returns the subset of the set or list  $s$  for which the real-valued function  $f$  takes on its minimum value.

Examples:

```
(%i1) extremal_subset ({-2, -1, 0, 1, 2}, abs, max);
(%o1) {- 2, 2}
(%i2) extremal_subset ({sqrt(2), 1.57, %pi/2}, sin, min);
(%o2) {sqrt(2)}
```

**flatten** ( $expr$ )

Function

Collects arguments of subexpressions which have the same operator as  $expr$  and constructs an expression from these collected arguments.

Subexpressions in which the operator is different from the main operator of  $expr$  are copied without modification, even if they, in turn, contain some subexpressions in which the operator is the same as for  $expr$ .

It may be possible for `flatten` to construct expressions in which the number of arguments differs from the declared arguments for an operator; this may provoke an error message from the simplifier or evaluator. `flatten` does not try to detect such situations.

Expressions with special representations, for example, canonical rational expressions (CRE), cannot be flattened; in such cases, `flatten` returns its argument unchanged.

Examples:

Applied to a list, `flatten` gathers all list elements that are lists.

```
(%i1) flatten ([a, b, [c, [d, e], f], [[g, h]], i, j]);
(%o1) [a, b, c, d, e, f, g, h, i, j]
```

Applied to a set, `flatten` gathers all members of set elements that are sets.

```
(%i1) flatten ({a, {b}, {{c}}});
(%o1) {a, b, c}
(%i2) flatten ({a, {[a], {a}}});
(%o2) {a, [a]}
```

**flatten** is similar to the effect of declaring the main operator n-ary. However, **flatten** has no effect on subexpressions which have an operator different from the main operator, while an n-ary declaration affects those.

```
(%i1) expr: flatten (f (g (f (f (x)))));
(%o1) f(g(f(f(x))))
(%i2) declare (f, nary);
(%o2) done
(%i3) ev (expr);
(%o3) f(g(f(x)))
```

**flatten** treats subscripted functions the same as any other operator.

```
(%i1) flatten (f[5] (f[5] (x, y), z));
(%o1) f (x, y, z)
5
```

It may be possible for **flatten** to construct expressions in which the number of arguments differs from the declared arguments for an operator;

```
(%i1) 'mod (5, 'mod (7, 4));
(%o1) mod(5, mod(7, 4))
(%i2) flatten (%);
(%o2) mod(5, 7, 4)
(%i3) ',"% nouns;
Wrong number of arguments to mod
-- an error. Quitting. To debug this try debugmode(true);
```

### **full\_listify** (*a*)

Function

Replaces every set operator in *a* by a list operator, and returns the result. **full\_listify** replaces set operators in nested subexpressions, even if the main operator is not **set**.

**listify** replaces only the main operator.

Examples:

```
(%i1) full_listify ({a, b, {c, {d, e, f}}, g});
(%o1) [a, b, [c, [d, e, f], g]]
(%i2) full_listify (F (G ({a, b, H({c, d, e}}))));
(%o2) F(G([a, b, H([c, d, e]])))
```

### **fullsetify** (*a*)

Function

When *a* is a list, replaces the list operator with a set operator, and applies **fullsetify** to each member which is a set. When *a* is not a list, it is returned unchanged.

**setify** replaces only the main operator.

Examples:

In line (%o2), the argument of **f** isn't converted to a set because the main operator of **f**([b]) isn't a list.

```
(%i1) fullsetify ([a, [a]]);
(%o1) {a, {a}}
(%i2) fullsetify ([a, f([b])]);
(%o2) {a, f([b])}
```

### **identity** (*x*)

Function

Returns *x* for any argument *x*.

Examples:

**identity** may be used as a predicate when the arguments are already Boolean values.

```
(%i1) every (identity, [true, true]);
(%o1) true
```

**integer\_partitions** (*n*)

Function

**integer\_partitions** (*n*, *len*)

Function

Returns integer partitions of *n*, that is, lists of integers which sum to *n*.

**integer\_partitions**(*n*) returns the set of all partitions of the integer *n*. Each partition is a list sorted from greatest to least.

**integer\_partitions**(*n*, *len*) returns all partitions that have length *len* or less; in this case, zeros are appended to each partition with fewer than *len* terms to make each partition have exactly *len* terms. Each partition is a list sorted from greatest to least.

A list  $[a_1, \dots, a_m]$  is a partition of a nonnegative integer *n* when (1) each  $a_i$  is a nonzero integer, and (2)  $a_1 + \dots + a_m = n$ . Thus 0 has no partitions.

Examples:

```
(%i1) integer_partitions (3);
(%o1) {[1, 1, 1], [2, 1], [3]}
(%i2) s: integer_partitions (25)$
(%i3) cardinality (s);
(%o3) 1958
(%i4) map (lambda ([x], apply ("+", x)), s);
(%o4) {25}
(%i5) integer_partitions (5, 3);
(%o5) {[2, 2, 1], [3, 1, 1], [3, 2, 0], [4, 1, 0], [5, 0, 0]}
(%i6) integer_partitions (5, 2);
(%o6) {[3, 2], [4, 1], [5, 0]}
```

To find all partitions that satisfy a condition, use the function **subset**; here is an example that finds all partitions of 10 that consist of prime numbers.

```
(%i1) s: integer_partitions (10)$
(%i2) cardinality (s);
(%o2) 42
(%i3) xprimep(x) := integerp(x) and (x > 1) and primep(x)$
(%i4) subset (s, lambda ([x], every (xprimep, x)));
(%o4) {[2, 2, 2, 2, 2], [3, 3, 2, 2], [5, 3, 2], [5, 5], [7, 3]}
```

**intersect** (*a\_1*, ..., *a\_n*)

Function

**intersect** is the same as **intersection**, which see.

**intersection** (*a\_1*, ..., *a\_n*)

Function

Returns a set containing the elements that are common to the sets *a\_1* through *a\_n*.

**intersection** complains if any argument is not a literal set.

Examples:

```
(%i1) S_1 : {a, b, c, d};
(%o1) {a, b, c, d}
(%i2) S_2 : {d, e, f, g};
(%o2) {d, e, f, g}
(%i3) S_3 : {c, d, e, f};
(%o3) {c, d, e, f}
(%i4) S_4 : {u, v, w};
(%o4) {u, v, w}
(%i5) intersection (S_1, S_2);
(%o5) {d}
(%i6) intersection (S_2, S_3);
(%o6) {d, e, f}
```

```
(%i7) intersection (S_1, S_2, S_3);
(%o7) {d}
(%i8) intersection (S_1, S_2, S_3, S_4);
(%o8) {}
```

**kron\_delta** (*x1, x2, ..., xp*)

Function

Represents the Kronecker delta function.

**kron\_delta** simplifies to 1 when *xi* and *yj* are equal for all pairs of arguments, and it simplifies to 0 when *xi* and *yj* are not equal for some pair of arguments. Equality is determined using **is(equal(xi,xj))** and inequality by **is(notequal(xi,xj))**. For exactly one argument, **kron\_delta** signals an error.

Examples:

```
(%i1) kron_delta(a,a);
(%o1) 1
(%i2) kron_delta(a,b,a,b);
(%o2) kron_delta(a, b)
(%i3) kron_delta(a,a,b,a+1);
(%o3) 0
(%i4) assume(equal(x,y));
(%o4) [equal(x, y)]
(%i5) kron_delta(x,y);
(%o5) 1
```

**listify** (*a*)

Function

Returns a list containing the members of *a* when *a* is a set. Otherwise, **listify** returns *a*.

**full\_listify** replaces all set operators in *a* by list operators.

Examples:

```
(%i1) listify ({a, b, c, d});
(%o1) [a, b, c, d]
(%i2) listify (F ({a, b, c, d}));
(%o2) F({a, b, c, d})
```

**lreduce** (*F, s*)

Function

**lreduce** (*F, s, s\_0*)

Function

Extends the binary function *F* to an *n*-ary function by composition, where *s* is a list.

**lreduce**(*F, s*) returns **F(... F(F(*s*\_1, *s*\_2), *s*\_3), ... *s*\_n)**. When the optional argument *s\_0* is present, the result is equivalent to **lreduce**(*F, cons*(*s\_0, s*)).

The function *F* is first applied to the *leftmost* list elements, thus the name "lreduce".

See also **rreduce**, **xreduce**, and **tree\_reduce**.

Examples:

**lreduce** without the optional argument.

```
(%i1) lreduce (f, [1, 2, 3]);
(%o1) f(f(1, 2), 3)
(%i2) lreduce (f, [1, 2, 3, 4]);
(%o2) f(f(f(1, 2), 3), 4)
```

**lreduce** with the optional argument.

```
(%i1) lreduce (f, [1, 2, 3], 4);
(%o1) f(f(f(4, 1), 2), 3)
```

**lreduce** applied to built-in binary operators. / is the division operator.

```
(%i1) lreduce ("^", args ({a, b, c, d}));
 b c d
(%o1) ((a))
(%i2) lreduce ("/", args ({a, b, c, d}));
 a
(%o2) -----
 b c d
```

**makeset** (*expr*, *x*, *s*)

Function

Returns a set with members generated from the expression *expr*, where *x* is a list of variables in *expr*, and *s* is a set or list of lists. To generate each set member, *expr* is evaluated with the variables *x* bound in parallel to a member of *s*.

Each member of *s* must have the same length as *x*. The list of variables *x* must be a list of symbols, without subscripts. Even if there is only one symbol, *x* must be a list of one element, and each member of *s* must be a list of one element.

See also `makelist`.

Examples:

```
(%i1) makeset (i/j, [i, j], [[1, a], [2, b], [3, c], [4, d]]);
 1 2 3 4
(%o1) {-, -, -, -}
 a b c d

(%i2) S : {x, y, z}$
(%i3) S3 : cartesian_product (S, S, S);
(%o3) {[x, x, x], [x, x, y], [x, x, z], [x, y, x], [x, y, y],
[x, y, z], [x, z, x], [x, z, y], [x, z, z], [y, x, x],
[y, x, y], [y, x, z], [y, y, x], [y, y, y], [y, y, z],
[y, z, x], [y, z, y], [y, z, z], [z, x, x], [z, x, y],
[z, x, z], [z, y, x], [z, y, y], [z, y, z], [z, z, x],
[z, z, y], [z, z, z]}
(%i4) makeset (i + j + k, [i, j, k], S3);
(%o4) {3 x, 3 y, y + 2 x, 2 y + x, 3 z, z + 2 x, z + y + x,
 z + 2 y, 2 z + x, 2 z + y}

(%i5) makeset (sin(x), [x], {[1], [2], [3]});
(%o5) {sin(1), sin(2), sin(3)}
```

**moebius** (*n*)

Function

Represents the Moebius function.

When *n* is product of *k* distinct primes, `moebius(n)` simplifies to  $(-1)^k$ ; when *n* = 1, it simplifies to 1; and it simplifies to 0 for all other positive integers.

`moebius` distributes over equations, lists, matrices, and sets.

Examples:

```
(%i1) moebius (1);
(%o1) 1
(%i2) moebius (2 * 3 * 5);
(%o2) - 1
(%i3) moebius (11 * 17 * 29 * 31);
(%o3) 1
(%i4) moebius (2^32);
(%o4) 0
(%i5) moebius (n);
(%o5) moebius(n)
(%i6) moebius (n = 12);
(%o6) moebius(n) = 0
(%i7) moebius ([11, 11 * 13, 11 * 13 * 15]);
```



```
(%o7) [- 1, 1, 1]
(%i8) moebius (matrix ([11, 12], [13, 14]));
 [- 1 0]
(%o8) []
 [- 1 1]
(%i9) moebius ({21, 22, 23, 24});
(%o9) {- 1, 0, 1}
```

**multinomial\_coeff** ( $a_1, \dots, a_n$ )

Function

**multinomial\_coeff** ()

Function

Returns the multinomial coefficient.

When each  $a_k$  is a nonnegative integer, the multinomial coefficient gives the number of ways of placing  $a_1 + \dots + a_n$  distinct objects into  $n$  boxes with  $a_k$  elements in the  $k$ 'th box. In general, **multinomial\_coeff** ( $a_1, \dots, a_n$ ) evaluates to  $(a_1 + \dots + a_n)! / (a_1! \dots a_n!)$ .

**multinomial\_coeff**() (with no arguments) evaluates to 1.

**minfactorial** may be able to simplify the value returned by **multinomial\_coeff**.

Examples:

```
(%i1) multinomial_coeff (1, 2, x);
 (x + 3)!
(%o1) -----
 2 x!

(%i2) minfactorial (%);
 (x + 1) (x + 2) (x + 3)
(%o2) -----
 2
 2
(%i3) multinomial_coeff (-6, 2);
 (- 4)!
(%o3) -----
 2 (- 6)!

(%i4) minfactorial (%);
(%o4) 10
```

**num\_distinct\_partitions** ( $n$ )

Function

**num\_distinct\_partitions** ( $n, list$ )

Function

Returns the number of distinct integer partitions of  $n$  when  $n$  is a nonnegative integer. Otherwise, **num\_distinct\_partitions** returns a noun expression.

**num\_distinct\_partitions**( $n, list$ ) returns a list of the number of distinct partitions of 1, 2, 3, ...,  $n$ .

A distinct partition of  $n$  is a list of distinct positive integers  $k_1, \dots, k_m$  such that  $n = k_1 + \dots + k_m$ .

Examples:

```
(%i1) num_distinct_partitions (12);
(%o1) 15
(%i2) num_distinct_partitions (12, list);
(%o2) [1, 1, 1, 2, 2, 3, 4, 5, 6, 8, 10, 12, 15]
(%i3) num_distinct_partitions (n);
(%o3) num_distinct_partitions(n)
```

**num\_partitions** ( $n$ )

Function

**num\_partitions** ( $n, list$ )

Function

Returns the number of integer partitions of  $n$  when  $n$  is a nonnegative integer. Otherwise, **num\_partitions** returns a noun expression.

`num_partitions(n, list)` returns a list of the number of integer partitions of 1, 2, 3, ...,  $n$ .

For a nonnegative integer  $n$ , `num_partitions(n)` is equal to `cardinality(integer_partitions(n))`; however, `num_partitions` does not actually construct the set of partitions, so it is much faster.

Examples:

```
(%i1) num_partitions (5) = cardinality (integer_partitions (5));
(%o1) 7 = 7
(%i2) num_partitions (8, list);
(%o2) [1, 1, 2, 3, 5, 7, 11, 15, 22]
(%i3) num_partitions (n);
(%o3) num_partitions(n)
```

### **partition\_set** ( $a, f$ )

Function

Partitions the set  $a$  according to the predicate  $f$ .

`partition_set` returns a list of two sets. The first set comprises the elements of  $a$  for which  $f$  evaluates to `false`, and the second comprises any other elements of  $a$ . `partition_set` does not apply  $f$  to the return value of  $f$ .

`partition_set` complains if  $a$  is not a literal set.

See also `subset`.

Examples:

```
(%i1) partition_set ({2, 7, 1, 8, 2, 8}, evenp);
(%o1) [{1, 7}, {2, 8}]
(%i2) partition_set ({x, rat(y), rat(y) + z, 1},
 lambda ([x], ratp(x)));
(%o2)/R/ [{1, x}, {y, y + z}]
```

### **permutations** ( $a$ )

Function

Returns a set of all distinct permutations of the members of the list or set  $a$ . Each permutation is a list, not a set.

When  $a$  is a list, duplicate members of  $a$  are included in the permutations.

`permutations` complains if  $a$  is not a literal list or set.

See also `random_permutation`.

Examples:

```
(%i1) permutations ([a, a]);
(%o1) {[a, a]}
(%i2) permutations ([a, a, b]);
(%o2) {[a, a, b], [a, b, a], [b, a, a]}
```

### **powerset** ( $a$ )

Function

### **powerset** ( $a, n$ )

Function

Returns the set of all subsets of  $a$ , or a subset of that set.

`powerset(a)` returns the set of all subsets of the set  $a$ . `powerset(a)` has  $2^{\text{cardinality}(a)}$  members.

`powerset(a, n)` returns the set of all subsets of  $a$  that have cardinality  $n$ .

`powerset` complains if  $a$  is not a literal set, or if  $n$  is not a nonnegative integer.

Examples:

```
(%i1) powerset ({a, b, c});
(%o1) [{}, {a}, {a, b}, {a, b, c}, {a, c}, {b}, {b, c}, {c}]
(%i2) powerset ({w, x, y, z}, 4);
(%o2) {{w, x, y, z}}
(%i3) powerset ({w, x, y, z}, 3);
```



**setdifference** (*a*, *b*)

Function

Returns a set containing the elements in the set *a* that are not in the set *b*.

**setdifference** complains if either *a* or *b* is not a literal set.

Examples:

```
(%i1) S_1 : {a, b, c, x, y, z};
(%o1) {a, b, c, x, y, z}
(%i2) S_2 : {aa, bb, c, x, y, zz};
(%o2) {aa, bb, c, x, y, zz}
(%i3) setdifference (S_1, S_2);
(%o3) {a, b, z}
(%i4) setdifference (S_2, S_1);
(%o4) {aa, bb, zz}
(%i5) setdifference (S_1, S_1);
(%o5) {}
(%i6) setdifference (S_1, {});
(%o6) {a, b, c, x, y, z}
(%i7) setdifference ({}, S_1);
(%o7) {}
```

**setequalp** (*a*, *b*)

Function

Returns **true** if sets *a* and *b* have the same number of elements and **is**(*x* = *y*) is **true** for *x* in the elements of *a* and *y* in the elements of *b*, considered in the order determined by **listify**. Otherwise, **setequalp** returns **false**.

Examples:

```
(%i1) setequalp ({1, 2, 3}, {1, 2, 3});
(%o1) true
(%i2) setequalp ({a, b, c}, {1, 2, 3});
(%o2) false
(%i3) setequalp ({x^2 - y^2}, {(x + y) * (x - y)});
(%o3) false
```

**setify** (*a*)

Function

Constructs a set from the elements of the list *a*. Duplicate elements of the list *a* are deleted and the elements are sorted according to the predicate **orderlessp**.

**setify** complains if *a* is not a literal list.

Examples:

```
(%i1) setify ([1, 2, 3, a, b, c]);
(%o1) {1, 2, 3, a, b, c}
(%i2) setify ([a, b, c, a, b, c]);
(%o2) {a, b, c}
(%i3) setify ([7, 13, 11, 1, 3, 9, 5]);
(%o3) {1, 3, 5, 7, 9, 11, 13}
```

**setp** (*a*)

Function

Returns **true** if and only if *a* is a Maxima set.

**setp** returns **true** for unsimplified sets (that is, sets with redundant members) as well as simplified sets.

**setp** is equivalent to the Maxima function **setp**(*a*) := not **atom**(*a*) and **op**(*a*) = 'set.

Examples:

```
(%i1) simp : false;
(%o1) false
(%i2) {a, a, a};
(%o2) {a, a, a}
(%i3) setp (%);
(%o3) true
```

**set\_partitions** (*a*)

Function

**set\_partitions** (*a*, *n*)

Function

Returns the set of all partitions of *a*, or a subset of that set.

**set\_partitions**(*a*, *n*) returns a set of all decompositions of *a* into *n* nonempty disjoint subsets.

**set\_partitions**(*a*) returns the set of all partitions.

**stirling2** returns the cardinality of the set of partitions of a set.

A set of sets *P* is a partition of a set *S* when

1. each member of *P* is a nonempty set,
2. distinct members of *P* are disjoint,
3. the union of the members of *P* equals *S*.

Examples:

The empty set is a partition of itself, the conditions 1 and 2 being vacuously true.

```
(%i1) set_partitions ({});
(%o1) {{{}}
```

The cardinality of the set of partitions of a set can be found using **stirling2**.

```
(%i1) s: {0, 1, 2, 3, 4, 5}$
(%i2) p: set_partitions (s, 3)$
(%i3) cardinality(p) = stirring2 (6, 3);
(%o3) 90 = 90
```

Each member of *p* should have *n* = 3 members; let's check.

```
(%i1) s: {0, 1, 2, 3, 4, 5}$
(%i2) p: set_partitions (s, 3)$
(%i3) map (cardinality, p);
(%o3) {3}
```

Finally, for each member of *p*, the union of its members should equal *s*; again let's check.

```
(%i1) s: {0, 1, 2, 3, 4, 5}$
(%i2) p: set_partitions (s, 3)$
(%i3) map (lambda ([x], apply (union, listify (x))), p);
(%o3) {{0, 1, 2, 3, 4, 5}}
```

**some** (*f*, *a*)

Function

**some** (*f*, *L\_1*, ..., *L\_n*)

Function

Returns **true** if the predicate *f* is **true** for one or more given arguments.

Given one set as the second argument, **some**(*f*, *s*) returns **true** if **is**(*f*(*a\_i*)) returns **true** for one or more *a\_i* in *s*. **some** may or may not evaluate *f* for all *a\_i* in *s*. Since sets are unordered, **some** may evaluate *f*(*a\_i*) in any order.

Given one or more lists as arguments, **some**(*f*, *L\_1*, ..., *L\_n*) returns **true** if **is**(*f*(*x\_1*, ..., *x\_n*)) returns **true** for one or more *x\_1*, ..., *x\_n* in *L\_1*, ..., *L\_n*, respectively. **some** may or may not evaluate *f* for some combinations *x\_1*, ..., *x\_n*. **some** evaluates lists in the order of increasing index.

Given an empty set {} or empty lists [] as arguments, **some** returns **false**.

When the global flag **maperror** is **true**, all lists *L\_1*, ..., *L\_n* must have equal lengths. When **maperror** is **false**, list arguments are effectively truncated to the length of the shortest list.

Return values of the predicate *f* which evaluate (via **is**) to something other than **true** or **false** are governed by the global flag **prederror**. When **prederror** is **true**, such values are treated as **false**. When **prederror** is **false**, such values are treated as **unknown**.

Examples:

**some** applied to a single set. The predicate is a function of one argument.

```
(%i1) some (integerp, {1, 2, 3, 4, 5, 6});
(%o1) true
(%i2) some (atom, {1, 2, sin(3), 4, 5 + y, 6});
(%o2) true
```

`some` applied to two lists. The predicate is a function of two arguments.

```
(%i1) some ("=", [a, b, c], [a, b, c]);
(%o1) true
(%i2) some ("#", [a, b, c], [a, b, c]);
(%o2) false
```

Return values of the predicate  $f$  which evaluate to something other than `true` or `false` are governed by the global flag `prederror`.

```
(%i1) prederror : false;
(%o1) false
(%i2) map (lambda ([a, b], is (a < b)), [x, y, z],
 [x^2, y^2, z^2]);
(%o2) [unknown, unknown, unknown]
(%i3) some ("<", [x, y, z], [x^2, y^2, z^2]);
(%o3) unknown
(%i4) some ("<", [x, y, z], [x^2, y^2, z + 1]);
(%o4) true
(%i5) prederror : true;
(%o5) true
(%i6) some ("<", [x, y, z], [x^2, y^2, z^2]);
(%o6) false
(%i7) some ("<", [x, y, z], [x^2, y^2, z + 1]);
(%o7) true
```

## **stirling1** ( $n, m$ )

Function

Represents the Stirling number of the first kind.

When  $n$  and  $m$  are nonnegative integers, the magnitude of `stirling1` ( $n, m$ ) is the number of permutations of a set with  $n$  members that have  $m$  cycles. For details, see Graham, Knuth and Patashnik *Concrete Mathematics*. Maxima uses a recursion relation to define `stirling1` ( $n, m$ ) for  $m$  less than 0; it is undefined for  $n$  less than 0 and for non-integer arguments.

`stirling1` is a simplifying function. Maxima knows the following identities.

1.  $stirling1(0, n) = kron_{delta}(0, n)$  (Ref. [1])
2.  $stirling1(n, n) = 1$  (Ref. [1])
3.  $stirling1(n, n - 1) = binomial(n, 2)$  (Ref. [1])
4.  $stirling1(n + 1, 0) = 0$  (Ref. [1])
5.  $stirling1(n + 1, 1) = n!$  (Ref. [1])
6.  $stirling1(n + 1, 2) = 2^n - 1$  (Ref. [1])

These identities are applied when the arguments are literal integers or symbols declared as integers, and the first argument is nonnegative. `stirling1` does not simplify for non-integer arguments.

References:

[1] Donald Knuth, *The Art of Computer Programming*, third edition, Volume 1, Section 1.2.6, Equations 48, 49, and 50.

Examples:

```
(%i1) declare (n, integer)$
(%i2) assume (n >= 0)$
(%i3) stirling1 (n, n);
(%o3)
```

1

`stirling1` does not simplify for non-integer arguments.

```
(%i1) stirling1 (sqrt(2), sqrt(2));
(%o1) stirling1(sqrt(2), sqrt(2))
```

Maxima applies identities to `stirling1`.

```
(%i1) declare (n, integer)$
(%i2) assume (n >= 0)$
(%i3) stirling1 (n + 1, n);

(%o3)
$$\frac{n (n + 1)}{2}$$

(%i4) stirling1 (n + 1, 1);
(%o4)
$$n!$$

```

### **stirling2** (*n*, *m*)

Function

Represents the Stirling number of the second kind.

When *n* and *m* are nonnegative integers, `stirling2` (*n*, *m*) is the number of ways a set with cardinality *n* can be partitioned into *m* disjoint subsets. Maxima uses a recursion relation to define `stirling2` (*n*, *m*) for *m* less than 0; it is undefined for *n* less than 0 and for non-integer arguments.

`stirling2` is a simplifying function. Maxima knows the following identities.

1.  $stirling2(0, n) = kron_{delta}(0, n)$  (Ref. [1])
2.  $stirling2(n, n) = 1$  (Ref. [1])
3.  $stirling2(n, n - 1) = binomial(n, 2)$  (Ref. [1])
4.  $stirling2(n + 1, 1) = 1$  (Ref. [1])
5.  $stirling2(n + 1, 2) = 2^n - 1$  (Ref. [1])
6.  $stirling2(n, 0) = kron_{delta}(n, 0)$  (Ref. [2])
7.  $stirling2(n, m) = 0$  when  $m > n$  (Ref. [2])
8.  $stirling2(n, m) = sum((-1)^{(m-k)} binomial(mk) k^n, i, 1, m) / m!$  when *m* and *n* are integers, and *n* is nonnegative. (Ref. [3])

These identities are applied when the arguments are literal integers or symbols declared as integers, and the first argument is nonnegative. `stirling2` does not simplify for non-integer arguments.

References:

- [1] Donald Knuth. *The Art of Computer Programming*, third edition, Volume 1, Section 1.2.6, Equations 48, 49, and 50.
- [2] Graham, Knuth, and Patashnik. *Concrete Mathematics*, Table 264.
- [3] Abramowitz and Stegun. *Handbook of Mathematical Functions*, Section 24.1.4.

Examples:

```
(%i1) declare (n, integer)$
(%i2) assume (n >= 0)$
(%i3) stirling2 (n, n);
(%o3) 1
```

`stirling2` does not simplify for non-integer arguments.

```
(%i1) stirling2 (%pi, %pi);
(%o1) stirling2(%pi, %pi)
```

Maxima applies identities to `stirling2`.

```
(%i1) declare (n, integer)$
(%i2) assume (n >= 0)$
(%i3) stirling2 (n + 9, n + 8);

(%o3)
$$\frac{(n + 8) (n + 9)}{2}$$

(%i4) stirling2 (n + 1, 2);

(%o4)
$$\frac{n}{2} - 1$$

```

**subset** (*a*, *f*)

Function

Returns the subset of the set *a* that satisfies the predicate *f*.

**subset** returns a set which comprises the elements of *a* for which *f* returns anything other than false. **subset** does not apply **is** to the return value of *f*.

**subset** complains if *a* is not a literal set.

See also **partition\_set**.

Examples:

```
(%i1) subset ({1, 2, x, x + y, z, x + y + z}, atom);
(%o1) {1, 2, x, z}
(%i2) subset ({1, 2, 7, 8, 9, 14}, evenp);
(%o2) {2, 8, 14}
```

**subsetp** (*a*, *b*)

Function

Returns **true** if and only if the set *a* is a subset of *b*.

**subsetp** complains if either *a* or *b* is not a literal set.

Examples:

```
(%i1) subsetp ({1, 2, 3}, {a, 1, b, 2, c, 3});
(%o1) true
(%i2) subsetp ({a, 1, b, 2, c, 3}, {1, 2, 3});
(%o2) false
```

**symmdifference** (*a*<sub>1</sub>, ..., *a*<sub>*n*</sub>)

Function

Returns the symmetric difference of sets *a*<sub>1</sub>, ..., *a*<sub>*n*</sub>.

Given two arguments, **symmdifference** (*a*, *b*) is the same as **union** (**setdifference** (*a*, *b*), **setdifference** (*b*, *a*)).

**symmdifference** complains if any argument is not a literal set.

Examples:

```
(%i1) S_1 : {a, b, c};
(%o1) {a, b, c}
(%i2) S_2 : {1, b, c};
(%o2) {1, b, c}
(%i3) S_3 : {a, b, z};
(%o3) {a, b, z}
(%i4) symmdifference ();
(%o4) {}
(%i5) symmdifference (S_1);
(%o5) {a, b, c}
(%i6) symmdifference (S_1, S_2);
(%o6) {1, a}
(%i7) symmdifference (S_1, S_2, S_3);
(%o7) {1, b, z}
(%i8) symmdifference ({}, S_1, S_2, S_3);
(%o8) {1, b, z}
```

**tree\_reduce** (*F*, *s*)

Function

**tree\_reduce** (*F*, *s*, *s*<sub>0</sub>)

Function

Extends the binary function *F* to an *n*-ary function by composition, where *s* is a set or list.

**tree\_reduce** is equivalent to the following: Apply *F* to successive pairs of elements to form a new list [*F*(*s*<sub>1</sub>, *s*<sub>2</sub>), *F*(*s*<sub>3</sub>, *s*<sub>4</sub>), ...], carrying the final element unchanged if there are an odd number of elements. Then repeat until the list is reduced to a single element, which is the return value.



When the optional argument `s_0` is present, the result is equivalent `tree_reduce(F, cons(s_0, s))`.

For addition of floating point numbers, `tree_reduce` may return a sum that has a smaller rounding error than either `rreduce` or `lreduce`.

The elements of `s` and the partial results may be arranged in a minimum-depth binary tree, thus the name "tree\_reduce".

Examples:

`tree_reduce` applied to a list with an even number of elements.

```
(%i1) tree_reduce (f, [a, b, c, d]);
(%o1) f(f(a, b), f(c, d))
```

`tree_reduce` applied to a list with an odd number of elements.

```
(%i1) tree_reduce (f, [a, b, c, d, e]);
(%o1) f(f(f(a, b), f(c, d)), e)
```

**union** (*a\_1*, ..., *a\_n*)

Function

Returns the union of the sets *a\_1* through *a\_n*.

`union()` (with no arguments) returns the empty set.

`union` complains if any argument is not a literal set.

Examples:

```
(%i1) S_1 : {a, b, c + d, %e};
(%o1) {e, a, b, d + c}
(%i2) S_2 : {%pi, %i, %e, c + d};
(%o2) {e, %i, %pi, d + c}
(%i3) S_3 : {17, 29, 1729, %pi, %i};
(%o3) {17, 29, 1729, %i, %pi}
(%i4) union ();
(%o4) {}
(%i5) union (S_1);
(%o5) {e, a, b, d + c}
(%i6) union (S_1, S_2);
(%o6) {e, %i, %pi, a, b, d + c}
(%i7) union (S_1, S_2, S_3);
(%o7) {17, 29, 1729, %e, %i, %pi, a, b, d + c}
(%i8) union ({}, S_1, S_2, S_3);
(%o8) {17, 29, 1729, %e, %i, %pi, a, b, d + c}
```

**xreduce** (*F*, *s*)

Function

**xreduce** (*F*, *s*, *s\_0*)

Function

Extends the function *F* to an n-ary function by composition, or, if *F* is already n-ary, applies *F* to *s*. When *F* is not n-ary, `xreduce` is the same as `lreduce`. The argument *s* is a list.

Functions known to be n-ary include addition `+`, multiplication `*`, `and`, `or`, `max`, `min`, and `append`. Functions may also be declared n-ary by `declare(F, nary)`. For these functions, `xreduce` is expected to be faster than either `rreduce` or `lreduce`.

When the optional argument `s_0` is present, the result is equivalent to `xreduce(s, cons(s_0, s))`.

Floating point addition is not exactly associative; be that as it may, `xreduce` applies Maxima's n-ary addition when *s* contains floating point numbers.

Examples:

`xreduce` applied to a function known to be n-ary. *F* is called once, with all arguments.

```
(%i1) declare (F, nary);
(%o1) done
(%i2) F ([L]) := L;
(%o2) F([L]) := L
(%i3) xreduce (F, [a, b, c, d, e]);
(%o3) [[[[["(", simp), a], b], c], d], e]
```

`xreduce` applied to a function not known to be n-ary. `G` is called several times, with two arguments each time.

```
(%i1) G ([L]) := L;
(%o1) G([L]) := L
(%i2) xreduce (G, [a, b, c, d, e]);
(%o2) [[[[["(", simp), a], b], c], d], e]
(%i3) lreduce (G, [a, b, c, d, e]);
(%o3) [[[a, b], c], d], e]
```

## 36 Function Definition

### 36.1 Introduction to Function Definition

### 36.2 Function

#### 36.2.1 Ordinary functions

To define a function in Maxima you use the `:=` operator. E.g.

```
f(x) := sin(x)
```

defines a function `f`. Anonymous functions may also be created using `lambda`. For example

```
lambda ([i, j], ...)
```

can be used instead of `f` where

```
f(i,j) := block ([], ...);
map (lambda ([i], i+1), 1)
```

would return a list with 1 added to each term.

You may also define a function with a variable number of arguments, by having a final argument which is assigned to a list of the extra arguments:

```
(%i1) f ([u]) := u;
(%o1) f([u]) := u
(%i2) f (1, 2, 3, 4);
(%o2) [1, 2, 3, 4]
(%i3) f (a, b, [u]) := [a, b, u];
(%o3) f(a, b, [u]) := [a, b, u]
(%i4) f (1, 2, 3, 4, 5, 6);
(%o4) [1, 2, [3, 4, 5, 6]]
```

The right hand side of a function is an expression. Thus if you want a sequence of expressions, you do

```
f(x) := (expr1, expr2, ..., exprn);
```

and the value of `exprn` is what is returned by the function.

If you wish to make a `return` from some expression inside the function then you must use `block` and `return`.

```
block ([], expr1, ..., if (a > 10) then return(a), ..., exprn)
```

is itself an expression, and so could take the place of the right hand side of a function definition. Here it may happen that the return happens earlier than the last expression.

The first `[]` in the block, may contain a list of variables and variable assignments, such as `[a: 3, b, c: []]`, which would cause the three variables `a`, `b`, and `c` to not refer to their global values, but rather have these special values for as long as the code executes inside the `block`, or inside functions called from inside the `block`. This is called *dynamic* binding, since the variables last from the start of the block to the time it exits. Once you return from the `block`, or throw out of it, the old values (if any) of the variables will be restored. It is certainly a good idea to protect your variables in this way. Note that the assignments in the block variables, are done in parallel. This means, that if you had used `c: a` in the above, the value of `c` would have been the value of `a` at the time you just entered the block, but before `a` was bound. Thus doing something like

```
block ([a: a], expr1, ... a: a+3, ..., exprn)
```

will protect the external value of `a` from being altered, but would let you access what that value was. Thus the right hand side of the assignments, is evaluated in the entering context, before any binding occurs. Using just `block ([x], ...)` would cause the `x` to have itself as value, just as if it would have if you entered a fresh Maxima session.

The actual arguments to a function are treated in exactly same way as the variables in a block. Thus in



```
(%o3) x + 1758
```

`e` is bound to a list, which appears as such in the arguments of `foo`, and interpolated into the arguments of `bar`.

```
(%i1) buildq ([e: [a, b, c]], foo (x, e, y));
(%o1) foo(x, [a, b, c], y)
(%i2) buildq ([e: [a, b, c]], bar (x, splice (e), y));
(%o2) bar(x, a, b, c, y)
```

The result is simplified after substitution. If simplification were applied before substitution, these two results would be the same.

```
(%i1) buildq ([e: [a, b, c]], splice (e) + splice (e));
(%o1) 2 c + 2 b + 2 a
(%i2) buildq ([e: [a, b, c]], 2 * splice (e));
(%o2) 2 a b c
```

The variables in `L` are bound in parallel; if bound sequentially, the first result would be `foo (b, b)`. Substitutions are carried out in parallel; compare the second result with the result of `subst`, which carries out substitutions sequentially.

```
(%i1) buildq ([a: b, b: a], foo (a, b));
(%o1) foo(b, a)
(%i2) buildq ([u: v, v: w, w: x, x: y, y: z, z: u],
 bar (u, v, w, x, y, z));
(%o2) bar(v, w, x, y, z, u)
(%i3) subst ([u=v, v=w, w=x, x=y, y=z, z=u],
 bar (u, v, w, x, y, z));
(%o3) bar(u, u, u, u, u, u)
```

Construct a list of equations with some variables or expressions on the left-hand side and their values on the right-hand side. `macroexpand` shows the expression returned by `show_values`.

```
(%i1) show_values ([L]) ::= buildq ([L], map ("=", 'L, L));
(%o1) show_values([L]) ::= buildq([L], map("=", 'L, L))
(%i2) (a: 17, b: 29, c: 1729)$
(%i3) show_values (a, b, c - a - b);
(%o3) [a = 17, b = 29, c - b - a = 1683]
(%i4) macroexpand (show_values (a, b, c - a - b));
(%o4) map(=, '([a, b, c - b - a]), [a, b, c - b - a])
```

Given a function of several arguments, create another function for which some of the arguments are fixed.

```
(%i1) curry (f, [a]) :=
 buildq ([f, a], lambda ([[x]], apply (f, append (a, x))))$
(%i2) by3 : curry ("*", 3);
(%o2) lambda([[x]], apply(*, append([3], x)))
(%i3) by3 (a + b);
(%o3) 3 (b + a)
```

## **macroexpand** (*expr*)

Function

Returns the macro expansion of `expr` without evaluating it, when `expr` is a macro function call. Otherwise, `macroexpand` returns `expr`.

If the expansion of `expr` yields another macro function call, that macro function call is also expanded.

`macroexpand` quotes its argument. However, if the expansion of a macro function call has side effects, those side effects are executed.

See also `::=`, `macros`, and `macroexpand1`.

Examples

```

(%i1) g (x) ::= x / 99;
(%o1) g(x) ::= --
 x
 99
(%i2) h (x) ::= buildq ([x], g (x - a));
(%o2) h(x) ::= buildq([x], g(x - a))
(%i3) a: 1234;
(%o3) 1234
(%i4) macroexpand (h (y));
(%o4) y - a

 99
(%i5) h (y);
(%o5) y - 1234

 99

```

**macroexpand1** (*expr*)

Function

Returns the macro expansion of *expr* without evaluating it, when *expr* is a macro function call. Otherwise, **macroexpand1** returns *expr*.

**macroexpand1** quotes its argument. However, if the expansion of a macro function call has side effects, those side effects are executed.

If the expansion of *expr* yields another macro function call, that macro function call is not expanded.

See also **::=**, **macros**, and **macroexpand**.

Examples

```

(%i1) g (x) ::= x / 99;
(%o1) g(x) ::= --
 x
 99
(%i2) h (x) ::= buildq ([x], g (x - a));
(%o2) h(x) ::= buildq([x], g(x - a))
(%i3) a: 1234;
(%o3) 1234
(%i4) macroexpand1 (h (y));
(%o4) g(y - a)
(%i5) h (y);
(%o5) y - 1234

 99

```

**macros**

Global variable

Default value: []

**macros** is the list of user-defined macro functions. The macro function definition operator **::=** puts a new macro function onto this list, and **kill**, **remove**, and **remfunction** remove macro functions from the list.

See also **infolists**.

**splice** (*a*)

Function

Splices (interpolates) the list named by the atom *a* into an expression, but only if **splice** appears within **buildq**; otherwise, **splice** is treated as an undefined function. If appearing within **buildq** as a alone (without **splice**), *a* is substituted (not interpolated) as a list into the result. The argument of **splice** can only be an atom; it cannot be a literal list or an expression which yields a list.

Typically `splice` supplies the arguments for a function or operator. For a function `f`, the expression `f (splice (a))` within `buildq` expands to `f (a[1], a[2], a[3], ...)`. For an operator `o`, the expression `"o" (splice (a))` within `buildq` expands to `"o" (a[1], a[2], a[3], ...)`, where `o` may be any type of operator (typically one which takes multiple arguments). Note that the operator must be enclosed in double quotes.

Examples

```
(%i1) buildq ([x: [1, %pi, z - y]], foo (splice (x)) / length (x));
 foo(1, %pi, z - y)
(%o1) -----
 length([1, %pi, z - y])
(%i2) buildq ([x: [1, %pi]], "/" (splice (x)));
 1
(%o2) ----
 %pi
(%i3) matchfix ("<>", "<>");
(%o3) <>
(%i4) buildq ([x: [1, %pi, z - y]], "<>" (splice (x)));
(%o4) <>1, %pi, z - y<>
```

## 36.4 Functions and Variables for Function Definition

**apply** (*F*, [*x*<sub>1</sub>, ..., *x*<sub>*n*</sub>])

Function

Constructs and evaluates an expression  $F(arg_1, \dots, arg_n)$ .

`apply` does not attempt to distinguish array functions from ordinary functions; when *F* is the name of an array function, `apply` evaluates  $F(\dots)$  (that is, a function call with parentheses instead of square brackets). `arrayapply` evaluates a function call with square brackets in this case.

Examples:

`apply` evaluates its arguments. In this example, `min` is applied to the value of *L*.

```
(%i1) L : [1, 5, -10.2, 4, 3];
(%o1) [1, 5, - 10.2, 4, 3]
(%i2) apply (min, L);
(%o2) - 10.2
```

`apply` evaluates arguments, even if the function *F* quotes them.

```
(%i1) F (x) := x / 1729;
 x
(%o1) F(x) := ----
 1729
(%i2) fname : F;
(%o2) F
(%i3) dispfun (F);
 x
(%t3) F(x) := ----
 1729

(%o3) [%t3]
(%i4) dispfun (fname);
fname is not the name of a user function.
-- an error. Quitting. To debug this try debugmode(true);
(%i5) apply (dispfun, [fname]);
 x
(%t5) F(x) := ----
 1729
(%o5) [%t5]
```

`apply` evaluates the function name  $F$ . Single quote `'` defeats evaluation. `demoivre` is the name of a global variable and also a function.

```
(%i1) demoivre;
(%o1) false
(%i2) demoivre (exp (%i * x));
(%o2) %i sin(x) + cos(x)
(%i3) apply (demoivre, [exp (%i * x)]);
demoivre evaluates to false
Improper name or value in functional position.
-- an error. Quitting. To debug this try debugmode(true);
(%i4) apply ('demoivre, [exp (%i * x)]);
(%o4) %i sin(x) + cos(x)
```

**block** ( $[v_1, \dots, v_m], \text{expr}_1, \dots, \text{expr}_n$ ) Function  
**block** ( $\text{expr}_1, \dots, \text{expr}_n$ ) Function

`block` evaluates  $\text{expr}_1, \dots, \text{expr}_n$  in sequence and returns the value of the last expression evaluated. The sequence can be modified by the `go`, `throw`, and `return` functions. The last expression is  $\text{expr}_n$  unless `return` or an expression containing `throw` is evaluated. Some variables  $v_1, \dots, v_m$  can be declared local to the block; these are distinguished from global variables of the same names. If no variables are declared local then the list may be omitted. Within the block, any variable other than  $v_1, \dots, v_m$  is a global variable.

`block` saves the current values of the variables  $v_1, \dots, v_m$  (if any) upon entry to the block, then unbinds the variables so that they evaluate to themselves. The local variables may be bound to arbitrary values within the block but when the block is exited the saved values are restored, and the values assigned within the block are lost.

The declaration `local(v_1, ..., v_m)` within `block` saves the properties associated with the symbols  $v_1, \dots, v_m$ , removes any properties before evaluating other expressions, and restores any saved properties on exit from the block. Some declarations are implemented as properties of a symbol, including `:=`, `array`, `dependencies`, `atvalue`, `matchdeclare`, `atomgrad`, `constant`, `nonscalar`, `assume`, and some others. The effect of `local` is to make such declarations effective only within the block; otherwise declarations within a block are actually global declarations.

`block` may appear within another `block`. Local variables are established each time a new `block` is evaluated. Local variables appear to be global to any enclosed blocks. If a variable is non-local in a block, its value is the value most recently assigned by an enclosing block, if any, otherwise, it is the value of the variable in the global environment. This policy may coincide with the usual understanding of "dynamic scope".

The value of the block is the value of the last statement or the value of the argument to the function `return` which may be used to exit explicitly from the block. The function `go` may be used to transfer control to the statement of the block that is tagged with the argument to `go`. To tag a statement, precede it by an atomic argument as another statement in the block. For example: `block ([x], x:1, loop, x: x+1, ..., go(loop), ...)`. The argument to `go` must be the name of a tag appearing within the block. One cannot use `go` to transfer to a tag in a block other than the one containing the `go`.

Blocks typically appear on the right side of a function definition but can be used in other places as well.

**break** ( $\text{expr}_1, \dots, \text{expr}_n$ ) Function

Evaluates and prints  $\text{expr}_1, \dots, \text{expr}_n$  and then causes a Maxima break at which point the user can examine and change his environment. Upon typing `exit`; the computation resumes.

**catch** ( $\text{expr}_1, \dots, \text{expr}_n$ ) Function

Evaluates  $\text{expr}_1, \dots, \text{expr}_n$  one by one; if any leads to the evaluation of an expression of the form `throw (arg)`, then the value of the `catch` is the value of `throw (arg)`, and no



further expressions are evaluated. This "non-local return" thus goes through any depth of nesting to the nearest enclosing **catch**. If there is no **catch** enclosing a **throw**, an error message is printed.

If the evaluation of the arguments does not lead to the evaluation of any **throw** then the value of **catch** is the value of *expr<sub>n</sub>*.

```
(%i1) lambda ([x], if x < 0 then throw(x) else f(x))$
(%i2) g(1) := catch (map ('', 1))$
(%i3) g ([1, 2, 3, 7]);
(%o3) [f(1), f(2), f(3), f(7)]
(%i4) g ([1, 2, -3, 7]);
(%o4) - 3
```

The function **g** returns a list of **f** of each element of **l** if **l** consists only of non-negative numbers; otherwise, **g** "catches" the first negative element of **l** and "throws" it up.

|                                                                                        |          |
|----------------------------------------------------------------------------------------|----------|
| <b>compfile</b> ( <i>filename</i> , <i>f<sub>1</sub></i> , ..., <i>f<sub>n</sub></i> ) | Function |
| <b>compfile</b> ( <i>filename</i> , <i>functions</i> )                                 | Function |
| <b>compfile</b> ( <i>filename</i> , <i>all</i> )                                       | Function |

Translates Maxima functions into Lisp and writes the translated code into the file *filename*.

**compfile**(*filename*, *f<sub>1</sub>*, ..., *f<sub>n</sub>*) translates the specified functions. **compfile**(*filename*, *functions*) and **compfile**(*filename*, *all*) translate all user-defined functions.

The Lisp translations are not evaluated, nor is the output file processed by the Lisp compiler. **translate** creates and evaluates Lisp translations. **compile\_file** translates Maxima into Lisp, and then executes the Lisp compiler.

See also **translate**, **translate\_file**, and **compile\_file**.

|                                                                     |          |
|---------------------------------------------------------------------|----------|
| <b>compile</b> ( <i>f<sub>1</sub></i> , ..., <i>f<sub>n</sub></i> ) | Function |
| <b>compile</b> ( <i>functions</i> )                                 | Function |
| <b>compile</b> ( <i>all</i> )                                       | Function |

Translates Maxima functions *f<sub>1</sub>*, ..., *f<sub>n</sub>* into Lisp, evaluates the Lisp translations, and calls the Lisp function **COMPILE** on each translated function. **compile** returns a list of the names of the compiled functions.

**compile** (*all*) or **compile** (*functions*) compiles all user-defined functions.

**compile** quotes its arguments; the quote-quote operator **''** defeats quotation.

|                                                                                                                    |          |
|--------------------------------------------------------------------------------------------------------------------|----------|
| <b>define</b> ( <i>f</i> ( <i>x<sub>1</sub></i> , ..., <i>x<sub>n</sub></i> ), <i>expr</i> )                       | Function |
| <b>define</b> ( <i>f</i> [ <i>x<sub>1</sub></i> , ..., <i>x<sub>n</sub></i> ], <i>expr</i> )                       | Function |
| <b>define</b> ( <i>funmake</i> ( <i>f</i> , [ <i>x<sub>1</sub></i> , ..., <i>x<sub>n</sub></i> ]), <i>expr</i> )   | Function |
| <b>define</b> ( <i>arraymake</i> ( <i>f</i> , [ <i>x<sub>1</sub></i> , ..., <i>x<sub>n</sub></i> ]), <i>expr</i> ) | Function |
| <b>define</b> ( <i>ev</i> ( <i>expr<sub>1</sub></i> ), <i>expr<sub>2</sub></i> )                                   | Function |

Defines a function named *f* with arguments *x<sub>1</sub>*, ..., *x<sub>n</sub>* and function body *expr*. **define** always evaluates its second argument (unless explicitly quoted). The function so defined may be an ordinary Maxima function (with arguments enclosed in parentheses) or an array function (with arguments enclosed in square brackets).

When the last or only function argument *x<sub>n</sub>* is a list of one element, the function defined by **define** accepts a variable number of arguments. Actual arguments are assigned one-to-one to formal arguments *x<sub>1</sub>*, ..., *x<sub>(n - 1)</sub>*, and any further actual arguments, if present, are assigned to *x<sub>n</sub>* as a list.

When the first argument of **define** is an expression of the form *f*(*x<sub>1</sub>*, ..., *x<sub>n</sub>*) or *f*[*x<sub>1</sub>*, ..., *x<sub>n</sub>*], the function arguments are evaluated but *f* is not evaluated, even if there is already a function or variable by that name.

When the first argument is an expression with operator **funmake**, **arraymake**, or **ev**, the first argument is evaluated; this allows for the function name to be computed, as well as the body.

All function definitions appear in the same namespace; defining a function **f** within another function **g** does not automatically limit the scope of **f** to **g**. However, **local(f)** makes the definition of function **f** effective only within the block or other compound expression in which **local** appears.

If some formal argument  $x_k$  is a quoted symbol (after evaluation), the function defined by **define** does not evaluate the corresponding actual argument. Otherwise all actual arguments are evaluated.

See also **:=** and **::=**.

Examples:

**define** always evaluates its second argument (unless explicitly quoted).

```
(%i1) expr : cos(y) - sin(x);
(%o1) cos(y) - sin(x)
(%i2) define (F1 (x, y), expr);
(%o2) F1(x, y) := cos(y) - sin(x)
(%i3) F1 (a, b);
(%o3) cos(b) - sin(a)
(%i4) F2 (x, y) := expr;
(%o4) F2(x, y) := expr
(%i5) F2 (a, b);
(%o5) cos(y) - sin(x)
```

The function defined by **define** may be an ordinary Maxima function or an array function.

```
(%i1) define (G1 (x, y), x.y - y.x);
(%o1) G1(x, y) := x . y - y . x
(%i2) define (G2 [x, y], x.y - y.x);
(%o2) G2 := x . y - y . x
 x, y
```

When the last or only function argument  $x_n$  is a list of one element, the function defined by **define** accepts a variable number of arguments.

```
(%i1) define (H ([L]), '(apply ("+", L)));
(%o1) H([L]) := apply("+", L)
(%i2) H (a, b, c);
(%o2) c + b + a
```

When the first argument is an expression with operator **funmake**, **arraymake**, or **ev**, the first argument is evaluated.

```
(%i1) [F : I, u : x];
(%o1) [I, x]
(%i2) funmake (F, [u]);
(%o2) I(x)
(%i3) define (funmake (F, [u]), cos(u) + 1);
(%o3) I(x) := cos(x) + 1
(%i4) define (arraymake (F, [u]), cos(u) + 1);
(%o4) I := cos(x) + 1
 x
(%i5) define (foo (x, y), bar (y, x));
(%o5) foo(x, y) := bar(y, x)
(%i6) define (ev (foo (x, y)), sin(x) - cos(y));
(%o6) bar(y, x) := sin(x) - cos(y)
```

**define\_variable** (*name*, *default\_value*, *mode*) Function

Introduces a global variable into the Maxima environment. **define\_variable** is useful in user-written packages, which are often translated or compiled.

**define\_variable** carries out the following steps:

1. **mode\_declare** (*name*, *mode*) declares the mode of *name* to the translator. See **mode\_declare** for a list of the possible modes.

2. If the variable is unbound, *default\_value* is assigned to *name*.
3. `declare (name, special)` declares it special.
4. Associates *name* with a test function to ensure that *name* is only assigned values of the declared mode.

The `value_check` property can be assigned to any variable which has been defined via `define_variable` with a mode other than `any`. The `value_check` property is a lambda expression or the name of a function of one variable, which is called when an attempt is made to assign a value to the variable. The argument of the `value_check` function is the would-be assigned value.

`define_variable` evaluates `default_value`, and quotes `name` and `mode`. `define_variable` returns the current value of `name`, which is `default_value` if `name` was unbound before, and otherwise it is the previous value of `name`.

Examples:

`foo` is a Boolean variable, with the initial value `true`.

```
(%i1) define_variable (foo, true, boolean);
(%o1)
true
(%i2) foo;
(%o2)
true
(%i3) foo: false;
(%o3)
false
(%i4) foo: %pi;
Error: foo was declared mode boolean, has value: %pi
-- an error. Quitting. To debug this try debugmode(true);
(%i5) foo;
(%o5)
false
```

`bar` is an integer variable, which must be prime.

```
(%i1) define_variable (bar, 2, integer);
(%o1)
2
(%i2) qput (bar, prime_test, value_check);
(%o2)
prime_test
(%i3) prime_test (y) := if not primep(y) then
 error (y, "is not prime.");
(%o3) prime_test(y) := if not primep(y)
 then error(y, "is not prime.")

(%i4) bar: 1439;
(%o4)
1439
(%i5) bar: 1440;
1440 is not prime.
#0: prime_test(y=1440)
-- an error. Quitting. To debug this try debugmode(true);
(%i6) bar;
(%o6)
1439
```

`baz_quux` is a variable which cannot be assigned a value. The mode `any_check` is like `any`, but `any_check` enables the `value_check` mechanism, and `any` does not.

```
(%i1) define_variable (baz_quux, 'baz_quux, any_check);
(%o1)
baz_quux
(%i2) F: lambda ([y], if y # 'baz_quux then
 error ("Cannot assign to 'baz_quux'."));
(%o2) lambda([y], if y # 'baz_quux
 then error(Cannot assign to 'baz_quux'.))

(%i3) qput (baz_quux, ''F, value_check);
(%o3) lambda([y], if y # 'baz_quux
```

```

 then error(Cannot assign to 'baz_quux'.))
(%i4) baz_quux: 'baz_quux;
(%o4) baz_quux
(%i5) baz_quux: sqrt(2);
Cannot assign to 'baz_quux'.
#0: lambda([y],if y # 'baz_quux then
 error("Cannot assign to 'baz_quux'."))(y=sqrt(2))
-- an error. Quitting. To debug this try debugmode(true);
(%i6) baz_quux;
(%o6) baz_quux

```

**dispfun** (*f<sub>1</sub>*, ..., *f<sub>n</sub>*)

Function

**dispfun** (*all*)

Function

Displays the definition of the user-defined functions *f<sub>1</sub>*, ..., *f<sub>n</sub>*. Each argument may be the name of a macro (defined with `::=`), an ordinary function (defined with `:=` or `define`), an array function (defined with `:=` or `define`, but enclosing arguments in square brackets `[ ]`), a subscripted function, (defined with `:=` or `define`, but enclosing some arguments in square brackets and others in parentheses `( )`) one of a family of subscripted functions selected by a particular subscript value, or a subscripted function defined with a constant subscript.

**dispfun** (*all*) displays all user-defined functions as given by the **functions**, **arrays**, and **macros** lists, omitting subscripted functions defined with constant subscripts.

**dispfun** creates an intermediate expression label (*%t1*, *%t2*, etc.) for each displayed function, and assigns the function definition to the label. In contrast, **fundef** returns the function definition.

**dispfun** quotes its arguments; the quote-quote operator `''` defeats quotation. **dispfun** returns the list of intermediate expression labels corresponding to the displayed functions.

Examples:

```

(%i1) m(x, y) ::= x^(-y);
(%o1) - y
 m(x, y) ::= x
(%i2) f(x, y) := x^(-y);
(%o2) - y
 f(x, y) := x
(%i3) g[x, y] := x^(-y);
(%o3) - y
 g
 x, y
 := x
(%i4) h[x](y) := x^(-y);
(%o4) - y
 h (y) := x
 x
(%i5) i[8](y) := 8^(-y);
(%o5) - y
 i (y) := 8
 8
(%i6) dispfun (m, f, g, h, h[5], h[10], i[8]);
(%t6) - y
 m(x, y) ::= x
(%t7) - y
 f(x, y) := x
(%t8) - y
 g
 x, y
 := x

```

```

(%t9) h (y) := x-y
 x

(%t10) h (y) := --
 5 y
 5

(%t11) h (y) := ---
 10 y
 10

(%t12) i (y) := 8-y
 8

(%o12) [%t6, %t7, %t8, %t9, %t10, %t11, %t12]
(%i12) ',':
(%o12) [m(x, y) := x-y, f(x, y) := x-y, gx, y := x-y,
 h (y) := x-y, h (y) := --, h (y) := ---, i (y) := 8-y]
 x 5 y 10 y 10 8
 5 5 10

```

**fullmap** (*f*, *expr\_1*, ...)

Function

Similar to **map**, but **fullmap** keeps mapping down all subexpressions until the main operators are no longer the same.

**fullmap** is used by the Maxima simplifier for certain matrix manipulations; thus, Maxima sometimes generates an error message concerning **fullmap** even though **fullmap** was not explicitly called by the user.

Examples:

```

(%i1) a + b * c;
(%o1) b c + a
(%i2) fullmap (g, %);
(%o2) g(b) g(c) + g(a)
(%i3) map (g, %th(2));
(%o3) g(b c) + g(a)

```

**fullmapl** (*f*, *list\_1*, ...)

Function

Similar to **fullmap**, but **fullmapl** only maps onto lists and matrices.

Example:

```

(%i1) fullmapl ("+", [3, [4, 5]], [[a, 1], [0, -1.5]]);
(%o1) [[a + 3, 4], [4, 3.5]]

```

**functions**

System variable

Default value: []

**functions** is the list of ordinary Maxima functions in the current session. An ordinary function is a function constructed by **define** or **:=** and called with parentheses (). A function may be defined at the Maxima prompt or in a Maxima file loaded by **load** or **batch**.

Array functions (called with square brackets, e.g.,  $F[x]$ ) and subscripted functions (called with square brackets and parentheses, e.g.,  $F[x](y)$ ) are listed by the global variable `arrays`, and not by `functions`.

Lisp functions are not kept on any list.

Examples:

```
(%i1) F_1 (x) := x - 100;
(%o1) F_1(x) := x - 100
(%i2) F_2 (x, y) := x / y;
(%o2) F_2(x, y) := -
 x
 y
(%i3) define (F_3 (x), sqrt (x));
(%o3) F_3(x) := sqrt(x)
(%i4) G_1 [x] := x - 100;
(%o4) G_1 := x - 100
 x
(%i5) G_2 [x, y] := x / y;
(%o5) G_2 := -
 x, y
 y
(%i6) define (G_3 [x], sqrt (x));
(%o6) G_3 := sqrt(x)
 x
(%i7) H_1 [x] (y) := x^y;
(%o7) H_1 (y) := x
 x
(%i8) functions;
(%o8) [F_1(x), F_2(x, y), F_3(x)]
(%i9) arrays;
(%o9) [G_1, G_2, G_3, H_1]
```

## **fundef** (*f*)

Function

Returns the definition of the function *f*.

The argument may be the name of a macro (defined with `::=`), an ordinary function (defined with `:=` or `define`), an array function (defined with `:=` or `define`, but enclosing arguments in square brackets `[ ]`), a subscripted function, (defined with `:=` or `define`, but enclosing some arguments in square brackets and others in parentheses `( )`) one of a family of subscripted functions selected by a particular subscript value, or a subscripted function defined with a constant subscript.

**fundef** quotes its argument; the quote-quote operator `''` defeats quotation.

**fundef** (*f*) returns the definition of *f*. In contrast, **dispfun** (*f*) creates an intermediate expression label and assigns the definition to the label.

## **funmake** (*F*, [*arg\_1*, ..., *arg\_n*])

Function

Returns an expression  $F(\text{arg}_1, \dots, \text{arg}_n)$ . The return value is simplified, but not evaluated, so the function *F* is not called, even if it exists.

**funmake** does not attempt to distinguish array functions from ordinary functions; when *F* is the name of an array function, **funmake** returns  $F(\dots)$  (that is, a function call with parentheses instead of square brackets). **arraymake** returns a function call with square brackets in this case.

**funmake** evaluates its arguments.

Examples:

**funmake** applied to an ordinary Maxima function.

```
(%i1) F (x, y) := y^2 - x^2;

(%o1) 2 2
 F(x, y) := y - x
(%i2) funmake (F, [a + 1, b + 1]);
(%o2) 2 2
 F(a + 1, b + 1)
(%i3) ',';

(%o3) 2 2
 (b + 1) - (a + 1)
```

funmake applied to a macro.

```
(%i1) G (x) ::= (x - 1)/2;

(%o1) x - 1
 G(x) ::= ----
 2

(%i2) funmake (G, [u]);
(%o2) G(u)
(%i3) ',';

(%o3) u - 1

 2
```

funmake applied to a subscripted function.

```
(%i1) H [a] (x) := (x - 1)^a;

(%o1) a
 H (x) := (x - 1)

(%i2) funmake (H [n], [%e]);

(%o2) n
 lambda([x], (x - 1))(%e)
(%i3) ',';

(%o3) n
 (%e - 1)
(%i4) funmake ('(H [n]), [%e]);
(%o4) H (%e)
 n

(%i5) ',';

(%o5) n
 (%e - 1)
```

funmake applied to a symbol which is not a defined function of any kind.

```
(%i1) funmake (A, [u]);
(%o1) A(u)
(%i2) ',';
(%o2) A(u)
```

funmake evaluates its arguments, but not the return value.

```
(%i1) det(a,b,c) := b^2 -4*a*c;

(%o1) 2
 det(a, b, c) := b - 4 a c
(%i2) (x : 8, y : 10, z : 12);
(%o2) 12
(%i3) f : det;
(%o3) det
(%i4) funmake (f, [x, y, z]);
(%o4) det(8, 10, 12)
(%i5) ',';
(%o5) - 284
```

Maxima simplifies funmake's return value.

```
(%i1) funmake (sin, [%pi / 2]);
(%o1) 1
```

|                                                                               |          |
|-------------------------------------------------------------------------------|----------|
| <b>lambda</b> ( $[x_1, \dots, x_m], \text{expr}_1, \dots, \text{expr}_n$ )    | Function |
| <b>lambda</b> ( $[L], \text{expr}_1, \dots, \text{expr}_n$ )                  | Function |
| <b>lambda</b> ( $[x_1, \dots, x_m, L], \text{expr}_1, \dots, \text{expr}_n$ ) | Function |

Defines and returns a lambda expression (that is, an anonymous function). The function may have required arguments  $x_1, \dots, x_m$  and/or optional arguments  $L$ , which appear within the function body as a list. The return value of the function is  $\text{expr}_n$ . A lambda expression can be assigned to a variable and evaluated like an ordinary function. A lambda expression may appear in some contexts in which a function name is expected.

When the function is evaluated, unbound local variables  $x_1, \dots, x_m$  are created. **lambda** may appear within **block** or another **lambda**; local variables are established each time another **block** or **lambda** is evaluated. Local variables appear to be global to any enclosed **block** or **lambda**. If a variable is not local, its value is the value most recently assigned in an enclosing **block** or **lambda**, if any, otherwise, it is the value of the variable in the global environment. This policy may coincide with the usual understanding of "dynamic scope".

After local variables are established,  $\text{expr}_1$  through  $\text{expr}_n$  are evaluated in turn. The special variable **%**, representing the value of the preceding expression, is recognized. **throw** and **catch** may also appear in the list of expressions.

**return** cannot appear in a lambda expression unless enclosed by **block**, in which case **return** defines the return value of the block and not of the lambda expression, unless the block happens to be  $\text{expr}_n$ . Likewise, **go** cannot appear in a lambda expression unless enclosed by **block**.

**lambda** quotes its arguments; the quote-quote operator **''** defeats quotation.

Examples:

- A lambda expression can be assigned to a variable and evaluated like an ordinary function.

```
(%i1) f: lambda ([x], x^2);
(%o1) lambda([x], x^2)
(%i2) f(a);
(%o2) a^2
```

- A lambda expression may appear in contexts in which a function evaluation is expected.

```
(%i3) lambda ([x], x^2) (a);
(%o3) a^2
(%i4) apply (lambda ([x], x^2), [a]);
(%o4) a^2
(%i5) map (lambda ([x], x^2), [a, b, c, d, e]);
(%o5) [a^2, b^2, c^2, d^2, e^2]
```

- Argument variables are local variables. Other variables appear to be global variables. Global variables are evaluated at the time the lambda expression is evaluated, unless some special evaluation is forced by some means, such as **''**.

```
(%i6) a: %pi$
(%i7) b: %e$
(%i8) g: lambda ([a], a*b);
(%o8) lambda([a], a b)
(%i9) b: %gamma$
(%i10) g(1/2);
```



```

 %gamma
(%o10) -----
 2
(%i11) g2: lambda ([a], a**b);
(%o11) lambda([a], a %gamma)
(%i12) b: %e$
(%i13) g2(1/2);
 %gamma
(%o13) -----
 2

```

- Lambda expressions may be nested. Local variables within the outer lambda expression appear to be global to the inner expression unless masked by local variables of the same names.

```

(%i14) h: lambda ([a, b], h2: lambda ([a], a*b), h2(1/2));
 1
(%o14) lambda([a, b], h2 : lambda([a], a b), h2(-))
 2
(%i15) h(%pi, %gamma);
 %gamma
(%o15) -----
 2

```

- Since `lambda` quotes its arguments, lambda expression `i` below does not define a "multiply by `a`" function. Such a function can be defined via `buildq`, as in lambda expression `i2` below.

```

(%i16) i: lambda ([a], lambda ([x], a*x));
(%o16) lambda([a], lambda([x], a x))
(%i17) i(1/2);
(%o17) lambda([x], a x)
(%i18) i2: lambda([a], buildq([a: a], lambda([x], a*x)));
(%o18) lambda([a], buildq([a : a], lambda([x], a x)))
(%i19) i2(1/2);
 x
(%o19) lambda([x], -)
 2
(%i20) i2(1/2)(%pi);
 %pi
(%o20) ----
 2

```

- A lambda expression may take a variable number of arguments, which are indicated by `[L]` as the sole or final argument. The arguments appear within the function body as a list.

```

(%i1) f : lambda ([aa, bb, [cc]], aa * cc + bb);
(%o1) lambda([aa, bb, [cc]], aa cc + bb)
(%i2) f (foo, %i, 17, 29, 256);
(%o2) [17 foo + %i, 29 foo + %i, 256 foo + %i]
(%i3) g : lambda ([[aa]], apply ("+", aa));
(%o3) lambda([[aa]], apply(+, aa))
(%i4) g (17, 29, x, y, z, %e);
(%o4) z + y + x + %e + 46

```

### **local** (*v*<sub>1</sub>, ..., *v*<sub>*n*</sub>)

Function

Saves the properties associated with the symbols *v*<sub>1</sub>, ..., *v*<sub>*n*</sub>, removes any properties before evaluating other expressions, and restores any saved properties on exit from the block or other compound expression in which `local` appears.

Some declarations are implemented as properties of a symbol, including `:=`, `array`, `dependencies`, `atvalue`, `matchdeclare`, `atomgrad`, `constant`, `nonscalar`, `assume`, and

some others. The effect of `local` is to make such declarations effective only within the block or other compound expression in which `local` appears; otherwise such declarations are global declarations.

`local` can only appear in `block` or in the body of a function definition or `lambda` expression, and only one occurrence is permitted in each.

`local` quotes its arguments. `local` returns `done`.

Example:

A local function definition.

```
(%i1) foo (x) := 1 - x;
(%o1) foo(x) := 1 - x
(%i2) foo (100);
(%o2) - 99
(%i3) block (local (foo), foo (x) := 2 * x, foo (100));
(%o3) 200
(%i4) foo (100);
(%o4) - 99
```

## macroexpansion

Option variable

Default value: `false`

`macroexpansion` controls whether the expansion (that is, the return value) of a macro function is substituted for the macro function call. A substitution may speed up subsequent expression evaluations, at the cost of storing the expansion.

- false**      The expansion of a macro function is not substituted for the macro function call.
- expand**    The first time a macro function call is evaluated, the expansion is stored. The expansion is not recomputed on subsequent calls; any side effects (such as `print` or assignment to global variables) happen only when the macro function call is first evaluated. Expansion in an expression does not affect other expressions which have the same macro function call.
- displace**   The first time a macro function call is evaluated, the expansion is substituted for the call, thus modifying the expression from which the macro function was called. The expansion is not recomputed on subsequent calls; any side effects happen only when the macro function call is first evaluated. Expansion in an expression does not affect other expressions which have the same macro function call.

### Examples

When `macroexpansion` is `false`, a macro function is called every time the calling expression is evaluated, and the calling expression is not modified.

```
(%i1) f (x) := h (x) / g (x);
(%o1) h(x)
 f(x) := ----
 g(x)
(%i2) g (x) ::= block (print ("x + 99 is equal to", x),
 return (x + 99));
(%o2) g(x) ::= block(print("x + 99 is equal to", x),
 return(x + 99))
(%i3) h (x) ::= block (print ("x - 99 is equal to", x),
 return (x - 99));
(%o3) h(x) ::= block(print("x - 99 is equal to", x),
 return(x - 99))
(%i4) macroexpansion: false;
(%o4) false
(%i5) f (a * b);
x - 99 is equal to x
```

```

x + 99 is equal to x
 a b - 99
(%o5) -----
 a b + 99

(%i6) dispfun (f);
 h(x)
(%t6) f(x) := -----
 g(x)

(%o6) done
(%i7) f (a * b);
x - 99 is equal to x
x + 99 is equal to x
 a b - 99
(%o7) -----
 a b + 99

```

When `macroexpansion` is `expand`, a macro function is called once, and the calling expression is not modified.

```

(%i1) f (x) := h (x) / g (x);
 h(x)
(%o1) f(x) := -----
 g(x)
(%i2) g (x) ::= block (print ("x + 99 is equal to", x),
 return (x + 99));
(%o2) g(x) ::= block(print("x + 99 is equal to", x),
 return(x + 99))
(%i3) h (x) ::= block (print ("x - 99 is equal to", x),
 return (x - 99));
(%o3) h(x) ::= block(print("x - 99 is equal to", x),
 return(x - 99))

(%i4) macroexpansion: expand;
(%o4) expand
(%i5) f (a * b);
x - 99 is equal to x
x + 99 is equal to x
 a b - 99
(%o5) -----
 a b + 99

(%i6) dispfun (f);
 h(x)
(%t6) f(x) := -----
 g(x)

(%o6) done
(%i7) f (a * b);
 a b - 99
(%o7) -----
 a b + 99

```

When `macroexpansion` is `expand`, a macro function is called once, and the calling expression is modified.

```

(%i1) f (x) := h (x) / g (x);
 h(x)
(%o1) f(x) := -----
 g(x)
(%i2) g (x) ::= block (print ("x + 99 is equal to", x),
 return (x + 99));

```

```

(%o2) g(x) ::= block(print("x + 99 is equal to", x),
 return(x + 99))
(%i3) h (x) ::= block (print ("x - 99 is equal to", x),
 return (x - 99));
(%o3) h(x) ::= block(print("x - 99 is equal to", x),
 return(x - 99))

(%i4) macroexpansion: displace;
(%o4) displace
(%i5) f (a * b);
x - 99 is equal to x
x + 99 is equal to x
 a b - 99
(%o5) -----
 a b + 99
(%i6) dispfun (f);
 x - 99
(%t6) f(x) := -----
 x + 99

(%o6) done
(%i7) f (a * b);
 a b - 99
(%o7) -----
 a b + 99

```

**mode\_checkp**

Option variable

Default value: `true`When `mode_checkp` is `true`, `mode_declare` checks the modes of bound variables.**mode\_check\_errorp**

Option variable

Default value: `false`When `mode_check_errorp` is `true`, `mode_declare` calls `error`.**mode\_check\_warnp**

Option variable

Default value: `true`When `mode_check_warnp` is `true`, mode errors are described.**mode\_declare** (*y<sub>1</sub>*, *mode<sub>1</sub>*, ..., *y<sub>n</sub>*, *mode<sub>n</sub>*)

Function

`mode_declare` is used to declare the modes of variables and functions for subsequent translation or compilation of functions. `mode_declare` is typically placed at the beginning of a function definition, at the beginning of a Maxima script, or executed at the interactive prompt.

The arguments of `mode_declare` are pairs consisting of a variable and a mode which is one of `boolean`, `fixnum`, `number`, `rational`, or `float`. Each variable may also be a list of variables all of which are declared to have the same mode.

If a variable is an array, and if every element of the array which is referenced has a value then `array (yi, complete, dim1, dim2, ...)` rather than

```
array(yi, dim1, dim2, ...)
```

should be used when first declaring the bounds of the array. If all the elements of the array are of mode `fixnum` (`float`), use `fixnum` (`float`) instead of `complete`. Also if every element of the array is of the same mode, say `m`, then

```
mode_declare (completearray (yi), m))
```

should be used for efficient translation.

Numeric code using arrays might run faster by declaring the expected size of the array, as in:

```
mode_declare (completearray (a [10, 10]), float)
```

for a floating point number array which is 10 x 10.

One may declare the mode of the result of a function by using `function (f_1, f_2, ...)` as an argument; here `f_1`, `f_2`, ... are the names of functions. For example the expression,

```
mode_declare ([function (f_1, f_2, ...)], fixnum)
```

declares that the values returned by `f_1`, `f_2`, ... are single-word integers.

`modedeclare` is a synonym for `mode_declare`.

### **mode\_identity** (*arg-1*, *arg-2*)

Function

A special form used with `mode_declare` and `macros` to declare, e.g., a list of lists of flonums, or other compound data object. The first argument to `mode_identity` is a primitive value mode name as given to `mode_declare` (i.e., one of `float`, `fixnum`, `number`, `list`, or `any`), and the second argument is an expression which is evaluated and returned as the value of `mode_identity`. However, if the return value is not allowed by the mode declared in the first argument, an error or warning is signalled. The important thing is that the mode of the expression as determined by the Maxima to Lisp translator, will be that given as the first argument, independent of anything that goes on in the second argument. E.g., `x: 3.3; mode_identity (fixnum, x);` yields an error. `mode_identity (flonum, x)` returns 3.3. This has a number of uses, e.g., if you knew that `first (l)` returned a number then you might write `mode_identity (number, first (l))`. However, a more efficient way to do it would be to define a new primitive,

```
firstnumb (x) ::= buildq ([x], mode_identity (number, x));
```

and use `firstnumb` every time you take the first of a list of numbers.

### **remfunction** (*f\_1*, ..., *f\_n*)

Function

### **remfunction** (*all*)

Function

Unbinds the function definitions of the symbols *f\_1*, ..., *f\_n*. The arguments may be the names of ordinary functions (created by `:=` or `define`) or macro functions (created by `::=`).

`remfunction (all)` unbinds all function definitions.

`remfunction` quotes its arguments.

`remfunction` returns a list of the symbols for which the function definition was unbound. `false` is returned in place of any symbol for which there is no function definition.

`remfunction` does not apply to array functions or subscripted functions. `remarray` applies to those types of functions.

### **savedef**

Option variable

Default value: `true`

When `savedef` is `true`, the Maxima version of a user function is preserved when the function is translated. This permits the definition to be displayed by `dispfun` and allows the function to be edited.

When `savedef` is `false`, the names of translated functions are removed from the functions list.

### **transcompile**

Option variable

Default value: `true`

When `transcompile` is `true`, `translate` and `translate_file` generate declarations to make the translated code more suitable for compilation.

`compile` sets `transcompile: true` for the duration.

|                                                   |          |
|---------------------------------------------------|----------|
| <b>translate</b> ( <i>f_1</i> , ..., <i>f_n</i> ) | Function |
| <b>translate</b> ( <i>functions</i> )             | Function |
| <b>translate</b> ( <i>all</i> )                   | Function |

Translates the user-defined functions *f\_1*, ..., *f\_n* from the Maxima language into Lisp and evaluates the Lisp translations. Typically the translated functions run faster than the originals.

**translate** (*all*) or **translate** (*functions*) translates all user-defined functions.

Functions to be translated should include a call to **mode\_declare** at the beginning when possible in order to produce more efficient code. For example:

```
f (x_1, x_2, ...) := block ([v_1, v_2, ...],
 mode_declare (v_1, mode_1, v_2, mode_2, ...), ...)
```

where the *x\_1*, *x\_2*, ... are the parameters to the function and the *v\_1*, *v\_2*, ... are the local variables.

The names of translated functions are removed from the **functions** list if **savedef** is **false** (see below) and are added to the **props** lists.

Functions should not be translated unless they are fully debugged.

Expressions are assumed simplified; if they are not, correct but non-optimal code gets generated. Thus, the user should not set the **simp** switch to **false** which inhibits simplification of the expressions to be translated.

The switch **translate**, if **true**, causes automatic translation of a user's function to Lisp. Note that translated functions may not run identically to the way they did before translation as certain incompatibilities may exist between the Lisp and Maxima versions. Principally, the **rat** function with more than one argument and the **ratvars** function should not be used if any variables are **mode\_declare**'d canonical rational expressions (CRE). Also the **prederror: false** setting will not translate.

**savedef** - if **true** will cause the Maxima version of a user function to remain when the function is **translate**'d. This permits the definition to be displayed by **dispfun** and allows the function to be edited.

**transrun** - if **false** will cause the interpreted version of all functions to be run (provided they are still around) rather than the translated version.

The result returned by **translate** is a list of the names of the functions translated.

|                                                                         |          |
|-------------------------------------------------------------------------|----------|
| <b>translate_file</b> ( <i>maxima_filename</i> )                        | Function |
| <b>translate_file</b> ( <i>maxima_filename</i> , <i>lisp_filename</i> ) | Function |

Translates a file of Maxima code into a file of Lisp code. **translate\_file** returns a list of three filenames: the name of the Maxima file, the name of the Lisp file, and the name of file containing additional information about the translation. **translate\_file** evaluates its arguments.

**translate\_file** ("foo.mac"); **load** ("foo.LISP") is the same as the command **batch** ("foo.mac") except for certain restrictions, the use of **'** and **%**, for example.

**translate\_file** (*maxima\_filename*) translates a Maxima file *maxima\_filename* into a similarly-named Lisp file. For example, **foo.mac** is translated into **foo.LISP**. The Maxima filename may include a directory name or names, in which case the Lisp output file is written to the same directory from which the Maxima input comes.

**translate\_file** (*maxima\_filename*, *lisp\_filename*) translates a Maxima file *maxima\_filename* into a Lisp file *lisp\_filename*. **translate\_file** ignores the filename extension, if any, of *lisp\_filename*; the filename extension of the Lisp output file is always **LISP**. The Lisp filename may include a directory name or names, in which case the Lisp output file is written to the specified directory.

**translate\_file** also writes a file of translator warning messages of various degrees of severity. The filename extension of this file is **UNLISP**. This file may contain valuable information, though possibly obscure, for tracking down bugs in translated code. The **UNLISP** file is always written to the same directory from which the Maxima input comes.

**translate\_file** emits Lisp code which causes some declarations and definitions to take effect as soon as the Lisp code is compiled. See **compile\_file** for more on this topic.

See also

`tr_array_as_ref`,  
`tr_bound_function_applyp`,  
`tr_exponent`,  
`tr_file_tty_messagesp`,  
`tr_float_can_branch_complex`,  
`tr_function_call_default`,  
`tr_numer`,  
`tr_optimize_max_loop`,  
`tr_semicompile`,  
`tr_state_vars`,  
`tr_warnings_get`,  
`tr_warn_bad_function_calls`,  
`tr_warn_fexpr`,  
`tr_warn_meval`,  
`tr_warn_mode`,  
`tr_warn_undeclared`,  
and `tr_warn_undefined_variable`.

### **transrun**

Option variable

Default value: `true`

When `transrun` is `false` will cause the interpreted version of all functions to be run (provided they are still around) rather than the translated version.

### **tr\_array\_as\_ref**

Option variable

Default value: `true`

If `translate_fast_arrays` is `false`, array references in Lisp code emitted by `translate_file` are affected by `tr_array_as_ref`. When `tr_array_as_ref` is `true`, array names are evaluated, otherwise array names appear as literal symbols in translated code.

`tr_array_as_ref` has no effect if `translate_fast_arrays` is `true`.

### **tr\_bound\_function\_applyp**

Option variable

Default value: `true`

When `tr_bound_function_applyp` is `true`, Maxima gives a warning if a bound variable (such as a function argument) is found being used as a function. `tr_bound_function_applyp` does not affect the code generated in such cases.

For example, an expression such as `g (f, x) := f (x+1)` will trigger the warning message.

### **tr\_file\_tty\_messagesp**

Option variable

Default value: `false`

When `tr_file_tty_messagesp` is `true`, messages generated by `translate_file` during translation of a file are displayed on the console and inserted into the UNLISP file. When `false`, messages about translation of the file are only inserted into the UNLISP file.

### **tr\_float\_can\_branch\_complex**

Option variable

Default value: `true`

Tells the Maxima-to-Lisp translator to assume that the functions `acos`, `asin`, `asec`, and `acsc` can return complex results.

The ostensible effect of `tr_float_can_branch_complex` is the following. However, it appears that this flag has no effect on the translator output.

When it is `true` then `acos(x)` is of mode `any` even if `x` is of mode `float` (as set by `mode_declare`). When `false` then `acos(x)` is of mode `float` if and only if `x` is of mode `float`.



**tr\_function\_call\_default**

Option variable

Default value: `general`

`false` means give up and call `meval`, `expr` means assume Lisp fixed arg function. `general`, the default gives code good for `mexprs` and `mlexprs` but not `macros`. `general` assures variable bindings are correct in compiled code. In `general` mode, when translating `F(X)`, if `F` is a bound variable, then it assumes that `apply (f, [x])` is meant, and translates a such, with appropriate warning. There is no need to turn this off. With the default settings, no warning messages implies full compatibility of translated and compiled code with the Maxima interpreter.

**tr\_numer**

Option variable

Default value: `false`

When `tr_numer` is `true`, `numer` properties are used for atoms which have them, e.g. `%pi`.

**tr\_optimize\_max\_loop**

Option variable

Default value: 100

`tr_optimize_max_loop` is the maximum number of times the macro-expansion and optimization pass of the translator will loop in considering a form. This is to catch macro expansion errors, and non-terminating optimization properties.

**tr\_semicompile**

Option variable

Default value: `false`

When `tr_semicompile` is `true`, `translate_file` and `compile` output forms which will be macroexpanded but not compiled into machine code by the Lisp compiler.

**tr\_state\_vars**

System variable

Default value:

```
[transcompile, tr_semicompile, tr_warn_undeclared, tr_warn_meval,
tr_warn_fexpr, tr_warn_mode, tr_warn_undefined_variable,
tr_function_call_default, tr_array_as_ref, tr_numer]
```

The list of the switches that affect the form of the translated output. This information is useful to system people when trying to debug the translator. By comparing the translated product to what should have been produced for a given state, it is possible to track down bugs.

**tr\_warnings\_get ()**

Function

Prints a list of warnings which have been given by the translator during the current translation.

**tr\_warn\_bad\_function\_calls**

Option variable

Default value: `true`

- Gives a warning when when function calls are being made which may not be correct due to improper declarations that were made at translate time.

**tr\_warn\_fexpr**

Option variable

Default value: `compile`

- Gives a warning if any FEXPRs are encountered. FEXPRs should not normally be output in translated code, all legitimate special program forms are translated.

**tr\_warn\_meval**

Option variable

Default value: `compile`

- Gives a warning if the function `meval` gets called. If `meval` is called that indicates problems in the translation.



**tr\_warn\_mode** Option variable

Default value: `all`

- Gives a warning when variables are assigned values inappropriate for their mode.

**tr\_warn\_undeclared** Option variable

Default value: `compile`

- Determines when to send warnings about undeclared variables to the TTY.

**tr\_warn\_undefined\_variable** Option variable

Default value: `all`

- Gives a warning when undefined global variables are seen.

**compile\_file** (*filename*) Function

**compile\_file** (*filename*, *compiled\_filename*) Function

**compile\_file** (*filename*, *compiled\_filename*, *lisp\_filename*) Function

Translates the Maxima file *filename* into Lisp, executes the Lisp compiler, and, if the translation and compilation succeed, loads the compiled code into Maxima.

`compile_file` returns a list of the names of four files: the original Maxima file, the Lisp translation, notes on translation, and the compiled code. If the compilation fails, the fourth item is `false`.

Some declarations and definitions take effect as soon as the Lisp code is compiled (without loading the compiled code). These include functions defined with the `:=` operator, macros define with the `::=` operator, `alias`, `declare`, `define_variable`, `mode_declare`, and `infix`, `matchfix`, `nofix`, `postfix`, `prefix`, and `compile`.

Assignments and function calls are not evaluated until the compiled code is loaded. In particular, within the Maxima file, assignments to the translation flags (`tr_numer`, etc.) have no effect on the translation.

*filename* may not contain `:lisp` statements.

`compile_file` evaluates its arguments.

**declare\_translated** (*f\_1*, *f\_2*, ...) Function

When translating a file of Maxima code to Lisp, it is important for the translator to know which functions it sees in the file are to be called as translated or compiled functions, and which ones are just Maxima functions or undefined. Putting this declaration at the top of the file, lets it know that although a symbol does which does not yet have a Lisp function value, will have one at call time. (`MFUNCTION-CALL fn arg1 arg2 ...`) is generated when the translator does not know `fn` is going to be a Lisp function.



## 37 Program Flow

### 37.1 Lisp and Maxima

Maxima is written in Lisp, and it is easy to access Lisp functions and variables from Maxima and vice versa. Lisp and Maxima symbols are distinguished by a naming convention. A Lisp symbol which begins with a dollar sign `$` corresponds to a Maxima symbol without the dollar sign.

A Maxima symbol which begins with a question mark `?` corresponds to a Lisp symbol without the question mark. For example, the Maxima symbol `foo` corresponds to the Lisp symbol `$F00`, while the Maxima symbol `?foo` corresponds to the Lisp symbol `F00`. Note that `?foo` is written without a space between `?` and `foo`; otherwise it might be mistaken for `describe ("foo")`.

Hyphen `-`, asterisk `*`, or other special characters in Lisp symbols must be escaped by backslash `\` where they appear in Maxima code. For example, the Lisp identifier `*foo-bar*` is written `?\*foo\~bar\*` in Maxima.

Lisp code may be executed from within a Maxima session. A single line of Lisp (containing one or more forms) may be executed by the special command `:lisp`. For example,

```
(%i1) :lisp (foo $x $y)
```

calls the Lisp function `foo` with Maxima variables `x` and `y` as arguments. The `:lisp` construct can appear at the interactive prompt or in a file processed by `batch` or `demo`, but not in a file processed by `load`, `batchload`, `translate_file`, or `compile_file`.

The function `to_lisp` opens an interactive Lisp session. Entering `(to-maxima)` closes the Lisp session and returns to Maxima.

Lisp functions and variables which are to be visible in Maxima as functions and variables with ordinary names (no special punctuation) must have Lisp names beginning with the dollar sign `$`.

Maxima is case-sensitive, distinguishing between lowercase and uppercase letters in identifiers. There are some rules governing the translation of names between Lisp and Maxima.

1. A Lisp identifier not enclosed in vertical bars corresponds to a Maxima identifier in lowercase. Whether the Lisp identifier is uppercase, lowercase, or mixed case, is ignored. E.g., Lisp `$foo`, `$F00`, and `$Foo` all correspond to Maxima `foo`. But this is because `$foo`, `$F00` and `$Foo` are converted by the Lisp reader by default to the Lisp symbol `$F00`.
2. A Lisp identifier which is all uppercase or all lowercase and enclosed in vertical bars corresponds to a Maxima identifier with case reversed. That is, uppercase is changed to lowercase and lowercase to uppercase. E.g., Lisp `|$F00|` and `|$foo|` correspond to Maxima `foo` and `F00`, respectively.
3. A Lisp identifier which is mixed uppercase and lowercase and enclosed in vertical bars corresponds to a Maxima identifier with the same case. E.g., Lisp `|$Foo|` corresponds to Maxima `Foo`.

The `#$` Lisp macro allows the use of Maxima expressions in Lisp code. `#$expr$` expands to a Lisp expression equivalent to the Maxima expression `expr`.

```
(msetq $foo #$[x, y]$)
```

This has the same effect as entering

```
(%i1) foo: [x, y];
```

The Lisp function `displa` prints an expression in Maxima format.

```
(%i1) :lisp #$[x, y, z]$
((MLIST SIMP) $X $Y $Z)
(%i1) :lisp (displa '((MLIST SIMP) $X $Y $Z))
[x, y, z]
NIL
```

Functions defined in Maxima are not ordinary Lisp functions. The Lisp function `mfuncall` calls a Maxima function. For example:

```
(%i1) foo(x,y) := x*y$
(%i2) :lisp (mfuncall '$foo 'a 'b)
((MTIMES SIMP) A B)
```

Some Lisp functions are shadowed in the Maxima package, namely the following.

|            |           |        |
|------------|-----------|--------|
| complement | continue  | //     |
| float      | functionp | array  |
| exp        | listen    | signum |
| atan       | asin      | acos   |
| asinh      | acosh     | atanh  |
| tanh       | cosh      | sinh   |
| tan        | break     | gcd    |

## 37.2 Garbage Collection

Symbolic computation tends to create a good deal of garbage (temporary or intermediate results that are eventually not used), and effective handling of this can be crucial to successful completion of some programs.

Under GCL, on UNIX systems where the `mprotect` system call is available (including SUN OS 4.0 and some variants of BSD) a stratified garbage collection is available. This limits the collection to pages which have been recently written to. See the GCL documentation under `ALLOCATE` and `GBC`. At the Lisp level doing `(setq si::*notify-gbc* t)` will help you determine which areas might need more space.

For other Lisps that run Maxima, we refer the reader to the documentation for that Lisp on how to control GC.

## 37.3 Introduction to Program Flow

Maxima provides a `do` loop for iteration, as well as more primitive constructs such as `go`.

## 37.4 Functions and Variables for Program Flow

|                      |          |
|----------------------|----------|
| <b>backtrace</b> ()  | Function |
| <b>backtrace</b> (n) | Function |

Prints the call stack, that is, the list of functions which called the currently active function.

`backtrace()` prints the entire call stack.

`backtrace (n)` prints the *n* most recent functions, including the currently active function.

`backtrace` can be called from a script, a function, or the interactive prompt (not only in a debugging context).

Examples:

- `backtrace()` prints the entire call stack.

```
(%i1) h(x) := g(x/7)$
(%i2) g(x) := f(x-11)$
(%i3) f(x) := e(x^2)$
(%i4) e(x) := (backtrace(), 2*x + 13)$
(%i5) h(10);
#0: e(x=4489/49)
#1: f(x=-67/7)
#2: g(x=10/7)
#3: h(x=10)
```

```
(%o5) 9615

49
```

- `backtrace (n)` prints the  $n$  most recent functions, including the currently active function.

```
(%i1) h(x) := (backtrace(1), g(x/7))$
(%i2) g(x) := (backtrace(1), f(x-11))$
(%i3) f(x) := (backtrace(1), e(x^2))$
(%i4) e(x) := (backtrace(1), 2*x + 13)$
(%i5) h(10);
#0: h(x=10)
#0: g(x=10/7)
#0: f(x=-67/7)
#0: e(x=4489/49)
```

```
(%o5)
9615

49
```

## do

Special operator

The `do` statement is used for performing iteration. Due to its great generality the `do` statement will be described in two parts. First the usual form will be given which is analogous to that used in several other programming languages (Fortran, Algol, PL/I, etc.); then the other features will be mentioned.

There are three variants of this form that differ only in their terminating conditions. They are:

- `for variable: initial_value step increment thru limit do body`
- `for variable: initial_value step increment while condition do body`
- `for variable: initial_value step increment unless condition do body`

(Alternatively, the `step` may be given after the termination condition or limit.)

*initial\_value*, *increment*, *limit*, and *body* can be any expressions. If the increment is 1 then "`step 1`" may be omitted.

The execution of the `do` statement proceeds by first assigning the *initial\_value* to the *variable* (henceforth called the control-variable). Then: (1) If the control-variable has exceeded the limit of a `thru` specification, or if the condition of the `unless` is `true`, or if the condition of the `while` is `false` then the `do` terminates. (2) The *body* is evaluated. (3) The increment is added to the control-variable. The process from (1) to (3) is performed repeatedly until the termination condition is satisfied. One may also give several termination conditions in which case the `do` terminates when any of them is satisfied.

In general the `thru` test is satisfied when the control-variable is greater than the *limit* if the *increment* was non-negative, or when the control-variable is less than the *limit* if the *increment* was negative. The *increment* and *limit* may be non-numeric expressions as long as this inequality can be determined. However, unless the *increment* is syntactically negative (e.g. is a negative number) at the time the `do` statement is input, Maxima assumes it will be positive when the `do` is executed. If it is not positive, then the `do` may not terminate properly.

Note that the *limit*, *increment*, and termination condition are evaluated each time through the loop. Thus if any of these involve much computation, and yield a result that does not change during all the executions of the *body*, then it is more efficient to set a variable to their value prior to the `do` and use this variable in the `do` form.

The value normally returned by a `do` statement is the atom `done`. However, the function `return` may be used inside the *body* to exit the `do` prematurely and give it any desired value. Note however that a `return` within a `do` that occurs in a `block` will exit only the `do` and not the `block`. Note also that the `go` function may not be used to exit from a `do` into a surrounding `block`.

The control-variable is always local to the `do` and thus any variable may be used without affecting the value of a variable with the same name outside of the `do`. The control-variable is unbound after the `do` terminates.

```
(%i1) for a:-3 thru 26 step 7 do display(a)$
 a = - 3

 a = 4

 a = 11

 a = 18

 a = 25

(%i1) s: 0$
(%i2) for i: 1 while i <= 10 do s: s+i;
(%o2) done
(%i3) s;
(%o3) 55
```

Note that the condition while  $i \leq 10$  is equivalent to unless  $i > 10$  and also thru 10.

```
(%i1) series: 1$
(%i2) term: exp (sin (x))$
(%i3) for p: 1 unless p > 7 do
 (term: diff (term, x)/p,
 series: series + subst (x=0, term)*x^p)$
(%i4) series;

 7 6 5 4 2
 x x x x x
 -- - --- - -- - -- + -- + x + 1
 90 240 15 8 2

(%o4)
```

which gives 8 terms of the Taylor series for  $e^{\sin(x)}$ .

```
(%i1) poly: 0$
(%i2) for i: 1 thru 5 do
 for j: i step -1 thru 1 do
 poly: poly + i*x^j$
(%i3) poly;

 5 4 3 2
 5 x + 9 x + 12 x + 14 x + 15 x

(%o3)
(%i4) guess: -3.0$
(%i5) for i: 1 thru 10 do
 (guess: subst (guess, x, 0.5*(x + 10/x)),
 if abs (guess^2 - 10) < 0.00005 then return (guess));
(%o5) - 3.162280701754386
```

This example computes the negative square root of 10 using the Newton- Raphson iteration a maximum of 10 times. Had the convergence criterion not been met the value returned would have been **done**.

Instead of always adding a quantity to the control-variable one may sometimes wish to change it in some other way for each iteration. In this case one may use **next expression** instead of **step increment**. This will cause the control-variable to be set to the result of evaluating *expression* each time through the loop.

```
(%i6) for count: 2 next 3*count thru 20 do display (count)$
 count = 2

 count = 6

 count = 18
```

As an alternative to **for variable: value ...do...** the syntax **for variable from value ...do...** may be used. This permits the **from value** to be placed after the **step** or **next**

value or after the termination condition. If *from value* is omitted then 1 is used as the initial value.

Sometimes one may be interested in performing an iteration where the control-variable is never actually used. It is thus permissible to give only the termination conditions omitting the initialization and updating information as in the following example to compute the square-root of 5 using a poor initial guess.

```
(%i1) x: 1000$
(%i2) thru 20 do x: 0.5*(x + 5.0/x)$
(%i3) x;
(%o3) 2.23606797749979
(%i4) sqrt(5), numer;
(%o4) 2.23606797749979
```

If it is desired one may even omit the termination conditions entirely and just give *do body* which will continue to evaluate the *body* indefinitely. In this case the function **return** should be used to terminate execution of the *do*.

```
(%i1) newton (f, x):= ([y, df, dfx], df: diff (f ('x), 'x),
do (y: ev(df), x: x - f(x)/y,
if abs (f (x)) < 5e-6 then return (x)))$
(%i2) sqr (x) := x^2 - 5.0$
(%i3) newton (sqr, 1000);
(%o3) 2.236068027062195
```

(Note that **return**, when executed, causes the current value of *x* to be returned as the value of the *do*. The block is exited and this value of the *do* is returned as the value of the block because the *do* is the last statement in the block.)

One other form of the *do* is available in Maxima. The syntax is:

*for variable in list end\_tests do body*

The elements of *list* are any expressions which will successively be assigned to the *variable* on each iteration of the *body*. The optional termination tests *end\_tests* can be used to terminate execution of the *do*; otherwise it will terminate when the *list* is exhausted or when a **return** is executed in the *body*. (In fact, *list* may be any non-atomic expression, and successive parts are taken.)

```
(%i1) for f in [log, rho, atan] do ldisp(f(1))$
(%t1) 0
(%t2) rho(1)
 %pi
(%t3) ---
 4
(%i4) ev(%t3,numer);
(%o4) 0.78539816
```

**errcatch** (*expr\_1, ..., expr\_n*) Function

Evaluates *expr\_1, ..., expr\_n* one by one and returns [*expr\_n*] (a list) if no error occurs. If an error occurs in the evaluation of any argument, **errcatch** prevents the error from propagating and returns the empty list [] without evaluating any more arguments.

**errcatch** is useful in *batch* files where one suspects an error might occur which would terminate the *batch* if the error weren't caught.

**error** (*expr\_1, ..., expr\_n*) Function  
**error** System variable

Evaluates and prints *expr\_1, ..., expr\_n*, and then causes an error return to top level Maxima or to the nearest enclosing **errcatch**.

The variable **error** is set to a list describing the error. The first element of **error** is a format string, which merges all the strings among the arguments *expr\_1, ..., expr\_n*, and the remaining elements are the values of any non-string arguments.

**errormsg**() formats and prints **error**. This is effectively reprinting the most recent error message.

**error\_size**

Option variable

Default value: 10

**error\_size** modifies error messages according to the size of expressions which appear in them. If the size of an expression (as determined by the Lisp function **ERROR-SIZE**) is greater than **error\_size**, the expression is replaced in the message by a symbol, and the symbol is assigned the expression. The symbols are taken from the list **error\_syms**.

Otherwise, the expression is smaller than **error\_size**, and the expression is displayed in the message.

See also **error** and **error\_syms**.

Example:

The size of U, as determined by **ERROR-SIZE**, is 24.

```
(%i1) U: (C^D^E + B + A)/(cos(X-1) + 1)$
```

```
(%i2) error_size: 20$
```

```
(%i3) error ("Example expression is", U);
```

Example expression is errexp1

-- an error. Quitting. To debug this try **debugmode(true)**;

```
(%i4) errexp1;
```

```
(%o4)
 E
 D
 C + B + A

cos(X - 1) + 1
```

```
(%i5) error_size: 30$
```

```
(%i6) error ("Example expression is", U);
```

```

 E
 D
 C + B + A

Example expression is -----
cos(X - 1) + 1
```

-- an error. Quitting. To debug this try **debugmode(true)**;

**error\_syms**

Option variable

Default value: [errexp1, errexp2, errexp3]

In error messages, expressions larger than **error\_size** are replaced by symbols, and the symbols are set to the expressions. The symbols are taken from the list **error\_syms**. The first too-large expression is replaced by **error\_syms[1]**, the second by **error\_syms[2]**, and so on.

If there are more too-large expressions than there are elements of **error\_syms**, symbols are constructed automatically, with the *n*-th symbol equivalent to **concat ('errexp, n)**.

See also **error** and **error\_size**.

**errormsg ()**

Function

Reprints the most recent error message. The variable **error** holds the message, and **errormsg** formats and prints it.

**errormsg**

Option variable

Default value: true

When **false** the output of error messages is suppressed.

The option variable **errormsg** can not be set in a block to a local value. The global value of **errormsg** is always present.



```
(%i1) errormsg;
(%o1)
true
(%i2) sin(a,b);
Wrong number of arguments to sin
-- an error. To debug this try: debugmode(true);
(%i3) errormsg:false;
(%o3)
false
(%i4) sin(a,b);

-- an error. To debug this try: debugmode(true);
```

The option variable `errmsg` can not be set in a block to a local value.

```
(%i1) f(bool):=block([errmsg:bool],
 print ("value of errmsg is",errmsg))$
(%i2) errmsg:true;
(%o2)
true
(%i3) f(false);
value of errmsg is true
(%o3)
true
(%i4) errmsg:false;
(%o4)
false
(%i5) f(true);
value of errmsg is false
(%o5)
false
```

**for** Special operator  
Used in iterations. See `do` for a description of Maxima's iteration facilities.

**go** (*tag*) Function  
is used within a `block` to transfer control to the statement of the block which is tagged with the argument to `go`. To tag a statement, precede it by an atomic argument as another statement in the `block`. For example:

```
block ([x], x:1, loop, x+1, ..., go(loop), ...)
```

The argument to `go` must be the name of a tag appearing in the same `block`. One cannot use `go` to transfer to tag in a `block` other than the one containing the `go`.

**if** Special operator  
Represents conditional evaluation. Various forms of `if` expressions are recognized.

`if cond_1 then expr_1 else expr_0` evaluates to `expr_1` if `cond_1` evaluates to `true`, otherwise the expression evaluates to `expr_0`.

The command `if cond_1 then expr_1 elseif cond_2 then expr_2 elseif ... else expr_0` evaluates to `expr_k` if `cond_k` is `true` and all preceding conditions are `false`. If none of the conditions are `true`, the expression evaluates to `expr_0`.

A trailing `else false` is assumed if `else` is missing. That is, the command `if cond_1 then expr_1` is equivalent to `if cond_1 then expr_1 else false`, and the command `if cond_1 then expr_1 elseif ... elseif cond_n then expr_n` is equivalent to `if cond_1 then expr_1 elseif ... elseif cond_n then expr_n else false`.

The alternatives `expr_0`, ..., `expr_n` may be any Maxima expressions, including nested `if` expressions. The alternatives are neither simplified nor evaluated unless the corresponding condition is `true`.

The conditions `cond_1`, ..., `cond_n` are expressions which potentially or actually evaluate to `true` or `false`. When a condition does not actually evaluate to `true` or `false`, the behavior of `if` is governed by the global flag `prederror`. When `prederror` is `true`, it is an error if any evaluated condition does not evaluate to `true` or `false`. Otherwise,

conditions which do not evaluate to **true** or **false** are accepted, and the result is a conditional expression.

Among other elements, conditions may comprise relational and logical operators as follows.

| Operation                | Symbol   | Type                |
|--------------------------|----------|---------------------|
| less than                | <        | relational infix    |
| less than or equal to    | <=       | relational infix    |
| equality (syntactic)     | =        | relational infix    |
| negation of =            | #        | relational infix    |
| equality (value)         | equal    | relational function |
| negation of equal        | notequal | relational function |
| greater than             | >=       | relational infix    |
| greater than or equal to | >        | relational infix    |
| and                      | and      | logical infix       |
| or                       | or       | logical infix       |
| not                      | not      | logical prefix      |

**map** (*f*, *expr\_1*, ..., *expr\_n*) Function

Returns an expression whose leading operator is the same as that of the expressions *expr\_1*, ..., *expr\_n* but whose subparts are the results of applying *f* to the corresponding subparts of the expressions. *f* is either the name of a function of *n* arguments or is a **lambda** form of *n* arguments.

**maperror** - if **false** will cause all of the mapping functions to (1) stop when they finish going down the shortest *expr\_i* if not all of the *expr\_i* are of the same length and (2) apply *f* to [*expr\_1*, *expr\_2*, ...] if the *expr\_i* are not all the same type of object. If **maperror** is **true** then an error message will be given in the above two instances.

One of the uses of this function is to **map** a function (e.g. **partfrac**) onto each term of a very large expression where it ordinarily wouldn't be possible to use the function on the entire expression due to an exhaustion of list storage space in the course of the computation.

```
(%i1) map(f,x+a*y+b*z);
(%o1) f(b z) + f(a y) + f(x)
(%i2) map(lambda([u],partfrac(u,x)),x+1/(x^3+4*x^2+5*x+2));
(%o2)
 1 1 1
 ----- - ----- + ----- + x
 x + 2 x + 1 2
 (x + 1)
(%i3) map(ratsimp, x/(x^2+x)+(y^2+y)/y);
(%o3)
 1
 y + ----- + 1
 x + 1
(%i4) map("=", [a,b], [-0.5,3]);
(%o4) [a = - 0.5, b = 3]
```

**mapatom** (*expr*) Function

Returns **true** if and only if *expr* is treated by the mapping routines as an atom. "Map-atoms" are atoms, numbers (including rational numbers), and subscripted variables.

**maperror** Option variable

Default value: **true**

When **maperror** is **false**, causes all of the mapping functions, for example

`map (f, expr_1, expr_2, ...)`

to (1) stop when they finish going down the shortest *expr\_i* if not all of the *expr\_i* are of the same length and (2) apply *f* to [*expr\_1*, *expr\_2*, ...] if the *expr\_i* are not all the same type of object.

If `maperror` is `true` then an error message is displayed in the above two instances.

## mapprint

Option variable

Default value: `true`

When `mapprint` is `true`, various information messages from `map`, `mapl`, and `fullmap` are produced in certain situations. These include situations where `map` would use `apply`, or `map` is truncating on the shortest list.

If `mapprint` is `false`, these messages are suppressed.

## maplist (f, expr\_1, ..., expr\_n)

Function

Returns a list of the applications of *f* to the parts of the expressions *expr\_1*, ..., *expr\_n*. *f* is the name of a function, or a lambda expression.

`maplist` differs from `map(f, expr_1, ..., expr_n)` which returns an expression with the same main operator as *expr\_i* has (except for simplifications and the case where `map` does an `apply`).

## prederror

Option variable

Default value: `false`

When `prederror` is `true`, an error message is displayed whenever the predicate of an `if` statement or an `is` function fails to evaluate to either `true` or `false`.

If `false`, `unknown` is returned instead in this case. The `prederror: false` mode is not supported in translated code; however, `maybe` is supported in translated code.

See also `is` and `maybe`.

## return (value)

Function

May be used to exit explicitly from a block, bringing its argument. See `block` for more information.

## scanmap (f, expr)

Function

## scanmap (f, expr, bottomup)

Function

Recursively applies *f* to *expr*, in a top down manner. This is most useful when complete factorization is desired, for example:

```
(%i1) exp: (a^2+2*a+1)*y + x^2$
```

```
(%i2) scanmap(factor,exp);
```

```
(%o2) 2 2
 (a + 1) y + x
```

Note the way in which `scanmap` applies the given function `factor` to the constituent subexpressions of *expr*; if another form of *expr* is presented to `scanmap` then the result may be different. Thus, `%o2` is not recovered when `scanmap` is applied to the expanded form of *exp*:

```
(%i3) scanmap(factor,expand(exp));
```

```
(%o3) 2 2
 a y + 2 a y + y + x
```

Here is another example of the way in which `scanmap` recursively applies a given function to all subexpressions, including exponents:

```
(%i4) expr : u*v^(a*x+b) + c$
```

```
(%i5) scanmap('f, expr);
```

```
 f(f(f(a) f(x)) + f(b))
```

```
(%o5) f(f(f(u) f(f(v))) + f(c))
```

`scanmap (f, expr, bottomup)` applies *f* to *expr* in a bottom-up manner. E.g., for undefined *f*,

```

scanmap(f,a*x+b) ->
 f(a*x+b) -> f(f(a*x)+f(b)) -> f(f(f(a)*f(x))+f(b))
scanmap(f,a*x+b,bottomup) -> f(a)*f(x)+f(b)
 -> f(f(a)*f(x))+f(b) ->
 f(f(f(a)*f(x))+f(b))

```

In this case, you get the same answer both ways.

|                                                                                                                                                          |                  |
|----------------------------------------------------------------------------------------------------------------------------------------------------------|------------------|
| <b>throw</b> ( <i>expr</i> )                                                                                                                             | Function         |
| Evaluates <i>expr</i> and throws the value back to the most recent <b>catch</b> . <b>throw</b> is used with <b>catch</b> as a nonlocal return mechanism. |                  |
| <b>while</b>                                                                                                                                             | Special operator |
| <b>unless</b>                                                                                                                                            | Special operator |
| See <b>do</b> .                                                                                                                                          |                  |

**outermap** (*f*, *a*<sub>1</sub>, ..., *a*<sub>*n*</sub>) Function

Applies the function *f* to each one of the elements of the outer product *a*<sub>1</sub> cross *a*<sub>2</sub> ... cross *a*<sub>*n*</sub>.

*f* is the name of a function of *n* arguments or a lambda expression of *n* arguments. Each argument *a*<sub>*k*</sub> may be a list or nested list, or a matrix, or any other kind of expression.

The **outermap** return value is a nested structure. Let *x* be the return value. Then *x* has the same structure as the first list, nested list, or matrix argument, *x*[*i*<sub>1</sub>] ... [*i*<sub>*m*</sub>] has the same structure as the second list, nested list, or matrix argument, *x*[*i*<sub>1</sub>] ... [*i*<sub>*m*</sub>][*j*<sub>1</sub>] ... [*j*<sub>*n*</sub>] has the same structure as the third list, nested list, or matrix argument, and so on, where *m*, *n*, ... are the numbers of indices required to access the elements of each argument (one for a list, two for a matrix, one or more for a nested list). Arguments which are not lists or matrices have no effect on the structure of the return value.

Note that the effect of **outermap** is different from that of applying *f* to each one of the elements of the outer product returned by **cartesian\_product**. **outermap** preserves the structure of the arguments in the return value, while **cartesian\_product** does not.

**outermap** evaluates its arguments.

See also **map**, **maplist**, and **apply**.

Examples:

Elementary examples of **outermap**. To show the argument combinations more clearly, *F* is left undefined.

```

(%i1) outermap(F, [a, b, c], [1, 2, 3]);
(%o1) [[F(a, 1), F(a, 2), F(a, 3)], [F(b, 1), F(b, 2), F(b, 3)],
 [F(c, 1), F(c, 2), F(c, 3)]]
(%i2) outermap(F, matrix([a, b],[c, d]), matrix([1, 2],[3, 4]));
 [[F(a, 1) F(a, 2)] [F(b, 1) F(b, 2)]]
 [[] []]
 [[F(a, 3) F(a, 4)] [F(b, 3) F(b, 4)]]
(%o2) [[] []]
 [[F(c, 1) F(c, 2)] [F(d, 1) F(d, 2)]]
 [[] []]
 [[F(c, 3) F(c, 4)] [F(d, 3) F(d, 4)]]
(%i3) outermap (F, [a, b], x, matrix ([1, 2], [3, 4]));
 [F(a, x, 1) F(a, x, 2)] [F(b, x, 1) F(b, x, 2)]
(%o3) [[], []]
 [F(a, x, 3) F(a, x, 4)] [F(b, x, 3) F(b, x, 4)]
(%i4) outermap (F, [a, b], matrix ([1, 2]), matrix ([x], [y]));
 [[F(a, 1, x)] [F(a, 2, x)]]
(%o4) [[[] []],
 [[F(a, 1, y)] [F(a, 2, y)]]]

```

```

[[F(b, 1, x)] [F(b, 2, x)]]
[[] []]
[[F(b, 1, y)] [F(b, 2, y)]]
(%i5) outermap ("+", [a, b, c], [1, 2, 3]);
(%o5) [[a + 1, a + 2, a + 3], [b + 1, b + 2, b + 3],
 [c + 1, c + 2, c + 3]]

```

A closer examination of the `outermap` return value. The first, second, and third arguments are a matrix, a list, and a matrix, respectively. The return value is a matrix. Each element of that matrix is a list, and each element of each list is a matrix.

```

(%i1) arg_1 : matrix ([a, b], [c, d]);
 [a b]
(%o1) []
 [c d]

(%i2) arg_2 : [11, 22];
(%o2) [11, 22]
(%i3) arg_3 : matrix ([xx, yy]);
(%o3) [xx yy]
(%i4) xx_0 : outermap(lambda([x, y, z], x / y + z), arg_1,
 arg_2, arg_3);
 [[a a] [a a]]
 [[xx + -- yy + --], [xx + -- yy + --]]
 [[11 11] [22 22]]
(%o4) Col 1 = [
 [[c c] [c c]]
 [[xx + -- yy + --], [xx + -- yy + --]]
 [[11 11] [22 22]]
 [[b b] [b b]]
 [[xx + -- yy + --], [xx + -- yy + --]]
 [[11 11] [22 22]]
 Col 2 = [
 [[d d] [d d]]
 [[xx + -- yy + --], [xx + -- yy + --]]
 [[11 11] [22 22]]
(%i5) xx_1 : xx_0 [1][1];
 [a a] [a a]
(%o5) [[xx + -- yy + --], [xx + -- yy + --]]
 [11 11] [22 22]
(%i6) xx_2 : xx_0 [1][1][1];
 [a a]
(%o6) [xx + -- yy + --]
 [11 11]
(%i7) xx_3 : xx_0 [1][1][1][1][1];
 a
(%o7) xx + --
 11
(%i8) [op (arg_1), op (arg_2), op (arg_3)];
(%o8) [matrix, [, matrix]
(%i9) [op (xx_0), op (xx_1), op (xx_2)];
(%o9) [matrix, [, matrix]

```

`outermap` preserves the structure of the arguments in the return value, while `cartesian_product` does not.

```

(%i1) outermap (F, [a, b, c], [1, 2, 3]);
(%o1) [[F(a, 1), F(a, 2), F(a, 3)], [F(b, 1), F(b, 2), F(b, 3)],
 [F(c, 1), F(c, 2), F(c, 3)]]
(%i2) setify (flatten (%));
(%o2) {F(a, 1), F(a, 2), F(a, 3), F(b, 1), F(b, 2), F(b, 3),

```

```
 F(c, 1), F(c, 2), F(c, 3)}
(%i3) map(lambda([L], apply(F, L)),
 cartesian_product({a, b, c}, {1, 2, 3}));
(%o3) {F(a, 1), F(a, 2), F(a, 3), F(b, 1), F(b, 2), F(b, 3),
 F(c, 1), F(c, 2), F(c, 3)}
(%i4) is (equal (% , %th (2)));
(%o4) true
```

## 38 Debugging

### 38.1 Source Level Debugging

Maxima has a built-in source level debugger. The user can set a breakpoint at a function, and then step line by line from there. The call stack may be examined, together with the variables bound at that level.

The command `:help` or `:h` shows the list of debugger commands. (In general, commands may be abbreviated if the abbreviation is unique. If not unique, the alternatives will be listed.) Within the debugger, the user can also use any ordinary Maxima functions to examine, define, and manipulate variables and expressions.

A breakpoint is set by the `:br` command at the Maxima prompt. Within the debugger, the user can advance one line at a time using the `:n` (“next”) command. The `:bt` (“backtrace”) command shows a list of stack frames. The `:r` (“resume”) command exits the debugger and continues with execution. These commands are demonstrated in the example below.

```
(%i1) load ("/tmp/foobar.mac");

(%o1) /tmp/foobar.mac

(%i2) :br foo
Turning on debugging debugmode(true)
Bkpt 0 for foo (in /tmp/foobar.mac line 1)

(%i2) bar (2,3);
Bkpt 0:(foobar.mac 1)
/tmp/foobar.mac:1::

(dbm:1) :bt <-- :bt typed here gives a backtrace
#0: foo(y=5)(foobar.mac line 1)
#1: bar(x=2,y=3)(foobar.mac line 9)

(dbm:1) :n <-- Here type :n to advance line
(foobar.mac 2)
/tmp/foobar.mac:2::

(dbm:1) :n <-- Here type :n to advance line
(foobar.mac 3)
/tmp/foobar.mac:3::

(dbm:1) u; <-- Investigate value of u
28

(dbm:1) u: 33; <-- Change u to be 33
33

(dbm:1) :r <-- Type :r to resume the computation

(%o2) 1094
```

The file `/tmp/foobar.mac` is the following:

```
foo(y) := block ([u:y^2],
 u: u+3,
 u: u^2,
 u);

bar(x,y) := (
```

```
x: x+2,
y: y+2,
x: foo(y),
x+y);
```

### USE OF THE DEBUGGER THROUGH EMACS

If the user is running the code under GNU emacs in a shell window (dbl shell), or is running the graphical interface version, Xmaxima, then if he stops at a break point, he will see his current position in the source file which will be displayed in the other half of the window, either highlighted in red, or with a little arrow pointing at the right line. He can advance single lines at a time by typing M-n (Alt-n).

Under Emacs you should run in a dbl shell, which requires the `dbl.el` file in the elisp directory. Make sure you install the elisp files or add the Maxima elisp directory to your path: e.g., add the following to your `.emacs` file or the `site-init.el`

```
(setq load-path (cons "/usr/share/maxima/5.9.1/emacs" load-path))
(autoload 'dbl "dbl")
```

then in emacs

M-x dbl

should start a shell window in which you can run programs, for example Maxima, gcl, gdb etc. This shell window also knows about source level debugging, and display of source code in the other window.

The user may set a break point at a certain line of the file by typing C-x space. This figures out which function the cursor is in, and then it sees which line of that function the cursor is on. If the cursor is on, say, line 2 of `foo`, then it will insert in the other window the command, `:br foo 2`, to break `foo` at its second line. To have this enabled, the user must have `maxima-mode.el` turned on in the window in which the file `foobar.mac` is visiting. There are additional commands available in that file window, such as evaluating the function into the Maxima, by typing Alt-Control-x.

## 38.2 Keyword Commands

Keyword commands are special keywords which are not interpreted as Maxima expressions. A keyword command can be entered at the Maxima prompt or the debugger prompt, although not at the break prompt. Keyword commands start with a colon, `:'`. For example, to evaluate a Lisp form you may type `:lisp` followed by the form to be evaluated.

```
(%i1) :lisp (+ 2 3)
5
```

The number of arguments taken depends on the particular command. Also, you need not type the whole command, just enough to be unique among the break keywords. Thus `:br` would suffice for `:break`.

The keyword commands are listed below.

**:break F n**

Set a breakpoint in function `F` at line offset `n` from the beginning of the function. If `F` is given as a string, then it is assumed to be a file, and `n` is the offset from the beginning of the file. The offset is optional. If not given, it is assumed to be zero (first line of the function or file).

**:bt** Print a backtrace of the stack frames

**:continue**

Continue the computation

**:delete** Delete the specified breakpoints, or all if none are specified

**:disable** Disable the specified breakpoints, or all if none are specified

**:enable** Enable the specified breakpoints, or all if none are specified

**:frame n** Print stack frame `n`, or the current frame if none is specified



**:help**        Print help on a debugger command, or all commands if none is specified

**:info**        Print information about item

**:lisp some-form**  
              Evaluate **some-form** as a Lisp form

**:lisp-quiet some-form**  
              Evaluate Lisp form **some-form** without any output

**:next**        Like **:step**, except **:next** steps over function calls

**:quit**        Quit the current debugger level without completing the computation

**:resume**     Continue the computation

**:step**        Continue the computation until it reaches a new source line

**:top**        Return to the Maxima prompt (from any debugger level) without completing the computation

### 38.3 Functions and Variables for Debugging

**debugmode** Option variable  
 Default value: **false**  
 When a Maxima error occurs, Maxima will start the debugger if **debugmode** is **true**. The user may enter commands to examine the call stack, set breakpoints, step through Maxima code, and so on. See **debugging** for a list of debugger commands.  
 Enabling **debugmode** will not catch Lisp errors.

**refcheck** Option variable  
 Default value: **false**  
 When **refcheck** is **true**, Maxima prints a message each time a bound variable is used for the first time in a computation.

**setcheck** Option variable  
 Default value: **false**  
 If **setcheck** is set to a list of variables (which can be subscripted), Maxima prints a message whenever the variables, or subscripted occurrences of them, are bound with the ordinary assignment operator **:**, the **::** assignment operator, or function argument binding, but not the function assignment **:=** nor the macro assignment **::=** operators. The message comprises the name of the variable and the value it is bound to.  
**setcheck** may be set to **all** or **true** thereby including all variables.  
 Each new assignment of **setcheck** establishes a new list of variables to check, and any variables previously assigned to **setcheck** are forgotten.  
 The names assigned to **setcheck** must be quoted if they would otherwise evaluate to something other than themselves. For example, if **x**, **y**, and **z** are already bound, then enter  
       **setcheck: ['x, 'y, 'z]\$**  
 to put them on the list of variables to check.  
 No printout is generated when a variable on the **setcheck** list is assigned to itself, e.g.,  
**x: 'X.**

**setcheckbreak** Option variable  
 Default value: **false**  
 When **setcheckbreak** is **true**, Maxima will present a break prompt whenever a variable on the **setcheck** list is assigned a new value. The break occurs before the assignment is carried out. At this point, **setval** holds the value to which the variable is about to be assigned. Hence, one may assign a different value by assigning to **setval**.  
 See also **setcheck** and **setval**.

**setval** System variable  
 Holds the value to which a variable is about to be set when a **setcheckbreak** occurs.  
 Hence, one may assign a different value by assigning to **setval**.  
 See also **setcheck** and **setcheckbreak**.

**timer** (*f<sub>1</sub>*, ..., *f<sub>n</sub>*) Function  
**timer** (*all*) Function  
**timer** () Function  
 Given functions *f<sub>1</sub>*, ..., *f<sub>n</sub>*, **timer** puts each one on the list of functions for which timing statistics are collected. **timer**(*f*)\$**timer**(*g*)\$ puts *f* and then *g* onto the list; the list accumulates from one call to the next.  
**timer**(*all*) puts all user-defined functions (as named by the global variable **functions**) on the list of timed functions.  
 With no arguments, **timer** returns the list of timed functions.  
 Maxima records how much time is spent executing each function on the list of timed functions. **timer\_info** returns the timing statistics, including the average time elapsed per function call, the number of calls, and the total time elapsed. **untimer** removes functions from the list of timed functions.  
**timer** quotes its arguments. *f*(*x*) := *x*<sup>2</sup>\$ *g*:*f*\$ **timer**(*g*)\$ does not put *f* on the timer list.  
 If **trace**(*f*) is in effect, then **timer**(*f*) has no effect; **trace** and **timer** cannot both be in effect at the same time.  
 See also **timer\_devalue**.

**untimer** (*f<sub>1</sub>*, ..., *f<sub>n</sub>*) Function  
**untimer** () Function  
 Given functions *f<sub>1</sub>*, ..., *f<sub>n</sub>*, **untimer** removes each function from the timer list.  
 With no arguments, **untimer** removes all functions currently on the timer list.  
 After **untimer** (*f*) is executed, **timer\_info** (*f*) still returns previously collected timing statistics, although **timer\_info**() (with no arguments) does not return information about any function not currently on the timer list. **timer** (*f*) resets all timing statistics to zero and puts *f* on the timer list again.

**timer\_devalue** Option variable  
 Default value: **false**  
 When **timer\_devalue** is **true**, Maxima subtracts from each timed function the time spent in other timed functions. Otherwise, the time reported for each function includes the time spent in other functions. Note that time spent in untimed functions is not subtracted from the total time.  
 See also **timer** and **timer\_info**.

**timer\_info** (*f<sub>1</sub>*, ..., *f<sub>n</sub>*) Function  
**timer\_info** () Function  
 Given functions *f<sub>1</sub>*, ..., *f<sub>n</sub>*, **timer\_info** returns a matrix containing timing information for each function. With no arguments, **timer\_info** returns timing information for all functions currently on the timer list.  
 The matrix returned by **timer\_info** contains the function name, time per function call, number of function calls, total time, and **gctime**, which meant "garbage collection time" in the original Macsyma but is now always zero.  
 The data from which **timer\_info** constructs its return value can also be obtained by the **get** function:  

```
get(f, 'calls); get(f, 'runtime); get(f, 'gctime);
```

  
 See also **timer**.

|                                                                            |          |
|----------------------------------------------------------------------------|----------|
| <b>trace</b> ( <i>f</i> <sub>1</sub> , ..., <i>f</i> <sub><i>n</i></sub> ) | Function |
| <b>trace</b> ( <i>all</i> )                                                | Function |
| <b>trace</b> ()                                                            | Function |

Given functions *f*<sub>1</sub>, ..., *f*<sub>*n*</sub>, **trace** instructs Maxima to print out debugging information whenever those functions are called. **trace**(*f*)\$ **trace**(*g*)\$ puts *f* and then *g* onto the list of functions to be traced; the list accumulates from one call to the next.

**trace**(*all*) puts all user-defined functions (as named by the global variable **functions**) on the list of functions to be traced.

With no arguments, **trace** returns a list of all the functions currently being traced.

The **untrace** function disables tracing. See also **trace\_options**.

**trace** quotes its arguments. Thus, *f*(*x*) := *x*<sup>2</sup>\$ *g*:*f*\$ **trace**(*g*)\$ does not put *f* on the trace list.

When a function is redefined, it is removed from the timer list. Thus after **timer**(*f*)\$ *f*(*x*) := *x*<sup>2</sup>\$, function *f* is no longer on the timer list.

If **timer** (*f*) is in effect, then **trace** (*f*) has no effect; **trace** and **timer** can't both be in effect for the same function.

|                                                                                                         |          |
|---------------------------------------------------------------------------------------------------------|----------|
| <b>trace_options</b> ( <i>f</i> , <i>option</i> <sub>1</sub> , ..., <i>option</i> <sub><i>n</i></sub> ) | Function |
| <b>trace_options</b> ( <i>f</i> )                                                                       | Function |

Sets the trace options for function *f*. Any previous options are superseded. **trace\_options** (*f*, ...) has no effect unless **trace** (*f*) is also called (either before or after **trace\_options**).

**trace\_options** (*f*) resets all options to their default values.

The option keywords are:

- **noprint** Do not print a message at function entry and exit.
- **break** Put a breakpoint before the function is entered, and after the function is exited. See **break**.
- **lisp\_print** Display arguments and return values as Lisp objects.
- **info** Print -> **true** at function entry and exit.
- **errorcatch** Catch errors, giving the option to signal an error, retry the function call, or specify a return value.

Trace options are specified in two forms. The presence of the option keyword alone puts the option into effect unconditionally. (Note that option *foo* is not put into effect by specifying *foo*: **true** or a similar form; note also that keywords need not be quoted.) Specifying the option keyword with a predicate function makes the option conditional on the predicate.

The argument list to the predicate function is always [*level*, *direction*, *function*, *item*] where *level* is the recursion level for the function, *direction* is either **enter** or **exit**, *function* is the name of the function, and *item* is the argument list (on entering) or the return value (on exiting).

Here is an example of unconditional trace options:

```
(%i1) ff(n) := if equal(n, 0) then 1 else n * ff(n - 1)$
```

```
(%i2) trace (ff)$
```

```
(%i3) trace_options (ff, lisp_print, break)$
```

```
(%i4) ff(3);
```

Here is the same function, with the **break** option conditional on a predicate:

```
(%i5) trace_options (ff, break(pp))$
```

```
(%i6) pp (level, direction, function, item) := block (print (item),
 return (function = 'ff and level = 3 and direction = exit))$
```

```
(%i7) ff(6);
```

**untrace** ( $f_1, \dots, f_n$ )

Function

**untrace** ()

Function

Given functions  $f_1, \dots, f_n$ , **untrace** disables tracing enabled by the **trace** function.

With no arguments, **untrace** disables tracing for all functions.

**untrace** returns a list of the functions for which it disabled tracing.

## 39 asympa

### 39.1 Introduction to asympa

#### **asympa**

Function

**asympa** is a package for asymptotic analysis. The package contains simplification functions for asymptotic analysis, including the “big O” and “little o” functions that are widely used in complexity analysis and numerical analysis.

`load ("asympa")` loads this package.

### 39.2 Functions and variables for asympa



## 40 augmented\_lagrangian

### 40.1 Functions and Variables for augmented\_lagrangian

**augmented\_lagrangian\_method** (*FOM*, *xx*, *C*, *yy*) Function  
**augmented\_lagrangian\_method** (*FOM*, *xx*, *C*, *yy*, *optional\_args*) Function  
**augmented\_lagrangian\_method** ([*FOM*, *grad*], *xx*, *C*, *yy*) Function  
**augmented\_lagrangian\_method** ([*FOM*, *grad*], *xx*, *C*, *yy*, *optional\_args*) Function

Returns an approximate minimum of the expression *FOM* with respect to the variables *xx*, holding the constraints *C* equal to zero. *yy* is a list of initial guesses for *xx*. The method employed is the augmented Lagrangian method (see Refs [1] and [2]).

*grad*, if present, is the gradient of *FOM* with respect to *xx*, represented as a list of expressions, one for each variable in *xx*. If not present, the gradient is constructed automatically.

*FOM* and each element of *grad*, if present, must be ordinary expressions, not names of functions or lambda expressions.

*optional\_args* represents additional arguments, specified as *symbol* = *value*. The optional arguments recognized are:

**niter**        Number of iterations of the augmented Lagrangian algorithm

**lbfgs\_tolerance**  
               Tolerance supplied to LBFGS

**iprint**        IPRINT parameter (a list of two integers which controls verbosity) supplied to LBFGS

**%lambda**      Initial value of %lambda to be used for calculating the augmented Lagrangian

This implementation minimizes the augmented Lagrangian by applying the limited-memory BFGS (LBFGS) algorithm, which is a quasi-Newton algorithm.

`load(augmented_lagrangian)` loads this function.

See also `lbfgs`.

References:

[1] <http://www-fp.mcs.anl.gov/otc/Guide/OptWeb/continuous/constrained/nonlinearcon/auglag.html>

[2] <http://www.cs.ubc.ca/spider/ascher/542/chap10.pdf>

Examples:

```
(%i1) load (lbfgs);
(%o1) /maxima/share/lbfgs/lbfgs.mac
(%i2) load (augmented_lagrangian);
(%o2) /maxima/share/contrib/augmented_lagrangian.mac
(%i3) FOM: x^2 + 2*y^2;
(%o3) 2 2
 2 y + x
(%i4) xx: [x, y];
(%o4) [x, y]
(%i5) C: [x + y - 1];
(%o5) [y + x - 1]
(%i6) yy: [1, 1];
(%o6) [1, 1]
(%i7) augmented_lagrangian_method(FOM, xx, C, yy, iprint=[-1,0]);
(%o7) [[x = 0.66665984108002, y = 0.33334027245545],
 %lambda = [- 1.333337940892525]]
```

Same example as before, but this time the gradient is supplied as an argument.

```

(%i1) load (lbfgs)$
(%i2) load (augmented_lagrangian)$
(%i3) FOM: x^2 + 2*y^2;

(%o3)

$$x^2 + 2y^2$$

(%i4) FOM: x^2 + 2*y^2;

(%o4)

$$x^2 + 2y^2$$

(%i5) xx: [x, y];
(%o5) [x, y]
(%i6) grad : [2*x, 4*y];
(%o6) [2 x, 4 y]
(%i7) C: [x + y - 1];
(%o7) [y + x - 1]
(%i8) yy: [1, 1];
(%o8) [1, 1]
(%i9) augmented_lagrangian_method ([FOM, grad], xx, C, yy,
 iprint = [-1, 0]);
(%o9) [[x = 0.666659841080025, y = .3333402724554462],
 %lambda = [- 1.333337940892543]]

```



## 41 Bernstein

### 41.1 Functions and Variables for Bernstein

#### **bernstein\_poly** (*k*, *n*, *x*)

Function

Provided *k* is not a negative integer, the Bernstein polynomials are defined by `bernstein_poly(k,n,x) = binomial(n,k) xk (1-x)(n-k)`; for a negative integer *k*, the Bernstein polynomial `bernstein_poly(k,n,x)` vanishes. When either *k* or *n* are non integers, the option variable `bernstein_explicit` controls the expansion of the Bernstein polynomials into its explicit form; example:

```
(%i1) load(bernstein)$

(%i2) bernstein_poly(k,n,x);
(%o2) bernstein_poly(k, n, x)
(%i3) bernstein_poly(k,n,x), bernstein_explicit : true;
 n - k k
(%o3) binomial(n, k) (1 - x) x
The Bernstein polynomials have both a gradev property and an integrate property:
(%i4) diff(bernstein_poly(k,n,x),x);
(%o4) (bernstein_poly(k - 1, n - 1, x)
 - bernstein_poly(k, n - 1, x)) n
(%i5) integrate(bernstein_poly(k,n,x),x);
(%o5)
 k + 1
 hypergeometric([k + 1, k - n], [k + 2], x) binomial(n, k) x

 k + 1
```

For numeric inputs, both real and complex, the Bernstein polynomials evaluate to a numeric result:

```
(%i6) bernstein_poly(5,9, 1/2 + %i);
 39375 %i 39375
(%o6) ----- + -----
 128 256
(%i7) bernstein_poly(5,9, 0.5b0 + %i);
(%o7) 3.076171875b2 %i + 1.5380859375b2
```

To use `bernstein_poly`, first `load("bernstein")`.

#### **bernstein\_explicit**

Variable

Default value: `false`

When either *k* or *n* are non integers, the option variable `bernstein_explicit` controls the expansion of `bernstein(k,n,x)` into its explicit form; example:

```
(%i1) bernstein_poly(k,n,x);
(%o1) bernstein_poly(k, n, x)
(%i2) bernstein_poly(k,n,x), bernstein_explicit : true;
 n - k k
(%o2) binomial(n, k) (1 - x) x
```

When both *k* and *n* are explicitly integers, `bernstein(k,n,x)` *always* expands to its explicit form.

#### **multiberstein\_poly** (*[k1,k2,...,kp]*, *[n1,n2,...,np]*, *[x1,x2,...,xp]*)

Function

The multiberstein polynomial `multiberstein_poly ([k1, k2, ..., kp], [n1, n2, ..., np], [x1, x2, ..., xp])` is the product of bernstein polynomials `bernstein_poly(k1, n1, x1) bernstein_poly(k2, n2, x2) ... bernstein_poly(kp, np, xp)`.

To use `multiberstein_poly`, first `load("bernstein")`.

**bernstein\_approx** ( $f, [x_1, x_1, \dots, x_n], n$ ) Function

Return the  $n$ -th order uniform Bernstein polynomial approximation for the function  $(x_1, x_2, \dots, x_n) \mapsto f$ . Examples

```
(%i1) bernstein_approx(f(x),[x], 2);
 2 1 2
(%o1) f(1) x + 2 f(-) (1 - x) x + f(0) (1 - x)
 2
(%i2) bernstein_approx(f(x,y),[x,y], 2);
 2 2 1 2
(%o2) f(1, 1) x y + 2 f(-, 1) (1 - x) x y
 2
 2 2 1 2
+ f(0, 1) (1 - x) y + 2 f(1, -) x (1 - y) y
 2
 1 1 1 2
+ 4 f(-, -) (1 - x) x (1 - y) y + 2 f(0, -) (1 - x) (1 - y) y
 2 2 2
+ f(1, 0) x (1 - y) + 2 f(-, 0) (1 - x) x (1 - y)
 2
+ f(0, 0) (1 - x) (1 - y) 2
```

To use `bernstein_approx`, first `load("bernstein")`.

**bernstein\_expand** ( $e, [x_1, x_1, \dots, x_n]$ ) Function

Express the *polynomial*  $e$  exactly as a linear combination of multi-variable Bernstein polynomials.

```
(%i1) bernstein_expand(x*y+1,[x,y]);
(%o1) 2 x y + (1 - x) y + x (1 - y) + (1 - x) (1 - y)
(%i2) expand(%);
(%o2) x y + 1
```

Maxima signals an error when the first argument isn't a polynomial.

To use `bernstein_expand`, first `load("bernstein")`.

## 42 bode

### 42.1 Functions and Variables for bode

**bode\_gain** (*H, range, ...plot\_opts...*)

Function

Function to draw Bode gain plots.

Examples (1 through 7 from

<http://www.swarthmore.edu/NatSci/echeeve1/Ref/Bode/BodeHow.html>,  
8 from Ron Crummett):

```
(%i1) load("bode")$

(%i2) H1 (s) := 100 * (1 + s) / ((s + 10) * (s + 100))$

(%i3) bode_gain (H1 (s), [w, 1/1000, 1000])$

(%i4) H2 (s) := 1 / (1 + s/omega0)$

(%i5) bode_gain (H2 (s), [w, 1/1000, 1000]), omega0 = 10$

(%i6) H3 (s) := 1 / (1 + s/omega0)^2$

(%i7) bode_gain (H3 (s), [w, 1/1000, 1000]), omega0 = 10$

(%i8) H4 (s) := 1 + s/omega0$

(%i9) bode_gain (H4 (s), [w, 1/1000, 1000]), omega0 = 10$

(%i10) H5 (s) := 1/s$

(%i11) bode_gain (H5 (s), [w, 1/1000, 1000])$

(%i12) H6 (s) := 1/((s/omega0)^2 + 2 * zeta * (s/omega0) + 1)$

(%i13) bode_gain (H6 (s), [w, 1/1000, 1000]),
 omega0 = 10, zeta = 1/10$

(%i14) H7 (s) := (s/omega0)^2 + 2 * zeta * (s/omega0) + 1$

(%i15) bode_gain (H7 (s), [w, 1/1000, 1000]),
 omega0 = 10, zeta = 1/10$

(%i16) H8 (s) := 0.5 / (0.0001 * s^3 + 0.002 * s^2 + 0.01 * s)$

(%i17) bode_gain (H8 (s), [w, 1/1000, 1000])$
```

To use this function write first `load("bode")`. See also `bode_phase`

**bode\_phase** (*H, range, ...plot\_opts...*)

Function

Function to draw Bode phase plots.

Examples (1 through 7 from

<http://www.swarthmore.edu/NatSci/echeeve1/Ref/Bode/BodeHow.html>,  
8 from Ron Crummett):

```

(%i1) load("bode")$

(%i2) H1 (s) := 100 * (1 + s) / ((s + 10) * (s + 100))$

(%i3) bode_phase (H1 (s), [w, 1/1000, 1000])$

(%i4) H2 (s) := 1 / (1 + s/omega0)$

(%i5) bode_phase (H2 (s), [w, 1/1000, 1000]), omega0 = 10$

(%i6) H3 (s) := 1 / (1 + s/omega0)^2$

(%i7) bode_phase (H3 (s), [w, 1/1000, 1000]), omega0 = 10$

(%i8) H4 (s) := 1 + s/omega0$

(%i9) bode_phase (H4 (s), [w, 1/1000, 1000]), omega0 = 10$

(%i10) H5 (s) := 1/s$

(%i11) bode_phase (H5 (s), [w, 1/1000, 1000])$

(%i12) H6 (s) := 1/((s/omega0)^2 + 2 * zeta * (s/omega0) + 1)$

(%i13) bode_phase (H6 (s), [w, 1/1000, 1000]),
 omega0 = 10, zeta = 1/10$

(%i14) H7 (s) := (s/omega0)^2 + 2 * zeta * (s/omega0) + 1$

(%i15) bode_phase (H7 (s), [w, 1/1000, 1000]),
 omega0 = 10, zeta = 1/10$

(%i16) H8 (s) := 0.5 / (0.0001 * s^3 + 0.002 * s^2 + 0.01 * s)$

(%i17) bode_phase (H8 (s), [w, 1/1000, 1000])$

(%i18) block ([bode_phase_unwrap : false],
 bode_phase (H8 (s), [w, 1/1000, 1000]));

(%i19) block ([bode_phase_unwrap : true],
 bode_phase (H8 (s), [w, 1/1000, 1000]));

```

To use this function write first `load("bode")`. See also `bode_gain`

## 43 cobyln

### 43.1 Introduction to cobyln

`fmin_cobyln` is a Common Lisp translation (via `f2cl`) of the Fortran constrained optimization routine COBYLN by Powell[1][2][3].

COBYLN minimizes an objective function  $F(X)$  subject to  $M$  inequality constraints of the form  $g(X) \geq 0$  on  $X$ , where  $X$  is a vector of variables that has  $N$  components.

Equality constraints  $g(X)=0$  can often be implemented by a pair of inequality constraints  $g(X) \geq 0$  and  $-g(X) \geq 0$ . Maxima's interface to COBYLN allows equality constraints and internally converts the equality constraints to a pair of inequality constraints.

The algorithm employs linear approximations to the objective and constraint functions, the approximations being formed by linear interpolation at  $N+1$  points in the space of the variables. The interpolation points are regarded as vertices of a simplex. The parameter `RHO` controls the size of the simplex and it is reduced automatically from `RHOBEG` to `RHOEND`. For each `RHO` the subroutine tries to achieve a good vector of variables for the current size, and then `RHO` is reduced until the value `RHOEND` is reached. Therefore `RHOBEG` and `RHOEND` should be set to reasonable initial changes to and the required accuracy in the variables respectively, but this accuracy should be viewed as a subject for experimentation because it is not guaranteed. The routine treats each constraint individually when calculating a change to the variables, rather than lumping the constraints together into a single penalty function. The name of the subroutine is derived from the phrase Constrained Optimization BY Linear Approximations.

References:

- [1] Fortran Code is from <http://plato.asu.edu/sub/nlores.html#general>
- [2] M. J. D. Powell, "A direct search optimization method that models the objective and constraint functions by linear interpolation," in *Advances in Optimization and Numerical Analysis*, eds. S. Gomez and J.-P. Hennart (Kluwer Academic: Dordrecht, 1994), p. 51-67.
- [3] M. J. D. Powell, "Direct search algorithms for optimization calculations," *Acta Numerica* 7, 287-336 (1998). Also available as University of Cambridge, Department of Applied Mathematics and Theoretical Physics, Numerical Analysis Group, Report NA1998/04 from <http://www.damtp.cam.ac.uk/user/na/reports.html>

### 43.2 Functions and Variables for cobyln

|                                                  |          |
|--------------------------------------------------|----------|
| <b>fmin_cobyln</b> ( $F, X, Y$ )                 | Function |
| <b>fmin_cobyln</b> ( $F, X, Y, optional\_args$ ) | Function |

Returns an approximate minimum of the expression  $F$  with respect to the variables  $X$ , subject to an optional set of constraints.  $Y$  is a list of initial guesses for  $X$ .

$F$  must be an ordinary expressions, not names of functions or lambda expressions.

`optional_args` represents additional arguments, specified as *symbol = value*. The optional arguments recognized are:

|                    |                                                                                                                                                                                                                                                    |
|--------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| <b>constraints</b> | List of inequality and equality constraints that must be satisfied by $X$ . The inequality constraints must be actual inequalities of the form $g(X) \geq h(X)$ or $g(X) \leq h(X)$ . The equality constraints must be of the form $g(X) = h(X)$ . |
| <b>rhobeg</b>      | Initial value of the internal <code>RHO</code> variable which controls the size of simplex. (Defaults to 1.0)                                                                                                                                      |
| <b>rhoend</b>      | The desired final value rho parameter. It is approximately the accuracy in the variables. (Defaults to 1d-6.)                                                                                                                                      |
| <b>iprint</b>      | Verbose output level. (Defaults to 0)                                                                                                                                                                                                              |
|                    | 0 - No output                                                                                                                                                                                                                                      |

- 1 - Summary at the end of the calculation
- 2 - Each new value of RHO and SIGMA is printed, including the vector of variables, some function information when RHO is reduced.
- 3 - Like 2, but information is printed when F(X) is computed.

**maxfun**      The maximum number of function evaluations. (Defaults to 1000).

On return, a vector is given:

1. The value of the variables giving the minimum. This is a list of elements of the form *var = value* for each of the variables listed in *X*.
2. The minimized function value
3. The number of function evaluations.
4. Return code with the following meanings
  1. 0 - No errors.
  2. 1 - Limit on maximum number of function evaluations reached.
  3. 2 - Rounding errors inhibiting progress.

`load(fmin_cobyla)` loads this function.

**bf\_fmin\_cobyla** (*F*, *X*, *Y*)

Function

**bf\_fmin\_cobyla** (*F*, *X*, *Y*, *optional\_args*)

Function

This function is identical to `fmin_cobyla`, except that bigfloat operations are used, and the default value for *rhoend* is  $10^{(\text{fpprec}/2)}$ .

See `fmin_cobyla` for more information.

`load(fmin_cobyla)` loads this function.

### 43.3 Examples for cobyla

Minimize  $x_1 \cdot x_2$  with  $1 - x_1^2 - x_2^2 \geq 0$ . The theoretical solution is  $x_1 = 1/\sqrt{2}$ ,  $x_2 = -1/\sqrt{2}$ .

```
(%i1) load(fmin_cobyla)$
(%i2) fmin_cobyla(x1*x2, [x1, x2], [1,1],
 constraints = [x1^2+x2^2<=1], iprint=1);
Normal return from subroutine COBYLA

NFVALS = 66 F = -5.000000E-01 MAXCV = 1.999845E-12
X = 7.071058E-01 -7.071077E-01
(%o2) [[x1 = 0.70710584934848, x2 = - 0.7071077130248],
 - 0.49999999999926, [[-1.999955756559757e-12], []], 66]
```

There are additional examples in the `share/cobyla/ex` directory.

## 44 contrib\_ode

### 44.1 Introduction to contrib\_ode

Maxima's ordinary differential equation (ODE) solver `ode2` solves elementary linear ODEs of first and second order. The function `contrib_ode` extends `ode2` with additional methods for linear and non-linear first order ODEs and linear homogeneous second order ODEs. The code is still under development and the calling sequence may change in future releases. Once the code has stabilized it may be moved from the contrib directory and integrated into Maxima.

This package must be loaded with the command `load('contrib_ode)` before use.

The calling convention for `contrib_ode` is identical to `ode2`. It takes three arguments: an ODE (only the left hand side need be given if the right hand side is 0), the dependent variable, and the independent variable. When successful, it returns a list of solutions.

The form of the solution differs from `ode2`. As non-linear equations can have multiple solutions, `contrib_ode` returns a list of solutions. Each solution can have a number of forms:

- an explicit solution for the dependent variable,
- an implicit solution for the dependent variable,
- a parametric solution in terms of variable `%t`, or
- a tranformation into another ODE in variable `%u`.

`%c` is used to represent the constant of integration for first order equations. `%k1` and `%k2` are the constants for second order equations. If `contrib_ode` cannot obtain a solution for whatever reason, it returns `false`, after perhaps printing out an error message.

It is necessary to return a list of solutions, as even first order non-linear ODEs can have multiple solutions. For example:

```
(%i1) load('contrib_ode)$

(%i2) eqn:x*'diff(y,x)^2-(1+x*y)*'diff(y,x)+y=0;

(%o2) dy 2 dy
 x (--) - (x y + 1) -- + y = 0
 dx dx

(%i3) contrib_ode(eqn,y,x);

(%o3) x
 [y = log(x) + %c, y = %c %e]
(%i4) method;

(%o4) factor
```

Nonlinear ODEs can have singular solutions without constants of integration, as in the second solution of the following example:

```
(%i1) load('contrib_ode)$

(%i2) eqn:'diff(y,x)^2+x*'diff(y,x)-y=0;

(%o2) dy 2 dy
 (--) + x -- - y = 0
 dx dx

(%i3) contrib_ode(eqn,y,x);

(%o3) 2 x
 [y = %c x + %c , y = - --]
 4
```

```
(%i4) method;
```

```
(%o4) clairault
```

The following ODE has two parametric solutions in terms of the dummy variable %t. In this case the parametric solutions can be manipulated to give explicit solutions.

```
(%i1) load('contrib_ode)$
```

```
(%i2) eqn:'diff(y,x)=(x+y)^2;
```

```
(%o2) dy
 -- = (y + x)2
 dx
```

```
(%i3) contrib_ode(eqn,y,x);
```

```
(%o3) [[x = %c - atan(sqrt(%t)), y = - x - sqrt(%t)],
 [x = atan(sqrt(%t)) + %c, y = sqrt(%t) - x]]
```

```
(%i4) method;
```

```
(%o4) lagrange
```

The following example (Kamke 1.112) demonstrates an implicit solution.

```
(%i1) load('contrib_ode)$
```

```
(%i2) assume(x>0,y>0);
```

```
(%o2) [x > 0, y > 0]
```

```
(%i3) eqn:x*'diff(y,x)-x*sqrt(y^2+x^2)-y;
```

```
(%o3) dy
 x -- - x sqrt(y2 + x2) - y
 dx
```

```
(%i4) contrib_ode(eqn,y,x);
```

```
(%o4) y
 [x - asinh(-) = %c]
 x
```

```
(%i5) method;
```

```
(%o5) lie
```

The following Riccati equation is transformed into a linear second order ODE in the variable %u. Maxima is unable to solve the new ODE, so it is returned unevaluated.

```
(%i1) load('contrib_ode)$
```

```
(%i2) eqn:x^2*'diff(y,x)=a+b*x^n+c*x^2*y^2;
```

```
(%o2) 2 dy 2 2 n
 x -- = c x y + b x + a
 dx
```

```
(%i3) contrib_ode(eqn,y,x);
```

```
(%o3) [[y = - ----, %u c (b xn-2 + $\frac{a}{x^2}$) + ---- c = 0]]
 %u c 2
 d %u

 dx
```

```
(%i4) method;
```



```
(%o4) riccati
```

For first order ODEs `contrib_ode` calls `ode2`. It then tries the following methods: factorization, Clairault, Lagrange, Riccati, Abel and Lie symmetry methods. The Lie method is not attempted on Abel equations if the Abel method fails, but it is tried if the Riccati method returns an unsolved second order ODE.

For second order ODEs `contrib_ode` calls `ode2` then `odelin`.

Extensive debugging traces and messages are displayed if the command `put('contrib_ode,true,'verbose)` is executed.

## 44.2 Functions and Variables for contrib\_ode

**contrib\_ode** (*eqn*, *y*, *x*) Function  
Returns a list of solutions of the ODE *eqn* with independent variable *x* and dependent variable *y*.

**odelin** (*eqn*, *y*, *x*) Function  
`odelin` solves linear homogeneous ODEs of first and second order with independent variable *x* and dependent variable *y*. It returns a fundamental solution set of the ODE.  
For second order ODEs, `odelin` uses a method, due to Bronstein and Lafaille, that searches for solutions in terms of given special functions.

```
(%i1) load('contrib_ode);

(%i2) odelin(x*(x+1)*'diff(y,x,2)+(x+5)*'diff(y,x,1)+(-4)*y,y,x);
...trying factor method
...solving 7 equations in 4 variables
...trying the Bessel solver
...solving 1 equations in 2 variables
...trying the F01 solver
...solving 1 equations in 3 variables
...trying the spheroidal wave solver
...solving 1 equations in 4 variables
...trying the square root Bessel solver
...solving 1 equations in 2 variables
...trying the 2F1 solver
...solving 9 equations in 5 variables
 gauss_a(- 6, - 2, - 3, - x) gauss_b(- 6, - 2, - 3, - x)
(%o2) {-----, -----}
 4 4
 x x
```

**ode\_check** (*eqn*, *soln*) Function  
Returns the value of ODE *eqn* after substituting a possible solution *soln*. The value is equivalent to zero if *soln* is a solution of *eqn*.

```
(%i1) load('contrib_ode)$

(%i2) eqn: 'diff(y,x,2)+(a*x+b)*y;

 2
 d y
(%o2) --- + (a x + b) y
 2
 dx

(%i3) ans: [y = bessell_y(1/3,2*(a*x+b)^(3/2)/(3*a))*%k2*sqrt(a*x+b)
```

```

+bessel_j(1/3,2*(a*x+b)^(3/2)/(3*a))*%k1*sqrt(a*x+b)];

 3/2
 1 2 (a x + b)
(%o3) [y = bessell_y(-, -----) %k2 sqrt(a x + b)
 3 3 a

 3/2
 1 2 (a x + b)
+ bessell_j(-, -----) %k1 sqrt(a x + b)]
 3 3 a

(%i4) ode_check(eqn,ans[1]);

(%o4) 0

```

**method**

System variable

The variable `method` is set to the successful solution method.

**%c**

Variable

`%c` is the integration constant for first order ODEs.

**%k1**

Variable

`%k1` is the first integration constant for second order ODEs.

**%k2**

Variable

`%k2` is the second integration constant for second order ODEs.

**gauss\_a** (*a, b, c, x*)

Function

`gauss_a(a,b,c,x)` and `gauss_b(a,b,c,x)` are  $2F_1$  geometric functions. They represent any two independent solutions of the hypergeometric differential equation  $x(1-x)\text{diff}(y,x,2) + [c-(a+b+1)x]\text{diff}(y,x) - aby = 0$  (A&S 15.5.1).

The only use of these functions is in solutions of ODEs returned by `odelin` and `contrib_ode`. The definition and use of these functions may change in future releases of Maxima.

See also `gauss_b`, `dgauss_a` and `gauss_b`.

**gauss\_b** (*a, b, c, x*)

Function

See `gauss_a`.

**dgauss\_a** (*a, b, c, x*)

Function

The derivative with respect to  $x$  of `gauss_a(a, b, c, x)`.

**dgauss\_b** (*a, b, c, x*)

Function

The derivative with respect to  $x$  of `gauss_b(a, b, c, x)`.

**kummer\_m** (*a, b, x*)

Function

Kummer's M function, as defined in Abramowitz and Stegun, *Handbook of Mathematical Functions*, Section 13.1.2.

The only use of this function is in solutions of ODEs returned by `odelin` and `contrib_ode`. The definition and use of this function may change in future releases of Maxima.

See also `kummer_u`, `dkummer_m` and `dkummer_u`.

**kummer\_u** (*a, b, x*)

Function

Kummer's U function, as defined in Abramowitz and Stegun, *Handbook of Mathematical Functions*, Section 13.1.3.

See `kummer_m`.

**dkummer\_m** (*a*, *b*, *x*) Function  
 The derivative with respect to *x* of `kummer_m(a, b, x)`.

**dkummer\_u** (*a*, *b*, *x*) Function  
 The derivative with respect to *x* of `kummer_u(a, b, x)`.

### 44.3 Possible improvements to contrib\_ode

These routines are work in progress. I still need to:

- Extend the FACTOR method `ode1_factor` to work for multiple roots.
- Extend the FACTOR method `ode1_factor` to attempt to solve higher order factors. At present it only attempts to solve linear factors.
- Fix the LAGRANGE routine `ode1_lagrange` to prefer real roots over complex roots.
- Add additional methods for Riccati equations.
- Improve the detection of Abel equations of second kind. The existing pattern matching is weak.
- Work on the Lie symmetry group routine `ode1_lie`. There are quite a few problems with it: some parts are unimplemented; some test cases seem to run forever; other test cases crash; yet others return very complex "solutions". I wonder if it really ready for release yet.
- Add more test cases.

### 44.4 Test cases for contrib\_ode

The routines have been tested on a approximately one thousand test cases from Murphy, Kamke, Zwillinger and elsewhere. These are included in the tests subdirectory.

- The Clairault routine `ode1_clairault` finds all known solutions, including singular solutions, of the Clairault equations in Murphy and Kamke.
- The other routines often return a single solution when multiple solutions exist.
- Some of the "solutions" from `ode1_lie` are overly complex and impossible to check.
- There are some crashes.

### 44.5 References for contrib\_ode

1. E. Kamke, Differentialgleichungen Lösungsmethoden und Lösungen, Vol 1, Geest & Portig, Leipzig, 1961
2. G. M. Murphy, Ordinary Differential Equations and Their Solutions, Van Nostrand, New York, 1960
3. D. Zwillinger, Handbook of Differential Equations, 3rd edition, Academic Press, 1998
4. F. Schwarz, Symmetry Analysis of Abel's Equation, Studies in Applied Mathematics, 100:269-294 (1998)
5. F. Schwarz, Algorithmic Solution of Abel's Equation, Computing 61, 39-49 (1998)
6. E. S. Cheb-Terrab, A. D. Roche, Symmetries and First Order ODE Patterns, Computer Physics Communications 113 (1998), p 239. (<http://lie.uwaterloo.ca/papers/ode.vii.pdf>)
7. E. S. Cheb-Terrab, T. Kolokolnikov, First Order ODEs, Symmetries and Linear Transformations, European Journal of Applied Mathematics, Vol. 14, No. 2, pp. 231-246 (2003). (<http://arxiv.org/abs/math-ph/0007023>, [http://lie.uwaterloo.ca/papers/ode\\_iv.pdf](http://lie.uwaterloo.ca/papers/ode_iv.pdf))
8. G. W. Bluman, S. C. Anco, Symmetry and Integration Methods for Differential Equations, Springer, (2002)
9. M. Bronstein, S. Lafaille, Solutions of linear ordinary differential equations in terms of special functions, Proceedings of ISSAC 2002, Lille, ACM Press, 23-28. (<http://www-sop.inria.fr/cafe/Manuel.Bronstein/publications/issac2002.pdf>)



## 45 descriptive

### 45.1 Introduction to descriptive

Package **descriptive** contains a set of functions for making descriptive statistical computations and graphing. Together with the source code there are three data sets in your Maxima tree: **pidigits.data**, **wind.data** and **biomed.data**.

Any statistics manual can be used as a reference to the functions in package **descriptive**.

For comments, bugs or suggestions, please contact me at '*mario AT edu DOT xunta DOT es*'.

Here is a simple example on how the descriptive functions in **descriptive** do they work, depending on the nature of their arguments, lists or matrices,

```
(%i1) load (descriptive)$
(%i2) /* univariate sample */ mean ([a, b, c]);
(%o2)
 c + b + a

 3
(%i3) matrix ([a, b], [c, d], [e, f]);
(%o3)
 [a b]
 []
 [c d]
 []
 [e f]
(%i4) /* multivariate sample */ mean (%);
(%o4)
 e + c + a f + d + b
 [-----, -----]
 3 3
```

Note that in multivariate samples the mean is calculated for each column.

In case of several samples with possible different sizes, the Maxima function **map** can be used to get the desired results for each sample,

```
(%i1) load (descriptive)$
(%i2) map (mean, [[a, b, c], [d, e]]);
(%o2)
 c + b + a e + d
 [-----, -----]
 3 2
```

In this case, two samples of sizes 3 and 2 were stored into a list.

Univariate samples must be stored in lists like

```
(%i1) s1 : [3, 1, 4, 1, 5, 9, 2, 6, 5, 3, 5];
(%o1)
 [3, 1, 4, 1, 5, 9, 2, 6, 5, 3, 5]
```

and multivariate samples in matrices as in

```
(%i1) s2 : matrix ([13.17, 9.29], [14.71, 16.88], [18.50, 16.88],
 [10.58, 6.63], [13.33, 13.25], [13.21, 8.12]);
(%o1)
 [13.17 9.29]
 []
 [14.71 16.88]
 []
 [18.5 16.88]
 []
 [10.58 6.63]
 []
 [13.33 13.25]
 []
 [13.21 8.12]
```

In this case, the number of columns equals the random variable dimension and the number of rows is the sample size.

Data can be introduced by hand, but big samples are usually stored in plain text files. For example, file `pidigits.data` contains the first 100 digits of number  $\pi$ :

```
3
1
4
1
5
9
2
6
5
3 ...
```

In order to load these digits in Maxima,

```
(%i1) s1 : read_list (file_search ("pidigits.data"))$
(%i2) length (s1);
(%o2) 100
```

On the other hand, file `wind.data` contains daily average wind speeds at 5 meteorological stations in the Republic of Ireland (This is part of a data set taken at 12 meteorological stations. The original file is freely downloadable from the StatLib Data Repository and its analysis is discussed in Haslett, J., Raftery, A. E. (1989) *Space-time Modelling with Long-memory Dependence: Assessing Ireland's Wind Power Resource, with Discussion*. Applied Statistics 38, 1-50). This loads the data:

```
(%i1) s2 : read_matrix (file_search ("wind.data"))$
(%i2) length (s2);
(%o2) 100
(%i3) s2 [%]; /* last record */
(%o3) [3.58, 6.0, 4.58, 7.62, 11.25]
```

Some samples contain non numeric data. As an example, file `biomed.data` (which is part of another bigger one downloaded from the StatLib Data Repository) contains four blood measures taken from two groups of patients, A and B, of different ages,

```
(%i1) s3 : read_matrix (file_search ("biomed.data"))$
(%i2) length (s3);
(%o2) 100
(%i3) s3 [1]; /* first record */
(%o3) [A, 30, 167.0, 89.0, 25.6, 364]
```

The first individual belongs to group A, is 30 years old and his/her blood measures were 167.0, 89.0, 25.6 and 364.

One must take care when working with categorical data. In the next example, symbol `a` is assigned a value in some previous moment and then a sample with categorical value `a` is taken,

```
(%i1) a : 1$
(%i2) matrix ([a, 3], [b, 5]);
(%o2) [1 3]
 []
 [b 5]
```

## 45.2 Functions and Variables for data manipulation

**continuous\_freq** (*list*)

Function

**continuous\_freq** (*list*, *m*)

Function

The argument of **continuous\_freq** must be a list of numbers. Divides the range in intervals and counts how many values are inside them. The second argument is optional and either equals the number of classes we want, 10 by default, or equals a list containing

the class limits and the number of classes we want, or a list containing only the limits. Argument *list* must be a list of (2 or 3) real numbers. If sample values are all equal, this function returns only one class of amplitude 2.

Examples:

Optional argument indicates the number of classes we want. The first list in the output contains the interval limits, and the second the corresponding counts: there are 16 digits inside the interval  $[0, 1.8]$ , 24 digits in  $(1.8, 3.6]$ , and so on.

```
(%i1) load (descriptive)$
(%i2) s1 : read_list (file_search ("pidigits.data"))$
(%i3) continuous_freq (s1, 5);
(%o3) [[0, 1.8, 3.6, 5.4, 7.2, 9.0], [16, 24, 18, 17, 25]]
```

Optional argument indicates we want 7 classes with limits -2 and 12:

```
(%i1) load (descriptive)$
(%i2) s1 : read_list (file_search ("pidigits.data"))$
(%i3) continuous_freq (s1, [-2,12,7]);
(%o3) [[- 2, 0, 2, 4, 6, 8, 10, 12], [8, 20, 22, 17, 20, 13, 0]]
```

Optional argument indicates we want the default number of classes with limits -2 and 12:

```
(%i1) load (descriptive)$
(%i2) s1 : read_list (file_search ("pidigits.data"))$
(%i3) continuous_freq (s1, [-2,12]);
 3 4 11 18 32 39 46 53
(%o3) [[- 2, - -, -, --, --, 5, --, --, --, --, 12],
 5 5 5 5 5 5 5 5
 [0, 8, 20, 12, 18, 9, 8, 25, 0, 0]]
```

### **discrete\_freq** (*list*)

Function

Counts absolute frequencies in discrete samples, both numeric and categorical. Its unique argument is a list,

```
(%i1) load (descriptive)$
(%i2) s1 : read_list (file_search ("pidigits.data"))$
(%i3) discrete_freq (s1);
(%o3) [[0, 1, 2, 3, 4, 5, 6, 7, 8, 9],
 [8, 8, 12, 12, 10, 8, 9, 8, 12, 13]]
```

The first list gives the sample values and the second their absolute frequencies. Commands ? col and ? transpose should help you to understand the last input.

### **standardize** (*list*)

Function

### **standardize** (*matrix*)

Function

Subtracts to each element of the list the sample mean and divides the result by the standard deviation. When the input is a matrix, **standardize** subtracts to each row the multivariate mean, and then divides each component by the corresponding standard deviation.

### **subsample** (*data\_matrix*, *predicate\_function*)

Function

### **subsample** (*data\_matrix*, *predicate\_function*, *col\_num1*, *col\_num2*, ...)

Function

This is a sort of variant of the Maxima **submatrix** function. The first argument is the data matrix, the second is a predicate function and optional additional arguments are the numbers of the columns to be taken. Its behaviour is better understood with examples.

These are multivariate records in which the wind speed in the first meteorological station were greater than 18. See that in the lambda expression the *i*-th component is referred to as *v*[*i*].

```
(%i1) load (descriptive)$
(%i2) s2 : read_matrix (file_search ("wind.data"))$
```

```
(%i3) subsample (s2, lambda([v], v[1] > 18));
 [19.38 15.37 15.12 23.09 25.25]
 []
 [18.29 18.66 19.08 26.08 27.63]
(%o3) []
 [20.25 21.46 19.95 27.71 23.38]
 []
 [18.79 18.96 14.46 26.38 21.84]
```

In the following example, we request only the first, second and fifth components of those records with wind speeds greater or equal than 16 in station number 1 and less than 25 knots in station number 4. The sample contains only data from stations 1, 2 and 5. In this case, the predicate function is defined as an ordinary Maxima function.

```
(%i1) load (descriptive)$
(%i2) s2 : read_matrix (file_search ("wind.data"))$
(%i3) g(x):= x[1] >= 16 and x[4] < 25$
(%i4) subsample (s2, g, 1, 2, 5);
 [19.38 15.37 25.25]
 []
 [17.33 14.67 19.58]
(%o4) []
 [16.92 13.21 21.21]
 []
 [17.25 18.46 23.87]
```

Here is an example with the categorical variables of `biomed.data`. We want the records corresponding to those patients in group B who are older than 38 years.

```
(%i1) load (descriptive)$
(%i2) s3 : read_matrix (file_search ("biomed.data"))$
(%i3) h(u):= u[1] = B and u[2] > 38 $
(%i4) subsample (s3, h);
 [B 39 28.0 102.3 17.1 146]
 []
 [B 39 21.0 92.4 10.3 197]
 []
 [B 39 23.0 111.5 10.0 133]
 []
 [B 39 26.0 92.6 12.3 196]
(%o4) []
 [B 39 25.0 98.7 10.0 174]
 []
 [B 39 21.0 93.2 5.9 181]
 []
 [B 39 18.0 95.0 11.3 66]
 []
 [B 39 39.0 88.5 7.6 168]
```

Probably, the statistical analysis will involve only the blood measures,

```
(%i1) load (descriptive)$
(%i2) s3 : read_matrix (file_search ("biomed.data"))$
```



```
(%i3) subsample (s3, lambda([v], v[1] = B and v[2] > 38),
3, 4, 5, 6);
[28.0 102.3 17.1 146]
[]
[21.0 92.4 10.3 197]
[]
[23.0 111.5 10.0 133]
[]
[26.0 92.6 12.3 196]
(%o3) []
[25.0 98.7 10.0 174]
[]
[21.0 93.2 5.9 181]
[]
[18.0 95.0 11.3 66]
[]
[39.0 88.5 7.6 168]
```

This is the multivariate mean of `s3`,

```
(%i1) load (descriptive)$
(%i2) s3 : read_matrix (file_search ("biomed.data"))$
(%i3) mean (s3);
 65 B + 35 A 317 6 NA + 8144.999999999999
(%o3) [-----, ---, 87.178, -----,
 100 10 100
 3 NA + 19587
 18.123, -----]
 100
```

Here, the first component is meaningless, since A and B are categorical, the second component is the mean age of individuals in rational form, and the fourth and last values exhibit some strange behaviour. This is because symbol NA is used here to indicate *non available* data, and the two means are nonsense. A possible solution would be to take out from the matrix those rows with NA symbols, although this deserves some loss of information.

```
(%i1) load (descriptive)$
(%i2) s3 : read_matrix (file_search ("biomed.data"))$
(%i3) g(v):= v[4] # NA and v[6] # NA $
(%i4) mean (subsample (s3, g, 3, 4, 5, 6));
(%o4) [79.4923076923077, 86.2032967032967, 16.93186813186813,
 2514
 ----]
 13
```

### **transform\_sample** (*matrix*, *varlist*, *exprlist*)

Function

Transforms the sample *matrix*, where each column is called according to *varlist*, following expressions in *exprlist*.

Examples:

The second argument assigns names to the three columns. With these names, a list of expressions define the transformation of the sample.

```
(%i1) load (descriptive)$
(%i2) data: matrix([3,2,7],[3,7,2],[8,2,4],[5,2,4]) $
```

```
(%i3) transform_sample(data, [a,b,c], [c, a*b, log(a)]);
 [7 6 log(3)]
 []
 [2 21 log(3)]
(%o3) []
 [4 16 log(8)]
 []
 [4 10 log(5)]
```

Add a constant column and remove the third variable.

```
(%i1) load (descriptive)$
(%i2) data: matrix([3,2,7],[3,7,2],[8,2,4],[5,2,4]) $
(%i3) transform_sample(data, [a,b,c], [makelist(1,k,length(data)),a,b]);
 [1 3 2]
 []
 [1 3 7]
(%o3) []
 [1 8 2]
 []
 [1 5 2]
```

### 45.3 Functions and Variables for descriptive statistics

**mean** (*list*)

Function

**mean** (*matrix*)

Function

This is the sample mean, defined as

$$\bar{x} = \frac{1}{n} \sum_{i=1}^n x_i$$

Example:

```
(%i1) load (descriptive)$
(%i2) s1 : read_list (file_search ("pidigits.data"))$
(%i3) mean (s1);
 471
(%o3) ---
 100

(%i4) %, numer;
(%o4) 4.71
(%i5) s2 : read_matrix (file_search ("wind.data"))$
(%i6) mean (s2);
(%o6) [9.9485, 10.1607, 10.8685, 15.7166, 14.8441]
```

**var** (*list*)

Function

**var** (*matrix*)

Function

This is the sample variance, defined as

$$\frac{1}{n} \sum_{i=1}^n (x_i - \bar{x})^2$$

Example:

```
(%i1) load (descriptive)$
(%i2) s1 : read_list (file_search ("pidigits.data"))$
(%i3) var (s1), numer;
(%o3) 8.425899999999999
```

See also function var1.

**var1** (*list*)

Function

**var1** (*matrix*)

Function

This is the sample variance, defined as

$$\frac{1}{n-1} \sum_{i=1}^n (x_i - \bar{x})^2$$

Example:

```
(%i1) load (descriptive)$
(%i2) s1 : read_list (file_search ("pidigits.data"))$
(%i3) var1 (s1), numer;
(%o3) 8.5110101010101
(%i4) s2 : read_matrix (file_search ("wind.data"))$
(%i5) var1 (s2);
(%o5) [17.39586540404041, 15.13912778787879, 15.63204924242424,
 32.50152569696971, 24.66977392929294]
```

See also function **var**.**std** (*list*)

Function

**std** (*matrix*)

Function

This is the the square root of function **var**, the variance with denominator  $n$ .

Example:

```
(%i1) load (descriptive)$
(%i2) s1 : read_list (file_search ("pidigits.data"))$
(%i3) std (s1), numer;
(%o3) 2.902740084816414
(%i4) s2 : read_matrix (file_search ("wind.data"))$
(%i5) std (s2);
(%o5) [4.149928523480858, 3.871399812729241, 3.933920277534866,
 5.672434260526957, 4.941970881136392]
```

See also functions **var** and **std1**.**std1** (*list*)

Function

**std1** (*matrix*)

Function

This is the the square root of function **var1**, the variance with denominator  $n-1$ .

Example:

```
(%i1) load (descriptive)$
(%i2) s1 : read_list (file_search ("pidigits.data"))$
(%i3) std1 (s1), numer;
(%o3) 2.917363553109228
(%i4) s2 : read_matrix (file_search ("wind.data"))$
(%i5) std1 (s2);
(%o5) [4.170835096721089, 3.89090320978032, 3.953738641137555,
 5.701010936401517, 4.966867617451963]
```

See also functions **var1** and **std**.**noncentral\_moment** (*list, k*)

Function

**noncentral\_moment** (*matrix, k*)

Function

The non central moment of order  $k$ , defined as

$$\frac{1}{n} \sum_{i=1}^n x_i^k$$

Example:

```
(%i1) load (descriptive)$
(%i2) s1 : read_list (file_search ("pidigits.data"))$
(%i3) noncentral_moment (s1, 1), numer; /* the mean */
(%o3)
4.71
(%i5) s2 : read_matrix (file_search ("wind.data"))$
(%i6) noncentral_moment (s2, 5);
(%o6) [319793.8724761505, 320532.1923892463,
391249.5621381556, 2502278.205988911, 1691881.797742255]
```

See also function `central_moment`.

**central\_moment** (*list*, *k*)

Function

**central\_moment** (*matrix*, *k*)

Function

The central moment of order *k*, defined as

$$\frac{1}{n} \sum_{i=1}^n (x_i - \bar{x})^k$$

Example:

```
(%i1) load (descriptive)$
(%i2) s1 : read_list (file_search ("pidigits.data"))$
(%i3) central_moment (s1, 2), numer; /* the variance */
(%o3)
8.425899999999999
(%i5) s2 : read_matrix (file_search ("wind.data"))$
(%i6) central_moment (s2, 3);
(%o6) [11.29584771375004, 16.97988248298583, 5.626661952750102,
37.5986572057918, 25.85981904394192]
```

See also functions `central_moment` and `mean`.

**cv** (*list*)

Function

**cv** (*matrix*)

Function

The variation coefficient is the quotient between the sample standard deviation (`std`) and the mean,

```
(%i1) load (descriptive)$
(%i2) s1 : read_list (file_search ("pidigits.data"))$
(%i3) cv (s1), numer;
(%o3)
.6193977819764815
(%i4) s2 : read_matrix (file_search ("wind.data"))$
(%i5) cv (s2);
(%o5) [.4192426091090204, .3829365309260502, 0.363779605385983,
.3627381836021478, .3346021393989506]
```

See also functions `std` and `mean`.

**smin** (*list*)

Function

**smin** (*matrix*)

Function

This is the minimum value of the sample *list*. When the argument is a matrix, `smin` returns a list containing the minimum values of the columns, which are associated to statistical variables.

```
(%i1) load (descriptive)$
(%i2) s1 : read_list (file_search ("pidigits.data"))$
(%i3) smin (s1);
(%o3)
0
(%i4) s2 : read_matrix (file_search ("wind.data"))$
(%i5) smin (s2);
(%o5) [0.58, 0.5, 2.67, 5.25, 5.17]
```

See also function `smax`.

**smax** (*list*) Function  
**smax** (*matrix*) Function

This is the maximum value of the sample *list*. When the argument is a matrix, **smax** returns a list containing the maximum values of the columns, which are associated to statistical variables.

```
(%i1) load (descriptive)$
(%i2) s1 : read_list (file_search ("pidigits.data"))$
(%i3) smax (s1);
(%o3)
 9
(%i4) s2 : read_matrix (file_search ("wind.data"))$
(%i5) smax (s2);
(%o5)
[20.25, 21.46, 20.04, 29.63, 27.63]
```

See also function **smin**.

**range** (*list*) Function  
**range** (*matrix*) Function

The range is the difference between the extreme values.

Example:

```
(%i1) load (descriptive)$
(%i2) s1 : read_list (file_search ("pidigits.data"))$
(%i3) range (s1);
(%o3)
 9
(%i4) s2 : read_matrix (file_search ("wind.data"))$
(%i5) range (s2);
(%o5)
[19.67, 20.96, 17.37, 24.38, 22.46]
```

**quantile** (*list*, *p*) Function  
**quantile** (*matrix*, *p*) Function

This is the *p*-quantile, with *p* a number in  $[0,1]$ , of the sample *list*. Although there are several definitions for the sample quantile (Hyndman, R. J., Fan, Y. (1996) *Sample quantiles in statistical packages*. American Statistician, 50, 361-365), the one based on linear interpolation is implemented in package **descriptive**.

Example:

```
(%i1) load (descriptive)$
(%i2) s1 : read_list (file_search ("pidigits.data"))$
(%i3) /* 1st and 3rd quartiles */
 [quantile (s1, 1/4), quantile (s1, 3/4)], numer;
(%o3)
 [2.0, 7.25]
(%i4) s2 : read_matrix (file_search ("wind.data"))$
(%i5) quantile (s2, 1/4);
(%o5)
[7.2575, 7.477500000000001, 7.82, 11.28, 11.48]
```

**median** (*list*) Function  
**median** (*matrix*) Function

Once the sample is ordered, if the sample size is odd the median is the central value, otherwise it is the mean of the two central values.

Example:

```
(%i1) load (descriptive)$
(%i2) s1 : read_list (file_search ("pidigits.data"))$
(%i3) median (s1);
(%o3)
 9
 -
 2
(%i4) s2 : read_matrix (file_search ("wind.data"))$
(%i5) median (s2);
(%o5)
[10.06, 9.855, 10.73, 15.48, 14.105]
```

The median is the 1/2-quantile.  
See also function `quantile`.

**qrangle** (*list*) Function  
**qrangle** (*matrix*) Function  
 The interquartile range is the difference between the third and first quartiles,  
`quantile(list,3/4) - quantile(list,1/4)`,  

```
(%i1) load (descriptive)$
(%i2) s1 : read_list (file_search ("pidigits.data"))$
(%i3) qrangle (s1);
```

21  
--  
4

```
(%i4) s2 : read_matrix (file_search ("wind.data"))$
(%i5) qrangle (s2);
(%o5) [5.385, 5.572499999999998, 6.022500000000001,
 8.729999999999999, 6.649999999999999]
```

See also function `quantile`.

**mean\_deviation** (*list*) Function  
**mean\_deviation** (*matrix*) Function

The mean deviation, defined as

$$\frac{1}{n} \sum_{i=1}^n |x_i - \bar{x}|$$

Example:

```
(%i1) load (descriptive)$
(%i2) s1 : read_list (file_search ("pidigits.data"))$
(%i3) mean_deviation (s1);
```

51  
--  
20

```
(%i4) s2 : read_matrix (file_search ("wind.data"))$
(%i5) mean_deviation (s2);
(%o5) [3.287959999999999, 3.075342, 3.23907, 4.715664000000001,
 4.028546000000002]
```

See also function `mean`.

**median\_deviation** (*list*) Function  
**median\_deviation** (*matrix*) Function

The median deviation, defined as

$$\frac{1}{n} \sum_{i=1}^n |x_i - med|$$

where `med` is the median of *list*.

Example:

```
(%i1) load (descriptive)$
(%i2) s1 : read_list (file_search ("pidigits.data"))$
(%i3) median_deviation (s1);
```

5  
--  
2

```
(%i4) s2 : read_matrix (file_search ("wind.data"))$
(%i5) median_deviation (s2);
(%o5) [2.75, 2.755, 3.08, 4.315, 3.31]
```

See also function `mean`.

**harmonic\_mean** (*list*)

Function

**harmonic\_mean** (*matrix*)

Function

The harmonic mean, defined as

$$\frac{n}{\sum_{i=1}^n \frac{1}{x_i}}$$

Example:

```
(%i1) load (descriptive)$
(%i2) y : [5, 7, 2, 5, 9, 5, 6, 4, 9, 2, 4, 2, 5]$
(%i3) harmonic_mean (y), numer;
(%o3) 3.901858027632205
(%i4) s2 : read_matrix (file_search ("wind.data"))$
(%i5) harmonic_mean (s2);
(%o5) [6.948015590052786, 7.391967752360356, 9.055658197151745,
13.44199028193692, 13.01439145898509]
```

See also functions `mean` and `geometric_mean`.**geometric\_mean** (*list*)

Function

**geometric\_mean** (*matrix*)

Function

The geometric mean, defined as

$$\left( \prod_{i=1}^n x_i \right)^{\frac{1}{n}}$$

Example:

```
(%i1) load (descriptive)$
(%i2) y : [5, 7, 2, 5, 9, 5, 6, 4, 9, 2, 4, 2, 5]$
(%i3) geometric_mean (y), numer;
(%o3) 4.454845412337012
(%i4) s2 : read_matrix (file_search ("wind.data"))$
(%i5) geometric_mean (s2);
(%o5) [8.82476274347979, 9.22652604739361, 10.0442675714889,
14.61274126349021, 13.96184163444275]
```

See also functions `mean` and `harmonic_mean`.**kurtosis** (*list*)

Function

**kurtosis** (*matrix*)

Function

The kurtosis coefficient, defined as

$$\frac{1}{ns^4} \sum_{i=1}^n (x_i - \bar{x})^4 - 3$$

Example:

```
(%i1) load (descriptive)$
(%i2) s1 : read_list (file_search ("pidigits.data"))$
(%i3) kurtosis (s1), numer;
(%o3) - 1.273247946514421
(%i4) s2 : read_matrix (file_search ("wind.data"))$
(%i5) kurtosis (s2);
(%o5) [- .2715445622195385, 0.119998784429451,
- .4275233490482861, - .6405361979019522, - .4952382132352935]
```

See also functions `mean`, `var` and `skewness`.

**skewness** (*list*)

Function

**skewness** (*matrix*)

Function

The skewness coefficient, defined as

$$\frac{1}{ns^3} \sum_{i=1}^n (x_i - \bar{x})^3$$

Example:

```
(%i1) load (descriptive)$
(%i2) s1 : read_list (file_search ("pidigits.data"))$
(%i3) skewness (s1), numer;
(%o3) .009196180476450424
(%i4) s2 : read_matrix (file_search ("wind.data"))$
(%i5) skewness (s2);
(%o5) [.1580509020000978, .2926379232061854, .09242174416107717,
 .2059984348148687, .2142520248890831]
```

See also functions `mean`, `var` and `kurtosis`.**pearson\_skewness** (*list*)

Function

**pearson\_skewness** (*matrix*)

Function

Pearson's skewness coefficient, defined as

$$\frac{3 (\bar{x} - med)}{s}$$

where *med* is the median of *list*.

Example:

```
(%i1) load (descriptive)$
(%i2) s1 : read_list (file_search ("pidigits.data"))$
(%i3) pearson_skewness (s1), numer;
(%o3) .2159484029093895
(%i4) s2 : read_matrix (file_search ("wind.data"))$
(%i5) pearson_skewness (s2);
(%o5) [-.08019976629211892, .2357036272952649,
 .1050904062491204, .1245042340592368, .4464181795804519]
```

See also functions `mean`, `var` and `median`.**quartile\_skewness** (*list*)

Function

**quartile\_skewness** (*matrix*)

Function

The quartile skewness coefficient, defined as

$$\frac{c_{\frac{3}{4}} - 2c_{\frac{1}{2}} + c_{\frac{1}{4}}}{c_{\frac{3}{4}} - c_{\frac{1}{4}}}$$

where  $c_p$  is the  $p$ -quantile of sample *list*.

Example:

```
(%i1) load (descriptive)$
(%i2) s1 : read_list (file_search ("pidigits.data"))$
(%i3) quartile_skewness (s1), numer;
(%o3) .04761904761904762
(%i4) s2 : read_matrix (file_search ("wind.data"))$
(%i5) quartile_skewness (s2);
(%o5) [-0.0408542246982353, .1467025572005382,
 0.0336239103362392, .03780068728522298, .2105263157894735]
```

See also function `quantile`.



**cov** (*matrix*)

Function

The covariance matrix of the multivariate sample, defined as

$$S = \frac{1}{n} \sum_{j=1}^n (X_j - \bar{X}) (X_j - \bar{X})'$$

where  $X_j$  is the  $j$ -th row of the sample matrix.

Example:

```
(%i1) load (descriptive)$
(%i2) s2 : read_matrix (file_search ("wind.data"))$
(%i3) fpprintprec : 7$ /* change precision for pretty output */
(%i4) cov (s2);
[17.22191 13.61811 14.37217 19.39624 15.42162]
[
[13.61811 14.98774 13.30448 15.15834 14.9711]
[
(%o4) [14.37217 13.30448 15.47573 17.32544 16.18171]
[
[19.39624 15.15834 17.32544 32.17651 20.44685]
[
[15.42162 14.9711 16.18171 20.44685 24.42308]
```

See also function cov1.

**cov1** (*matrix*)

Function

The covariance matrix of the multivariate sample, defined as

$$\frac{1}{n-1} \sum_{j=1}^n (X_j - \bar{X}) (X_j - \bar{X})'$$

where  $X_j$  is the  $j$ -th row of the sample matrix.

Example:

```
(%i1) load (descriptive)$
(%i2) s2 : read_matrix (file_search ("wind.data"))$
(%i3) fpprintprec : 7$ /* change precision for pretty output */
(%i4) cov1 (s2);
[17.39587 13.75567 14.51734 19.59216 15.5774]
[
[13.75567 15.13913 13.43887 15.31145 15.12232]
[
(%o4) [14.51734 13.43887 15.63205 17.50044 16.34516]
[
[19.59216 15.31145 17.50044 32.50153 20.65338]
[
[15.5774 15.12232 16.34516 20.65338 24.66977]
```

See also function cov.

**global\_variances** (*matrix*)

Function

**global\_variances** (*matrix, options ...*)

Function

Function **global\_variances** returns a list of global variance measures:

- *total variance*: **trace**(S\_1),
- *mean variance*: **trace**(S\_1)/p,
- *generalized variance*: **determinant**(S\_1),
- *generalized standard deviation*: **sqrt**(**determinant**(S\_1)),
- *effective variance* **determinant**(S\_1)^(1/p), (defined in: Peña, D. (2002) *Análisis de datos multivariantes*; McGraw-Hill, Madrid.)

- *effective standard deviation*: `determinant(S_1)^(1/(2*p))`.

where  $p$  is the dimension of the multivariate random variable and  $S_1$  the covariance matrix returned by `cov1`.

Option:

- `'data`, default `'true`, indicates whether the input matrix contains the sample data, in which case the covariance matrix `cov1` must be calculated, or not, and then the covariance matrix (symmetric) must be given, instead of the data.

Example:

```
(%i1) load (descriptive)$
(%i2) s2 : read_matrix (file_search ("wind.data"))$
(%i3) global_variances (s2);
(%o3) [105.338342060606, 21.06766841212119, 12874.34690469686,
 113.4651792608501, 6.636590811800795, 2.576158149609762]
```

Calculate the `global_variances` from the covariance matrix.

```
(%i1) load (descriptive)$
(%i2) s2 : read_matrix (file_search ("wind.data"))$
(%i3) s : cov1 (s2)$
(%i4) global_variances (s, data=false);
(%o4) [105.338342060606, 21.06766841212119, 12874.34690469686,
 113.4651792608501, 6.636590811800795, 2.576158149609762]
```

See also `cov` and `cov1`.

**cor** (*matrix*)

Function

**cor** (*matrix*, *logical\_value*)

Function

The correlation matrix of the multivariate sample.

Option:

- `'data`, default `'true`, indicates whether the input matrix contains the sample data, in which case the covariance matrix `cov1` must be calculated, or not, and then the covariance matrix (symmetric) must be given, instead of the data.

Example:

```
(%i1) load (descriptive)$
(%i2) fpprintprec : 7 $
(%i3) s2 : read_matrix (file_search ("wind.data"))$
(%i4) cor (s2);
[1.0 .8476339 .8803515 .8239624 .7519506]
[
[.8476339 1.0 .8735834 .6902622 0.782502]
[
(%o4) [.8803515 .8735834 1.0 .7764065 .8323358]
[
[.8239624 .6902622 .7764065 1.0 .7293848]
[
[.7519506 0.782502 .8323358 .7293848 1.0]
]
```

Calculate de correlation matrix from the covariance matrix.

```
(%i1) load (descriptive)$
(%i2) fpprintprec : 7 $
(%i3) s2 : read_matrix (file_search ("wind.data"))$
(%i4) s : cov1 (s2)$
```

```
(%i5) cor (s, data=false); /* this is faster */
[1.0 .8476339 .8803515 .8239624 .7519506]
[
[.8476339 1.0 .8735834 .6902622 0.782502]
[
(%o5) [.8803515 .8735834 1.0 .7764065 .8323358]
[
[.8239624 .6902622 .7764065 1.0 .7293848]
[
[.7519506 0.782502 .8323358 .7293848 1.0]
[
```

See also `cov` and `cov1`.

**list\_correlations** (*matrix*)

Function

**list\_correlations** (*matrix, options ...*)

Function

Function `list_correlations` returns a list of correlation measures:

- *precision matrix*: the inverse of the covariance matrix  $S_1$ ,

$$S_1^{-1} = (s^{ij})_{i,j=1,2,\dots,p}$$

- *multiple correlation vector*:  $(R_1^2, R_2^2, \dots, R_p^2)$ , with

$$R_i^2 = 1 - \frac{1}{s^{ii}s_{ii}}$$

being an indicator of the goodness of fit of the linear multivariate regression model on  $X_i$  when the rest of variables are used as regressors.

- *partial correlation matrix*: with element  $(i, j)$  being

$$r_{ij.rest} = -\frac{s^{ij}}{\sqrt{s^{ii}s^{jj}}}$$

Option:

- `'data`, default `'true`, indicates whether the input matrix contains the sample data, in which case the covariance matrix `cov1` must be calculated, or not, and then the covariance matrix (symmetric) must be given, instead of the data.

Example:

```
(%i1) load (descriptive)$
(%i2) s2 : read_matrix (file_search ("wind.data"))$
(%i3) z : list_correlations (s2)$
(%i4) fpprintprec : 5$ /* for pretty output */
(%i5) z[1]; /* precision matrix */
[.38486 - .13856 - .15626 - .10239 .031179]
[
[- .13856 .34107 - .15233 .038447 - .052842]
[
(%o5) [- .15626 - .15233 .47296 - .024816 - .10054]
[
[- .10239 .038447 - .024816 .10937 - .034033]
[
[.031179 - .052842 - .10054 - .034033 .14834]
[
(%i6) z[2]; /* multiple correlation vector */
(%o6) [.85063, .80634, .86474, .71867, .72675]
```

```
(%i7) z[3]; /* partial correlation matrix */
[- 1.0 .38244 .36627 .49908 - .13049]
[
[.38244 - 1.0 .37927 - .19907 .23492]
[
(%o7) [.36627 .37927 - 1.0 .10911 .37956]
[
[.49908 - .19907 .10911 - 1.0 .26719]
[
[- .13049 .23492 .37956 .26719 - 1.0]
[
```

See also `cov` and `cov1`.

**principal\_components** (*matrix*)

Function

**principal\_components** (*matrix, options ...*)

Function

Calculates the principal components of a multivariate sample. Principal components are used in multivariate statistical analysis to reduce the dimensionality of the sample.

Option:

- `'data`, default `'true`, indicates whether the input matrix contains the sample data, in which case the covariance matrix `cov1` must be calculated, or not, and then the covariance matrix (symmetric) must be given, instead of the data.

The output of function `principal_components` is a list with the following results:

- variances of the principal components,
- percentage of total variance explained by each principal component,
- rotation matrix.

Examples:

In this sample, the first component explains 83.13 per cent of total variance.

```
(%i1) load (descriptive)$
(%i2) s2 : read_matrix (file_search ("wind.data"))$
(%i3) fpprintprec:4 $
(%i4) res: principal_components(s2);
0 errors, 0 warnings
(%o4) [[87.57, 8.753, 5.515, 1.889, 1.613],
[83.13, 8.31, 5.235, 1.793, 1.531],
[.4149 .03379 - .4757 - 0.581 - .5126]
[
[0.369 - .3657 - .4298 .7237 - .1469]
[
[.3959 - .2178 - .2181 - .2749 .8201]]
[
[.5548 .7744 .1857 .2319 .06498]
[
[.4765 - .4669 0.712 - .09605 - .1969]
(%i5) /* accumulated percentages */
block([ap: copy(res[2])],
for k:2 thru length(ap) do ap[k]: ap[k]+ap[k-1],
ap);
(%o5) [83.13, 91.44, 96.68, 98.47, 100.0]
(%i6) /* sample dimension */
p: length(first(res));
(%o6) 5
(%i7) /* plot percentages to select number of
principal components for further work */
draw2d(
fill_density = 0.2,
```

```

 apply(bars, makelist([k, res[2][k], 1/2], k, p)),
 points_joined = true,
 point_type = filled_circle,
 point_size = 3,
 points(makelist([k, res[2][k]], k, p)),
 xlabel = "Variances",
 ylabel = "Percentages",
 xticks = setify(makelist([concat("PC",k),k], k, p))) $

```

In case of covariance matrix is known, it can be passed to the function, but option `data=false` must be used.

```

(%i1) load (descriptive)$
(%i2) S: matrix([1,-2,0],[-2,5,0],[0,0,2]);
 [1 -2 0]
 []
(%o2) [-2 5 0]
 []
 [0 0 2]

(%i3) fpprintprec:4 $
(%i4) /* the argument is a covariance matrix */
 res: principal_components(S, data=false);
0 errors, 0 warnings
 [- .3827 0.0 .9239]
 []
(%o4) [[5.828, 2.0, .1716], [72.86, 25.0, 2.145], [.9239 0.0 .3827]]
 []
 [0.0 1.0 0.0]

(%i5) /* transformation to get the principal components
 from original records */
 matrix([a1,b2,c3],[a2,b2,c2]).last(res);
 [.9239 b2 - .3827 a1 1.0 c3 .3827 b2 + .9239 a1]
(%o5) []
 [.9239 b2 - .3827 a2 1.0 c2 .3827 b2 + .9239 a2]

```

## 45.4 Functions and Variables for statistical graphs

**barsplot** (*data1, data2, ..., option\_1, option\_2, ...*)

Function

**barsplot\_description** (...)

Function

Plots bars diagrams for discrete statistical variables, both for one or multiple samples.

*data* can be a list of outcomes representing one sample, or a matrix of *m* rows and *n* columns, representing *n* samples of size *m* each.

Available options are:

- *box\_width* (default, 3/4): relative width of rectangles. This value must be in the range [0,1].
- *grouping* (default, **clustered**): indicates how multiple samples are shown. Valid values are: **clustered** and **stacked**.
- *groups\_gap* (default, 1): a positive integer number representing the gap between two consecutive groups of bars.
- *bars\_colors* (default, []): a list of colors for multiple samples. When there are more samples than specified colors, the extra necessary colors are chosen at random. See [color](#) to learn more about them.
- *frequency* (default, **absolute**): indicates the scale of the ordinates. Possible values are: **absolute**, **relative**, and **percent**.
- *ordering* (default, **orderlessp**): possible values are **orderlessp** or **ordergreatp**, indicating how statistical outcomes should be ordered on the x-axis.

- *sample\_keys* (default, []): a list with the strings to be used in the legend. When the list length is other than 0 or the number of samples, an error message is returned.
- *start\_at* (default, 0): indicates where the plot begins to be plotted on the x axis.
- All global **draw** options, except *xtics*, which is internally assigned by **barsplot**. If you want to set your own values for this option or want to build complex scenes, make use of **barsplot\_description**. See example below.
- The following local **draw** options: *key*, *color*, *fill\_color*, *fill\_density* and *line\_width*. See also **bars**.

Function **barsplot\_description** creates a graphic object suitable for creating complex scenes, together with other graphic objects. There is also a function **wxbarsplot** for creating embedded histograms in interfaces wxMaxima and iMaxima.

Examples:

Univariate sample in matrix form. Absolute frequencies.

```
(%i1) load (descriptive)$
(%i2) m : read_matrix (file_search ("biomed.data"))$
(%i3) barsplot(
 col(m,2),
 title = "Ages",
 xlabel = "years",
 box_width = 1/2,
 fill_density = 3/4)$
```

Two samples of different sizes, with relative frequencies and user declared colors.

```
(%i1) load (descriptive)$
(%i2) l1: makelist(random(10),k,1,50)$
(%i3) l2: makelist(random(10),k,1,100)$
(%i4) barsplot(
 l1,l2,
 box_width = 1,
 fill_density = 1,
 bars_colors = [black, grey],
 frequency = relative,
 sample_keys = ["A", "B"])$
```

Four non numeric samples of equal size.

```
(%i1) load (descriptive)$
(%i2) barsplot(
 makelist([Yes, No, Maybe][random(3)+1],k,1,50),
 makelist([Yes, No, Maybe][random(3)+1],k,1,50),
 makelist([Yes, No, Maybe][random(3)+1],k,1,50),
 makelist([Yes, No, Maybe][random(3)+1],k,1,50),
 title = "Asking for something to four groups",
 ylabel = "# of individuals",
 groups_gap = 3,
 fill_density = 0.5,
 ordering = ordergreatp)$
```

Stacked bars.

```
(%i1) load (descriptive)$
```

```
(%i2) barsplot(
 makelist([Yes, No, Maybe][random(3)+1],k,1,50),
 makelist([Yes, No, Maybe][random(3)+1],k,1,50),
 makelist([Yes, No, Maybe][random(3)+1],k,1,50),
 makelist([Yes, No, Maybe][random(3)+1],k,1,50),
 title = "Asking for something to four groups",
 ylabel = "# of individuals",
 grouping = stacked,,
 fill_density = 0.5,
 ordering = ordergreatp)$
```

barsplot in a multiplot context.

```
(%i1) load (descriptive)$
(%i2) l1:makelist(random(10),k,1,50)$
(%i3) l2:makelist(random(10),k,1,100)$
(%i4) bp1 :
 barsplot_description(
 l1,
 box_width = 1,
 fill_density = 0.5,
 bars_colors = [blue],
 frequency = relative)$
(%i5) bp2 :
 barsplot_description(
 l2,
 box_width = 1,
 fill_density = 0.5,
 bars_colors = [red],
 frequency = relative)$
(%i6) draw(gr2d(bp1), gr2d(bp2))$
```

For bars diagrams related options, see `bars` of package `draw`. See also functions `histogram` and `piechart`.

|                                                                         |          |
|-------------------------------------------------------------------------|----------|
| <b>boxplot</b> ( <i>data</i> )                                          | Function |
| <b>boxplot</b> ( <i>data</i> , <i>option_1</i> , <i>option_2</i> , ...) | Function |
| <b>boxplot_description</b> (...)                                        | Function |

This function plots box-and-whisker diagrams. Argument *data* can be a list, which is not of great interest, since these diagrams are mainly used for comparing different samples, or a matrix, so it is possible to compare two or more components of a multivariate statistical variable. But it is also allowed *data* to be a list of samples with possible different sample sizes, in fact this is the only function in package `descriptive` that admits this type of data structure.

Available options are:

- *box\_width* (default, 3/4): relative width of boxes. This value must be in the range [0,1].
- *box\_orientation* (default, `vertical`): possible values: `vertical` and `horizontal`.
- All `draw` options, except `points_joined`, `point_size`, `point_type`, `xtics`, `ytics`, `xrange`, and `yrange`, which are internally assigned by `boxplot`. If you want to set your own values for this options or want to build complex scenes, make use of `boxplot_description`.
- The following local `draw` options: `key`, `color`, and `line_width`.

Function `boxplot_description` creates a graphic object suitable for creating complex scenes, together with other graphic objects. There is also a function `wxboxplot` for creating embedded histograms in interfaces `wxMaxima` and `iMaxima`.

Examples:

Box-and-whisker diagram from a multivariate sample.

```
(%i1) load (descriptive)$
(%i2) s2 : read_matrix(file_search("wind.data"))$
(%i3) boxplot(s2,
 box_width = 0.2,
 title = "Windspeed in knots",
 xlabel = "Stations",
 color = red,
 line_width = 2)$
```

Box-and-whisker diagram from three samples of different sizes.

```
(%i1) load (descriptive)$
(%i2) A :
 [[6, 4, 6, 2, 4, 8, 6, 4, 6, 4, 3, 2],
 [8, 10, 7, 9, 12, 8, 10],
 [16, 13, 17, 12, 11, 18, 13, 18, 14, 12]]$
(%i3) boxplot (A, box_orientation = horizontal)$
```

|                                                                                        |          |
|----------------------------------------------------------------------------------------|----------|
| <b>histogram</b> ( <i>list</i> )                                                       | Function |
| <b>histogram</b> ( <i>list</i> , <i>option_1</i> , <i>option_2</i> , ...)              | Function |
| <b>histogram</b> ( <i>one_column_matrix</i> )                                          | Function |
| <b>histogram</b> ( <i>one_column_matrix</i> , <i>option_1</i> , <i>option_2</i> , ...) | Function |
| <b>histogram</b> ( <i>one_row_matrix</i> )                                             | Function |
| <b>histogram</b> ( <i>one_row_matrix</i> , <i>option_1</i> , <i>option_2</i> , ...)    | Function |
| <b>histogram_description</b> (...)                                                     | Function |

This function plots an histogram from a continuous sample. Sample data must be stored in a list of numbers or a one dimensional matrix.

Available options are:

- *nclasses* (default, 10): number of classes of the histogram, or a list indicating the limits of the classes and the number of them, or only the limits.
- *frequency* (default, **absolute**): indicates the scale of the ordinates. Possible values are: **absolute**, **relative**, **percent**, and **density**. With **density**, the histogram area has a total area of one.
- *htics* (default, **auto**): format of the histogram tics. Possible values are: **auto**, **endpoints**, **intervals**, or a list of labels.
- All global draw options, except **xrange**, **yrange**, and **xtics**, which are internally assigned by **histogram**. If you want to set your own values for these options, make use of **histogram\_description**. See examples below.
- The following local draw options: **key**, **color**, **fill\_color**, **fill\_density** and **line\_width**. See also **bars**.

Function **histogram\_description** creates a graphic object suitable for creating complex scenes, together with other graphic objects. There is also a function **wxhistogram** for creating embedded histograms in interfaces wxMaxima and iMaxima.

Examples:

A simple with eight classes:

```
(%i1) load (descriptive)$
(%i2) s1 : read_list (file_search ("pidigits.data"))$
(%i3) histogram (
 s1,
 nclasses = 8,
 title = "pi digits",
 xlabel = "digits",
 ylabel = "Absolute frequency",
 fill_color = grey,
 fill_density = 0.6)$
```

Setting the limits of the histogram to -2 and 12, with 3 classes. Also, we introduce predefined tics:



```
(%i1) load (descriptive)$
(%i2) s1 : read_list (file_search ("pidigits.data"))$
(%i3) histogram (
 s1,
 nclasses = [-2,12,3],
 htics = ["A", "B", "C"],
 terminal = png,
 fill_color = "#23afa0",
 fill_density = 0.6)$
```

We make use of `histogram_description` for setting the `xrange` and adding an explicit curve into the scene:

```
(%i1) load (descriptive)$
(%i2) (load("distrib"),
 m: 14, s: 2,
 s2: random_normal(m, s, 1000)) $
(%i3) draw2d(
 grid = true,
 xrange = [5, 25],
 histogram_description(
 s2,
 nclasses = 9,
 frequency = density,
 fill_density = 0.5),
 explicit(pdf_normal(x,m,s), x, m - 3*s, m + 3* s))$
```

|                                                                                       |          |
|---------------------------------------------------------------------------------------|----------|
| <b>piechart</b> ( <i>list</i> )                                                       | Function |
| <b>piechart</b> ( <i>list</i> , <i>option_1</i> , <i>option_2</i> , ...)              | Function |
| <b>piechart</b> ( <i>one_column_matrix</i> )                                          | Function |
| <b>piechart</b> ( <i>one_column_matrix</i> , <i>option_1</i> , <i>option_2</i> , ...) | Function |
| <b>piechart</b> ( <i>one_row_matrix</i> )                                             | Function |
| <b>piechart</b> ( <i>one_row_matrix</i> , <i>option_1</i> , <i>option_2</i> , ...)    | Function |
| <b>piechart_description</b> (...)                                                     | Function |

Similar to `barsplot`, but plots sectors instead of rectangles.

Available options are:

- *sector\_colors* (default, []): a list of colors for sectors. When there are more sectors than specified colors, the extra necessary colors are chosen at random. See `color` to learn more about them.
- *pie\_center* (default, [0,0]): diagram's center.
- *pie\_radius* (default, 1): diagram's radius.
- All global `draw` options, except `key`, which is internally assigned by `piechart`. If you want to set your own values for this option or want to build complex scenes, make use of `piechart_description`.
- The following local `draw` options: `key`, `color`, `fill_density` and `line_width`. See also `ellipse`.

Function `piechart_description` creates a graphic object suitable for creating complex scenes, together with other graphic objects. There is also a function `wxpiechart` for creating embedded histograms in interfaces `wxMaxima` and `iMaxima`.

Example:

```
(%i1) load (descriptive)$
(%i2) s1 : read_list (file_search ("pidigits.data"))$
(%i3) piechart(
 s1,
 xrange = [-1.1, 1.3],
 yrange = [-1.1, 1.1],
 title = "Digit frequencies in pi")$
```

See also function `barsplot`.

|                                                                               |          |
|-------------------------------------------------------------------------------|----------|
| <b>scatterplot</b> ( <i>list</i> )                                            | Function |
| <b>scatterplot</b> ( <i>list</i> , <i>option_1</i> , <i>option_2</i> , ...)   | Function |
| <b>scatterplot</b> ( <i>matrix</i> )                                          | Function |
| <b>scatterplot</b> ( <i>matrix</i> , <i>option_1</i> , <i>option_2</i> , ...) | Function |
| <b>scatterplot_description</b> (...)                                          | Function |

Plots scatter diagrams both for univariate (*list*) and multivariate (*matrix*) samples.

Available options are the same admitted by **histogram**.

Function **scatterplot\_description** creates a graphic object suitable for creating complex scenes, together with other graphic objects. There is also a function **wxscatterplot** for creating embedded histograms in interfaces wxMaxima and iMaxima.

Examples:

Univariate scatter diagram from a simulated Gaussian sample.

```
(%i1) load (descriptive)$
(%i2) load (distrib)$
(%i3) scatterplot(
 random_normal(0,1,200),
 xaxis = true,
 point_size = 2,
 dimensions = [600,150])$
```

Two dimensional scatter plot.

```
(%i1) load (descriptive)$
(%i2) s2 : read_matrix (file_search ("wind.data"))$
(%i3) scatterplot(
 submatrix(s2, 1,2,3),
 title = "Data from stations #4 and #5",
 point_type = diamant,
 point_size = 2,
 color = blue)$
```

Three dimensional scatter plot.

```
(%i1) load (descriptive)$
(%i2) s2 : read_matrix (file_search ("wind.data"))$
(%i3) scatterplot(submatrix (s2, 1,2), nclasses=4)$
```

Five dimensional scatter plot, with five classes histograms.

```
(%i1) load (descriptive)$
(%i2) s2 : read_matrix (file_search ("wind.data"))$
(%i3) scatterplot(
 s2,
 nclasses = 5,
 frequency = relative,
 fill_color = blue,
 fill_density = 0.3,
 xtics = 5)$
```

For plotting isolated or line-joined points in two and three dimensions, see **points**. See also **histogram**.

|                                                                                               |          |
|-----------------------------------------------------------------------------------------------|----------|
| <b>starplot</b> ( <i>data1</i> , <i>data2</i> , ..., <i>option_1</i> , <i>option_2</i> , ...) | Function |
| <b>starplot_description</b> (...)                                                             | Function |

Plots star diagrams for discrete statistical variables, both for one or multiple samples.

*data* can be a list of outcomes representing one sample, or a matrix of *m* rows and *n* columns, representing *n* samples of size *m* each.

Available options are:

- *stars\_colors* (default, []): a list of colors for multiple samples. When there are more samples than specified colors, the extra necessary colors are chosen at random. See **color** to learn more about them.

- *frequency* (default, **absolute**): indicates the scale of the radii. Possible values are: **absolute** and **relative**.
- *ordering* (default, **orderlessp**): possible values are **orderlessp** or **ordergreatp**, indicating how statistical outcomes should be ordered.
- *sample\_keys* (default, **[]**): a list with the strings to be used in the legend. When the list length is other than 0 or the number of samples, an error message is returned.
- *star\_center* (default, **[0,0]**): diagram's center.
- *star\_radius* (default, **1**): diagram's radius.
- All global **draw** options, except **points\_joined**, **point\_type**, and **key**, which are internally assigned by **starplot**. If you want to set your own values for this options or want to build complex scenes, make use of **starplot\_description**.
- The following local **draw** option: **line\_width**.

Function **starplot\_description** creates a graphic object suitable for creating complex scenes, together with other graphic objects. There is also a function **wxstarplot** for creating embedded histograms in interfaces **wxMaxima** and **iMaxima**.

Example:

Plot based on absolute frequencies. Location and radius defined by the user.

```
(%i1) load (descriptive)$
(%i2) l1: makelist(random(10),k,1,50)$
(%i3) l2: makelist(random(10),k,1,200)$
(%i4) starplot(
 l1, l2,
 stars_colors = [blue,red],
 sample_keys = ["1st sample", "2nd sample"],
 star_center = [1,2],
 star_radius = 4,
 proportional_axes = xy,
 line_width = 2) $
```

**stemplot** (*data*)

Function

**stemplot** (*data*, *option*)

Function

Plots stem and leaf diagrams.

Unique available option is:

- *leaf\_unit* (default, **1**): indicates the unit of the leaves; must be a power of 10.

Example:

```
(%i1) load (descriptive)$
(%i2) load(distrib)$
```

```
(%i3) stemplot(
 random_normal(15, 6, 100),
 leaf_unit = 0.1);
```

```
-5|4
0|37
1|7
3|6
4|4
5|4
6|57
7|0149
8|3
9|1334588
10|07888
11|01144467789
12|12566889
13|24778
14|047
15|223458
16|4
17|11557
18|000247
19|4467799
20|00
21|1
22|2335
23|01457
24|12356
25|455
27|79
key: 6|3 = 6.3
```

```
(%o3)
```

```
done
```

## 46 diag

### 46.1 Functions and Variables for diag

#### diag (*lm*)

Function

Constructs a square matrix with the matrices of *lm* in the diagonal. *lm* is a list of matrices or scalars.

Example:

```
(%i1) load("diag")$

(%i2) a1:matrix([1,2,3],[0,4,5],[0,0,6])$

(%i3) a2:matrix([1,1],[1,0])$

(%i4) diag([a1,x,a2]);
```

$$\begin{bmatrix} 1 & 2 & 3 & 0 & 0 & 0 \\ 0 & 4 & 5 & 0 & 0 & 0 \\ 0 & 0 & 6 & 0 & 0 & 0 \\ 0 & 0 & 0 & x & 0 & 0 \\ 0 & 0 & 0 & 0 & 1 & 1 \\ 0 & 0 & 0 & 0 & 1 & 0 \end{bmatrix}$$

```
(%o4)
```

To use this function write first `load("diag")`.

#### JF (*lambda,n*)

Function

Returns the Jordan cell of order *n* with eigenvalue *lambda*.

Example:

```
(%i1) load("diag")$

(%i2) JF(2,5);
```

$$\begin{bmatrix} 2 & 1 & 0 & 0 & 0 \\ 0 & 2 & 1 & 0 & 0 \\ 0 & 0 & 2 & 1 & 0 \\ 0 & 0 & 0 & 2 & 1 \\ 0 & 0 & 0 & 0 & 2 \end{bmatrix}$$

```
(%o2)
```

```
(%i3) JF(3,2);
```

$$\begin{bmatrix} 3 & 1 \\ 0 & 3 \end{bmatrix}$$

```
(%o3)
```

To use this function write first `load("diag")`.

#### jordan (*mat*)

Function

Returns the Jordan form of matrix *mat*, but codified in a Maxima list. To get the corresponding matrix, call function `dispJordan` using as argument the output of `jordan`.

Example:

```
(%i1) load("diag")$

(%i3) a:matrix([2,0,0,0,0,0,0,0],
 [1,2,0,0,0,0,0,0],
 [-4,1,2,0,0,0,0,0],
 [2,0,0,2,0,0,0,0],
 [-7,2,0,0,2,0,0,0],
 [9,0,-2,0,1,2,0,0],
 [-34,7,1,-2,-1,1,2,0],
 [145,-17,-16,3,9,-2,0,3])$

(%i34) jordan(a);
(%o4) [[2, 3, 3, 1], [3, 1]]
(%i5) dispJordan(%);
 [2 1 0 0 0 0 0 0]
 [
 [0 2 1 0 0 0 0 0]
 [
 [0 0 2 0 0 0 0 0]
 [
 [0 0 0 2 1 0 0 0]
(%o5) [
 [0 0 0 0 2 1 0 0]
 [
 [0 0 0 0 0 2 0 0]
 [
 [0 0 0 0 0 0 2 0]
 [
 [0 0 0 0 0 0 0 3]
```

To use this function write first `load("diag")`. See also `dispJordan` and `minimalPoly`.

### **dispJordan** (*l*)

Function

Returns the Jordan matrix associated to the codification given by the Maxima list *l*, which is the output given by function `jordan`.

Example:

```
(%i1) load("diag")$

(%i2) b1:matrix([0,0,1,1,1],
 [0,0,0,1,1],
 [0,0,0,0,1],
 [0,0,0,0,0],
 [0,0,0,0,0])$

(%i3) jordan(b1);
(%o3) [[0, 3, 2]]
(%i4) dispJordan(%);
 [0 1 0 0 0]
 [
 [0 0 1 0 0]
 [
 [0 0 0 0 0]
(%o4) [
 [
 [0 0 0 0 1]
 [
 [0 0 0 0 0]
```

To use this function write first `load("diag")`. See also `jordan` and `minimalPoly`.

**minimalPoly** (*l*)

Function

Returns the minimal polynomial associated to the codification given by the Maxima list *l*, which is the output given by function `jordan`.

Example:

```
(%i1) load("diag")$

(%i2) a:matrix([2,1,2,0],
 [-2,2,1,2],
 [-2,-1,-1,1],
 [3,1,2,-1])$

(%i3) jordan(a);
(%o3) [[- 1, 1], [1, 3]]
(%i4) minimalPoly(%);
(%o4) (x - 1)3 (x + 1)
```

To use this function write first `load("diag")`. See also `jordan` and `dispJordan`.

**ModeMatrix** (*A,l*)

Function

Returns the matrix *M* such that  $(Mm1).A.M = J$ , where *J* is the Jordan form of *A*. The Maxima list *l* is the codified form of the Jordan form as returned by function `jordan`.

Example:

```
(%i1) load("diag")$

(%i2) a:matrix([2,1,2,0],
 [-2,2,1,2],
 [-2,-1,-1,1],
 [3,1,2,-1])$

(%i3) jordan(a);
(%o3) [[- 1, 1], [1, 3]]
(%i4) M: ModeMatrix(a,%);
(%o4) [1 - 1 1 1]
 []
 [1]
 [- - - 1 0 0]
 [9]
 []
 [13]
 [- -- 1 - 1 0]
 [9]
 []
 [17]
 [-- - 1 1 1]
 [9]
(%i5) is((M^-1).a.M = dispJordan(%o3));
(%o5) true
```

Note that `dispJordan(%o3)` is the Jordan form of matrix *a*.

To use this function write first `load("diag")`. See also `jordan` and `dispJordan`.

**mat\_function** (*f,mat*)

Function

Returns  $f(mat)$ , where *f* is an analytic function and *mat* a matrix. This computation is based on Cauchy's integral formula, which states that if *f*(*x*) is analytic and

```
mat = diag([JF(m1,n1), ..., JF(mk,nk)]),
```

then

```
f(mat) = ModeMatrix*diag([f(JF(m1,n1)), ..., f(JF(mk,nk))])
 *ModeMatrix^(-1)
```

Note that there are about 6 or 8 other methods for this calculation.

Some examples follow.

Example 1:

```
(%i1) load("diag")$

(%i2) b2:matrix([0,1,0], [0,0,1], [-1,-3,-3])$

(%i3) mat_function(exp,t*b2);

(%o3) matrix([----- + t %e-t + %e-t,
 2
 - t - t - t
 t %e %e %e
 2
 - t - t - t
 %e %e %e
 2 2 2
 t (- ---- - ---- + %e) + t (2 %e - ----)
 t 2 t
 2 2 2
 - t - t - t
 %e %e %e
 2 2 2
 + 2 %e , t (%e - ----) + t (- ---- - ----)
 t t t
 2 2 2
 - t - t - t
 t %e 2 %e %e
 2 2 2
 + %e], [- ----, - t (- ---- - ---- + %e),
 2 t 2
 - t - t 2 - t
 2 %e %e t %e
 2 t 2
 - t (- ---- - ----)], [- ---- - t %e ,
 2 t 2
 - t - t - t
 2 %e %e %e
 2 2 2
 t (- ---- - ---- + %e) - t (2 %e - ----),
 t 2 t
 - t - t - t
 2 %e %e %e
 2 t 2
 t (- ---- - ----) - t (%e - ----)])

(%i4) ratsimp(%);

(%o4) Col 1 = [
 2 - t
 (t + 2 t + 2) %e

 2
]
 [
 2 - t
 t %e
 - ----
 2
]
 [
 2 - t
 (t - 2 t) %e

 2
]
```



$$\begin{aligned}
 \text{Col 2} &= \begin{bmatrix} (t^2 + t) e^{-t} \\ - (t^2 - t - 1) e^{-t} \\ (t^2 - 3t) e^{-t} \\ t^2 e^{-t} \\ \frac{t^2}{2} \end{bmatrix} \\
 \text{Col 3} &= \begin{bmatrix} (t^2 - 2t) e^{-t} \\ - \frac{t^2}{2} \\ (t^2 - 4t + 2) e^{-t} \\ \frac{t^2}{2} \end{bmatrix}
 \end{aligned}$$

Example 2:

```
(%i5) b1:matrix([0,0,1,1,1],
 [0,0,0,1,1],
 [0,0,0,0,1],
 [0,0,0,0,0],
 [0,0,0,0,0])$

(%i6) mat_function(exp,t*b1);
 [2]
 [t]
 [1 0 t t -- + t]
 [2]
 []
(%o6) [0 1 0 t t]
 []
 [0 0 1 0 t]
 []
 [0 0 0 1 0]
 []
 [0 0 0 0 1]

(%i7) minimalPoly(jordan(b1));
 3
(%o7) x
(%i8) ident(5)+t*b1+1/2*(t^2)*b1^2;
 [2]
 [t]
 [1 0 t t -- + t]
 [2]
 []
(%o8) [0 1 0 t t]
 []
 [0 0 1 0 t]
 []
```

```

 [0 0 0 1 0]
 []
 [0 0 0 0 1]
(%i9) mat_function(exp,%i*t*b1);
 [2]
 [t]
 [1 0 %i t %i t %i t - --]
 [2]
 []
(%o9) [0 1 0 %i t %i t]
 []
 [0 0 1 0 %i t]
 []
 [0 0 0 1 0]
 []
 [0 0 0 0 1]
(%i10) mat_function(cos,t*b1)+%i*mat_function(sin,t*b1);
 [2]
 [t]
 [1 0 %i t %i t %i t - --]
 [2]
 []
(%o10) [0 1 0 %i t %i t]
 []
 [0 0 1 0 %i t]
 []
 [0 0 0 1 0]
 []
 [0 0 0 0 1]

```

Example 3:

```

(%i11) a1:matrix([2,1,0,0,0,0],
 [-1,4,0,0,0,0],
 [-1,1,2,1,0,0],
 [-1,1,-1,4,0,0],
 [-1,1,-1,1,3,0],
 [-1,1,-1,1,1,2])$

(%i12) fpow(x):=block([k],declare(k,integer),x^k)$

(%i13) mat_function(fpow,a1);
 [k k - 1] [k - 1]
 [3 - k 3] [k 3]
 [] []
 [k - 1] [k k - 1]
 [- k 3] [3 + k 3]
 [] []
 [k - 1] [k - 1]
 [- k 3] [k 3]
(%o13) Col 1 = [] Col 2 = []
 [k - 1] [k - 1]
 [- k 3] [k 3]
 [] []
 [k - 1] [k - 1]
 [- k 3] [k 3]
 [] []
 [k - 1] [k - 1]

```

[illegible]

To use this function write first `load("diag")`.



## 47 distrib

### 47.1 Introduction to distrib

Package `distrib` contains a set of functions for making probability computations on both discrete and continuous univariate models.

What follows is a short reminder of basic probabilistic related definitions.

Let  $f(x)$  be the *density function* of an absolute continuous random variable  $X$ . The *distribution function* is defined as

$$F(x) = \int_{-\infty}^x f(u) du$$

which equals the probability  $Pr(X \leq x)$ .

The *mean* value is a localization parameter and is defined as

$$E[X] = \int_{-\infty}^{\infty} x f(x) dx$$

The *variance* is a measure of variation,

$$V[X] = \int_{-\infty}^{\infty} f(x) (x - E[X])^2 dx$$

which is a positive real number. The square root of the variance is the *standard deviation*,  $D[X] = \sqrt{V[X]}$ , and it is another measure of variation.

The *skewness coefficient* is a measure of non-symmetry,

$$SK[X] = \frac{\int_{-\infty}^{\infty} f(x) (x - E[X])^3 dx}{D[X]^3}$$

And the *kurtosis coefficient* measures the peakedness of the distribution,

$$KU[X] = \frac{\int_{-\infty}^{\infty} f(x) (x - E[X])^4 dx}{D[X]^4} - 3$$

If  $X$  is gaussian,  $KU[X] = 0$ . In fact, both skewness and kurtosis are shape parameters used to measure the non-gaussianity of a distribution.

If the random variable  $X$  is discrete, the density, or *probability*, function  $f(x)$  takes positive values within certain countable set of numbers  $x_i$ , and zero elsewhere. In this case, the distribution function is

$$F(x) = \sum_{x_i \leq x} f(x_i)$$

The mean, variance, standard deviation, skewness coefficient and kurtosis coefficient take the form

$$E[X] = \sum_{x_i} x_i f(x_i),$$

$$V[X] = \sum_{x_i} f(x_i) (x_i - E[X])^2,$$

$$D[X] = \sqrt{V[X]},$$

$$SK[X] = \frac{\sum_{x_i} f(x_i) (x_i - E[X])^3}{D[X]^3}$$

and

$$KU[X] = \frac{\sum_{x_i} f(x) (x - E[X])^4 dx}{D[X]^4} - 3,$$

respectively.

There is a naming convention in package `distrib`. Every function name has two parts, the first one makes reference to the function or parameter we want to calculate,

Functions:

|                       |              |
|-----------------------|--------------|
| Density function      | (pdf_*)      |
| Distribution function | (cdf_*)      |
| Quantile              | (quantile_*) |
| Mean                  | (mean_*)     |
| Variance              | (var_*)      |
| Standard deviation    | (std_*)      |
| Skewness coefficient  | (skewness_*) |
| Kurtosis coefficient  | (kurtosis_*) |
| Random variate        | (random_*)   |

The second part is an explicit reference to the probabilistic model,

Continuous distributions:

|                    |                       |
|--------------------|-----------------------|
| Normal             | (*normal)             |
| Student            | (*student_t)          |
| Chi^2              | (*chi2)               |
| Noncentral Chi^2   | (*noncentral_chi2)    |
| F                  | (*f)                  |
| Exponential        | (*exp)                |
| Lognormal          | (*lognormal)          |
| Gamma              | (*gamma)              |
| Beta               | (*beta)               |
| Continuous uniform | (*continuous_uniform) |
| Logistic           | (*logistic)           |
| Pareto             | (*pareto)             |
| Weibull            | (*weibull)            |
| Rayleigh           | (*rayleigh)           |
| Laplace            | (*laplace)            |
| Cauchy             | (*cauchy)             |
| Gumbel             | (*gumbel)             |

Discrete distributions:

|                   |                            |
|-------------------|----------------------------|
| Binomial          | (*binomial)                |
| Poisson           | (*poisson)                 |
| Bernoulli         | (*bernoulli)               |
| Geometric         | (*geometric)               |
| Discrete uniform  | (*discrete_uniform)        |
| hypergeometric    | (*hypergeometric)          |
| Negative binomial | (*negative_binomial)       |
| Finite discrete   | (*general_finite_discrete) |

For example, `pdf_student_t(x,n)` is the density function of the Student distribution with  $n$  degrees of freedom, `std_pareto(a,b)` is the standard deviation of the Pareto distribution with parameters  $a$  and  $b$  and `kurtosis_poisson(m)` is the kurtosis coefficient of the Poisson distribution with mean  $m$ .

In order to make use of package `distrib` you need first to load it by typing

```
(%i1) load(distrib)$
```

For comments, bugs or suggestions, please contact the author at 'mario AT edu DOT xunta DOT es'.

## 47.2 Functions and Variables for continuous distributions

**pdf\_normal** ( $x, m, s$ ) Function

Returns the value at  $x$  of the density function of a  $Normal(m, s)$  random variable, with  $s > 0$ . To make use of this function, write first `load(distrib)`.

**cdf\_normal** ( $x, m, s$ ) Function

Returns the value at  $x$  of the distribution function of a  $Normal(m, s)$  random variable, with  $s > 0$ . This function is defined in terms of Maxima's built-in error function `erf`.

```
(%i1) load (distrib)$
(%i2) assume(s>0)$ cdf_normal(x,m,s);
 x - m
 erf(-----)
 sqrt(2) s
(%o3) ----- + -
 2 2
```

See also `erf`.

**quantile\_normal** ( $q, m, s$ ) Function

Returns the  $q$ -quantile of a  $Normal(m, s)$  random variable, with  $s > 0$ ; in other words, this is the inverse of `cdf_normal`. Argument  $q$  must be an element of  $[0, 1]$ . To make use of this function, write first `load(distrib)`.

```
(%i1) load (distrib)$
(%i2) quantile_normal(95/100,0,1);
 9
(%o2) sqrt(2) inverse_erf(---)
 10
(%i3) float(%);
(%o3) 1.644853626951472
```

**mean\_normal** ( $m, s$ ) Function

Returns the mean of a  $Normal(m, s)$  random variable, with  $s > 0$ , namely  $m$ . To make use of this function, write first `load(distrib)`.

**var\_normal** ( $m, s$ ) Function

Returns the variance of a  $Normal(m, s)$  random variable, with  $s > 0$ , namely  $s^2$ . To make use of this function, write first `load(distrib)`.

**std\_normal** ( $m, s$ ) Function

Returns the standard deviation of a  $Normal(m, s)$  random variable, with  $s > 0$ , namely  $s$ . To make use of this function, write first `load(distrib)`.

**skewness\_normal** ( $m, s$ ) Function

Returns the skewness coefficient of a  $Normal(m, s)$  random variable, with  $s > 0$ , which is always equal to 0. To make use of this function, write first `load(distrib)`.

**kurtosis\_normal** ( $m, s$ ) Function

Returns the kurtosis coefficient of a  $Normal(m, s)$  random variable, with  $s > 0$ , which is always equal to 0. To make use of this function, write first `load(distrib)`.

**random\_normal** ( $m, s$ ) Function

**random\_normal** ( $m, s, n$ ) Function

Returns a  $Normal(m, s)$  random variate, with  $s > 0$ . Calling `random_normal` with a third argument  $n$ , a random sample of size  $n$  will be simulated.

This is an implementation of the Box-Mueller algorithm, as described in Knuth, D.E. (1981) *Seminumerical Algorithms. The Art of Computer Programming*. Addison-Wesley.

To make use of this function, write first `load(distrib)`.

**pdf\_student\_t** ( $x, n$ ) Function  
 Returns the value at  $x$  of the density function of a Student random variable  $t(n)$ , with  $n > 0$  degrees of freedom. To make use of this function, write first `load(distrib)`.

**cdf\_student\_t** ( $x, n$ ) Function  
 Returns the value at  $x$  of the distribution function of a Student random variable  $t(n)$ , with  $n > 0$  degrees of freedom.

```
(%i1) load (distrib)$
(%i2) cdf_student_t(1/2, 7/3);

 7 1 28
 beta_incomplete_regularized(-, -, --)
 6 2 31

(%o2) 1 - -----
 2

(%i3) float(%);
(%o3) .6698450596140415
```

**quantile\_student\_t** ( $q, n$ ) Function  
 Returns the  $q$ -quantile of a Student random variable  $t(n)$ , with  $n > 0$ ; in other words, this is the inverse of `cdf_student_t`. Argument  $q$  must be an element of  $[0, 1]$ . To make use of this function, write first `load(distrib)`.

**mean\_student\_t** ( $n$ ) Function  
 Returns the mean of a Student random variable  $t(n)$ , with  $n > 0$ , which is always equal to 0. To make use of this function, write first `load(distrib)`.

**var\_student\_t** ( $n$ ) Function  
 Returns the variance of a Student random variable  $t(n)$ , with  $n > 2$ .

```
(%i1) load (distrib)$
(%i2) assume(n>2)$ var_student_t(n);

 n

 n - 2

(%o3)
```

**std\_student\_t** ( $n$ ) Function  
 Returns the standard deviation of a Student random variable  $t(n)$ , with  $n > 2$ . To make use of this function, write first `load(distrib)`.

**skewness\_student\_t** ( $n$ ) Function  
 Returns the skewness coefficient of a Student random variable  $t(n)$ , with  $n > 3$ , which is always equal to 0. To make use of this function, write first `load(distrib)`.

**kurtosis\_student\_t** ( $n$ ) Function  
 Returns the kurtosis coefficient of a Student random variable  $t(n)$ , with  $n > 4$ . To make use of this function, write first `load(distrib)`.

**random\_student\_t** ( $n$ ) Function  
**random\_student\_t** ( $n, m$ ) Function

Returns a Student random variate  $t(n)$ , with  $n > 0$ . Calling `random_student_t` with a second argument  $m$ , a random sample of size  $m$  will be simulated.

The implemented algorithm is based on the fact that if  $Z$  is a normal random variable  $N(0, 1)$  and  $S^2$  is a chi square random variable with  $n$  degrees of freedom,  $Chi^2(n)$ , then

$$X = \frac{Z}{\sqrt{\frac{S^2}{n}}}$$

is a Student random variable with  $n$  degrees of freedom,  $t(n)$ .

To make use of this function, write first `load(distrib)`.



**pdf\_noncentral\_student\_t** ( $x, n, ncp$ )

Function

Returns the value at  $x$  of the density function of a noncentral Student random variable  $nc_t(n, ncp)$ , with  $n > 0$  degrees of freedom and noncentrality parameter  $ncp$ . To make use of this function, write first `load(distrib)`.

Sometimes an extra work is necessary to get the final result.

```
(%i1) load (distrib)$
(%i2) expand(pdf_noncentral_student_t(3,5,0.1));
 .01370030107589574 sqrt(5)
(%o2) -----
 sqrt(2) sqrt(14) sqrt(%pi)
 1.654562884111515E-4 sqrt(5)
+ -----
 sqrt(%pi)
 .02434921505438663 sqrt(5)
+ -----
 %pi
(%i3) float(%);
(%o3) .02080593159405669
```

**cdf\_noncentral\_student\_t** ( $x, n, ncp$ )

Function

Returns the value at  $x$  of the distribution function of a noncentral Student random variable  $nc_t(n, ncp)$ , with  $n > 0$  degrees of freedom and noncentrality parameter  $ncp$ . This function has no closed form and it is numerically computed if the global variable `numer` equals `true` or at least one of the arguments is a float, otherwise it returns a nominal expression.

```
(%i1) load (distrib)$
(%i2) cdf_noncentral_student_t(-2,5,-5);
(%o2) cdf_noncentral_student_t(- 2, 5, - 5)
(%i3) cdf_noncentral_student_t(-2.0,5,-5);
(%o3) .9952030093319743
```

**quantile\_noncentral\_student\_t** ( $q, n, ncp$ )

Function

Returns the  $q$ -quantile of a noncentral Student random variable  $nc_t(n, ncp)$ , with  $n > 0$  degrees of freedom and noncentrality parameter  $ncp$ ; in other words, this is the inverse of `cdf_noncentral_student_t`. Argument  $q$  must be an element of  $[0, 1]$ . To make use of this function, write first `load(distrib)`.

**mean\_noncentral\_student\_t** ( $n, ncp$ )

Function

Returns the mean of a noncentral Student random variable  $nc_t(n, ncp)$ , with  $n > 1$  degrees of freedom and noncentrality parameter  $ncp$ . To make use of this function, write first `load(distrib)`.

```
(%i1) load (distrib)$
(%i2) (assume(df>1), mean_noncentral_student_t(df,k));
 df - 1
 gamma(-----) sqrt(df) k
 2
(%o2) -----
 df
 sqrt(2) gamma(--)
 2
```

**var\_noncentral\_student\_t** ( $n, ncp$ )

Function

Returns the variance of a noncentral Student random variable  $nc_t(n, ncp)$ , with  $n > 2$  degrees of freedom and noncentrality parameter  $ncp$ . To make use of this function, write first `load(distrib)`.

**std\_noncentral\_student\_t** ( $n, ncp$ ) Function

Returns the standard deviation of a noncentral Student random variable  $nc_t(n, ncp)$ , with  $n > 2$  degrees of freedom and noncentrality parameter  $ncp$ . To make use of this function, write first `load(distrib)`.

**skewness\_noncentral\_student\_t** ( $n, ncp$ ) Function

Returns the skewness coefficient of a noncentral Student random variable  $nc_t(n, ncp)$ , with  $n > 3$  degrees of freedom and noncentrality parameter  $ncp$ . To make use of this function, write first `load(distrib)`.

**kurtosis\_noncentral\_student\_t** ( $n, ncp$ ) Function

Returns the kurtosis coefficient of a noncentral Student random variable  $nc_t(n, ncp)$ , with  $n > 4$  degrees of freedom and noncentrality parameter  $ncp$ . To make use of this function, write first `load(distrib)`.

**random\_noncentral\_student\_t** ( $n, ncp$ ) Function

**random\_noncentral\_student\_t** ( $n, ncp, m$ ) Function

Returns a noncentral Student random variate  $nc_t(n, ncp)$ , with  $n > 0$ . Calling `random_noncentral_student_t` with a third argument  $m$ , a random sample of size  $m$  will be simulated.

The implemented algorithm is based on the fact that if  $X$  is a normal random variable  $N(ncp, 1)$  and  $S^2$  is a chi square random variable with  $n$  degrees of freedom,  $Chi^2(n)$ , then

$$U = \frac{X}{\sqrt{\frac{S^2}{n}}}$$

is a noncentral Student random variable with  $n$  degrees of freedom and noncentrality parameter  $ncp$ ,  $nc_t(n, ncp)$ .

To make use of this function, write first `load(distrib)`.

**pdf\_chi2** ( $x, n$ ) Function

Returns the value at  $x$  of the density function of a Chi-square random variable  $Chi^2(n)$ , with  $n > 0$ .

The  $Chi^2(n)$  random variable is equivalent to the  $Gamma(n/2, 2)$ , therefore when Maxima has not enough information to get the result, a noun form based on the gamma density is returned.

```
(%i1) load (distrib)$
(%i2) pdf_chi2(x,n);
```

$$\frac{x^{\frac{n}{2}-1} e^{-x/2}}{2^{\frac{n}{2}} \Gamma(\frac{n}{2})}$$

```
(%o4)
```

**cdf\_chi2** ( $x, n$ ) Function

Returns the value at  $x$  of the distribution function of a Chi-square random variable  $Chi^2(n)$ , with  $n > 0$ .

```
(%i1) load (distrib)$
(%i2) cdf_chi2(3,4);
```

$$1 - \frac{\Gamma(2, 3/2)}{\Gamma(2)}$$

```
(%i3) float(%);
(%o3) .4421745996289256
```

**quantile\_chi2** (*q,n*)

Function

Returns the  $q$ -quantile of a Chi-square random variable  $Chi^2(n)$ , with  $n > 0$ ; in other words, this is the inverse of `cdf_chi2`. Argument  $q$  must be an element of  $[0, 1]$ .

This function has no closed form and it is numerically computed if the global variable `numer` equals `true`, otherwise it returns a nominal expression based on the gamma quantile function, since the  $Chi^2(n)$  random variable is equivalent to the  $Gamma(n/2, 2)$ .

```
(%i1) load (distrib)$
(%i2) quantile_chi2(0.99,9);
(%o2) 21.66599433346194
(%i3) quantile_chi2(0.99,n);

(%o3) quantile_gamma(0.99, - , 2)
 n
 2
```

**mean\_chi2** (*n*)

Function

Returns the mean of a Chi-square random variable  $Chi^2(n)$ , with  $n > 0$ .

The  $Chi^2(n)$  random variable is equivalent to the  $Gamma(n/2, 2)$ , therefore when Maxima has not enough information to get the result, a noun form based on the gamma mean is returned.

```
(%i1) load (distrib)$
(%i2) mean_chi2(n);

(%o2) mean_gamma(- , 2)
 n
 2

(%i3) assume(n>0)$ mean_chi2(n);
(%o4) n
```

**var\_chi2** (*n*)

Function

Returns the variance of a Chi-square random variable  $Chi^2(n)$ , with  $n > 0$ .

The  $Chi^2(n)$  random variable is equivalent to the  $Gamma(n/2, 2)$ , therefore when Maxima has not enough information to get the result, a noun form based on the gamma variance is returned.

```
(%i1) load (distrib)$
(%i2) var_chi2(n);

(%o2) var_gamma(- , 2)
 n
 2

(%i3) assume(n>0)$ var_chi2(n);
(%o4) 2 n
```

**std\_chi2** (*n*)

Function

Returns the standard deviation of a Chi-square random variable  $Chi^2(n)$ , with  $n > 0$ .

The  $Chi^2(n)$  random variable is equivalent to the  $Gamma(n/2, 2)$ , therefore when Maxima has not enough information to get the result, a noun form based on the gamma standard deviation is returned.

```
(%i1) load (distrib)$
(%i2) std_chi2(n);

(%o2) std_gamma(- , 2)
 n
 2

(%i3) assume(n>0)$ std_chi2(n);
(%o4) sqrt(2) sqrt(n)
```

**skewness\_chi2** (*n*)

Function

Returns the skewness coefficient of a Chi-square random variable  $Chi^2(n)$ , with  $n > 0$ .

The  $Chi^2(n)$  random variable is equivalent to the  $Gamma(n/2, 2)$ , therefore when Maxima has not enough information to get the result, a noun form based on the gamma skewness coefficient is returned.

```
(%i1) load (distrib)$
(%i2) skewness_chi2(n);

(%o2) skewness_gamma(-, 2)
 n
 2

(%i3) assume(n>0)$ skewness_chi2(n);
 2 sqrt(2)
(%o4) -----
 sqrt(n)
```

### **kurtosis\_chi2** (*n*)

Function

Returns the kurtosis coefficient of a Chi-square random variable  $Chi^2(n)$ , with  $n > 0$ .

The  $Chi^2(n)$  random variable is equivalent to the  $Gamma(n/2, 2)$ , therefore when Maxima has not enough information to get the result, a noun form based on the gamma kurtosis coefficient is returned.

```
(%i1) load (distrib)$
(%i2) kurtosis_chi2(n);

(%o2) kurtosis_gamma(-, 2)
 n
 2

(%i3) assume(n>0)$ kurtosis_chi2(n);
 12
(%o4) --
 n
```

### **random\_chi2** (*n*)

Function

### **random\_chi2** (*n,m*)

Function

Returns a Chi-square random variate  $Chi^2(n)$ , with  $n > 0$ . Calling **random\_chi2** with a second argument *m*, a random sample of size *m* will be simulated.

The simulation is based on the Ahrens-Cheng algorithm. See **random\_gamma** for details.

To make use of this function, write first **load(distrib)**.

### **pdf\_noncentral\_chi2** (*x,n,ncp*)

Function

Returns the value at *x* of the density function of a noncentral Chi-square random variable  $ncChi^2(n, ncp)$ , with  $n > 0$  and noncentrality parameter  $ncp \geq 0$ . To make use of this function, write first **load(distrib)**.

### **cdf\_noncentral\_chi2** (*x,n,ncp*)

Function

Returns the value at *x* of the distribution function of a noncentral Chi-square random variable  $ncChi^2(n, ncp)$ , with  $n > 0$  and noncentrality parameter  $ncp \geq 0$ . To make use of this function, write first **load(distrib)**.

### **quantile\_noncentral\_chi2** (*q,n,ncp*)

Function

Returns the *q*-quantile of a noncentral Chi-square random variable  $ncChi^2(n, ncp)$ , with  $n > 0$  and noncentrality parameter  $ncp \geq 0$ ; in other words, this is the inverse of **cdf\_noncentral\_chi2**. Argument *q* must be an element of  $[0, 1]$ .

This function has no closed form and it is numerically computed if the global variable **numer** equals **true**, otherwise it returns a nominal expression.

### **mean\_noncentral\_chi2** (*n,ncp*)

Function

Returns the mean of a noncentral Chi-square random variable  $ncChi^2(n, ncp)$ , with  $n > 0$  and noncentrality parameter  $ncp \geq 0$ .

**var\_noncentral\_chi2** ( $n, ncp$ ) Function  
 Returns the variance of a noncentral Chi-square random variable  $nc_Chi^2(n, ncp)$ , with  $n > 0$  and noncentrality parameter  $ncp \geq 0$ .

**std\_noncentral\_chi2** ( $n, ncp$ ) Function  
 Returns the standard deviation of a noncentral Chi-square random variable  $nc_Chi^2(n, ncp)$ , with  $n > 0$  and noncentrality parameter  $ncp \geq 0$ .

**skewness\_noncentral\_chi2** ( $n, ncp$ ) Function  
 Returns the skewness coefficient of a noncentral Chi-square random variable  $nc_Chi^2(n, ncp)$ , with  $n > 0$  and noncentrality parameter  $ncp \geq 0$ .

**kurtosis\_noncentral\_chi2** ( $n, ncp$ ) Function  
 Returns the kurtosis coefficient of a noncentral Chi-square random variable  $nc_Chi^2(n, ncp)$ , with  $n > 0$  and noncentrality parameter  $ncp \geq 0$ .

**random\_noncentral\_chi2** ( $n, ncp$ ) Function  
**random\_noncentral\_chi2** ( $n, ncp, m$ ) Function  
 Returns a noncentral Chi-square random variate  $nc_Chi^2(n, ncp)$ , with  $n > 0$  and noncentrality parameter  $ncp \geq 0$ . Calling **random\_noncentral\_chi2** with a third argument  $m$ , a random sample of size  $m$  will be simulated.  
 To make use of this function, write first **load(distrib)**.

**pdf\_f** ( $x, m, n$ ) Function  
 Returns the value at  $x$  of the density function of a F random variable  $F(m, n)$ , with  $m, n > 0$ . To make use of this function, write first **load(distrib)**.

**cdf\_f** ( $x, m, n$ ) Function  
 Returns the value at  $x$  of the distribution function of a F random variable  $F(m, n)$ , with  $m, n > 0$ .

```
(%i1) load (distrib)$
(%i2) cdf_f(2,3,9/4);

 9 3 3
(%o2) 1 - beta_incomplete_regularized(-, -, --)
 8 2 11

(%i3) float(%);
(%o3) 0.66756728179008
```

**quantile\_f** ( $q, m, n$ ) Function  
 Returns the  $q$ -quantile of a F random variable  $F(m, n)$ , with  $m, n > 0$ ; in other words, this is the inverse of **cdf\_f**. Argument  $q$  must be an element of  $[0, 1]$ .

This function has no closed form and it is numerically computed if the global variable **numer** equals **true**, otherwise it returns a nominal expression.

```
(%i1) load (distrib)$
(%i2) quantile_f(2/5,sqrt(3),5);
 2
(%o2) quantile_f(-, sqrt(3), 5)
 5

(%i3) %,numer;
(%o3) 0.518947838573693
```

**mean\_f** ( $m, n$ ) Function  
 Returns the mean of a F random variable  $F(m, n)$ , with  $m > 0, n > 2$ . To make use of this function, write first **load(distrib)**.

**var\_f** (*m,n*) Function  
 Returns the variance of a F random variable  $F(m,n)$ , with  $m > 0, n > 4$ . To make use of this function, write first `load(distrib)`.

**std\_f** (*m,n*) Function  
 Returns the standard deviation of a F random variable  $F(m,n)$ , with  $m > 0, n > 4$ . To make use of this function, write first `load(distrib)`.

**skewness\_f** (*m,n*) Function  
 Returns the skewness coefficient of a F random variable  $F(m,n)$ , with  $m > 0, n > 6$ . To make use of this function, write first `load(distrib)`.

**kurtosis\_f** (*m,n*) Function  
 Returns the kurtosis coefficient of a F random variable  $F(m,n)$ , with  $m > 0, n > 8$ . To make use of this function, write first `load(distrib)`.

**random\_f** (*m,n*) Function

**random\_f** (*m,n,k*) Function

Returns a F random variate  $F(m,n)$ , with  $m,n > 0$ . Calling `random_f` with a third argument *k*, a random sample of size *k* will be simulated.

The simulation algorithm is based on the fact that if *X* is a  $Chi^2(m)$  random variable and *Y* is a  $Chi^2(n)$  random variable, then

$$F = \frac{nX}{mY}$$

is a F random variable with *m* and *n* degrees of freedom,  $F(m,n)$ .

To make use of this function, write first `load(distrib)`.

**pdf\_exp** (*x,m*) Function

Returns the value at *x* of the density function of an *Exponential*(*m*) random variable, with  $m > 0$ .

The *Exponential*(*m*) random variable is equivalent to the *Weibull*(1, 1/*m*), therefore when Maxima has not enough information to get the result, a noun form based on the Weibull density is returned.

```
(%i1) load (distrib)$
(%i2) pdf_exp(x,m);

(%o2) 1
 pdf_weibull(x, 1, -)
 m

(%i3) assume(x>0,m>0)$ pdf_exp(x,m);
 - m x
(%o4) m %e
```

**cdf\_exp** (*x,m*) Function

Returns the value at *x* of the distribution function of an *Exponential*(*m*) random variable, with  $m > 0$ .

The *Exponential*(*m*) random variable is equivalent to the *Weibull*(1, 1/*m*), therefore when Maxima has not enough information to get the result, a noun form based on the Weibull distribution is returned.

```
(%i1) load (distrib)$
(%i2) cdf_exp(x,m);

(%o2) 1
 cdf_weibull(x, 1, -)
 m

(%i3) assume(x>0,m>0)$ cdf_exp(x,m);
 - m x
(%o4) 1 - %e
```

**quantile\_exp** (*q,m*)

Function

Returns the  $q$ -quantile of an *Exponential*( $m$ ) random variable, with  $m > 0$ ; in other words, this is the inverse of **cdf\_exp**. Argument  $q$  must be an element of  $[0, 1]$ .

The *Exponential*( $m$ ) random variable is equivalent to the *Weibull*(1,  $1/m$ ), therefore when Maxima has not enough information to get the result, a noun form based on the Weibull quantile is returned.

```
(%i1) load (distrib)$
(%i2) quantile_exp(0.56,5);
(%o2) .1641961104139661
(%i3) quantile_exp(0.56,m);

(%o3) quantile_weibull(0.56, 1, -)
 1
 m
```

**mean\_exp** (*m*)

Function

Returns the mean of an *Exponential*( $m$ ) random variable, with  $m > 0$ .

The *Exponential*( $m$ ) random variable is equivalent to the *Weibull*(1,  $1/m$ ), therefore when Maxima has not enough information to get the result, a noun form based on the Weibull mean is returned.

```
(%i1) load (distrib)$
(%i2) mean_exp(m);

(%o2) mean_weibull(1, -)
 1
 m

(%i3) assume(m>0)$ mean_exp(m);
 1
(%o4) -
 m
```

**var\_exp** (*m*)

Function

Returns the variance of an *Exponential*( $m$ ) random variable, with  $m > 0$ .

The *Exponential*( $m$ ) random variable is equivalent to the *Weibull*(1,  $1/m$ ), therefore when Maxima has not enough information to get the result, a noun form based on the Weibull variance is returned.

```
(%i1) load (distrib)$
(%i2) var_exp(m);

(%o2) var_weibull(1, -)
 1
 m

(%i3) assume(m>0)$ var_exp(m);
 1
(%o4) --
 2
 m
```

**std\_exp** (*m*)

Function

Returns the standard deviation of an *Exponential*( $m$ ) random variable, with  $m > 0$ .

The *Exponential*( $m$ ) random variable is equivalent to the *Weibull*(1,  $1/m$ ), therefore when Maxima has not enough information to get the result, a noun form based on the Weibull standard deviation is returned.

```
(%i1) load (distrib)$
(%i2) std_exp(m);

(%o2) std_weibull(1, -)
 1
 m
```

```
(%i3) assume(m>0)$ std_exp(m);
 1
(%o4) -
 m
```

**skewness\_exp (m)**

Function

Returns the skewness coefficient of an *Exponential*( $m$ ) random variable, with  $m > 0$ .

The *Exponential*( $m$ ) random variable is equivalent to the *Weibull*(1,  $1/m$ ), therefore when Maxima has not enough information to get the result, a noun form based on the Weibull skewness coefficient is returned.

```
(%i1) load (distrib)$
(%i2) skewness_exp(m);
 1
(%o2) skewness_weibull(1, -)
 m
(%i3) assume(m>0)$ skewness_exp(m);
(%o4) 2
```

**kurtosis\_exp (m)**

Function

Returns the kurtosis coefficient of an *Exponential*( $m$ ) random variable, with  $m > 0$ .

The *Exponential*( $m$ ) random variable is equivalent to the *Weibull*(1,  $1/m$ ), therefore when Maxima has not enough information to get the result, a noun form based on the Weibull kurtosis coefficient is returned.

```
(%i1) load (distrib)$
(%i2) kurtosis_exp(m);
 1
(%o2) kurtosis_weibull(1, -)
 m
(%i3) assume(m>0)$ kurtosis_exp(m);
(%o4) 6
```

**random\_exp (m)**

Function

**random\_exp (m,k)**

Function

Returns an *Exponential*( $m$ ) random variate, with  $m > 0$ . Calling **random\_exp** with a second argument  $k$ , a random sample of size  $k$  will be simulated.

The simulation algorithm is based on the general inverse method.

To make use of this function, write first **load(distrib)**.

**pdf\_lognormal (x,m,s)**

Function

Returns the value at  $x$  of the density function of a *Lognormal*( $m, s$ ) random variable, with  $s > 0$ . To make use of this function, write first **load(distrib)**.

**cdf\_lognormal (x,m,s)**

Function

Returns the value at  $x$  of the distribution function of a *Lognormal*( $m, s$ ) random variable, with  $s > 0$ . This function is defined in terms of Maxima's built-in error function **erf**.

```
(%i1) load (distrib)$
(%i2) assume(x>0, s>0)$ cdf_lognormal(x,m,s);
 log(x) - m
 erf(-----)
 sqrt(2) s
(%o3) ----- + -
 2 2
```

See also **erf**.



**quantile\_lognormal** ( $q,m,s$ ) Function

Returns the  $q$ -quantile of a *Lognormal*( $m,s$ ) random variable, with  $s > 0$ ; in other words, this is the inverse of **cdf\_lognormal**. Argument  $q$  must be an element of  $[0,1]$ . To make use of this function, write first **load(distrib)**.

```
(%i1) load (distrib)$
(%i2) quantile_lognormal(95/100,0,1);
 sqrt(2) inverse_erf(9/10)
(%o2) %e
(%i3) float(%);
(%o3) 5.180251602233015
```

**mean\_lognormal** ( $m,s$ ) Function

Returns the mean of a *Lognormal*( $m,s$ ) random variable, with  $s > 0$ . To make use of this function, write first **load(distrib)**.

**var\_lognormal** ( $m,s$ ) Function

Returns the variance of a *Lognormal*( $m,s$ ) random variable, with  $s > 0$ . To make use of this function, write first **load(distrib)**.

**std\_lognormal** ( $m,s$ ) Function

Returns the standard deviation of a *Lognormal*( $m,s$ ) random variable, with  $s > 0$ . To make use of this function, write first **load(distrib)**.

**skewness\_lognormal** ( $m,s$ ) Function

Returns the skewness coefficient of a *Lognormal*( $m,s$ ) random variable, with  $s > 0$ . To make use of this function, write first **load(distrib)**.

**kurtosis\_lognormal** ( $m,s$ ) Function

Returns the kurtosis coefficient of a *Lognormal*( $m,s$ ) random variable, with  $s > 0$ . To make use of this function, write first **load(distrib)**.

**random\_lognormal** ( $m,s$ ) Function

**random\_lognormal** ( $m,s,n$ ) Function

Returns a *Lognormal*( $m,s$ ) random variate, with  $s > 0$ . Calling **random\_lognormal** with a third argument  $n$ , a random sample of size  $n$  will be simulated.

Log-normal variates are simulated by means of random normal variates. See **random\_normal** for details.

To make use of this function, write first **load(distrib)**.

**pdf\_gamma** ( $x,a,b$ ) Function

Returns the value at  $x$  of the density function of a *Gamma*( $a,b$ ) random variable, with  $a,b > 0$ . To make use of this function, write first **load(distrib)**.

**cdf\_gamma** ( $x,a,b$ ) Function

Returns the value at  $x$  of the distribution function of a *Gamma*( $a,b$ ) random variable, with  $a,b > 0$ .

```
(%i1) load (distrib)$
(%i2) cdf_gamma(3,5,21);
 1
(%o2) 1 - gamma_incomplete_regularized(5, -)
 7
(%i3) float(%);
(%o3) 4.402663157376807E-7
```

**quantile\_gamma** ( $q,a,b$ ) Function  
 Returns the  $q$ -quantile of a  $\text{Gamma}(a,b)$  random variable, with  $a,b > 0$ ; in other words, this is the inverse of **cdf\_gamma**. Argument  $q$  must be an element of  $[0,1]$ . To make use of this function, write first **load(distrib)**.

**mean\_gamma** ( $a,b$ ) Function  
 Returns the mean of a  $\text{Gamma}(a,b)$  random variable, with  $a,b > 0$ . To make use of this function, write first **load(distrib)**.

**var\_gamma** ( $a,b$ ) Function  
 Returns the variance of a  $\text{Gamma}(a,b)$  random variable, with  $a,b > 0$ . To make use of this function, write first **load(distrib)**.

**std\_gamma** ( $a,b$ ) Function  
 Returns the standard deviation of a  $\text{Gamma}(a,b)$  random variable, with  $a,b > 0$ . To make use of this function, write first **load(distrib)**.

**skewness\_gamma** ( $a,b$ ) Function  
 Returns the skewness coefficient of a  $\text{Gamma}(a,b)$  random variable, with  $a,b > 0$ . To make use of this function, write first **load(distrib)**.

**kurtosis\_gamma** ( $a,b$ ) Function  
 Returns the kurtosis coefficient of a  $\text{Gamma}(a,b)$  random variable, with  $a,b > 0$ . To make use of this function, write first **load(distrib)**.

**random\_gamma** ( $a,b$ ) Function  
**random\_gamma** ( $a,b,n$ ) Function

Returns a  $\text{Gamma}(a,b)$  random variate, with  $a,b > 0$ . Calling **random\_gamma** with a third argument  $n$ , a random sample of size  $n$  will be simulated.

The implemented algorithm is a combination of two procedures, depending on the value of parameter  $a$ :

For  $a \geq 1$ , Cheng, R.C.H. and Feast, G.M. (1979). *Some simple gamma variate generators*. Appl. Stat., 28, 3, 290-295.

For  $0 < a < 1$ , Ahrens, J.H. and Dieter, U. (1974). *Computer methods for sampling from gamma, beta, poisson and binomial cdf.tributions*. Computing, 12, 223-246.

To make use of this function, write first **load(distrib)**.

**pdf\_beta** ( $x,a,b$ ) Function  
 Returns the value at  $x$  of the density function of a  $\text{Beta}(a,b)$  random variable, with  $a,b > 0$ . To make use of this function, write first **load(distrib)**.

**cdf\_beta** ( $x,a,b$ ) Function  
 Returns the value at  $x$  of the distribution function of a  $\text{Beta}(a,b)$  random variable, with  $a,b > 0$ .

```
(%i1) load (distrib)$
(%i2) cdf_beta(1/3,15,2);

 11

 14348907

(%o2)

(%i3) float(%);
(%o3) 7.666089131388195E-7
```

**quantile\_beta** ( $q,a,b$ ) Function  
 Returns the  $q$ -quantile of a  $\text{Beta}(a,b)$  random variable, with  $a,b > 0$ ; in other words, this is the inverse of **cdf\_beta**. Argument  $q$  must be an element of  $[0,1]$ . To make use of this function, write first **load(distrib)**.

- mean\_beta** ( $a,b$ ) Function  
Returns the mean of a  $Beta(a,b)$  random variable, with  $a,b > 0$ . To make use of this function, write first `load(distrib)`.
- var\_beta** ( $a,b$ ) Function  
Returns the variance of a  $Beta(a,b)$  random variable, with  $a,b > 0$ . To make use of this function, write first `load(distrib)`.
- std\_beta** ( $a,b$ ) Function  
Returns the standard deviation of a  $Beta(a,b)$  random variable, with  $a,b > 0$ . To make use of this function, write first `load(distrib)`.
- skewness\_beta** ( $a,b$ ) Function  
Returns the skewness coefficient of a  $Beta(a,b)$  random variable, with  $a,b > 0$ . To make use of this function, write first `load(distrib)`.
- kurtosis\_beta** ( $a,b$ ) Function  
Returns the kurtosis coefficient of a  $Beta(a,b)$  random variable, with  $a,b > 0$ . To make use of this function, write first `load(distrib)`.
- random\_beta** ( $a,b$ ) Function  
**random\_beta** ( $a,b,n$ ) Function  
Returns a  $Beta(a,b)$  random variate, with  $a,b > 0$ . Calling `random_beta` with a third argument  $n$ , a random sample of size  $n$  will be simulated.  
The implemented algorithm is defined in Cheng, R.C.H. (1978). *Generating Beta Variates with Nonintegral Shape Parameters*. Communications of the ACM, 21:317-322  
To make use of this function, write first `load(distrib)`.
- pdf\_continuous\_uniform** ( $x,a,b$ ) Function  
Returns the value at  $x$  of the density function of a  $ContinuousUniform(a,b)$  random variable, with  $a < b$ . To make use of this function, write first `load(distrib)`.
- cdf\_continuous\_uniform** ( $x,a,b$ ) Function  
Returns the value at  $x$  of the distribution function of a  $ContinuousUniform(a,b)$  random variable, with  $a < b$ . To make use of this function, write first `load(distrib)`.
- quantile\_continuous\_uniform** ( $q,a,b$ ) Function  
Returns the  $q$ -quantile of a  $ContinuousUniform(a,b)$  random variable, with  $a < b$ ; in other words, this is the inverse of `cdf_continuous_uniform`. Argument  $q$  must be an element of  $[0, 1]$ . To make use of this function, write first `load(distrib)`.
- mean\_continuous\_uniform** ( $a,b$ ) Function  
Returns the mean of a  $ContinuousUniform(a,b)$  random variable, with  $a < b$ . To make use of this function, write first `load(distrib)`.
- var\_continuous\_uniform** ( $a,b$ ) Function  
Returns the variance of a  $ContinuousUniform(a,b)$  random variable, with  $a < b$ . To make use of this function, write first `load(distrib)`.
- std\_continuous\_uniform** ( $a,b$ ) Function  
Returns the standard deviation of a  $ContinuousUniform(a,b)$  random variable, with  $a < b$ . To make use of this function, write first `load(distrib)`.
- skewness\_continuous\_uniform** ( $a,b$ ) Function  
Returns the skewness coefficient of a  $ContinuousUniform(a,b)$  random variable, with  $a < b$ . To make use of this function, write first `load(distrib)`.

- kurtosis\_continuous\_uniform** ( $a, b$ ) Function  
 Returns the kurtosis coefficient of a *ContinuousUniform*( $a, b$ ) random variable, with  $a < b$ . To make use of this function, write first `load(distrib)`.
- random\_continuous\_uniform** ( $a, b$ ) Function  
**random\_continuous\_uniform** ( $a, b, n$ ) Function  
 Returns a *ContinuousUniform*( $a, b$ ) random variate, with  $a < b$ . Calling `random_continuous_uniform` with a third argument  $n$ , a random sample of size  $n$  will be simulated.  
 This is a direct application of the `random` built-in Maxima function.  
 See also `random`. To make use of this function, write first `load(distrib)`.
- pdf\_logistic** ( $x, a, b$ ) Function  
 Returns the value at  $x$  of the density function of a *Logistic*( $a, b$ ) random variable, with  $b > 0$ . To make use of this function, write first `load(distrib)`.
- cdf\_logistic** ( $x, a, b$ ) Function  
 Returns the value at  $x$  of the distribution function of a *Logistic*( $a, b$ ) random variable, with  $b > 0$ . To make use of this function, write first `load(distrib)`.
- quantile\_logistic** ( $q, a, b$ ) Function  
 Returns the  $q$ -quantile of a *Logistic*( $a, b$ ) random variable, with  $b > 0$ ; in other words, this is the inverse of `cdf_logistic`. Argument  $q$  must be an element of  $[0, 1]$ . To make use of this function, write first `load(distrib)`.
- mean\_logistic** ( $a, b$ ) Function  
 Returns the mean of a *Logistic*( $a, b$ ) random variable, with  $b > 0$ . To make use of this function, write first `load(distrib)`.
- var\_logistic** ( $a, b$ ) Function  
 Returns the variance of a *Logistic*( $a, b$ ) random variable, with  $b > 0$ . To make use of this function, write first `load(distrib)`.
- std\_logistic** ( $a, b$ ) Function  
 Returns the standard deviation of a *Logistic*( $a, b$ ) random variable, with  $b > 0$ . To make use of this function, write first `load(distrib)`.
- skewness\_logistic** ( $a, b$ ) Function  
 Returns the skewness coefficient of a *Logistic*( $a, b$ ) random variable, with  $b > 0$ . To make use of this function, write first `load(distrib)`.
- kurtosis\_logistic** ( $a, b$ ) Function  
 Returns the kurtosis coefficient of a *Logistic*( $a, b$ ) random variable, with  $b > 0$ . To make use of this function, write first `load(distrib)`.
- random\_logistic** ( $a, b$ ) Function  
**random\_logistic** ( $a, b, n$ ) Function  
 Returns a *Logistic*( $a, b$ ) random variate, with  $b > 0$ . Calling `random_logistic` with a third argument  $n$ , a random sample of size  $n$  will be simulated.  
 The implemented algorithm is based on the general inverse method.  
 To make use of this function, write first `load(distrib)`.
- pdf\_pareto** ( $x, a, b$ ) Function  
 Returns the value at  $x$  of the density function of a *Pareto*( $a, b$ ) random variable, with  $a, b > 0$ . To make use of this function, write first `load(distrib)`.

- cdf\_pareto** ( $x, a, b$ ) Function  
Returns the value at  $x$  of the distribution function of a *Pareto*( $a, b$ ) random variable, with  $a, b > 0$ . To make use of this function, write first `load(distrib)`.
- quantile\_pareto** ( $q, a, b$ ) Function  
Returns the  $q$ -quantile of a *Pareto*( $a, b$ ) random variable, with  $a, b > 0$ ; in other words, this is the inverse of `cdf_pareto`. Argument  $q$  must be an element of  $[0, 1]$ . To make use of this function, write first `load(distrib)`.
- mean\_pareto** ( $a, b$ ) Function  
Returns the mean of a *Pareto*( $a, b$ ) random variable, with  $a > 1, b > 0$ . To make use of this function, write first `load(distrib)`.
- var\_pareto** ( $a, b$ ) Function  
Returns the variance of a *Pareto*( $a, b$ ) random variable, with  $a > 2, b > 0$ . To make use of this function, write first `load(distrib)`.
- std\_pareto** ( $a, b$ ) Function  
Returns the standard deviation of a *Pareto*( $a, b$ ) random variable, with  $a > 2, b > 0$ . To make use of this function, write first `load(distrib)`.
- skewness\_pareto** ( $a, b$ ) Function  
Returns the skewness coefficient of a *Pareto*( $a, b$ ) random variable, with  $a > 3, b > 0$ . To make use of this function, write first `load(distrib)`.
- kurtosis\_pareto** ( $a, b$ ) Function  
Returns the kurtosis coefficient of a *Pareto*( $a, b$ ) random variable, with  $a > 4, b > 0$ . To make use of this function, write first `load(distrib)`.
- random\_pareto** ( $a, b$ ) Function  
**random\_pareto** ( $a, b, n$ ) Function  
Returns a *Pareto*( $a, b$ ) random variate, with  $a > 0, b > 0$ . Calling `random_pareto` with a third argument  $n$ , a random sample of size  $n$  will be simulated.  
The implemented algorithm is based on the general inverse method.  
To make use of this function, write first `load(distrib)`.
- pdf\_weibull** ( $x, a, b$ ) Function  
Returns the value at  $x$  of the density function of a *Weibull*( $a, b$ ) random variable, with  $a, b > 0$ . To make use of this function, write first `load(distrib)`.
- cdf\_weibull** ( $x, a, b$ ) Function  
Returns the value at  $x$  of the distribution function of a *Weibull*( $a, b$ ) random variable, with  $a, b > 0$ . To make use of this function, write first `load(distrib)`.
- quantile\_weibull** ( $q, a, b$ ) Function  
Returns the  $q$ -quantile of a *Weibull*( $a, b$ ) random variable, with  $a, b > 0$ ; in other words, this is the inverse of `cdf_weibull`. Argument  $q$  must be an element of  $[0, 1]$ . To make use of this function, write first `load(distrib)`.
- mean\_weibull** ( $a, b$ ) Function  
Returns the mean of a *Weibull*( $a, b$ ) random variable, with  $a, b > 0$ . To make use of this function, write first `load(distrib)`.
- var\_weibull** ( $a, b$ ) Function  
Returns the variance of a *Weibull*( $a, b$ ) random variable, with  $a, b > 0$ . To make use of this function, write first `load(distrib)`.

**std\_weibull** (*a,b*) Function  
 Returns the standard deviation of a *Weibull(a,b)* random variable, with  $a, b > 0$ . To make use of this function, write first `load(distrib)`.

**skewness\_weibull** (*a,b*) Function  
 Returns the skewness coefficient of a *Weibull(a,b)* random variable, with  $a, b > 0$ . To make use of this function, write first `load(distrib)`.

**kurtosis\_weibull** (*a,b*) Function  
 Returns the kurtosis coefficient of a *Weibull(a,b)* random variable, with  $a, b > 0$ . To make use of this function, write first `load(distrib)`.

**random\_weibull** (*a,b*) Function  
**random\_weibull** (*a,b,n*) Function  
 Returns a *Weibull(a,b)* random variate, with  $a, b > 0$ . Calling `random_weibull` with a third argument *n*, a random sample of size *n* will be simulated.  
 The implemented algorithm is based on the general inverse method.  
 To make use of this function, write first `load(distrib)`.

**pdf\_rayleigh** (*x,b*) Function  
 Returns the value at *x* of the density function of a *Rayleigh(b)* random variable, with  $b > 0$ .

The *Rayleigh(b)* random variable is equivalent to the *Weibull(2,1/b)*, therefore when Maxima has not enough information to get the result, a noun form based on the Weibull density is returned.

```
(%i1) load (distrib)$
(%i2) pdf_rayleigh(x,b);

(%o2) 1
 pdf_weibull(x, 2, -)
 b
(%i3) assume(x>0,b>0)$ pdf_rayleigh(x,b);
 2 2
 2 - b x
(%o4) 2 b x %e
```

**cdf\_rayleigh** (*x,b*) Function  
 Returns the value at *x* of the distribution function of a *Rayleigh(b)* random variable, with  $b > 0$ .

The *Rayleigh(b)* random variable is equivalent to the *Weibull(2,1/b)*, therefore when Maxima has not enough information to get the result, a noun form based on the Weibull distribution is returned.

```
(%i1) load (distrib)$
(%i2) cdf_rayleigh(x,b);

(%o2) 1
 cdf_weibull(x, 2, -)
 b
(%i3) assume(x>0,b>0)$ cdf_rayleigh(x,b);
 2 2
 - b x
(%o4) 1 - %e
```

**quantile\_rayleigh** (*q,b*) Function  
 Returns the *q*-quantile of a *Rayleigh(b)* random variable, with  $b > 0$ ; in other words, this is the inverse of `cdf_rayleigh`. Argument *q* must be an element of  $[0, 1]$ .  
 The *Rayleigh(b)* random variable is equivalent to the *Weibull(2,1/b)*, therefore when Maxima has not enough information to get the result, a noun form based on the Weibull quantile is returned.

```
(%i1) load (distrib)$
(%i2) quantile_rayleigh(0.99,b);

(%o2) quantile_weibull(0.99, 2, -)
 1
 b
(%i3) assume(x>0,b>0)$ quantile_rayleigh(0.99,b);
 2.145966026289347
(%o4) -----
 b
```

**mean\_rayleigh (b)**

Function

Returns the mean of a *Rayleigh(b)* random variable, with  $b > 0$ .

The *Rayleigh(b)* random variable is equivalent to the *Weibull(2,1/b)*, therefore when Maxima has not enough information to get the result, a noun form based on the Weibull mean is returned.

```
(%i1) load (distrib)$
(%i2) mean_rayleigh(b);

(%o2) mean_weibull(2, -)
 1
 b
(%i3) assume(b>0)$ mean_rayleigh(b);
 sqrt(%pi)
(%o4) -----
 2 b
```

**var\_rayleigh (b)**

Function

Returns the variance of a *Rayleigh(b)* random variable, with  $b > 0$ .

The *Rayleigh(b)* random variable is equivalent to the *Weibull(2,1/b)*, therefore when Maxima has not enough information to get the result, a noun form based on the Weibull variance is returned.

```
(%i1) load (distrib)$
(%i2) var_rayleigh(b);

(%o2) var_weibull(2, -)
 1
 b
(%i3) assume(b>0)$ var_rayleigh(b);
 %pi
 1 - ---
 4
(%o4) -----
 2
 b
```

**std\_rayleigh (b)**

Function

Returns the standard deviation of a *Rayleigh(b)* random variable, with  $b > 0$ .

The *Rayleigh(b)* random variable is equivalent to the *Weibull(2,1/b)*, therefore when Maxima has not enough information to get the result, a noun form based on the Weibull standard deviation is returned.

```
(%i1) load (distrib)$
(%i2) std_rayleigh(b);

(%o2) std_weibull(2, -)
 1
 b
(%i3) assume(b>0)$ std_rayleigh(b);
 %pi
```



$$\frac{\sqrt{1 - \frac{1}{4b}}}{b}$$

**skewness\_rayleigh (b)**

Function

Returns the skewness coefficient of a *Rayleigh(b)* random variable, with  $b > 0$ .

The *Rayleigh(b)* random variable is equivalent to the *Weibull(2,1/b)*, therefore when Maxima has not enough information to get the result, a noun form based on the Weibull skewness coefficient is returned.

```
(%i1) load (distrib)$
(%i2) skewness_rayleigh(b);
```

$$\frac{\sqrt{\pi}}{4} - \frac{3 \sqrt{\pi}}{4}$$

```
(%i3) assume(b>0)$ skewness_rayleigh(b);
```

$$\frac{\sqrt{\pi}^{3/2}}{(1 - \frac{1}{4b})^{3/2}}$$
**kurtosis\_rayleigh (b)**

Function

Returns the kurtosis coefficient of a *Rayleigh(b)* random variable, with  $b > 0$ .

The *Rayleigh(b)* random variable is equivalent to the *Weibull(2,1/b)*, therefore when Maxima has not enough information to get the result, a noun form based on the Weibull kurtosis coefficient is returned.

```
(%i1) load (distrib)$
(%i2) kurtosis_rayleigh(b);
```

$$\frac{3 \sqrt{\pi}}{2} - \frac{16}{\sqrt{\pi}^2}$$

```
(%i3) assume(b>0)$ kurtosis_rayleigh(b);
```

$$\frac{3 \sqrt{\pi}^2}{(1 - \frac{1}{4b})^2} - 3$$
**random\_rayleigh (b)**

Function

**random\_rayleigh (b,n)**

Function

Returns a *Rayleigh(b)* random variate, with  $b > 0$ . Calling **random\_rayleigh** with a second argument  $n$ , a random sample of size  $n$  will be simulated.

The implemented algorithm is based on the general inverse method.

To make use of this function, write first **load(distrib)**.

**pdf\_laplace (x,a,b)**

Function

Returns the value at  $x$  of the density function of a *Laplace(a,b)* random variable, with  $b > 0$ . To make use of this function, write first **load(distrib)**.



- cdf\_laplace** ( $x, a, b$ ) Function  
Returns the value at  $x$  of the distribution function of a *Laplace*( $a, b$ ) random variable, with  $b > 0$ . To make use of this function, write first `load(distrib)`.
- quantile\_laplace** ( $q, a, b$ ) Function  
Returns the  $q$ -quantile of a *Laplace*( $a, b$ ) random variable, with  $b > 0$ ; in other words, this is the inverse of `cdf_laplace`. Argument  $q$  must be an element of  $[0, 1]$ . To make use of this function, write first `load(distrib)`.
- mean\_laplace** ( $a, b$ ) Function  
Returns the mean of a *Laplace*( $a, b$ ) random variable, with  $b > 0$ . To make use of this function, write first `load(distrib)`.
- var\_laplace** ( $a, b$ ) Function  
Returns the variance of a *Laplace*( $a, b$ ) random variable, with  $b > 0$ . To make use of this function, write first `load(distrib)`.
- std\_laplace** ( $a, b$ ) Function  
Returns the standard deviation of a *Laplace*( $a, b$ ) random variable, with  $b > 0$ . To make use of this function, write first `load(distrib)`.
- skewness\_laplace** ( $a, b$ ) Function  
Returns the skewness coefficient of a *Laplace*( $a, b$ ) random variable, with  $b > 0$ . To make use of this function, write first `load(distrib)`.
- kurtosis\_laplace** ( $a, b$ ) Function  
Returns the kurtosis coefficient of a *Laplace*( $a, b$ ) random variable, with  $b > 0$ . To make use of this function, write first `load(distrib)`.
- random\_laplace** ( $a, b$ ) Function  
**random\_laplace** ( $a, b, n$ ) Function  
Returns a *Laplace*( $a, b$ ) random variate, with  $b > 0$ . Calling `random_laplace` with a third argument  $n$ , a random sample of size  $n$  will be simulated.  
The implemented algorithm is based on the general inverse method.  
To make use of this function, write first `load(distrib)`.
- pdf\_cauchy** ( $x, a, b$ ) Function  
Returns the value at  $x$  of the density function of a *Cauchy*( $a, b$ ) random variable, with  $b > 0$ . To make use of this function, write first `load(distrib)`.
- cdf\_cauchy** ( $x, a, b$ ) Function  
Returns the value at  $x$  of the distribution function of a *Cauchy*( $a, b$ ) random variable, with  $b > 0$ . To make use of this function, write first `load(distrib)`.
- quantile\_cauchy** ( $q, a, b$ ) Function  
Returns the  $q$ -quantile of a *Cauchy*( $a, b$ ) random variable, with  $b > 0$ ; in other words, this is the inverse of `cdf_cauchy`. Argument  $q$  must be an element of  $[0, 1]$ . To make use of this function, write first `load(distrib)`.
- random\_cauchy** ( $a, b$ ) Function  
**random\_cauchy** ( $a, b, n$ ) Function  
Returns a *Cauchy*( $a, b$ ) random variate, with  $b > 0$ . Calling `random_cauchy` with a third argument  $n$ , a random sample of size  $n$  will be simulated.  
The implemented algorithm is based on the general inverse method.  
To make use of this function, write first `load(distrib)`.

**pdf\_gumbel** ( $x, a, b$ ) Function  
 Returns the value at  $x$  of the density function of a *Gumbel*( $a, b$ ) random variable, with  $b > 0$ . To make use of this function, write first `load(distrib)`.

**cdf\_gumbel** ( $x, a, b$ ) Function  
 Returns the value at  $x$  of the distribution function of a *Gumbel*( $a, b$ ) random variable, with  $b > 0$ . To make use of this function, write first `load(distrib)`.

**quantile\_gumbel** ( $q, a, b$ ) Function  
 Returns the  $q$ -quantile of a *Gumbel*( $a, b$ ) random variable, with  $b > 0$ ; in other words, this is the inverse of `cdf_gumbel`. Argument  $q$  must be an element of  $[0, 1]$ . To make use of this function, write first `load(distrib)`.

**mean\_gumbel** ( $a, b$ ) Function  
 Returns the mean of a *Gumbel*( $a, b$ ) random variable, with  $b > 0$ .  

```
(%i1) load (distrib)$
(%i2) assume(b>0)$ mean_gumbel(a,b);
(%o3) %gamma b + a
```

 where symbol `%gamma` stands for the Euler-Mascheroni constant. See also `%gamma`.

**var\_gumbel** ( $a, b$ ) Function  
 Returns the variance of a *Gumbel*( $a, b$ ) random variable, with  $b > 0$ . To make use of this function, write first `load(distrib)`.

**std\_gumbel** ( $a, b$ ) Function  
 Returns the standard deviation of a *Gumbel*( $a, b$ ) random variable, with  $b > 0$ . To make use of this function, write first `load(distrib)`.

**skewness\_gumbel** ( $a, b$ ) Function  
 Returns the skewness coefficient of a *Gumbel*( $a, b$ ) random variable, with  $b > 0$ .  

```
(%i1) load (distrib)$
(%i2) assume(b>0)$ skewness_gumbel(a,b);
 12 sqrt(6) zeta(3)
(%o3) -----
 3
 %pi
(%i4) numer:true$ skewness_gumbel(a,b);
(%o5) 1.139547099404649
```

 where `zeta` stands for the Riemann's zeta function.

**kurtosis\_gumbel** ( $a, b$ ) Function  
 Returns the kurtosis coefficient of a *Gumbel*( $a, b$ ) random variable, with  $b > 0$ . To make use of this function, write first `load(distrib)`.

**random\_gumbel** ( $a, b$ ) Function  
**random\_gumbel** ( $a, b, n$ ) Function  
 Returns a *Gumbel*( $a, b$ ) random variate, with  $b > 0$ . Calling `random_gumbel` with a third argument  $n$ , a random sample of size  $n$  will be simulated.  
 The implemented algorithm is based on the general inverse method.  
 To make use of this function, write first `load(distrib)`.

### 47.3 Functions and Variables for discrete distributions

**pdf\_general\_finite\_discrete** (*x,v*) Function

Returns the value at *x* of the probability function of a general finite discrete random variable, with vector probabilities *v*, such that  $\Pr(X=i) = v_i$ . Vector *v* can be a list of nonnegative expressions, whose components will be normalized to get a vector of probabilities. To make use of this function, write first `load(distrib)`.

```
(%i1) load (distrib)$
(%i2) pdf_general_finite_discrete(2, [1/7, 4/7, 2/7]);
 4
(%o2) -
 7
(%i3) pdf_general_finite_discrete(2, [1, 4, 2]);
 4
(%o3) -
 7
```

**cdf\_general\_finite\_discrete** (*x,v*) Function

Returns the value at *x* of the distribution function of a general finite discrete random variable, with vector probabilities *v*.

See `pdf_general_finite_discrete` for more details.

```
(%i1) load (distrib)$
(%i2) cdf_general_finite_discrete(2, [1/7, 4/7, 2/7]);
 5
(%o2) -
 7
(%i3) cdf_general_finite_discrete(2, [1, 4, 2]);
 5
(%o3) -
 7
(%i4) cdf_general_finite_discrete(2+1/2, [1, 4, 2]);
 5
(%o4) -
 7
```

**quantile\_general\_finite\_discrete** (*q,v*) Function

Returns the *q*-quantile of a general finite discrete random variable, with vector probabilities *v*.

See `pdf_general_finite_discrete` for more details.

**mean\_general\_finite\_discrete** (*v*) Function

Returns the mean of a general finite discrete random variable, with vector probabilities *v*.

See `pdf_general_finite_discrete` for more details.

**var\_general\_finite\_discrete** (*v*) Function

Returns the variance of a general finite discrete random variable, with vector probabilities *v*.

See `pdf_general_finite_discrete` for more details.

**std\_general\_finite\_discrete** (*v*) Function

Returns the standard deviation of a general finite discrete random variable, with vector probabilities *v*.

See `pdf_general_finite_discrete` for more details.

**skewness\_general\_finite\_discrete** ( $v$ ) Function  
 Returns the skewness coefficient of a general finite discrete random variable, with vector probabilities  $v$ .

See `pdf_general_finite_discrete` for more details.

**kurtosis\_general\_finite\_discrete** ( $v$ ) Function  
 Returns the kurtosis coefficient of a general finite discrete random variable, with vector probabilities  $v$ .

See `pdf_general_finite_discrete` for more details.

**random\_general\_finite\_discrete** ( $v$ ) Function  
**random\_general\_finite\_discrete** ( $v, m$ ) Function

Returns a general finite discrete random variate, with vector probabilities  $v$ . Calling `random_general_finite_discrete` with a second argument  $m$ , a random sample of size  $m$  will be simulated.

See `pdf_general_finite_discrete` for more details.

```
(%i1) load (distrib)$
(%i2) random_general_finite_discrete([1,3,1,5]);
(%o2)
4
(%i3) random_general_finite_discrete([1,3,1,5], 10);
(%o3)
[4, 2, 2, 3, 2, 4, 4, 1, 2, 2]
```

**pdf\_binomial** ( $x, n, p$ ) Function  
 Returns the value at  $x$  of the probability function of a *Binomial*( $n, p$ ) random variable, with  $0 < p < 1$  and  $n$  a positive integer. To make use of this function, write first `load(distrib)`. 4 (%o6) - 7

**cdf\_binomial** ( $x, n, p$ ) Function  
 Returns the value at  $x$  of the distribution function of a *Binomial*( $n, p$ ) random variable, with  $0 < p < 1$  and  $n$  a positive integer.

```
(%i1) load (distrib)$
(%i2) cdf_binomial(5,7,1/6);
(%o2)
7775

7776
(%i3) float(%);
(%o3)
.9998713991769548
```

**quantile\_binomial** ( $q, n, p$ ) Function  
 Returns the  $q$ -quantile of a *Binomial*( $n, p$ ) random variable, with  $0 < p < 1$  and  $n$  a positive integer; in other words, this is the inverse of `cdf_binomial`. Argument  $q$  must be an element of  $[0, 1]$ . To make use of this function, write first `load(distrib)`.

**mean\_binomial** ( $n, p$ ) Function  
 Returns the mean of a *Binomial*( $n, p$ ) random variable, with  $0 < p < 1$  and  $n$  a positive integer. To make use of this function, write first `load(distrib)`.

**var\_binomial** ( $n, p$ ) Function  
 Returns the variance of a *Binomial*( $n, p$ ) random variable, with  $0 < p < 1$  and  $n$  a positive integer. To make use of this function, write first `load(distrib)`.

**std\_binomial** ( $n, p$ ) Function  
 Returns the standard deviation of a *Binomial*( $n, p$ ) random variable, with  $0 < p < 1$  and  $n$  a positive integer. To make use of this function, write first `load(distrib)`.

**skewness\_binomial** ( $n,p$ ) Function  
 Returns the skewness coefficient of a *Binomial*( $n,p$ ) random variable, with  $0 < p < 1$  and  $n$  a positive integer. To make use of this function, write first `load(distrib)`.

**kurtosis\_binomial** ( $n,p$ ) Function  
 Returns the kurtosis coefficient of a *Binomial*( $n,p$ ) random variable, with  $0 < p < 1$  and  $n$  a positive integer. To make use of this function, write first `load(distrib)`.

**random\_binomial** ( $n,p$ ) Function  
**random\_binomial** ( $n,p,m$ ) Function  
 Returns a *Binomial*( $n,p$ ) random variate, with  $0 < p < 1$  and  $n$  a positive integer. Calling `random_binomial` with a third argument  $m$ , a random sample of size  $m$  will be simulated. The implemented algorithm is based on the one described in Kachitvichyanukul, V. and Schmeiser, B.W. (1988) *Binomial Random Variate Generation*. Communications of the ACM, 31, Feb., 216.  
 To make use of this function, write first `load(distrib)`.

**pdf\_poisson** ( $x,m$ ) Function  
 Returns the value at  $x$  of the probability function of a *Poisson*( $m$ ) random variable, with  $m > 0$ . To make use of this function, write first `load(distrib)`.

**cdf\_poisson** ( $x,m$ ) Function  
 Returns the value at  $x$  of the distribution function of a *Poisson*( $m$ ) random variable, with  $m > 0$ .  

```
(%i1) load (distrib)$
(%i2) cdf_poisson(3,5);
(%o2) gamma_incomplete_regularized(4, 5)
(%i3) float(%);
(%o3) .2650259152973623
```

**quantile\_poisson** ( $q,m$ ) Function  
 Returns the  $q$ -quantile of a *Poisson*( $m$ ) random variable, with  $m > 0$ ; in other words, this is the inverse of `cdf_poisson`. Argument  $q$  must be an element of  $[0, 1]$ . To make use of this function, write first `load(distrib)`.

**mean\_poisson** ( $m$ ) Function  
 Returns the mean of a *Poisson*( $m$ ) random variable, with  $m > 0$ . To make use of this function, write first `load(distrib)`.

**var\_poisson** ( $m$ ) Function  
 Returns the variance of a *Poisson*( $m$ ) random variable, with  $m > 0$ . To make use of this function, write first `load(distrib)`.

**std\_poisson** ( $m$ ) Function  
 Returns the standard deviation of a *Poisson*( $m$ ) random variable, with  $m > 0$ . To make use of this function, write first `load(distrib)`.

**skewness\_poisson** ( $m$ ) Function  
 Returns the skewness coefficient of a *Poisson*( $m$ ) random variable, with  $m > 0$ . To make use of this function, write first `load(distrib)`.

**kurtosis\_poisson** ( $m$ ) Function  
 Returns the kurtosis coefficient of a Poisson random variable *Poi*( $m$ ), with  $m > 0$ . To make use of this function, write first `load(distrib)`.

**random\_poisson** ( $m$ ) Function  
**random\_poisson** ( $m, n$ ) Function

Returns a *Poisson*( $m$ ) random variate, with  $m > 0$ . Calling **random\_poisson** with a second argument  $n$ , a random sample of size  $n$  will be simulated.

The implemented algorithm is the one described in Ahrens, J.H. and Dieter, U. (1982) *Computer Generation of Poisson Deviates From Modified Normal Distributions*. ACM Trans. Math. Software, 8, 2, June, 163-179.

To make use of this function, write first **load(distrib)**.

**pdf\_bernoulli** ( $x, p$ ) Function

Returns the value at  $x$  of the probability function of a *Bernoulli*( $p$ ) random variable, with  $0 < p < 1$ .

The *Bernoulli*( $p$ ) random variable is equivalent to the *Binomial*(1,  $p$ ), therefore when Maxima has not enough information to get the result, a noun form based on the binomial probability function is returned.

```
(%i1) load (distrib)$
(%i2) pdf_bernoulli(1,p);
(%o2) pdf_binomial(1, 1, p)
(%i3) assume(0<p,p<1)$ pdf_bernoulli(1,p);
(%o4) p
```

**cdf\_bernoulli** ( $x, p$ ) Function

Returns the value at  $x$  of the distribution function of a *Bernoulli*( $p$ ) random variable, with  $0 < p < 1$ . To make use of this function, write first **load(distrib)**.

**quantile\_bernoulli** ( $q, p$ ) Function

Returns the  $q$ -quantile of a *Bernoulli*( $p$ ) random variable, with  $0 < p < 1$ ; in other words, this is the inverse of **cdf\_bernoulli**. Argument  $q$  must be an element of  $[0, 1]$ . To make use of this function, write first **load(distrib)**.

**mean\_bernoulli** ( $p$ ) Function

Returns the mean of a *Bernoulli*( $p$ ) random variable, with  $0 < p < 1$ .

The *Bernoulli*( $p$ ) random variable is equivalent to the *Binomial*(1,  $p$ ), therefore when Maxima has not enough information to get the result, a noun form based on the binomial mean is returned.

```
(%i1) load (distrib)$
(%i2) mean_bernoulli(p);
(%o2) mean_binomial(1, p)
(%i3) assume(0<p,p<1)$ mean_bernoulli(p);
(%o4) p
```

**var\_bernoulli** ( $p$ ) Function

Returns the variance of a *Bernoulli*( $p$ ) random variable, with  $0 < p < 1$ .

The *Bernoulli*( $p$ ) random variable is equivalent to the *Binomial*(1,  $p$ ), therefore when Maxima has not enough information to get the result, a noun form based on the binomial variance is returned.

```
(%i1) load (distrib)$
(%i2) var_bernoulli(p);
(%o2) var_binomial(1, p)
(%i3) assume(0<p,p<1)$ var_bernoulli(p);
(%o4) (1 - p) p
```

**std\_bernoulli** ( $p$ ) Function

Returns the standard deviation of a *Bernoulli*( $p$ ) random variable, with  $0 < p < 1$ .

The *Bernoulli*( $p$ ) random variable is equivalent to the *Binomial*(1,  $p$ ), therefore when Maxima has not enough information to get the result, a noun form based on the binomial standard deviation is returned.

```
(%i1) load (distrib)$
(%i2) std_bernoulli(p);
(%o2) std_binomial(1, p)
(%i3) assume(0<p,p<1)$ std_bernoulli(p);
(%o4) sqrt(1 - p) sqrt(p)
```

**skewness\_bernoulli (p)**

Function

Returns the skewness coefficient of a *Bernoulli*( $p$ ) random variable, with  $0 < p < 1$ .

The *Bernoulli*( $p$ ) random variable is equivalent to the *Binomial*(1, $p$ ), therefore when Maxima has not enough information to get the result, a noun form based on the binomial skewness coefficient is returned.

```
(%i1) load (distrib)$
(%i2) skewness_bernoulli(p);
(%o2) skewness_binomial(1, p)
(%i3) assume(0<p,p<1)$ skewness_bernoulli(p);
(%o4) 1 - 2 p

 sqrt(1 - p) sqrt(p)
```

**kurtosis\_bernoulli (p)**

Function

Returns the kurtosis coefficient of a *Bernoulli*( $p$ ) random variable, with  $0 < p < 1$ .

The *Bernoulli*( $p$ ) random variable is equivalent to the *Binomial*(1, $p$ ), therefore when Maxima has not enough information to get the result, a noun form based on the binomial kurtosis coefficient is returned.

```
(%i1) load (distrib)$
(%i2) kurtosis_bernoulli(p);
(%o2) kurtosis_binomial(1, p)
(%i3) assume(0<p,p<1)$ kurtosis_bernoulli(p);
(%o4) 1 - 6 (1 - p) p

 (1 - p) p
```

**random\_bernoulli (p)**

Function

**random\_bernoulli (p,n)**

Function

Returns a *Bernoulli*( $p$ ) random variate, with  $0 < p < 1$ . Calling **random\_bernoulli** with a second argument  $n$ , a random sample of size  $n$  will be simulated.

This is a direct application of the **random** built-in Maxima function.

See also **random**. To make use of this function, write first **load(distrib)**.

**pdf\_geometric (x,p)**

Function

Returns the value at  $x$  of the probability function of a *Geometric*( $p$ ) random variable, with  $0 < p < 1$ . To make use of this function, write first **load(distrib)**.

**cdf\_geometric (x,p)**

Function

Returns the value at  $x$  of the distribution function of a *Geometric*( $p$ ) random variable, with  $0 < p < 1$ . To make use of this function, write first **load(distrib)**.

**quantile\_geometric (q,p)**

Function

Returns the  $q$ -quantile of a *Geometric*( $p$ ) random variable, with  $0 < p < 1$ ; in other words, this is the inverse of **cdf\_geometric**. Argument  $q$  must be an element of  $[0, 1]$ . To make use of this function, write first **load(distrib)**.

**mean\_geometric (p)**

Function

Returns the mean of a *Geometric*( $p$ ) random variable, with  $0 < p < 1$ . To make use of this function, write first **load(distrib)**.



- var\_geometric** ( $p$ ) Function  
 Returns the variance of a *Geometric*( $p$ ) random variable, with  $0 < p < 1$ . To make use of this function, write first `load(distrib)`.
- std\_geometric** ( $p$ ) Function  
 Returns the standard deviation of a *Geometric*( $p$ ) random variable, with  $0 < p < 1$ . To make use of this function, write first `load(distrib)`.
- skewness\_geometric** ( $p$ ) Function  
 Returns the skewness coefficient of a *Geometric*( $p$ ) random variable, with  $0 < p < 1$ . To make use of this function, write first `load(distrib)`.
- kurtosis\_geometric** ( $p$ ) Function  
 Returns the kurtosis coefficient of a geometric random variable *Geo*( $p$ ), with  $0 < p < 1$ . To make use of this function, write first `load(distrib)`.
- random\_geometric** ( $p$ ) Function  
**random\_geometric** ( $p, n$ ) Function  
 Returns a *Geometric*( $p$ ) random variate, with  $0 < p < 1$ . Calling `random_geometric` with a second argument  $n$ , a random sample of size  $n$  will be simulated.  
 The algorithm is based on simulation of Bernoulli trials.  
 To make use of this function, write first `load(distrib)`.
- pdf\_discrete\_uniform** ( $x, n$ ) Function  
 Returns the value at  $x$  of the probability function of a *DiscreteUniform*( $n$ ) random variable, with  $n$  a strictly positive integer. To make use of this function, write first `load(distrib)`.
- cdf\_discrete\_uniform** ( $x, n$ ) Function  
 Returns the value at  $x$  of the distribution function of a *DiscreteUniform*( $n$ ) random variable, with  $n$  a strictly positive integer. To make use of this function, write first `load(distrib)`.
- quantile\_discrete\_uniform** ( $q, n$ ) Function  
 Returns the  $q$ -quantile of a *DiscreteUniform*( $n$ ) random variable, with  $n$  a strictly positive integer; in other words, this is the inverse of `cdf_discrete_uniform`. Argument  $q$  must be an element of  $[0, 1]$ . To make use of this function, write first `load(distrib)`.
- mean\_discrete\_uniform** ( $n$ ) Function  
 Returns the mean of a *DiscreteUniform*( $n$ ) random variable, with  $n$  a strictly positive integer. To make use of this function, write first `load(distrib)`.
- var\_discrete\_uniform** ( $n$ ) Function  
 Returns the variance of a *DiscreteUniform*( $n$ ) random variable, with  $n$  a strictly positive integer. To make use of this function, write first `load(distrib)`.
- std\_discrete\_uniform** ( $n$ ) Function  
 Returns the standard deviation of a *DiscreteUniform*( $n$ ) random variable, with  $n$  a strictly positive integer. To make use of this function, write first `load(distrib)`.
- skewness\_discrete\_uniform** ( $n$ ) Function  
 Returns the skewness coefficient of a *DiscreteUniform*( $n$ ) random variable, with  $n$  a strictly positive integer. To make use of this function, write first `load(distrib)`.
- kurtosis\_discrete\_uniform** ( $n$ ) Function  
 Returns the kurtosis coefficient of a *DiscreteUniform*( $n$ ) random variable, with  $n$  a strictly positive integer. To make use of this function, write first `load(distrib)`.



**random\_discrete\_uniform** ( $n$ ) Function  
**random\_discrete\_uniform** ( $n, m$ ) Function

Returns a *DiscreteUniform*( $n$ ) random variate, with  $n$  a strictly positive integer. Calling **random\_discrete\_uniform** with a second argument  $m$ , a random sample of size  $m$  will be simulated.

This is a direct application of the **random** built-in Maxima function.

See also **random**. To make use of this function, write first **load(distrib)**.

**pdf\_hypergeometric** ( $x, n1, n2, n$ ) Function

Returns the value at  $x$  of the probability function of a *Hypergeometric*( $n1, n2, n$ ) random variable, with  $n1$ ,  $n2$  and  $n$  non negative integers and  $n \leq n1 + n2$ . Being  $n1$  the number of objects of class A,  $n2$  the number of objects of class B, and  $n$  the size of the sample without replacement, this function returns the probability of event "exactly  $x$  objects are of class A".

To make use of this function, write first **load(distrib)**.

**cdf\_hypergeometric** ( $x, n1, n2, n$ ) Function

Returns the value at  $x$  of the distribution function of a *Hypergeometric*( $n1, n2, n$ ) random variable, with  $n1$ ,  $n2$  and  $n$  non negative integers and  $n \leq n1 + n2$ . See **pdf\_hypergeometric** for a more complete description.

To make use of this function, write first **load(distrib)**.

**quantile\_hypergeometric** ( $q, n1, n2, n$ ) Function

Returns the  $q$ -quantile of a *Hypergeometric*( $n1, n2, n$ ) random variable, with  $n1$ ,  $n2$  and  $n$  non negative integers and  $n \leq n1 + n2$ ; in other words, this is the inverse of **cdf\_hypergeometric**. Argument  $q$  must be an element of  $[0, 1]$ . To make use of this function, write first **load(distrib)**.

**mean\_hypergeometric** ( $n1, n2, n$ ) Function

Returns the mean of a discrete uniform random variable *Hyp*( $n1, n2, n$ ), with  $n1$ ,  $n2$  and  $n$  non negative integers and  $n \leq n1 + n2$ . To make use of this function, write first **load(distrib)**.

**var\_hypergeometric** ( $n1, n2, n$ ) Function

Returns the variance of a hypergeometric random variable *Hyp*( $n1, n2, n$ ), with  $n1$ ,  $n2$  and  $n$  non negative integers and  $n \leq n1 + n2$ . To make use of this function, write first **load(distrib)**.

**std\_hypergeometric** ( $n1, n2, n$ ) Function

Returns the standard deviation of a *Hypergeometric*( $n1, n2, n$ ) random variable, with  $n1$ ,  $n2$  and  $n$  non negative integers and  $n \leq n1 + n2$ . To make use of this function, write first **load(distrib)**.

**skewness\_hypergeometric** ( $n1, n2, n$ ) Function

Returns the skewness coefficient of a *Hypergeometric*( $n1, n2, n$ ) random variable, with  $n1$ ,  $n2$  and  $n$  non negative integers and  $n \leq n1 + n2$ . To make use of this function, write first **load(distrib)**.

**kurtosis\_hypergeometric** ( $n1, n2, n$ ) Function

Returns the kurtosis coefficient of a *Hypergeometric*( $n1, n2, n$ ) random variable, with  $n1$ ,  $n2$  and  $n$  non negative integers and  $n \leq n1 + n2$ . To make use of this function, write first **load(distrib)**.

**random\_hypergeometric** ( $n1, n2, n$ ) Function  
**random\_hypergeometric** ( $n1, n2, n, m$ ) Function

Returns a *Hypergeometric*( $n1, n2, n$ ) random variate, with  $n1$ ,  $n2$  and  $n$  non negative integers and  $n \leq n1 + n2$ . Calling **random\_hypergeometric** with a fourth argument  $m$ , a random sample of size  $m$  will be simulated.

Algorithm described in Kachitvichyanukul, V., Schmeiser, B.W. (1985) *Computer generation of hypergeometric random variates*. Journal of Statistical Computation and Simulation 22, 127-145.

To make use of this function, write first **load(distrib)**.

**pdf\_negative\_binomial** ( $x, n, p$ ) Function

Returns the value at  $x$  of the probability function of a *NegativeBinomial*( $n, p$ ) random variable, with  $0 < p < 1$  and  $n$  a positive number. To make use of this function, write first **load(distrib)**.

**cdf\_negative\_binomial** ( $x, n, p$ ) Function

Returns the value at  $x$  of the distribution function of a *NegativeBinomial*( $n, p$ ) random variable, with  $0 < p < 1$  and  $n$  a positive number.

```
(%i1) load (distrib)$
(%i2) cdf_negative_binomial(3,4,1/8);
 3271
(%o2) -----
 524288

(%i3) float(%);
(%o3) .006238937377929687
```

**quantile\_negative\_binomial** ( $q, n, p$ ) Function

Returns the  $q$ -quantile of a *NegativeBinomial*( $n, p$ ) random variable, with  $0 < p < 1$  and  $n$  a positive number; in other words, this is the inverse of **cdf\_negative\_binomial**. Argument  $q$  must be an element of  $[0, 1]$ . To make use of this function, write first **load(distrib)**.

**mean\_negative\_binomial** ( $n, p$ ) Function

Returns the mean of a *NegativeBinomial*( $n, p$ ) random variable, with  $0 < p < 1$  and  $n$  a positive number. To make use of this function, write first **load(distrib)**.

**var\_negative\_binomial** ( $n, p$ ) Function

Returns the variance of a *NegativeBinomial*( $n, p$ ) random variable, with  $0 < p < 1$  and  $n$  a positive number. To make use of this function, write first **load(distrib)**.

**std\_negative\_binomial** ( $n, p$ ) Function

Returns the standard deviation of a *NegativeBinomial*( $n, p$ ) random variable, with  $0 < p < 1$  and  $n$  a positive number. To make use of this function, write first **load(distrib)**.

**skewness\_negative\_binomial** ( $n, p$ ) Function

Returns the skewness coefficient of a *NegativeBinomial*( $n, p$ ) random variable, with  $0 < p < 1$  and  $n$  a positive number. To make use of this function, write first **load(distrib)**.

**kurtosis\_negative\_binomial** ( $n, p$ ) Function

Returns the kurtosis coefficient of a *NegativeBinomial*( $n, p$ ) random variable, with  $0 < p < 1$  and  $n$  a positive number. To make use of this function, write first **load(distrib)**.

**random\_negative\_binomial** ( $n, p$ ) Function

**random\_negative\_binomial** ( $n, p, m$ ) Function

Returns a *NegativeBinomial*( $n, p$ ) random variate, with  $0 < p < 1$  and  $n$  a positive number. Calling **random\_negative\_binomial** with a third argument  $m$ , a random sample of size  $m$  will be simulated.

Algorithm described in Devroye, L. (1986) *Non-Uniform Random Variate Generation*. Springer Verlag, p. 480.

To make use of this function, write first `load(distrib)`.



## 48 draw

### 48.1 Introduction to draw

**draw** is a Maxima-Gnuplot interface.

There are three main functions to be used at Maxima level: **draw2d**, **draw3d** and **draw**.

Follow this link for more elaborated examples of this package:

<http://riotorto.users.sourceforge.net/gnuplot>

You need Gnuplot 4.2 or newer to run this program.

### 48.2 Functions and Variables for draw

#### 48.2.1 Scenes

**gr2d** (*graphic option*, ..., *graphic object*, ...) Scene constructor

Function **gr2d** builds an object describing a 2D scene. Arguments are *graphic options*, *graphic objects*, or lists containing both graphic options and objects. This scene is interpreted sequentially: *graphic options* affect those *graphic objects* placed on its right. Some *graphic options* affect the global appearance of the scene.

This is the list of *graphic objects* available for scenes in two dimensions: **bars**, **ellipse**, **explicit**, **image**, **implicit**, **label**, **parametric**, **points**, **polar**, **polygon**, **quadrilateral**, **rectangle**, **triangle**, **vector**, and **geomap** (this one defined in package **worldmap**).

See also **draw** and **draw2d**.

To make use of this object, write first **load(draw)**.

**gr3d** (*graphic option*, ..., *graphic object*, ...) Scene constructor

Function **gr3d** builds an object describing a 3d scene. Arguments are *graphic options*, *graphic objects*, or lists containing both graphic options and objects. This scene is interpreted sequentially: *graphic options* affect those *graphic objects* placed on its right. Some *graphic options* affect the global appearance of the scene.

This is the list of *graphic objects* available for scenes in three dimensions: **cylindrical**, **elevation\_grid**, **explicit**, **implicit**, **label**, **mesh**, **parametric**, **parametric\_surface**, **points**, **quadrilateral**, **spherical**, **triangle**, **tube**, **vector**, and **geomap** (this one defined in package **worldmap**).

See also **draw** and **draw3d**.

To make use of this object, write first **load(draw)**.

#### 48.2.2 Functions

**draw** (*gr2d*, ..., *gr3d*, ..., *options*, ...) Function

Plots a series of scenes; its arguments are **gr2d** and/or **gr3d** objects, together with some options, or lists of scenes and options. By default, the scenes are put together in one column.

Function **draw** accepts the following global options: **terminal**, **columns**, **dimensions**, **file\_name** and **delay**.

Functions **draw2d** and **draw3d** are short cuts to be used when only one scene is required, in two or three dimensions, respectively.

See also **gr2d** and **gr3d**.

To make use of this function, write first **load(draw)**.

Example:

```
(%i1) load(draw)$
(%i2) scene1: gr2d(title="Ellipse",
 nticks=30,
 parametric(2*cos(t),5*sin(t),t,0,2*%pi))$
(%i3) scene2: gr2d(title="Triangle",
 polygon([4,5,7],[6,4,2]))$
(%i4) draw(scene1, scene2, columns = 2)$
```

The two draw sentences are equivalent:

```
(%i1) load(draw)$
(%i2) draw(gr3d(explicit(x^2+y^2,x,-1,1,y,-1,1)));
(%o2) [gr3d(explicit)]
(%i3) draw3d(explicit(x^2+y^2,x,-1,1,y,-1,1));
(%o3) [gr3d(explicit)]
```

An animated gif file:

```
(%i1) load(draw)$
(%i2) draw(
 delay = 100,
 file_name = "zzz",
 terminal = 'animated_gif,
 gr2d(explicit(x^2,x,-1,1)),
 gr2d(explicit(x^3,x,-1,1)),
 gr2d(explicit(x^4,x,-1,1)));
End of animation sequence
(%o2) [gr2d(explicit), gr2d(explicit), gr2d(explicit)]
```

See also `gr2d`, `gr3d`, `draw2d` and `draw3d`.

**draw2d** (*option*, *graphic\_object*, ...) Function

This function is a short cut for `draw(gr2d(options, ..., graphic_object, ...))`.

It can be used to plot a unique scene in 2d.

To make use of this function, write first `load(draw)`.

See also `draw` and `gr2d`.

**draw3d** (*option*, *graphic\_object*, ...) Function

This function is a short cut for `draw(gr3d(options, ..., graphic_object, ...))`.

It can be used to plot a unique scene in 3d.

To make use of this function, write first `load(draw)`.

See also `draw` and `gr3d`.

**draw\_file** (*graphic option*, ..., *graphic object*, ...) Function

Saves the current plot into a file. Accepted graphics options are: `terminal`, `dimensions`, `file_name` and `background_color`.

Example:

```
(%i1) load(draw)$
(%i2) /* screen plot */
 draw(gr3d(explicit(x^2+y^2,x,-1,1,y,-1,1)))$
(%i3) /* same plot in eps format */
 draw_file(terminal = eps,
 dimensions = [5,5]) $
```

**multiplot\_mode** (*term*) Function

This function enables Maxima to work in one-window multiplot mode with terminal *term*; accepted arguments for this function are `screen`, `wxt`, `aquaterm` and `none`.

When multiplot mode is enabled, each call to `draw` sends a new plot to the same window, without erasing the previous ones. To disable the multiplot mode, write `multiplot_mode(none)`.

When multiplot mode is enabled, global option `terminal` is blocked and you have to disable this working mode before changing to another terminal.

This feature does not work in Windows platforms.

Example:

```
(%i1) load(draw)$
(%i2) set_draw_defaults(
 xrange = [-1,1],
 yrange = [-1,1],
 grid = true,
 title = "Step by step plot")$
(%i3) multiplot_mode(screen)$
(%i4) draw2d(color=blue, explicit(x^2,x,-1,1))$
(%i5) draw2d(color=red, explicit(x^3,x,-1,1))$
(%i6) draw2d(color=brown, explicit(x^4,x,-1,1))$
(%i7) multiplot_mode(none)$
```

**set\_draw\_defaults** (*graphic option, ..., graphic object, ...*) Function

Sets user graphics options. This function is useful for plotting a sequence of graphics with common graphics options. Calling this function without arguments removes user defaults.

Example:

```
(%i1) load(draw)$
(%i2) set_draw_defaults(
 xrange = [-10,10],
 yrange = [-2, 2],
 color = blue,
 grid = true)$
(%i3) /* plot with user defaults */
 draw2d(explicit(((1+x)**2/(1+x*x))-1,x,-10,10))$
(%i4) set_draw_defaults()$
(%i5) /* plot with standard defaults */
 draw2d(explicit(((1+x)**2/(1+x*x))-1,x,-10,10))$
```

To make use of this function, write first `load(draw)`.

### 48.2.3 Graphics options

**adapt\_depth** Graphic option

Default value: 10

`adapt_depth` is the maximum number of splittings used by the adaptive plotting routine.

This option is relevant only for 2d `explicit` functions.

**allocation** Graphic option

Default value: `false`

With option `allocation` it is possible to place a scene in the output window at will; this is of interest in multiplots. When `false`, the scene is placed automatically, depending on the value assigned to option `columns`. In any other case, `allocation` must be set to a list of two pairs of numbers; the first corresponds to the position of the lower left corner of the scene, and the second pair gives the width and height of the plot. All quantities must be given in relative coordinates, between 0 and 1.

Examples:

In site graphics.

```
(%i1) load(draw)$
(%i2) draw(
 gr2d(
 explicit(x^2,x,-1,1)),
```

```

gr2d(
 allocation = [[1/4, 1/4],[1/2, 1/2]],
 explicit(x^3,x,-1,1),
 grid = true)) $

```

Multiplot with selected dimensions.

```

(%i1) load(draw)$
(%i2) draw(
 terminal = wxt,
 gr2d(
 allocation = [[0, 0],[1, 1/4]],
 explicit(x^2,x,-1,1)),
 gr3d(
 allocation = [[0, 1/4],[1, 3/4]],
 explicit(x^2+y^2,x,-1,1,y,-1,1)))$

```

See also option `columns`.

### **axis\_3d**

Graphic option

Default value: `true`

If `axis_3d` is `true`, the  $x$ ,  $y$  and  $z$  axis are shown in 3d scenes.

Since this is a global graphics option, its position in the scene description does not matter.

Example:

```

(%i1) load(draw)$
(%i2) draw3d(axis_3d = false,
 explicit(sin(x^2+y^2),x,-2,2,y,-2,2))$

```

See also `axis_bottom`, `axis_left`, `axis_top`, and `axis_right` for axis in 2d.

### **axis\_bottom**

Graphic option

Default value: `true`

If `axis_bottom` is `true`, the bottom axis is shown in 2d scenes.

Since this is a global graphics option, its position in the scene description does not matter.

Example:

```

(%i1) load(draw)$
(%i2) draw2d(axis_bottom = false,
 explicit(x^3,x,-1,1))$

```

See also `axis_left`, `axis_top`, `axis_right`, and `axis_3d`.

### **axis\_left**

Graphic option

Default value: `true`

If `axis_left` is `true`, the left axis is shown in 2d scenes.

Since this is a global graphics option, its position in the scene description does not matter.

Example:

```

(%i1) load(draw)$
(%i2) draw2d(axis_left = false,
 explicit(x^3,x,-1,1))$

```

See also `axis_bottom`, `axis_top`, `axis_right`, and `axis_3d`.

### **axis\_right**

Graphic option

Default value: `true`

If `axis_right` is `true`, the right axis is shown in 2d scenes.

Since this is a global graphics option, its position in the scene description does not matter.

Example:



```
(%i1) load(draw)$
(%i2) draw2d(axis_right = false,
 explicit(x^3,x,-1,1))$
```

See also `axis_bottom`, `axis_left`, `axis_top`, and `axis_3d`.

### **axis\_top**

Graphic option

Default value: `true`

If `axis_top` is `true`, the top axis is shown in 2d scenes.

Since this is a global graphics option, its position in the scene description does not matter.

Example:

```
(%i1) load(draw)$
(%i2) draw2d(axis_top = false,
 explicit(x^3,x,-1,1))$
```

See also `axis_bottom`, `axis_left`, `axis_right`, and `axis_3d`.

### **background\_color**

Graphic option

Default value: `white`

Sets the background color for terminals. Default background color is white.

Since this is a global graphics option, its position in the scene description does not matter.

See also `color`.

### **border**

Graphic option

Default value: `true`

If `border` is `true`, borders of polygons are painted according to `line_type` and `line_width`.

This option affects the following graphic objects:

- `gr2d`: polygon, rectangle, and ellipse.

Example:

```
(%i1) load(draw)$
(%i2) draw2d(color = brown,
 line_width = 8,
 polygon([[3,2],[7,2],[5,5]]),
 border = false,
 fill_color = blue,
 polygon([[5,2],[9,2],[7,5]]))$
```

### **cbrange**

Graphic option

Default value: `auto`

If `cbrange` is `auto`, the range for the values which are colored when `enhanced3d` is not `false` is computed automatically. Values outside of the color range use color of the nearest extreme.

When `enhanced3d` or `colorbox` is `false`, option `cbrange` has no effect.

If the user wants a specific interval for the colored values, it must be given as a Maxima list, as in `cbrange=[-2, 3]`.

Since this is a global graphics option, its position in the scene description does not matter.

Example:

```
(%i1) load(draw)$
(%i2) draw3d (
 enhanced3d = true,
 color = green,
 cbrange = [-3,10],
 explicit(x^2+y^2, x,-2,2,y,-2,2)) $
```

See also `enhanced3d`, `colorbox` and `cbtics`.

**cbtics**

Graphic option

Default value: `auto`

This graphic option controls the way tic marks are drawn on the colorbox when option `enhanced3d` is not false.

When `enhanced3d` or `colorbox` is false, option `cbtics` has no effect.

See `xtics` for a complete description.

Example :

```
(%i1) load(draw)$
(%i2) draw3d (
 enhanced3d = true,
 color = green,
 cbtics = {["High",10],["Medium",05],["Low",0]},
 cbrange = [0, 10],
 explicit(x^2+y^2, x,-2,2,y,-2,2)) $
```

See also `enhanced3d`, `colorbox` and `cbrange`.

**color**

Graphic option

Default value: `blue`

`color` specifies the color for plotting lines, points, borders of polygons and labels.

Colors can be given as names or in hexadecimal *rgb* code.

Available color names are:

|                 |                 |                |              |
|-----------------|-----------------|----------------|--------------|
| white           | black           | gray0          | grey0        |
| gray10          | grey10          | gray20         | grey20       |
| gray30          | grey30          | gray40         | grey40       |
| gray50          | grey50          | gray60         | grey60       |
| gray70          | grey70          | gray80         | grey80       |
| gray90          | grey90          | gray100        | grey100      |
| gray            | grey            | light_gray     | light_grey   |
| dark_gray       | dark_grey       | red            | light_red    |
| dark_red        | yellow          | light_yellow   | dark_yellow  |
| green           | light_green     | dark_green     | spring_green |
| forest_green    | sea_green       | blue           | light_blue   |
| dark_blue       | midnight_blue   | navy           | medium_blue  |
| royalblue       | skyblue         | cyan           | light_cyan   |
| dark_cyan       | magenta         | light_magenta  | dark_magenta |
| turquoise       | light_turquoise | dark_turquoise | pink         |
| light_pink      | dark_pink       | coral          | light_coral  |
| orange_red      | salmon          | light_salmon   | dark_salmon  |
| aquamarine      | khaki           | dark_khaki     | goldenrod    |
| light_goldenrod | dark_goldenrod  | gold           | beige        |
| brown           | orange          | dark_orange    | violet       |
| dark_violet     | plum            | purple         |              |

Chromatic components in hexadecimal code are introduced in the form `"#rrggbb"`.

Example:

```
(%i1) load(draw)$
(%i2) draw2d(explicit(x^2,x,-1,1), /* default is black */
 color = red,
 explicit(0.5 + x^2,x,-1,1),
 color = blue,
 explicit(1 + x^2,x,-1,1),
 color = light_blue,
 explicit(1.5 + x^2,x,-1,1),
 color = "#23ab0f",
```

```
label(["This is a label",0,1.2]))$
```

See also `fill_color`.

## colorbox

Graphic option

Default value: `true`

If `colorbox` is `true`, a color scale without label is drawn together with `image` 2D objects, or coloured 3D objects. If `colorbox` is `false`, no color scale is shown. If `colorbox` is a string, a color scale with label is drawn.

Since this is a global graphics option, its position in the scene description does not matter.

Example:

Color scale and images.

```
(%i1) load(draw)$
(%i2) im: apply('matrix,
 makelist(makelist(random(200),i,1,30),i,1,30))$
(%i3) draw2d(image(im,0,0,30,30))$
(%i4) draw2d(colorbox = false, image(im,0,0,30,30))$
```

Color scale and 3D coloured object.

```
(%i1) load(draw)$
(%i2) draw3d(
 colorbox = "Magnitude",
 enhanced3d = true,
 explicit(x^2+y^2,x,-1,1,y,-1,1))$
```

See also `palette`.

## columns

Graphic option

Default value: 1

`columns` is the number of columns in multiple plots.

Since this is a global graphics option, its position in the scene description does not matter.

It can be also used as an argument of function `draw`.

Example:

```
(%i1) load(draw)$
(%i2) scene1: gr2d(title="Ellipse",
 nticks=30,
 parametric(2*cos(t),5*sin(t),t,0,2*%pi))$
(%i3) scene2: gr2d(title="Triangle",
 polygon([4,5,7],[6,4,2]))$
(%i4) draw(scene1, scene2, columns = 2)$
```

## contour

Graphic option

Default value: `none`

Option `contour` enables the user to select where to plot contour lines. Possible values are:

- `none`: no contour lines are plotted.
- `base`: contour lines are projected on the xy plane.
- `surface`: contour lines are plotted on the surface.
- `both`: two contour lines are plotted: on the xy plane and on the surface.
- `map`: contour lines are projected on the xy plane, and the view point is set just in the vertical.

Since this is a global graphics option, its position in the scene description does not matter.

Example:

```
(%i1) load(draw)$
(%i2) draw3d(explicit(20*exp(-x^2-y^2)-10,x,0,2,y,-3,3),
 contour_levels = 15,
 contour = both,
 surface_hide = true) $
```

**contour\_levels**

Graphic option

Default value: 5

This graphic option controls the way contours are drawn. `contour_levels` can be set to a positive integer number, a list of three numbers or an arbitrary set of numbers:

- When option `contour_levels` is bounded to positive integer  $n$ ,  $n$  contour lines will be drawn at equal intervals. By default, five equally spaced contours are plotted.
- When option `contour_levels` is bounded to a list of length three of the form `[lowest,s,highest]`, contour lines are plotted from `lowest` to `highest` in steps of `s`.
- When option `contour_levels` is bounded to a set of numbers of the form `{n1, n2, ...}`, contour lines are plotted at values `n1`, `n2`, ...

Since this is a global graphics option, its position in the scene description does not matter.

Examples:

Ten equally spaced contour lines. The actual number of levels can be adjusted to give simple labels.

```
(%i1) load(draw)$
(%i2) draw3d(color = green,
 explicit(20*exp(-x^2-y^2)-10,x,0,2,y,-3,3),
 contour_levels = 10,
 contour = both,
 surface_hide = true) $
```

From -8 to 8 in steps of 4.

```
(%i1) load(draw)$
(%i2) draw3d(color = green,
 explicit(20*exp(-x^2-y^2)-10,x,0,2,y,-3,3),
 contour_levels = [-8,4,8],
 contour = both,
 surface_hide = true) $
```

Isolines at levels -7, -6, 0.8 and 5.

```
(%i1) load(draw)$
(%i2) draw3d(color = green,
 explicit(20*exp(-x^2-y^2)-10,x,0,2,y,-3,3),
 contour_levels = {-7, -6, 0.8, 5},
 contour = both,
 surface_hide = true) $
```

See also `contour`.

**data\_file\_name**

Graphic option

Default value: "data.gnuplot"

This is the name of the file with the numeric data needed by Gnuplot to build the requested plot.

Since this is a global graphics option, its position in the scene description does not matter. It can be also used as an argument of function `draw`.

See example in `gnuplot_file_name`.

**delay**

Graphic option

Default value: 5

This is the delay in 1/100 seconds of frames in animated gif files.

Since this is a global graphics option, its position in the scene description does not matter. It can be also used as an argument of function `draw`.

Example:

```
(%i1) load(draw)$
(%i2) draw(
 delay = 100,
 file_name = "zzz",
 terminal = 'animated_gif,
 gr2d(explicit(x^2,x,-1,1)),
 gr2d(explicit(x^3,x,-1,1)),
 gr2d(explicit(x^4,x,-1,1)));
End of animation sequence
(%o2) [gr2d(explicit), gr2d(explicit), gr2d(explicit)]
```

Option `delay` is only active in animated gif's; it is ignored in any other case.

See also `terminal`, `dimensions`.

## dimensions

Graphic option

Default value: `[600,500]`

Dimensions of the output terminal. Its value is a list formed by the width and the height. The meaning of the two numbers depends on the terminal you are working with.

With terminals `gif`, `animated_gif`, `png`, `jpg`, `svg`, `screen`, `wxt`, and `aquaterm`, the integers represent the number of points in each direction. If they are not integers, they are rounded.

With terminals `eps`, `eps_color`, `pdf`, and `pdfcairo`, both numbers represent hundredths of cm, which means that, by default, pictures in these formats are 6 cm in width and 5 cm in height.

Since this is a global graphics option, its position in the scene description does not matter. It can be also used as an argument of function `draw`.

Examples:

Option `dimensions` applied to file output and to `wxt` canvas.

```
(%i1) load(draw)$
(%i2) draw2d(
 dimensions = [300,300],
 terminal = 'png,
 explicit(x^4,x,-1,1)) $
(%i3) draw2d(
 dimensions = [300,300],
 terminal = 'wxt,
 explicit(x^4,x,-1,1)) $
```

Option `dimensions` applied to `eps` output. We want an `eps` file with A4 portrait dimensions.

```
(%i1) load(draw)$
(%i2) A4portrait: 100*[21, 29.7]$
(%i3) draw3d(
 dimensions = A4portrait,
 terminal = 'eps,
 explicit(x^2-y^2,x,-2,2,y,-2,2)) $
```

## draw\_realpart

Graphic option

Default value: `true`

When `true`, functions to be drawn are considered as complex functions whose real part value should be plotted; when `false`, nothing will be plotted when the function does not give a real value.

This option affects objects `explicit` and `parametric` in 2D and 3D, and `parametric_surface`.

Example:

Option `draw_realpart` affects objects `explicit` and `parametric`.

```
(%i1) load(draw)$
(%i2) draw2d(
 draw_realpart = false,
 explicit(sqrt(x^2 - 4*x) - x, x, -1, 5),
 color = red,
 draw_realpart = true,
 parametric(x,sqrt(x^2 - 4*x) - x + 1, x, -1, 5));
```

## enhanced3d

Graphic option

Default value: none

If **enhanced3d** is **none**, surfaces are not colored in 3D plots. In order to get a colored surface, a list must be assigned to option **enhanced3d**, where the first element is an expression and the rest are the names of the variables or parameters used in that expression. A list such `[f(x,y,z), x, y, z]` means that point `[x,y,z]` of the surface is assigned number `f(x,y,z)`, which will be colored according to the actual **palette**. For those 3D graphic objects defined in terms of parameters, it is possible to define the color number in terms of the parameters, as in `[f(u), u]`, as in objects **parametric** and **tube**, or `[f(u,v), u, v]`, as in object **parametric\_surface**. While all 3D objects admit the model based on absolute coordinates, `[f(x,y,z), x, y, z]`, only two of them, namely **explicit** and **elevation\_grid**, accept also models defined on the `[x,y]` coordinates, `[f(x,y), x, y]`. 3D graphic object **implicit** accepts only the `[f(x,y,z), x, y, z]` model. Object **points** accepts also the `[f(x,y,z), x, y, z]` model, but when points have a chronological nature, model `[f(k), k]` is also valid, being `k` an ordering parameter.

When **enhanced3d** is assigned something different to **none**, options **color** and **surface\_hide** are ignored.

The names of the variables defined in the lists may be different to those used in the definitions of the graphic objects.

In order to maintain back compatibility, **enhanced3d = false** is equivalent to **enhanced3d = none**, and **enhanced3d = true** is equivalent to **enhanced3d = [z, x, y, z]**. If an expression is given to **enhanced3d**, its variables must be the same used in the surface definition. This is not necessary when using lists.

See option **palette** to learn how palettes are specified.

Examples:

**explicit** object with coloring defined by the `[f(x,y,z), x, y, z]` model.

```
(%i1) load(draw)$
(%i2) draw3d(
 enhanced3d = [x-z/10,x,y,z],
 palette = gray,
 explicit(20*exp(-x^2-y^2)-10,x,-3,3,y,-3,3))$
```

**explicit** object with coloring defined by the `[f(x,y), x, y]` model. The names of the variables defined in the lists may be different to those used in the definitions of the graphic objects; in this case, `r` corresponds to `x`, and `s` to `y`.

```
(%i1) load(draw)$
(%i2) draw3d(
 enhanced3d = [sin(r*s),r,s],
 explicit(20*exp(-x^2-y^2)-10,x,-3,3,y,-3,3))$
```

**parametric** object with coloring defined by the `[f(x,y,z), x, y, z]` model.

```
(%i1) load(draw)$
(%i2) draw3d(
 nticks = 100,
 line_width = 2,
 enhanced3d = [if y>= 0 then 1 else 0, x, y, z],
 parametric(sin(u)^2,cos(u),u,u,0,4*%pi)) $
```

**parametric** object with coloring defined by the `[f(u), u]` model. In this case, `(u-1)^2` is a shortcut for `[(u-1)^2,u]`.

```
(%i1) load(draw)$
(%i2) draw3d(
 nticks = 60,
 line_width = 3,
 enhanced3d = (u-1)^2,
 parametric(cos(5*u)^2,sin(7*u),u-2,u,0,2))$
```

elevation\_grid object with coloring defined by the  $[f(x,y), x, y]$  model.

```
(%i1) load(draw)$
(%i2) m: apply(
 matrix,
 makelist(makelist(cos(i^2/80-k/30),k,1,30),i,1,20)) $
(%i3) draw3d(
 enhanced3d = [cos(x*y*10),x,y],
 elevation_grid(m,-1,-1,2,2),
 xlabel = "x",
 ylabel = "y");
```

tube object with coloring defined by the  $[f(x,y,z), x, y, z]$  model.

```
(%i1) load(draw)$
(%i2) draw3d(
 enhanced3d = [cos(x-y),x,y,z],
 palette = gray,
 xu_grid = 50,
 tube(cos(a), a, 0, 1, a, 0, 4*%pi))$
```

tube object with coloring defined by the  $[f(u), u]$  model. Here, `enhanced3d = -a` would be the shortcut for `enhanced3d = [-foo,foo]`.

```
(%i1) load(draw)$
(%i2) draw3d(
 tube_extremes = [open, closed],
 palette = [26,15,-2],
 enhanced3d = [-foo, foo],
 tube(a, a, a^2, 1, a, -2, 2))$
```

implicit and points objects with coloring defined by the  $[f(x,y,z), x, y, z]$  model.

```
(%i1) load(draw)$
(%i2) draw3d(
 enhanced3d = [x-y,x,y,z],
 implicit((x^2+y^2+z^2-1)*(x^2+(y-1.5)^2+z^2-0.5)=0.015,
 x,-1,1,y,-1.2,2.3,z,-1,1)) $
(%i3) m: makelist([random(1.0),random(1.0),random(1.0)],k,1,2000)$
(%i4) draw3d(
 point_type = filled_circle,
 point_size = 2,
 enhanced3d = [u+v-w,u,v,w],
 points(m)) $
```

When points have a chronological nature, model  $[f(k), k]$  is also valid, being  $k$  an ordering parameter.

```
(%i1) load(draw)$
(%i2) m:makelist([random(1.0), random(1.0), random(1.0)],k,1,5)$
(%i3) draw3d(
 enhanced3d = [sin(j), j],
 point_size = 3,
 point_type = filled_circle,
 points_joined = true,
 points(m)) $
```

**error\_type**

Graphic option

Default value: `y`

Depending on its value, which can be `x`, `y`, or `xy`, graphic object `errors` will draw points with horizontal, vertical, or both, error bars. When `error_type=boxes`, boxes will be drawn instead of crosses.

See also `errors`.

**file\_name**

Graphic option

Default value: `"maxima_out"`

This is the name of the file where terminals `png`, `jpg`, `gif`, `eps`, `eps_color`, `pdf`, `pdfcairo` and `svg` will save the graphic.

Since this is a global graphics option, its position in the scene description does not matter. It can be also used as an argument of function `draw`.

Example:

```
(%i1) load(draw)$
(%i2) draw2d(file_name = "myfile",
 explicit(x^2,x,-1,1),
 terminal = 'png)$
```

See also `terminal`, `dimensions`.

**fill\_color**

Graphic option

Default value: `"red"`

`fill_color` specifies the color for filling polygons and 2d `explicit` functions.

See `color` to learn how colors are specified.

**fill\_density**

Graphic option

Default value: `0`

`fill_density` is a number between 0 and 1 that specifies the intensity of the `fill_color` in `bars` objects.

See `bars` for examples.

**filled\_func**

Graphic option

Default value: `false`

Option `filled_func` controls how regions limited by functions should be filled. When `filled_func` is `true`, the region bounded by the function defined with object `explicit` and the bottom of the graphic window is filled with `fill_color`. When `filled_func` contains a function expression, then the region bounded by this function and the function defined with object `explicit` will be filled. By default, `explicit` functions are not filled.

This option affects only the 2d graphic object `explicit`.

Example:

Region bounded by an `explicit` object and the bottom of the graphic window.

```
(%i1) load(draw)$
(%i2) draw2d(fill_color = red,
 filled_func = true,
 explicit(sin(x),x,0,10))$
```

Region bounded by an `explicit` object and the function defined by option `filled_func`. Note that the variable in `filled_func` must be the same as that used in `explicit`.

```
(%i1) load(draw)$
(%i2) draw2d(fill_color = grey,
 filled_func = sin(x),
 explicit(-sin(x),x,0,%pi));
```

See also `fill_color` and `explicit`.



**font**

Graphic option

Default value: "" (empty string)

This option can be used to set the font face to be used by the terminal. Only one font face and size can be used throughout the plot.

Since this is a global graphics option, its position in the scene description does not matter.

See also **font\_size**.

Gnuplot doesn't handle fonts by itself, it leaves this task to the support libraries of the different terminals, each one with its own philosophy about it. A brief summary follows:

- *x11*: Uses the normal x11 font server mechanism.

Example:

```
(%i1) load(draw)$
(%i2) draw2d(font = "Arial",
 font_size = 20,
 label(["Arial font, size 20",1,1]))$
```

- *windows*: The windows terminal doesn't support changing of fonts from inside the plot. Once the plot has been generated, the font can be changed right-clicking on the menu of the graph window.
- *png, jpeg, gif*: The *libgd* library uses the font path stored in the environment variable **GDFONTPATH**; in this case, it is only necessary to set option **font** to the font's name. It is also possible to give the complete path to the font file.

Examples:

Option **font** can be given the complete path to the font file:

```
(%i1) load(draw)$
(%i2) path: "/usr/share/fonts/truetype/freefont/" $
(%i3) file: "FreeSerifBoldItalic.ttf" $
(%i4) draw2d(
 font = concat(path, file),
 font_size = 20,
 color = red,
 label(["FreeSerifBoldItalic font, size 20",1,1]),
 terminal = png)$
```

If environment variable **GDFONTPATH** is set to the path where font files are allocated, it is possible to set graphic option **font** to the name of the font.

```
(%i1) load(draw)$
(%i2) draw2d(
 font = "FreeSerifBoldItalic",
 font_size = 20,
 color = red,
 label(["FreeSerifBoldItalic font, size 20",1,1]),
 terminal = png)$
```

- *Postscript*: Standard Postscript fonts are: "Times-Roman", "Times-Italic", "Times-Bold", "Times-BoldItalic", "Helvetica", "Helvetica-Oblique", "Helvetica-Bold", "Helvetica-BoldOblique", "Courier", "Courier-Oblique", "Courier-Bold", and "Courier-BoldOblique".

Example:

```
(%i1) load(draw)$
(%i2) draw2d(
 font = "Courier-Oblique",
 font_size = 15,
 label(["Courier-Oblique font, size 15",1,1]),
 terminal = eps)$
```

- *pdf*: Uses same fonts as *Postscript*.
- *pdfcairo*: Uses same fonts as *wxt*.

- *wxt*: The *pango* library finds fonts via the `fontconfig` utility.
- *aqua*: Default is "Times-Roman".

The gnuplot documentation is an important source of information about terminals and fonts.

### font\_size

Graphic option

Default value: 10

This option can be used to set the font size to be used by the terminal. Only one font face and size can be used throughout the plot. `font_size` is active only when option `font` is not equal to the empty string.

Since this is a global graphics option, its position in the scene description does not matter. See also `font`.

### gnuplot\_file\_name

Graphic option

Default value: "maxout.gnuplot"

This is the name of the file with the necessary commands to be processed by Gnuplot.

Since this is a global graphics option, its position in the scene description does not matter. It can be also used as an argument of function `draw`.

Example:

```
(%i1) load(draw)$
(%i2) draw2d(
 file_name = "my_file",
 gnuplot_file_name = "my_commands_for_gnuplot",
 data_file_name = "my_data_for_gnuplot",
 terminal = png,
 explicit(x^2,x,-1,1)) $
```

See also `data_file_name`.

### grid

Graphic option

Default value: `false`

If `grid` is `true`, a grid will be drawn on the *xy* plane.

Since this is a global graphics option, its position in the scene description does not matter.

Example:

```
(%i1) load(draw)$
(%i2) draw2d(grid= true,
 explicit(exp(u),u,-2,2))$
```

### head\_angle

Graphic option

Default value: 45

`head_angle` indicates the angle, in degrees, between the arrow heads and the segment.

This option is relevant only for `vector` objects.

Example:

```
(%i1) load(draw)$
(%i2) draw2d(xrange = [0,10],
 yrange = [0,9],
 head_length = 0.7,
 head_angle = 10,
 vector([1,1],[0,6]),
 head_angle = 20,
 vector([2,1],[0,6]),
 head_angle = 30,
 vector([3,1],[0,6]),
 head_angle = 40,
```

```

vector([4,1],[0,6]),
head_angle = 60,
vector([5,1],[0,6]),
head_angle = 90,
vector([6,1],[0,6]),
head_angle = 120,
vector([7,1],[0,6]),
head_angle = 160,
vector([8,1],[0,6]),
head_angle = 180,
vector([9,1],[0,6]))$

```

See also `head_both`, `head_length`, and `head_type`.

### **head\_both**

Graphic option

Default value: `false`

If `head_both` is `true`, vectors are plotted with two arrow heads. If `false`, only one arrow is plotted.

This option is relevant only for `vector` objects.

Example:

```

(%i1) load(draw)$
(%i2) draw2d(xrange = [0,8],
 yrange = [0,8],
 head_length = 0.7,
 vector([1,1],[6,0]),
 head_both = true,
 vector([1,7],[6,0]))$

```

See also `head_length`, `head_angle`, and `head_type`.

### **head\_length**

Graphic option

Default value: 2

`head_length` indicates, in x-axis units, the length of arrow heads.

This option is relevant only for `vector` objects.

Example:

```

(%i1) load(draw)$
(%i2) draw2d(xrange = [0,12],
 yrange = [0,8],
 vector([0,1],[5,5]),
 head_length = 1,
 vector([2,1],[5,5]),
 head_length = 0.5,
 vector([4,1],[5,5]),
 head_length = 0.25,
 vector([6,1],[5,5]))$

```

See also `head_both`, `head_angle`, and `head_type`.

### **head\_type**

Graphic option

Default value: `filled`

`head_type` is used to specify how arrow heads are plotted. Possible values are: `filled` (closed and filled arrow heads), `empty` (closed but not filled arrow heads), and `nofilled` (open arrow heads).

This option is relevant only for `vector` objects.

Example:

```
(%i1) load(draw)$
(%i2) draw2d(xrange = [0,12],
 yrange = [0,10],
 head_length = 1,
 vector([0,1],[5,5]), /* default type */
 head_type = 'empty,
 vector([3,1],[5,5]),
 head_type = 'nofilled,
 vector([6,1],[5,5]))$
```

See also `head_both`, `head_angle`, and `head_length`.

### **ip\_grid**

Graphic option

Default value: `[50, 50]`

`ip_grid` sets the grid for the first sampling in implicit plots.

This option is relevant only for `implicit` objects.

### **ip\_grid\_in**

Graphic option

Default value: `[5, 5]`

`ip_grid_in` sets the grid for the second sampling in implicit plots.

This option is relevant only for `implicit` objects.

### **key**

Graphic option

Default value: `""` (empty string)

`key` is the name of a function in the legend. If `key` is an empty string, no key is assigned to the function.

This option affects the following graphic objects:

- `gr2d`: `points`, `polygon`, `rectangle`, `ellipse`, `vector`, `explicit`, `implicit`, `parametric`, and `polar`.
- `gr3d`: `points`, `explicit`, `parametric`, and `parametric_surface`.

Example:

```
(%i1) load(draw)$
(%i2) draw2d(key = "Sinus",
 explicit(sin(x),x,0,10),
 key = "Cosinus",
 color = red,
 explicit(cos(x),x,0,10))$
```

### **label\_alignment**

Graphic option

Default value: `center`

`label_alignment` is used to specify where to write labels with respect to the given coordinates. Possible values are: `center`, `left`, and `right`.

This option is relevant only for `label` objects.

Example:

```
(%i1) load(draw)$
(%i2) draw2d(xrange = [0,10],
 yrange = [0,10],
 points_joined = true,
 points([[5,0],[5,10]]),
 color = blue,
 label(["Centered alignment (default)",5,2]),
 label_alignment = 'left,
 label(["Left alignment",5,5]),
 label_alignment = 'right,
 label(["Right alignment",5,8]))$
```

See also `label_orientation`, and `color`.

**label\_orientation**

Graphic option

Default value: `horizontal`

`label_orientation` is used to specify orientation of labels. Possible values are: `horizontal`, and `vertical`.

This option is relevant only for `label` objects.

Example:

In this example, a dummy point is added to get an image. Package `draw` needs always data to draw an scene.

```
(%i1) load(draw)$
(%i2) draw2d(xrange = [0,10],
 yrange = [0,10],
 point_size = 0,
 points([[5,5]]),
 color = navy,
 label(["Horizontal orientation (default)",5,2]),
 label_orientation = 'vertical,
 color = "#654321",
 label(["Vertical orientation",1,5]))$
```

See also `label_alignment` and `color`.

**line\_type**

Graphic option

Default value: `solid`

`line_type` indicates how lines are displayed; possible values are `solid` and `dots`.

This option affects the following graphic objects:

- `gr2d`: `points`, `polygon`, `rectangle`, `ellipse`, `vector`, `explicit`, `implicit`, `parametric` and `polar`.
- `gr3d`: `points`, `explicit`, `parametric` and `parametric_surface`.

Example:

```
(%i1) load(draw)$
(%i2) draw2d(line_type = dots,
 explicit(1 + x^2,x,-1,1),
 line_type = solid, /* default */
 explicit(2 + x^2,x,-1,1))$
```

See also `line_width`.

**line\_width**

Graphic option

Default value: `1`

`line_width` is the width of plotted lines. Its value must be a positive number.

This option affects the following graphic objects:

- `gr2d`: `points`, `polygon`, `rectangle`, `ellipse`, `vector`, `explicit`, `implicit`, `parametric` and `polar`.
- `gr3d`: `points` and `parametric`.

Example:

```
(%i1) load(draw)$
(%i2) draw2d(explicit(x^2,x,-1,1), /* default width */
 line_width = 5.5,
 explicit(1 + x^2,x,-1,1),
 line_width = 10,
 explicit(2 + x^2,x,-1,1))$
```

See also `line_type`.

**logcb**

Graphic option

Default value: `false`

If `logcb` is `true`, the ticks in the colorbox will be drawn in the logarithmic scale.

When `enhanced3d` or `colorbox` is `false`, option `logcb` has no effect.

Since this is a global graphics option, its position in the scene description does not matter.

Example:

```
(%i1) load(draw)$
(%i2) draw3d (
 enhanced3d = true,
 color = green,
 logcb = true,
 logz = true,
 palette = [-15,24,-9],
 explicit(exp(x^2-y^2), x,-2,2,y,-2,2)) $
```

See also `enhanced3d`, `colorbox` and `cbrange`.

**logx**

Graphic option

Default value: `false`

If `logx` is `true`, the  $x$  axis will be drawn in the logarithmic scale.

Since this is a global graphics option, its position in the scene description does not matter.

Example:

```
(%i1) load(draw)$
(%i2) draw2d(explicit(log(x),x,0.01,5),
 logx = true)$
```

See also `logy` and `logz`.

**logy**

Graphic option

Default value: `false`

If `logy` is `true`, the  $y$  axis will be drawn in the logarithmic scale.

Since this is a global graphics option, its position in the scene description does not matter.

Example:

```
(%i1) load(draw)$
(%i2) draw2d(logy = true,
 explicit(exp(x),x,0,5))$
```

See also `logx` and `logz`.

**logz**

Graphic option

Default value: `false`

If `logz` is `true`, the  $z$  axis will be drawn in the logarithmic scale.

Since this is a global graphics option, its position in the scene description does not matter.

Example:

```
(%i1) load(draw)$
(%i2) draw3d(logz = true,
 explicit(exp(u^2+v^2),u,-2,2,v,-2,2))$
```

See also `logx` and `logy`.

**nticks**

Graphic option

Default value: 29

In 2d, `nticks` gives the initial number of points used by the adaptive plotting routine for explicit objects. It is also the number of points that will be shown in parametric and polar curves.

This option affects the following graphic objects:

- `gr2d`: `ellipse`, `explicit`, `parametric` and `polar`.
- `gr3d`: `parametric`.

Example:

```
(%i1) load(draw)$
(%i2) draw2d(transparent = true,
 ellipse(0,0,4,2,0,180),
 nticks = 5,
 ellipse(0,0,4,2,180,180))$
```

## palette

Graphic option

Default value: `color`

`palette` indicates how to map gray levels onto color components. It works together with option `enhanced3d` in 3D graphics, who associates every point of a surfaces to a real number or gray level. It also works with gray images. With `palette`, levels are transformed into colors.

There are two ways for defining these transformations.

First, `palette` can be a vector of length three with components ranging from -36 to +36; each value is an index for a formula mapping the levels onto red, green and blue colors, respectively:

|                    |                |                               |
|--------------------|----------------|-------------------------------|
| 0: 0               | 1: 0.5         | 2: 1                          |
| 3: x               | 4: x^2         | 5: x^3                        |
| 6: x^4             | 7: sqrt(x)     | 8: sqrt(sqrt(x))              |
| 9: sin(90x)        | 10: cos(90x)   | 11:  x-0.5                    |
| 12: (2x-1)^2       | 13: sin(180x)  | 14:  cos(180x)                |
| 15: sin(360x)      | 16: cos(360x)  | 17:  sin(360x)                |
| 18:  cos(360x)     | 19:  sin(720x) | 20:  cos(720x)                |
| 21: 3x             | 22: 3x-1       | 23: 3x-2                      |
| 24:  3x-1          | 25:  3x-2      | 26: (3x-1)/2                  |
| 27: (3x-2)/2       | 28:  (3x-1)/2  | 29:  (3x-2)/2                 |
| 30: x/0.32-0.78125 | 31: 2*x-0.84   | 32: 4x;1;-2x+1.84;x/0.08-11.5 |
| 33:  2*x - 0.5     | 34: 2*x        | 35: 2*x - 0.5                 |
| 36: 2*x - 1        |                |                               |

negative numbers mean negative colour component. `palette = gray` and `palette = color` are short cuts for `palette = [3,3,3]` and `palette = [7,5,15]`, respectively.

Second, `palette` can be a user defined lookup table. In this case, the format for building a lookup table of length `n` is `palette=[color_1, color_2, ..., color_n]`, where `color_i` is a well formed color (see option `color`), such that `color_1` is assigned to the lowest gray level and `color_n` to the highest. The rest of colors are interpolated.

Since this is a global graphics option, its position in the scene description does not matter.

Examples:

It works together with option `enhanced3d` in 3D graphics.

```
(%i1) load(draw)$
(%i2) draw3d(
 enhanced3d = [z-x+2*y,x,y,z],
 palette = [32, -8, 17],
 explicit(20*exp(-x^2-y^2)-10,x,-3,3,y,-3,3))$
```

It also works with gray images.

```
(%i1) load(draw)$
(%i2) im: apply(
 'matrix,
 makelist(makelist(random(200),i,1,30),i,1,30))$
(%i3) /* palette = color, default */
 draw2d(image(im,0,0,30,30))$
(%i4) draw2d(palette = gray, image(im,0,0,30,30))$
```

```
(%i5) draw2d(palette = [15,20,-4],
 colorbox=false,
 image(im,0,0,30,30))$
```

`palette` can be a user defined lookup table. In this example, low values of  $x$  are colored in red, and higher values in yellow.

```
(%i1) load(draw)$
(%i2) draw3d(
 palette = [red, blue, yellow],
 enhanced3d = x,
 explicit(x^2+y^2,x,-1,1,y,-1,1)) $
```

See also `colorbox` and `enhanced3d`.

## point\_size

Graphic option

Default value: 1

`point_size` sets the size for plotted points. It must be a non negative number.

This option has no effect when graphic option `point_type` is set to `dot`.

This option affects the following graphic objects:

- `gr2d`: points.
- `gr3d`: points.

Example:

```
(%i1) load(draw)$
(%i2) draw2d(points(makelist([random(20),random(50)],k,1,10)),
 point_size = 5,
 points(makelist(k,k,1,20),makelist(random(30),k,1,20)))$
```

## point\_type

Graphic option

Default value: 1

`point_type` indicates how isolated points are displayed; the value of this option can be any integer index greater or equal than -1, or the name of a point style: `$none` (-1), `dot` (0), `plus` (1), `multiply` (2), `asterisk` (3), `square` (4), `filled_square` (5), `circle` (6), `filled_circle` (7), `up_triangle` (8), `filled_up_triangle` (9), `down_triangle` (10), `filled_down_triangle` (11), `diamant` (12) and `filled_diamant` (13).

This option affects the following graphic objects:

- `gr2d`: points.
- `gr3d`: points.

Example:

```
(%i1) load(draw)$
(%i2) draw2d(xrange = [0,10],
 yrange = [0,10],
 point_size = 3,
 point_type = diamant,
 points([[1,1],[5,1],[9,1]]),
 point_type = filled_down_triangle,
 points([[1,2],[5,2],[9,2]]),
 point_type = asterisk,
 points([[1,3],[5,3],[9,3]]),
 point_type = filled_diamant,
 points([[1,4],[5,4],[9,4]]),
 point_type = 5,
 points([[1,5],[5,5],[9,5]]),
 point_type = 6,
 points([[1,6],[5,6],[9,6]]),
 point_type = filled_circle,
```



```

points([[1,7],[5,7],[9,7]]),
point_type = 8,
points([[1,8],[5,8],[9,8]]),
point_type = filled_diamant,
points([[1,9],[5,9],[9,9]]))$

```

### points\_joined

Graphic option

Default value: `false`

When `points_joined` is `true`, points are joined by lines; when `false`, isolated points are drawn. A third possible value for this graphic option is `impulses`; in such case, vertical segments are drawn from points to the x-axis (2D) or to the xy-plane (3D).

This option affects the following graphic objects:

- `gr2d: points.`
- `gr3d: points.`

Example:

```

(%i1) load(draw)$
(%i2) draw2d(xrange = [0,10],
 yrange = [0,4],
 point_size = 3,
 point_type = up_triangle,
 color = blue,
 points([[1,1],[5,1],[9,1]]),
 points_joined = true,
 point_type = square,
 line_type = dots,
 points([[1,2],[5,2],[9,2]]),
 point_type = circle,
 color = red,
 line_width = 7,
 points([[1,3],[5,3],[9,3]]))$

```

### proportional\_axes

Graphic option

Default value: `none`

When `proportional_axes` is equal to `xy` or `xyz`, a 2D or 3D scene will be drawn with axes proportional to their relative lengths.

Since this is a global graphics option, its position in the scene description does not matter.

This option works with Gnuplot version 4.2.6 or greater.

Examples:

Single 2D plot.

```

(%i1) load(draw)$
(%i2) draw2d(
 ellipse(0,0,1,1,0,360),
 transparent=true,
 color = blue,
 line_width = 4,
 ellipse(0,0,2,1/2,0,360),
 proportional_axes = xy) $

```

Multiplot.

```

(%i1) load(draw)$
(%i2) draw(
 terminal = wxt,
 gr2d(proportional_axes = xy,
 explicit(x^2,x,0,1)),
 gr2d(explicit(x^2,x,0,1),

```

```

xrange = [0,1],
yrange = [0,2],
proportional_axes=xy),
gr2d(explicit(x^2,x,0,1))

```

## surface\_hide

Graphic option

Default value: `false`

If `surface_hide` is `true`, hidden parts are not plotted in 3d surfaces.

Since this is a global graphics option, its position in the scene description does not matter.

Example:

```

(%i1) load(draw)$
(%i2) draw(columns=2,
 gr3d(explicit(exp(sin(x)+cos(x^2)),x,-3,3,y,-3,3)),
 gr3d(surface_hide = true,
 explicit(exp(sin(x)+cos(x^2)),x,-3,3,y,-3,3)))$

```

## terminal

Graphic option

Default value: `screen`

Selects the terminal to be used by Gnuplot; possible values are: `screen` (default), `png`, `pngcairo`, `jpg`, `gif`, `eps`, `eps_color`, `epslatex`, `epslatex_standalone`, `svg`, `dumb`, `dumb_file`, `pdf`, `pdfcairo`, `wxt`, `animated_gif`, `multipage_pdfcairo`, `multipage_pdf`, `multipage_eps`, `multipage_eps_color`, and `aquaterm`.

Terminals `screen`, `wxt` and `aquaterm` can be also defined as a list with two elements: the name of the terminal itself and a non negative integer number. In this form, multiple windows can be opened at the same time, each with its corresponding number. This feature does not work in Windows platforms.

Since this is a global graphics option, its position in the scene description does not matter. It can be also used as an argument of function `draw`.

N.B. `pdfcairo` requires Gnuplot 4.3 or newer. `pdf` requires Gnuplot to be compiled with the option `--enable-pdf` and `libpdf` must be installed. The pdf library is available from: <http://www.pdflib.com/en/download/pdflib-family/pdflib-lite/>

Examples:

```

(%i1) load(draw)$
(%i2) /* screen terminal (default) */
draw2d(explicit(x^2,x,-1,1))$
(%i3) /* png file */
draw2d(terminal = 'png,
 explicit(x^2,x,-1,1))$
(%i4) /* jpg file */
draw2d(terminal = 'jpg,
 dimensions = [300,300],
 explicit(x^2,x,-1,1))$
(%i5) /* eps file */
draw2d(file_name = "myfile",
 explicit(x^2,x,-1,1),
 terminal = 'eps)$
(%i6) /* pdf file */
draw2d(file_name = "mypdf",
 dimensions = 100*[12.0,8.0],
 explicit(x^2,x,-1,1),
 terminal = 'pdf)$
(%i7) /* wxwidgets window */
draw2d(explicit(x^2,x,-1,1),
 terminal = 'wxt)$

```

Multiple windows.

```
(%i1) load(draw)$
(%i2) draw2d(explicit(x^5,x,-2,2), terminal=[screen, 3])$
(%i3) draw2d(explicit(x^2,x,-2,2), terminal=[screen, 0])$
```

An animated gif file.

```
(%i1) load(draw)$
(%i2) draw(
 delay = 100,
 file_name = "zzz",
 terminal = 'animated_gif,
 gr2d(explicit(x^2,x,-1,1)),
 gr2d(explicit(x^3,x,-1,1)),
 gr2d(explicit(x^4,x,-1,1)));
End of animation sequence
(%o2) [gr2d(explicit), gr2d(explicit), gr2d(explicit)]
```

Option `delay` is only active in animated gif's; it is ignored in any other case.

Multipage output in eps format.

```
(%i1) load(draw)$
(%i2) draw(
 file_name = "parabol",
 terminal = multipage_eps,
 dimensions = 100*[10,10],
 gr2d(explicit(x^2,x,-1,1)),
 gr3d(explicit(x^2+y^2,x,-1,1,y,-1,1))) $
```

See also `file_name`, `dimensions` and `delay`.

## title

Graphic option

Default value: "" (empty string)

Option `title`, a string, is the main title for the scene. By default, no title is written.

Since this is a global graphics option, its position in the scene description does not matter.

Example:

```
(%i1) load(draw)$
(%i2) draw2d(explicit(exp(u),u,-2,2),
 title = "Exponential function")$
```

## transform

Graphic option

Default value: `none`

If `transform` is `none`, the space is not transformed and graphic objects are drawn as defined. When a space transformation is desired, a list must be assigned to option `transform`. In case of a 2D scene, the list takes the form `[f1(x,y), f2(x,y), x, y]`. In case of a 3D scene, the list is of the form `[f1(x,y,z), f2(x,y,z), f3(x,y,z), x, y, z]`.

The names of the variables defined in the lists may be different to those used in the definitions of the graphic objects.

Examples:

Rotation in 2D.

```
(%i1) load(draw)$
(%i2) th : %pi / 4$
(%i3) draw2d(
 color = "#e245f0",
 proportional_axes = 'xy,
 line_width = 8,
 triangle([3,2],[7,2],[5,5]),
 border = false,
 fill_color = yellow,
 transform = [cos(th)*x - sin(th)*y,
```

```

sin(th)*x + cos(th)*y, x, y],
triangle([3,2],[7,2],[5,5]))$

```

Translation in 3D.

```

(%i1) load(draw)$
(%i2) draw3d(
 color = "#a02c00",
 explicit(20*exp(-x^2-y^2)-10,x,-3,3,y,-3,3),
 transform = [x+10,y+10,z+10,x,y,z],
 color = blue,
 explicit(20*exp(-x^2-y^2)-10,x,-3,3,y,-3,3))$

```

## transparent

Graphic option

Default value: `false`

If `transparent` is `true`, interior regions of polygons are filled according to `fill_color`.

This option affects the following graphic objects:

- `gr2d`: `polygon`, `rectangle`, and `ellipse`.

Example:

```

(%i1) load(draw)$
(%i2) draw2d(polygon([[3,2],[7,2],[5,5]]),
 transparent = true,
 color = blue,
 polygon([[5,2],[9,2],[7,5]]))$

```

## tube\_extremes

Graphic option

Default value: `[open, open]`

A list with two possible elements, `open` and `closed`, indicating whether the extremes of a graphic object `tube` remain open or must be closed. By default, both extremes are left open.

Example:

```

(%i1) load(draw)$
(%i2) draw3d(
 tube_extremes = [open, closed],
 tube(0, 0, a, 1,
 a, 0, 8))$

```

## unit\_vectors

Graphic option

Default value: `false`

If `unit_vectors` is `true`, vectors are plotted with module 1. This is useful for plotting vector fields. If `unit_vectors` is `false`, vectors are plotted with its original length.

This option is relevant only for `vector` objects.

Example:

```

(%i1) load(draw)$
(%i2) draw2d(xrange = [-1,6],
 yrange = [-1,6],
 head_length = 0.1,
 vector([0,0],[5,2]),
 unit_vectors = true,
 color = red,
 vector([0,3],[5,2]))$

```

## user\_preamble

Graphic option

Default value: `""` (empty string)

Expert Gnuplot users can make use of this option to fine tune Gnuplot's behaviour by writing settings to be sent before the `plot` or `splot` command.

The value of this option must be a string or a list of strings (one per line).

Since this is a global graphics option, its position in the scene description does not matter.

Example:

The *dumb* terminal is not supported by package **draw**, but it is possible to set it by making use of option **user\_preamble**,

```
(%i1) load(draw)$
(%i2) draw2d(explicit(exp(x)-1,x,-1,1),
 parametric(cos(u),sin(u),u,0,2*%pi),
 user_preamble="set terminal dumb")$
```

## view

Graphic option

Default value: [60,30]

A pair of angles, measured in degrees, indicating the view direction in a 3D scene. The first angle is the vertical rotation around the x axis, in the range [0,360]. The second one is the horizontal rotation around the z axis, in the range [0,360].

Since this is a global graphics option, its position in the scene description does not matter.

Example:

```
(%i1) load(draw)$
(%i2) draw3d(view = [170, 360],
 explicit(sin(x^2+y^2),x,-2,2,y,-2,2))$
```

## wired\_surface

Graphic option

Default value: false

Indicates whether 3D surfaces in **enhanced3d** mode show the grid joining the points or not.

Since this is a global graphics option, its position in the scene description does not matter.

Example:

```
(%i1) load(draw)$
(%i2) draw3d(
 enhanced3d = [sin(x),x,y],
 wired_surface = true,
 explicit(x^2+y^2,x,-1,1,y,-1,1)) $
```

## x\_voxel

Graphic option

Default value: 10

**x\_voxel** is the number of voxels in the x direction to be used by the *marching cubes algorithm* implemented by the 3d **implicit** object. It is also used by graphic object **region**.

## xaxis

Graphic option

Default value: false

If **xaxis** is true, the x axis is drawn.

Since this is a global graphics option, its position in the scene description does not matter.

Example:

```
(%i1) load(draw)$
(%i2) draw2d(explicit(x^3,x,-1,1),
 xaxis = true,
 xaxis_color = blue)$
```

See also **xaxis\_width**, **xaxis\_type** and **xaxis\_color**.

**xaxis\_color**

Graphic option

Default value: "black"

**xaxis\_color** specifies the color for the x axis. See **color** to know how colors are defined.

Since this is a global graphics option, its position in the scene description does not matter.

Example:

```
(%i1) load(draw)$
(%i2) draw2d(explicit(x^3,x,-1,1),
 xaxis = true,
 xaxis_color = red)$
```

See also **xaxis**, **xaxis\_width** and **xaxis\_type**.**xaxis\_secondary**

Graphic option

Default value: false

If **xaxis\_secondary** is true, function values can be plotted with respect to the second x axis, which will be drawn on top of the scene.

Note that this is a local graphics option which only affects to 2d plots.

Example:

```
(%i1) load(draw)$
(%i2) draw2d(
 key = "Bottom x-axis",
 explicit(x+1,x,1,2),
 color = red,
 key = "Above x-axis",
 xticks_secondary = true,
 xaxis_secondary = true,
 explicit(x^2,x,-1,1)) $
```

See also **xrange\_secondary**, **xticks\_secondary**, **xticks\_rotate\_secondary**, **xticks\_axis\_secondary** and **xaxis\_secondary**.**xaxis\_type**

Graphic option

Default value: dots

**xaxis\_type** indicates how the x axis is displayed; possible values are **solid** and **dots**.

Since this is a global graphics option, its position in the scene description does not matter.

Example:

```
(%i1) load(draw)$
(%i2) draw2d(explicit(x^3,x,-1,1),
 xaxis = true,
 xaxis_type = solid)$
```

See also **xaxis**, **xaxis\_width** and **xaxis\_color**.**xaxis\_width**

Graphic option

Default value: 1

**xaxis\_width** is the width of the x axis. Its value must be a positive number.

Since this is a global graphics option, its position in the scene description does not matter.

Example:

```
(%i1) load(draw)$
(%i2) draw2d(explicit(x^3,x,-1,1),
 xaxis = true,
 xaxis_width = 3)$
```

See also **xaxis**, **xaxis\_type** and **xaxis\_color**.

**xlabel**

Graphic option

Default value: "" (empty string)

Option **xlabel**, a string, is the label for the x axis. By default, no label is written.

Since this is a global graphics option, its position in the scene description does not matter.

Example:

```
(%i1) load(draw)$
(%i2) draw2d(xlabel = "Time",
 explicit(exp(u),u,-2,2),
 ylabel = "Population")$
```

See also **ylabel**, and **zlabel**.

**xrange**

Graphic option

Default value: **auto**

If **xrange** is **auto**, the range for the x coordinate is computed automatically.

If the user wants a specific interval for x, it must be given as a Maxima list, as in **xrange**=[-2, 3].

Since this is a global graphics option, its position in the scene description does not matter.

Example:

```
(%i1) load(draw)$
(%i2) draw2d(xrange = [-3,5],
 explicit(x^2,x,-1,1))$
```

See also **yrange** and **zrange**.

**xrange\_secondary**

Graphic option

Default value: **auto**

If **xrange\_secondary** is **auto**, the range for the second x axis is computed automatically.

If the user wants a specific interval for the second x axis, it must be given as a Maxima list, as in **xrange\_secondary**=[-2, 3].

Since this is a global graphics option, its position in the scene description does not matter.

See also **xrange**, **yrange**, **zrange** and **yrange\_secondary**.

**xtics**

Graphic option

Default value: **auto**

This graphic option controls the way tic marks are drawn on the x axis.

- When option **xtics** is bounded to symbol *auto*, tic marks are drawn automatically.
- When option **xtics** is bounded to symbol *none*, tic marks are not drawn.
- When option **xtics** is bounded to a positive number, this is the distance between two consecutive tic marks.
- When option **xtics** is bounded to a list of length three of the form [start,incr,end], tic marks are plotted from **start** to **end** at intervals of length **incr**.
- When option **xtics** is bounded to a set of numbers of the form {n1, n2, ...}, tic marks are plotted at values n1, n2, ...
- When option **xtics** is bounded to a set of pairs of the form [{"label1", n1}, {"label2", n2}, ...], tic marks corresponding to values n1, n2, ... are labeled with "label1", "label2", ..., respectively.

Since this is a global graphics option, its position in the scene description does not matter.

Examples:

Disable tics.

```
(%i1) load(draw)$
(%i2) draw2d(xtics = 'none,
 explicit(x^3,x,-1,1))$
```

Tics every 1/4 units.

```
(%i1) load(draw)$
(%i2) draw2d(xtics = 1/4,
 explicit(x^3,x,-1,1))$
```

Tics from  $-3/4$  to  $3/4$  in steps of  $1/8$ .

```
(%i1) load(draw)$
(%i2) draw2d(xtics = [-3/4,1/8,3/4],
 explicit(x^3,x,-1,1))$
```

Tics at points  $-1/2$ ,  $-1/4$  and  $3/4$ .

```
(%i1) load(draw)$
(%i2) draw2d(xtics = {-1/2,-1/4,3/4},
 explicit(x^3,x,-1,1))$
```

Labeled tics.

```
(%i1) load(draw)$
(%i2) draw2d(xtics = [{"High",0.75},{"Medium",0},{"Low",-0.75}],
 explicit(x^3,x,-1,1))$
```

See also `ytics`, and `ztics`.

### **xtics\_axis**

Graphic option

Default value: `false`

If `xtics_axis` is `true`, tic marks and their labels are plotted just along the  $x$  axis, if it is `false` tics are plotted on the border.

Since this is a global graphics option, its position in the scene description does not matter.

### **xtics\_rotate**

Graphic option

Default value: `false`

If `xtics_rotate` is `true`, tic marks on the  $x$  axis are rotated 90 degrees.

Since this is a global graphics option, its position in the scene description does not matter.

### **xtics\_rotate\_secondary**

Graphic option

Default value: `false`

If `xtics_rotate_secondary` is `true`, tic marks on the secondary  $x$  axis are rotated 90 degrees.

Since this is a global graphics option, its position in the scene description does not matter.

### **xtics\_secondary**

Graphic option

Default value: `auto`

This graphic option controls the way tic marks are drawn on the second  $x$  axis.

See `xtics` for a complete description.

### **xtics\_secondary\_axis**

Graphic option

Default value: `false`

If `xtics_secondary_axis` is `true`, tic marks and their labels are plotted just along the secondary  $x$  axis, if it is `false` tics are plotted on the border.

Since this is a global graphics option, its position in the scene description does not matter.

### **xu\_grid**

Graphic option

Default value: 30

`xu_grid` is the number of coordinates of the first variable ( $x$  in explicit and  $u$  in parametric 3d surfaces) to build the grid of sample points.

This option affects the following graphic objects:

- `gr3d`: `explicit` and `parametric_surface`.

Example:



```
(%i1) load(draw)$
(%i2) draw3d(xu_grid = 10,
 yv_grid = 50,
 explicit(x^2+y^2,x,-3,3,y,-3,3))$
```

See also `yv_grid`.

### **xy\_file**

Graphic option

Default value: "" (empty string)

`xy_file` is the name of the file where the coordinates will be saved after clicking with the mouse button and hitting the 'x' key. By default, no coordinates are saved.

Since this is a global graphics option, its position in the scene description does not matter.

### **xyplane**

Graphic option

Default value: `false`

Allocates the xy-plane in 3D scenes. When `xyplane` is `false`, the xy-plane is placed automatically; when it is a real number, the xy-plane intersects the z-axis at this level. This option has no effect in 2D scenes.

Since this is a global graphics option, its position in the scene description does not matter.

Example:

```
(%i1) load(draw)$
(%i2) draw3d(xyplane = %e-2,
 explicit(x^2+y^2,x,-1,1,y,-1,1))$
```

### **y\_voxel**

Graphic option

Default value: 10

`y_voxel` is the number of voxels in the y direction to be used by the *marching cubes algorithm* implemented by the 3d implicit object. It is also used by graphic object `region`.

### **yaxis**

Graphic option

Default value: `false`

If `yaxis` is `true`, the y axis is drawn.

Since this is a global graphics option, its position in the scene description does not matter.

Example:

```
(%i1) load(draw)$
(%i2) draw2d(explicit(x^3,x,-1,1),
 yaxis = true,
 yaxis_color = blue)$
```

See also `yaxis_width`, `yaxis_type` and `yaxis_color`.

### **yaxis\_color**

Graphic option

Default value: "black"

`yaxis_color` specifies the color for the y axis. See `color` to know how colors are defined.

Since this is a global graphics option, its position in the scene description does not matter.

Example:

```
(%i1) load(draw)$
(%i2) draw2d(explicit(x^3,x,-1,1),
 yaxis = true,
 yaxis_color = red)$
```

See also `yaxis`, `yaxis_width` and `yaxis_type`.

**yaxis\_secondary**

Graphic option

Default value: `false`

If `yaxis_secondary` is `true`, function values can be plotted with respect to the second y axis, which will be drawn on the right side of the scene.

Note that this is a local graphics option which only affects to 2d plots.

Example:

```
(%i1) load(draw)$
(%i2) draw2d(
 explicit(sin(x),x,0,10),
 yaxis_secondary = true,
 ytics_secondary = true,
 color = blue,
 explicit(100*sin(x+0.1)+2,x,0,10));
```

See also `yrange_secondary`, `yticks_secondary`, `yticks_rotate_secondary` and `yticks_axis_secondary`.

**yaxis\_type**

Graphic option

Default value: `dots`

`yaxis_type` indicates how the y axis is displayed; possible values are `solid` and `dots`.

Since this is a global graphics option, its position in the scene description does not matter.

Example:

```
(%i1) load(draw)$
(%i2) draw2d(explicit(x^3,x,-1,1),
 yaxis = true,
 yaxis_type = solid)$
```

See also `yaxis`, `yaxis_width` and `yaxis_color`.

**yaxis\_width**

Graphic option

Default value: `1`

`yaxis_width` is the width of the y axis. Its value must be a positive number.

Since this is a global graphics option, its position in the scene description does not matter.

Example:

```
(%i1) load(draw)$
(%i2) draw2d(explicit(x^3,x,-1,1),
 yaxis = true,
 yaxis_width = 3)$
```

See also `yaxis`, `yaxis_type` and `yaxis_color`.

**ylabel**

Graphic option

Default value: `""` (empty string)

Option `ylabel`, a string, is the label for the y axis. By default, no label is written.

Since this is a global graphics option, its position in the scene description does not matter.

Example:

```
(%i1) load(draw)$
(%i2) draw2d(xlabel = "Time",
 ylabel = "Population",
 explicit(exp(u),u,-2,2))$
```

See also `xlabel`, and `zlabel`.

**yrange**

Graphic option

Default value: `auto`If `yrange` is `auto`, the range for the  $y$  coordinate is computed automatically.If the user wants a specific interval for  $y$ , it must be given as a Maxima list, as in `yrange=[-2, 3]`.

Since this is a global graphics option, its position in the scene description does not matter.

Example:

```
(%i1) load(draw)$
(%i2) draw2d(yrange = [-2,3],
 explicit(x^2,x,-1,1),
 xrange = [-3,3])$
```

See also `xrange`, `yrange_secondary` and `zrange`.**yrange\_secondary**

Graphic option

Default value: `auto`If `yrange_secondary` is `auto`, the range for the second  $y$  axis is computed automatically.If the user wants a specific interval for the second  $y$  axis, it must be given as a Maxima list, as in `yrange_secondary=[-2, 3]`.

Since this is a global graphics option, its position in the scene description does not matter.

Example:

```
(%i1) load(draw)$
(%i2) draw2d(
 explicit(sin(x),x,0,10),
 yaxis_secondary = true,
 ytics_secondary = true,
 xrange = [-3, 3],
 yrange_secondary = [-20, 20],
 color = blue,
 explicit(100*sin(x+0.1)+2,x,0,10)) $
```

See also `xrange`, `yrange` and `zrange`.**yticks**

Graphic option

Default value: `auto`This graphic option controls the way tic marks are drawn on the  $y$  axis.See `xticks` for a complete description.**yticks\_axis**

Graphic option

Default value: `false`If `yticks_axis` is `true`, tic marks and their labels are plotted just along the  $y$  axis, if it is `false` tics are plotted on the border.

Since this is a global graphics option, its position in the scene description does not matter.

**yticks\_rotate**

Graphic option

Default value: `false`If `yticks_rotate` is `true`, tic marks on the  $y$  axis are rotated 90 degrees.

Since this is a global graphics option, its position in the scene description does not matter.

**yticks\_rotate\_secondary**

Graphic option

Default value: `false`If `yticks_rotate_secondary` is `true`, tic marks on the secondary  $y$  axis are rotated 90 degrees.

Since this is a global graphics option, its position in the scene description does not matter.

**ytics\_secondary**

Graphic option

Default value: `auto`This graphic option controls the way tic marks are drawn on the second *y* axis.See `xtics` for a complete description.**ytics\_secondary\_axis**

Graphic option

Default value: `false`If `ytics_secondary_axis` is `true`, tic marks and their labels are plotted just along the secondary *y* axis, if it is `false` tics are plotted on the border.

Since this is a global graphics option, its position in the scene description does not matter.

**yv\_grid**

Graphic option

Default value: 30

`yv_grid` is the number of coordinates of the second variable (*y* in explicit and *v* in parametric 3d surfaces) to build the grid of sample points.

This option affects the following graphic objects:

- `gr3d`: `explicit` and `parametric_surface`.

Example:

```
(%i1) load(draw)$
(%i2) draw3d(xu_grid = 10,
 yv_grid = 50,
 explicit(x^2+y^2,x,-3,3,y,-3,3))$
```

See also `xu_grid`.**z\_voxel**

Graphic option

Default value: 10

`z_voxel` is the number of voxels in the *z* direction to be used by the *marching cubes algorithm* implemented by the 3d `implicit` object.**zaxis**

Graphic option

Default value: `false`If `zaxis` is `true`, the *z* axis is drawn in 3D plots. This option has no effect in 2D scenes.

Since this is a global graphics option, its position in the scene description does not matter.

Example:

```
(%i1) load(draw)$
(%i2) draw3d(explicit(x^2+y^2,x,-1,1,y,-1,1),
 zaxis = true,
 zaxis_type = solid,
 zaxis_color = blue)$
```

See also `zaxis_width`, `zaxis_type` and `zaxis_color`.**zaxis\_color**

Graphic option

Default value: `"black"``zaxis_color` specifies the color for the *z* axis. See `color` to know how colors are defined. This option has no effect in 2D scenes.

Since this is a global graphics option, its position in the scene description does not matter.

Example:

```
(%i1) load(draw)$
(%i2) draw3d(explicit(x^2+y^2,x,-1,1,y,-1,1),
 zaxis = true,
 zaxis_type = solid,
 zaxis_color = red)$
```

See also `zaxis`, `zaxis_width` and `zaxis_type`.

**zaxis\_type**

Graphic option

Default value: `dots`

`zaxis_type` indicates how the  $z$  axis is displayed; possible values are `solid` and `dots`. This option has no effect in 2D scenes.

Since this is a global graphics option, its position in the scene description does not matter.

Example:

```
(%i1) load(draw)$
(%i2) draw3d(implicit(x^2+y^2,x,-1,1,y,-1,1),
 zaxis = true,
 zaxis_type = solid)$
```

See also `zaxis`, `zaxis_width` and `zaxis_color`.

**zaxis\_width**

Graphic option

Default value: `1`

`zaxis_width` is the width of the  $z$  axis. Its value must be a positive number. This option has no effect in 2D scenes.

Since this is a global graphics option, its position in the scene description does not matter.

Example:

```
(%i1) load(draw)$
(%i2) draw3d(implicit(x^2+y^2,x,-1,1,y,-1,1),
 zaxis = true,
 zaxis_type = solid,
 zaxis_width = 3)$
```

See also `zaxis`, `zaxis_type` and `zaxis_color`.

**zlabel**

Graphic option

Default value: `""` (empty string)

Option `zlabel`, a string, is the label for the  $z$  axis. By default, no label is written.

Since this is a global graphics option, its position in the scene description does not matter.

Example:

```
(%i1) load(draw)$
(%i2) draw3d(zlabel = "Z variable",
 ylabel = "Y variable",
 implicit(sin(x^2+y^2),x,-2,2,y,-2,2),
 xlabel = "X variable")$
```

See also `xlabel`, and `ylabel`.

**zrange**

Graphic option

Default value: `auto`

If `zrange` is `auto`, the range for the  $z$  coordinate is computed automatically.

If the user wants a specific interval for  $z$ , it must be given as a Maxima list, as in `zrange=[-2, 3]`.

Since this is a global graphics option, its position in the scene description does not matter.

Example:

```
(%i1) load(draw)$
(%i2) draw3d(yrange = [-3,3],
 zrange = [-2,5],
 implicit(x^2+y^2,x,-1,1,y,-1,1),
 xrange = [-3,3])$
```

See also `xrange` and `yrange`.

**ztics** Graphic option

Default value: `auto`

This graphic option controls the way tic marks are drawn on the  $z$  axis.

See `xtics` for a complete description.

**ztics\_axis** Graphic option

Default value: `false`

If `ztics_axis` is `true`, tic marks and their labels are plotted just along the  $z$  axis, if it is `false` tics are plotted on the border.

Since this is a global graphics option, its position in the scene description does not matter.

**ztics\_rotate** Graphic option

Default value: `false`

If `ztics_rotate` is `true`, tic marks on the  $z$  axis are rotated 90 degrees.

Since this is a global graphics option, its position in the scene description does not matter.

## 48.2.4 Graphics objects

**bars** (`[x1,h1,w1], [x2,h2,w2, ...]`) Graphic object

Draws vertical bars in 2D.

### 2D

`bars ([x1,h1,w1], [x2,h2,w2, ...])` draws bars centered at values  $x1, x2, \dots$  with heights  $h1, h2, \dots$  and widths  $w1, w2, \dots$

This object is affected by the following *graphic options*: `key`, `fill_color`, `fill_density` and `line_width`.

Example:

```
(%i1) load(draw)$
(%i2) draw2d(
 key = "Group A",
 fill_color = blue,
 fill_density = 0.2,
 bars([0.8,5,0.4],[1.8,7,0.4],[2.8,-4,0.4]),
 key = "Group B",
 fill_color = red,
 fill_density = 0.6,
 line_width = 4,
 bars([1.2,4,0.4],[2.2,-2,0.4],[3.2,5,0.4]),
 xaxis = true);
```

**cylindrical** (`radius, z, minz, maxz, azi, minazi, maxazi`) Graphic object

Draws 3D functions defined in cylindrical coordinates.

### 3D

`cylindrical(radius, z, minz, maxz, azi, minazi, maxazi)` plots the function  $radius(z, azi)$  defined in cylindrical coordinates, with variable  $z$  taking values from  $minz$  to  $maxz$  and *azimuth*  $azi$  taking values from  $minazi$  to  $maxazi$ .

This object is affected by the following *graphic options*: `xu_grid`, `yv_grid`, `line_type`, `key`, `wired_surface`, `enhanced3d` and `color`.

Example:

```
(%i1) load(draw)$
(%i2) draw3d(cylindrical(1,z,-2,2,az,0,2*%pi))$
```

**elevation\_grid** (*mat, x0, y0, width, height*)

Graphic object

Draws matrix *mat* in 3D space. *z* values are taken from *mat*, the abscissas range from *x0* to *x0 + width* and ordinates from *y0* to *y0 + height*. Element *a*(1,1) is projected on point (*x0*, *y0 + height*), *a*(1, *n*) on (*x0 + width*, *y0 + height*), *a*(*m*, 1) on (*x0*, *y0*), and *a*(*m*, *n*) on (*x0 + width*, *y0*).

This object is affected by the following *graphic options*: *line\_type*, *line\_width*, *key*, *wired\_surface*, *enhanced3d*, and *color*.

In older versions of Maxima, *elevation\_grid* was called *mesh*. See also *mesh*.

Example:

```
(%i1) load(draw)$
(%i2) m: apply(
 matrix,
 makelist(makelist(random(10.0),k,1,30),i,1,20)) $
(%i3) draw3d(
 color = blue,
 elevation_grid(m,0,0,3,2),
 xlabel = "x",
 ylabel = "y",
 surface_hide = true);
```

**ellipse** (*xc, yc, a, b, ang1, ang2*)

Graphic object

Draws ellipses and circles in 2D.

**2D**

*ellipse* (*xc, yc, a, b, ang1, ang2*) plots an ellipse centered at [*xc, yc*] with horizontal and vertical semi axis *a* and *b*, respectively, starting at angle *ang1* with an amplitude equal to angle *ang2*.

This object is affected by the following *graphic options*: *nticks*, *transparent*, *fill\_color*, *border*, *line\_width*, *line\_type*, *key* and *color*.

Example:

```
(%i1) load(draw)$
(%i2) draw2d(transparent = false,
 fill_color = red,
 color = gray30,
 transparent = false,
 line_width = 5,
 ellipse(0,6,3,2,270,-270),
 /* center (x,y), a, b, start & end in degrees */
 transparent = true,
 color = blue,
 line_width = 3,
 ellipse(2.5,6,2,3,30,-90),
 xrange = [-3,6],
 yrange = [2,9])$
```

**errors** ([*x1, x2, ...*], [*y1, y2, ...*])

Graphic object

Draws points with error bars, horizontally, vertically or both, depending on the value of option *error\_type*.

**2D**

If *error\_type* = *x*, arguments to *errors* must be of the form [*x, y, xdelta*] or [*x, y, xlow, xhigh*]. If *error\_type* = *y*, arguments must be of the form [*x, y, ydelta*] or [*x, y, ylow, yhigh*]. If *error\_type* = *xy* or *error\_type* = *boxes*, arguments to *errors* must be of the form [*x, y, xdelta, ydelta*] or [*x, y, xlow, xhigh, ylow, yhigh*].

See also *error\_type*.

This object is affected by the following *graphic options*: `error_type`, `points_joined`, `line_width`, `key`, `line_type`, `color`, `fill_density`, `xaxis_secondary`, and `yaxis_secondary`.

Option `fill_density` is only relevant when `error_type=boxes`.

Examples:

Horizontal error bars.

```
(%i1) load(draw)$
(%i2) draw2d(
 error_type = y,
 errors([[1,2,1], [3,5,3], [10,3,1], [17,6,2]]))$
```

Vertical and horizontal error bars.

```
(%i1) load(draw)$
(%i2) draw2d(
 error_type = xy,
 points_joined = true,
 color = blue,
 errors([[1,2,1,2], [3,5,2,1], [10,3,1,1], [17,6,1/2,2]]));
```

**explicit** (*fcn, var, minval, maxval*)

Graphic object

**explicit** (*fcn, var1, minval1, maxval1, var2, minval2, maxval2*)

Graphic object

Draws explicit functions in 2D and 3D.

## 2D

`explicit(fcn, var, minval, maxval)` plots explicit function *fcn*, with variable *var* taking values from *minval* to *maxval*.

This object is affected by the following *graphic options*: `nticks`, `adapt_depth`, `draw_realpart`, `line_width`, `line_type`, `key`, `filled_func`, `fill_color` and `color`.

Example:

```
(%i1) load(draw)$
(%i2) draw2d(line_width = 3,
 color = blue,
 explicit(x^2,x,-3,3))$
(%i3) draw2d(fill_color = brown,
 filled_func = true,
 explicit(x^2,x,-3,3))$
```

## 3D

`explicit(fcn, var1, minval1, maxval1, var2, minval2, maxval2)` plots the explicit function *fcn*, with variable *var1* taking values from *minval1* to *maxval1* and variable *var2* taking values from *minval2* to *maxval2*.

This object is affected by the following *graphic options*: `draw_realpart`, `xu_grid`, `yv_grid`, `line_type`, `line_width`, `key`, `wired_surface`, `enhanced3d`, and `color`.

Example:

```
(%i1) load(draw)$
(%i2) draw3d(key = "Gauss",
 color = "#a02c00",
 explicit(20*exp(-x^2-y^2)-10,x,-3,3,y,-3,3),
 yv_grid = 10,
 color = blue,
 key = "Plane",
 explicit(x+y,x,-5,5,y,-5,5),
 surface_hide = true)$
```

See also `filled_func` for filled functions.



**image** (*im,x0,y0,width,height*)

Graphic object

Renders images in 2D.

**2D**

**image** (*im,x0,y0,width,height*) plots image *im* in the rectangular region from vertex (*x0,y0*) to (*x0+width,y0+height*) on the real plane. Argument *im* must be a matrix of real numbers, a matrix of vectors of length three or a *picture* object.

If *im* is a matrix of real numbers or a *levels picture* object, pixel values are interpreted according to graphic option **palette**, which is a vector of length three with components ranging from -36 to +36; each value is an index for a formula mapping the levels onto red, green and blue colors, respectively:

|                               |                   |                   |
|-------------------------------|-------------------|-------------------|
| 0: 0                          | 1: 0.5            | 2: 1              |
| 3: x                          | 4: x <sup>2</sup> | 5: x <sup>3</sup> |
| 6: x <sup>4</sup>             | 7: sqrt(x)        | 8: sqrt(sqrt(x))  |
| 9: sin(90x)                   | 10: cos(90x)      | 11:  x-0.5        |
| 12: (2x-1) <sup>2</sup>       | 13: sin(180x)     | 14:  cos(180x)    |
| 15: sin(360x)                 | 16: cos(360x)     | 17:  sin(360x)    |
| 18:  cos(360x)                | 19:  sin(720x)    | 20:  cos(720x)    |
| 21: 3x                        | 22: 3x-1          | 23: 3x-2          |
| 24:  3x-1                     | 25:  3x-2         | 26: (3x-1)/2      |
| 27: (3x-2)/2                  | 28:  (3x-1)/2     | 29:  (3x-2)/2     |
| 30: x/0.32-0.78125            |                   | 31: 2*x-0.84      |
| 32: 4x;1;-2x+1.84;x/0.08-11.5 |                   |                   |
| 33:  2*x - 0.5                | 34: 2*x           | 35: 2*x - 0.5     |
| 36: 2*x - 1                   |                   |                   |

negative numbers mean negative colour component.

**palette = gray** and **palette = color** are short cuts for **palette = [3,3,3]** and **palette = [7,5,15]**, respectively.

If *im* is a matrix of vectors of length three or an *rgb picture* object, they are interpreted as red, green and blue color components.

Examples:

If *im* is a matrix of real numbers, pixel values are interpreted according to graphic option **palette**.

```
(%i1) load(draw)$
(%i2) im: apply(
 'matrix,
 makelist(makelist(random(200),i,1,30),i,1,30))$
(%i3) /* palette = color, default */
 draw2d(image(im,0,0,30,30))$
(%i4) draw2d(palette = gray, image(im,0,0,30,30))$
(%i5) draw2d(palette = [15,20,-4],
 colorbox=false,
 image(im,0,0,30,30))$
```

See also **colorbox**.

If *im* is a matrix of vectors of length three, they are interpreted as red, green and blue color components.

```
(%i1) load(draw)$
(%i2) im: apply(
 'matrix,
 makelist(
 makelist([random(300),
 random(300),
 random(300)],i,1,30),i,1,30))$
(%i3) draw2d(image(im,0,0,30,30))$
```

Package **draw** automatically loads package **picture**. In this example, a level picture object is built by hand and then rendered.

```
(%i1) load(draw)$
(%i2) im: make_level_picture([45,87,2,134,204,16],3,2);
(%o2) picture(level, 3, 2, {Array: #(45 87 2 134 204 16)})
(%i3) /* default color palette */
 draw2d(image(im,0,0,30,30))$
(%i4) /* gray palette */
 draw2d(palette = gray,
 image(im,0,0,30,30))$
```

An xpm file is read and then rendered.

```
(%i1) load(draw)$
(%i2) im: read_xpm("myfile.xpm")$
(%i3) draw2d(image(im,0,0,10,7))$
```

See also `make_level_picture`, `make_rgb_picture` and `read_xpm`.

<http://www.telefonica.net/web2/biomates/maxima/gpdraw/image>  
contains more elaborated examples.

**implicit** (*fcn*,*x*,*xmin*,*xmax*,*y*,*ymin*,*ymax*) Graphic object  
**implicit** (*fcn*,*x*,*xmin*,*xmax*,*y*,*ymin*,*ymax*,*z*,*zmin*,*zmax*) Graphic object

Draws implicit functions in 2D and 3D.

## 2D

`implicit(fcn,x,xmin,xmax,y,ymin,ymax)` plots the implicit function defined by *fcn*, with variable *x* taking values from *xmin* to *xmax*, and variable *y* taking values from *ymin* to *ymax*.

This object is affected by the following *graphic options*: `ip_grid`, `ip_grid_in`, `line_width`, `line_type`, `key` and `color`.

Example:

```
(%i1) load(draw)$
(%i2) draw2d(terminal = eps,
 grid = true,
 line_type = solid,
 key = "y^2=x^3-2*x+1",
 implicit(y^2=x^3-2*x+1, x, -4,4, y, -4,4),
 line_type = dots,
 key = "x^3+y^3 = 3*x*y^2-x-1",
 implicit(x^3+y^3 = 3*x*y^2-x-1, x,-4,4, y,-4,4),
 title = "Two implicit functions")$
```

## 3D

`implicit(fcn,x,xmin,xmax,y,ymin,ymax,z,zmin,zmax)` plots the implicit surface defined by *fcn*, with variable *x* taking values from *xmin* to *xmax*, variable *y* taking values from *ymin* to *ymax* and variable *z* taking values from *zmin* to *zmax*. This object implements the *marching cubes algorithm*.

This object is affected by the following *graphic options*: `x_voxel`, `y_voxel`, `z_voxel`, `line_width`, `line_type`, `key`, `wired_surface`, `enhanced3d`, and `color`.

Example:

```
(%i1) load(draw)$
(%i2) draw3d(
 color=blue,
 implicit((x^2+y^2+z^2-1)*(x^2+(y-1.5)^2+z^2-0.5)=0.015,
 x,-1,1,y,-1.2,2.3,z,-1,1),
 surface_hide=true);
```

**label** ([*string*,*x*,*y*],...) Graphic object  
**label** ([*string*,*x*,*y*,*z*],...) Graphic object

Writes labels in 2D and 3D.

Colored labels work only with Gnuplot 4.3. This is a known bug in package **draw**.

This object is affected by the following *graphic options*: `label_alignment`, `label_orientation` and `color`.

## 2D

`label([string,x,y])` writes the *string* at point `[x,y]`.

Example:

```
(%i1) load(draw)$
(%i2) draw2d(yrange = [0.1,1.4],
 color = red,
 label(["Label in red",0,0.3]),
 color = "#0000ff",
 label(["Label in blue",0,0.6]),
 color = light_blue,
 label(["Label in light-blue",0,0.9],
 ["Another light-blue",0,1.2]))$
```

## 3D

`label([string,x,y,z])` writes the *string* at point `[x,y,z]`.

Example:

```
(%i1) load(draw)$
(%i2) draw3d(explicit(exp(sin(x)+cos(x^2)),x,-3,3,y,-3,3),
 color = red,
 label(["UP 1",-2,0,3], ["UP 2",1.5,0,4]),
 color = blue,
 label(["DOWN 1",2,0,-3]))$
```

## **mesh** (*row\_1,row\_2,...*)

Graphic object

Draws a quadrangular mesh in 3D.

## 3D

Argument *row\_i* is a list of *n* 3D points of the form `[[x_i1,y_i1,z_i1], ..., [x_in,y_in,z_in]]`, and all rows are of equal length. All these points define an arbitrary surface in 3D and in some sense it's a generalization of the `elevation_grid` object.

This object is affected by the following *graphic options*: `line_type`, `line_width`, `color`, `key`, `wired_surface`, `enhanced3d`, and `transform`.

Examples:

A simple example.

```
(%i1) load(draw)$
(%i2) draw3d(
 mesh([[1,1,3], [7,3,1], [12,-2,4], [15,0,5]],
 [[2,7,8], [4,3,1], [10,5,8], [12,7,1]],
 [[-2,11,10], [6,9,5], [6,15,1], [20,15,2]])) $
```

Plotting a triangle in 3D.

```
(%i1) load(draw)$
(%i2) draw3d(
 line_width = 2,
 mesh([[1,0,0], [0,1,0]],
 [[0,0,1], [0,0,1]])) $
```

Two quadrilaterals.

```
(%i1) load(draw)$
(%i2) draw3d(
 surface_hide = true,
 line_width = 3,
 color = red,
 mesh([[0,0,0], [0,1,0]],
```



|                                                                             |                |
|-----------------------------------------------------------------------------|----------------|
| <b>points</b> ( $[[x1,y1], [x2,y2],...]$ )                                  | Graphic object |
| <b>points</b> ( $[x1,x2,...], [y1,y2,...]$ )                                | Graphic object |
| <b>points</b> ( $[y1,y2,...]$ )                                             | Graphic object |
| <b>points</b> ( $[[x1,y1,z1], [x2,y2,z2],...]$ )                            | Graphic object |
| <b>points</b> ( $[x1,x2,...], [y1,y2,...], [z1,z2,...]$ )                   | Graphic object |
| <b>points</b> ( <i>matrix</i> )                                             | Graphic object |
| <b>points</b> ( <i>1d_y_array</i> )                                         | Graphic object |
| <b>points</b> ( <i>1d_x_array</i> , <i>1d_y_array</i> )                     | Graphic object |
| <b>points</b> ( <i>1d_x_array</i> , <i>1d_y_array</i> , <i>1d_z_array</i> ) | Graphic object |
| <b>points</b> ( <i>2d_xy_array</i> )                                        | Graphic object |
| <b>points</b> ( <i>2d_xyz_array</i> )                                       | Graphic object |

Draws points in 2D and 3D.

This object is affected by the following *graphic options*: **point\_size**, **point\_type**, **points\_joined**, **line\_width**, **key**, **line\_type** and **color**. In 3D mode, it is also affected by **enhanced3d**.

## 2D

**points** ( $[[x1,y1], [x2,y2],...]$ ) or **points** ( $[x1,x2,...], [y1,y2,...]$ ) plots points  $[x1,y1]$ ,  $[x2,y2]$ , etc. If abscissas are not given, they are set to consecutive positive integers, so that **points** ( $[y1,y2,...]$ ) draws points  $[1,y1]$ ,  $[2,y2]$ , etc. If *matrix* is a two-column or two-row matrix, **points** (*matrix*) draws the associated points. If *matrix* is a one-column or one-row matrix, abscissas are assigned automatically.

If *1d\_y\_array* is a 1D lisp array of numbers, **points** (*1d\_y\_array*) plots them setting abscissas to consecutive positive integers. **points** (*1d\_x\_array*, *1d\_y\_array*) plots points with their coordinates taken from the two arrays passed as arguments. If *2d\_xy\_array* is a 2D array with two columns, or with two rows, **points** (*2d\_xy\_array*) plots the corresponding points on the plane.

Examples:

Two types of arguments for **points**, a list of pairs and two lists of separate coordinates.

```
(%i1) load(draw)$
(%i2) draw2d(
 key = "Small points",
 points(makelist([random(20),random(50)],k,1,10)),
 point_type = circle,
 point_size = 3,
 points_joined = true,
 key = "Great points",
 points(makelist(k,k,1,20),makelist(random(30),k,1,20)),
 point_type = filled_down_triangle,
 key = "Automatic abscissas",
 color = red,
 points([2,12,8]))$
```

Drawing impulses.

```
(%i1) load(draw)$
(%i2) draw2d(
 points_joined = impulses,
 line_width = 2,
 color = red,
 points(makelist([random(20),random(50)],k,1,10)))$
```

Array with ordinates.

```
(%i1) load(draw)$
(%i2) a: make_array (flonum, 100) $
(%i3) for i:0 thru 99 do a[i]: random(1.0) $
(%i4) draw2d(points(a)) $
```

Two arrays with separate coordinates.

```
(%i1) load(draw)$
(%i2) x: make_array (flonum, 100) $
(%i3) y: make_array (fixnum, 100) $
(%i4) for i:0 thru 99 do (
 x[i]: float(i/100),
 y[i]: random(10)) $
(%i5) draw2d(points(x, y)) $
```

A two-column 2D array.

```
(%i1) load(draw)$
(%i2) xy: make_array(flonum, 100, 2) $
(%i3) for i:0 thru 99 do (
 xy[i, 0]: float(i/100),
 xy[i, 1]: random(10)) $
(%i4) draw2d(points(xy)) $
```

Drawing an array filled with function read\_array.

```
(%i1) load(draw)$
(%i2) a: make_array(flonum,100) $
(%i3) read_array (file_search ("pidigits.data"), a) $
(%i4) draw2d(points(a)) $
```

### 3D

`points([[x1, y1, z1], [x2, y2, z2], ...])` or `points([x1, x2, ...], [y1, y2, ...], [z1, z2, ...])` plots points `[x1, y1, z1]`, `[x2, y2, z2]`, etc. If *matrix* is a three-column or three-row matrix, `points (matrix)` draws the associated points.

When arguments are list arrays, `points (1d_x_array, 1d_y_array, 1d_z_array)` takes coordinates from the three 1D arrays. If `2d_xyz_array` is a 2D array with three columns, or with three rows, `points (2d_xyz_array)` plots the corresponding points.

Examples:

One tridimensional sample,

```
(%i1) load(draw)$
(%i2) load (numericalio)$
(%i3) s2 : read_matrix (file_search ("wind.data"))$
(%i4) draw3d(title = "Daily average wind speeds",
 point_size = 2,
 points(args(submatrix (s2, 4, 5)))) $
```

Two tridimensional samples,

```
(%i1) load(draw)$
(%i2) load (numericalio)$
(%i3) s2 : read_matrix (file_search ("wind.data"))$
(%i4) draw3d(
 title = "Daily average wind speeds. Two data sets",
 point_size = 2,
 key = "Sample from stations 1, 2 and 3",
 points(args(submatrix (s2, 4, 5))),
 point_type = 4,
 key = "Sample from stations 1, 4 and 5",
 points(args(submatrix (s2, 2, 3))))$
```

Unidimensional arrays,

```
(%i1) load(draw)$
(%i2) x: make_array (fixnum, 10) $
(%i3) y: make_array (fixnum, 10) $
(%i4) z: make_array (fixnum, 10) $
(%i5) for i:0 thru 9 do (
 x[i]: random(10),
 y[i]: random(10),
```

```

 z[i]: random(10)) $
 (%i6) draw3d(points(x,y,z)) $
Bidimensional colored array,
 (%i1) load(draw)$
 (%i2) xyz: make_array(fixnum, 10, 3) $
 (%i3) for i:0 thru 9 do (
 xyz[i, 0]: random(10),
 xyz[i, 1]: random(10),
 xyz[i, 2]: random(10)) $
 (%i4) draw3d(
 enhanced3d = true,
 points_joined = true,
 points(xyz)) $

```

Color numbers explicitly specified by the user.

```

 (%i1) load(draw)$
 (%i2) pts: makelist([t,t^2,cos(t)], t, 0, 15)$
 (%i3) col_num: makelist(k, k, 1, length(pts))$
 (%i4) draw3d(
 enhanced3d = ['part(col_num,k),k],
 point_size = 3,
 point_type = filled_circle,
 points(pts))$

```

### **polar** (*radius,ang,minang,maxang*)

Graphic object

Draws 2D functions defined in polar coordinates.

#### **2D**

**polar** (*radius,ang,minang,maxang*) plots function *radius(ang)* defined in polar coordinates, with variable *ang* taking values from *minang* to *maxang*.

This object is affected by the following *graphic options*: *nticks*, *line\_width*, *line\_type*, *key* and *color*.

Example:

```

 (%i1) load(draw)$
 (%i2) draw2d(user_preamble = "set grid polar",
 nticks = 200,
 xrange = [-5,5],
 yrange = [-5,5],
 color = blue,
 line_width = 3,
 title = "Hyperbolic Spiral",
 polar(10/theta,theta,1,10*%pi))$

```

### **polygon** ([[*x1, y1*], [*x2, y2*], ...])

Graphic object

### **polygon** ([*x1, x2, ...*], [*y1, y2, ...*])

Graphic object

Draws polygons in 2D.

#### **2D**

The commands **polygon**([[*x1, y1*], [*x2, y2*], ...]) or **polygon**([*x1, x2, ...*], [*y1, y2, ...*]) plot on the plane a polygon with vertices [*x1, y1*], [*x2, y2*], etc.

This object is affected by the following *graphic options*: *transparent*, *fill\_color*, *border*, *line\_width*, *key*, *line\_type* and *color*.

Example:

```

 (%i1) load(draw)$
 (%i2) draw2d(color = "#e245f0",
 line_width = 8,
 polygon([[3,2],[7,2],[5,5]]),

```



```
border = false,
fill_color = yellow,
polygon([5,2],[9,2],[7,5])))$
```

### **quadrilateral** (*point\_1, point\_2, point\_3, point\_4*)

Graphic object

Draws a quadrilateral.

#### **2D**

`quadrilateral([x1, y1], [x2, y2], [x3, y3], [x4, y4])` draws a quadrilateral with vertices `[x1, y1]`, `[x2, y2]`, `[x3, y3]`, and `[x4, y4]`.

This object is affected by the following *graphic options*:

`transparent`, `fill_color`, `border`, `line_width`, `key`, `xaxis_secondary`, `yaxis_secondary`, `line_type`, `transform` and `color`.

Example:

```
(%i1) load(draw)$
(%i2) draw2d(
 quadrilateral([1,1],[2,2],[3,-1],[2,-2]))$
```

#### **3D**

`quadrilateral([x1, y1, z1], [x2, y2, z2], [x3, y3, z3], [x4, y4, z4])` draws a quadrilateral with vertices `[x1, y1, z1]`, `[x2, y2, z2]`, `[x3, y3, z3]`, and `[x4, y4, z4]`.

This object is affected by the following *graphic options*: `line_type`, `line_width`, `color`, `key`, `enhanced3d`, and `transform`.

### **rectangle** (`[x1,y1], [x2,y2]`)

Graphic object

Draws rectangles in 2D.

#### **2D**

`rectangle ([x1,y1], [x2,y2])` draws a rectangle with opposite vertices `[x1,y1]` and `[x2,y2]`.

This object is affected by the following *graphic options*: `transparent`, `fill_color`, `border`, `line_width`, `key`, `line_type` and `color`.

Example:

```
(%i1) load(draw)$
(%i2) draw2d(fill_color = red,
 line_width = 6,
 line_type = dots,
 transparent = false,
 fill_color = blue,
 rectangle([-2,-2],[8,-1]), /* opposite vertices */
 transparent = true,
 line_type = solid,
 line_width = 1,
 rectangle([9,4],[2,-1.5]),
 xrange = [-3,10],
 yrange = [-3,4.5])$
```

### **region** (*expr, var1, minval1, maxval1, var2, minval2, maxval2*)

Graphic object

Plots a region on the plane defined by inequalities.

**2D** *expr* is an expression formed by inequalities and boolean operators `and`, `or`, and `not`. The region is bounded by the rectangle defined by `[minval1, maxval1]` and `[minval2, maxval2]`.

This object is affected by the following *graphic options*: `fill_color`, `key`, `x_voxel`, and `y_voxel`.

Example:



```
(%i1) load(draw)$
(%i2) draw2d(
 x_voxel = 30,
 y_voxel = 30,
 region(x^2+y^2<1 and x^2+y^2 > 1/2,
 x, -1.5, 1.5, y, -1.5, 1.5));
```

**spherical** (*radius, azi, minazi, maxazi, zen, minzen, maxzen*)

Graphic object

Draws 3D functions defined in spherical coordinates.

### 3D

**spherical**(*radius, azi, minazi, maxazi, zen, minzen, maxzen*) plots the function *radius*(*azi, zen*) defined in spherical coordinates, with *azimuth* *azi* taking values from *minazi* to *maxazi* and *zenith* *zen* taking values from *minzen* to *maxzen*.

This object is affected by the following *graphic options*: *xu\_grid*, *yv\_grid*, *line\_type*, *key*, *wired\_surface*, *enhanced3d* and *color*.

Example:

```
(%i1) load(draw)$
(%i2) draw3d(spherical(1,a,0,2*%pi,z,0,%pi))$
```

**triangle** (*point\_1, point\_2, point\_3*)

Graphic object

Draws a triangle.

### 2D

**triangle** ([*x1,y1*], [*x2,y2*], [*x3,y3*]) draws a triangle with vertices [*x1,y1*], [*x2,y2*], and [*x3,y3*].

This object is affected by the following *graphic options*:

*transparent*, *fill\_color*, *border*, *line\_width*, *key*, *xaxis\_secondary*, *yaxis\_secondary*, *line\_type*, *transform*, and *color*.

Example:

```
(%i1) load(draw)$
(%i2) draw2d(
 triangle([1,1],[2,2],[3,-1]))$
```

### 3D

**triangle** ([*x1,y1,z1*], [*x2,y2,z2*], [*x3,y3,z3*]) draws a triangle with vertices [*x1,y1,z1*], [*x2,y2,z2*], and [*x3,y3,z3*].

This object is affected by the following *graphic options*: *line\_type*, *line\_width*, *color*, *key*, *enhanced3d*, and *transform*.

**tube** (*xfun,yfun,zfun,rfun,p,pmin,pmax*)

Graphic object

Draws a tube in 3D with varying diameter.

### 3D

[*xfun,yfun,zfun*] is the parametric curve with parameter *p* taking values from *pmin* to *pmax*. Circles of radius *rfun* are placed with their centers on the parametric curve and perpendicular to it.

This object is affected by the following *graphic options*: *xu\_grid*, *yv\_grid*, *line\_type*, *line\_width*, *key*, *wired\_surface*, *enhanced3d*, *color*, and *tube\_extremes*.

Example:

```
(%i1) load(draw)$
(%i2) draw3d(
 enhanced3d = true,
 xu_grid = 50,
 tube(cos(a), a, 0, cos(a/10)^2,
 a, 0, 4*%pi))$
```

**vector** ( $[x,y], [dx,dy]$ ) Graphic object  
**vector** ( $[x,y,z], [dx,dy,dz]$ ) Graphic object

Draws vectors in 2D and 3D.

This object is affected by the following *graphic options*: `head_both`, `head_length`, `head_angle`, `head_type`, `line_width`, `line_type`, `key` and `color`.

### 2D

**vector** ( $[x,y], [dx,dy]$ ) plots vector  $[dx,dy]$  with origin in  $[x,y]$ .

Example:

```
(%i1) load(draw)$
(%i2) draw2d(xrange = [0,12],
 yrange = [0,10],
 head_length = 1,
 vector([0,1],[5,5]), /* default type */
 head_type = 'empty,
 vector([3,1],[5,5]),
 head_both = true,
 head_type = 'nofilled,
 line_type = dots,
 vector([6,1],[5,5]))$
```

### 3D

**vector** ( $[x,y,z], [dx,dy,dz]$ ) plots vector  $[dx,dy,dz]$  with origin in  $[x,y,z]$ .

Example:

```
(%i1) load(draw)$
(%i2) draw3d(color = cyan,
 vector([0,0,0],[1,1,1]/sqrt(3)),
 vector([0,0,0],[1,-1,0]/sqrt(2)),
 vector([0,0,0],[1,1,-2]/sqrt(6)))$
```

## 48.3 Functions and Variables for pictures

**get\_pixel** ( $pic,x,y$ ) Function  
 Returns pixel from picture. Coordinates  $x$  and  $y$  range from 0 to `width-1` and `height-1`, respectively.

**make\_level\_picture** ( $data$ ) Function  
**make\_level\_picture** ( $data,width,height$ ) Function

Returns a levels *picture* object. **make\_level\_picture** ( $data$ ) builds the *picture* object from matrix  $data$ . **make\_level\_picture** ( $data,width,height$ ) builds the object from a list of numbers; in this case, both the *width* and the *height* must be given.

The returned *picture* object contains the following four parts:

1. symbol `level`
2. image width
3. image height
4. an integer array with pixel data ranging from 0 to 255. Argument  $data$  must contain only numbers ranged from 0 to 255; negative numbers are substituted by 0, and those which are greater than 255 are set to 255.

Example:

Level picture from matrix.

```
(%i1) load(draw)$
(%i2) make_level_picture(matrix([3,2,5],[7,-9,3000]));
(%o2) picture(level, 3, 2, {Array: #(3 2 5 7 0 255)})
```

Level picture from numeric list.

```
(%i1) load(draw)$
(%i2) make_level_picture([-2,0,54,%pi],2,2);
(%o2) picture(level, 2, 2, {Array: #(0 0 54 3)})
```

**make\_rgb\_picture** (*redlevel,greenlevel,bluelevel*)

Function

Returns an rgb-coloured *picture* object. All three arguments must be levels picture; with red, green and blue levels.

The returned *picture* object contains the following four parts:

1. symbol **rgb**
2. image width
3. image height
4. an integer array of length  $3*width*height$  with pixel data ranging from 0 to 255. Each pixel is represented by three consecutive numbers (red, green, blue).

Example:

```
(%i1) load(draw)$
(%i2) red: make_level_picture(matrix([3,2],[7,260]));
(%o2) picture(level, 2, 2, {Array: #(3 2 7 255)})
(%i3) green: make_level_picture(matrix([54,23],[73,-9]));
(%o3) picture(level, 2, 2, {Array: #(54 23 73 0)})
(%i4) blue: make_level_picture(matrix([123,82],[45,32.5698]));
(%o4) picture(level, 2, 2, {Array: #(123 82 45 33)})
(%i5) make_rgb_picture(red,green,blue);
(%o5) picture(rgb, 2, 2,
 {Array: #(3 54 123 2 23 82 7 73 45 255 0 33)})
```

**negative\_picture** (*pic*)

Function

Returns the negative of a (*level* or *rgb*) picture.

**picture\_equalp** (*x,y*)

Function

Returns **true** in case of equal pictures, and **false** otherwise.

**picturep** (*x*)

Function

Returns **true** if the argument is a well formed image, and **false** otherwise.

**read\_xpm** (*xpm\_file*)

Function

Reads a file in xpm and returns a picture object.

**rgb2level** (*pic*)

Function

Transforms an *rgb* picture into a *level* one by averaging the red, green and blue channels.

**take\_channel** (*im,color*)

Function

If argument *color* is **red**, **green** or **blue**, function **take\_channel** returns the corresponding color channel of picture *im*. Example:

```
(%i1) load(draw)$
(%i2) red: make_level_picture(matrix([3,2],[7,260]));
(%o2) picture(level, 2, 2, {Array: #(3 2 7 255)})
(%i3) green: make_level_picture(matrix([54,23],[73,-9]));
(%o3) picture(level, 2, 2, {Array: #(54 23 73 0)})
(%i4) blue: make_level_picture(matrix([123,82],[45,32.5698]));
(%o4) picture(level, 2, 2, {Array: #(123 82 45 33)})
(%i5) make_rgb_picture(red,green,blue);
(%o5) picture(rgb, 2, 2,
 {Array: #(3 54 123 2 23 82 7 73 45 255 0 33)})
(%i6) take_channel(%,'green); /* simple quote!!! */
(%o6) picture(level, 2, 2, {Array: #(54 23 73 0)})
```

## 48.4 Functions and Variables for worldmap

This package automatically loads package `draw`.

### 48.4.1 Variables and Functions

#### **boundaries\_array**

Global variable

Default value: `false`

`boundaries_array` is where the graphic object `geomap` looks for boundaries coordinates.

Each component of `boundaries_array` is an array of floating point quantities, the coordinates of a polygonal segment or map boundary.

See also `geomap`.

#### **numbered\_boundaries** (*nlist*)

Function

Draws a list of polygonal segments (boundaries), labeled by its numbers (`boundaries_array` coordinates). This is of great help when building new geographical entities.

Example:

Map of Europe labeling borders with their component number in `boundaries_array`.

```
(%i1) load(worldmap)$
(%i2) european_borders:
 region_boundaries(-31.81,74.92,49.84,32.06)$
(%i3) numbered_boundaries(european_borders)$
```

#### **make\_poly\_continent** (*continent\_name*)

Function

#### **make\_poly\_continent** (*country\_list*)

Function

Makes the necessary polygons to draw a colored continent or a list of countries.

Example:

```
(%i1) load(worldmap)$
(%i2) /* A continent */
 make_poly_continent(Africa)$
(%i3) apply(draw2d, %)$
(%i4) /* A list of countries */
 make_poly_continent([Germany,Denmark,Poland])$
(%i5) apply(draw2d, %)$
```

#### **make\_poly\_country** (*country\_name*)

Function

Makes the necessary polygons to draw a colored country. If islands exist, one country can be defined with more than just one polygon.

Example:

```
(%i1) load(worldmap)$
(%i2) make_poly_country(India)$
(%i3) apply(draw2d, %)$
```

#### **make\_polygon** (*nlist*)

Function

Returns a `polygon` object from boundary indices. Argument *nlist* is a list of components of `boundaries_array`.

Example:

Bhutan is defined by boundary numbers 171, 173 and 1143, so that `make_polygon([171,173,1143])` appends arrays of coordinates `boundaries_array[171]`, `boundaries_array[173]` and `boundaries_array[1143]` and returns a `polygon` object suited to be plotted by `draw`. To avoid an error message, arrays must be compatible in the sense that any two consecutive arrays have two coordinates in the extremes in common. In this example, the two first components of `boundaries_array[171]` are equal to the last two coordinates of `boundaries_array[173]`, and the two first of

`boundaries_array[173]` are equal to the two first of `boundaries_array[1143]`; in conclusion, boundary numbers 171, 173 and 1143 (in this order) are compatible and the colored polygon can be drawn.

```
(%i1) load(worldmap)$
(%i2) Bhutan;
(%o2) [[171, 173, 1143]]
(%i3) boundaries_array[171];
(%o3) {Array:
 #(88.750549 27.14727 88.806351 27.25305 88.901367 27.282221
 88.917877 27.321039)}
(%i4) boundaries_array[173];
(%o4) {Array:
 #(91.659554 27.76511 91.6008 27.66666 91.598022 27.62499
 91.631348 27.536381 91.765533 27.45694 91.775253 27.4161
 92.007751 27.471939 92.11441 27.28583 92.015259 27.168051
 92.015533 27.08083 92.083313 27.02277 92.112183 26.920271
 92.069977 26.86194 91.997192 26.85194 91.915253 26.893881
 91.916924 26.85416 91.8358 26.863331 91.712479 26.799999
 91.542191 26.80444 91.492188 26.87472 91.418854 26.873329
 91.371353 26.800831 91.307457 26.778049 90.682457 26.77417
 90.392197 26.903601 90.344131 26.894159 90.143044 26.75333
 89.98996 26.73583 89.841919 26.70138 89.618301 26.72694
 89.636093 26.771111 89.360786 26.859989 89.22081 26.81472
 89.110237 26.829161 88.921631 26.98777 88.873016 26.95499
 88.867737 27.080549 88.843307 27.108601 88.750549
 27.14727)}
(%i5) boundaries_array[1143];
(%o5) {Array:
 #(91.659554 27.76511 91.666924 27.88888 91.65831 27.94805
 91.338028 28.05249 91.314972 28.096661 91.108856 27.971109
 91.015808 27.97777 90.896927 28.05055 90.382462 28.07972
 90.396088 28.23555 90.366074 28.257771 89.996353 28.32333
 89.83165 28.24888 89.58609 28.139999 89.35997 27.87166
 89.225517 27.795 89.125793 27.56749 88.971077 27.47361
 88.917877 27.321039)}
(%i6) Bhutan_polygon: make_polygon([171,173,1143])$
(%i7) draw2d(Bhutan_polygon)$
```

**region\_boundaries** (*x1,y1,x2,y2*) Function

Detects polygonal segments of global variable `boundaries_array` fully contained in the rectangle with vertices (*x1,y1*) -upper left- and (*x2,y2*) -bottom right-.

Example:

Returns segment numbers for plotting southern Italy.

```
(%i1) load(worldmap)$
(%i2) region_boundaries(10.4,41.5,20.7,35.4);
(%o2) [1846, 1863, 1864, 1881, 1888, 1894]
(%i3) draw2d(geomap(%))$
```

**region\_boundaries\_plus** (*x1,y1,x2,y2*) Function

Detects polygonal segments of global variable `boundaries_array` containing at least one vertex in the rectangle defined by vertices (*x1,y1*) -upper left- and (*x2,y2*) -bottom right-.

Example:

```
(%i1) load(worldmap)$
(%i2) region_boundaries_plus(10.4,41.5,20.7,35.4);
(%o2) [1060, 1062, 1076, 1835, 1839, 1844, 1846, 1858,
```

```

1861, 1863, 1864, 1871, 1881, 1888, 1894, 1897]
(%i3) draw2d(geomap(%))$

```

## 48.4.2 Graphic objects

**geomap** (*numlist*) Graphic object  
**geomap** (*numlist*, *3Dprojection*) Graphic object

Draws cartographic maps in 2D and 3D.

### 2D

This function works together with global variable `boundaries_array`.

Argument *numlist* is a list containing numbers or lists of numbers. All these numbers must be integers greater or equal than zero, representing the components of global array `boundaries_array`.

Each component of `boundaries_array` is an array of floating point quantities, the coordinates of a polygonal segment or map boundary.

`geomap (numlist)` flattens its arguments and draws the associated boundaries in `boundaries_array`.

This object is affected by the following *graphic options*: `line_width`, `line_type` and `color`.

Examples:

A simple map defined by hand:

```

(%i1) load(worldmap)$
(%i2) /* Vertices of boundary #0: {(1,1),(2,5),(4,3)} */
(bnd0: make_array(flonum,6),
 bnd0[0]:1.0, bnd0[1]:1.0, bnd0[2]:2.0,
 bnd0[3]:5.0, bnd0[4]:4.0, bnd0[5]:3.0)$
(%i3) /* Vertices of boundary #1: {(4,3),(5,4),(6,4),(5,1)} */
(bnd1: make_array(flonum,8),
 bnd1[0]:4.0, bnd1[1]:3.0, bnd1[2]:5.0, bnd1[3]:4.0,
 bnd1[4]:6.0, bnd1[5]:4.0, bnd1[6]:5.0, bnd1[7]:1.0)$
(%i4) /* Vertices of boundary #2: {(5,1),(3,0),(1,1)} */
(bnd2: make_array(flonum,6),
 bnd2[0]:5.0, bnd2[1]:1.0, bnd2[2]:3.0,
 bnd2[3]:0.0, bnd2[4]:1.0, bnd2[5]:1.0)$
(%i5) /* Vertices of boundary #3: {(1,1),(4,3)} */
(bnd3: make_array(flonum,4),
 bnd3[0]:1.0, bnd3[1]:1.0, bnd3[2]:4.0, bnd3[3]:3.0)$
(%i6) /* Vertices of boundary #4: {(4,3),(5,1)} */
(bnd4: make_array(flonum,4),
 bnd4[0]:4.0, bnd4[1]:3.0, bnd4[2]:5.0, bnd4[3]:1.0)$
(%i7) /* Pack all together in boundaries_array */
(boundaries_array: make_array(any,5),
 boundaries_array[0]: bnd0, boundaries_array[1]: bnd1,
 boundaries_array[2]: bnd2, boundaries_array[3]: bnd3,
 boundaries_array[4]: bnd4)$
(%i8) draw2d(geomap([0,1,2,3,4]))$

```

The auxiliary package `worldmap` sets the global variable `boundaries_array` to real world boundaries in (longitude, latitude) coordinates. These data are in the public domain and come from <http://www-cger.nies.go.jp/grid-e/gridtxt/grid19.html>. Package `worldmap` defines also boundaries for countries, continents and coastlines as lists with the necessary components of `boundaries_array` (see file `share/draw/worldmap.mac` for more information). Package `worldmap` automatically loads package `worldmap`.

```

(%i1) load(worldmap)$
(%i2) c1: gr2d(geomap(Canada,United_States,

```

```

 Mexico,Cuba))$
(%i3) c2: gr2d(geomap(Africa))$
(%i4) c3: gr2d(geomap(Oceania,China,Japan))$
(%i5) c4: gr2d(geomap(France,Portugal,Spain,
 Morocco,Western_Sahara))$
(%i6) draw(columns = 2,
 c1,c2,c3,c4)$

```

Package `worldmap` is also useful for plotting countries as polygons. In this case, graphic object `geomap` is no longer necessary and the `polygon` object is used instead. Since lists are now used and not arrays, maps rendering will be slower. See also `make_poly_country` and `make_poly_continent` to understand the following code.

```

(%i1) load(worldmap)$
(%i2) mymap: append(
 [color = white], /* borders are white */
 [fill_color = red], make_poly_country(Bolivia),
 [fill_color = cyan], make_poly_country(Paraguay),
 [fill_color = green], make_poly_country(Colombia),
 [fill_color = blue], make_poly_country(Chile),
 [fill_color = "#23ab0f"], make_poly_country(Brazil),
 [fill_color = goldenrod], make_poly_country(Argentina),
 [fill_color = "midnight-blue"], make_poly_country(Uruguay))$
(%i3) apply(draw2d, mymap)$

```

### 3D

`geomap (numlist)` projects map boundaries on the sphere of radius 1 centered at (0,0,0). It is possible to change the sphere or the projection type by using `geomap (numlist, 3Dprojection)`.

Available 3D projections:

- `[spherical_projection,x,y,z,r]`: projects map boundaries on the sphere of radius  $r$  centered at  $(x,y,z)$ .

```

(%i1) load(worldmap)$
(%i2) draw3d(geomap(Australia), /* default projection */
 geomap(Australia,
 [spherical_projection,2,2,2,3]))$

```

- `[cylindrical_projection,x,y,z,r,rc]`: re-projects spherical map boundaries on the cylinder of radius  $rc$  and axis passing through the poles of the globe of radius  $r$  centered at  $(x,y,z)$ .

```

(%i1) load(worldmap)$
(%i2) draw3d(geomap([America_coastlines,Eurasia_coastlines],
 [cylindrical_projection,2,2,2,3,4]))$

```

- `[conic_projection,x,y,z,r,alpha]`: re-projects spherical map boundaries on the cones of angle  $alpha$ , with axis passing through the poles of the globe of radius  $r$  centered at  $(x,y,z)$ . Both the northern and southern cones are tangent to sphere.

```

(%i1) load(worldmap)$
(%i2) draw3d(geomap(World_coastlines,
 [conic_projection,0,0,0,1,90]))$

```

See also <http://www.telefonica.net/web2/biomates/maxima/gpdraw/geomap> for more elaborated examples.





## 49 drawdf

### 49.1 Introduction to drawdf

The function **drawdf** draws the direction field of a first-order Ordinary Differential Equation (ODE) or a system of two autonomous first-order ODE's.

Since this is an additional package, in order to use it you must first load it with **load(drawdf)**. Drawdf is built upon the **draw** package, which requires Gnuplot 4.2.

To plot the direction field of a single ODE, the ODE must be written in the form:

$$\frac{dy}{dx} = F(x, y)$$

and the function  $F$  should be given as the argument for **drawdf**. If the independent and dependent variables are not  $x$ , and  $y$ , as in the equation above, then those two variables should be named explicitly in a list given as an argument to the drawdf command (see the examples).

To plot the direction field of a set of two autonomous ODE's, they must be written in the form

$$\frac{dx}{dt} = G(x, y) \quad \frac{dy}{dt} = F(x, y)$$

and the argument for **drawdf** should be a list with the two functions  $G$  and  $F$ , in that order; namely, the first expression in the list will be taken to be the time derivative of the variable represented on the horizontal axis, and the second expression will be the time derivative of the variable represented on the vertical axis. Those two variables do not have to be  $x$  and  $y$ , but if they are not, then the second argument given to drawdf must be another list naming the two variables, first the one on the horizontal axis and then the one on the vertical axis.

If only one ODE is given, **drawdf** will implicitly admit  $x=t$ , and  $G(x,y)=1$ , transforming the non-autonomous equation into a system of two autonomous equations.

### 49.2 Functions and Variables for drawdf

#### 49.2.1 Functions

|                                                                                                                          |          |
|--------------------------------------------------------------------------------------------------------------------------|----------|
| <b>drawdf</b> ( <i>dydx</i> , ... <i>options and objects</i> ...)                                                        | Function |
| <b>drawdf</b> ( <i>dvdu</i> , [ <i>u,v</i> ], ... <i>options and objects</i> ...)                                        | Function |
| <b>drawdf</b> ( <i>dvdu</i> , [ <i>u,umin,umax</i> ], [ <i>v,vmin,vmax</i> ], ... <i>options and objects</i> ...)        | Function |
| <b>drawdf</b> ([ <i>dxdt,dydt</i> ], ... <i>options and objects</i> ...)                                                 | Function |
| <b>drawdf</b> ([ <i>dudt,dvdt</i> ], [ <i>u,v</i> ], ... <i>options and objects</i> ...)                                 | Function |
| <b>drawdf</b> ([ <i>dudt,dvdt</i> ], [ <i>u,umin,umax</i> ], [ <i>v,vmin,vmax</i> ], ... <i>options and objects</i> ...) | Function |

Function **drawdf** draws a 2D direction field with optional solution curves and other graphics using the **draw** package.

The first argument specifies the derivative(s), and must be either an expression or a list of two expressions. *dydx*, *dxdt* and *dydt* are expressions that depend on  $x$  and  $y$ . *dvdu*, *dudt* and *dvdt* are expressions that depend on  $u$  and  $v$ .

If the independent and dependent variables are not  $x$  and  $y$ , then their names must be specified immediately following the derivative(s), either as a list of two names [*u,v*], or as two lists of the form [*u,umin,umax*] and [*v,vmin,vmax*].

The remaining arguments are *graphic options*, *graphic objects*, or lists containing graphic options and objects, nested to arbitrary depth. The set of graphic options and objects supported by **drawdf** is a superset of those supported by **draw2d** and **gr2d** from the **draw** package.

The arguments are interpreted sequentially: *graphic options* affect all following *graphic objects*. Furthermore, *graphic objects* are drawn on the canvas in order specified, and may

obscure graphics drawn earlier. Some *graphic options* affect the global appearance of the scene.

The additional *graphic objects* supported by `drawdf` include: `solns_at`, `points_at`, `saddles_at`, `soln_at`, `point_at`, and `saddle_at`.

The additional *graphic options* supported by `drawdf` include: `field_degree`, `soln_arrows`, `field_arrows`, `field_grid`, `field_color`, `show_field`, `tstep`, `nsteps`, `duration`, `direction`, `field_tstep`, `field_nsteps`, and `field_duration`.

Commonly used *graphic objects* inherited from the `draw` package include: `explicit`, `implicit`, `parametric`, `polygon`, `points`, `vector`, `label`, and all others supported by `draw2d` and `gr2d`.

Commonly used *graphic options* inherited from the `draw` package include: `points_joined`, `color`, `point_type`, `point_size`, `line_width`, `line_type`, `key`, `title`, `xlabel`, `ylabel`, `user_preamble`, `terminal`, `dimensions`, `file_name`, and all others supported by `draw2d` and `gr2d`.

See also `draw2d`.

Users of wxMaxima or IMaxima may optionally use `wxdrawdf`, which is identical to `drawdf` except that the graphics are drawn within the notebook using `wxdraw`.

To make use of this function, write first `load(drawdf)`.

Examples:

```
(%i1) load(drawdf)$
(%i2) drawdf(exp(-x)+y)$ /* default vars: x,y */
(%i3) drawdf(exp(-t)+y, [t,y])$ /* default range: [-10,10] */
(%i4) drawdf([y,-9*sin(x)-y/5], [x,1,5], [y,-2,2])$
```

For backward compatibility, `drawdf` accepts most of the parameters supported by `plotdf`.

```
(%i5) drawdf(2*cos(t)-1+y, [t,y], [t,-5,10], [y,-4,9],
 [trajectory_at,0,0])$
```

`soln_at` and `solns_at` draw solution curves passing through the specified points, using a slightly enhanced 4th-order Runge Kutta numerical integrator.

```
(%i6) drawdf(2*cos(t)-1+y, [t,-5,10], [y,-4,9],
 solns_at([0,0.1],[0,-0.1]),
 color=blue, soln_at(0,0))$
```

`field_degree=2` causes the field to be composed of quadratic splines, based on the first and second derivatives at each grid point. `field_grid=[COLS,ROWS]` specifies the number of columns and rows in the grid.

```
(%i7) drawdf(2*cos(t)-1+y, [t,-5,10], [y,-4,9],
 field_degree=2, field_grid=[20,15],
 solns_at([0,0.1],[0,-0.1]),
 color=blue, soln_at(0,0))$
```

`soln_arrows=true` adds arrows to the solution curves, and (by default) removes them from the direction field. It also changes the default colors to emphasize the solution curves.

```
(%i8) drawdf(2*cos(t)-1+y, [t,-5,10], [y,-4,9],
 soln_arrows=true,
 solns_at([0,0.1],[0,-0.1],[0,0]))$
```

`duration=40` specifies the time duration of numerical integration (default 10). Integration will also stop automatically if the solution moves too far away from the plotted region, or if the derivative becomes complex or infinite. Here we also specify `field_degree=2` to plot quadratic splines. The equations below model a predator-prey system.

```
(%i9) drawdf([x*(1-x-y), y*(3/4-y-x/2)], [x,0,1.1], [y,0,1],
 field_degree=2, duration=40,
 soln_arrows=true, point_at(1/2,1/2),
 solns_at([0.1,0.2], [0.2,0.1], [1,0.8], [0.8,1],
 [0.1,0.1], [0.6,0.05], [0.05,0.4],
 [1,0.01], [0.01,0.75]))$
```

`field_degree='solns` causes the field to be composed of many small solution curves computed by 4th-order Runge Kutta, with better results in this case.

```
(%i10) drawdf([x*(1-x-y), y*(3/4-y-x/2)], [x,0,1.1], [y,0,1],
 field_degree='solns, duration=40,
 soln_arrows=true, point_at(1/2,1/2),
 solns_at([0.1,0.2], [0.2,0.1], [1,0.8],
 [0.8,1], [0.1,0.1], [0.6,0.05],
 [0.05,0.4], [1,0.01], [0.01,0.75]))$
```

`saddles_at` attempts to automatically linearize the equation at each saddle, and to plot a numerical solution corresponding to each eigenvector, including the separatrices. `tstep=0.05` specifies the maximum time step for the numerical integrator (the default is 0.1). Note that smaller time steps will sometimes be used in order to keep the  $x$  and  $y$  steps small. The equations below model a damped pendulum.

```
(%i11) drawdf([y,-9*sin(x)-y/5], tstep=0.05,
 soln_arrows=true, point_size=0.5,
 points_at([0,0], [2*pi,0], [-2*pi,0]),
 field_degree='solns,
 saddles_at([pi,0], [-pi,0]))$
```

`show_field=false` suppresses the field entirely.

```
(%i12) drawdf([y,-9*sin(x)-y/5], tstep=0.05,
 show_field=false, soln_arrows=true,
 point_size=0.5,
 points_at([0,0], [2*pi,0], [-2*pi,0]),
 saddles_at([3*pi,0], [-3*pi,0],
 [pi,0], [-pi,0]))$
```

`drawdf` passes all unrecognized parameters to `draw2d` or `gr2d`, allowing you to combine the full power of the `draw` package with `drawdf`.

```
(%i13) drawdf(x^2+y^2, [x,-2,2], [y,-2,2], field_color=gray,
 key="soln 1", color=black, soln_at(0,0),
 key="soln 2", color=red, soln_at(0,1),
 key="isocline", color=green, line_width=2,
 nticks=100, parametric(cos(t),sin(t),t,0,2*pi))$
```

`drawdf` accepts nested lists of graphic options and objects, allowing convenient use of `makelist` and other function calls to generate graphics.

```
(%i14) colors : ['red','blue','purple','orange','green]$
(%i15) drawdf([x-x*y/2, (x*y - 3*y)/4],
 [x,2.5,3.5], [y,1.5,2.5],
 field_color = gray,
 makelist([key = concat("soln",k),
 color = colors[k],
 soln_at(3, 2 + k/20)],
 k,1,5))$
```



## 50 dynamics

### 50.1 Introduction to dynamics

The additional package **dynamics** includes several functions to create various graphical representations of discrete dynamical systems and fractals, and an implementation of the Runge-Kutta 4th-order numerical method for solving systems of differential equations.

To use the functions in this package you must first load it with `load("dynamics")`.

#### Changes introduced in Maxima 5.12

Starting with Maxima 5.12, the **dynamics** package now uses the function `plot2d` to do the graphs. The commands that produce graphics (with the exception of `julia` and `mandelbrot`) now accept any options of `plot2d`, including the option to change among the various graphical interfaces, using different plot styles and colors, and representing one or both axes in a logarithmic scale. The old options *domain*, *pointsize*, *xcenter*, *xradius*, *ycenter*, *yradius*, *xaxislabel* and *yaxislabel* are not accepted in this new version.

All programs will now accept any variables names, and not just *x* and *y* as in the older versions. Two required parameters have changes in two of the programs: `evolution2d` now requires a list naming explicitly the two independent variables, and the horizontal range for `orbits` no longer requires a step size; the range should only specify the variable name, and the minimum and maximum values; the number of steps can now be changed with the option *nticks*.

### 50.2 Functions and Variables for dynamics

**chaosgame** (`[[x1, y1]...[xm, ym]], [x0, y0], b, n, ..., options, ...`); Function  
 Implements the so-called chaos game: the initial point  $(x_0, y_0)$  is plotted and then one of the  $m$  points  $[x_1, y_1]...[x_m, y_m]$  will be selected at random. The next point plotted will be on the segment from the previous point plotted to the point chosen randomly, at a distance from the random point which will be  $b$  times that segment's length. The procedure is repeated  $n$  times.

**evolution** (`F, y0, n, ..., options, ...`); Function  
 Draws  $n+1$  points in a two-dimensional graph, where the horizontal coordinates of the points are the integers  $0, 1, 2, \dots, n$ , and the vertical coordinates are the corresponding values  $y(n)$  of the sequence defined by the recurrence relation

$$y_{n+1} = F(y_n)$$

With initial value  $y(0)$  equal to  $y_0$ .  $F$  must be an expression that depends only on one variable (in the example, it depend on  $y$ , but any other variable can be used),  $y_0$  must be a real number and  $n$  must be a positive integer.

**evolution2d** (`[F, G], [u, v], [u0, y0], n, ..., options, ...`); Function  
 Shows, in a two-dimensional plot, the first  $n+1$  points in the sequence of points defined by the two-dimensional discrete dynamical system with recurrence relations

$$\begin{cases} u_{n+1} = F(u_n, v_n) \\ v_{n+1} = G(u_n, v_n) \end{cases}$$

With initial values  $u_0$  and  $v_0$ .  $F$  and  $G$  must be two expressions that depend only on two variables,  $u$  and  $v$ , which must be named explicitly in a list.

**ifs** ( $[r1, \dots, rm]$ ,  $[A1, \dots, Am]$ ,  $[[x1, y1], \dots, [xm, ym]]$ ,  $[x0, y0]$ ,  $n$ ,  $\dots$ , *options*, ...); Function

Implements the Iterated Function System method. This method is similar to the method described in the function **chaosgame**, but instead of shrinking the segment from the current point to the randomly chosen point, the 2 components of that segment will be multiplied by the 2 by 2 matrix  $A_i$  that corresponds to the point chosen randomly.

The random choice of one of the  $m$  attractive points can be made with a non-uniform probability distribution defined by the weights  $r1, \dots, rm$ . Those weights are given in cumulative form; for instance if there are 3 points with probabilities 0.2, 0.5 and 0.3, the weights  $r1$ ,  $r2$  and  $r3$  could be 2, 7 and 10.

**julia** ( $x$ ,  $y$ , ...*options*...) Function

Creates a graphics file with the representation of the Julia set for the complex number  $(x + i y)$ . The parameters  $x$  and  $y$  must be real. The file is created in the current directory or in the user's directory, using the XPM graphics format. The program may take several seconds to run and after it is finished, a message will be printed with the name of the file created.

The points which do not belong to the Julia set are assigned different colors, according to the number of iterations it takes the sequence starting at that point to move out of the convergence circle of radius 2. The maximum number of iterations is set with the option *levels*; after that number of iterations, if the sequence is still inside the convergence circle, the point will be painted with the color defined by the option *color*.

All the colors used for the points that do not belong to the Julia set will have the same *saturation* and *value*, but with different hue angles distributed uniformly between *hue* and  $(hue + huerange)$ .

*options* is an optional sequence of options. The list of accepted options is given in a section below.

**mandelbrot** (*options*) Function

Creates a graphics file with the representation of the Mandelbrot set. The file is created in the current directory or in the user's directory, using the XPM graphics format. The program may take several seconds to run and after it is finished, a message will be printed with the name of the file created.

The points which do not belong to the Mandelbrot set are assigned different colors, according to the number of iterations it takes the sequence generated with that point to move out of the convergence circle of radius 2. The maximum number of iterations is set with the option *levels*; after that number of iterations, if the sequence is still inside the convergence circle, the point will be painted with the color defined by the option *color*.

All the colors used for the points that do not belong to the Mandelbrot set will have the same *saturation* and *value*, but with different hue angles distributed uniformly between *hue* and  $(hue + huerange)$ .

*options* is an optional sequence of options. The list of accepted options is given in a section below.

**orbits** ( $F$ ,  $y0$ ,  $n1$ ,  $n2$ ,  $[x, x0, xf, xstep]$ , ...*options*...); Function

Draws the orbits diagram for a family of one-dimensional discrete dynamical systems, with one parameter  $x$ ; that kind of diagram is used to study the bifurcations of a one-dimensional discrete system.

The function  $F(y)$  defines a sequence with a starting value of  $y0$ , as in the case of the function **evolution**, but in this case that function will also depend on a parameter  $x$  that will take values in the interval from  $x0$  to  $xf$  with increments of  $xstep$ . Each value used for the parameter  $x$  is shown on the horizontal axis. The vertical axis will show the  $n2$  values of the sequence  $y(n1+1), \dots, y(n1+n2+1)$  obtained after letting the sequence evolve  $n1$  iterations.

**rk** (*ODE*, *var*, *initial*, *domain*)

Function

**rk** ([*ODE1*, ..., *ODEm*], [*v1*, ..., *vm*], [*init1*, ..., *initm*], *domain*)

Function

The first form solves numerically one first-order ordinary differential equation, and the second form solves a system of *m* of those equations, using the 4th order Runge-Kutta method. *var* represents the dependent variable. *ODE* must be an expression that depends only on the independent and dependent variables and defines the derivative of the dependent variable with respect to the independent variable.

The independent variable is specified with *domain*, which must be a list of four elements as, for instance:

[*t*, 0, 10, 0.1]

the first element of the list identifies the independent variable, the second and third elements are the initial and final values for that variable, and the last element sets the increments that should be used within that interval.

If *m* equations are going to be solved, there should be *m* dependent variables *v1*, *v2*, ..., *vm*. The initial values for those variables will be *init1*, *init2*, ..., *initm*. There will still be just one independent variable defined by *domain*, as in the previous case. *ODE1*, ..., *ODEm* are the expressions that define the derivatives of each dependent variable in terms of the independent variable. The only variables that may appear in those expressions are the independent variable and any of the dependent variables. It is important to give the derivatives *ODE1*, ..., *ODEm* in the list in exactly the same order used for the dependent variables; for instance, the third element in the list will be interpreted as the derivative of the third dependent variable.

The program will try to integrate the equations from the initial value of the independent variable until its last value, using constant increments. If at some step one of the dependent variables takes an absolute value too large, the integration will be interrupted at that point. The result will be a list with as many elements as the number of iterations made. Each element in the results list is itself another list with *m*+1 elements: the value of the independent variable, followed by the values of the dependent variables corresponding to that point.

**staircase** (*F*, *y0*, *n*, ...*options*...);

Function

Draws a staircase diagram for the sequence defined by the recurrence relation

$$y_{n+1} = F(y_n)$$

The interpretation and allowed values of the input parameters is the same as for the function **evolution**. A staircase diagram consists of a plot of the function *F*(*y*), together with the line *G*(*y*) = *y*. A vertical segment is drawn from the point (*y0*, *y0*) on that line until the point where it intersects the function *F*. From that point a horizontal segment is drawn until it reaches the point (*y1*, *y1*) on the line, and the procedure is repeated *n* times until the point (*yn*, *yn*) is reached.

### Options

Each option is a list of two or more items. The first item is the name of the option, and the remainder comprises the arguments for the option.

The options accepted by the functions **evolution**, **evolution2d**, **staircase**, **orbits**, **ifs** and **chaosgame** are the same as the options for **plot2d**. In addition to those options, **orbits** accepts an extra option *pixels* that sets up the maximum number of different points that will be represented in the vertical direction.

The following options are accepted by the functions **julia** and **mandelbrot**:

- *size* takes either one or two arguments. If only one argument is given, the width and height of the graphic file created will be equal to that value, in pixels. If two arguments are given, they will define the width and height. The default value is 400 pixels for both the width and height. If the two values are not equal, the set will appear distorted.
- *levels* defines the maximum number of iterations, which is also equal to the number of colors used for points not belonging to the set. The default value is 12; larger values mean much longer processing times.




- *huerange* defines the range of hue angles used for the hue of points not belonging to the set. The default value is 360, which means that the colors will expand all the range of hues. Values bigger than 360, will mean repeated ranges of the hue, and negative values can be used to make the hue angle decrease as the number of iterations increases.
- *hue* sets the hue, in degrees, of the first color used for the points which do not belong to the set. Its default value is 300 degrees, which corresponds to magenta; the values for other standard colors are 0 for red, 45 for orange, 60 for yellow, 120 for green, 180 for cyan and 240 for blue. See also option *huerange*.
- *saturation* sets the value of the saturation used for points not belonging to the set. It must be between 0 and 1. The default is 0.46.
- *value* sets the value of the colors used for points not belonging to the set. It must be between 0 and 1; the higher the value, the brighter the colors. The default is 0.96
- *color* must be followed by three parameters that define the hue, saturation and value, for the color used to represent the points of the set. The default value is 0 for the three parameters, which corresponds to black. For an explanation of the range of allowed values, see options *hue*, *saturation* and *value*.
- *center* must be followed by two real parameters, which give the coordinates, on the complex plane, of the point in the center of the region shown. The default value is 0 for both coordinates (the origin).
- *radius* sets the radius of the biggest circle inside the square region that will be displayed. The default value is 2.
- *filename* gives the name of the file where the resulting graph will be saved. The extension .xpm will be added to that name. If the file already exists, it will be replaced by the file generated by the function. The default values are *julia* for the Julia set, and *mandelbrot* for the Mandelbrot set.


### Examples

Graphical representation and staircase diagram for the sequence:  $2, \cos(2), \cos(\cos(2)), \dots$

```
(%i1) load("dynamics")$
(%i2) evolution(cos(y), 2, 11);
(%i3) staircase(cos(y), 1, 11, [y, 0, 1.2]);
```








If your system is slow, you'll have to reduce the number of iterations in the following examples. And if the dots appear too small in your monitor, you might want to try a different style, such as `[style,[points,0.8]]`.

Orbits diagram for the quadratic map, with a parameter  $a$ .


$$x_{n+1} = a + x_n^2$$

```
(%i4) orbits(x^2+a, 0, 50, 200, [a, -2, 0.25], [style, dots]);
```



To enlarge the region around the lower bifurcation near  $x = -1.25$  use:

```
(%i5) orbits(x^2+a, 0, 100, 400, [a,-1,-1.53], [x,-1.6,-0.8],
[nticks, 400], [style,dots]);
```




Evolution of a two-dimensional system that leads to a fractal:

```
(%i6) f: 0.6*x*(1+2*x)+0.8*y*(x-1)-y^2-0.9$
```


```
(%i7) g: 0.1*x*(1-6*x+4*y)+0.1*y*(1+9*y)-0.4$
```

```
(%i8) evolution2d([f,g], [x,y], [-0.5,0], 50000, [style,dots]);
```




And an enlargement of a small region in that fractal:

```
(%i9) evolution2d([f,g], [x,y], [-0.5,0], 300000, [x,-0.8,-0.6],
[y,-0.4,-0.2], [style,dots]);
```




A plot of Sierpinsky's triangle, obtained with the chaos game:

```
(%i9) chaosgame([[0, 0], [1, 0], [0.5, sqrt(3)/2]], [0.1, 0.1], 1/2,
30000, [style,dots]);
```




Barnsley's fern, obtained with an Iterated Function System:

```
(%i10) a1: matrix([0.85,0.04],[-0.04,0.85])$
(%i11) a2: matrix([0.2,-0.26],[0.23,0.22])$
(%i12) a3: matrix([-0.15,0.28],[0.26,0.24])$
(%i13) a4: matrix([0,0],[0,0.16])$
(%i14) p1: [0,1.6]$
(%i15) p2: [0,1.6]$
(%i16) p3: [0,0.44]$
(%i17) p4: [0,0]$
(%i18) w: [85,92,99,100]$
(%i19) ifs(w, [a1,a2,a3,a4], [p1,p2,p3,p4], [5,0], 50000, [style,dots]);
```



To create a file named *dynamics9.xpm* with a graphical representation of the Mandelbrot set, with 12 colors, use:


```
mandelbrot([filename,"dynamics9"])$
```



and the Julia set for the number  $(-0.55 + i 0.6)$  can be obtained with:

```
julia(-0.55, 0.6, [levels, 36], [center, 0, 0.6], [radius, 0.3],
 [hue, 240], [huerange, -180], [filename, "dynamics10"])$
```

the graph will be saved in the file *dynamics10.xpm* and will show the region from -0.3 to 0.3 in the x direction, and from 0.3 to 0.9 in the y direction. 36 colors will be used, starting with blue and ending with yellow.



To solve numerically the differential equation

$$\frac{dx}{dt} = t - x^2$$

With initial value  $x(t=0) = 1$ , in the interval of  $t$  from 0 to 8 and with increments of 0.1 for  $t$ , use:

```
(%i20) results: rk(t-x^2,x,1,[t,0,8,0.1])$
```

the results will be saved in the list **results**.

To solve numerically the system:

$$\begin{cases} \frac{dx}{dt} = 4 - x^2 - 4y^2 \\ \frac{dy}{dt} = y^2 - x^2 + 1 \end{cases}$$

for  $t$  between 0 and 4, and with values of -1.25 and 0.75 for  $x$  and  $y$  at  $t=0$ :

```
(%i21) sol: rk([4-x^2-4*y^2,y^2-x^2+1],[x,y],[-1.25,0.75],[t,0,4,0.02])$
```



## 51 ezunits

### 51.1 Introduction to ezunits

**ezunits** is a package for working with dimensional quantities, including some functions for dimensional analysis. **ezunits** can carry out arithmetic operations on dimensional quantities and unit conversions. The built-in units include Systeme Internationale (SI) and US customary units, and other units can be declared. See also **physical\_constants**, a collection of physical constants.

`load(ezunits)` loads this package. `demo(ezunits)` displays several examples. The convenience function `known_units` returns a list of the built-in and user-declared units, while `display_known_unit_conversions` displays the set of known conversions in an easy-to-read format.

An expression  $a^b$  represents a dimensional quantity, with **a** indicating a nondimensional quantity and **b** indicating the dimensional units. A symbol can be used as a unit without declaring it as such; unit symbols need not have any special properties. The quantity and unit of an expression  $a^b$  can be extracted by the `qty` and `units` functions, respectively.

A symbol may be declared to be a dimensional quantity, with specified quantity or specified units or both.

An expression  $a^b \rightarrow c$  converts from unit **b** to unit **c**. **ezunits** has built-in conversions for SI base units, SI derived units, and some non-SI units. Unit conversions not already known to **ezunits** can be declared. The unit conversions known to **ezunits** are specified by the global variable `known_unit_conversions`, which comprises built-in and user-defined conversions. Conversions for products, quotients, and powers of units are derived from the set of known unit conversions.

As Maxima generally prefers exact numbers (integers or rationals) to inexact (float or bigfloat), so **ezunits** preserves exact numbers when they appear in dimensional quantities. All built-in unit conversions are expressed in terms of exact numbers; inexact numbers in declared conversions are coerced to exact.

There is no preferred system for display of units; input units are not converted to other units unless conversion is explicitly indicated. **ezunits** recognizes the prefixes m-, k-, M, and G- (for milli-, kilo-, mega-, and giga-) as applied to SI base units and SI derived units, but such prefixes are applied only when indicated by an explicit conversion.

Arithmetic operations on dimensional quantities are carried out by conventional rules for such operations.

$$(x^a) * (y^b) \text{ is equal to } (x * y)^{(a * b)}.$$

$$(x^a) + (y^a) \text{ is equal to } (x + y)^a.$$

$$(x^a)^y \text{ is equal to } x^{y^a} \text{ when } y \text{ is nondimensional.}$$

**ezunits** does not require that units in a sum have the same dimensions; such terms are not added together, and no error is reported.

**ezunits** includes functions for elementary dimensional analysis, namely the fundamental dimensions and fundamental units of a dimensional quantity, and computation of dimensionless quantities and natural units. The functions for dimensional analysis were adapted from similar functions in another package, written by Barton Willis.

For the purpose of dimensional analysis, a list of fundamental dimensions and an associated list of fundamental units are maintained; by default the fundamental dimensions are length, mass, time, charge, temperature, and quantity, and the fundamental units are the associated SI units, but other fundamental dimensions and units can be declared.

## 51.2 Introduction to `physical_constants`

`physical_constants` is a collection of physical constants, copied from CODATA 2006 recommended values. [1] `load(physical_constants)` loads this package, and loads `ezunits` also, if it is not already loaded.

A physical constant is represented as a symbol which has a property which is the constant value. The constant value is a dimensional quantity, as represented by `ezunits`. The function `constvalue` fetches the constant value; the constant value is not the ordinary value of the symbol, so symbols of physical constants persist in evaluated expressions until their values are fetched by `constvalue`.

`physical_constants` includes some auxiliary information, namely, a description string for each constant, an estimate of the error of its numerical value, and a property for TeX display. To identify physical constants, each symbol has the `physical_constant` property; `propvars(physical_constant)` therefore shows the list of all such symbols.

`physical_constants` comprises the following constants.

|                          |                                    |
|--------------------------|------------------------------------|
| <code>%c</code>          | speed of light in vacuum           |
| <code>%mu_0</code>       | magnetic constant                  |
| <code>%e_0</code>        | electric constant                  |
| <code>%Z_0</code>        | characteristic impedance of vacuum |
| <code>%G</code>          | Newtonian constant of gravitation  |
| <code>%h</code>          | Planck constant                    |
| <code>%h_bar</code>      | Planck constant                    |
| <code>%m_P</code>        | Planck mass                        |
| <code>%T_P</code>        | Planck temperature                 |
| <code>%l_P</code>        | Planck length                      |
| <code>%t_P</code>        | Planck time                        |
| <code>%%e</code>         | elementary charge                  |
| <code>%Phi_0</code>      | magnetic flux quantum              |
| <code>%G_0</code>        | conductance quantum                |
| <code>%K_J</code>        | Josephson constant                 |
| <code>%R_K</code>        | von Klitzing constant              |
| <code>%mu_B</code>       | Bohr magneton                      |
| <code>%mu_N</code>       | nuclear magneton                   |
| <code>%alpha</code>      | fine-structure constant            |
| <code>%R_inf</code>      | Rydberg constant                   |
| <code>%a_0</code>        | Bohr radius                        |
| <code>%E_h</code>        | Hartree energy                     |
| <code>%ratio_h_me</code> | quantum of circulation             |
| <code>%m_e</code>        | electron mass                      |
| <code>%N_A</code>        | Avogadro constant                  |
| <code>%m_u</code>        | atomic mass constant               |
| <code>%F</code>          | Faraday constant                   |
| <code>%R</code>          | molar gas constant                 |
| <code>%%k</code>         | Boltzmann constant                 |





Computing conversions to base units; may take a moment.

```

366838848464007200
(%o5) ----- ' J
 9
(%i6) E ' ' GJ;
458548560580009
(%o6) ----- ' GJ
 11250000
(%i7) float (%);
(%o7) 4.0759872051556356e+7 ' GJ

```

### 51.3 Functions and Variables for ezunits

‘ Operator

The dimensional quantity operator. An expression  $a'b$  represents a dimensional quantity, with  $a$  indicating a nondimensional quantity and  $b$  indicating the dimensional units. A symbol can be used as a unit without declaring it as such; unit symbols need not have any special properties. The quantity and unit of an expression  $a'b$  can be extracted by the `qty` and `units` functions, respectively.

Arithmetic operations on dimensional quantities are carried out by conventional rules for such operations.

$(x'a) * (y'b)$  is equal to  $(x * y)'(a * b)$ .

$(x'a) + (y'a)$  is equal to  $(x + y)'a$ .

$(x'a)^y$  is equal to  $x^y'a^y$  when  $y$  is nondimensional.

`ezunits` does not require that units in a sum have the same dimensions; such terms are not added together, and no error is reported.

`load(ezunits)` enables this operator.

Examples:

SI (Système Internationale) units.

```

(%i1) load (ezunits)$
(%i2) foo : 10 ' m;
(%o2) 10 ' m
(%i3) qty (foo);
(%o3) 10
(%i4) units (foo);
(%o4) m
(%i5) dimensions (foo);
(%o5) length

```

"Customary" units.

```

(%i1) load (ezunits)$
(%i2) bar : x ' acre;
(%o2) x ' acre
(%i3) dimensions (bar);
(%o3) length^2
(%i4) fundamental_units (bar);
(%o4) m^2

```

Units ad hoc.

```

(%i1) load (ezunits)$
(%i2) baz : 3 ' sheep + 8 ' goat + 1 ' horse;
(%o2) 8 ' goat + 3 ' sheep + 1 ' horse
(%i3) subst ([sheep = 3*goat, horse = 10*goat], baz);

```

```
(%o3) 27 ' goat
(%i4) baz2 : 1000'gallon/fortnight;
 gallon
(%o4) 1000 ' -----
 fortnight
(%i5) subst (fortnight = 14*day, baz2);
 500 gallon
(%o5) --- ' -----
 7 day
```

Arithmetic operations on dimensional quantities.

```
(%i1) load (ezunits)$
(%i2) 100 ' kg + 200 ' kg;
(%o2) 300 ' kg
(%i3) 100 ' m^3 - 100 ' m^3;
 3
(%o3) 0 ' m
(%i4) (10 ' kg) * (17 ' m/s^2);
 kg m
(%o4) 170 ' ----
 2
 s
(%i5) (x ' m) / (y ' s);
 x m
(%o5) - ' -
 y s
(%i6) (a ' m)^2;
 2 2
(%o6) a ' m
```

“

Operator

The unit conversion operator. An expression  $a'b'c$  converts from unit  $b$  to unit  $c$ . **ezunits** has built-in conversions for SI base units, SI derived units, and some non-SI units. Unit conversions not already known to **ezunits** can be declared. The unit conversions known to **ezunits** are specified by the global variable **known\_unit\_conversions**, which comprises built-in and user-defined conversions. Conversions for products, quotients, and powers of units are derived from the set of known unit conversions.

There is no preferred system for display of units; input units are not converted to other units unless conversion is explicitly indicated. **ezunits** does not attempt to simplify units by prefixes (milli-, centi-, deci-, etc) unless such conversion is explicitly indicated.

**load(ezunits)** enables this operator.

Examples:

The set of known unit conversions.

```
(%i1) load (ezunits)$
(%i2) display2d : false$
(%i3) known_unit_conversions;
(%o3) {acre = 4840*yard^2,Btu = 1055*J,cfm = feet^3/minute,
 cm = m/100,day = 86400*s,feet = 381*m/1250,ft = feet,
 g = kg/1000,gallon = 757*l/200,GHz = 1000000000*Hz,
 GOhm = 1000000000*Ohm,GPa = 1000000000*Pa,
 GWb = 1000000000*Wb,Gg = 1000000*kg,Gm = 1000000000*m,
 Gmol = 1000000*mol,Gs = 1000000000*s,ha = hectare,
 hectare = 100*m^2,hour = 3600*s,Hz = 1/s,inch = feet/12,
 km = 1000*m,kmol = 1000*mol,ks = 1000*s,l = liter,
 lbf = pound_force,lbm = pound_mass,liter = m^3/1000,
 metric_ton = Mg,mg = kg/1000000,MHz = 1000000*Hz,
 microgram = kg/1000000000,micrometer = m/1000000,
```

```

micron = micrometer,microsecond = s/1000000,
mile = 5280*feet,minute = 60*s,mm = m/1000,
mmol = mol/1000,month = 2629800*s,MOhm = 1000000*Ohm,
MPa = 1000000*Pa,ms = s/1000,MWb = 1000000*Wb,
Mg = 1000*kg,Mm = 1000000*m,Mmol = 1000000000*mol,
Ms = 1000000*s,ns = s/1000000000,ounce = pound_mass/16,
oz = ounce,Ohm = s*J/C^2,
pound_force = 32*ft*pound_mass/s^2,
pound_mass = 200*kg/441,psi = pound_force/inch^2,
Pa = N/m^2,week = 604800*s,Wb = J/A,yard = 3*feet,
year = 31557600*s,C = s*A,F = C^2/J,GA = 1000000000*A,
GC = 1000000000*C,GF = 1000000000*F,GH = 1000000000*H,
GJ = 1000000000*J,GK = 1000000000*K,GN = 1000000000*N,
GS = 1000000000*S,GT = 1000000000*T,GV = 1000000000*V,
GW = 1000000000*W,H = J/A^2,J = m*N,kA = 1000*A,
kC = 1000*C,kF = 1000*F,kH = 1000*H,kHz = 1000*Hz,
kJ = 1000*J,kK = 1000*K,kN = 1000*N,kOhm = 1000*Ohm,
kPa = 1000*Pa,kS = 1000*S,kT = 1000*T,kV = 1000*V,
kW = 1000*W,kWb = 1000*Wb,mA = A/1000,mC = C/1000,
mF = F/1000,mH = H/1000,mHz = Hz/1000,mJ = J/1000,
mK = K/1000,mN = N/1000,mOhm = Ohm/1000,mPa = Pa/1000,
mS = S/1000,mT = T/1000,mV = V/1000,mW = W/1000,
mWb = Wb/1000,MA = 1000000*A,MC = 1000000*C,
MF = 1000000*F,MH = 1000000*H,MJ = 1000000*J,
MK = 1000000*K,MN = 1000000*N,MS = 1000000*S,
MT = 1000000*T,MV = 1000000*V,MW = 1000000*W,
N = kg*m/s^2,R = 5*K/9,S = 1/Ohm,T = J/(m^2*A),V = J/C,
W = J/s}

```

Elementary unit conversions.

```

(%i1) load (ezunits)$
(%i2) 1 ' ft ' ' m;
Computing conversions to base units; may take a moment.

(%o2)
 381
---- ' m
 1250

(%i3) %, numer;
(%o3) 0.3048 ' m

(%i4) 1 ' kg ' ' lbm;

(%o4)
 441
--- ' lbm
 200

(%i5) %, numer;
(%o5) 2.205 ' lbm

(%i6) 1 ' W ' ' Btu/hour;

(%o6)
 720 Btu
--- ' ----
 211 hour

(%i7) %, numer;

(%o7) 3.412322274881517 ' ----
 Btu
 hour

(%i8) 100 ' degC ' ' degF;
(%o8) 212 ' degF
(%i9) -40 ' degF ' ' degC;
(%o9) (- 40) ' degC
(%i10) 1 ' acre*ft ' ' m^3;

```

```

 60228605349 3
(%o10) ----- ' m
 48828125

```

```
(%i11) %, numer;
```

```

 3
(%o11) 1233.48183754752 ' m

```

Coercing quantities in feet and meters to one or the other.

```

(%i1) load (ezunits)$
(%i2) 100 ' m + 100 ' ft;
(%o2) 100 ' m + 100 ' ft
(%i3) (100 ' m + 100 ' ft) ' ' ft;
Computing conversions to base units; may take a moment.

```

```

 163100
(%o3) ----- ' ft
 381

```

```
(%i4) %, numer;
```

```
(%o4) 428.0839895013123 ' ft
```

```
(%i5) (100 ' m + 100 ' ft) ' ' m;
```

```

 3262
(%o5) ---- ' m
 25

```

```
(%i6) %, numer;
```

```
(%o6) 130.48 ' m
```

Dimensional analysis to find fundamental dimensions and fundamental units.

```

(%i1) load (ezunits)$
(%i2) foo : 1 ' acre * ft;
(%o2) 1 ' acre ft
(%i3) dimensions (foo);

```

```

 3
(%o3) length

```

```
(%i4) fundamental_units (foo);
```

```

 3
(%o4) m

```

```
(%i5) foo ' ' m^3;
```

Computing conversions to base units; may take a moment.

```

 60228605349 3
(%o5) ----- ' m
 48828125

```

```
(%i6) %, numer;
```

```

 3
(%o6) 1233.48183754752 ' m

```

Declared unit conversions.

```

(%i1) load (ezunits)$
(%i2) declare_unit_conversion (MMBtu = 10^6*Btu, kW = 1000*W);
(%o2) done
(%i3) declare_unit_conversion (kWh = kW*hour, MWh = 1000*kWh,
 bell = 1800*s);
(%o3) done

```

```

(%i4) 1 ' kW*s ' ' MWh;

```

Computing conversions to base units; may take a moment.

```

 1
(%o4) ----- ' MWh
 3600000

```

```

(%i5) 1 ' kW/m^2 ' ' MMBtu/bell/ft^2;
 1306449 MMBtu

```

```
(%o5) ----- ' -----
 8242187500 2
 bell ft
```

|                                                   |          |
|---------------------------------------------------|----------|
| <b>constvalue</b> ( <i>x</i> )                    | Function |
| <b>declare_constvalue</b> ( <i>a</i> , <i>x</i> ) | Function |
| <b>remove_constvalue</b> ( <i>a</i> )             | Function |

Returns the declared constant value of a symbol, or value of an expression with declared constant values substituted for symbols.

Constant values are declared by **declare\_constvalue**. Note that constant values as recognized by **constvalue** are separate from values declared by **numerval** and recognized by **constantp**.

The **physical\_units** package declares constant values for a number of physical constants.

**remove\_constvalue** reverts the effect of **declare\_constvalue**.

**load(ezunits)** loads these functions.

Examples:

Constant value of a physical constant.

```
(%i1) load (physical_constants)$
(%i2) constvalue (%G);

 3
 m
(%o2) 6.67428 ' -----
 2
 kg s

(%i3) get ('%G, 'description);
(%o3) Newtonian constant of gravitation
```

Declaring a new constant.

```
(%i1) load (ezunits)$
(%i2) declare_constvalue (F00, 100 ' lbm / acre);

 lbm
(%o2) 100 ' ----
 acre

(%i3) F00 * (50 ' acre);
(%o3) 50 F00 ' acre

(%i4) constvalue (%);
(%o4) 5000 ' lbm
```

|                                              |          |
|----------------------------------------------|----------|
| <b>units</b> ( <i>x</i> )                    | Function |
| <b>declare_units</b> ( <i>a</i> , <i>u</i> ) | Function |

Returns the units of a dimensional quantity *x*, or returns 1 if *x* is nondimensional.

*x* may be a literal dimensional expression *a*'*b*, a symbol with declared units via **declare\_units**, or an expression containing either or both of those.

**declare\_units** declares that **units**(*a*) should return *u*, where *u* is an expression.

**load(ezunits)** loads these functions.

Examples:

**units** applied to literal dimensional expressions.

```
(%i1) load (ezunits)$
(%i2) foo : 100 ' kg;
(%o2) 100 ' kg

(%i3) bar : x ' m/s;

 m
(%o3) x ' -
 s

(%i4) units (foo);
```

```

(%o4) kg
(%i5) units (bar);
 m
(%o5) -
 s
(%i6) units (foo * bar);
 kg m
(%o6) ----
 s
(%i7) units (foo / bar);
 kg s
(%o7) ----
 m
(%i8) units (foo^2);
 2
(%o8) kg
units applied to symbols with declared units.
(%i1) load (ezunits)$
(%i2) units (aa);
(%o2) 1
(%i3) declare_units (aa, J);
(%o3) J
(%i4) units (aa);
(%o4) J
(%i5) units (aa^2);
 2
(%o5) J
(%i6) foo : 100 ' kg;
(%o6) 100 ' kg
(%i7) units (aa * foo);
(%o7) kg J

```

**qty (x)**

Function

**declare\_qty (a, x)**

Function

**qty** returns the nondimensional part of a dimensional quantity  $x$ , or returns  $x$  if  $x$  is nondimensional.  $x$  may be a literal dimensional expression  $a'b$ , a symbol with declared quantity, or an expression containing either or both of those.

**declare\_qty** declares that **qty**( $a$ ) should return  $x$ , where  $x$  is a nondimensional quantity.

**load(ezunits)** loads these functions.

Examples:

**qty** applied to literal dimensional expressions.

```

(%i1) load (ezunits)$
(%i2) foo : 100 ' kg;
(%o2) 100 ' kg
(%i3) qty (foo);
(%o3) 100
(%i4) bar : v ' m/s;
 m
(%o4) v ' -
 s
(%i5) foo * bar;
 kg m
(%o5) 100 v ' ----
 s
(%i6) qty (foo * bar);

```

```

(%o6) 100 v
qty applied to symbols with declared quantity.
(%i1) load (ezunits)$
(%i2) declare_qty (aa, xx);
(%o2) xx
(%i3) qty (aa);
(%o3) xx
(%i4) qty (aa^2);
(%o4) 2
 xx
(%i5) foo : 100 ' kg;
(%o5) 100 ' kg
(%i6) qty (aa * foo);
(%o6) 100 xx

```

### **unitp (x)** Function

Returns **true** if  $x$  is a literal dimensional expression, a symbol declared dimensional, or an expression in which the main operator is declared dimensional. **unitp** returns **false** otherwise.

`load(ezunits)` loads this function.

Examples:

**unitp** applied to a literal dimensional expression.

```

(%i1) load (ezunits)$
(%i2) unitp (100 ' kg);
(%o2) true

```

**unitp** applied to a symbol declared dimensional.

```

(%i1) load (ezunits)$
(%i2) unitp (foo);
(%o2) false
(%i3) declare (foo, dimensional);
(%o3) done
(%i4) unitp (foo);
(%o4) true

```

**unitp** applied to an expression in which the main operator is declared dimensional.

```

(%i1) load (ezunits)$
(%i2) unitp (bar (x, y, z));
(%o2) false
(%i3) declare (bar, dimensional);
(%o3) done
(%i4) unitp (bar (x, y, z));
(%o4) true

```

### **declare\_unit\_conversion (u = v, ...)** Function

Appends equations  $u = v, \dots$  to the list of unit conversions known to the unit conversion operator `'`.  $u$  and  $v$  are both multiplicative terms, in which any variables are units, or both literal dimensional expressions.

At present, it is necessary to express conversions such that the left-hand side of each equation is a simple unit (not a multiplicative expression) or a literal dimensional expression with the quantity equal to 1 and the unit being a simple unit. This limitation might be relaxed in future versions.

`known_unit_conversions` is the list of known unit conversions.

`load(ezunits)` loads this function.

Examples:

Unit conversions expressed by equations of multiplicative terms.



```
(%i1) load (ezunits)$
(%i2) declare_unit_conversion (nautical_mile = 1852 * m,
 fortnight = 14 * day);
(%o2)
done
(%i3) 100 ' nautical_mile / fortnight ' m/s;
Computing conversions to base units; may take a moment.
463 m
(%o3) ---- ' -
3024 s
```

Unit conversions expressed by equations of literal dimensional expressions.

```
(%i1) load (ezunits)$
(%i2) declare_unit_conversion (1 ' fluid_ounce = 2 ' tablespoon);
(%o2)
done
(%i3) declare_unit_conversion (1 ' tablespoon = 3 ' teaspoon);
(%o3)
done
(%i4) 15 ' fluid_ounce ' teaspoon;
Computing conversions to base units; may take a moment.
(%o4)
90 ' teaspoon
```

**declare\_dimensions** ( $a_1, d_1, \dots, a_n, d_n$ )

Function

**remove\_dimensions** ( $a_1, \dots, a_n$ )

Function

**declare\_dimensions** declares  $a_1, \dots, a_n$  to have dimensions  $d_1, \dots, d_n$ , respectively.

Each  $a_k$  is a symbol or a list of symbols. If it is a list, then every symbol in  $a_k$  is declared to have dimension  $d_k$ .

**remove\_dimensions** reverts the effect of **declare\_dimensions**.

**load(ezunits)** loads these functions.

Examples:

```
(%i1) load (ezunits) $
(%i2) declare_dimensions ([x, y, z], length, [t, u], time);
(%o2)
done
(%i3) dimensions (y^2/u);
2
length
(%o3) ----
time
(%i4) fundamental_units (y^2/u);
0 errors, 0 warnings
2
m
(%o4) --
s
```

**declare\_fundamental\_dimensions** ( $d_1, d_2, d_3, \dots$ )

Function

**remove\_fundamental\_dimensions** ( $d_1, d_2, d_3, \dots$ )

Function

**fundamental\_dimensions**

Global variable

**declare\_fundamental\_dimensions** declares fundamental dimensions. Symbols  $d_1, d_2, d_3, \dots$  are appended to the list of fundamental dimensions, if they are not already on the list.

**remove\_fundamental\_dimensions** reverts the effect of **declare\_fundamental\_dimensions**.

**fundamental\_dimensions** is the list of fundamental dimensions. By default, the list comprises several physical dimensions.

**load(ezunits)** loads these functions.

Examples:

```
(%i1) load (ezunits) $
(%i2) fundamental_dimensions;
(%o2) [length, mass, time, current, temperature, quantity]
(%i3) declare_fundamental_dimensions (money, cattle, happiness);
(%o3) done
(%i4) fundamental_dimensions;
(%o4) [length, mass, time, current, temperature, quantity,
 money, cattle, happiness]
(%i5) remove_fundamental_dimensions (cattle, happiness);
(%o5) done
(%i6) fundamental_dimensions;
(%o6) [length, mass, time, current, temperature, quantity, money]
```

**declare\_fundamental\_units** ( $u_1, d_1, \dots, u_n, d_n$ ) Function

**remove\_fundamental\_units** ( $u_1, \dots, u_n$ ) Function

**declare\_fundamental\_units** declares  $u_1, \dots, u_n$  to have dimensions  $d_1, \dots, d_n$ , respectively. All arguments must be symbols.

After calling **declare\_fundamental\_units**, **dimensions**( $u_k$ ) returns  $d_k$  for each argument  $u_1, \dots, u_n$ , and **fundamental\_units**( $d_k$ ) returns  $u_k$  for each argument  $d_1, \dots, d_n$ .

**remove\_fundamental\_units** reverts the effect of **declare\_fundamental\_units**.

**load**(ezunits) loads these functions.

Examples:

```
(%i1) load (ezunits) $
(%i2) declare_fundamental_dimensions (money, cattle, happiness);
(%o2) done
(%i3) declare_fundamental_units (dollar, money, goat, cattle,
 smile, happiness);
(%o3) [dollar, goat, smile]
(%i4) dimensions (100 ' dollar/goat/km^2);
 money
(%o4) -----
 2
 cattle length
(%i5) dimensions (x ' smile/kg);
 happiness
(%o5) -----
 mass
(%i6) fundamental_units (money*cattle/happiness);
0 errors, 0 warnings
 dollar goat
(%o6) -----
 smile
```

**dimensions** ( $x$ ) Function

**dimensions\_as\_list** ( $x$ ) Function

**dimensions** returns the dimensions of the dimensional quantity  $x$  as an expression comprising products and powers of base dimensions.

**dimensions\_as\_list** returns the dimensions of the dimensional quantity  $x$  as a list, in which each element is an integer which indicates the power of the corresponding base dimension in the dimensions of  $x$ .

**load**(ezunits) loads these functions.

Examples:

```
(%i1) load (ezunits)$
(%i2) dimensions (1000 ' kg*m^2/s^3);
```

```

 2
 length mass
(%o2) -----
 3
 time
(%i3) declare_units (foo, acre*ft/hour);
 acre ft
(%o3) -----
 hour
(%i4) dimensions (foo);
 3
 length
(%o4) -----
 time

(%i1) load (ezunits)$
(%i2) fundamental_dimensions;
(%o2) [length, mass, time, charge, temperature, quantity]
(%i3) dimensions_as_list (1000 ' kg*m^2/s^3);
(%o3) [2, 1, - 3, 0, 0, 0]
(%i4) declare_units (foo, acre*ft/hour);
 acre ft
(%o4) -----
 hour
(%i5) dimensions_as_list (foo);
(%o5) [3, 0, - 1, 0, 0, 0]

```

**fundamental\_units** ( $x$ )

## Function

**fundamental\_units** ()

## Function

`fundamental_units(x)` returns the units associated with the fundamental dimensions of `x`, as determined by `dimensions(x)`.

$x$  may be a literal dimensional expression  $a^i b$ , a symbol with declared units via `declare_units`, or an expression containing either or both of those.

`fundamental_units()` returns the list of all known fundamental units, as declared by `declare_fundamental_units`.

`load(ezunits)` loads this function.

Examples:

```
(%i1) load (ezunits)$
(%i2) fundamental_units ();
(%o2) [m, kg, s, A, K, mol]
(%i3) fundamental_units (100 ' mile/hour);
(%o3) m
-
s
(%i4) declare_units (aa, g/foot^2);
(%o4) g

2
foot
(%i5) fundamental_units (aa);
(%o5) kg
--
2
m
```

**dimensionless** (*L*)

Function

Returns a basis for the dimensionless quantities which can be formed from a list *L* of dimensional quantities.

`load(ezunits)` loads this function.

Examples:

```
(%i1) load (ezunits) $
(%i2) dimensionless ([x ' m, y ' m/s, z ' s]);
0 errors, 0 warnings
0 errors, 0 warnings
```

```
(%o2)
 y z
[---]
 x
```

Dimensionless quantities derived from fundamental physical quantities. Note that the first element on the list is proportional to the fine-structure constant.

```
(%i1) load (ezunits) $
(%i2) load (physical_constants) $
(%i3) dimensionless([%h_bar, %m_e, %m_P, %%e, %c, %e_0]);
0 errors, 0 warnings
0 errors, 0 warnings
```

```
(%o3)
 2
 %%e %m_e
[-----, ----]
 %c %e_0 %h_bar %m_P
```

**natural\_unit** (*expr*, [*v*<sub>1</sub>, ..., *v*<sub>*n*</sub>])

Function

Finds exponents *e*<sub>1</sub>, ..., *e*<sub>*n*</sub> such that `dimension(expr) = dimension(v1e1 ... vnen)`.

`load(ezunits)` loads this function.

Examples:

## 52 f90

### 52.1 Functions and Variables for f90

**f90** (*expr\_1*, ..., *expr\_n*) Function

Prints one or more expressions *expr\_1*, ..., *expr\_n* as a Fortran 90 program. Output is printed to the standard output.

f90 prints output in the so-called "free form" input format for Fortran 90: there is no special attention to column positions. Long lines are split at a fixed width with the ampersand & continuation character.

load(f90) loads this function. See also the function **fortran**.

Examples:

```
(%i1) load (f90)$
(%i2) foo : expand ((xxx + yyy + 7)^4);
 4 3 3 2 2 2
(%o2) yyy + 4 xxx yyy + 28 yyy + 6 xxx yyy + 84 xxx yyy
 2 3 2
+ 294 yyy + 4 xxx yyy + 84 xxx yyy + 588 xxx yyy + 1372 yyy
 4 3 2
+ xxx + 28 xxx + 294 xxx + 1372 xxx + 2401
(%i3) f90 ('foo = foo);
foo = yyy**4+4*xxx*yyy**3+28*yyy**3+6*xxx**2*yyy**2+84*xxx*yyy**2&
+294*yyy**2+4*xxx**3*yyy+84*xxx**2*yyy+588*xxx*yyy+1372*yyy+xxx**&
4+28*xxx**3+294*xxx**2+1372*xxx+2401
(%o3) false
```

Multiple expressions. Capture standard output into a file via the **with\_stdout** function.

```
(%i1) load (f90)$
(%i2) foo : sin (3*x + 1) - cos (7*x - 2);
(%o2) sin(3 x + 1) - cos(7 x - 2)
(%i3) with_stdout ("foo.f90",
 f90 (x=0.25, y=0.625, 'foo=foo, 'stop, 'end));
(%o3) false
(%i4) printfile ("foo.f90");
x = 0.25
y = 0.625
foo = sin(3*x+1)-cos(7*x-2)
stop
end
(%o4) foo.f90
```





**annuity\_fv** (*rate,FV,num*)

Function

We can calculate the annuity knowing the desired value (future value), it is a constant and periodic payment. *rate* is the interest rate, *FV* is the future value and *num* is the number of periods.

Example:

```
(%i1) load(finance)$
(%i2) annuity_fv(0.12,65000,10);
(%o2) 3703.970670389863
```

**geo\_annuity\_pv** (*rate,growing\_rate,PV,num*)

Function

We can calculate the annuity knowing the present value (like an ammount), in a growing periodic payment. *rate* is the interest rate, *growing\_rate* is the growing rate, *PV* is the present value and *num* is the number of periods.

Example:

```
(%i1) load(finance)$
(%i2) geo_annuity_pv(0.14,0.05,5000,10);
(%o2) 802.6888176505123
```

**geo\_annuity\_fv** (*rate,growing\_rate,FV,num*)

Function

We can calculate the annuity knowing the desired value (future value), in a growing periodic payment. *rate* is the interest rate, *growing\_rate* is the growing rate, *FV* is the future value and *num* is the number of periods.

Example:

```
(%i1) load(finance)$
(%i2) geo_annuity_fv(0.14,0.05,5000,10);
(%o2) 216.5203395312695
```

**amortization** (*rate,ammount,num*)

Function

Amortization table determinated by a specific rate. *rate* is the interest rate, *ammount* is the ammount value, and *num* is the number of periods.

Example:

```
(%i1) load(finance)$
(%i2) amortization(0.05,56000,12)$
```

| "n"    | "Balance" | "Interest" | "Amortization" | "Payment" |
|--------|-----------|------------|----------------|-----------|
| 0.000  | 56000.000 | 0.000      | 0.000          | 0.000     |
| 1.000  | 52481.777 | 2800.000   | 3518.223       | 6318.223  |
| 2.000  | 48787.643 | 2624.089   | 3694.134       | 6318.223  |
| 3.000  | 44908.802 | 2439.382   | 3878.841       | 6318.223  |
| 4.000  | 40836.019 | 2245.440   | 4072.783       | 6318.223  |
| 5.000  | 36559.597 | 2041.801   | 4276.422       | 6318.223  |
| 6.000  | 32069.354 | 1827.980   | 4490.243       | 6318.223  |
| 7.000  | 27354.599 | 1603.468   | 4714.755       | 6318.223  |
| 8.000  | 22404.106 | 1367.730   | 4950.493       | 6318.223  |
| 9.000  | 17206.088 | 1120.205   | 5198.018       | 6318.223  |
| 10.000 | 11748.170 | 860.304    | 5457.919       | 6318.223  |
| 11.000 | 6017.355  | 587.408    | 5730.814       | 6318.223  |
| 12.000 | 0.000     | 300.868    | 6017.355       | 6318.223  |

**arit\_amortization** (*rate,increment,ammount,num*)

Function

The amortization table determinated by a specific rate and with growing payment can be claculated by **arit\_amortization**. Notice that the payment is not constant, it presents an arithmetic growing, increment is then the difference between two consecutive rows in the "Payment" column. *rate* is the interest rate, *increment* is the increment, *ammount* is the ammount value, and *num* is the number of periods.

Example:



```
(%i1) load(finance)$
(%i2) arit_amortization(0.05,1000,56000,12)$
```

| "n"    | "Balance" | "Interest" | "Amortization" | "Payment" |
|--------|-----------|------------|----------------|-----------|
| 0.000  | 56000.000 | 0.000      | 0.000          | 0.000     |
| 1.000  | 57403.679 | 2800.000   | -1403.679      | 1396.321  |
| 2.000  | 57877.541 | 2870.184   | -473.863       | 2396.321  |
| 3.000  | 57375.097 | 2893.877   | 502.444        | 3396.321  |
| 4.000  | 55847.530 | 2868.755   | 1527.567       | 4396.321  |
| 5.000  | 53243.586 | 2792.377   | 2603.945       | 5396.321  |
| 6.000  | 49509.443 | 2662.179   | 3734.142       | 6396.321  |
| 7.000  | 44588.594 | 2475.472   | 4920.849       | 7396.321  |
| 8.000  | 38421.703 | 2229.430   | 6166.892       | 8396.321  |
| 9.000  | 30946.466 | 1921.085   | 7475.236       | 9396.321  |
| 10.000 | 22097.468 | 1547.323   | 8848.998       | 10396.321 |
| 11.000 | 11806.020 | 1104.873   | 10291.448      | 11396.321 |
| 12.000 | -0.000    | 590.301    | 11806.020      | 12396.321 |

**geo\_amortization** (*rate*,*growing\_rate*,*ammount*,*num*) Function

The amortization table determined by rate, ammount, and number of periods can be found by **geo\_amortization**. Notice that the payment is not constant, it presents a geometric growing, *growing\_rate* is then the quotient between two consecutive rows in the "Payment" column. *rate* is the interest rate, *ammount* is the ammount value, and *num* is the number of periods.

Example:

```
(%i1) load(finance)$
(%i2) geo_amortization(0.05,0.03,56000,12)$
```

| "n"    | "Balance" | "Interest" | "Amortization" | "Payment" |
|--------|-----------|------------|----------------|-----------|
| 0.000  | 56000.000 | 0.000      | 0.000          | 0.000     |
| 1.000  | 53365.296 | 2800.000   | 2634.704       | 5434.704  |
| 2.000  | 50435.816 | 2668.265   | 2929.480       | 5597.745  |
| 3.000  | 47191.930 | 2521.791   | 3243.886       | 5765.677  |
| 4.000  | 43612.879 | 2359.596   | 3579.051       | 5938.648  |
| 5.000  | 39676.716 | 2180.644   | 3936.163       | 6116.807  |
| 6.000  | 35360.240 | 1983.836   | 4316.475       | 6300.311  |
| 7.000  | 30638.932 | 1768.012   | 4721.309       | 6489.321  |
| 8.000  | 25486.878 | 1531.947   | 5152.054       | 6684.000  |
| 9.000  | 19876.702 | 1274.344   | 5610.176       | 6884.520  |
| 10.000 | 13779.481 | 993.835    | 6097.221       | 7091.056  |
| 11.000 | 7164.668  | 688.974    | 6614.813       | 7303.787  |
| 12.000 | 0.000     | 358.233    | 7164.668       | 7522.901  |

**saving** (*rate*,*ammount*,*num*) Function

The table that represents the values in a constant and periodic saving can be found by **saving**. *ammount* represents the desired quantity and *num* the number of periods to save.

Example:

```
(%i1) load(finance)$
(%i2) saving(0.15,12000,15)$
```

| "n"   | "Balance" | "Interest" | "Payment" |
|-------|-----------|------------|-----------|
| 0.000 | 0.000     | 0.000      | 0.000     |
| 1.000 | 252.205   | 0.000      | 252.205   |
| 2.000 | 542.240   | 37.831     | 252.205   |
| 3.000 | 875.781   | 81.336     | 252.205   |
| 4.000 | 1259.352  | 131.367    | 252.205   |
| 5.000 | 1700.460  | 188.903    | 252.205   |
| 6.000 | 2207.733  | 255.069    | 252.205   |
| 7.000 | 2791.098  | 331.160    | 252.205   |

|        |           |          |         |
|--------|-----------|----------|---------|
| 8.000  | 3461.967  | 418.665  | 252.205 |
| 9.000  | 4233.467  | 519.295  | 252.205 |
| 10.000 | 5120.692  | 635.020  | 252.205 |
| 11.000 | 6141.000  | 768.104  | 252.205 |
| 12.000 | 7314.355  | 921.150  | 252.205 |
| 13.000 | 8663.713  | 1097.153 | 252.205 |
| 14.000 | 10215.474 | 1299.557 | 252.205 |
| 15.000 | 12000.000 | 1532.321 | 252.205 |

**npv** (*rate, val*) Function  
 Calculates the present value of a value series to evaluate the viability in a project. *flowValues* is a list with the values for each period.

Example:

```
(%i1) load(finance)$
(%i2) npv(0.25, [100, 500, 323, 124, 300]);
(%o2) 714.4703999999999
```

**irr** (*val, IO*) Function  
 IRR (Internal Rate of Return) is the value of rate which makes Net Present Value zero. *flowValues* los valores para cada periodo (para periodos mayores a 0) y *IO* el valor para el periodo cero.

Example:

```
(%i1) load(finance)$
(%i2) res:irr([-5000, 0, 800, 1300, 1500, 2000], 0)$
(%i3) rhs(res[1][1]);
(%o3) .03009250374237132
```

**benefit\_cost** (*rate, input, output*) Function  
 Calculates the ratio Benefit/Cost. Benefit is the Net Present Value (NPV) of the inputs, and Cost is the Net Present Value (NPV) of the outputs. Notice that if there is not an input or output value in a specific period, the input/output would be a zero for that period. *rate* is the interest rate, *input* is a list of input values, and *output* is a list of output values.

Example:

```
(%i1) load(finance)$
(%i2) benefit_cost(0.24, [0, 300, 500, 150], [100, 320, 0, 180]);
(%o2) 1.427249324905784
```

## 54 fractals

### 54.1 Introduction to fractals

This package defines some well known fractals:

- with random IFS (Iterated Function System): the Sierpinsky triangle, a Tree and a Fern
- Complex Fractals: the Mandelbrot and Julia Sets
- the Koch snowflake sets
- Peano maps: the Sierpinski and Hilbert maps

Author: José Ramírez Labrador.

For questions, suggestions and bugs, please feel free to contact me at  
pepe DOT ramirez AAATTT uca DOT es

### 54.2 Definitions for IFS fractals

Some fractals can be generated by iterative applications of contractive affine transformations in a random way; see

Hoggar S. G., "Mathematics for computer graphics", Cambridge University Press 1994.

We define a list with several contractive affine transformations, and we randomly select the transformation in a recursive way. The probability of the choice of a transformation must be related with the contraction ratio.

You can change the transformations and find another fractal

**sierpinski**(*n*) Function  
Sierpinski Triangle: 3 contractive maps; .5 contraction constant and translations; all maps have the same contraction ratio. Argument *n* must be great enough, 10000 or greater.

Example:

```
(%i1) load(fractals)$
(%i2) n: 10000$
(%i3) plot2d([discrete,sierpinski(n)], [style,dots])$
```

**treefale**(*n*) Function  
3 contractive maps all with the same contraction ratio. Argument *n* must be great enough, 10000 or greater.

Example:

```
(%i1) load(fractals)$
(%i2) n: 10000$
(%i3) plot2d([discrete,treefale(n)], [style,dots])$
```

**fern**(*n*) Function  
4 contractive maps, the probability to choice a transformation must be related with the contraction ratio. Argument *n* must be great enough, 10000 or greater.

Example:

```
(%i1) load(fractals)$
(%i2) n: 10000$
(%i3) plot2d([discrete,fern(n)], [style,dots])$
```

### 54.3 Definitions for complex fractals

#### **mandelbrot\_set** (*x*, *y*)

Function

Mandelbrot set.

Example:

This program is time consuming because it must make a lot of operations; the computing time is also related with the number of grid points.

```
(%i1) load(fractals)$
(%i2) plot3d (mandelbrot_set, [x, -2.5, 1], [y, -1.5, 1.5],
 [gnuplot_preamble, "set view map"],
 [gnuplot_pm3d, true],
 [grid, 150, 150])$
```

#### **julia\_set** (*x*, *y*)

Function

Julia sets.

This program is time consuming because it must make a lot of operations; the computing time is also related with the number of grid points.

Example:

```
(%i1) load(fractals)$
(%i2) plot3d (julia_set, [x, -2, 1], [y, -1.5, 1.5],
 [gnuplot_preamble, "set view map"],
 [gnuplot_pm3d, true],
 [grid, 150, 150])$
```

See also `julia_parameter`.

#### **julia\_parameter**

Optional variable

Default value: %i

Complex parameter for Julia fractals. Its default value is %i; we suggest the values  $-.745 + i \cdot .113002$ ,  $-.39054 - i \cdot .58679$ ,  $-.15652 + i \cdot 1.03225$ ,  $-.194 + i \cdot .6557$  and  $.011031 - i \cdot .67037$ .

#### **julia\_sin** (*x*, *y*)

Function

While function `julia_set` implements the transformation `julia_parameter + z^2`, function `julia_sin` implements `julia_parameter * sin(z)`. See source code for more details.

This program runs slowly because it calculates a lot of sines.

Example:

This program is time consuming because it must make a lot of operations; the computing time is also related with the number of grid points.

```
(%i1) load(fractals)$
(%i2) julia_parameter:1+.1*i$
(%i3) plot3d (julia_sin, [x, -2, 2], [y, -3, 3],
 [gnuplot_preamble, "set view map"],
 [gnuplot_pm3d, true],
 [grid, 150, 150])$
```

See also `julia_parameter`.

## 54.4 Definitions for Koch snowflakes

### **snowmap** (*ent*, *nn*)

Function

Koch snowflake sets. Function **snowmap** plots the snow Koch map over the vertex of an initial closed polygonal, in the complex plane. Here the orientation of the polygon is important. Argument *nn* is the number of recursive applications of Koch transformation; *nn* must be small (5 or 6).

Examples:

```
(%i1) load(fractals)$
(%i2) plot2d([discrete,
 snowmap([1,exp(%i*%pi*2/3),exp(-%i*%pi*2/3),1],4)])$
(%i3) plot2d([discrete,
 snowmap([1,exp(-%i*%pi*2/3),exp(%i*%pi*2/3),1],4)])$
(%i4) plot2d([discrete, snowmap([0,1,1+%i,%i,0],4)])$
(%i5) plot2d([discrete, snowmap([0,%i,1+%i,1,0],4)])$
```

## 54.5 Definitions for Peano maps

Continuous curves that cover an area. Warning: the number of points exponentially grows with *n*.

### **hilbertmap** (*nn*)

Function

Hilbert map. Argument *nn* must be small (5, for example). Maxima can crash if *nn* is 7 or greater.

Example:

```
(%i1) load(fractals)$
(%i2) plot2d([discrete,hilbertmap(6)])$
```

### **sierpinski** (*nn*)

Function

Sierpinski map. Argument *nn* must be small (5, for example). Maxima can crash if *nn* is 7 or greater.

Example:

```
(%i1) load(fractals)$
(%i2) plot2d([discrete,sierpinski(6)])$
```



## 55 ggf

### 55.1 Functions and Variables for ggf

#### **GGFINFINITY**

Option variable

Default value: 3

This is an option variable for function **ggf**.

When computing the continued fraction of the generating function, a partial quotient having a degree (strictly) greater than *GGFINFINITY* will be discarded and the current convergent will be considered as the exact value of the generating function; most often the degree of all partial quotients will be 0 or 1; if you use a greater value, then you should give enough terms in order to make the computation accurate enough.

See also **ggf**.

#### **GGFCFMAX**

Option variable

Default value: 3

This is an option variable for function **ggf**.

When computing the continued fraction of the generating function, if no good result has been found (see the *GGFINFINITY* flag) after having computed *GGFCFMAX* partial quotients, the generating function will be considered as not being a fraction of two polynomials and the function will exit. Put freely a greater value for more complicated generating functions.

See also **ggf**.

#### **ggf** (*l*)

Function

Compute the generating function (if it is a fraction of two polynomials) of a sequence, its first terms being given. *l* is a list of numbers.

The solution is returned as a fraction of two polynomials. If no solution has been found, it returns with **done**.

This function is controlled by global variables *GGFINFINITY* and *GGFCFMAX*. See also *GGFINFINITY* and *GGFCFMAX*.

To use this function write first `load("ggf")`.





## 56 graphs

### 56.1 Introduction to graphs

The `graphs` package provides graph and digraph data structure for Maxima. Graphs and digraphs are simple (have no multiple edges nor loops), although digraphs can have a directed edge from  $u$  to  $v$  and a directed edge from  $v$  to  $u$ .

Internally graphs are represented by adjacency lists and implemented as a lisp structures. Vertices are identified by their ids (an id is an integer). Edges/arcs are represented by lists of length 2. Labels can be assigned to vertices of graphs/digraphs and weights can be assigned to edges/arcs of graphs/digraphs.

There is a `draw_graph` function for drawing graphs. Graphs are drawn using a force based vertex positioning algorithm. `draw_graph` can also use graphviz programs available from <http://www.graphviz.org>. `draw_graph` is based on the maxima `draw` package.

To use the `graphs` package, first load it with `load(graphs)`.

### 56.2 Functions and Variables for graphs

#### 56.2.1 Building graphs

|                                                                         |          |
|-------------------------------------------------------------------------|----------|
| <b>create_graph</b> ( <i>v_list</i> , <i>e_list</i> )                   | Function |
| <b>create_graph</b> ( <i>n</i> , <i>e_list</i> )                        | Function |
| <b>create_graph</b> ( <i>v_list</i> , <i>e_list</i> , <i>directed</i> ) | Function |

Creates a new graph on the set of vertices *v\_list* and with edges *e\_list*.

*v\_list* is a list of vertices ( $[v_1, v_2, \dots, v_n]$ ) or a list of vertices together with vertex labels ( $[[v_1, l_1], [v_2, l_2], \dots, [v_n, l_n]]$ ).

*n* is the number of vertices. Vertices will be identified by integers from 0 to  $n-1$ .

*e\_list* is a list of edges ( $[e_1, e_2, \dots, e_m]$ ) or a list of edges together with edge-weights ( $[[e_1, w_1], \dots, [e_m, w_m]]$ ).

If *directed* is not `false`, a directed graph will be returned.

Example 1: create a cycle on 3 vertices:

```
(%i1) load (graphs)$
(%i2) g : create_graph([1,2,3], [[1,2], [2,3], [1,3]])$
(%i3) print_graph(g)$
Graph on 3 vertices with 3 edges.
Adjacencies:
3 : 1 2
2 : 3 1
1 : 3 2
```

Example 2: create a cycle on 3 vertices with edge weights:

```
(%i1) load (graphs)$
(%i2) g : create_graph([1,2,3], [[[1,2], 1.0], [[2,3], 2.0],
 [[1,3], 3.0]])$
(%i3) print_graph(g)$
Graph on 3 vertices with 3 edges.
Adjacencies:
3 : 1 2
2 : 3 1
1 : 3 2
```

Example 3: create a directed graph:

```
(%i1) load (graphs)$
(%i2) d : create_graph(
 [1,2,3,4],
 [
 [1,3], [1,4],
 [2,3], [2,4]
],
 'directed = true)$
(%i3) print_graph(d)$
Digraph on 4 vertices with 4 arcs.
Adjacencies:
 4 :
 3 :
 2 : 4 3
 1 : 4 3
```

**copy\_graph (*g*)**

Function

Returns a copy of the graph *g*.**circulant\_graph (*n*, *d*)**

Function

Returns the circulant graph with parameters *n* and *d*.

Example:

```
(%i1) load (graphs)$
(%i2) g : circulant_graph(10, [1,3])$
(%i3) print_graph(g)$
Graph on 10 vertices with 20 edges.
Adjacencies:
 9 : 2 6 0 8
 8 : 1 5 9 7
 7 : 0 4 8 6
 6 : 9 3 7 5
 5 : 8 2 6 4
 4 : 7 1 5 3
 3 : 6 0 4 2
 2 : 9 5 3 1
 1 : 8 4 2 0
 0 : 7 3 9 1
```

**clebsch\_graph ()**

Function

Returns the Clebsch graph.

**complement\_graph (*g*)**

Function

Returns the complement of the graph *g*.**complete\_bipartite\_graph (*n*, *m*)**

Function

Returns the complete bipartite graph on *n+m* vertices.**complete\_graph (*n*)**

Function

Returns the complete graph on *n* vertices.**cycle\_digraph (*n*)**

Function

Returns the directed cycle on *n* vertices.**cycle\_graph (*n*)**

Function

Returns the cycle on *n* vertices.

|                                                             |          |
|-------------------------------------------------------------|----------|
| <b>cuboctahedron_graph</b> ( $n$ )                          | Function |
| Returns the cuboctahedron graph.                            |          |
| <b>cube_graph</b> ( $n$ )                                   | Function |
| Returns the $n$ -dimensional cube.                          |          |
| <b>dodecahedron_graph</b> ()                                | Function |
| Returns the dodecahedron graph.                             |          |
| <b>empty_graph</b> ( $n$ )                                  | Function |
| Returns the empty graph on $n$ vertices.                    |          |
| <b>flower_snark</b> ( $n$ )                                 | Function |
| Returns the flower graph on $4n$ vertices.                  |          |
| Example:                                                    |          |
| (%i1) load (graphs)\$                                       |          |
| (%i2) f5 : flower_snark(5)\$                                |          |
| (%i3) chromatic_index(f5);                                  |          |
| (%o3)                                                       | 4        |
| <b>from_adjacency_matrix</b> ( $A$ )                        | Function |
| Returns the graph represented by its adjacency matrix $A$ . |          |
| <b>frucht_graph</b> ()                                      | Function |
| Returns the Frucht graph.                                   |          |
| <b>graph_product</b> ( $g1, g1$ )                           | Function |
| Returns the direct product of graphs $g1$ and $g2$ .        |          |
| Example:                                                    |          |
| (%i1) load (graphs)\$                                       |          |
| (%i2) grid : graph_product(path_graph(3), path_graph(4))\$  |          |
| (%i3) draw_graph(grid)\$                                    |          |
| <b>graph_union</b> ( $g1, g1$ )                             | Function |
| Returns the union (sum) of graphs $g1$ and $g2$ .           |          |
| <b>grid_graph</b> ( $n, m$ )                                | Function |
| Returns the $n \times m$ grid.                              |          |
| <b>great_rhombicosidodecahedron_graph</b> ()                | Function |
| Returns the great rhombicosidodecahedron graph.             |          |
| <b>great_rhombicuboctahedron_graph</b> ()                   | Function |
| Returns the great rhombicuboctahedron graph.                |          |
| <b>grotzch_graph</b> ()                                     | Function |
| Returns the Grotzch graph.                                  |          |
| <b>heawood_graph</b> ()                                     | Function |
| Returns the Heawood graph.                                  |          |
| <b>icosahedron_graph</b> ()                                 | Function |
| Returns the icosahedron graph.                              |          |

**icosidodecahedron\_graph ()**

Function

Returns the icosidodecahedron graph.

**induced\_subgraph (V, g)**

Function

Returns the graph induced on the subset  $V$  of vertices of the graph  $g$ .

Example:

```
(%i1) load (graphs)$
(%i2) p : petersen_graph()$
(%i3) V : [0,1,2,3,4]$
(%i4) g : induced_subgraph(V, p)$
(%i5) print_graph(g)$
Graph on 5 vertices with 5 edges.
Adjacencies:
 4 : 3 0
 3 : 2 4
 2 : 1 3
 1 : 0 2
 0 : 1 4
```

**line\_graph (g)**

Function

Returns the line graph of the graph  $g$ .**make\_graph (vrt, f)**

Function

**make\_graph (vrt, f, oriented)**

Function

Creates a graph using a predicate function  $f$ . $vrt$  is a list/set of vertices or an integer. If  $vrt$  is an integer, then vertices of the graph will be integers from 1 to  $vrt$ . $f$  is a predicate function. Two vertices  $a$  and  $b$  will be connected if  $f(a,b)=\text{true}$ .If *directed* is not *false*, then the graph will be directed.

Example 1:

```
(%i1) load(graphs)$
(%i2) g : make_graph(powerset({1,2,3,4,5}, 2), disjointp)$
(%i3) is_isomorphic(g, petersen_graph());
(%o3) true
(%i4) get_vertex_label(1, g);
(%o4) {1, 2}
```

Example 2:

```
(%i1) load(graphs)$
(%i2) f(i, j) := is (mod(j, i)=0)$
(%i3) g : make_graph(20, f, directed=true)$
(%i4) out_neighbors(4, g);
(%o4) [8, 12, 16, 20]
(%i5) in_neighbors(18, g);
(%o5) [1, 2, 3, 6, 9]
```

**mycielski\_graph (g)**

Function

Returns the mycielskian graph of the graph  $g$ .**new\_graph ()**

Function

Returns the graph with no vertices and no edges.

**path\_digraph (n)**

Function

Returns the directed path on  $n$  vertices.

|                                                                                                                                                                                                                          |          |
|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|
| <b>path_graph</b> ( <i>n</i> )                                                                                                                                                                                           | Function |
| Returns the path on <i>n</i> vertices.                                                                                                                                                                                   |          |
| <b>petersen_graph</b> ()                                                                                                                                                                                                 | Function |
| <b>petersen_graph</b> ( <i>n</i> , <i>d</i> )                                                                                                                                                                            | Function |
| Returns the petersen graph $P_{\{n,d\}}$ . The default values for <i>n</i> and <i>d</i> are <b>n=5</b> and <b>d=2</b> .                                                                                                  |          |
| <b>random_bipartite_graph</b> ( <i>a</i> , <i>b</i> , <i>p</i> )                                                                                                                                                         | Function |
| Returns a random bipartite graph on <b>a+b</b> vertices. Each edge is present with probability <i>p</i> .                                                                                                                |          |
| <b>random_digraph</b> ( <i>n</i> , <i>p</i> )                                                                                                                                                                            | Function |
| Returns a random directed graph on <i>n</i> vertices. Each arc is present with probability <i>p</i> .                                                                                                                    |          |
| <b>random_regular_graph</b> ( <i>n</i> )                                                                                                                                                                                 | Function |
| <b>random_regular_graph</b> ( <i>n</i> , <i>d</i> )                                                                                                                                                                      | Function |
| Returns a random <i>d</i> -regular graph on <i>n</i> vertices. The default value for <i>d</i> is <b>d=3</b> .                                                                                                            |          |
| <b>random_graph</b> ( <i>n</i> , <i>p</i> )                                                                                                                                                                              | Function |
| Returns a random graph on <i>n</i> vertices. Each edge is present with probability <i>p</i> .                                                                                                                            |          |
| <b>random_graph1</b> ( <i>n</i> , <i>m</i> )                                                                                                                                                                             | Function |
| Returns a random graph on <i>n</i> vertices and random <i>m</i> edges.                                                                                                                                                   |          |
| <b>random_network</b> ( <i>n</i> , <i>p</i> , <i>w</i> )                                                                                                                                                                 | Function |
| Returns a random network on <i>n</i> vertices. Each arc is present with probability <i>p</i> and has a weight in the range [0, <b>w</b> ]. The function returns a list [ <b>network</b> , <b>source</b> , <b>sink</b> ]. |          |
| Example:                                                                                                                                                                                                                 |          |
| (%i1) load (graphs)\$                                                                                                                                                                                                    |          |
| (%i2) [net, s, t] : random_network(50, 0.2, 10.0);                                                                                                                                                                       |          |
| (%o2) [DIGRAPH, 50, 51]                                                                                                                                                                                                  |          |
| (%i3) max_flow(net, s, t)\$                                                                                                                                                                                              |          |
| (%i4) first(%);                                                                                                                                                                                                          |          |
| (%o4) 27.65981397932507                                                                                                                                                                                                  |          |
| <b>random_tournament</b> ( <i>n</i> )                                                                                                                                                                                    | Function |
| Returns a random tournament on <i>n</i> vertices.                                                                                                                                                                        |          |
| <b>random_tree</b> ( <i>n</i> )                                                                                                                                                                                          | Function |
| Returns a random tree on <i>n</i> vertices.                                                                                                                                                                              |          |
| <b>small_rhombicosidodecahedron_graph</b> ()                                                                                                                                                                             | Function |
| Returns the small rhombicosidodecahedron graph.                                                                                                                                                                          |          |
| <b>small_rhombicuboctahedron_graph</b> ()                                                                                                                                                                                | Function |
| Returns the small rhombicuboctahedron graph.                                                                                                                                                                             |          |
| <b>snub_cube_graph</b> ()                                                                                                                                                                                                | Function |
| Returns the snub cube graph.                                                                                                                                                                                             |          |
| <b>snub_dodecahedron_graph</b> ()                                                                                                                                                                                        | Function |
| Returns the snub dodecahedron graph.                                                                                                                                                                                     |          |
| <b>truncated_cube_graph</b> ()                                                                                                                                                                                           | Function |
| Returns the truncated cube graph.                                                                                                                                                                                        |          |

|                                                               |          |
|---------------------------------------------------------------|----------|
| <b>truncated_dodecahedron_graph</b> ()                        | Function |
| Returns the truncated dodecahedron graph.                     |          |
| <b>truncated_icosahedron_graph</b> ()                         | Function |
| Returns the truncated icosahedron graph.                      |          |
| <b>truncated_tetrahedron_graph</b> ()                         | Function |
| Returns the truncated tetrahedron graph.                      |          |
| <b>tutte_graph</b> ()                                         | Function |
| Returns the Tutte graph.                                      |          |
| <b>underlying_graph</b> ( <i>g</i> )                          | Function |
| Returns the underlying graph of the directed graph <i>g</i> . |          |
| <b>wheel_graph</b> ( <i>n</i> )                               | Function |
| Returns the wheel graph on <i>n+1</i> vertices.               |          |

### 56.2.2 Graph properties

|                                                                                                                                                                                                                                                 |                                                                              |
|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------------------------------------------------------------|
| <b>adjacency_matrix</b> ( <i>gr</i> )                                                                                                                                                                                                           | Function                                                                     |
| Returns the adjacency matrix of the graph <i>gr</i> .                                                                                                                                                                                           |                                                                              |
| Example:                                                                                                                                                                                                                                        |                                                                              |
| <pre>(%i1) load (graphs)\$ (%i2) c5 : cycle_graph(4)\$ (%i3) adjacency_matrix(c5);</pre>                                                                                                                                                        | <pre>[ 0  1  0  1 ] [ [ 1  0  1  0 ] [ [ 0  1  0  1 ] [ [ 1  0  1  0 ]</pre> |
| <b>average_degree</b> ( <i>gr</i> )                                                                                                                                                                                                             | Function                                                                     |
| Returns the average degree of vertices in the graph <i>gr</i> .                                                                                                                                                                                 |                                                                              |
| Example:                                                                                                                                                                                                                                        |                                                                              |
| <pre>(%i1) load (graphs)\$ (%i2) average_degree(grotzch_graph());</pre>                                                                                                                                                                         | <pre>40 -- 11</pre>                                                          |
| <b>biconnected_components</b> ( <i>gr</i> )                                                                                                                                                                                                     | Function                                                                     |
| Returns the (vertex sets of) 2-connected components of the graph <i>gr</i> .                                                                                                                                                                    |                                                                              |
| Example:                                                                                                                                                                                                                                        |                                                                              |
| <pre>(%i1) load (graphs)\$ (%i2) g : create_graph(       [1,2,3,4,5,6,7],       [         [1,2],[2,3],[2,4],[3,4],         [4,5],[5,6],[4,6],[6,7]       ]) (%i3) biconnected_components(g); (%o3) [[6, 7], [4, 5, 6], [1, 2], [2, 3, 4]]</pre> |                                                                              |

**bipartition** (*gr*)

Function

Returns a bipartition of the vertices of the graph *gr* or an empty list if *gr* is not bipartite.

Example:

```
(%i1) load (graphs)$
(%i2) h : heawood_graph()$
(%i3) [A,B]:bipartition(h);
(%o3) [[8, 12, 6, 10, 0, 2, 4], [13, 5, 11, 7, 9, 1, 3]]
(%i4) draw_graph(h, show_vertices=A, program=circular)$
```

**chromatic\_index** (*gr*)

Function

Returns the chromatic index of the graph *gr*.

Example:

```
(%i1) load (graphs)$
(%i2) p : petersen_graph()$
(%i3) chromatic_index(p);
(%o3) 4
```

**chromatic\_number** (*gr*)

Function

Returns the chromatic number of the graph *gr*.

Example:

```
(%i1) load (graphs)$
(%i2) chromatic_number(cycle_graph(5));
(%o2) 3
(%i3) chromatic_number(cycle_graph(6));
(%o3) 2
```

**clear\_edge\_weight** (*e*, *gr*)

Function

Removes the weight of the edge *e* in the graph *gr*.

Example:

```
(%i1) load (graphs)$
(%i2) g : create_graph(3, [[0,1], 1.5], [[1,2], 1.3])$
(%i3) get_edge_weight([0,1], g);
(%o3) 1.5
(%i4) clear_edge_weight([0,1], g)$
(%i5) get_edge_weight([0,1], g);
(%o5) 1
```

**clear\_vertex\_label** (*v*, *gr*)

Function

Removes the label of the vertex *v* in the graph *gr*.

Example:

```
(%i1) load (graphs)$
(%i2) g : create_graph([[0,"Zero"], [1, "One"]], [[0,1]])$
(%i3) get_vertex_label(0, g);
(%o3) Zero
(%i4) clear_vertex_label(0, g);
(%o4) done
(%i5) get_vertex_label(0, g);
(%o5) false
```

**connected\_components** (*gr*)

Function

Returns the (vertex sets of) connected components of the graph *gr*.

Example:

```
(%i1) load (graphs)$
(%i2) g: graph_union(cycle_graph(5), path_graph(4))$
(%i3) connected_components(g);
(%o3) [[1, 2, 3, 4, 0], [8, 7, 6, 5]]
```

**diameter** (*gr*) Function

Returns the diameter of the graph *gr*.

Example:

```
(%i1) load (graphs)$
(%i2) diameter(dodecahedron_graph());
(%o2) 5
```

**edge\_coloring** (*gr*) Function

Returns an optimal coloring of the edges of the graph *gr*.

The function returns the chromatic index and a list representing the coloring of the edges of *gr*.

Example:

```
(%i1) load (graphs)$
(%i2) p : petersen_graph()$
(%i3) [ch_index, col] : edge_coloring(p);
(%o3) [4, [[0, 5], 3], [[5, 7], 1], [[0, 1], 1], [[1, 6], 2],
[[6, 8], 1], [[1, 2], 3], [[2, 7], 4], [[7, 9], 2], [[2, 3], 2],
[[3, 8], 3], [[5, 8], 2], [[3, 4], 1], [[4, 9], 4], [[6, 9], 3],
[[0, 4], 2]]]
(%i4) assoc([0,1], col);
(%o4) 1
(%i5) assoc([0,5], col);
(%o5) 3
```

**degree\_sequence** (*gr*) Function

Returns the list of vertex degrees of the graph *gr*.

Example:

```
(%i1) load (graphs)$
(%i2) degree_sequence(random_graph(10, 0.4));
(%o2) [2, 2, 2, 2, 2, 2, 3, 3, 3, 3]
```

**edge\_connectivity** (*gr*) Function

Returns the edge-connectivity of the graph *gr*.

See also `min_edge_cut`.

**edges** (*gr*) Function

Returns the list of edges (arcs) in a (directed) graph *gr*.

Example:

```
(%i1) load (graphs)$
(%i2) edges(complete_graph(4));
(%o2) [[2, 3], [1, 3], [1, 2], [0, 3], [0, 2], [0, 1]]
```

**get\_edge\_weight** (*e*, *gr*) Function

**get\_edge\_weight** (*e*, *gr*, *ifnot*) Function

Returns the weight of the edge *e* in the graph *gr*.

If there is no weight assigned to the edge, the function returns 1. If the edge is not present in the graph, the function signals an error or returns the optional argument *ifnot*.

Example:

```
(%i1) load (graphs)$
(%i2) c5 : cycle_graph(5)$
(%i3) get_edge_weight([1,2], c5);
(%o3) 1
(%i4) set_edge_weight([1,2], 2.0, c5);
(%o4) done
(%i5) get_edge_weight([1,2], c5);
(%o5) 2.0
```



**get\_vertex\_label** (*v*, *gr*)

Function

Returns the label of the vertex *v* in the graph *gr*.

Example:

```
(%i1) load (graphs)$
(%i2) g : create_graph([[0,"Zero"], [1, "One"]], [[0,1]])$
(%i3) get_vertex_label(0, g);
(%o3) Zero
```

**graph\_charpoly** (*gr*, *x*)

Function

Returns the characteristic polynomial (in variable *x*) of the graph *gr*.

Example:

```
(%i1) load (graphs)$
(%i2) p : petersen_graph()$
(%i3) graph_charpoly(p, x), factor;
(%o3) 5 4
 (x - 3) (x - 1) (x + 2)
```

**graph\_center** (*gr*)

Function

Returns the center of the graph *gr*.

Example:

```
(%i1) load (graphs)$
(%i2) g : grid_graph(5,5)$
(%i3) graph_center(g);
(%o3) [12]
```

**graph\_eigenvalues** (*gr*)

Function

Returns the eigenvalues of the graph *gr*. The function returns eigenvalues in the same format as maxima **eigenvalue** function.

Example:

```
(%i1) load (graphs)$
(%i2) p : petersen_graph()$
(%i3) graph_eigenvalues(p);
(%o3) [[3, - 2, 1], [1, 4, 5]]
```

**graph\_periphery** (*gr*)

Function

Returns the periphery of the graph *gr*.

Example:

```
(%i1) load (graphs)$
(%i2) g : grid_graph(5,5)$
(%i3) graph_periphery(g);
(%o3) [24, 20, 4, 0]
```

**graph\_size** (*gr*)

Function

Returns the number of edges in the graph *gr*.

Example:

```
(%i1) load (graphs)$
(%i2) p : petersen_graph()$
(%i3) graph_size(p);
(%o3) 15
```

**graph\_order** (*gr*)

Function

Returns the number of vertices in the graph *gr*.

Example:

```
(%i1) load (graphs)$
(%i2) p : petersen_graph()$
(%i3) graph_order(p);
(%o3) 10
```

**girth** (*gr*)

Function

Returns the length of the shortest cycle in *gr*.

Example:

```
(%i1) load (graphs)$
(%i2) g : heawood_graph()$
(%i3) girth(g);
(%o3) 6
```

**hamilton\_cycle** (*gr*)

Function

Returns the Hamilton cycle of the graph *gr* or an empty list if *gr* is not hamiltonian.

Example:

```
(%i1) load (graphs)$
(%i2) c : cube_graph(3)$
(%i3) hc : hamilton_cycle(c);
(%o3) [7, 3, 2, 6, 4, 0, 1, 5, 7]
(%i4) draw_graph(c, show_edges=vertices_to_cycle(hc))$
```

**hamilton\_path** (*gr*)

Function

Returns the Hamilton path of the graph *gr* or an empty list if *gr* does not have a Hamilton path.

Example:

```
(%i1) load (graphs)$
(%i2) p : petersen_graph()$
(%i3) hp : hamilton_path(p);
(%o3) [0, 5, 7, 2, 1, 6, 8, 3, 4, 9]
(%i4) draw_graph(p, show_edges=vertices_to_path(hp))$
```

**isomorphism** (*gr1*, *gr2*)

Function

Returns a an isomorphism between graphs/digraphs *gr1* and *gr2*. If *gr1* and *gr2* are not isomorphic, it returns an empty list.

Example:

```
(%i1) load (graphs)$
(%i2) clk5:complement_graph(line_graph(complete_graph(5)))$
(%i3) isomorphism(clk5, petersen_graph());
(%o3) [9 -> 0, 2 -> 1, 6 -> 2, 5 -> 3, 0 -> 4, 1 -> 5, 3 -> 6,
 4 -> 7, 7 -> 8, 8 -> 9]
```

**in\_neighbors** (*v*, *gr*)

Function

Returns the list of in-neighbors of the vertex *v* in the directed graph *gr*.

Example:

```
(%i1) load (graphs)$
(%i2) p : path_digraph(3)$
(%i3) in_neighbors(2, p);
(%o3) [1]
(%i4) out_neighbors(2, p);
(%o4) []
```

**is\_biconnected** (*gr*)

Function

Returns **true** if *gr* is 2-connected and **false** otherwise.

Example:

```
(%i1) load (graphs)$
(%i2) is_biconnected(cycle_graph(5));
(%o2) true
(%i3) is_biconnected(path_graph(5));
(%o3) false
```

**is\_bipartite** (*gr*)

Function

Returns **true** if *gr* is bipartite (2-colorable) and **false** otherwise.

Example:

```
(%i1) load (graphs)$
(%i2) is_bipartite(petersen_graph());
(%o2) false
(%i3) is_bipartite(heawood_graph());
(%o3) true
```

**is\_connected** (*gr*)

Function

Returns **true** if the graph *gr* is connected and **false** otherwise.

Example:

```
(%i1) load (graphs)$
(%i2) is_connected(graph_union(cycle_graph(4), path_graph(3)));
(%o2) false
```

**is\_digraph** (*gr*)

Function

Returns **true** if *gr* is a directed graph and **false** otherwise.

Example:

```
(%i1) load (graphs)$
(%i2) is_digraph(path_graph(5));
(%o2) false
(%i3) is_digraph(path_digraph(5));
(%o3) true
```

**is\_edge\_in\_graph** (*e*, *gr*)

Function

Returns **true** if *e* is an edge (arc) in the (directed) graph *g* and **false** otherwise.

Example:

```
(%i1) load (graphs)$
(%i2) c4 : cycle_graph(4)$
(%i3) is_edge_in_graph([2,3], c4);
(%o3) true
(%i4) is_edge_in_graph([3,2], c4);
(%o4) true
(%i5) is_edge_in_graph([2,4], c4);
(%o5) false
(%i6) is_edge_in_graph([3,2], cycle_digraph(4));
(%o6) false
```

**is\_graph** (*gr*)

Function

Returns **true** if *gr* is a graph and **false** otherwise.

Example:

```
(%i1) load (graphs)$
(%i2) is_graph(path_graph(5));
(%o2) true
(%i3) is_graph(path_digraph(5));
(%o3) false
```

**is\_graph\_or\_digraph** (*gr*)

Function

Returns **true** if *gr* is a graph or a directed graph and **false** otherwise.

Example:

```
(%i1) load (graphs)$
(%i2) is_graph_or_digraph(path_graph(5));
(%o2) true
(%i3) is_graph_or_digraph(path_digraph(5));
(%o3) true
```

**is\_isomorphic** (*gr1*, *gr2*)

Function

Returns **true** if graphs/digraphs *gr1* and *gr2* are isomorphic and **false** otherwise.See also **isomorphism**.

Example:

```
(%i1) load (graphs)$
(%i2) clk5:complement_graph(line_graph(complete_graph(5)))$
(%i3) is_isomorphic(clk5, petersen_graph());
(%o3) true
```

**is\_planar** (*gr*)

Function

Returns **true** if *gr* is a planar graph and **false** otherwise.

The algorithm used is the Demoucron's algorithm, which is a quadratic time algorithm.

Example:

```
(%i1) load (graphs)$
(%i2) is_planar(dodecahedron_graph());
(%o2) true
(%i3) is_planar(petersen_graph());
(%o3) false
(%i4) is_planar(petersen_graph(10,2));
(%o4) true
```

**is\_sconnected** (*gr*)

Function

Returns **true** if the directed graph *gr* is strongly connected and **false** otherwise.

Example:

```
(%i1) load (graphs)$
(%i2) is_sconnected(cycle_digraph(5));
(%o2) true
(%i3) is_sconnected(path_digraph(5));
(%o3) false
```

**is\_vertex\_in\_graph** (*v*, *gr*)

Function

Returns **true** if *v* is a vertex in the graph *g* and **false** otherwise.

Example:

```
(%i1) load (graphs)$
(%i2) c4 : cycle_graph(4)$
(%i3) is_vertex_in_graph(0, c4);
(%o3) true
(%i4) is_vertex_in_graph(6, c4);
(%o4) false
```

**is\_tree** (*gr*)

Function

Returns **true** if *gr* is a tree and **false** otherwise.

Example:

```
(%i1) load (graphs)$
(%i2) is_tree(random_tree(4));
(%o2) true
(%i3) is_tree(graph_union(random_tree(4), random_tree(5)));
(%o3) false
```

**laplacian\_matrix** (*gr*)

Function

Returns the laplacian matrix of the graph *gr*.

Example:

```
(%i1) load (graphs)$
(%i2) laplacian_matrix(cycle_graph(5));
 [2 -1 0 0 -1]
 [2 -1 0 0]
 [-1 2 -1 0 0]
 [0 2 -1 0]
(%o2) [0 -1 2 -1 0]
 [0 2 -1 0]
 [0 0 -1 2 -1]
 [0 2 -1 0]
 [-1 0 0 -1 2]
```

**max\_clique** (*gr*)

Function

Returns a maximum clique of the graph *gr*.

Example:

```
(%i1) load (graphs)$
(%i2) g : random_graph(100, 0.5)$
(%i3) max_clique(g);
(%o3) [6, 12, 31, 36, 52, 59, 62, 63, 80]
```

**max\_degree** (*gr*)

Function

Returns the maximal degree of vertices of the graph *gr* and a vertex of maximal degree.

Example:

```
(%i1) load (graphs)$
(%i2) g : random_graph(100, 0.02)$
(%i3) max_degree(g);
(%o3) [6, 79]
(%i4) vertex_degree(95, g);
(%o4) 2
```

**max\_flow** (*net*, *s*, *t*)

Function

Returns a maximum flow through the network *net* with the source *s* and the sink *t*.

The function returns the value of the maximal flow and a list representing the weights of the arcs in the optimal flow.

Example:

```
(%i1) load (graphs)$
(%i2) net : create_graph(
 [1,2,3,4,5,6],
 [[1,2], 1.0],
 [[1,3], 0.3],
 [[2,4], 0.2],
 [[2,5], 0.3],
 [[3,4], 0.1],
 [[3,5], 0.1],
 [[4,6], 1.0],
```

```

 [[5,6], 1.0]],
 directed=true)$
(%i3) [flow_value, flow] : max_flow(net, 1, 6);
(%o3) [0.7, [[[1, 2], 0.5], [[1, 3], 0.2], [[2, 4], 0.2],
[[2, 5], 0.3], [[3, 4], 0.1], [[3, 5], 0.1], [[4, 6], 0.3],
[[5, 6], 0.4]]]
(%i4) f1 : 0$
(%i5) for u in out_neighbors(1, net)
 do f1 : f1 + assoc([1, u], flow)$
(%i6) f1;
(%o6)
 0.7

```

**max\_independent\_set** (*gr*)

Function

Returns a maximum independent set of the graph *gr*.

Example:

```

(%i1) load (graphs)$
(%i2) d : dodecahedron_graph()$
(%i3) mi : max_independent_set(d);
(%o3)
 [0, 3, 5, 9, 10, 11, 18, 19]
(%i4) draw_graph(d, show_vertices=mi)$

```

**max\_matching** (*gr*)

Function

Returns a maximum matching of the graph *gr*.

Example:

```

(%i1) load (graphs)$
(%i2) d : dodecahedron_graph()$
(%i3) m : max_matching(d);
(%o3) [[5, 7], [8, 9], [6, 10], [14, 19], [13, 18], [12, 17],
 [11, 16], [0, 15], [3, 4], [1, 2]]
(%i4) draw_graph(d, show_edges=m)$

```

**min\_degree** (*gr*)

Function

Returns the minimum degree of vertices of the graph *gr* and a vertex of minimum degree.

Example:

```

(%i1) load (graphs)$
(%i2) g : random_graph(100, 0.1)$
(%i3) min_degree(g);
(%o3)
 [3, 49]
(%i4) vertex_degree(21, g);
(%o4)
 9

```

**min\_edge\_cut** (*gr*)

Function

Returns the minimum edge cut in the graph *gr*.See also `edge_connectivity`.**min\_vertex\_cover** (*gr*)

Function

Returns the minimum vertex cover of the graph *gr*.**min\_vertex\_cut** (*gr*)

Function

Returns the minimum vertex cut in the graph *gr*.See also `vertex_connectivity`.**minimum\_spanning\_tree** (*gr*)

Function

Returns the minimum spanning tree of the graph *gr*.

Example:

```
(%i1) load (graphs)$
(%i2) g : graph_product(path_graph(10), path_graph(10))$
(%i3) t : minimum_spanning_tree(g)$
(%i4) draw_graph(g, show_edges=edges(t))$
```

**neighbors** (*v*, *gr*)

Function

Returns the list of neighbors of the vertex *v* in the graph *gr*.

Example:

```
(%i1) load (graphs)$
(%i2) p : petersen_graph()$
(%i3) neighbors(3, p);
(%o3) [4, 8, 2]
```

**odd\_girth** (*gr*)

Function

Returns the length of the shortest odd cycle in the graph *gr*.

Example:

```
(%i1) load (graphs)$
(%i2) g : graph_product(cycle_graph(4), cycle_graph(7))$
(%i3) girth(g);
(%o3) 4
(%i4) odd_girth(g);
(%o4) 7
```

**out\_neighbors** (*v*, *gr*)

Function

Returns the list of out-neighbors of the vertex *v* in the directed graph *gr*.

Example:

```
(%i1) load (graphs)$
(%i2) p : path_digraph(3)$
(%i3) in_neighbors(2, p);
(%o3) [1]
(%i4) out_neighbors(2, p);
(%o4) []
```

**planar\_embedding** (*gr*)

Function

Returns the list of facial walks in a planar embedding of *gr* and **false** if *gr* is not a planar graph.

The graph *gr* must be biconnected.

The algorithm used is the Demoucron's algorithm, which is a quadratic time algorithm.

Example:

```
(%i1) load (graphs)$
(%i2) planar_embedding(grid_graph(3,3));
(%o2) [[3, 6, 7, 8, 5, 2, 1, 0], [4, 3, 0, 1], [3, 4, 7, 6],
 [8, 7, 4, 5], [1, 2, 5, 4]]
```

**print\_graph** (*gr*)

Function

Prints some information about the graph *gr*.

Example:

```
(%i1) load (graphs)$
(%i2) c5 : cycle_graph(5)$
(%i3) print_graph(c5)$
Graph on 5 vertices with 5 edges.
Adjacencies:
 4 : 0 3
 3 : 4 2
```

```

 2 : 3 1
 1 : 2 0
 0 : 4 1
(%i4) dc5 : cycle_digraph(5)$
(%i5) print_graph(dc5)$
Digraph on 5 vertices with 5 arcs.
Adjacencies:
 4 : 0
 3 : 4
 2 : 3
 1 : 2
 0 : 1
(%i6) out_neighbors(0, dc5);
(%o6) [1]

```

**radius** (*gr*)

Function

Returns the radius of the graph *gr*.

Example:

```

(%i1) load (graphs)$
(%i2) radius(dodecahedron_graph());
(%o2) 5

```

**set\_edge\_weight** (*e*, *w*, *gr*)

Function

Assigns the weight *w* to the edge *e* in the graph *gr*.

Example:

```

(%i1) load (graphs)$
(%i2) g : create_graph([1, 2], [[[1,2], 1.2]])$
(%i3) get_edge_weight([1,2], g);
(%o3) 1.2
(%i4) set_edge_weight([1,2], 2.1, g);
(%o4) done
(%i5) get_edge_weight([1,2], g);
(%o5) 2.1

```

**set\_vertex\_label** (*v*, *l*, *gr*)

Function

Assigns the label *l* to the vertex *v* in the graph *gr*.

Example:

```

(%i1) load (graphs)$
(%i2) g : create_graph([1, "One"], [2, "Two"], [[1,2]])$
(%i3) get_vertex_label(1, g);
(%o3) One
(%i4) set_vertex_label(1, "oNE", g);
(%o4) done
(%i5) get_vertex_label(1, g);
(%o5) oNE

```

**shortest\_path** (*u*, *v*, *gr*)

Function

Returns the shortest path from *u* to *v* in the graph *gr*.

Example:

```

(%i1) load (graphs)$
(%i2) d : dodecahedron_graph()$
(%i3) path : shortest_path(0, 7, d);
(%o3) [0, 1, 19, 13, 7]
(%i4) draw_graph(d, show_edges=vertices_to_path(path))$

```



**shortest\_weighted\_path** (*u*, *v*, *gr*) Function

Returns the length of the shortest weighted path and the shortest weighted path from *u* to *v* in the graph *gr*.

The length of a weighted path is the sum of edge weights of edges in the path. If an edge has no weight, then it has a default weight 1.

Example:

```
(%i1) load (graphs)$
(%i2) g: petersen_graph(20, 2)$
(%i3) for e in edges(g) do set_edge_weight(e, random(1.0), g)$
(%i4) shortest_weighted_path(0, 10, g);
(%o4) [2.575143920268482, [0, 20, 38, 36, 34, 32, 30, 10]]
```

**strong\_components** (*gr*) Function

Returns the strong components of a directed graph *gr*.

Example:

```
(%i1) load (graphs)$
(%i2) t : random_tournament(4)$
(%i3) strong_components(t);
(%o3) [[1], [0], [2], [3]]
(%i4) vertex_out_degree(3, t);
(%o4) 3
```

**topological\_sort** (*dag*) Function

Returns a topological sorting of the vertices of a directed graph *dag* or an empty list if *dag* is not a directed acyclic graph.

Example:

```
(%i1) load (graphs)$
(%i2) g:create_graph(
 [1,2,3,4,5],
 [
 [1,2], [2,5], [5,3],
 [5,4], [3,4], [1,3]
],
 directed=true)$
(%i3) topological_sort(g);
(%o3) [1, 2, 5, 3, 4]
```

**vertex\_connectivity** (*g*) Function

Returns the vertex connectivity of the graph *g*.

See also `min_vertex_cut`.

**vertex\_degree** (*v*, *gr*) Function

Returns the degree of the vertex *v* in the graph *gr*.

**vertex\_distance** (*u*, *v*, *gr*) Function

Returns the length of the shortest path between *u* and *v* in the (directed) graph *gr*.

Example:

```
(%i1) load (graphs)$
(%i2) d : dodecahedron_graph()$
(%i3) vertex_distance(0, 7, d);
(%o3) 4
(%i4) shortest_path(0, 7, d);
(%o4) [0, 1, 19, 13, 7]
```

**vertex\_eccentricity** (*v*, *gr*)

Function

Returns the eccentricity of the vertex *v* in the graph *gr*.

Example:

```
(%i1) load (graphs)$
(%i2) g:cycle_graph(7)$
(%i3) vertex_eccentricity(0, g);
(%o3) 3
```

**vertex\_in\_degree** (*v*, *gr*)

Function

Returns the in-degree of the vertex *v* in the directed graph *gr*.

Example:

```
(%i1) load (graphs)$
(%i2) p5 : path_digraph(5)$
(%i3) print_graph(p5)$
Digraph on 5 vertices with 4 arcs.
Adjacencies:
 4 :
 3 : 4
 2 : 3
 1 : 2
 0 : 1
(%i4) vertex_in_degree(4, p5);
(%o4) 1
(%i5) in_neighbors(4, p5);
(%o5) [3]
```

**vertex\_out\_degree** (*v*, *gr*)

Function

Returns the out-degree of the vertex *v* in the directed graph *gr*.

Example:

```
(%i1) load (graphs)$
(%i2) t : random_tournament(10)$
(%i3) vertex_out_degree(0, t);
(%o3) 2
(%i4) out_neighbors(0, t);
(%o4) [7, 1]
```

**vertices** (*gr*)

Function

Returns the list of vertices in the graph *gr*.

Example:

```
(%i1) load (graphs)$
(%i2) vertices(complete_graph(4));
(%o2) [3, 2, 1, 0]
```

**vertex\_coloring** (*gr*)

Function

Returns an optimal coloring of the vertices of the graph *gr*.The function returns the chromatic number and a list representing the coloring of the vertices of *gr*.

Example:

```
(%i1) load (graphs)$
(%i2) p:petersen_graph()$
(%i3) vertex_coloring(p);
(%o3) [3, [[0, 2], [1, 3], [2, 2], [3, 3], [4, 1], [5, 3],
[6, 1], [7, 1], [8, 2], [9, 2]]]
```

**wiener\_index** (*gr*)

Function

Returns the Wiener index of the graph *gr*.

Example:

```
(%i2) wiener_index(dodecahedron_graph());
(%o2) 500
```

**56.2.3 Modifying graphs****add\_edge** (*e*, *gr*)

Function

Adds the edge *e* to the graph *gr*.

Example:

```
(%i1) load (graphs)$
(%i2) p : path_graph(4)$
(%i3) neighbors(0, p);
(%o3) [1]
(%i4) add_edge([0,3], p);
(%o4) done
(%i5) neighbors(0, p);
(%o5) [3, 1]
```

**add\_edges** (*e\_list*, *gr*)

Function

Adds all edges in the list *e\_list* to the graph *gr*.

Example:

```
(%i1) load (graphs)$
(%i2) g : empty_graph(3)$
(%i3) add_edges([[0,1],[1,2]], g)$
(%i4) print_graph(g)$
Graph on 3 vertices with 2 edges.
Adjacencies:
 2 : 1
 1 : 2 0
 0 : 1
```

**add\_vertex** (*v*, *gr*)

Function

Adds the vertex *v* to the graph *gr*.

Example:

```
(%i1) load (graphs)$
(%i2) g : path_graph(2)$
(%i3) add_vertex(2, g)$
(%i4) print_graph(g)$
Graph on 3 vertices with 1 edges.
Adjacencies:
 2 :
 1 : 0
 0 : 1
```

**add\_vertices** (*v\_list*, *gr*)

Function

Adds all vertices in the list *v\_list* to the graph *gr*.**connect\_vertices** (*v\_list*, *u\_list*, *gr*)

Function

Connects all vertices from the list *v\_list* with the vertices in the list *u\_list* in the graph *gr*.*v\_list* and *u\_list* can be single vertices or lists of vertices.

Example:

```
(%i1) load (graphs)$
(%i2) g : empty_graph(4)$
(%i3) connect_vertices(0, [1,2,3], g)$
(%i4) print_graph(g)$
Graph on 4 vertices with 3 edges.
Adjacencies:
 3 : 0
 2 : 0
 1 : 0
 0 : 3 2 1
```

**contract\_edge** (*e*, *gr*)

Function

Contracts the edge *e* in the graph *gr*.

Example:

```
(%i1) load (graphs)$
(%i2) g: create_graph(
 8, [[0,3],[1,3],[2,3],[3,4],[4,5],[4,6],[4,7]])$
(%i3) print_graph(g)$
Graph on 8 vertices with 7 edges.
Adjacencies:
 7 : 4
 6 : 4
 5 : 4
 4 : 7 6 5 3
 3 : 4 2 1 0
 2 : 3
 1 : 3
 0 : 3
(%i4) contract_edge([3,4], g)$
(%i5) print_graph(g)$
Graph on 7 vertices with 6 edges.
Adjacencies:
 7 : 3
 6 : 3
 5 : 3
 3 : 5 6 7 2 1 0
 2 : 3
 1 : 3
 0 : 3
```

**remove\_edge** (*e*, *gr*)

Function

Removes the edge *e* from the graph *gr*.

Example:

```
(%i1) load (graphs)$
(%i2) c3 : cycle_graph(3)$
(%i3) remove_edge([0,1], c3)$
(%i4) print_graph(c3)$
Graph on 3 vertices with 2 edges.
Adjacencies:
 2 : 0 1
 1 : 2
 0 : 2
```

**remove\_vertex** (*v*, *gr*)

Function

Removes the vertex *v* from the graph *gr*.

### 56.2.4 Reading and writing to files

|                                                                                                                         |          |
|-------------------------------------------------------------------------------------------------------------------------|----------|
| <b>dimacs_export</b> ( <i>gr</i> , <i>fl</i> )                                                                          | Function |
| <b>dimacs_export</b> ( <i>gr</i> , <i>fl</i> , <i>comment1</i> , ..., <i>commentn</i> )                                 | Function |
| Exports the graph into the file <i>fl</i> in the DIMACS format. Optional comments will be added to the top of the file. |          |
| <b>dimacs_import</b> ( <i>fl</i> )                                                                                      | Function |
| Returns the graph from file <i>fl</i> in the DIMACS format.                                                             |          |
| <b>graph6_decode</b> ( <i>str</i> )                                                                                     | Function |
| Returns the graph encoded in the graph6 format in the string <i>str</i> .                                               |          |
| <b>graph6_encode</b> ( <i>gr</i> )                                                                                      | Function |
| Returns a string which encodes the graph <i>gr</i> in the graph6 format.                                                |          |
| <b>graph6_export</b> ( <i>gr_list</i> , <i>fl</i> )                                                                     | Function |
| Exports graphs in the list <i>gr_list</i> to the file <i>fl</i> in the graph6 format.                                   |          |
| <b>graph6_import</b> ( <i>fl</i> )                                                                                      | Function |
| Returns a list of graphs from the file <i>fl</i> in the graph6 format.                                                  |          |
| <b>sparse6_decode</b> ( <i>str</i> )                                                                                    | Function |
| Returns the graph encoded in the sparse6 format in the string <i>str</i> .                                              |          |
| <b>sparse6_encode</b> ( <i>gr</i> )                                                                                     | Function |
| Returns a string which encodes the graph <i>gr</i> in the sparse6 format.                                               |          |
| <b>sparse6_export</b> ( <i>gr_list</i> , <i>fl</i> )                                                                    | Function |
| Exports graphs in the list <i>gr_list</i> to the file <i>fl</i> in the sparse6 format.                                  |          |
| <b>sparse6_import</b> ( <i>fl</i> )                                                                                     | Function |
| Returns a list of graphs from the file <i>fl</i> in the sparse6 format.                                                 |          |

### 56.2.5 Visualization

|                                                                                                                                                                                                                                                                                 |          |
|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|
| <b>draw_graph</b> ( <i>graph</i> )                                                                                                                                                                                                                                              | Function |
| <b>draw_graph</b> ( <i>graph</i> , <i>option1</i> , ..., <i>optionk</i> )                                                                                                                                                                                                       | Function |
| Draws the graph using the <b>draw</b> package.                                                                                                                                                                                                                                  |          |
| The algorithm used to position vertices is specified by the optional argument <i>program</i> . The default value is <b>program=spring_embedding</b> . <i>draw_graph</i> can also use the graphviz programs for positioning vertices, but graphviz must be installed separately. |          |

Example 1:

```
(%i1) load (graphs)$
(%i2) g:grid_graph(10,10)$
(%i3) m:max_matching(g)$
(%i4) draw_graph(g,
 spring_embedding_depth=100,
 show_edges=m, edge_type=dots,
 vertex_size=0)$
```

Example 2:

```
(%i1) load (graphs)$
(%i2) g:create_graph(16,
[
 [0,1],[1,3],[2,3],[0,2],[3,4],[2,4],
 [5,6],[6,4],[4,7],[6,7],[7,8],[7,10],[7,11],
 [8,10],[11,10],[8,9],[11,12],[9,15],[12,13],
 [10,14],[15,14],[13,14]
])$
(%i3) t:minimum_spanning_tree(g)$
(%i4) draw_graph(
 g,
 show_edges=edges(t),
 show_edge_width=4,
 show_edge_color=green,
 vertex_type=filled_square,
 vertex_size=2
)$
```

Example 3:

```
(%i1) load (graphs)$
(%i2) g:create_graph(16,
[
 [0,1],[1,3],[2,3],[0,2],[3,4],[2,4],
 [5,6],[6,4],[4,7],[6,7],[7,8],[7,10],[7,11],
 [8,10],[11,10],[8,9],[11,12],[9,15],[12,13],
 [10,14],[15,14],[13,14]
])$
(%i3) mi : max_independent_set(g)$
(%i4) draw_graph(
 g,
 show_vertices=mi,
 show_vertex_type=filled_up_triangle,
 show_vertex_size=2,
 edge_color=cyan,
 edge_width=3,
 show_id=true,
 text_color=brown
)$
```

Example 4:

```
(%i1) load (graphs)$
(%i2) net : create_graph(
 [0,1,2,3,4,5],
 [
 [[0,1], 3], [[0,2], 2],
 [[1,3], 1], [[1,4], 3],
 [[2,3], 2], [[2,4], 2],
 [[4,5], 2], [[3,5], 2]
],
 directed=true
)$
(%i3) draw_graph(
 net,
 show_weight=true,
 vertex_size=0,
 show_vertices=[0,5],
 show_vertex_type=filled_square,
 head_length=0.2,
```

```

 head_angle=10,
 edge_color="dark-green",
 text_color=blue
)$

```

Example 5:

```

(%i1) load(graphs)$
(%i2) g: petersen_graph(20, 2);
(%o2) GRAPH
(%i3) draw_graph(g, redraw=true, program=planar_embedding);
(%o3) done

```

Example 6:

```

(%i1) load(graphs)$
(%i2) t: tutte_graph();
(%o2) GRAPH
(%i3) draw_graph(t, redraw=true,
 fixed_vertices=[1,2,3,4,5,6,7,8,9]);
(%o3) done

```

### **draw\_graph\_program**

Option variable

Default value: *spring\_embedding*

The default value for the program used to position vertices in `draw_graph` program.

### **show\_id**

draw\_graph option

Default value: *false*

If *true* then ids of the vertices are displayed.

### **show\_label**

draw\_graph option

Default value: *false*

If *true* then labels of the vertices are displayed.

### **label\_alignment**

draw\_graph option

Default value: *center*

Determines how to align the labels/ids of the vertices. Can be *left*, *center* or *right*.

### **show\_weight**

draw\_graph option

Default value: *false*

If *true* then weights of the edges are displayed.

### **vertex\_type**

draw\_graph option

Default value: *circle*

Defines how vertices are displayed. See the *point\_type* option for the `draw` package for possible values.

### **vertex\_size**

draw\_graph option

The size of vertices.

### **vertex\_color**

draw\_graph option

The color used for displaying vertices.

### **show\_vertices**

draw\_graph option

Default value: `[]`

Display selected vertices in the using a different color.

|                                                                                                                                                                          |                   |
|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------|
| <b>show_vertex_type</b>                                                                                                                                                  | draw_graph option |
| Defines how vertices specified in <i>show_vertices</i> are displayed. See the <i>point_type</i> option for the <b>draw</b> package for possible values.                  |                   |
| <b>show_vertex_size</b>                                                                                                                                                  | draw_graph option |
| The size of vertices in <i>show_vertices</i> .                                                                                                                           |                   |
| <b>show_vertex_color</b>                                                                                                                                                 | draw_graph option |
| The color used for displaying vertices in the <i>show_vertices</i> list.                                                                                                 |                   |
| <b>vertex_partition</b>                                                                                                                                                  | draw_graph option |
| Default value: []                                                                                                                                                        |                   |
| A partition $[[v_1, v_2, \dots], \dots, [v_k, \dots, v_n]]$ of the vertices of the graph. The vertices of each list in the partition will be drawn in a different color. |                   |
| <b>vertex_coloring</b>                                                                                                                                                   | draw_graph option |
| Specifies coloring of the vertices. The coloring <i>col</i> must be specified in the format as returned by <i>vertex_coloring</i> .                                      |                   |
| <b>edge_color</b>                                                                                                                                                        | draw_graph option |
| The color used for displaying edges.                                                                                                                                     |                   |
| <b>edge_width</b>                                                                                                                                                        | draw_graph option |
| The width of edges.                                                                                                                                                      |                   |
| <b>edge_type</b>                                                                                                                                                         | draw_graph option |
| Defines how edges are displayed. See the <i>line_type</i> option for the <b>draw</b> package.                                                                            |                   |
| <b>show_edges</b>                                                                                                                                                        | draw_graph option |
| Display edges specified in the list <i>e_list</i> using a different color.                                                                                               |                   |
| <b>show_edge_color</b>                                                                                                                                                   | draw_graph option |
| The color used for displaying edges in the <i>show_edges</i> list.                                                                                                       |                   |
| <b>show_edge_width</b>                                                                                                                                                   | draw_graph option |
| The width of edges in <i>show_edges</i> .                                                                                                                                |                   |
| <b>show_edge_type</b>                                                                                                                                                    | draw_graph option |
| Defines how edges in <i>show_edges</i> are displayed. See the <i>line_type</i> option for the <b>draw</b> package.                                                       |                   |
| <b>edge_partition</b>                                                                                                                                                    | draw_graph option |
| A partition $[[e_1, e_2, \dots], \dots, [e_k, \dots, e_m]]$ of edges of the graph. The edges of each list in the partition will be drawn using a different color.        |                   |
| <b>edge_coloring</b>                                                                                                                                                     | draw_graph option |
| The coloring of edges. The coloring must be specified in the format as returned by the function <i>edge_coloring</i> .                                                   |                   |
| <b>redraw</b>                                                                                                                                                            | draw_graph option |
| Default value: <i>false</i>                                                                                                                                              |                   |
| If <b>true</b> , vertex positions are recomputed even if the positions have been saved from a previous drawing of the graph.                                             |                   |



|                                                                                                                                                                                                                                                                                                                                                                                                                          |                   |
|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------|
| <b>head_angle</b>                                                                                                                                                                                                                                                                                                                                                                                                        | draw_graph option |
| Default value: 15                                                                                                                                                                                                                                                                                                                                                                                                        |                   |
| The angle for the arrows displayed on arcs (in directed graphs).                                                                                                                                                                                                                                                                                                                                                         |                   |
| <b>head_length</b>                                                                                                                                                                                                                                                                                                                                                                                                       | draw_graph option |
| Default value: 0.1                                                                                                                                                                                                                                                                                                                                                                                                       |                   |
| The length for the arrows displayed on arcs (in directed graphs).                                                                                                                                                                                                                                                                                                                                                        |                   |
| <b>spring_embedding_depth</b>                                                                                                                                                                                                                                                                                                                                                                                            | draw_graph option |
| Default value: 50                                                                                                                                                                                                                                                                                                                                                                                                        |                   |
| The number of iterations in the spring embedding graph drawing algorithm.                                                                                                                                                                                                                                                                                                                                                |                   |
| <b>terminal</b>                                                                                                                                                                                                                                                                                                                                                                                                          | draw_graph option |
| The terminal used for drawing (see the <i>terminal</i> option in the <b>draw</b> package).                                                                                                                                                                                                                                                                                                                               |                   |
| <b>file_name</b>                                                                                                                                                                                                                                                                                                                                                                                                         | draw_graph option |
| The filename of the drawing if terminal is not screen.                                                                                                                                                                                                                                                                                                                                                                   |                   |
| <b>program</b>                                                                                                                                                                                                                                                                                                                                                                                                           | draw_graph option |
| Defines the program used for positioning vertices of the graph. Can be one of the graphviz programs (dot, neato, twopi, circ, fdp), <i>circular</i> , <i>spring_embedding</i> or <i>planar_embedding</i> . <i>planar_embedding</i> is only available for 2-connected planar graphs. When <b>program=spring_embedding</b> , a set of vertices with fixed position can be specified with the <i>fixed_vertices</i> option. |                   |
| <b>fixed_vertices</b>                                                                                                                                                                                                                                                                                                                                                                                                    | draw_graph option |
| Specifies a list of vertices which will have positions fixed along a regular polygon. Can be used when <b>program=spring_embedding</b> .                                                                                                                                                                                                                                                                                 |                   |
| <b>vertices_to_path</b> ( <i>v_list</i> )                                                                                                                                                                                                                                                                                                                                                                                | Function          |
| Converts a list <i>v_list</i> of vertices to a list of edges of the path defined by <i>v_list</i> .                                                                                                                                                                                                                                                                                                                      |                   |
| <b>vertices_to_cycle</b> ( <i>v_list</i> )                                                                                                                                                                                                                                                                                                                                                                               | Function          |
| Converts a list <i>v_list</i> of vertices to a list of edges of the cycle defined by <i>v_list</i> .                                                                                                                                                                                                                                                                                                                     |                   |



## 57 grobner

### 57.1 Introduction to grobner

`grobner` is a package for working with Groebner bases in Maxima.

To use the following functions you must load the ‘`grobner.lisp`’ package.

```
load(grobner);
```

A demo can be started by

```
demo("grobner.demo");
```

or

```
batch("grobner.demo")
```

Some of the calculation in the demo will take a lot of time therefore the output ‘`grobner-demo.output`’ of the demo can be found in the same directory as the demo file.

#### 57.1.1 Notes on the grobner package

The package was written by

Marek Rychlik

<http://alamos.math.arizona.edu>

and is released 2002-05-24 under the terms of the General Public License(GPL) (see file ‘`grobner.lisp`’. This documentation was extracted from the files

‘`README`’, ‘`grobner.lisp`’, ‘`grobner.demo`’, ‘`grobner-demo.output`’

by Günter Nowak. Suggestions for improvement of the documentation can be discussed at the *maxima*-mailing-list [maxima@math.utexas.edu](mailto:maxima@math.utexas.edu). The code is a little bit out of date now. Modern implementation use the fast  $F_4$  algorithm described in

A new efficient algorithm for computing Gröbner bases (F4)

Jean-Charles Faugère

LIP6/CNRS Université Paris VI

January 20, 1999

#### 57.1.2 Implementations of admissible monomial orders in grobner

- `lex`  
pure lexicographic, default order for monomial comparisons
- `grlex`  
total degree order, ties broken by lexicographic
- `grevlex`  
total degree, ties broken by reverse lexicographic
- `invlex`  
inverse lexicographic order

### 57.2 Functions and Variables for grobner

#### 57.2.1 Global switches for grobner

**poly\_monomial\_order**

Option variable

Default value: `lex`

This global switch controls which monomial order is used in polynomial and Groebner Bases calculations. If not set, `lex` will be used.



**poly\_subtract** (*poly1*, *poly2*, *varlist*) Function  
 Subtracts a polynomial *poly2* from *poly1*.

```
(%i1) poly_subtract(z+x^2*y,x-z,[x,y,z]);
(%o1) 2
 2 z + x y - x
```

**poly\_multiply** (*poly1*, *poly2*, *varlist*) Function  
 Returns the product of polynomials *poly1* and *poly2*.

```
(%i2) poly_multiply(z+x^2*y,x-z,[x,y,z])-(z+x^2*y)*(x-z),expand;
(%o1) 0
```

**poly\_s\_polynomial** (*poly1*, *poly2*, *varlist*) Function  
 Returns the *syzygy polynomial* (*S-polynomial*) of two polynomials *poly1* and *poly2*.

**poly\_primitive\_part** (*poly1*, *varlist*) Function  
 Returns the polynomial *poly* divided by the GCD of its coefficients.

```
(%i1) poly_primitive_part(35*y+21*x,[x,y]);
(%o1) 5 y + 3 x
```

**poly\_normalize** (*poly*, *varlist*) Function  
 Returns the polynomial *poly* divided by the leading coefficient. It assumes that the division is possible, which may not always be the case in rings which are not fields.

### 57.2.3 Other functions in grobner

**poly\_expand** (*poly*, *varlist*) Function  
 This function parses polynomials to internal form and back. It is equivalent to **expand**(*poly*) if *poly* parses correctly to a polynomial. If the representation is not compatible with a polynomial in variables *varlist*, the result is an error. It can be used to test whether an expression correctly parses to the internal representation. The following examples illustrate that indexed and transcendental function variables are allowed.

```
(%i1) poly_expand((x-y)*(y+x),[x,y]);
(%o1) 2 2
 x - y
(%i2) poly_expand((y+x)^2,[x,y]);
(%o2) 2 2
 y + 2 x y + x
(%i3) poly_expand((y+x)^5,[x,y]);
(%o3) 5 4 2 3 3 2 4 5
 y + 5 x y + 10 x y + 10 x y + 5 x y + x
(%i4) poly_expand(-1-x*exp(y)+x^2/sqrt(y),[x]);
(%o4) 2
 y x
 - x %e + ----- - 1
 sqrt(y)
(%i5) poly_expand(-1-sin(x)^2+sin(x),[sin(x)]);
(%o5) 2
 - sin (x) + sin(x) - 1
```

**poly\_expt** (*poly*, *number*, *varlist*) Function  
 exponentiates *poly* by a positive integer *number*. If *number* is not a positive integer an error will be raised.

```
(%i1) poly_expt(x-y,3,[x,y])-(x-y)^3,expand;
(%o1) 0
```

**poly\_content** (*poly*, *varlist*) Function  
 poly\_content extracts the GCD of its coefficients

```
(%i1) poly_content(35*y+21*x,[x,y]);
(%o1) 7
```

**poly\_pseudo\_divide** (*poly*, *polylist*, *varlist*) Function  
 Pseudo-divide a polynomial *poly* by the list of *n* polynomials *polylist*. Return multiple values. The first value is a list of quotients *a*. The second value is the remainder *r*. The third argument is a scalar coefficient *c*, such that  $c * poly$  can be divided by *polylist* within the ring of coefficients, which is not necessarily a field. Finally, the fourth value is an integer count of the number of reductions performed. The resulting objects satisfy the equation:

$$c * poly = \sum_{i=1}^n (a_i * polylist_i) + r$$

**poly\_exact\_divide** (*poly1*, *poly2*, *varlist*) Function  
 Divide a polynomial *poly1* by another polynomial *poly2*. Assumes that exact division with no remainder is possible. Returns the quotient.

**poly\_normal\_form** (*poly*, *polylist*, *varlist*) Function  
 poly\_normal\_form finds the normal form of a polynomial *poly* with respect to a set of polynomials *polylist*.

**poly\_buchberger\_criterion** (*polylist*, *varlist*) Function  
 Returns **true** if *polylist* is a Groebner basis with respect to the current term order, by using the Buchberger criterion: for every two polynomials *h1* and *h2* in *polylist* the S-polynomial  $S(h1, h2)$  reduces to 0 modulo *polylist*.

**poly\_buchberger** (*polylist*, *varlist*) Function  
 poly\_buchberger performs the Buchberger algorithm on a list of polynomials and returns the resulting Groebner basis.

## 57.2.4 Standard postprocessing of Groebner Bases

The *k*-th elimination ideal  $I_k$  of an ideal  $I$  over  $K[x_1, \dots, x_1]$  is  $I \cap K[x_{k+1}, \dots, x_n]$ .  
 The colon ideal  $I : J$  is the ideal  $\{h | \forall w \in J : wh \in I\}$ .  
 The ideal  $I : p^\infty$  is the ideal  $\{h | \exists n \in \mathbb{N} : p^n h \in I\}$ .  
 The ideal  $I : J^\infty$  is the ideal  $\{h | \exists n \in \mathbb{N}, \exists p \in J : p^n h \in I\}$ .  
 The radical ideal  $\sqrt{I}$  is the ideal  $\{h | \exists n \in \mathbb{N} : h^n \in I\}$ .

**poly\_reduction** (*polylist*, *varlist*) Function  
 poly\_reduction reduces a list of polynomials *polylist*, so that each polynomial is fully reduced with respect to the other polynomials.

**poly\_minimization** (*polylist*, *varlist*) Function  
 Returns a sublist of the polynomial list *polylist* spanning the same monomial ideal as *polylist* but minimal, i.e. no leading monomial of a polynomial in the sublist divides the leading monomial of another polynomial.

**poly\_normalize\_list** (*polylist*, *varlist*) Function  
*poly\_normalize\_list* applies *poly\_normalize* to each polynomial in the list. That means it divides every polynomial in a list *polylist* by its leading coefficient.

**poly\_grobner** (*polylist*, *varlist*) Function  
 Returns a Groebner basis of the ideal span by the polynomials *polylist*. Affected by the global flags.

**poly\_reduced\_grobner** (*polylist*, *varlist*) Function  
 Returns a reduced Groebner basis of the ideal span by the polynomials *polylist*. Affected by the global flags.

**poly\_depends\_p** (*poly*, *var*, *varlist*) Function  
*poly\_depends* tests whether a polynomial depends on a variable *var*.

**poly\_elimination\_ideal** (*polylist*, *number*, *varlist*) Function  
*poly\_elimination\_ideal* returns the grobner basis of the *number*-th elimination ideal of an ideal specified as a list of generating polynomials (not necessarily Groebner basis).

**poly\_colon\_ideal** (*polylist1*, *polylist2*, *varlist*) Function  
 Returns the reduced Groebner basis of the colon ideal  
 $I(\text{polylist1}) : I(\text{polylist2})$   
 where *polylist1* and *polylist2* are two lists of polynomials.

**poly\_ideal\_intersection** (*polylist1*, *polylist2*, *varlist*) Function  
*poly\_ideal\_intersection* returns the intersection of two ideals.

**poly\_lcm** (*poly1*, *poly2*, *varlist*) Function  
 Returns the lowest common multiple of *poly1* and *poly2*.

**poly\_gcd** (*poly1*, *poly2*, *varlist*) Function  
 Returns the greatest common divisor of *poly1* and *poly2*.  
 See also *ezgcd*, *gcd*, *gcdex*, and *gcddivide*.  
 Example:

```
(%i1) p1:6*x^3+19*x^2+19*x+6;
 3 2
(%o1) 6 x + 19 x + 19 x + 6
(%i2) p2:6*x^5+13*x^4+12*x^3+13*x^2+6*x;
 5 4 3 2
(%o2) 6 x + 13 x + 12 x + 13 x + 6 x
(%i3) poly_gcd(p1, p2, [x]);
 2
(%o3) 6 x + 13 x + 6
```

**poly\_grobner\_equal** (*polylist1*, *polylist2*, *varlist*) Function  
*poly\_grobner\_equal* tests whether two Groebner Bases generate the same ideal. Returns **true** if two lists of polynomials *polylist1* and *polylist2*, assumed to be Groebner Bases, generate the same ideal, and **false** otherwise. This is equivalent to checking that every polynomial of the first basis reduces to 0 modulo the second basis and vice versa. Note that in the example below the first list is not a Groebner basis, and thus the result is **false**.

```
(%i1) poly_grobner_equal([y+x,x-y],[x,y],[x,y]);
(%o1) false
```

**poly\_grobner\_subsetp** (*polylist1*, *polylist2*, *varlist*) Function  
**poly\_grobner\_subsetp** tests whether an ideal generated by *polylist1* is contained in the ideal generated by *polylist2*. For this test to always succeed, *polylist2* must be a Groebner basis.

**poly\_grobner\_member** (*poly*, *polylist*, *varlist*) Function  
 Returns **true** if a polynomial *poly* belongs to the ideal generated by the polynomial list *polylist*, which is assumed to be a Groebner basis. Returns **false** otherwise.  
**poly\_grobner\_member** tests whether a polynomial belongs to an ideal generated by a list of polynomials, which is assumed to be a Groebner basis. Equivalent to **normal\_form** being 0.

**poly\_ideal\_saturation1** (*polylist*, *poly*, *varlist*) Function  
 Returns the reduced Groebner basis of the saturation of the ideal

$$I(\text{polylist}) : \text{poly}^\infty$$

Geometrically, over an algebraically closed field, this is the set of polynomials in the ideal generated by *polylist* which do not identically vanish on the variety of *poly*.

**poly\_ideal\_saturation** (*polylist1*, *polylist2*, *varlist*) Function  
 Returns the reduced Groebner basis of the saturation of the ideal

$$I(\text{polylist1}) : I(\text{polylist2})^\infty$$

Geometrically, over an algebraically closed field, this is the set of polynomials in the ideal generated by *polylist1* which do not identically vanish on the variety of *polylist2*.

**poly\_ideal\_polysaturation1** (*polylist1*, *polylist2*, *varlist*) Function  
*polylist2* is a list of *n* polynomials [**poly1**, ..., **polyn**]. Returns the reduced Groebner basis of the ideal

$$I(\text{polylist}) : \text{poly1}^\infty : \dots : \text{polyn}^\infty$$

obtained by a sequence of successive saturations in the polynomials of the polynomial list *polylist2* of the ideal generated by the polynomial list *polylist1*.

**poly\_ideal\_polysaturation** (*polylist*, *polylistlist*, *varlist*) Function  
*polylistlist* is a list of *n* list of polynomials [**polylist1**, ..., **polylistn**]. Returns the reduced Groebner basis of the saturation of the ideal

$$I(\text{polylist}) : I(\text{polylist}_1)^\infty : \dots : I(\text{polylist}_n)^\infty$$

**poly\_saturation\_extension** (*poly*, *polylist*, *varlist1*, *varlist2*) Function  
**poly\_saturation\_extension** implements the famous Rabinowitz trick.

**poly\_polysaturation\_extension** (*poly*, *polylist*, *varlist1*, *varlist2*) Function



## 58 impdiff

### 58.1 Functions and Variables for impdiff

**implicit\_derivative** (*f,indvarlist,orderlist,depvar*)

Function

This subroutine computes implicit derivatives of multivariable functions. *f* is an array function, the indexes are the derivative degree in the *indvarlist* order; *indvarlist* is the independent variable list; *orderlist* is the order desired; and *depvar* is the dependent variable.

To use this function write first `load("impdiff")`.



## 59 interpol

### 59.1 Introduction to interpol

Package `interpol` defines the Lagrangian, the linear and the cubic splines methods for polynomial interpolation.

For comments, bugs or suggestions, please contact me at '*mario AT edu DOT xunta DOT es*'.

### 59.2 Functions and Variables for interpol

**lagrange** (*points*) Function  
**lagrange** (*points, option*) Function

Computes the polynomial interpolation by the Lagrangian method. Argument *points* must be either:

- a two column matrix, `p:matrix([2,4],[5,6],[9,3])`,
- a list of pairs, `p: [[2,4],[5,6],[9,3]]`,
- a list of numbers, `p: [4,6,3]`, in which case the abscissas will be assigned automatically to 1, 2, 3, etc.

In the first two cases the pairs are ordered with respect to the first coordinate before making computations.

With the *option* argument it is possible to select the name for the independent variable, which is 'x' by default; to define another one, write something like `varname='z'`.

Note that when working with high degree polynomials, floating point evaluations are unstable.

See also `linearinterpol`, `cspline`, and `ratinterpol`.

Examples:

```
(%i1) load(interpol)$
(%i2) p: [[7,2],[8,2],[1,5],[3,2],[6,7]]$
(%i3) lagrange(p);
 (x - 7) (x - 6) (x - 3) (x - 1)
(%o3) -----
 35
 (x - 8) (x - 6) (x - 3) (x - 1)
- -----
 12
 7 (x - 8) (x - 7) (x - 3) (x - 1)
+ -----
 30
 (x - 8) (x - 7) (x - 6) (x - 1)
- -----
 60
 (x - 8) (x - 7) (x - 6) (x - 3)
+ -----
 84
(%i4) f(x):='';
 (x - 7) (x - 6) (x - 3) (x - 1)
(%o4) f(x) := -----
 35
 (x - 8) (x - 6) (x - 3) (x - 1)
- -----
 12
 7 (x - 8) (x - 7) (x - 3) (x - 1)
```

```

+ -----
 30
 (x - 8) (x - 7) (x - 6) (x - 1)
- -----
 60
 (x - 8) (x - 7) (x - 6) (x - 3)
+ -----
 84
(%i5) /* Evaluate the polynomial at some points */
 expand(map(f,[2.3,5/7,%pi]));
(%o5) [- 1.567535, -----, -----, -----, -----]
 84035 420 210 420
 5288 %pi 186
 - ----- + ----]
 105 5

(%i6) %,numer;
(%o6) [- 1.567535, 10.9366573451538, 2.89319655125692]
(%i7) load(draw)$ /* load draw package */
(%i8) /* Plot the polynomial together with points */
 draw2d(
 color = red,
 key = "Lagrange polynomial",
 explicit(f(x),x,0,10),
 point_size = 3,
 color = blue,
 key = "Sample points",
 points(p))$
(%i9) /* Change variable name */
 lagrange(p, varname=w);
 (w - 7) (w - 6) (w - 3) (w - 1)
(%o9) -----
 35
 (w - 8) (w - 6) (w - 3) (w - 1)
- -----
 12
 7 (w - 8) (w - 7) (w - 3) (w - 1)
+ -----
 30
 (w - 8) (w - 7) (w - 6) (w - 1)
- -----
 60
 (w - 8) (w - 7) (w - 6) (w - 3)
+ -----
 84

```

**charfun2** (*x*, *a*, *b*)

Function

Returns **true** if number *x* belongs to the interval  $[a, b]$ , and **false** otherwise.

**linearinterpol** (*points*)

Function

**linearinterpol** (*points*, *option*)

Function

Computes the polynomial interpolation by the linear method. Argument *points* must be either:

- a two column matrix, `p:matrix([2,4],[5,6],[9,3])`,
- a list of pairs, `p: [[2,4],[5,6],[9,3]]`,

- a list of numbers, `p`: `[4,6,3]`, in which case the abscissas will be assigned automatically to 1, 2, 3, etc.

In the first two cases the pairs are ordered with respect to the first coordinate before making computations.

With the *option* argument it is possible to select the name for the independent variable, which is 'x' by default; to define another one, write something like `varname='z'`.

See also `lagrange`, `cspline`, and `ratinterpol`.

Examples:

```
(%i1) load(interpol)$
(%i2) p: matrix([7,2],[8,3],[1,5],[3,2],[6,7])$
(%i3) linearinterpol(p);
 13 3 x
 2 2
(%o3) (--- - ---) charfun2(x, minf, 3)
 2 2
 + (x - 5) charfun2(x, 7, inf) + (37 - 5 x) charfun2(x, 6, 7)
 5 x
 + (--- - 3) charfun2(x, 3, 6)
 3

(%i4) f(x):='';
 13 3 x
(%o4) f(x) := (--- - ---) charfun2(x, minf, 3)
 2 2
 + (x - 5) charfun2(x, 7, inf) + (37 - 5 x) charfun2(x, 6, 7)
 5 x
 + (--- - 3) charfun2(x, 3, 6)
 3

(%i5) /* Evaluate the polynomial at some points */
 map(f,[7.3,25/7,%pi]);
 62 5 %pi
(%o5) [2.3, --, ----- - 3]
 21 3

(%i6) %,numer;
(%o6) [2.3, 2.952380952380953, 2.235987755982989]
(%i7) load(draw)$ /* load draw package */
(%i8) /* Plot the polynomial together with points */
draw2d(
 color = red,
 key = "Linear interpolator",
 explicit(f(x),x,-5,20),
 point_size = 3,
 color = blue,
 key = "Sample points",
 points(args(p)))$
(%i9) /* Change variable name */
linearinterpol(p, varname='s');
 13 3 s
(%o9) (--- - ---) charfun2(s, minf, 3)
 2 2
 + (s - 5) charfun2(s, 7, inf) + (37 - 5 s) charfun2(s, 6, 7)
 5 s
 + (--- - 3) charfun2(s, 3, 6)
 3
```

**cspline** (*points*)

Function

**cspline** (*points, option1, option2, ...*)

Function

Computes the polynomial interpolation by the cubic splines method. Argument *points* must be either:

- a two column matrix, *p*: `matrix([2,4],[5,6],[9,3])`,
- a list of pairs, *p*: `[[2,4],[5,6],[9,3]]`,
- a list of numbers, *p*: `[4,6,3]`, in which case the abscissas will be assigned automatically to 1, 2, 3, etc.

In the first two cases the pairs are ordered with respect to the first coordinate before making computations.

There are three options to fit specific needs:

- *'d1*, default *'unknown*, is the first derivative at  $x_1$ ; if it is *'unknown*, the second derivative at  $x_1$  is made equal to 0 (natural cubic spline); if it is equal to a number, the second derivative is calculated based on this number.
- *'dn*, default *'unknown*, is the first derivative at  $x_n$ ; if it is *'unknown*, the second derivative at  $x_n$  is made equal to 0 (natural cubic spline); if it is equal to a number, the second derivative is calculated based on this number.
- *'varname*, default *'x*, is the name of the independent variable.

See also `lagrange`, `linearinterpol`, and `ratinterpol`.

Examples:

```
(%i1) load(interpol)$
(%i2) p:[[7,2],[8,2],[1,5],[3,2],[6,7]]$
(%i3) /* Unknown first derivatives at the extremes
 is equivalent to natural cubic splines */
 cspline(p);
 3 2
 1159 x 1159 x 6091 x 8283
(%o3) (----- - ----- - ----- + ----) charfun2(x, minf, 3)
 3288 1096 3288 1096
 3 2
 2587 x 5174 x 494117 x 108928
+ (- ----- + ----- - ----- + -----) charfun2(x, 7, inf)
 1644 137 1644 137
 3 2
 4715 x 15209 x 579277 x 199575
+ (----- - ----- + ----- - -----) charfun2(x, 6, 7)
 1644 274 1644 274
 3 2
 3287 x 2223 x 48275 x 9609
+ (- ----- + ----- - ----- + ----) charfun2(x, 3, 6)
 4932 274 1644 274

(%i4) f(x):=''%$
(%i5) /* Some evaluations */
 map(f,[2.3,5/7,%pi]), numer;
(%o5) [1.991460766423356, 5.823200187269903, 2.227405312429507]
(%i6) load(draw)$ /* load draw package */
(%i7) /* Plotting interpolating function */
 draw2d(
 color = red,
 key = "Cubic splines",
 explicit(f(x),x,0,10),
 point_size = 3,
 color = blue,
 key = "Sample points",
```

```

 points(p))$
(%i8) /* New call, but giving values at the derivatives */
 cspline(p,d1=0,dn=0);
 3 2
 1949 x 11437 x 17027 x 1247
(%o8) (----- - ----- + ----- + ----) charfun2(x, minf, 3)
 2256 2256 2256 752
 3 2
 1547 x 35581 x 68068 x 173546
+ (- ----- + ----- - ----- + -----) charfun2(x, 7, inf)
 564 564 141 141
 3 2
 607 x 35147 x 55706 x 38420
+ (----- - ----- + ----- - -----) charfun2(x, 6, 7)
 188 564 141 47
 3 2
 3895 x 1807 x 5146 x 2148
+ (- ----- + ----- - ----- + ----) charfun2(x, 3, 6)
 5076 188 141 47
(%i8) /* Defining new interpolating function */
 g(x):=''%$
(%i9) /* Plotting both functions together */
 draw2d(
 color = black,
 key = "Cubic splines (default)",
 explicit(f(x),x,0,10),
 color = red,
 key = "Cubic splines (d1=0,dn=0)",
 explicit(g(x),x,0,10),
 point_size = 3,
 color = blue,
 key = "Sample points",
 points(p))$

```

**ratinterpol** (*points*, *numdeg*)

Function

**ratinterpol** (*points*, *numdeg*, *option1*, *option2*, ...)

Function

Generates a rational interpolator for data given by *points* and the degree of the numerator being equal to *numdeg*; the degree of the denominator is calculated automatically. Argument *points* must be either:

- a two column matrix, *p*: `matrix([2,4],[5,6],[9,3])`,
- a list of pairs, *p*: `[[2,4],[5,6],[9,3]]`,
- a list of numbers, *p*: `[4,6,3]`, in which case the abscissas will be assigned automatically to 1, 2, 3, etc.

In the first two cases the pairs are ordered with respect to the first coordinate before making computations.

There are two options to fit specific needs:

- `'denterm`, default 1, is the independent term of the polynomial in the denominator.
- `'varname`, default `'x`, is the name of the independent variable.

See also `lagrange`, `linearinterpol`, `cspline`, `minpack_lsquares`, and `lbfgs`.

Examples:

```

(%i1) load(interpol)$
(%i2) load(draw)$
(%i3) p:[[7.2,2.5],[8.5,2.1],[1.6,5.1],[3.4,2.4],[6.7,7.9]]$
(%i4) for k:0 thru length(p)-1 do

```

```
draw2d(
 explicit(ratinterpol(p,k),x,0,9),
 point_size = 3,
 points(p),
 title = concat("Degree of numerator = ",k),
 yrange=[0,10])$
```



## 60 lapack

### 60.1 Introduction to lapack

`lapack` is a Common Lisp translation (via the program `f2c`) of the Fortran library LAPACK, as obtained from the SLATEC project.

### 60.2 Functions and Variables for lapack

**dgeev** (*A*) Function  
**dgeev** (*A*, *right\_p*, *left\_p*) Function

Computes the eigenvalues and, optionally, the eigenvectors of a matrix *A*. All elements of *A* must be integer or floating point numbers. *A* must be square (same number of rows and columns). *A* might or might not be symmetric.

`dgeev(A)` computes only the eigenvalues of *A*. `dgeev(A, right_p, left_p)` computes the eigenvalues of *A* and the right eigenvectors when *right\_p* = `true` and the left eigenvectors when *left\_p* = `true`.

A list of three items is returned. The first item is a list of the eigenvalues. The second item is `false` or the matrix of right eigenvectors. The third item is `false` or the matrix of left eigenvectors.

The right eigenvector  $v(j)$  (the  $j$ -th column of the right eigenvector matrix) satisfies

$$A.v(j) = \text{lambda}(j).v(j)$$

where  $\text{lambda}(j)$  is the corresponding eigenvalue. The left eigenvector  $u(j)$  (the  $j$ -th column of the left eigenvector matrix) satisfies

$$u(j) ** H.A = \text{lambda}(j).u(j) ** H$$

where  $u(j) ** H$  denotes the conjugate transpose of  $u(j)$ . The Maxima function `ctranspose` computes the conjugate transpose.

The computed eigenvectors are normalized to have Euclidean norm equal to 1, and largest component has imaginary part equal to zero.

Example:

```
(%i1) load (lapack)$
(%i2) fpprintprec : 6;
(%o2)
(%i3) M : matrix ([9.5, 1.75], [3.25, 10.45]);
 [9.5 1.75]
(%o3) [
 [3.25 10.45]

(%i4) dgeev (M);
(%o4) [[7.54331, 12.4067], false, false]
(%i5) [L, v, u] : dgeev (M, true, true);
 [- .666642 - .515792]
(%o5) [[7.54331, 12.4067], [
 [.745378 - .856714]
 [- .856714 - .745378]
 [
 [.515792 - .666642]

(%i6) D : apply (diag_matrix, L);
 [7.54331 0]
(%o6) [
 [0 12.4067]

(%i7) M . v - v . D;
 [0.0 - 8.88178E-16]
(%o7) [
```

```

 [- 8.88178E-16 0.0]
(%i8) transpose (u) . M - D . transpose (u);
 [0.0 - 4.44089E-16]
(%o8) [
 [0.0 0.0]

```

**dgeqrf (A)**

Function

Computes the QR decomposition of the matrix  $A$ . All elements of  $A$  must be integer or floating point numbers.  $A$  may or may not have the same number of rows and columns.

A list of two items is returned. The first item is the matrix  $Q$ , which is a square, orthonormal matrix which has the same number of rows as  $A$ . The second item is the matrix  $R$ , which is the same size as  $A$ , and which has all elements equal to zero below the diagonal. The product  $Q \cdot R$ , where "." is the noncommutative multiplication operator, is equal to  $A$  (ignoring floating point round-off errors).

```

(%i1) load (lapack) $
(%i2) fpprintprec : 6 $
(%i3) M : matrix ([1, -3.2, 8], [-11, 2.7, 5.9]) $
(%i4) [q, r] : dgeqrf (M);
 [- .0905357 .995893]
(%o4) [[
 [.995893 .0905357]
 [- 11.0454 2.97863 5.15148]
 [
 [0 - 2.94241 8.50131]
 [
 [- 7.77156E-16 1.77636E-15 - 8.88178E-16]
(%i5) q . r - M;
 [
(%o5) [
 [0.0 - 1.33227E-15 8.88178E-16]
(%i6) mat_norm (% , 1);
(%o6) 3.10862E-15

```

**dgesv (A, b)**

Function

Computes the solution  $x$  of the linear equation  $Ax = b$ , where  $A$  is a square matrix, and  $b$  is a matrix of the same number of rows as  $A$  and any number of columns. The return value  $x$  is the same size as  $b$ .

The elements of  $A$  and  $b$  must evaluate to real floating point numbers via `float`; thus elements may be any numeric type, symbolic numerical constants, or expressions which evaluate to floats. The elements of  $x$  are always floating point numbers. All arithmetic is carried out as floating point operations.

`dgesv` computes the solution via the LU decomposition of  $A$ .

Examples:

`dgesv` computes the solution of the linear equation  $Ax = b$ .

```

(%i1) A : matrix ([1, -2.5], [0.375, 5]);
 [1 - 2.5]
(%o1) [
 [0.375 5]
(%i2) b : matrix ([1.75], [-0.625]);
 [1.75]
(%o2) [
 [- 0.625]
(%i3) x : dgesv (A, b);
 [1.210526315789474]
(%o3) [
 [- 0.215789473684211]
(%i4) dlange (inf_norm, b - A.x);
(%o4) 0.0

```

$b$  is a matrix with the same number of rows as  $A$  and any number of columns.  $x$  is the same size as  $b$ .

```
(%i1) A : matrix ([1, -0.15], [1.82, 2]);
 [1 - 0.15]
(%o1) []
 [1.82 2]
(%i2) b : matrix ([3.7, 1, 8], [-2.3, 5, -3.9]);
 [3.7 1 8]
(%o2) []
 [- 2.3 5 - 3.9]

(%i3) x : dgesv (A, b);
 [3.103827540695117 1.20985481742191 6.781786185657722]
(%o3) []
 [-3.974483062032557 1.399032116146062 -8.121425428948527]
(%i4) dlange (inf_norm, b - A . x);
(%o4) 1.1102230246251565E-15
```

The elements of  $A$  and  $b$  must evaluate to real floating point numbers.

```
(%i1) A : matrix ([5, -%pi], [1b0, 11/17]);
 [5 - %pi]
 []
(%o1) []
 [11]
 [1.0b0 --]
 [17]

(%i2) b : matrix ([%e], [sin(1)]);
 [%e]
(%o2) []
 [sin(1)]

(%i3) x : dgesv (A, b);
 [0.690375643155986]
(%o3) []
 [0.233510982552952]
(%i4) dlange (inf_norm, b - A . x);
(%o4) 2.220446049250313E-16
```

### **dgesvd** ( $A$ )

Function

### **dgesvd** ( $A$ , $left\_p$ , $right\_p$ )

Function

Computes the singular value decomposition (SVD) of a matrix  $A$ , comprising the singular values and, optionally, the left and right singular vectors. All elements of  $A$  must be integer or floating point numbers.  $A$  might or might not be square (same number of rows and columns).

Let  $m$  be the number of rows, and  $n$  the number of columns of  $A$ . The singular value decomposition of  $A$  comprises three matrices,  $U$ ,  $Sigma$ , and  $V^T$ , such that

$$A = U.Sigma.V^T$$

where  $U$  is an  $m$ -by- $m$  unitary matrix,  $Sigma$  is an  $m$ -by- $n$  diagonal matrix, and  $V^T$  is an  $n$ -by- $n$  unitary matrix.

Let  $sigma[i]$  be a diagonal element of  $Sigma$ , that is,  $Sigma[i, i] = sigma[i]$ . The elements  $sigma[i]$  are the so-called singular values of  $A$ ; these are real and nonnegative, and returned in descending order. The first  $\min(m, n)$  columns of  $U$  and  $V$  are the left and right singular vectors of  $A$ . Note that **dgesvd** returns the transpose of  $V$ , not  $V$  itself.

**dgesvd**( $A$ ) computes only the singular values of  $A$ . **dgesvd**( $A$ ,  $left\_p$ ,  $right\_p$ ) computes the singular values of  $A$  and the left singular vectors when  $left\_p = \text{true}$  and the right singular vectors when  $right\_p = \text{true}$ .

A list of three items is returned. The first item is a list of the singular values. The second item is **false** or the matrix of left singular vectors. The third item is **false** or the matrix of right singular vectors.

Example:

```

(%i1) load (lapack)$
(%i2) fpprintprec : 6;
(%o2)
6
(%i3) M: matrix([1, 2, 3], [3.5, 0.5, 8], [-1, 2, -3], [4, 9, 7]);
 [1 2 3]
 []
 [3.5 0.5 8]
 []
(%o3) [- 1 2 - 3]
 []
 [4 9 7]

(%i4) dgesvd (M);
(%o4) [[14.4744, 6.38637, .452547], false, false]
(%i5) [sigma, U, VT] : dgesvd (M, true, true);
(%o5) [[14.4744, 6.38637, .452547],
[- .256731 .00816168 .959029 - .119523]
[
[- .526456 .672116 - .206236 - .478091]
[
[.107997 - .532278 - .0708315 - 0.83666]
[
[- .803287 - .514659 - .180867 .239046]
[- .374486 - .538209 - .755044]
[
[.130623 - .836799 0.5317]]
[
[- .917986 .100488 .383672]
(%i6) m : length (U);
(%o6) 4
(%i7) n : length (VT);
(%o7) 3
(%i8) Sigma:
 genmatrix(lambda ([i, j], if i=j then sigma[i] else 0),
 m, n);
 [14.4744 0 0]
 [
 [0 6.38637 0]
 [
 [0 0 .452547]
 [
 [0 0 0]
(%i9) U . Sigma . VT - M;
 [1.11022E-15 0.0 1.77636E-15]
 [
 [1.33227E-15 1.66533E-15 0.0]
 [
(%o9) [- 4.44089E-16 - 8.88178E-16 4.44089E-16]
 [
 [8.88178E-16 1.77636E-15 8.88178E-16]
(%i10) transpose (U) . U;
 [1.0 5.55112E-17 2.498E-16 2.77556E-17]
 [
 [5.55112E-17 1.0 5.55112E-17 4.16334E-17]
 [
(%o10) [2.498E-16 5.55112E-17 1.0 - 2.08167E-16]
 [

```

```

 [2.77556E-17 4.16334E-17 - 2.08167E-16 1.0]
(%i11) VT . transpose (VT);
 [1.0 0.0 - 5.55112E-17]
 []
(%o11) [0.0 1.0 5.55112E-17]
 []
 [- 5.55112E-17 5.55112E-17 1.0]

```

**dlange** (*norm*, *A*)

Function

**zlange** (*norm*, *A*)

Function

Computes a norm or norm-like function of the matrix *A*.

**max** Compute  $\max(\text{abs}(A(i, j)))$  where *i* and *j* range over the rows and columns, respectively, of *A*. Note that this function is not a proper matrix norm.

**one\_norm** Compute the  $L[1]$  norm of *A*, that is, the maximum of the sum of the absolute value of elements in each column.

**inf\_norm** Compute the  $L[\text{inf}]$  norm of *A*, that is, the maximum of the sum of the absolute value of elements in each row.

**frobenius**

Compute the Frobenius norm of *A*, that is, the square root of the sum of squares of the matrix elements.

**dgemm** (*A*, *B*)

Function

**dgemm** (*A*, *B*, *options*)

Function

Compute the product of two matrices and optionally add the product to a third matrix.

In the simplest form, **dgemm**(*A*, *B*) computes the product of the two real matrices, *A* and *B*.

In the second form, **dgemm** computes the  $\alpha * A * B + \beta * C$  where *A*, *B*, *C* are real matrices of the appropriate sizes and  $\alpha$  and  $\beta$  are real numbers. Optionally, *A* and/or *B* can be transposed before computing the product. The extra parameters are specified by optional keyword arguments: The keyword arguments are optional and may be specified in any order. They all take the form **key=val**. The keyword arguments are:

**C** The matrix *C* that should be added. The default is **false**, which means no matrix is added.

**alpha** The product of *A* and *B* is multiplied by this value. The default is 1.

**beta** If a matrix *C* is given, this value multiplies *C* before it is added. The default value is 0, which implies that *C* is not added, even if *C* is given. Hence, be sure to specify a non-zero value for **beta**.

**transpose\_a**

If **true**, the transpose of *A* is used instead of *A* for the product. The default is **false**.

**transpose\_b**

If **true**, the transpose of *B* is used instead of *B* for the product. The default is **false**.

```

(%i1) load (lapack)$
(%i2) A : matrix([1,2,3],[4,5,6],[7,8,9]);
 [1 2 3]
 []
(%o2) [4 5 6]
 []
 [7 8 9]
(%i3) B : matrix([-1,-2,-3],[-4,-5,-6],[-7,-8,-9]);
 [-1 -2 -3]
 []

```

```

(%o3)
 [- 4 - 5 - 6]
 []
 [- 7 - 8 - 9]

(%i4) C : matrix([3,2,1],[6,5,4],[9,8,7]);
 [3 2 1]
 []
 [6 5 4]
 []
 [9 8 7]

(%i5) dgemm(A,B);
 [- 30.0 - 36.0 - 42.0]
 []
 [- 66.0 - 81.0 - 96.0]
 []
 [- 102.0 - 126.0 - 150.0]

(%i6) A . B;
 [- 30 - 36 - 42]
 []
 [- 66 - 81 - 96]
 []
 [- 102 - 126 - 150]

(%i7) dgemm(A,B,transpose_a=true);
 [- 66.0 - 78.0 - 90.0]
 []
 [- 78.0 - 93.0 - 108.0]
 []
 [- 90.0 - 108.0 - 126.0]

(%i8) transpose(A) . B;
 [- 66 - 78 - 90]
 []
 [- 78 - 93 - 108]
 []
 [- 90 - 108 - 126]

(%i9) dgemm(A,B,c=C,beta=1);
 [- 27.0 - 34.0 - 41.0]
 []
 [- 60.0 - 76.0 - 92.0]
 []
 [- 93.0 - 118.0 - 143.0]

(%i10) A . B + C;
 [- 27 - 34 - 41]
 []
 [- 60 - 76 - 92]
 []
 [- 93 - 118 - 143]

(%i11) dgemm(A,B,c=C,beta=1, alpha=-1);
 [33.0 38.0 43.0]
 []
 [72.0 86.0 100.0]
 []
 [111.0 134.0 157.0]

(%i12) -A . B + C;
 [33 38 43]
 []
 [72 86 100]
 []

```

[ 111 134 157 ]





## 61 lbfgs

### 61.1 Introduction to lbfgs

**lbfgs** is an implementation of the L-BFGS algorithm [1] to solve unconstrained minimization problems via a limited-memory quasi-Newton (BFGS) algorithm. It is called a limited-memory method because a low-rank approximation of the Hessian matrix inverse is stored instead of the entire Hessian inverse. The program was originally written in Fortran [2] by Jorge Nocedal, incorporating some functions originally written by Jorge J. Moré and David J. Thuente, and translated into Lisp automatically via the program **f2c1**. The Maxima package **lbfgs** comprises the translated code plus an interface function which manages some details.

References:

[1] D. Liu and J. Nocedal. "On the limited memory BFGS method for large scale optimization". *Mathematical Programming B* 45:503–528 (1989)

[2] [http://netlib.org/opt/lbfgs\\_um.shar](http://netlib.org/opt/lbfgs_um.shar)

### 61.2 Functions and Variables for lbfgs

|                                                                                                    |          |
|----------------------------------------------------------------------------------------------------|----------|
| <b>lbfgs</b> ( <i>FOM</i> , <i>X</i> , <i>X0</i> , <i>epsilon</i> , <i>iprint</i> )                | Function |
| <b>lbfgs</b> ([ <i>FOM</i> , <i>grad</i> ] <i>X</i> , <i>X0</i> , <i>epsilon</i> , <i>iprint</i> ) | Function |

Finds an approximate solution of the unconstrained minimization of the figure of merit *FOM* over the list of variables *X*, starting from initial estimates *X0*, such that  $norm(grad(FOM)) < epsilon * max(1, norm(X))$ .

*grad*, if present, is the gradient of *FOM* with respect to the variables *X*. *grad* is a list, with one element for each element of *X*. If not present, the gradient is computed automatically by symbolic differentiation.

The algorithm applied is a limited-memory quasi-Newton (BFGS) algorithm [1]. It is called a limited-memory method because a low-rank approximation of the Hessian matrix inverse is stored instead of the entire Hessian inverse. Each iteration of the algorithm is a line search, that is, a search along a ray in the variables *X*, with the search direction computed from the approximate Hessian inverse. The *FOM* is always decreased by a successful line search. Usually (but not always) the norm of the gradient of *FOM* also decreases.

*iprint* controls progress messages printed by **lbfgs**.

**iprint**[1]

*iprint*[1] controls the frequency of progress messages.

**iprint**[1] < 0

No progress messages.

**iprint**[1] = 0

Messages at the first and last iterations.

**iprint**[1] > 0

Print a message every *iprint*[1] iterations.

**iprint**[2]

*iprint*[2] controls the verbosity of progress messages.

**iprint**[2] = 0

Print out iteration count, number of evaluations of *FOM*, value of *FOM*, norm of the gradient of *FOM*, and step length.

**iprint**[2] = 1

Same as *iprint*[2] = 0, plus *X0* and the gradient of *FOM* evaluated at *X0*.

**iprint**[2] = 2

Same as *iprint*[2] = 1, plus values of *X* at each iteration.

```
iprint[2] = 3
```

Same as `iprint[2] = 2`, plus the gradient of *FOM* at each iteration.

The columns printed by `lbfgs` are the following.

**I**            Number of iterations. It is incremented for each line search.  
**NFN**        Number of evaluations of the figure of merit.  
**FUNC**       Value of the figure of merit at the end of the most recent line search.  
**GNORM**      Norm of the gradient of the figure of merit at the end of the most recent line search.

**STEPLENGTH**

An internal parameter of the search algorithm.

Additional information concerning details of the algorithm are found in the comments of the original Fortran code [2].

See also `lbfgs_nfeval_max` and `lbfgs_ncorrections`.

References:

[1] D. Liu and J. Nocedal. "On the limited memory BFGS method for large scale optimization". *Mathematical Programming B* 45:503–528 (1989)

[2] [http://netlib.org/opt/lbfgs\\_um.shar](http://netlib.org/opt/lbfgs_um.shar)

Examples:

The same FOM as computed by `FGCOMPUTE` in the program `sdrive.f` in the `LBFGS` package from Netlib. Note that the variables in question are subscripted variables. The FOM has an exact minimum equal to zero at  $u[k] = 1$  for  $k = 1, \dots, 8$ .

```
(%i1) load (lbfgs);
(%o1) /usr/share/maxima/5.10.0cvs/share/lbfgs/lbfgs.mac
(%i2) t1[j] := 1 - u[j];
(%o2)
 t1 := 1 - u
 j
(%i3) t2[j] := 10*(u[j + 1] - u[j]^2);
 j
(%o3)
 t2 := 10 (u - u)
 j j + 1 j
(%i4) n : 8;
(%o4)
 8
(%i5) FOM : sum (t1[2*j - 1]^2 + t2[2*j - 1]^2, j, 1, n/2);
 2 2 2 2 2 2
(%o5) 100 (u - u) + (1 - u) + 100 (u - u) + (1 - u)
 8 7 7 6 5 5
 2 2 2 2 2 2 2 2
 + 100 (u - u) + (1 - u) + 100 (u - u) + (1 - u)
 4 3 3 2 1 1
(%i6) lbfgs (FOM, '[u[1],u[2],u[3],u[4],u[5],u[6],u[7],u[8]],
 [-1.2, 1, -1.2, 1, -1.2, 1, -1.2, 1], 1e-3, [1, 0]);

N= 8 NUMBER OF CORRECTIONS=25
INITIAL VALUES
F= 9.680000000000000D+01 GNORM= 4.657353755084532D+02

```

| I | NFN | FUNC                  | GNORM                 | STEPLENGTH            |
|---|-----|-----------------------|-----------------------|-----------------------|
| 1 | 3   | 1.651479526340304D+01 | 4.324359291335977D+00 | 7.926153934390631D-04 |
| 2 | 4   | 1.650209316638371D+01 | 3.575788161060007D+00 | 1.000000000000000D+00 |
| 3 | 5   | 1.645461701312851D+01 | 6.230869903601577D+00 | 1.000000000000000D+00 |
| 4 | 6   | 1.636867301275588D+01 | 1.177589920974980D+01 | 1.000000000000000D+00 |
| 5 | 7   | 1.612153014409201D+01 | 2.292797147151288D+01 | 1.000000000000000D+00 |

```

6 8 1.569118407390628D+01 3.687447158775571D+01 1.000000000000000D+00
7 9 1.510361958398942D+01 4.501931728123680D+01 1.000000000000000D+00
8 10 1.391077875774294D+01 4.526061463810632D+01 1.000000000000000D+00
9 11 1.165625686278198D+01 2.748348965356917D+01 1.000000000000000D+00
10 12 9.859422687859137D+00 2.111494974231644D+01 1.000000000000000D+00
11 13 7.815442521732281D+00 6.110762325766556D+00 1.000000000000000D+00
12 15 7.346380905773160D+00 2.165281166714631D+01 1.285316401779533D-01
13 16 6.330460634066370D+00 1.401220851762050D+01 1.000000000000000D+00
14 17 5.238763939851439D+00 1.702473787613255D+01 1.000000000000000D+00
15 18 3.754016790406701D+00 7.981845727704576D+00 1.000000000000000D+00
16 20 3.001238402309352D+00 3.925482944716691D+00 2.333129631296807D-01
17 22 2.794390709718290D+00 8.243329982546473D+00 2.503577283782332D-01
18 23 2.563783562918759D+00 1.035413426521790D+01 1.000000000000000D+00
19 24 2.019429976377856D+00 1.065187312346769D+01 1.000000000000000D+00
20 25 1.428003167670903D+00 2.475962450826961D+00 1.000000000000000D+00
21 27 1.197874264861340D+00 8.441707983493810D+00 4.303451060808756D-01
22 28 9.023848941942773D-01 1.113189216635162D+01 1.000000000000000D+00
23 29 5.508226405863770D-01 2.380830600326308D+00 1.000000000000000D+00
24 31 3.902893258815567D-01 5.625595816584421D+00 4.834988416524465D-01
25 32 3.207542206990315D-01 1.149444645416472D+01 1.000000000000000D+00
26 33 1.874468266362791D-01 3.632482152880997D+00 1.000000000000000D+00
27 34 9.575763380706598D-02 4.816497446154354D+00 1.000000000000000D+00
28 35 4.085145107543406D-02 2.087009350166495D+00 1.000000000000000D+00
29 36 1.931106001379290D-02 3.886818608498966D+00 1.000000000000000D+00
30 37 6.894000721499670D-03 3.198505796342214D+00 1.000000000000000D+00
31 38 1.443296033051864D-03 1.590265471025043D+00 1.000000000000000D+00
32 39 1.571766603154336D-04 3.098257063980634D-01 1.000000000000000D+00
33 40 1.288011776581970D-05 1.207784183577257D-02 1.000000000000000D+00
34 41 1.806140173752971D-06 4.587890233385193D-02 1.000000000000000D+00
35 42 1.769004645459358D-07 1.790537375052208D-02 1.000000000000000D+00
36 43 3.312164100763217D-10 6.782068426119681D-04 1.000000000000000D+00

```

THE MINIMIZATION TERMINATED WITHOUT DETECTING ERRORS.

IFLAG = 0

```

(%o6) [u1 = 1.000005339815974, u2 = 1.000009942839805,
 u3 = 1.000005339815974, u4 = 1.000009942839805,
 u5 = 1.000005339815974, u6 = 1.000009942839805,
 u7 = 1.000005339815974, u8 = 1.000009942839805]

```

A regression problem. The FOM is the mean square difference between the predicted value  $F(X[i])$  and the observed value  $Y[i]$ . The function  $F$  is a bounded monotone function (a so-called "sigmoidal" function). In this example, `lbfgs` computes approximate values for the parameters of  $F$  and `plot2d` displays a comparison of  $F$  with the observed data.

```

(%i1) load (lbfgs);
(%o1) /usr/share/maxima/5.10.0cvs/share/lbfgs/lbfgs.mac
(%i2) FOM : '((1/length(X))*sum((F(X[i]) - Y[i])^2, i, 1,
 length(X)));
 2
 sum((F(X) - Y) , i, 1, length(X))
 i i
(%o2) -----
 length(X)
(%i3) X : [1, 2, 3, 4, 5];
(%o3) [1, 2, 3, 4, 5]

```

```
(%i4) Y : [0, 0.5, 1, 1.25, 1.5];
(%o4) [0, 0.5, 1, 1.25, 1.5]
(%i5) F(x) := A/(1 + exp(-B*(x - C)));
(%o5) F(x) := -----
 A
 1 + exp((- B) (x - C))
(%i6) ''FOM;
(%o6) ((----- - 1.5) + (----- - 1.25)
 A 2 A 2
 - B (5 - C) - B (4 - C)
 %e + 1 %e + 1
 A 2 A 2
+ (----- - 1) + (----- - 0.5)
 - B (3 - C) - B (2 - C)
 %e + 1 %e + 1
 2
 A
+ -----)/5
 - B (1 - C) 2
 (%e + 1)
(%i7) estimates : lbfgs (FOM, '[A, B, C], [1, 1, 1], 1e-4, [1, 0]);

N= 3 NUMBER OF CORRECTIONS=25
 INITIAL VALUES
F= 1.348738534246918D-01 GNORM= 2.000215531936760D-01

```

| I | NFN | FUNC                  | GNORM                 | STEPLNGTH             |
|---|-----|-----------------------|-----------------------|-----------------------|
| 1 | 3   | 1.177820636622582D-01 | 9.893138394953992D-02 | 8.554435968992371D-01 |
| 2 | 6   | 2.302653892214013D-02 | 1.180098521565904D-01 | 2.100000000000000D+01 |
| 3 | 8   | 1.496348495303005D-02 | 9.611201567691633D-02 | 5.257340567840707D-01 |
| 4 | 9   | 7.900460841091139D-03 | 1.325041647391314D-02 | 1.000000000000000D+00 |
| 5 | 10  | 7.314495451266917D-03 | 1.510670810312237D-02 | 1.000000000000000D+00 |
| 6 | 11  | 6.750147275936680D-03 | 1.914964958023047D-02 | 1.000000000000000D+00 |
| 7 | 12  | 5.850716021108205D-03 | 1.028089194579363D-02 | 1.000000000000000D+00 |
| 8 | 13  | 5.778664230657791D-03 | 3.676866074530332D-04 | 1.000000000000000D+00 |
| 9 | 14  | 5.777818823650782D-03 | 3.010740179797255D-04 | 1.000000000000000D+00 |

```
THE MINIMIZATION TERMINATED WITHOUT DETECTING ERRORS.
IFLAG = 0
(%o7) [A = 1.461933911464101, B = 1.601593973254802,
 C = 2.528933072164854]
(%i8) plot2d ([F(x), [discrete, X, Y]], [x, -1, 6]), ''estimates;
(%o8)
```

Gradient of FOM is specified (instead of computing it automatically).

```
(%i1) load (lbfgs)$
(%i2) F(a, b, c) := (a - 5)^2 + (b - 3)^4 + (c - 2)^6;
(%o2) F(a, b, c) := (a - 5) + (b - 3) + (c - 2)
 2 4 6
(%i3) F_grad : map (lambda ([x], diff (F(a, b, c), x)), [a, b, c]);
(%o3) [2 (a - 5), 4 (b - 3) , 6 (c - 2)]
(%i4) estimates : lbfgs ([F(a, b, c), F_grad],
 [a, b, c], [0, 0, 0], 1e-4, [1, 0]);

```

```

N= 3 NUMBER OF CORRECTIONS=25
 INITIAL VALUES
F= 1.7000000000000000D+02 GNORM= 2.205175729958953D+02

```

| I  | NFN | FUNC                  | GNORM                 | STEPLength            |
|----|-----|-----------------------|-----------------------|-----------------------|
| 1  | 2   | 6.632967565917638D+01 | 6.498411132518770D+01 | 4.534785987412505D-03 |
| 2  | 3   | 4.368890936228036D+01 | 3.784147651974131D+01 | 1.000000000000000D+00 |
| 3  | 4   | 2.685298972775190D+01 | 1.640262125898521D+01 | 1.000000000000000D+00 |
| 4  | 5   | 1.909064767659852D+01 | 9.733664001790506D+00 | 1.000000000000000D+00 |
| 5  | 6   | 1.006493272061515D+01 | 6.344808151880209D+00 | 1.000000000000000D+00 |
| 6  | 7   | 1.215263596054294D+00 | 2.204727876126879D+00 | 1.000000000000000D+00 |
| 7  | 8   | 1.080252896385334D-02 | 1.431637116951849D-01 | 1.000000000000000D+00 |
| 8  | 9   | 8.407195124830908D-03 | 1.126344579730013D-01 | 1.000000000000000D+00 |
| 9  | 10  | 5.022091686198527D-03 | 7.750731829225274D-02 | 1.000000000000000D+00 |
| 10 | 11  | 2.277152808939775D-03 | 5.032810859286795D-02 | 1.000000000000000D+00 |
| 11 | 12  | 6.489384688303218D-04 | 1.932007150271008D-02 | 1.000000000000000D+00 |
| 12 | 13  | 2.075791943844548D-04 | 6.964319310814364D-03 | 1.000000000000000D+00 |
| 13 | 14  | 7.349472666162257D-05 | 4.017449067849554D-03 | 1.000000000000000D+00 |
| 14 | 15  | 2.293617477985237D-05 | 1.334590390856715D-03 | 1.000000000000000D+00 |
| 15 | 16  | 7.683645404048675D-06 | 6.011057038099201D-04 | 1.000000000000000D+00 |

```

THE MINIMIZATION TERMINATED WITHOUT DETECTING ERRORS.
IFLAG = 0
(%o4) [a = 5.000086823042934, b = 3.05239542970518,
 c = 1.927980629919583]

```

**lbfgs\_nfeval\_max**

Variable

Default value: 100

**lbfgs\_nfeval\_max** is the maximum number of evaluations of the figure of merit (FOM) in **lbfgs**. When **lbfgs\_nfeval\_max** is reached, **lbfgs** returns the result of the last successful line search.

**lbfgs\_ncorrections**

Variable

Default value: 25

**lbfgs\_ncorrections** is the number of corrections applied to the approximate inverse Hessian matrix which is maintained by **lbfgs**.



## 62 lindstedt

### 62.1 Functions and Variables for lindstedt

**Lindstedt** (*eq,pvar,torder,ic*)

Function

This is a first pass at a Lindstedt code. It can solve problems with initial conditions entered, which can be arbitrary constants, (just not %k1 and %k2) where the initial conditions on the perturbation equations are  $z[i] = 0, z'[i] = 0$  for  $i > 0$ . *ic* is the list of initial conditions.

Problems occur when initial conditions are not given, as the constants in the perturbation equations are the same as the zero order equation solution. Also, problems occur when the initial conditions for the perturbation equations are not  $z[i] = 0, z'[i] = 0$  for  $i > 0$ , such as the Van der Pol equation.

Example:

```
(%i1) load("makeOrders")$

(%i2) load("lindstedt")$

(%i3) Lindstedt('diff(x,t,2)+x-(e*x^3)/6,e,2,[1,0]);
 2
 e (cos(5 T) - 24 cos(3 T) + 23 cos(T))
(%o3) [[-----
 36864
 e (cos(3 T) - cos(T))
 - ----- + cos(T)],
 192
 2
 7 e e
T = (- ---- - -- + 1) t]]
 3072 16
```

To use this function write first `load("makeOrders")` and `load("lindstedt")`.





## 63 linearalgebra

### 63.1 Introduction to linearalgebra

linearalgebra is a collection of functions for linear algebra.

Example:

```
(%i1) M : matrix ([1, 2], [1, 2]);
 [1 2]
(%o1) []
 [1 2]

(%i2) nullspace (M);
 [1]
 []
(%o2) span([1])
 [-]
 [2]

(%i3) columnspace (M);
 [1]
(%o3) span([])
 [1]

(%i4) ptriangularize (M - z*ident(2), z);
 [1 2 - z]
(%o4) []
 [2]
 [0 3 z - z]

(%i5) M : matrix ([1, 2, 3], [4, 5, 6], [7, 8, 9]) - z*ident(3);
 [1 - z 2 3]
 []
(%o5) [4 5 - z 6]
 []
 [7 8 9 - z]

(%i6) MM : ptriangularize (M, z);
 [4 5 - z 6]
 []
 [2]
 [66 z 102 z 132]
 [0 -- - -- + ---- + ---]
(%o6) [49 7 49 49]
 []
 [3 2]
 [49 z 245 z 147 z]
 [0 0 ---- - ---- - ----]
 [264 88 44]

(%i7) algebraic : true;
(%o7) true
(%i8) tellrat (MM [3, 3]);
 3 2
(%o8) [z - 15 z - 18 z]

(%i9) MM : ratsimp (MM);
 [4 5 - z 6]
 []
 [2]
(%o9) [66 7 z - 102 z - 132]
 [0 -- - ----]
 [49 49]
```

```

 [
 [0 0 0]
]
(%i10) nullspace (MM);
 [
 [1]
 []
 [2]
 [z - 14 z - 16]
 [-----]
 [8]
]
(%o10) span([
 []
 [2]
 [z - 18 z - 12]
 [- -----]
 [12]
])
(%i11) M : matrix ([1, 2, 3, 4], [5, 6, 7, 8], [9, 10, 11, 12],
 [13, 14, 15, 16]);
 [1 2 3 4]
 []
 [5 6 7 8]
 []
 [9 10 11 12]
 []
 [13 14 15 16]
]
(%o11)
(%i12) columnspace (M);
 [1] [2]
 [] []
 [5] [6]
 [] []
 [9] [10]
 [] []
 [13] [14]
]
(%o12) span([
 [1] [2]
 [] []
 [5] [6]
 [] []
 [9] [10]
 [] []
 [13] [14]
])
(%i13) apply ('orthogonal_complement, args (nullspace (transpose (M))));
 [0] [1]
 [] []
 [1] [0]
 [] []
 [2] [- 1]
 [] []
 [3] [- 2]
]
(%o13) span([
 [1] [0]
 [] []
 [2] [- 1]
 [] []
 [3] [- 2]
])

```

## 63.2 Functions and Variables for linearalgebra

**addmatrices** ( $f, M_1, \dots, M_n$ )

Function

Using the function  $f$  as the addition function, return the sum of the matrices  $M_1, \dots, M_n$ . The function  $f$  must accept any number of arguments (a Maxima nary function).

Examples:

```

(%i1) m1 : matrix([1,2],[3,4])$
(%i2) m2 : matrix([7,8],[9,10])$
(%i3) addmatrices('max,m1,m2);
(%o3) matrix([7,8],[9,10])
(%i4) addmatrices('max,m1,m2,5*m1);
(%o4) matrix([7,10],[15,20])

```

**blockmatrixp** ( $M$ )

Function

Return true if and only if  $M$  is a matrix and every entry of  $M$  is a matrix.

**columnop** ( $M, i, j, \text{theta}$ ) Function  
 If  $M$  is a matrix, return the matrix that results from doing the column operation  $C_i \leftarrow C_i - \text{theta} * C_j$ . If  $M$  doesn't have a row  $i$  or  $j$ , signal an error.

**columnswap** ( $M, i, j$ ) Function  
 If  $M$  is a matrix, swap columns  $i$  and  $j$ . If  $M$  doesn't have a column  $i$  or  $j$ , signal an error.

**columnspace** ( $M$ ) Function  
 If  $M$  is a matrix, return `span (v_1, ..., v_n)`, where the set  $\{v_1, \dots, v_n\}$  is a basis for the column space of  $M$ . The span of the empty set is  $\{0\}$ . Thus, when the column space has only one member, return `span ()`.

**copy** ( $e$ ) Function  
 Return a copy of the Maxima expression  $e$ . Although  $e$  can be any Maxima expression, the copy function is the most useful when  $e$  is either a list or a matrix; consider:

```
(%i1) m : [1,[2,3]]$
(%i2) mm : m$
(%i3) mm[2][1] : x$
(%i4) m;
(%o4) [1,[x,3]]
(%i5) mm;
(%o5) [1,[x,3]]
```

Let's try the same experiment, but this time let  $mm$  be a copy of  $m$

```
(%i6) m : [1,[2,3]]$
(%i7) mm : copy(m)$
(%i8) mm[2][1] : x$
(%i9) m;
(%o9) [1,[2,3]]
(%i10) mm;
(%o10) [1,[x,3]]
```

This time, the assignment to  $mm$  does not change the value of  $m$ .

**cholesky** ( $M$ ) Function

**cholesky** ( $M, \text{field}$ ) Function  
 Return the Cholesky factorization of the matrix selfadjoint (or hermitian) matrix  $M$ . The second argument defaults to 'generalring.' For a description of the possible values for  $\text{field}$ , see `lu_factor`.

**ctranspose** ( $M$ ) Function  
 Return the complex conjugate transpose of the matrix  $M$ . The function `ctranspose` uses `matrix_element_transpose` to transpose each matrix element.

**diag\_matrix** ( $d_1, d_2, \dots, d_n$ ) Function  
 Return a diagonal matrix with diagonal entries  $d_1, d_2, \dots, d_n$ . When the diagonal entries are matrices, the zero entries of the returned matrix are zero matrices of the appropriate size; for example:

```
(%i1) diag_matrix(diag_matrix(1,2),diag_matrix(3,4));
(%o1) [[1 0] [0 0]]
 [[] []]
 [[0 2] [0 0]]
 [[] []]
 [[0 0] [3 0]]
```

```

 [[] []]
 [[0 0] [0 4]]
(%i2) diag_matrix(p,q);

 [p 0]
 []
(%o2) []
 [0 q]

```

**dotproduct** (*u*, *v*)

Function

Return the dotproduct of vectors *u* and *v*. This is the same as `conjugate(transpose(u)) . v`. The arguments *u* and *v* must be column vectors.

**eigens\_by\_jacobi** (*A*)

Function

**eigens\_by\_jacobi** (*A*, *field\_type*)

Function

Computes the eigenvalues and eigenvectors of *A* by the method of Jacobi rotations. *A* must be a symmetric matrix (but it need not be positive definite nor positive semidefinite). *field\_type* indicates the computational field, either `floatfield` or `bigfloatfield`. If *field\_type* is not specified, it defaults to `floatfield`.

The elements of *A* must be numbers or expressions which evaluate to numbers via `float` or `bfloat` (depending on *field\_type*).

Examples:

```

(%i1) S: matrix([1/sqrt(2), 1/sqrt(2)],[-1/sqrt(2), 1/sqrt(2)]);
 [1 1]
 [---- ----]
 [sqrt(2) sqrt(2)]
(%o1) []
 [1 1]
 [- ---- ----]
 [sqrt(2) sqrt(2)]
(%i2) L : matrix ([sqrt(3), 0], [0, sqrt(5)]);
 [sqrt(3) 0]
(%o2) []
 [0 sqrt(5)]
(%i3) M : S . L . transpose (S);
 [sqrt(5) sqrt(3) sqrt(5) sqrt(3)]
 [---- + ---- ---- - ----]
 [2 2 2 2]
(%o3) []
 [sqrt(5) sqrt(3) sqrt(5) sqrt(3)]
 [---- - ---- ---- + ----]
 [2 2 2 2]
(%i4) eigens_by_jacobi (M);
The largest percent change was 0.1454972243679
The largest percent change was 0.0
number of sweeps: 2
number of rotations: 1
(%o4) [[1.732050807568877, 2.23606797749979],
 [0.70710678118655 0.70710678118655]
 []
 [- 0.70710678118655 0.70710678118655]
(%i5) float ([[sqrt(3), sqrt(5)], S]);
(%o5) [[1.732050807568877, 2.23606797749979],
 [0.70710678118655 0.70710678118655]
 []
 [- 0.70710678118655 0.70710678118655]

```

```
(%i6) eigens_by_jacobi (M, bigfloatfield);
The largest percent change was 1.454972243679028b-1
The largest percent change was 0.0b0
number of sweeps: 2
number of rotations: 1
(%o6) [[1.732050807568877b0, 2.23606797749979b0],
 [7.071067811865475b-1 7.071067811865475b-1]
 [
 [- 7.071067811865475b-1 7.071067811865475b-1]]
```

**get\_lu\_factors** (*x*) Function

When  $x = \text{lu\_factor}(A)$ , then **get\_lu\_factors** returns a list of the form  $[P, L, U]$ , where  $P$  is a permutation matrix,  $L$  is lower triangular with ones on the diagonal, and  $U$  is upper triangular, and  $A = P L U$ .

**hankel** (*col*) Function

**hankel** (*col*, *row*) Function

Return a Hankel matrix  $H$ . The first column of  $H$  is *col*; except for the first entry, the last row of  $H$  is *row*. The default for *row* is the zero vector with the same length as *col*.

**hessian** (*f*, *x*) Function

Returns the Hessian matrix of  $f$  with respect to the list of variables  $x$ . The  $(i, j)$ -th element of the Hessian matrix is  $\text{diff}(f, x[i], 1, x[j], 1)$ .

Examples:

```
(%i1) hessian (x * sin (y), [x, y]);
 [0 cos(y)]
(%o1) [
 [cos(y) - x sin(y)]

(%i2) depends (F, [a, b]);
(%o2) [F(a, b)]

(%i3) hessian (F, [a, b]);
 [2 2]
 [d F d F]
 [--- -----]
 [2 da db]
 [da]
(%o3) [
 [2 2]
 [d F d F]
 [----- ---]
 [da db 2]
 [db]
```

**hilbert\_matrix** (*n*) Function

Return the  $n$  by  $n$  Hilbert matrix. When  $n$  isn't a positive integer, signal an error.

**identfor** (*M*) Function

**identfor** (*M*, *fld*) Function

Return an identity matrix that has the same shape as the matrix  $M$ . The diagonal entries of the identity matrix are the multiplicative identity of the field *fld*; the default for *fld* is *generalring*.

The first argument  $M$  should be a square matrix or a non-matrix. When  $M$  is a matrix, each entry of  $M$  can be a square matrix – thus  $M$  can be a blocked Maxima matrix. The matrix can be blocked to any (finite) depth.

See also **zerofor**

**invert\_by\_lu** ( $M$ , ( $rng$  generalring)) Function  
 Invert a matrix  $M$  by using the LU factorization. The LU factorization is done using the ring  $rng$ .

**jacobian** ( $f$ ,  $x$ ) Function  
 Returns the Jacobian matrix of the list of functions  $f$  with respect to the list of variables  $x$ . The  $(i, j)$ -th element of the Jacobian matrix is `diff(f[i], x[j])`.

Examples:

```
(%i1) jacobian ([sin (u - v), sin (u * v)], [u, v]);
 [cos(v - u) - cos(v - u)]
(%o1) [
 [v cos(u v) u cos(u v)]
(%i2) depends ([F, G], [y, z]);
(%o2) [F(y, z), G(y, z)]
(%i3) jacobian ([F, G], [y, z]);
 [dF dF]
 [-- --]
 [dy dz]
(%o3) [
 [dG dG]
 [-- --]
 [dy dz]
```

**kronecker\_product** ( $A$ ,  $B$ ) Function  
 Return the Kronecker product of the matrices  $A$  and  $B$ .

**listp** ( $e$ ,  $p$ ) Function  
**listp** ( $e$ ) Function  
 Given an optional argument  $p$ , return **true** if  $e$  is a Maxima list and  $p$  evaluates to **true** for every list element. When **listp** is not given the optional argument, return **true** if  $e$  is a Maxima list. In all other cases, return **false**.

**locate\_matrix\_entry** ( $M$ ,  $r_1$ ,  $c_1$ ,  $r_2$ ,  $c_2$ ,  $f$ ,  $rel$ ) Function  
 The first argument must be a matrix; the arguments  $r_1$  through  $c_2$  determine a sub-matrix of  $M$  that consists of rows  $r_1$  through  $r_2$  and columns  $c_1$  through  $c_2$ .  
 Find a entry in the sub-matrix  $M$  that satisfies some property. Three cases:  
 (1)  $rel = 'bool$  and  $f$  a predicate:  
 Scan the sub-matrix from left to right then top to bottom, and return the index of the first entry that satisfies the predicate  $f$ . If no matrix entry satisfies  $f$ , return **false**.  
 (2)  $rel = 'max$  and  $f$  real-valued:  
 Scan the sub-matrix looking for an entry that maximizes  $f$ . Return the index of a maximizing entry.  
 (3)  $rel = 'min$  and  $f$  real-valued:  
 Scan the sub-matrix looking for an entry that minimizes  $f$ . Return the index of a minimizing entry.

**lu\_backsub** ( $M$ ,  $b$ ) Function  
 When  $M = lu\_factor(A, field)$ , then **lu\_backsub** ( $M$ ,  $b$ ) solves the linear system  $A x = b$ .

**lu\_factor** (*M*, *field*)

Function

Return a list of the form  $[LU, perm, fld]$ , or  $[LU, perm, fld, lower-cnd\ upper-cnd]$ , where

(1) The matrix  $LU$  contains the factorization of  $M$  in a packed form. Packed form means three things: First, the rows of  $LU$  are permuted according to the list  $perm$ . If, for example,  $perm$  is the list  $[3, 2, 1]$ , the actual first row of the  $LU$  factorization is the third row of the matrix  $LU$ . Second, the lower triangular factor of  $m$  is the lower triangular part of  $LU$  with the diagonal entries replaced by all ones. Third, the upper triangular factor of  $M$  is the upper triangular part of  $LU$ .

(2) When the field is either `floatfield` or `complexfield`, the numbers *lower-cnd* and *upper-cnd* are lower and upper bounds for the infinity norm condition number of  $M$ . For all fields, the condition number might not be estimated; for such fields, `lu_factor` returns a two item list. Both the lower and upper bounds can differ from their true values by arbitrarily large factors. (See also `mat_cond`.)

The argument  $M$  must be a square matrix.

The optional argument *fld* must be a symbol that determines a ring or field. The pre-defined fields and rings are:

- (a) `generalring` – the ring of Maxima expressions,
- (b) `floatfield` – the field of floating point numbers of the type double,
- (c) `complexfield` – the field of complex floating point numbers of the type double,
- (d) `crering` – the ring of Maxima CRE expressions,
- (e) `rationalfield` – the field of rational numbers,
- (f) `runningerror` – track the all floating point rounding errors,
- (g) `noncommutingring` – the ring of Maxima expressions where multiplication is the non-commutative dot operator.

When the field is `floatfield`, `complexfield`, or `runningerror`, the algorithm uses partial pivoting; for all other fields, rows are switched only when needed to avoid a zero pivot.

Floating point addition arithmetic isn't associative, so the meaning of 'field' differs from the mathematical definition.

A member of the field `runningerror` is a two member Maxima list of the form  $[x, n]$ , where  $x$  is a floating point number and  $n$  is an integer. The relative difference between the 'true' value of  $x$  and  $x$  is approximately bounded by the machine epsilon times  $n$ . The running error bound drops some terms that of the order the square of the machine epsilon.

There is no user-interface for defining a new field. A user that is familiar with Common Lisp should be able to define a new field. To do this, a user must define functions for the arithmetic operations and functions for converting from the field representation to Maxima and back. Additionally, for ordered fields (where partial pivoting will be used), a user must define functions for the magnitude and for comparing field members. After that all that remains is to define a Common Lisp structure `mring`. The file `mring` has many examples.

To compute the factorization, the first task is to convert each matrix entry to a member of the indicated field. When conversion isn't possible, the factorization halts with an error message. Members of the field needn't be Maxima expressions. Members of the `complexfield`, for example, are Common Lisp complex numbers. Thus after computing the factorization, the matrix entries must be converted to Maxima expressions.

See also `get_lu_factors`.

Examples:

```
(%i1) w[i,j] := random (1.0) + %i * random (1.0);
(%o1) w := random(1.) + %i random(1.)
 i, j
(%i2) showtime : true$
Evaluation took 0.00 seconds (0.00 elapsed)
(%i3) M : genmatrix (w, 100, 100)$
Evaluation took 7.40 seconds (8.23 elapsed)
```

```
(%i4) lu_factor (M, complexfield)$
Evaluation took 28.71 seconds (35.00 elapsed)
(%i5) lu_factor (M, generalring)$
Evaluation took 109.24 seconds (152.10 elapsed)
(%i6) showtime : false$

(%i7) M : matrix ([1 - z, 3], [3, 8 - z]);
 [1 - z 3]
(%o7) []
 [3 8 - z]
(%i8) lu_factor (M, generalring);
 [1 - z 3]
 []
(%o8) [[3 9], [1, 2], generalring]
 [----- - z - ----- + 8]
 [1 - z 1 - z]
(%i9) get_lu_factors (%);
 [1 0] [1 - z 3]
 [1 0] [] []
(%o9) [[], [3], []
 [0 1] [----- 1] [0 - z - ----- + 8]
 [1 - z] [1 - z]
(%i10) %[1] . %[2] . %[3];
 [1 - z 3]
(%o10) []
 [3 8 - z]
```

**mat\_cond** ( $M, 1$ ) Function  
**mat\_cond** ( $M, inf$ ) Function

Return the  $p$ -norm matrix condition number of the matrix  $m$ . The allowed values for  $p$  are 1 and  $inf$ . This function uses the LU factorization to invert the matrix  $m$ . Thus the running time for **mat\_cond** is proportional to the cube of the matrix size; **lu\_factor** determines lower and upper bounds for the infinity norm condition number in time proportional to the square of the matrix size.

**mat\_norm** ( $M, 1$ ) Function  
**mat\_norm** ( $M, inf$ ) Function  
**mat\_norm** ( $M, frobenius$ ) Function

Return the matrix  $p$ -norm of the matrix  $M$ . The allowed values for  $p$  are 1,  $inf$ , and **frobenius** (the Frobenius matrix norm). The matrix  $M$  should be an unblocked matrix.

**matrixp** ( $e, p$ ) Function  
**matrixp** ( $e$ ) Function

Given an optional argument  $p$ , return **true** if  $e$  is a matrix and  $p$  evaluates to **true** for every matrix element. When **matrixp** is not given an optional argument, return **true** if  $e$  is a matrix. In all other cases, return **false**.

See also **blockmatrixp**

**matrix\_size** ( $M$ ) Function

Return a two member list that gives the number of rows and columns, respectively of the matrix  $M$ .

**mat\_fullunblocker** ( $M$ ) Function

If  $M$  is a block matrix, unblock the matrix to all levels. If  $M$  is a matrix, return  $M$ ; otherwise, signal an error.



**mat\_trace** (*M*) Function  
 Return the trace of the matrix *M*. If *M* isn't a matrix, return a noun form. When *M* is a block matrix, **mat\_trace**(*M*) returns the same value as does **mat\_trace**(**mat\_unblocker**(*m*)).

**mat\_unblocker** (*M*) Function  
 If *M* is a block matrix, unblock *M* one level. If *M* is a matrix, **mat\_unblocker** (*M*) returns *M*; otherwise, signal an error.  
 Thus if each entry of *M* is matrix, **mat\_unblocker** (*M*) returns an unblocked matrix, but if each entry of *M* is a block matrix, **mat\_unblocker** (*M*) returns a block matrix with one less level of blocking.  
 If you use block matrices, most likely you'll want to set **matrix\_element\_mult** to "." and **matrix\_element\_transpose** to 'transpose'. See also **mat\_fullunblocker**.

Example:

```
(%i1) A : matrix ([1, 2], [3, 4]);
 [1 2]
(%o1) []
 [3 4]
(%i2) B : matrix ([7, 8], [9, 10]);
 [7 8]
(%o2) []
 [9 10]
(%i3) matrix ([A, B]);
 [[1 2] [7 8]]
(%o3) [[] []]
 [[3 4] [9 10]]
(%i4) mat_unblocker (%);
 [1 2 7 8]
(%o4) []
 [3 4 9 10]
```

**nullspace** (*M*) Function  
 If *M* is a matrix, return **span** (*v*<sub>1</sub>, ..., *v*<sub>*n*</sub>), where the set {*v*<sub>1</sub>, ..., *v*<sub>*n*</sub>} is a basis for the nullspace of *M*. The span of the empty set is {0}. Thus, when the nullspace has only one member, return **span** ().

**nullity** (*M*) Function  
 If *M* is a matrix, return the dimension of the nullspace of *M*.

**orthogonal\_complement** (*v*<sub>1</sub>, ..., *v*<sub>*n*</sub>) Function  
 Return **span** (*u*<sub>1</sub>, ..., *u*<sub>*m*</sub>), where the set {*u*<sub>1</sub>, ..., *u*<sub>*m*</sub>} is a basis for the orthogonal complement of the set (*v*<sub>1</sub>, ..., *v*<sub>*n*</sub>).  
 Each vector *v*<sub>1</sub> through *v*<sub>*n*</sub> must be a column vector.

**polynomialp** (*p*, *L*, *coeffp*, *exponp*) Function  
**polynomialp** (*p*, *L*, *coeffp*) Function  
**polynomialp** (*p*, *L*) Function

Return **true** if *p* is a polynomial in the variables in the list *L*. The predicate *coeffp* must evaluate to **true** for each coefficient, and the predicate *exponp* must evaluate to **true** for all exponents of the variables in *L*. If you want to use a non-default value for *exponp*, you must supply *coeffp* with a value even if you want to use the default for *coeffp*.

The command **polynomialp** (*p*, *L*, *coeffp*) is equivalent to **polynomialp** (*p*, *L*, *coeffp*, 'nonnegintegerp') and the command **polynomialp** (*p*, *L*) is equivalent to **polynomialp** (*p*, *L*, 'constantp', 'nonnegintegerp').

The polynomial needn't be expanded:

```
(%i1) polynomialp ((x + 1)*(x + 2), [x]);
(%o1) true
(%i2) polynomialp ((x + 1)*(x + 2)^a, [x]);
(%o2) false
```

An example using non-default values for `coeff` and `exponp`:

```
(%i1) polynomialp ((x + 1)*(x + 2)^(3/2), [x], numberp, numberp);
(%o1) true
(%i2) polynomialp ((x^(1/2) + 1)*(x + 2)^(3/2), [x], numberp,
 numberp);
(%o2) true
```

Polynomials with two variables:

```
(%i1) polynomialp (x^2 + 5*x*y + y^2, [x]);
(%o1) false
(%i2) polynomialp (x^2 + 5*x*y + y^2, [x, y]);
(%o2) true
```

### **polytocompanion** ( $p, x$ )

Function

If  $p$  is a polynomial in  $x$ , return the companion matrix of  $p$ . For a monic polynomial  $p$  of degree  $n$ , we have  $p = (-1)^n \text{charpoly}(\text{polytocompanion}(p, x))$ .

When  $p$  isn't a polynomial in  $x$ , signal an error.

### **ptriangularize** ( $M, v$ )

Function

If  $M$  is a matrix with each entry a polynomial in  $v$ , return a matrix  $M2$  such that

- (1)  $M2$  is upper triangular,
- (2)  $M2 = E_{-n} \dots E_{-1} M$ , where  $E_{-1}$  through  $E_{-n}$  are elementary matrices whose entries are polynomials in  $v$ ,
- (3)  $|\det(M)| = |\det(M2)|$ ,

Note: This function doesn't check that every entry is a polynomial in  $v$ .

### **rowop** ( $M, i, j, \text{theta}$ )

Function

If  $M$  is a matrix, return the matrix that results from doing the row operation  $R_i \leftarrow R_i - \text{theta} * R_j$ . If  $M$  doesn't have a row  $i$  or  $j$ , signal an error.

### **rank** ( $M$ )

Function

Return the rank of that matrix  $M$ . The rank is the dimension of the column space. Example:

```
(%i1) rank(matrix([1,2],[2,4]));
(%o1) 1
(%i2) rank(matrix([1,b],[c,d]));
Proviso: {d - b c # 0}
(%o2) 2
```

### **rowswap** ( $M, i, j$ )

Function

If  $M$  is a matrix, swap rows  $i$  and  $j$ . If  $M$  doesn't have a row  $i$  or  $j$ , signal an error.

### **toeplitz** ( $col$ )

Function

### **toeplitz** ( $col, row$ )

Function

Return a Toeplitz matrix  $T$ . The first first column of  $T$  is  $col$ ; except for the first entry, the first row of  $T$  is  $row$ . The default for  $row$  is complex conjugate of  $col$ . Example:

```
(%i1) toeplitz([1,2,3],[x,y,z]);
 [1 y z]
 []
(%o1) [2 1 y]
 []
 [3 2 1]

(%i2) toeplitz([1,1+%i]);
 [1 1 - %I]
(%o2) []
 [%I + 1 1]
```

**vandermonde\_matrix** ( $[x_1, \dots, x_n]$ )

Function

Return a  $n$  by  $n$  matrix whose  $i$ -th row is  $[1, x_i, x_i^2, \dots, x_i^{(n-1)}]$ .

**zerofor** ( $M$ )

Function

**zerofor** ( $M, fld$ )

Function

Return a zero matrix that has the same shape as the matrix  $M$ . Every entry of the zero matrix is the additive identity of the field  $fld$ ; the default for  $fld$  is *generalring*.

The first argument  $M$  should be a square matrix or a non-matrix. When  $M$  is a matrix, each entry of  $M$  can be a square matrix – thus  $M$  can be a blocked Maxima matrix. The matrix can be blocked to any (finite) depth.

See also **identfor**

**zeromatrixp** ( $M$ )

Function

If  $M$  is not a block matrix, return **true** if **is (equal (e, 0))** is true for each element  $e$  of the matrix  $M$ . If  $M$  is a block matrix, return **true** if **zeromatrixp** evaluates to **true** for each element of  $e$ .



## 64 lsquares

### 64.1 Introduction to lsquares

**lsquares** is a collection of functions to implement the method of least squares to estimate parameters for a model from numerical data.

### 64.2 Functions and Variables for lsquares

**lsquares\_estimates** (*D*, *x*, *e*, *a*) Function

**lsquares\_estimates** (*D*, *x*, *e*, *a*, *initial* = *L*, *tol* = *t*) Function

Estimate parameters *a* to best fit the equation *e* in the variables *x* and *a* to the data *D*, as determined by the method of least squares. **lsquares\_estimates** first seeks an exact solution, and if that fails, then seeks an approximate solution.

The return value is a list of lists of equations of the form [*a* = ..., *b* = ..., *c* = ...]. Each element of the list is a distinct, equivalent minimum of the mean square error.

The data *D* must be a matrix. Each row is one datum (which may be called a ‘record’ or ‘case’ in some contexts), and each column contains the values of one variable across all data. The list of variables *x* gives a name for each column of *D*, even the columns which do not enter the analysis. The list of parameters *a* gives the names of the parameters for which estimates are sought. The equation *e* is an expression or equation in the variables *x* and *a*; if *e* is not an equation, it is treated the same as *e* = 0.

Additional arguments to **lsquares\_estimates** are specified as equations and passed on verbatim to the function **lbfgs** which is called to find estimates by a numerical method when an exact result is not found.

If some exact solution can be found (via **solve**), the data *D* may contain non-numeric values. However, if no exact solution is found, each element of *D* must have a numeric value. This includes numeric constants such as **%pi** and **%e** as well as literal numbers (integers, rationals, ordinary floats, and bigfloats). Numerical calculations are carried out with ordinary floating-point arithmetic, so all other kinds of numbers are converted to ordinary floats for calculations.

**load(lsquares)** loads this function.

See also **lsquares\_estimates\_exact**, **lsquares\_estimates\_approximate**, **lsquares\_mse**, **lsquares\_residuals**, and **lsquares\_residual\_mse**.

Examples:

A problem for which an exact solution is found.

```
(%i1) load (lsquares)$
(%i2) M : matrix (
 [1,1,1], [3/2,1,2], [9/4,2,1], [3,2,2], [2,2,1]);
 [1 1 1]
 []
 [3]
 [- 1 2]
 [2]
 []
 [9]
 [- 2 1]
 [4]
 []
 [3 2 2]
 []
 [2 2 1]

(%o2)

(%i3) lsquares_estimates (
```

```

M, [z,x,y], (z+D)^2 = A*x+B*y+C, [A,B,C,D]);
(%o3) 59 27 10921 107
 [[A = - --, B = - --, C = ----, D = - ---]]
 16 16 1024 32

```

A problem for which no exact solution is found, so `lsquares_estimates` resorts to numerical approximation.

```

(%i1) load (lsquares)$
(%i2) M : matrix ([1, 1], [2, 7/4], [3, 11/4], [4, 13/4]);
 [1 1]
 []
 [7]
 [2 -]
 [4]
 []
(%o2) [11]
 [3 --]
 [4]
 []
 [13]
 [4 --]
 [4]

(%i3) lsquares_estimates (
 M, [x,y], y=a*x^b+c, [a,b,c], initial=[3,3,3], iprint=[-1,0]);
(%o3) [[a = 1.387365874920637, b = .7110956639593767,
 c = - .4142705622439105]]

```

### **lsquares\_estimates\_exact** (*MSE*, *a*)

Function

Estimate parameters *a* to minimize the mean square error *MSE*, by constructing a system of equations and attempting to solve them symbolically via `solve`. The mean square error is an expression in the parameters *a*, such as that returned by `lsquares_mse`.

The return value is a list of lists of equations of the form `[a = ..., b = ..., c = ...]`. The return value may contain zero, one, or two or more elements. If two or more elements are returned, each represents a distinct, equivalent minimum of the mean square error.

See also `lsquares_estimates`, `lsquares_estimates_approximate`, `lsquares_mse`, `lsquares_residuals`, and `lsquares_residual_mse`.

Example:

```

(%i1) load (lsquares)$
(%i2) M : matrix (
 [1,1,1], [3/2,1,2], [9/4,2,1], [3,2,2], [2,2,1]);
 [1 1 1]
 []
 [3]
 [- 1 2]
 [2]
 []
(%o2) [9]
 [- 2 1]
 [4]
 []
 [3 2 2]
 []
 [2 2 1]

(%i3) mse : lsquares_mse (M, [z, x, y], (z + D)^2 = A*x + B*y + C);
 5
 ====
 \
 2
 2

```

```

> ((D + M) - C - M B - M A)
/ i, 1 i, 3 i, 2
====
i = 1
(%o3) -----
 5
(%i4) lsquares_estimates_exact (mse, [A, B, C, D]);
 59 27 10921 107
(%o4) [[A = - --, B = - --, C = -----, D = - ----]]
 16 16 1024 32

```

**lsquares\_estimates\_approximate** (*MSE*, *a*, *initial* = *L*, *tol* = *t*) Function

Estimate parameters *a* to minimize the mean square error *MSE*, via the numerical minimization function **lbfgs**. The mean square error is an expression in the parameters *a*, such as that returned by **lsquares\_mse**.

The solution returned by **lsquares\_estimates\_approximate** is a local (perhaps global) minimum of the mean square error. For consistency with **lsquares\_estimates\_exact**, the return value is a nested list which contains one element, namely a list of equations of the form [*a* = ..., *b* = ..., *c* = ...].

Additional arguments to **lsquares\_estimates\_approximate** are specified as equations and passed on verbatim to the function **lbfgs**.

*MSE* must evaluate to a number when the parameters are assigned numeric values. This requires that the data from which *MSE* was constructed comprise only numeric constants such as **%pi** and **%e** and literal numbers (integers, rationals, ordinary floats, and bigfloats). Numerical calculations are carried out with ordinary floating-point arithmetic, so all other kinds of numbers are converted to ordinary floats for calculations.

**load(lsquares)** loads this function.

See also **lsquares\_estimates**, **lsquares\_estimates\_exact**, **lsquares\_mse**, **lsquares\_residuals**, and **lsquares\_residual\_mse**.

Example:

```

(%i1) load (lsquares)$
(%i2) M : matrix (
 [1,1,1], [3/2,1,2], [9/4,2,1], [3,2,2], [2,2,1]);
 [1 1 1]
 []
 [3]
 [- 1 2]
 [2]
 []
(%o2) [9]
 [- 2 1]
 [4]
 []
 [3 2 2]
 []
 [2 2 1]
(%i3) mse : lsquares_mse (M, [z, x, y], (z + D)^2 = A*x + B*y + C);
 5
 ====
 \
 > ((D + M)^2 - C - M B - M A)^2
 / i, 1 i, 3 i, 2
 ====
 i = 1
(%o3) -----
 5

```

```
(%i4) lsquares_estimates_approximate (
 mse, [A, B, C, D], iprint = [-1, 0]);
(%o4) [[A = - 3.67850494740174, B = - 1.683070351177813,
 C = 10.63469950148635, D = - 3.340357993175206]]
```

**lsquares\_mse** (*D*, *x*, *e*)

Function

Returns the mean square error (MSE), a summation expression, for the equation *e* in the variables *x*, with data *D*.

The MSE is defined as:

$$\frac{1}{n} \sum_{i=1}^n [\text{lhs}(e_i) - \text{rhs}(e_i)]^2,$$

where *n* is the number of data and *e*[*i*] is the equation *e* evaluated with the variables in *x* assigned values from the *i*-th datum, *D*[*i*].

load(lsquares) loads this function.

Example:

```
(%i1) load (lsquares)$
(%i2) M : matrix (
 [1,1,1], [3/2,1,2], [9/4,2,1], [3,2,2], [2,2,1]);
 [1 1 1]
 []
 [3]
 [- 1 2]
 [2]
 []
 [9]
 [- 2 1]
 [4]
 []
 [3 2 2]
 []
 [2 2 1]
(%o2)
 [1 1 1]
 []
 [3]
 [- 1 2]
 [2]
 []
 [9]
 [- 2 1]
 [4]
 []
 [3 2 2]
 []
 [2 2 1]

(%i3) mse : lsquares_mse (M, [z, x, y], (z + D)^2 = A*x + B*y + C);
 5
 ====
 \
 > ((D + M)^2 - C - M B - M A)
 / i, 1 i, 3 i, 2
 ====
 i = 1
(%o3) -----
 5

(%i4) diff (mse, D);
 5
 ====
 \
 4 > (D + M) ((D + M)^2 - C - M B - M A)
 / i, 1 i, 1 i, 3 i, 2
 ====
 i = 1
(%o4) -----
 5

(%i5) ''mse, nouns;
```



$$\begin{aligned}
& \text{(\%o5)} \quad \left( (D+3)^2 - C - 2B - 2A \right)^2 + \left( (D+\frac{9}{4})^2 - C - B - 2A \right)^2 \\
& + \left( (D+2)^2 - C - B - 2A \right)^2 + \left( (D+\frac{3}{2})^2 - C - 2B - A \right)^2 \\
& + \left( (D+1)^2 - C - B - A \right)^2 \bigg/ 5
\end{aligned}$$

**lsquares\_residuals** (*D*, *x*, *e*, *a*)

Function

Returns the residuals for the equation *e* with specified parameters *a* and data *D*.

*D* is a matrix, *x* is a list of variables, *e* is an equation or general expression; if not an equation, *e* is treated as if it were *e* = 0. *a* is a list of equations which specify values for any free parameters in *e* aside from *x*.

The residuals are defined as:

$$\text{lhs}(e_i) - \text{rhs}(e_i),$$

where *e*[*i*] is the equation *e* evaluated with the variables in *x* assigned values from the *i*-th datum, *D*[*i*], and assigning any remaining free variables from *a*.

`load(lsquares)` loads this function.

Example:

```

(%i1) load (lsquares)$
(%i2) M : matrix (
 [1,1,1], [3/2,1,2], [9/4,2,1], [3,2,2], [2,2,1]);
 [1 1 1]
 []
 [3]
 [- 1 2]
 [2]
 []
 [9]
 [- 2 1]
 [4]
 []
 [3 2 2]
 []
 [2 2 1]
(%o2)
(%i3) a : lsquares_estimates (
 M, [z,x,y], (z+D)^2 = A*x+B*y+C, [A,B,C,D]);
 59 27 10921 107
(%o3) [[A = - --, B = - --, C = ----, D = - ---]]
 16 16 1024 32
(%i4) lsquares_residuals (
 M, [z,x,y], (z+D)^2 = A*x+B*y+C, first(a));
 13 13 13 13 13
(%o4) [--, - --, - --, --, --]
 64 64 32 64 64

```

**lsquares\_residual\_mse** (*D*, *x*, *e*, *a*)

Function

Returns the residual mean square error (MSE) for the equation *e* with specified parameters *a* and data *D*.

The residual MSE is defined as:

$$\frac{1}{n} \sum_{i=1}^n [\text{lhs}(e_i) - \text{rhs}(e_i)]^2,$$

where  $e[i]$  is the equation  $e$  evaluated with the variables in  $x$  assigned values from the  $i$ -th datum,  $D[i]$ , and assigning any remaining free variables from  $a$ .

`load(lsquares)` loads this function.

Example:

```
(%i1) load (lsquares)$
(%i2) M : matrix (
 [1,1,1], [3/2,1,2], [9/4,2,1], [3,2,2], [2,2,1]);
 [1 1 1]
 []
 [3]
 [- 1 2]
 [2]
 []
 [9]
 [- 2 1]
 [4]
 []
 [3 2 2]
 []
 [2 2 1]
(%o2)
(%i3) a : lsquares_estimates (
 M, [z,x,y], (z+D)^2 = A*x+B*y+C, [A,B,C,D]);
 59 27 10921 107
(%o3) [[A = - --, B = - --, C = ----, D = - ----]]
 16 16 1024 32
(%i4) lsquares_residual_mse (
 M, [z,x,y], (z + D)^2 = A*x + B*y + C, first (a));
 169
(%o4) ----
 2560
```

**plsquares** (*Mat*, *VarList*, *depvars*)

Function

**plsquares** (*Mat*, *VarList*, *depvars*, *maxexpon*)

Function

**plsquares** (*Mat*, *VarList*, *depvars*, *maxexpon*, *maxdegree*)

Function

Multivariable polynomial adjustment of a data table by the "least squares" method. *Mat* is a matrix containing the data, *VarList* is a list of variable names (one for each *Mat* column, but use "-" instead of varnames to ignore *Mat* columns), *depvars* is the name of a dependent variable or a list with one or more names of dependent variables (which names should be in *VarList*), *maxexpon* is the optional maximum exponent for each independent variable (1 by default), and *maxdegree* is the optional maximum polynomial degree (*maxexpon* by default); note that the sum of exponents of each term must be equal or smaller than *maxdegree*, and if *maxdegree* = 0 then no limit is applied.

If *depvars* is the name of a dependent variable (not in a list), **plsquares** returns the adjusted polynomial. If *depvars* is a list of one or more dependent variables, **plsquares** returns a list with the adjusted polynomial(s). The Coefficients of Determination are displayed in order to inform about the goodness of fit, which ranges from 0 (no correlation) to 1 (exact correlation). These values are also stored in the global variable *DETCOE* (a list if *depvars* is a list).

A simple example of multivariable linear adjustment:

```
(%i1) load("plsquares")$

(%i2) plsquares(matrix([1,2,0],[3,5,4],[4,7,9],[5,8,10]),
 [x,y,z],z);
 Determination Coefficient for z = .9897039897039897
 11 y - 9 x - 14
```

```
(%o2) z = -----
 3
```

The same example without degree restrictions:

```
(%i3) plsquares(matrix([1,2,0],[3,5,4],[4,7,9],[5,8,10]),
 [x,y,z],z,1,0);
Determination Coefficient for z = 1.0
 x y + 23 y - 29 x - 19
(%o3) z = -----
 6
```

How many diagonals does a N-sides polygon have? What polynomial degree should be used?

```
(%i4) plsquares(matrix([3,0],[4,2],[5,5],[6,9],[7,14],[8,20]),
 [N,diagonals],diagonals,5);
Determination Coefficient for diagonals = 1.0
 2
 N - 3 N
(%o4) diagonals = -----
 2
(%i5) ev(% , N=9); /* Testing for a 9 sides polygon */
(%o5) diagonals = 27
```

How many ways do we have to put two queens without they are threatened into a n x n chessboard?

```
(%i6) plsquares(matrix([0,0],[1,0],[2,0],[3,8],[4,44]),
 [n,positions],[positions],4);
Determination Coefficient for [positions] = [1.0]
 4 3 2
 3 n - 10 n + 9 n - 2 n
(%o6) [positions = -----]
 6
(%i7) ev(%[1], n=8); /* Testing for a (8 x 8) chessboard */
(%o7) positions = 1288
```

An example with six dependent variables:

```
(%i8) mtrx:matrix([0,0,0,0,0,1,1,1],[0,1,0,1,1,1,0,0],
 [1,0,0,1,1,1,0,0],[1,1,1,1,0,0,0,1])$
(%i8) plsquares(mtrx,[a,b,_And,_Or,_Xor,_Nand,_Nor,_Nxor],
 [_And,_Or,_Xor,_Nand,_Nor,_Nxor],1,0);
Determination Coefficient for
[_And, _Or, _Xor, _Nand, _Nor, _Nxor] =
[1.0, 1.0, 1.0, 1.0, 1.0, 1.0]
(%o2) [_And = a b, _Or = - a b + b + a,
_Xor = - 2 a b + b + a, _Nand = 1 - a b,
_Nor = a b - b - a + 1, _Nxor = 2 a b - b - a + 1]
```

To use this function write first load("lsquares").



## 65 minpack

### 65.1 Introduction to minpack

Minpack is a Common Lisp translation (via `f2cl`) of the Fortran library MINPACK, as obtained from Netlib.

### 65.2 Functions and Variables for minpack

**minpack\_lsquares** (*flist*, *varlist*, *guess* [, *tolerance*, *jacobian*]) Function

Compute the point that minimizes the sum of the squares of the functions in the list *flist*. The variables are in the list *varlist*. An initial guess of the optimum point must be provided in *guess*.

The optional keyword arguments, *tolerance* and *jacobian* provide some control over the algorithm. *tolerance* is the estimated relative error desired in the sum of squares. *jacobian* can be used to specify the Jacobian. If *jacobian* is not given or is `true` (the default), the Jacobian is computed from *flist*. If *jacobian* is `false`, a numerical approximation is used.

**minpack\_lsquares** returns a list. The first item is the estimated solution; the second is the sum of squares, and the third indicates the success of the algorithm. The possible values are

- 0        improper input parameters.
- 1        algorithm estimates that the relative error in the sum of squares is at most **tolerance**.
- 2        algorithm estimates that the relative error between *x* and the solution is at most **tolerance**.
- 3        conditions for `info = 1` and `info = 2` both hold.
- 4        *fvec* is orthogonal to the columns of the jacobian to machine precision.
- 5        number of calls to *fcn* with `iflag = 1` has reached `100*(n+1)`.
- 6        *tol* is too small. no further reduction in the sum of squares is possible.
- 7        *tol* is too small. no further improvement in the approximate solution *x* is possible.

```
/* Problem 6: Powell singular function */
(%i1) powell(x1,x2,x3,x4) :=
 [x1+10*x2, sqrt(5)*(x3-x4), (x2-2*x3)^2,
 sqrt(10)*(x1-x4)^2]$
(%i2) minpack_lsquares(powell(x1,x2,x3,x4), [x1,x2,x3,x4],
 [3,-1,0,1]);
(%o2) [[1.652117596168394e-17, - 1.652117596168393e-18,
 2.643388153869468e-18, 2.643388153869468e-18],
 6.109327859207777e-34, 4]
/* Same problem but use numerical approximation to Jacobian */
(%i3) minpack_lsquares(powell(x1,x2,x3,x4), [x1,x2,x3,x4],
 [3,-1,0,1], jacobian = false);
(%o3) [[5.060282149485331e-11, - 5.060282149491206e-12,
 2.179447843547218e-11, 2.179447843547218e-11],
 3.534491794847031e-21, 5]
```

**minpack\_solve** (*flist*, *varlist*, *guess* [, *tolerance*, *jacobian*]) Function

Solve a system of *n* equations in *n* unknowns. The *n* equations are given in the list *flist*, and the unknowns are in *varlist*. An initial guess of the solution must be provided in *guess*.

The optional keyword arguments, *tolerance* and *jacobian* provide some control over the algorithm. *tolerance* is the estimated relative error desired in the sum of squares. *jacobian* can be used to specify the Jacobian. If *jacobian* is not given or is **true** (the default), the Jacobian is computed from *flist*. If *jacobian* is **false**, a numerical approximation is used. **minpack\_solve** returns a list. The first item is the estimated solution; the second is the sum of squares, and the third indicates the success of the algorithm. The possible values are

- 0           improper input parameters.
- 1           algorithm estimates that the relative error in the solution is at most **tolerance**.
- 2           number of calls to fcn with iflag = 1 has reached 100\*(n+1).
- 3           tol is too small. no further reduction in the sum of squares is possible.
- 4           Iteration is not making good progress.

## 66 makeOrders

### 66.1 Functions and Variables for makeOrders

**makeOrders** (*indvarlist,orderlist*)

Function

Returns a list of all powers for a polynomial up to and including the arguments.

```
(%i1) load("makeOrders")$
```

```
(%i2) makeOrders([a,b],[2,3]);
```

```
(%o2) [[0, 0], [0, 1], [0, 2], [0, 3], [1, 0], [1, 1],
 [1, 2], [1, 3], [2, 0], [2, 1], [2, 2], [2, 3]]
```

```
(%i3) expand((1+a+a^2)*(1+b+b^2+b^3));
```

```
(%o3) a2 b3 + a3 b3 + b3 + a2 b2 + a2 b2 + b2 + a2 b2 + a2 b2
 + b2 + a2 + a + 1
```

where [0, 1] is associated with the term  $b$  and [2, 3] with  $a^2b^3$ .

To use this function write first `load("makeOrders")`.





## 67 mnewton

### 67.1 Introduction to mnewton

**mnewton** is an implementation of Newton's method for solving nonlinear equations in one or more variables.

### 67.2 Functions and Variables for mnewton

#### **newtonepsilon**

Option variable

Default value:  $10.0^{(-\text{fpprec}/2)}$

Precision to determine when the **mnewton** function has converged towards the solution. If **newtonepsilon** is a bigfloat, then **mnewton** computations are done with bigfloats. See also **mnewton**.

#### **newtonmaxiter**

Option variable

Default value: 50

Maximum number of iterations to stop the **mnewton** function if it does not converge or if it converges too slowly.

See also **mnewton**.

#### **mnewton** (*FuncList*, *VarList*, *GuessList*)

Function

Multiple nonlinear functions solution using the Newton method. *FuncList* is the list of functions to solve, *VarList* is the list of variable names, and *GuessList* is the list of initial approximations.

The solution is returned in the same format that **solve()** returns. If the solution is not found, [] is returned.

This function is controlled by global variables **newtonepsilon** and **newtonmaxiter**.

```
(%i1) load("mnewton")$

(%i2) mnewton([x1+3*log(x1)-x2^2, 2*x1^2-x1*x2-5*x1+1],
 [x1, x2], [5, 5]);
(%o2) [[x1 = 3.756834008012769, x2 = 2.779849592817897]]
(%i3) mnewton([2*a^a-5], [a], [1]);
(%o3) [[a = 1.70927556786144]]
(%i4) mnewton([2*3^u-v/u-5, u+2^v-4], [u, v], [2, 2]);
(%o4) [[u = 1.066618389595407, v = 1.552564766841786]]
```

The variable **newtonepsilon** controls the precision of the approximations. It also controls if computations are performed with floats or bigfloats.

```
(%i1) load(mnewton)$

(%i2) (fpprec : 25, newtonepsilon : bfloat(10^(-fpprec+5)))$

(%i3) mnewton([2*3^u-v/u-5, u+2^v-4], [u, v], [2, 2]);
(%o3) [[u = 1.066618389595406772591173b0,
 v = 1.552564766841786450100418b0]]
```

To use this function write first **load("mnewton")**. See also **newtonepsilon** and **newtonmaxiter**.



## 68 numericalio

### 68.1 Introduction to numericalio

**numericalio** is a collection of functions to read and write files and streams. Functions for plain-text input and output can read and write numbers (integer, float, or bigfloat), symbols, and strings. Functions for binary input and output can read and write only floating-point numbers.

If there already exists a list, matrix, or array object to store input data, **numericalio** input functions can write data into that object. Otherwise, **numericalio** can guess, to some degree, the structure of an object to store the data, and return that object.

#### 68.1.1 Plain-text input and output

In plain-text input and output, it is assumed that each item to read or write is an atom: an integer, float, bigfloat, string, or symbol, and not a rational or complex number or any other kind of nonatomic expression. The **numericalio** functions may attempt to do something sensible faced with nonatomic expressions, but the results are not specified here and subject to change.

Atoms in both input and output files have the same format as in Maxima batch files or the interactive console. In particular, strings are enclosed in double quotes, backslash `\` prevents any special interpretation of the next character, and the question mark `?` is recognized at the beginning of a symbol to mean a Lisp symbol (as opposed to a Maxima symbol). No continuation character (to join broken lines) is recognized.

#### 68.1.2 Separator flag values for input

The functions for plain-text input and output take an optional argument, *separator\_flag*, that tells what character separates data.

For plain-text input, these values of *separator\_flag* are recognized: **comma** for comma separated values, **pipe** for values separated by the vertical bar character `|`, **semicolon** for values separated by semicolon `;`, and **space** for values separated by space or tab characters. If the file name ends in `.csv` and *separator\_flag* is not specified, **comma** is assumed. If the file name ends in something other than `.csv` and *separator\_flag* is not specified, **space** is assumed.

In plain-text input, multiple successive space and tab characters count as a single separator. However, multiple comma, pipe, or semicolon characters are significant. Successive comma, pipe, or semicolon characters (with or without intervening spaces or tabs) are considered to have **false** between the separators. For example, `1234,,Foo` is treated the same as `1234,false,Foo`.

#### 68.1.3 Separator flag values for output

For plain-text output, **tab**, for values separated by the tab character, is recognized as a value of *separator\_flag*, as well as **comma**, **pipe**, **semicolon**, and **space**.

In plain-text output, **false** atoms are written as such; a list `[1234, false, Foo]` is written `1234,false,Foo`, and there is no attempt to collapse the output to `1234,,Foo`.

#### 68.1.4 Binary floating-point input and output

**numericalio** functions can read and write 8-byte IEEE 754 floating-point numbers. These numbers can be stored either least significant byte first or most significant byte first, according to the global flag set by **assume\_external\_byte\_order**. If not specified, **numericalio** assumes the external byte order is most-significant byte first.

Other kinds of numbers are coerced to 8-byte floats; **numericalio** cannot read or write binary non-numeric data.

Some Lisp implementations do not recognize IEEE 754 special values (positive and negative infinity, not-a-number values, denormalized values). The effect of reading such values with **numericalio** is undefined.

**numericalio** includes functions to open a stream for reading or writing a stream of bytes.

## 68.2 Functions and Variables for plain-text input and output

|                                                                    |          |
|--------------------------------------------------------------------|----------|
| <b>read_matrix</b> ( <i>S</i> )                                    | Function |
| <b>read_matrix</b> ( <i>S</i> , <i>M</i> )                         | Function |
| <b>read_matrix</b> ( <i>S</i> , <i>separator_flag</i> )            | Function |
| <b>read_matrix</b> ( <i>S</i> , <i>M</i> , <i>separator_flag</i> ) | Function |

**read\_matrix**(*S*) reads the source *S* and returns its entire content as a matrix. The size of the matrix is inferred from the input data; each line of the file becomes one row of the matrix. If some lines have different lengths, **read\_matrix** complains.

**read\_matrix**(*S*, *M*) read the source *S* into the matrix *M*, until *M* is full or the source is exhausted. Input data are read into the matrix in row-major order; the input need not have the same number of rows and columns as *M*.

The source *S* may be a file name or a stream.

The recognized values of *separator\_flag* are **comma**, **pipe**, **semicolon**, and **space**. If *separator\_flag* is not specified, the file is assumed space-delimited.

|                                                                   |          |
|-------------------------------------------------------------------|----------|
| <b>read_array</b> ( <i>S</i> , <i>A</i> )                         | Function |
| <b>read_array</b> ( <i>S</i> , <i>A</i> , <i>separator_flag</i> ) | Function |

Reads the source *S* into the array *A*, until *A* is full or the source is exhausted. Input data are read into the array in row-major order; the input need not conform to the dimensions of *A*.

The source *S* may be a file name or a stream.

The recognized values of *separator\_flag* are **comma**, **pipe**, **semicolon**, and **space**. If *separator\_flag* is not specified, the file is assumed space-delimited.

|                                                                          |          |
|--------------------------------------------------------------------------|----------|
| <b>read_hashed_array</b> ( <i>S</i> , <i>A</i> )                         | Function |
| <b>read_hashed_array</b> ( <i>S</i> , <i>A</i> , <i>separator_flag</i> ) | Function |

Reads the source *S* and returns its entire content as a hashed array. The source *S* may be a file name or a stream.

**read\_hashed\_array** treats the first item on each line as a hash key, and associates the remainder of the line (as a list) with the key. For example, the line **567 12 17 32 55** is equivalent to **A[567]: [12, 17, 32, 55]**\$. Lines need not have the same numbers of elements.

The recognized values of *separator\_flag* are **comma**, **pipe**, **semicolon**, and **space**. If *separator\_flag* is not specified, the file is assumed space-delimited.

|                                                              |          |
|--------------------------------------------------------------|----------|
| <b>read_nested_list</b> ( <i>S</i> )                         | Function |
| <b>read_nested_list</b> ( <i>S</i> , <i>separator_flag</i> ) | Function |

Reads the source *S* and returns its entire content as a nested list. The source *S* may be a file name or a stream.

**read\_nested\_list** returns a list which has a sublist for each line of input. Lines need not have the same numbers of elements. Empty lines are *not* ignored: an empty line yields an empty sublist.

The recognized values of *separator\_flag* are **comma**, **pipe**, **semicolon**, and **space**. If *separator\_flag* is not specified, the file is assumed space-delimited.

|                                                                  |          |
|------------------------------------------------------------------|----------|
| <b>read_list</b> ( <i>S</i> )                                    | Function |
| <b>read_list</b> ( <i>S</i> , <i>L</i> )                         | Function |
| <b>read_list</b> ( <i>S</i> , <i>separator_flag</i> )            | Function |
| <b>read_list</b> ( <i>S</i> , <i>L</i> , <i>separator_flag</i> ) | Function |

**read\_list**(*S*) reads the source *S* and returns its entire content as a flat list.

**read\_list**(*S*, *L*) reads the source *S* into the list *L*, until *L* is full or the source is exhausted.

The source *S* may be a file name or a stream.

The recognized values of *separator\_flag* are **comma**, **pipe**, **semicolon**, and **space**. If *separator\_flag* is not specified, the file is assumed space-delimited.

**write\_data** (*X*, *D*) Function  
**write\_data** (*X*, *D*, *separator\_flag*) Function  
 Writes the object *X* to the destination *D*.  
*write\_data* writes a matrix in row-major order, with one line per row.  
*write\_data* writes an array created by **array** or **make\_array** in row-major order, with a new line at the end of every slab. Higher-dimensional slabs are separated by additional new lines.  
*write\_data* writes a hashed array with each key followed by its associated list on one line.  
*write\_data* writes a nested list with each sublist on one line.  
*write\_data* writes a flat list all on one line.  
 The destination *D* may be a file name or a stream. When the destination is a file name, the global variable **file\_output\_append** governs whether the output file is appended or truncated. When the destination is a stream, no special action is taken by **write\_data** after all the data are written; in particular, the stream remains open.  
 The recognized values of *separator\_flag* are **comma**, **pipe**, **semicolon**, **space**, and **tab**. If *separator\_flag* is not specified, the file is assumed space-delimited.

### 68.3 Functions and Variables for binary input and output

**assume\_external\_byte\_order** (*byte\_order\_flag*) Function  
 Tells **numericalio** the byte order for reading and writing binary data. Two values of *byte\_order\_flag* are recognized: **lsb** which indicates least-significant byte first, also called little-endian byte order; and **msb** which indicates most-significant byte first, also called big-endian byte order.  
 If not specified, **numericalio** assumes the external byte order is most-significant byte first.

**openr\_binary** (*file\_name*) Function  
 Returns an input stream of 8-bit unsigned bytes to read the file named by *file\_name*.

**openw\_binary** (*file\_name*) Function  
 Returns an output stream of 8-bit unsigned bytes to write the file named by *file\_name*.

**opena\_binary** (*file\_name*) Function  
 Returns an output stream of 8-bit unsigned bytes to append the file named by *file\_name*.

**read\_binary\_matrix** (*S*, *M*) Function  
 Reads binary 8-byte floating point numbers from the source *S* into the matrix *M* until *M* is full, or the source is exhausted. Elements of *M* are read in row-major order.  
 The source *S* may be a file name or a stream.  
 The byte order in elements of the source is specified by **assume\_external\_byte\_order**.

**read\_binary\_array** (*S*, *A*) Function  
 Reads binary 8-byte floating point numbers from the source *S* into the array *A* until *A* is full, or the source is exhausted. *A* must be an array created by **array** or **make\_array**. Elements of *A* are read in row-major order.  
 The source *S* may be a file name or a stream.  
 The byte order in elements of the source is specified by **assume\_external\_byte\_order**.

**read\_binary\_list** (*S*) Function  
**read\_binary\_list** (*S*, *L*) Function  
*read\_binary\_list*(*S*) reads the entire content of the source *S* as a sequence of binary 8-byte floating point numbers, and returns it as a list. The source *S* may be a file name or a stream.  
*read\_binary\_list*(*S*, *L*) reads 8-byte binary floating point numbers from the source *S* until the list *L* is full, or the source is exhausted.  
 The byte order in elements of the source is specified by **assume\_external\_byte\_order**.

**write\_binary\_data** (*X*, *D*)

Function

Writes the object *X*, comprising binary 8-byte IEEE 754 floating-point numbers, to the destination *D*. Other kinds of numbers are coerced to 8-byte floats. **write\_binary\_data** cannot write non-numeric data.

The object *X* may be a list, a nested list, a matrix, or an array created by **array** or **make\_array**; *X* cannot be an undeclared array or any other type of object. **write\_binary\_data** writes nested lists, matrices, and arrays in row-major order.

The destination *D* may be a file name or a stream. When the destination is a file name, the global variable **file\_output\_append** governs whether the output file is appended or truncated. When the destination is a stream, no special action is taken by **write\_binary\_data** after all the data are written; in particular, the stream remains open.

The byte order in elements of the destination is specified by **assume\_external\_byte\_order**.

## 69 opsubst

### 69.1 Functions and Variables for opsubst

**opsubst** ( $f,g,e$ ) Function  
**opsubst** ( $g=f,e$ ) Function  
**opsubst** ( $[g1=f1,g2=f2,\dots, gn=fn],e$ ) Function

The function **opsubst** is similar to the function **subst**, except that **opsubst** only makes substitutions for the operators in an expression. In general, When  $f$  is an operator in the expression  $e$ , substitute  $g$  for  $f$  in the expression  $e$ .

To determine the operator, **opsubst** sets **inflag** to true. This means **opsubst** substitutes for the internal, not the displayed, operator in the expression.

Examples:

```
(%i1) load (opsubst)$

(%i2) opsubst(f,g,g(g(x)));
(%o2) f(f(x))
(%i3) opsubst(f,g,g(g));
(%o3) f(g)
(%i4) opsubst(f,g[x],g[x](z));
(%o4) f(z)
(%i5) opsubst(g[x],f, f(z));
(%o5) g (z)
 x
(%i6) opsubst(tan, sin, sin(sin));
(%o6) tan(sin)
(%i7) opsubst([f=g,g=h],f(x));
(%o7) h(x)
```

Internally, Maxima does not use the unary negation, division, or the subtraction operators; thus:

```
(%i8) opsubst("+","-",a-b);
(%o8) a - b
(%i9) opsubst("f","-",-a);
(%o9) - a
(%i10) opsubst("^^","/",a/b);
(%o10) a
 -
 b
```

The internal representation of  $-a*b$  is  $*(-1,a,b)$ ; thus

```
(%i11) opsubst("[","*", -a*b);
(%o11) [- 1, a, b]
```

When either operator isn't a Maxima symbol, generally some other function will signal an error:

```
(%i12) opsubst(a+b,f, f(x));

Improper name or value in functional position:
b + a
-- an error. Quitting. To debug this try debugmode(true);
```

However, subscripted operators are allowed:

```
(%i13) opsubst(g[5],f, f(x));
(%o13) g (x)
 5
```

To use this function write first `load("opsubst")`.





## 70 orthopoly

### 70.1 Introduction to orthogonal polynomials

**orthopoly** is a package for symbolic and numerical evaluation of several kinds of orthogonal polynomials, including Chebyshev, Laguerre, Hermite, Jacobi, Legendre, and ultraspherical (Gegenbauer) polynomials. Additionally, **orthopoly** includes support for the spherical Bessel, spherical Hankel, and spherical harmonic functions.

For the most part, **orthopoly** follows the conventions of Abramowitz and Stegun *Handbook of Mathematical Functions*, Chapter 22 (10th printing, December 1972); additionally, we use Gradshteyn and Ryzhik, *Table of Integrals, Series, and Products* (1980 corrected and enlarged edition), and Eugen Merzbacher *Quantum Mechanics* (2nd edition, 1970).

Barton Willis of the University of Nebraska at Kearney (UNK) wrote the **orthopoly** package and its documentation. The package is released under the GNU General Public License (GPL).

#### 70.1.1 Getting Started with orthopoly

`load (orthopoly)` loads the **orthopoly** package.

To find the third-order Legendre polynomial,

```
(%i1) legendre_p (3, x);
```

$$\frac{5}{2} (1-x)^3 + \frac{15}{2} (1-x)^2 - 6 (1-x) + 1$$

```
(%o1)
```

To express this as a sum of powers of  $x$ , apply `ratsimp` or `rat` to the result.

```
(%i2) [ratsimp (%), rat (%)];
```

$$\left[ \frac{5x^3 - 3x}{2}, \frac{5x^3 - 3x}{2} \right]$$

```
(%o2)/R/
```

Alternatively, make the second argument to `legendre_p` (its “main” variable) a canonical rational expression (CRE).

```
(%i1) legendre_p (3, rat (x));
```

$$\frac{5x^3 - 3x}{2}$$

```
(%o1)/R/
```

For floating point evaluation, **orthopoly** uses a running error analysis to estimate an upper bound for the error. For example,

```
(%i1) jacobi_p (150, 2, 3, 0.2);
```

```
(%o1) interval(- 0.062017037936715, 1.533267919277521E-11)
```

Intervals have the form `interval (c, r)`, where  $c$  is the center and  $r$  is the radius of the interval. Since Maxima does not support arithmetic on intervals, in some situations, such as graphics, you want to suppress the error and output only the center of the interval. To do this, set the option variable `orthopoly_returns_intervals` to `false`.

```
(%i1) orthopoly_returns_intervals : false;
```

```
(%o1) false
```

```
(%i2) jacobi_p (150, 2, 3, 0.2);
```

```
(%o2) - 0.062017037936715
```

Refer to the section see [\[Floating point Evaluation\]](#), page 758 for more information.

Most functions in **orthopoly** have a `gradef` property; thus

```
(%i1) diff (hermite (n, x), x);
(%o1)

$$2 n H_{n-1}(x)$$

(%i2) diff (gen_laguerre (n, a, x), x);
(%o2)

$$\frac{n L_n^{(a)}(x) - (n+a) L_{n-1}^{(a)}(x) \text{unit_step}(n)}{x}$$

```

The unit step function in the second example prevents an error that would otherwise arise by evaluating with  $n$  equal to 0.

```
(%i3) ev (% , n = 0);
(%o3) 0
```

The `gradeof` property only applies to the “main” variable; derivatives with respect other arguments usually result in an error message; for example

```
(%i1) diff (hermite (n, x), x);
(%o1)

$$2 n H_{n-1}(x)$$

(%i2) diff (hermite (n, x), n);
```

Maxima doesn't know the derivative of `hermite` with respect the first argument

-- an error. Quitting. To debug this try `debugmode(true)`;

Generally, functions in `orthopoly` map over lists and matrices. For the mapping to fully evaluate, the option variables `doallmxops` and `listarith` must both be `true` (the defaults). To illustrate the mapping over matrices, consider

```
(%i1) hermite (2, x);
(%o1)

$$-2(1-2x^2)$$

(%i2) m : matrix ([0, x], [y, 0]);
(%o2)

$$\begin{bmatrix} 0 & x \\ y & 0 \end{bmatrix}$$

(%i3) hermite (2, m);
(%o3)

$$\begin{bmatrix} -2 & -2(1-2x^2) \\ -2(1-2y^2) & -2 \end{bmatrix}$$

```

In the second example, the  $i, j$  element of the value is `hermite (2, m[i,j])`; this is not the same as computing  $-2 + 4 m . m$ , as seen in the next example.

```
(%i4) -2 * matrix ([1, 0], [0, 1]) + 4 * m . m;
(%o4)

$$\begin{bmatrix} 4xy-2 & 0 \\ 0 & 4xy-2 \end{bmatrix}$$

```

If you evaluate a function at a point outside its domain, generally `orthopoly` returns the function unevaluated. For example,

```
(%i1) legendre_p (2/3, x);
(%o1)

$$P_{2/3}(x)$$

```

`orthopoly` supports translation into TeX; it also does two-dimensional output on a terminal.

```
(%i1) spherical_harmonic (1, m, theta, phi);
(%o1)

$$Y_m(\theta, \phi)$$

```

```

 1
(%i2) tex (%);
$$Y_{l}^{m}\left(\vartheta,\varphi\right)$$
(%o2)
 false
(%i3) jacobi_p (n, a, a - b, x/2);
 (a, a - b) x
(%o3) P (-)
 n 2

(%i4) tex (%);
$$P_n^{\left(a,a-b\right)}\left(\frac{x}{2}\right)$$
(%o4)
 false

```

### 70.1.2 Limitations

When an expression involves several orthogonal polynomials with symbolic orders, it's possible that the expression actually vanishes, yet Maxima is unable to simplify it to zero. If you divide by such a quantity, you'll be in trouble. For example, the following expression vanishes for integers  $n$  greater than 1, yet Maxima is unable to simplify it to zero.

```

(%i1) (2*n - 1) * legendre_p (n - 1, x) * x - n * legendre_p (n, x)
 + (1 - n) * legendre_p (n - 2, x);
(%o1) (2 n - 1) P (x) x - n P (x) + (1 - n) P (x)
 n - 1 n n - 2

```

For a specific  $n$ , we can reduce the expression to zero.

```

(%i2) ev (% ,n = 10, ratsimp);
(%o2)
 0

```

Generally, the polynomial form of an orthogonal polynomial is ill-suited for floating point evaluation. Here's an example.

```

(%i1) p : jacobi_p (100, 2, 3, x)$

(%i2) subst (0.2, x, p);
(%o2)
 3.4442767023833592E+35
(%i3) jacobi_p (100, 2, 3, 0.2);
(%o3)
 interval(0.18413609135169, 6.8990300925815987E-12)
(%i4) float(jacobi_p (100, 2, 3, 2/10));
(%o4)
 0.18413609135169

```

The true value is about 0.184; this calculation suffers from extreme subtractive cancellation error. Expanding the polynomial and then evaluating, gives a better result.

```

(%i5) p : expand(p)$
(%i6) subst (0.2, x, p);
(%o6) 0.18413609766122982

```

This isn't a general rule; expanding the polynomial does not always result in an expression that is better suited for numerical evaluation. By far, the best way to do numerical evaluation is to make one or more of the function arguments floating point numbers. By doing that, specialized floating point algorithms are used for evaluation.

Maxima's `float` function is somewhat indiscriminate; if you apply `float` to an expression involving an orthogonal polynomial with a symbolic degree or order parameter, these parameters may be converted into floats; after that, the expression will not evaluate fully. Consider

```

(%i1) assoc_legendre_p (n, 1, x);
 1
(%o1) P (x)
 n

(%i2) float (%);
 1.0
(%o2) P (x)
 n

```

```
(%i3) ev (% , n=2, x=0.9);
 1.0
(%o3) P (0.9)
 2
```

The expression in (%o3) will not evaluate to a float; `orthopoly` doesn't recognize floating point values where it requires an integer. Similarly, numerical evaluation of the `pochhammer` function for orders that exceed `pochhammer_max_index` can be troublesome; consider

```
(%i1) x : pochhammer (1, 10), pochhammer_max_index : 5;
(%o1) (1)
 10
```

Applying `float` doesn't evaluate `x` to a float

```
(%i2) float (x);
(%o2) (1.0)
 10.0
```

To evaluate `x` to a float, you'll need to bind `pochhammer_max_index` to 11 or greater and apply `float` to `x`.

```
(%i3) float (x), pochhammer_max_index : 11;
(%o3) 3628800.0
```

The default value of `pochhammer_max_index` is 100; change its value after loading `orthopoly`.

Finally, be aware that reference books vary on the definitions of the orthogonal polynomials; we've generally used the conventions of Abramowitz and Stegun.

Before you suspect a bug in `orthopoly`, check some special cases to determine if your definitions match those used by `orthopoly`. Definitions often differ by a normalization; occasionally, authors use "shifted" versions of the functions that makes the family orthogonal on an interval other than  $(-1, 1)$ . To define, for example, a Legendre polynomial that is orthogonal on  $(0, 1)$ , define

```
(%i1) shifted_legendre_p (n, x) := legendre_p (n, 2*x - 1)$

(%i2) shifted_legendre_p (2, rat (x));
 2
(%o2)/R/ 6 x - 6 x + 1
(%i3) legendre_p (2, rat (x));
 2
 3 x - 1
(%o3)/R/ -----
 2
```

### 70.1.3 Floating point Evaluation

Most functions in `orthopoly` use a running error analysis to estimate the error in floating point evaluation; the exceptions are the spherical Bessel functions and the associated Legendre polynomials of the second kind. For numerical evaluation, the spherical Bessel functions call SLATEC functions. No specialized method is used for numerical evaluation of the associated Legendre polynomials of the second kind.

The running error analysis ignores errors that are second or higher order in the machine epsilon (also known as unit roundoff). It also ignores a few other errors. It's possible (although unlikely) that the actual error exceeds the estimate.

Intervals have the form `interval (c, r)`, where `c` is the center of the interval and `r` is its radius. The center of an interval can be a complex number, and the radius is always a positive real number.

Here is an example.

```
(%i1) fpprec : 50$

(%i2) y0 : jacobi_p (100, 2, 3, 0.2);
(%o2) interval(0.1841360913516871, 6.8990300925815987E-12)
```

```
(%i3) y1 : bfloat (jacobi_p (100, 2, 3, 1/5));
(%o3) 1.8413609135168563091370224958913493690868904463668b-1
```

Let's test that the actual error is smaller than the error estimate

```
(%i4) is (abs (part (y0, 1) - y1) < part (y0, 2));
(%o4) true
```

Indeed, for this example the error estimate is an upper bound for the true error.

Maxima does not support arithmetic on intervals.

```
(%i1) legendre_p (7, 0.1) + legendre_p (8, 0.1);
(%o1) interval(0.18032072148437508, 3.1477135311021797E-15)
 + interval(- 0.19949294375000004, 3.3769353084291579E-15)
```

A user could define arithmetic operators that do interval math. To define interval addition, we can define

```
(%i1) infix ("@+")$
(%i2) "@+(x,y) := interval (part (x, 1) + part (y, 1), part (x, 2)
 + part (y, 2))$
(%i3) legendre_p (7, 0.1) @+ legendre_p (8, 0.1);
(%o3) interval(- 0.019172222265624955, 6.5246488395313372E-15)
```

The special floating point routines get called when the arguments are complex. For example,

```
(%i1) legendre_p (10, 2 + 3.0*i);
(%o1) interval(- 3.876378825E+7 %i - 6.0787748E+7,
 1.2089173052721777E-6)
```

Let's compare this to the true value.

```
(%i1) float (expand (legendre_p (10, 2 + 3*i)));
(%o1) - 3.876378825E+7 %i - 6.0787748E+7
```

Additionally, when the arguments are big floats, the special floating point routines get called; however, the big floats are converted into double floats and the final result is a double.

```
(%i1) ultraspherical (150, 0.5b0, 0.9b0);
(%o1) interval(- 0.043009481257265, 3.3750051301228864E-14)
```

### 70.1.4 Graphics and orthopoly


To plot expressions that involve the orthogonal polynomials, you must do two things:

1. Set the option variable `orthopoly_returns_intervals` to `false`,
2. Quote any calls to `orthopoly` functions.

If function calls aren't quoted, Maxima evaluates them to polynomials before plotting; consequently, the specialized floating point code doesn't get called. Here is an example of how to plot an expression that involves a Legendre polynomial.

```
(%i1) plot2d ('(legendre_p (5, x)), [x, 0, 1]),
 orthopoly_returns_intervals : false;
```

```
(%o1)
```



The *entire* expression `legendre_p (5, x)` is quoted; this is different than just quoting the function name using `'legendre_p (5, x)`.

### 70.1.5 Miscellaneous Functions

The `orthopoly` package defines the Pochhammer symbol and a unit step function. `orthopoly` uses the Kronecker delta function and the unit step function in `grdef` statements.

To convert Pochhammer symbols into quotients of gamma functions, use `makegamma`.

```
(%i1) makegamma (pochhammer (x, n));
 gamma(x + n)
(%o1) -----
 gamma(x)
(%i2) makegamma (pochhammer (1/2, 1/2));
 1
(%o2) -----
 sqrt(%pi)
```

Derivatives of the Pochhammer symbol are given in terms of the `psi` function.

```
(%i1) diff (pochhammer (x, n), x);
(%o1) (x) (psi (x + n) - psi (x))
 n 0 0
(%i2) diff (pochhammer (x, n), n);
(%o2) (x) psi (x + n)
 n 0
```

You need to be careful with the expression in (%o1); the difference of the `psi` functions has polynomials when  $x = -1, -2, \dots, -n$ . These polynomials cancel with factors in `pochhammer` ( $x, n$ ) making the derivative a degree  $n - 1$  polynomial when  $n$  is a positive integer.

The Pochhammer symbol is defined for negative orders through its representation as a quotient of gamma functions. Consider

```
(%i1) q : makegamma (pochhammer (x, n));
 gamma(x + n)
(%o1) -----
 gamma(x)
(%i2) sublis ([x=11/3, n= -6], q);
 729
(%o2) -----
 2240
```

Alternatively, we can get this result directly.

```
(%i1) pochhammer (11/3, -6);
 729
```

```
(%o1) - ----
 2240
```

The unit step function is left-continuous; thus

```
(%i1) [unit_step (-1/10), unit_step (0), unit_step (1/10)];
(%o1) [0, 0, 1]
```

If you need a unit step function that is neither left or right continuous at zero, define your own using `signum`; for example,

```
(%i1) xunit_step (x) := (1 + signum (x))/2$

(%i2) [xunit_step (-1/10), xunit_step (0), xunit_step (1/10)];
1
(%o2) [0, -, 1]
2
```

Do not redefine `unit_step` itself; some code in `orthopoly` requires that the unit step function be left-continuous.

### 70.1.6 Algorithms

Generally, `orthopoly` does symbolic evaluation by using a hypergeometric representation of the orthogonal polynomials. The hypergeometric functions are evaluated using the (undocumented) functions `hypergeo11` and `hypergeo21`. The exceptions are the half-integer Bessel functions and the associated Legendre function of the second kind. The half-integer Bessel functions are evaluated using an explicit representation, and the associated Legendre function of the second kind is evaluated using recursion.

For floating point evaluation, we again convert most functions into a hypergeometric form; we evaluate the hypergeometric functions using forward recursion. Again, the exceptions are the half-integer Bessel functions and the associated Legendre function of the second kind. Numerically, the half-integer Bessel functions are evaluated using the SLATEC code.

## 70.2 Functions and Variables for orthogonal polynomials

|                                                                                                                                                                                                            |          |
|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|
| <b>assoc_legendre_p</b> ( $n, m, x$ )                                                                                                                                                                      | Function |
| The associated Legendre function of the first kind of degree $n$ and order $m$ .<br>Reference: Abramowitz and Stegun, equations 22.5.37, page 779, 8.6.6 (second equation), page 334, and 8.2.5, page 333. |          |
| <b>assoc_legendre_q</b> ( $n, m, x$ )                                                                                                                                                                      | Function |
| The associated Legendre function of the second kind of degree $n$ and order $m$ .<br>Reference: Abramowitz and Stegun, equation 8.5.3 and 8.1.8.                                                           |          |
| <b>chebyshev_t</b> ( $n, x$ )                                                                                                                                                                              | Function |
| The Chebyshev function of the first kind.<br>Reference: Abramowitz and Stegun, equation 22.5.47, page 779.                                                                                                 |          |
| <b>chebyshev_u</b> ( $n, x$ )                                                                                                                                                                              | Function |
| The Chebyshev function of the second kind.<br>Reference: Abramowitz and Stegun, equation 22.5.48, page 779.                                                                                                |          |
| <b>gen_laguerre</b> ( $n, a, x$ )                                                                                                                                                                          | Function |
| The generalized Laguerre polynomial of degree $n$ .<br>Reference: Abramowitz and Stegun, equation 22.5.54, page 780.                                                                                       |          |
| <b>hermite</b> ( $n, x$ )                                                                                                                                                                                  | Function |
| The Hermite polynomial.<br>Reference: Abramowitz and Stegun, equation 22.5.55, page 780.                                                                                                                   |          |

**interval** (*e*) Function  
 Return **true** if the input is an interval and return false if it isn't.

**jacobi\_p** (*n, a, b, x*) Function  
 The Jacobi polynomial.  
 The Jacobi polynomials are actually defined for all *a* and *b*; however, the Jacobi polynomial weight  $(1 - x)^a (1 + x)^b$  isn't integrable for  $a \leq -1$  or  $b \leq -1$ .  
 Reference: Abramowitz and Stegun, equation 22.5.42, page 779.

**laguerre** (*n, x*) Function  
 The Laguerre polynomial.  
 Reference: Abramowitz and Stegun, equations 22.5.16 and 22.5.54, page 780.

**legendre\_p** (*n, x*) Function  
 The Legendre polynomial of the first kind.  
 Reference: Abramowitz and Stegun, equations 22.5.50 and 22.5.51, page 779.

**legendre\_q** (*n, x*) Function  
 The Legendre polynomial of the first kind.  
 Reference: Abramowitz and Stegun, equations 8.5.3 and 8.1.8.

**orthopoly\_recur** (*f, args*) Function  
 Returns a recursion relation for the orthogonal function family *f* with arguments *args*.  
 The recursion is with respect to the polynomial degree.

```
(%i1) orthopoly_recur (legendre_p, [n, x]);
 (2 n + 1) P (x) x - n P (x)
 n n - 1
(%o1) P (x) = -----
 n + 1 n + 1
```

The second argument to **orthopoly\_recur** must be a list with the correct number of arguments for the function *f*; if it isn't, Maxima signals an error.

```
(%i1) orthopoly_recur (jacobi_p, [n, x]);
```

```
Function jacobi_p needs 4 arguments, instead it received 2
-- an error. Quitting. To debug this try debugmode(true);
```

Additionally, when *f* isn't the name of one of the families of orthogonal polynomials, an error is signalled.

```
(%i1) orthopoly_recur (foo, [n, x]);
```

```
A recursion relation for foo isn't known to Maxima
-- an error. Quitting. To debug this try debugmode(true);
```

**orthopoly\_returns\_intervals** Variable  
 Default value: **true**

When **orthopoly\_returns\_intervals** is **true**, floating point results are returned in the form **interval** (*c, r*), where *c* is the center of an interval and *r* is its radius. The center can be a complex number; in that case, the interval is a disk in the complex plane.

**orthopoly\_weight** (*f, args*) Function  
 Returns a three element list; the first element is the formula of the weight for the orthogonal polynomial family *f* with arguments given by the list *args*; the second and third elements give the lower and upper endpoints of the interval of orthogonality. For example,



```
(%i1) w : orthopoly_weight (hermite, [n, x]);
 2
 - x
(%o1) [%e , - inf, inf]
(%i2) integrate(w[1]*hermite(3, x)*hermite(2, x), x, w[2], w[3]);
(%o2) 0
```

The main variable of  $f$  must be a symbol; if it isn't, Maxima signals an error.

### pochhammer ( $n, x$ )

Function

The Pochhammer symbol. For nonnegative integers  $n$  with  $n \leq \text{pochhammer\_max\_index}$ , the expression `pochhammer ( $x, n$ )` evaluates to the product  $x (x + 1) (x + 2) \dots (x + n - 1)$  when  $n > 0$  and to 1 when  $n = 0$ . For negative  $n$ , `pochhammer ( $x, n$ )` is defined as  $(-1)^n / \text{pochhammer} (1 - x, -n)$ . Thus

```
(%i1) pochhammer (x, 3);
(%o1) x (x + 1) (x + 2)
(%i2) pochhammer (x, -3);
(%o2) 1

 (1 - x) (2 - x) (3 - x)
```

To convert a Pochhammer symbol into a quotient of gamma functions, (see Abramowitz and Stegun, equation 6.1.22) use `makegamma`; for example

```
(%i1) makegamma (pochhammer (x, n));
 gamma(x + n)
(%o1) -----
 gamma(x)
```

When  $n$  exceeds `pochhammer_max_index` or when  $n$  is symbolic, `pochhammer` returns a noun form.

```
(%i1) pochhammer (x, n);
(%o1) (x)
 n
```

### pochhammer\_max\_index

Variable

Default value: 100

`pochhammer ( $n, x$ )` expands to a product if and only if  $n \leq \text{pochhammer\_max\_index}$ .

Examples:

```
(%i1) pochhammer (x, 3), pochhammer_max_index : 3;
(%o1) x (x + 1) (x + 2)
(%i2) pochhammer (x, 4), pochhammer_max_index : 3;
(%o2) (x)
 4
```

Reference: Abramowitz and Stegun, equation 6.1.16, page 256.

### spherical\_bessel\_j ( $n, x$ )

Function

The spherical Bessel function of the first kind.

Reference: Abramowitz and Stegun, equations 10.1.8, page 437 and 10.1.15, page 439.

### spherical\_bessel\_y ( $n, x$ )

Function

The spherical Bessel function of the second kind.

Reference: Abramowitz and Stegun, equations 10.1.9, page 437 and 10.1.15, page 439.

### spherical\_hankel1 ( $n, x$ )

Function

The spherical Hankel function of the first kind.

Reference: Abramowitz and Stegun, equation 10.1.36, page 439.

- spherical\_hankel2** ( $n, x$ ) Function  
The spherical Hankel function of the second kind.  
Reference: Abramowitz and Stegun, equation 10.1.17, page 439.
- spherical\_harmonic** ( $n, m, x, y$ ) Function  
The spherical harmonic function.  
Reference: Merzbacher 9.64.
- unit\_step** ( $x$ ) Function  
The left-continuous unit step function; thus **unit\_step** ( $x$ ) vanishes for  $x \leq 0$  and equals 1 for  $x > 0$ .  
If you want a unit step function that takes on the value  $1/2$  at zero, use  $(1 + \text{signum}(x))/2$ .
- ultraspherical** ( $n, a, x$ ) Function  
The ultraspherical polynomial (also known as the Gegenbauer polynomial).  
Reference: Abramowitz and Stegun, equation 22.5.46, page 779.

## 71 plotdf

### 71.1 Introduction to plotdf

The function `plotdf` creates a plot of the direction field (also called slope field) for a first-order Ordinary Differential Equation (ODE) or a system of two autonomous first-order ODE's.

Plotdf requires Xmaxima. It can be used from the console or any other interface to Maxima, but the resulting file will be sent to Xmaxima for plotting. Please make sure you have installed Xmaxima before trying to use plotdf.

To plot the direction field of a single ODE, the ODE must be written in the form:

$$\frac{dy}{dx} = F(x, y)$$

and the function  $F$  should be given as the argument for `plotdf`. If the independent and dependent variables are not  $x$ , and  $y$ , as in the equation above, then those two variables should be named explicitly in a list given as an argument to the `plotdf` command (see the examples).

To plot the direction field of a set of two autonomous ODE's, they must be written in the form

$$\frac{dx}{dt} = G(x, y) \quad \frac{dy}{dt} = F(x, y)$$

and the argument for `plotdf` should be a list with the two functions  $G$  and  $F$ , in that order; namely, the first expression in the list will be taken to be the time derivative of the variable represented on the horizontal axis, and the second expression will be the time derivative of the variable represented on the vertical axis. Those two variables do not have to be  $x$  and  $y$ , but if they are not, then the second argument given to `plotdf` must be another list naming the two variables, first the one on the horizontal axis and then the one on the vertical axis.

If only one ODE is given, `plotdf` will implicitly admit  $x=t$ , and  $G(x,y)=1$ , transforming the non-autonomous equation into a system of two autonomous equations.

### 71.2 Functions and Variables for plotdf

|                                                         |          |
|---------------------------------------------------------|----------|
| <code>plotdf (dydx, ...options...)</code>               | Function |
| <code>plotdf (dvdu, [u,v], ...options...)</code>        | Function |
| <code>plotdf ([dxdt,dydt], ...options...)</code>        | Function |
| <code>plotdf ([dudt,dvdt], [u,v], ...options...)</code> | Function |

Displays a direction field in two dimensions  $x$  and  $y$ .

$dydx$ ,  $dxdt$  and  $dydt$  are expressions that depend on  $x$  and  $y$ .  $dvdu$ ,  $dudt$  and  $dvdt$  are expressions that depend on  $u$  and  $v$ . In addition to those two variables, the expressions can also depend on a set of parameters, with numerical values given with the `parameters` option (the option syntax is given below), or with a range of allowed values specified by a `sliders` option.

Several other options can be given within the command, or selected in the menu. Integral curves can be obtained by clicking on the plot, or with the option `trajectory_at`. The direction of the integration can be controlled with the `direction` option, which can have values of *forward*, *backward* or *both*. The number of integration steps is given by `nsteps` and the time interval between them is set up with the `tstep` option. The Adams Moulton method is used for the integration; it is also possible to switch to an adaptive Runge-Kutta 4th order method.

#### Plot window menu:

The menu in the plot window has the following options: *Zoom*, will change the behavior of the mouse so that it will allow you to zoom in on a region of the plot by clicking with the left button. Each click near a point magnifies the plot, keeping the center at the point where you clicked. Holding the `Shift` key while clicking, zooms out to the previous

magnification. To resume computing trajectories when you click on a point, select *Integrate* from the menu.

The option *Config* in the menu can be used to change the ODE(s) in use and various other settings. After configuration changes are made, the menu option *Replot* should be selected, to activate the new settings. If a pair of coordinates are entered in the field *Trajectory at* in the *Config* dialog menu, and the **enter** key is pressed, a new integral curve will be shown, in addition to the ones already shown. When *Replot* is selected, only the last integral curve entered will be shown.

Holding the right mouse button down while the cursor is moved, can be used to drag the plot sideways or up and down. Additional parameters such as the number of steps, the initial value of  $t$  and the  $x$  and  $y$  centers and radii, may be set in the *Config* menu.

A copy of the plot can be saved as a postscript file, using the menu option *Save*.

### Plot options:

The `plotdf` command may include several commands, each command is a list of two or more items. The first item is the name of the option, and the remainder comprises the value or values assigned to the option.


The options which are recognized by `plotdf` are the following:

- *tstep* defines the length of the increments on the independent variable  $t$ , used to compute an integral curve. If only one expression  $dydx$  is given to `plotdf`, the  $x$  variable will be directly proportional to  $t$ . The default value is 0.1.
- *nsteps* defines the number of steps of length `tstep` that will be used for the independent variable, to compute an integral curve. The default value is 100.
- *direction* defines the direction of the independent variable that will be followed to compute an integral curve. Possible values are **forward**, to make the independent variable increase `nsteps` times, with increments `tstep`, **backward**, to make the independent variable decrease, or **both** that will lead to an integral curve that extends `nsteps` forward, and `nsteps` backward. The keywords **right** and **left** can be used as synonyms for **forward** and **backward**. The default value is **both**.
- *tinitial* defines the initial value of variable  $t$  used to compute integral curves. Since the differential equations are autonomous, that setting will only appear in the plot of the curves as functions of  $t$ . The default value is 0.
- *versus\_t* is used to create a second plot window, with a plot of an integral curve, as two functions  $x$ ,  $y$ , of the independent variable  $t$ . If `versus_t` is given any value different from 0, the second plot window will be displayed. The second plot window includes another menu, similar to the menu of the main plot window. The default value is 0.
- *trajectory\_at* defines the coordinates *xinitial* and *yinitial* for the starting point of an integral curve. The option is empty by default.
- *parameters* defines a list of parameters, and their numerical values, used in the definition of the differential equations. The name and values of the parameters must be given in a string with a comma-separated sequence of pairs **name=value**.
- *sliders* defines a list of parameters that will be changed interactively using slider buttons, and the range of variation of those parameters. The names and ranges of the parameters must be given in a string with a comma-separated sequence of elements **name=min:max**
- *xfun* defines a string with semi-colon-separated sequence of functions of  $x$  to be displayed, on top of the direction field. Those functions will be parsed by Tcl and not by Maxima.
- $x$  should be followed by two numbers, which will set up the minimum and maximum values shown on the horizontal axis. If the variable on the horizontal axis is not  $x$ , then this option should have the name of the variable on the horizontal axis. The default horizontal range is from -10 to 10.
- $y$  should be followed by two numbers, which will set up the minimum and maximum values shown on the vertical axis. If the variable on the vertical axis is not  $y$ , then this option should have the name of the variable on the vertical axis. The default vertical range is from -10 to 10.

**Examples:**

- To show the direction field of the differential equation  $y' = \exp(-x) + y$  and the solution that goes through  $(2, -0.1)$ :


```
(%i1) plotdf(exp(-x)+y,[trajectory_at,2,-0.1])$
```



- To obtain the direction field for the equation  $\text{diff}(y, x) = x - y^2$  and the solution with initial condition  $y(-1) = 3$ , we can use the command:


```
(%i1) plotdf(x-y^2,[xfun,"sqrt(x);-sqrt(x)"],
[trajectory_at,-1,3], [direction,forward],
[y,-5,5], [x,-4,16])$
```

The graph also shows the function  $y = \sqrt{x}$ .




- The following example shows the direction field of a harmonic oscillator, defined by the two equations  $dz/dt = v$  and  $dv/dt = -k * z/m$ , and the integral curve through  $(z, v) = (6, 0)$ , with a slider that will allow you to change the value of  $m$  interactively ( $k$  is fixed at 2):

```
(%i1) plotdf([v,-k*z/m], [z,v], [parameters,"m=2,k=2"],
 [sliders,"m=1:5"], [trajectory_at,6,0])$
```




- To plot the direction field of the Duffing equation,  $m * x'' + c * x' + k * x + b * x^3 = 0$ , we introduce the variable  $y = x'$  and use:

```
(%i1) plotdf([y,-(k*x + c*y + b*x^3)/m],
 [parameters,"k=-1,m=1.0,c=0,b=1"],
 [sliders,"k=-2:2,m=-1:1"], [tstep,0.1])$
```




- The direction field for a damped pendulum, including the solution for the given initial conditions, with a slider that can be used to change the value of the mass  $m$ , and with a plot of the two state variables as a function of time:

```
(%i1) plotdf([w,-g*sin(a)/l - b*w/m/l], [a,w],
[parameters,"g=9.8,l=0.5,m=0.3,b=0.05"],
[trajectory_at,1.05,-9],[tstep,0.01],
[a,-10,2], [w,-14,14], [direction,forward],
[nsteps,300], [sliders,"m=0.1:1"], [versus_t,1])$
```



m: 0.297







## 72 romberg

### 72.1 Functions and Variables for romberg

**romberg** (*expr*, *x*, *a*, *b*)

Function

**romberg** (*F*, *a*, *b*)

Function

Computes a numerical integration by Romberg's method.

**romberg**(*expr*, *x*, *a*, *b*) returns an estimate of the integral **integrate**(*expr*, *x*, *a*, *b*). *expr* must be an expression which evaluates to a floating point value when *x* is bound to a floating point value.

**romberg**(*F*, *a*, *b*) returns an estimate of the integral **integrate**(*F*(*x*), *x*, *a*, *b*) where *x* represents the unnamed, sole argument of *F*; the actual argument is not named *x*. *F* must be a Maxima or Lisp function which returns a floating point value when the argument is a floating point value. *F* may name a translated or compiled Maxima function.

The accuracy of **romberg** is governed by the global variables **rombergabs** and **rombertol**. **romberg** terminates successfully when the absolute difference between successive approximations is less than **rombergabs**, or the relative difference in successive approximations is less than **rombertol**. Thus when **rombergabs** is 0.0 (the default) only the relative error test has any effect on **romberg**.

**romberg** halves the stepsize at most **rombergit** times before it gives up; the maximum number of function evaluations is therefore  $2^{\text{rombergit}}$ . If the error criterion established by **rombergabs** and **rombertol** is not satisfied, **romberg** prints an error message. **romberg** always makes at least **rombergmin** iterations; this is a heuristic intended to prevent spurious termination when the integrand is oscillatory.

**romberg** repeatedly evaluates the integrand after binding the variable of integration to a specific value (and not before). This evaluation policy makes it possible to nest calls to **romberg**, to compute multidimensional integrals. However, the error calculations do not take the errors of nested integrations into account, so errors may be underestimated. Also, methods devised especially for multidimensional problems may yield the same accuracy with fewer function evaluations.

**load**(**romberg**) loads this function.

See also **QUADPACK**, a collection of numerical integration functions.

Examples:

A 1-dimensional integration.

```
(%i1) load (romberg);
(%o1) /usr/share/maxima/5.11.0/share/numeric/romberg.lisp
(%i2) f(x) := 1/((x - 1)^2 + 1/100) + 1/((x - 2)^2 + 1/1000)
 + 1/((x - 3)^2 + 1/200);
(%o2) f(x) := ----- + ----- + -----
 2 1 2 1 2 1
 (x - 1) + --- (x - 2) + --- (x - 3) + ---
 100 1000 200

(%i3) rombertol : 1e-6;
(%o3) 9.999999999999995E-7
(%i4) rombergit : 15;
(%o4) 15
(%i5) estimate : romberg (f(x), x, -5, 5);
(%o5) 173.6730736617464
(%i6) exact : integrate (f(x), x, -5, 5);
(%o6) 10 sqrt(10) atan(70 sqrt(10))
 + 10 sqrt(10) atan(30 sqrt(10)) + 10 sqrt(2) atan(80 sqrt(2))
 + 10 sqrt(2) atan(20 sqrt(2)) + 10 atan(60) + 10 atan(40)
(%i7) abs (estimate - exact) / exact, numer;
```

```
(%o7) 7.5527060865060088E-11
```

A 2-dimensional integration, implemented by nested calls to `romberg`.

```
(%i1) load (romberg);
(%o1) /usr/share/maxima/5.11.0/share/numeric/romberg.lisp
(%i2) g(x, y) := x*y / (x + y);

(%o2) g(x, y) := -----
 x y
 x + y

(%i3) rombergtol : 1e-6;
(%o3) 9.999999999999995E-7
(%i4) estimate : romberg (romberg (g(x, y), y, 0, x/2), x, 1, 3);
(%o4) 0.81930239628356
(%i5) assume (x > 0);
(%o5) [x > 0]
(%i6) integrate (integrate (g(x, y), y, 0, x/2), x, 1, 3);

 3
 2 log(-) - 1
 9
 - 9 log(-) + 9 log(3) + ----- + -
 2 6 2

(%i7) exact : radcan (%);
 26 log(3) - 26 log(2) - 13
(%o7) - -----
 3

(%i8) abs (estimate - exact) / exact, numer;
(%o8) 1.3711979871851024E-10
```

## rombergabs

Option variable

Default value: 0.0

The accuracy of `romberg` is governed by the global variables `rombergabs` and `rombergtol`. `romberg` terminates successfully when the absolute difference between successive approximations is less than `rombergabs`, or the relative difference in successive approximations is less than `rombergtol`. Thus when `rombergabs` is 0.0 (the default) only the relative error test has any effect on `romberg`.

See also `rombergit` and `rombergmin`.

## rombergit

Option variable

Default value: 11

`romberg` halves the stepsize at most `rombergit` times before it gives up; the maximum number of function evaluations is therefore  $2^{\text{rombergit}}$ . `romberg` always makes at least `rombergmin` iterations; this is a heuristic intended to prevent spurious termination when the integrand is oscillatory.

See also `rombergabs` and `rombergtol`.

## rombergmin

Option variable

Default value: 0

`romberg` always makes at least `rombergmin` iterations; this is a heuristic intended to prevent spurious termination when the integrand is oscillatory.

See also `rombergit`, `rombergabs`, and `rombergtol`.

## rombergtol

Option variable

Default value: 1e-4

The accuracy of `romberg` is governed by the global variables `rombergabs` and `rombergtol`. `romberg` terminates successfully when the absolute difference between successive approximations is less than `rombergabs`, or the relative difference in successive approximations is

less than `rombertol`. Thus when `rombergabs` is 0.0 (the default) only the relative error test has any effect on `romberg`.

See also `rombergit` and `rombergmin`.



## 73 simplex

### 73.1 Introduction to simplex

**simplex** is a package for linear optimization using the simplex algorithm.

Example:

```
(%i1) load("simplex")$
(%i2) minimize_lp(x+y, [3*x+2*y>2, x+4*y>3]);
 9 7 1
(%o2) [--, [y = --, x = -]]
 10 10 5
```

### 73.2 Functions and Variables for simplex

#### **epsilon\_lp**

Option variable

Default value:  $10^{-8}$

Epsilon used for numerical computations in **linear\_program**.

See also: **linear\_program**.

#### **linear\_program** (*A*, *b*, *c*)

Function

**linear\_program** is an implementation of the simplex algorithm. **linear\_program**(*A*, *b*, *c*) computes a vector *x* for which *c*·*x* is minimum possible among vectors for which *A*·*x* = *b* and *x* ≥ 0. Argument *A* is a matrix and arguments *b* and *c* are lists.

**linear\_program** returns a list which contains the minimizing vector *x* and the minimum value *c*·*x*. If the problem is not bounded, it returns "Problem not bounded!" and if the problem is not feasible, it returns "Problem not feasible!".

To use this function first load the **simplex** package with **load(simplex)**;

Example:

```
(%i2) A: matrix([1,1,-1,0], [2,-3,0,-1], [4,-5,0,0])$
(%i3) b: [1,1,6]$
(%i4) c: [1,-2,0,0]$
(%i5) linear_program(A, b, c);
 13 19 3
(%o5) [--, 4, --, 0], - -]
 2 2 2
```

See also: **minimize\_lp**, **scale\_lp**, and **epsilon\_lp**.

#### **maximize\_lp** (*obj*, *cond*, [*pos*])

Function

Maximizes linear objective function *obj* subject to some linear constraints *cond*. See **minimize\_lp** for detailed description of arguments and return value.

See also: **minimize\_lp**.

#### **minimize\_lp** (*obj*, *cond*, [*pos*])

Function

Minimizes a linear objective function *obj* subject to some linear constraints *cond*. *cond* a list of linear equations or inequalities. In strict inequalities > is replaced by ≥ and < by ≤. The optional argument *pos* is a list of decision variables which are assumed to be positive.

If the minimum exists, **minimize\_lp** returns a list which contains the minimum value of the objective function and a list of decision variable values for which the minimum is attained. If the problem is not bounded, **minimize\_lp** returns "Problem not bounded!" and if the problem is not feasible, it returns "Problem not feasible!".

The decision variables are not assumed to be nonnegative by default. If all decision variables are nonnegative, set **nonnegative\_lp** to **true**. If only some of decision variables are

positive, list them in the optional argument *pos* (note that this is more efficient than adding constraints).

`minimize_lp` uses the simplex algorithm which is implemented in maxima `linear_program` function.

To use this function first load the `simplex` package with `load(simplex);`.

Examples:

```
(%i1) minimize_lp(x+y, [3*x+y=0, x+2*y>2]);
 4 6 2
(%o1) [-, [y = -, x = - -]]
 5 5 5

(%i2) minimize_lp(x+y, [3*x+y>0, x+2*y>2]), nonegative_lp=true;
(%o2) [1, [y = 1, x = 0]]
(%i3) minimize_lp(x+y, [3*x+y=0, x+2*y>2]), nonegative_lp=true;
(%o3) Problem not feasible!
(%i4) minimize_lp(x+y, [3*x+y>0]);
(%o4) Problem not bounded!
```

See also: `maximize_lp`, `nonegative_lp`, `epsilon_lp`.

## **nonegative\_lp**

Option variable

Default value: `false`

If `nonegative_lp` is true all decision variables to `minimize_lp` and `maximize_lp` are assumed to be positive.

See also: `minimize_lp`.

## 74 simplification

### 74.1 Introduction to simplification

The directory `maxima/share/simplification` contains several scripts which implement simplification rules and functions, and also some functions not related to simplification.

### 74.2 Package `absimp`

The `absimp` package contains pattern-matching rules that extend the built-in simplification rules for the `abs` and `signum` functions. `absimp` respects relations established with the built-in `assume` function and by declarations such as `modedecclare (m, even, n, odd)` for even or odd integers.

`absimp` defines `unitramp` and `unitstep` functions in terms of `abs` and `signum`.

`load (absimp)` loads this package. `demo (absimp)` shows a demonstration of this package.

Examples:

|       |                                 |                           |
|-------|---------------------------------|---------------------------|
| (%i1) | <code>load (absimp)\$</code>    |                           |
| (%i2) | <code>(abs (x))^2;</code>       |                           |
| (%o2) |                                 | $x^2$                     |
| (%i3) | <code>diff (abs (x), x);</code> |                           |
| (%o3) |                                 | $\frac{x}{\text{abs}(x)}$ |
| (%i4) | <code>cosh (abs (x));</code>    |                           |
| (%o4) |                                 | <code>cosh(x)</code>      |

### 74.3 Package `facexp`

The `facexp` package contains several related functions that provide the user with the ability to structure expressions by controlled expansion. This capability is especially useful when the expression contains variables that have physical meaning, because it is often true that the most economical form of such an expression can be obtained by fully expanding the expression with respect to those variables, and then factoring their coefficients. While it is true that this procedure is not difficult to carry out using standard Maxima functions, additional fine-tuning may also be desirable, and these finishing touches can be more difficult to apply.

The function `facsum` and its related forms provide a convenient means for controlling the structure of expressions in this way. Another function, `collectterms`, can be used to add two or more expressions that have already been simplified to this form, without resimplifying the whole expression again. This function may be useful when the expressions are very large.

`load (facexp)` loads this package. `demo (facexp)` shows a demonstration of this package.

**facsum** (*expr*, *arg\_1*, ..., *arg\_n*)

Function

Returns a form of *expr* which depends on the arguments *arg\_1*, ..., *arg\_n*. The arguments can be any form suitable for `ratvars`, or they can be lists of such forms. If the arguments are not lists, then the form returned is fully expanded with respect to the arguments, and the coefficients of the arguments are factored. These coefficients are free of the arguments, except perhaps in a non-rational sense.

If any of the arguments are lists, then all such lists are combined into a single list, and instead of calling `factor` on the coefficients of the arguments, `facsum` calls itself on these coefficients, using this newly constructed single list as the new argument list for this recursive call. This process can be repeated to arbitrary depth by nesting the desired elements in lists.

It is possible that one may wish to `facsum` with respect to more complicated subexpressions, such as  $\log (x + y)$ . Such arguments are also permissible.

Occasionally the user may wish to obtain any of the above forms for expressions which are specified only by their leading operators. For example, one may wish to **facsum** with respect to all **log**'s. In this situation, one may include among the arguments either the specific **log**'s which are to be treated in this way, or alternatively, either the expression **operator (log)** or **'operator (log)**. If one wished to **facsum** the expression *expr* with respect to the operators *op\_1*, ..., *op\_n*, one would evaluate **facsum (expr, operator (op\_1, ..., op\_n))**. The **operator** form may also appear inside list arguments.

In addition, the setting of the switches **facsum\_combine** and **nextlayerfactor** may affect the result of **facsum**.

### **nextlayerfactor**

Global variable

Default value: **false**

When **nextlayerfactor** is **true**, recursive calls of **facsum** are applied to the factors of the factored form of the coefficients of the arguments.

When **false**, **facsum** is applied to each coefficient as a whole whenever recursive calls to **facsum** occur.

Inclusion of the atom **nextlayerfactor** in the argument list of **facsum** has the effect of **nextlayerfactor: true**, but for the next level of the expression *only*. Since **nextlayerfactor** is always bound to either **true** or **false**, it must be presented single-quoted whenever it appears in the argument list of **facsum**.

### **facsum\_combine**

Global variable

Default value: **true**

**facsum\_combine** controls the form of the final result returned by **facsum** when its argument is a quotient of polynomials. If **facsum\_combine** is **false** then the form will be returned as a fully expanded sum as described above, but if **true**, then the expression returned is a ratio of polynomials, with each polynomial in the form described above.

The **true** setting of this switch is useful when one wants to **facsum** both the numerator and denominator of a rational expression, but does not want the denominator to be multiplied through the terms of the numerator.

### **factorfacsum (expr, arg\_1, ... arg\_n)**

Function

Returns a form of *expr* which is obtained by calling **facsum** on the factors of *expr* with *arg\_1*, ... *arg\_n* as arguments. If any of the factors of *expr* is raised to a power, both the factor and the exponent will be processed in this way.

### **collectterms (expr, arg\_1, ..., arg\_n)**

Function

If several expressions have been simplified with the following functions **facsum**, **factorfacsum**, **factenexpand**, **facexptn** or **factorfacexptn**, and they are to be added together, it may be desirable to combine them using the function **collectterms**. **collectterms** can take as arguments all of the arguments that can be given to these other associated functions with the exception of **nextlayerfactor**, which has no effect on **collectterms**. The advantage of **collectterms** is that it returns a form similar to **facsum**, but since it is adding forms that have already been processed by **facsum**, it does not need to repeat that effort. This capability is especially useful when the expressions to be summed are very large.

## 74.4 Package functs

### **rempart (expr, n)**

Function

Removes part *n* from the expression *expr*.

If *n* is a list of the form [*l*, *m*] then parts *l* thru *m* are removed.

To use this function write first **load(functs)**.



**wronskian** ( $[f_1, \dots, f_n], x$ ) Function

Returns the Wronskian matrix of the list of expressions  $[f_1, \dots, f_n]$  in the variable  $x$ . The determinant of the Wronskian matrix is the Wronskian determinant of the list of expressions.

To use **wronskian**, first **load(funcs)**. Example:

```
(%i1) load(funcs)$
(%i2) wronskian([f(x), g(x)],x);
(%o2) matrix([f(x),g(x)],['diff(f(x),x,1),'diff(g(x),x,1)])
```

**tracematrix** ( $M$ ) Function

Returns the trace (sum of the diagonal elements) of matrix  $M$ .

To use this function write first **load(funcs)**.

**rational** ( $z$ ) Function

Multiplies numerator and denominator of  $z$  by the complex conjugate of denominator, thus rationalizing the denominator. Returns canonical rational expression (CRE) form if given one, else returns general form.

To use this function write first **load(funcs)**.

**logand** ( $x,y$ ) Function

Returns logical (bit-wise) "and" of arguments  $x$  and  $y$ .

To use this function write first **load(funcs)**.

**logor** ( $x,y$ ) Function

Returns logical (bit-wise) "or" of arguments  $x$  and  $y$ .

To use this function write first **load(funcs)**.

**logxor** ( $x,y$ ) Function

Returns logical (bit-wise) exclusive-or of arguments  $x$  and  $y$ .

To use this function write first **load(funcs)**.

**nonzeroandfreeof** ( $x, \text{expr}$ ) Function

Returns **true** if  $\text{expr}$  is nonzero and **freeof** ( $x, \text{expr}$ ) returns **true**. Returns **false** otherwise.

To use this function write first **load(funcs)**.

**linear** ( $\text{expr}, x$ ) Function

When  $\text{expr}$  is an expression linear in variable  $x$ , **linear** returns  $a*x + b$  where  $a$  is nonzero, and  $a$  and  $b$  are free of  $x$ . Otherwise, **linear** returns  $\text{expr}$ .

To use this function write first **load(funcs)**.

**gcddivide** ( $p, q$ ) Function

When the option variable **takegcd** is **true** which is the default, **gcddivide** divides the polynomials  $p$  and  $q$  by their greatest common divisor and returns the ratio of the results. **gcddivide** calls the function **ezgcd** to divide the polynomials by the greatest common divisor.

When **takegcd** is **false**, **gcddivide** returns the ratio  $p/q$ .

To use this function write first **load(funcs)**.

See also **ezgcd**, **gcd**, **gcdex**, and **poly\_gcd**.

Example:

```
(%i1) load(funcs)$

(%i2) p1:6*x^3+19*x^2+19*x+6;
 3 2
(%o2) 6 x + 19 x + 19 x + 6
(%i3) p2:6*x^5+13*x^4+12*x^3+13*x^2+6*x;
 5 4 3 2
(%o3) 6 x + 13 x + 12 x + 13 x + 6 x
(%i4) gcddivide(p1, p2);
 x + 1
(%o4) -----
 3
 x + x

(%i5) takegcd:false;
(%o5) false
(%i6) gcddivide(p1, p2);
 3 2
 6 x + 19 x + 19 x + 6
(%o6) -----
 5 4 3 2
 6 x + 13 x + 12 x + 13 x + 6 x
(%i7) ratsimp(%);
 x + 1
(%o7) -----
 3
 x + x
```

**arithmetic** ( $a, d, n$ ) Function  
 Returns the  $n$ -th term of the arithmetic series  $a, a + d, a + 2*d, \dots, a + (n - 1)*d$ .  
 To use this function write first `load(funcs)`.

**geometric** ( $a, r, n$ ) Function  
 Returns the  $n$ -th term of the geometric series  $a, a*r, a*r^2, \dots, a*r^{(n - 1)}$ .  
 To use this function write first `load(funcs)`.

**harmonic** ( $a, b, c, n$ ) Function  
 Returns the  $n$ -th term of the harmonic series  $a/b, a/(b + c), a/(b + 2*c), \dots, a/(b + (n - 1)*c)$ .  
 To use this function write first `load(funcs)`.

**arithsum** ( $a, d, n$ ) Function  
 Returns the sum of the arithmetic series from 1 to  $n$ .  
 To use this function write first `load(funcs)`.

**geosum** ( $a, r, n$ ) Function  
 Returns the sum of the geometric series from 1 to  $n$ . If  $n$  is infinity (`inf`) then a sum is finite only if the absolute value of  $r$  is less than 1.  
 To use this function write first `load(funcs)`.

**gaussprob** ( $x$ ) Function  
 Returns the Gaussian probability function  $\%e^{(-x^2/2)} / \text{sqrt}(2*\%pi)$ .  
 To use this function write first `load(funcs)`.

**gd** ( $x$ ) Function  
 Returns the Gudermannian function  $2*\text{atan}(\%e^x) - \%pi/2$ .  
 To use this function write first `load(funcs)`.

|                                                                                                 |          |
|-------------------------------------------------------------------------------------------------|----------|
| <b>agd</b> ( <i>x</i> )                                                                         | Function |
| Returns the inverse Gudermannian function $\log(\tan(\pi/4 + x/2))$ .                           |          |
| To use this function write first <code>load(functions)</code> .                                 |          |
| <b>vers</b> ( <i>x</i> )                                                                        | Function |
| Returns the versed sine $1 - \cos(x)$ .                                                         |          |
| To use this function write first <code>load(functions)</code> .                                 |          |
| <b>covers</b> ( <i>x</i> )                                                                      | Function |
| Returns the covered sine $1 - \sin(x)$ .                                                        |          |
| To use this function write first <code>load(functions)</code> .                                 |          |
| <b>exsec</b> ( <i>x</i> )                                                                       | Function |
| Returns the exsecant $\sec(x) - 1$ .                                                            |          |
| To use this function write first <code>load(functions)</code> .                                 |          |
| <b>hav</b> ( <i>x</i> )                                                                         | Function |
| Returns the haversine $(1 - \cos(x))/2$ .                                                       |          |
| To use this function write first <code>load(functions)</code> .                                 |          |
| <b>combination</b> ( <i>n</i> , <i>r</i> )                                                      | Function |
| Returns the number of combinations of <i>n</i> objects taken <i>r</i> at a time.                |          |
| To use this function write first <code>load(functions)</code> .                                 |          |
| <b>permutation</b> ( <i>n</i> , <i>r</i> )                                                      | Function |
| Returns the number of permutations of <i>r</i> objects selected from a set of <i>n</i> objects. |          |
| To use this function write first <code>load(functions)</code> .                                 |          |

## 74.5 Package ineq

The `ineq` package contains simplification rules for inequalities.

Example session:

```
(%i1) load(ineq)$
Warning: Putting rules on '+' or '*' is inefficient, and may not work.
Warning: Putting rules on '+' or '*' is inefficient, and may not work.
Warning: Putting rules on '+' or '*' is inefficient, and may not work.
Warning: Putting rules on '+' or '*' is inefficient, and may not work.
Warning: Putting rules on '+' or '*' is inefficient, and may not work.
Warning: Putting rules on '+' or '*' is inefficient, and may not work.
Warning: Putting rules on '+' or '*' is inefficient, and may not work.
Warning: Putting rules on '+' or '*' is inefficient, and may not work.
(%i2) a>=4; /* a sample inequality */
(%o2) a >= 4
(%i3) (b>c)+%; /* add a second, strict inequality */
(%o3) b + a > c + 4
(%i4) 7*(x<y); /* multiply by a positive number */
(%o4) 7 x < 7 y
(%i5) -2*(x>=3*z); /* multiply by a negative number */
(%o5) - 2 x <= - 6 z
(%i6) (1+a^2)*(1/(1+a^2)<=1); /* Maxima knows that 1+a^2 > 0 */
(%o6) 1 <= a^2 + 1
(%i7) assume(x>0)$ x*(2<3); /* assuming x>0 */
(%o7) 2 x < 3 x
```

```

(%i8) a>=b; /* another inequality */
(%o8)

$$a \geq b$$

(%i9) 3+%; /* add something */
(%o9)

$$a + 3 \geq b + 3$$

(%i10) %-3; /* subtract it out */
(%o10)

$$a \geq b$$

(%i11) a>=c-b; /* yet another inequality */
(%o11)

$$a \geq c - b$$

(%i12) b+%; /* add b to both sides */
(%o12)

$$b + a \geq c$$

(%i13) %-c; /* subtract c from both sides */
(%o13)

$$-c + b + a \geq 0$$

(%i14) -%; /* multiply by -1 */
(%o14)

$$c - b - a \leq 0$$

(%i15) (z-1)^2>-2*z; /* determining truth of assertion */
(%o15)

$$(z - 1)^2 > -2z$$

(%i16) expand(%)+2*z; /* expand this and add 2*z to both sides */
(%o16)

$$z^2 + 1 > 0$$

(%i17) %,pred;
(%o17)
true

```

Be careful about using parentheses around the inequalities: when the user types in  $(A > B) + (C = 5)$  the result is  $A + C > B + 5$ , but  $A > B + C = 5$  is a syntax error, and  $(A > B + C) = 5$  is something else entirely.

Do `disprule (all)` to see a complete listing of the rule definitions.

The user will be queried if Maxima is unable to decide the sign of a quantity multiplying an inequality.

The most common mis-feature is illustrated by:

```

(%i1) eq: a > b;
(%o1)

$$a > b$$

(%i2) 2*eq;
(%o2)

$$2 (a > b)$$

(%i3) % - eq;
(%o3)

$$a > b$$


```

Another problem is 0 times an inequality; the default to have this turn into 0 has been left alone. However, if you type `X*some_inequality` and Maxima asks about the sign of `X` and you respond `zero` (or `z`), the program returns `X*some_inequality` and not use the information that `X` is 0. You should do `ev (% , x: 0)` in such a case, as the database will only be used for comparison purposes in decisions, and not for the purpose of evaluating `X`.

The user may note a slower response when this package is loaded, as the simplifier is forced to examine more rules than without the package, so you might wish to remove the rules after making use of them. Do `kill (rules)` to eliminate all of the rules (including any that you might have defined); or you may be more selective by killing only some of them; or use `remrule` on a specific rule.

Note that if you load this package after defining your own rules you will clobber your rules that have the same name. The rules in this package are: `*rule1`, ..., `*rule8`, `+rule1`, ..., `+rule18`, and you must enclose the rulename in quotes to refer to it, as in `remrule ("+", "+rule1")` to specifically remove the first rule on `+` or `disprule ("*rule2")` to display the definition of the second multiplicative rule.

## 74.6 Package rducon

**reduce\_consts** (*expr*)

Function

Replaces constant subexpressions of *expr* with constructed constant atoms, saving the definition of all these constructed constants in the list of equations `const_eqns`, and returning the modified *expr*. Those parts of *expr* are constant which return `true` when operated on by the function `constantp`. Hence, before invoking `reduce_consts`, one should do

```
declare ([objects to be given the constant property], constant)$
```

to set up a database of the constant quantities occurring in your expressions.

If you are planning to generate Fortran output after these symbolic calculations, one of the first code sections should be the calculation of all constants. To generate this code segment, do

```
map ('fortran, const_eqns)$
```

Variables besides `const_eqns` which affect `reduce_consts` are:

`const_prefix` (default value: `xx`) is the string of characters used to prefix all symbols generated by `reduce_consts` to represent constant subexpressions.

`const_counter` (default value: 1) is the integer index used to generate unique symbols to represent each constant subexpression found by `reduce_consts`.

`load (rducon)` loads this function. `demo (rducon)` shows a demonstration of this function.

**74.7 Package scifac****gcfac** (*expr*)

Function

`gcfac` is a factoring function that attempts to apply the same heuristics which scientists apply in trying to make expressions simpler. `gcfac` is limited to monomial-type factoring. For a sum, `gcfac` does the following:

1. Factors over the integers.
2. Factors out the largest powers of terms occurring as coefficients, regardless of the complexity of the terms.
3. Uses (1) and (2) in factoring adjacent pairs of terms.
4. Repeatedly and recursively applies these techniques until the expression no longer changes.

Item (3) does not necessarily do an optimal job of pairwise factoring because of the combinatorially-difficult nature of finding which of all possible rearrangements of the pairs yields the most compact pair-factored result.

`load (scifac)` loads this function. `demo (scifac)` shows a demonstration of this function.

**74.8 Package sqdnst****sqrtdenest** (*expr*)

Function

Denests `sqrt` of simple, numerical, binomial surds, where possible. E.g.

```
(%i1) load (sqdnst)$
(%i2) sqrt(sqrt(3)/2+1)/sqrt(11*sqrt(2)-12);
 sqrt(3)
 sqrt(----- + 1)
 2
(%o2) -----
 sqrt(11 sqrt(2) - 12)
(%i3) sqrtdenest(%);
 sqrt(3) 1
 ----- + -
```

$$\begin{array}{r}
 \phantom{(\%o3)} \qquad \qquad \qquad \begin{array}{cc} 2 & 2 \\ \hline 1/4 & 3/4 \\ 3^2 & - 2 \end{array} \\
 (\%o3)
 \end{array}$$

Sometimes it helps to apply `sqrtdenest` more than once, on such as `(19601-13860 sqrt(2))^(7/4)`.

`load (sqdnst)` loads this function.

## 75 solve\_rec

### 75.1 Introduction to solve\_rec

`solve_rec` is a package for solving linear recurrences with polynomial coefficients.

A demo is available with `demo(solve_rec);`.

Example:

```
(%i1) load("solve_rec")$
(%i2) solve_rec((n+4)*s[n+2] + s[n+1] - (n+1)*s[n], s[n]);
```

$$s_n = \frac{{}^k_1 (2n+3) (-1)^n}{(n+1)(n+2)} + \frac{{}^k_2}{(n+1)(n+2)}$$

```
(%o2)
```

### 75.2 Functions and Variables for solve\_rec

**reduce\_order** (*rec, sol, var*)

Function

Reduces the order of linear recurrence *rec* when a particular solution *sol* is known. The reduced recurrence can be used to get other solutions.

Example:

```
(%i3) rec: x[n+2] = x[n+1] + x[n]/n;
```

$$x_{n+2} = x_{n+1} + \frac{x_n}{n}$$

```
(%o3)
```

```
(%i4) solve_rec(rec, x[n]);
WARNING: found some hypergeometrical solutions!
```

```
(%o4)
```

$$x_n = {}^k_1 n$$

```
(%i5) reduce_order(rec, n, x[n]);
(%t5)
```

$$\frac{x_n}{n} = n \frac{z}{n}$$

```
(%t6)
```

$$\frac{z}{n} = \frac{u}{j} > \frac{u}{j}$$

$$\frac{z}{n} = 0$$

```
(%o6)
```

$$(-n-2) \frac{u}{n+1} - \frac{u}{n}$$

```
(%i6) solve_rec((n+2)*%u[n+1] + %u[n], %u[n]);
```

$$(\%o6) \quad \frac{{}^n k \quad (-1)^n}{n \quad (n+1)!} \quad %u$$

So the general solution is

$$\frac{{}^n k}{2} \sum_{j=0}^{n-1} \frac{(-1)^j}{(j+1)!} + {}^n k_1$$

### simplify\_products

Option variable

Default value: `true`

If `simplify_products` is `true`, `solve_rec` will try to simplify products in result.

See also: `solve_rec`.

### simplify\_sum (expr)

Function

Tries to simplify all sums appearing in `expr` to a closed form.

To use this function first load the `simplify_sum` package with `load(simplify_sum)`.

Example:

```
(%i1) load("simplify_sum")$
(%i2) sum(binomial(n+k,k)/2^k,k,1,n)+sum(binomial(2*n,2*k),k,1,n);
```

$$(\%o2) \quad \sum_{k=1}^n \frac{\text{binomial}(n+k, k)}{2^k} + \sum_{k=1}^n \text{binomial}(2n, 2k)$$

```
(%i3) simplify_sum(%);
```

$$(\%o3) \quad \frac{2^{2n}-1}{2} + 2^n - 2$$

### solve\_rec (eqn, var, [init])

Function

Solves for hypergeometrical solutions to linear recurrence `eqn` with polynomial coefficients in variable `var`. Optional arguments `init` are initial conditions.

`solve_rec` can solve linear recurrences with constant coefficients, finds hypergeometrical solutions to homogeneous linear recurrences with polynomial coefficients, rational solutions to linear recurrences with polynomial coefficients and can solve Ricatti type recurrences.

Note that the running time of the algorithm used to find hypergeometrical solutions is exponential in the degree of the leading and trailing coefficient.

To use this function first load the `solve_rec` package with `load(solve_rec);`.

Example of linear recurrence with constant coefficients:



```
(%i2) solve_rec(a[n]=a[n-1]+a[n-2]+n/2^n, a[n]);
```

$$a_n = \frac{(\sqrt{5}-1)^n}{2^n} - \frac{(\sqrt{5}-1)^n}{5 \cdot 2^n} + \frac{(\sqrt{5}+1)^n}{2^n} - \frac{(\sqrt{5}+1)^n}{5 \cdot 2^n}$$

Example of linear recurrence with polynomial coefficients:

```
(%i7) 2*x*(x+1)*y[x] - (x^2+3*x-2)*y[x+1] + (x-1)*y[x+2];
```

$$(x-1)y_{x+2} - (x^2+3x-2)y_{x+1} + 2x(x+1)y_x$$

```
(%o7) (x - 1) y_{x+2} - (x^2 + 3 x - 2) y_{x+1} + 2 x (x + 1) y_x
```

```
(%i8) solve_rec(%, y[x], y[1]=1, y[3]=3);
```

$$y_x = \frac{x^3}{4} - \frac{x!}{2}$$

```
(%o9) y_x = \frac{x^3}{4} - \frac{x!}{2}
```

Example of Ricatti type recurrence:

```
(%i2) x*y[x+1]*y[x] - y[x+1]/(x+2) + y[x]/(x-1) = 0;
```

$$x y_{x+1} y_x - \frac{y_{x+1}}{x+2} + \frac{y_x}{x-1} = 0$$

```
(%o2) x y_{x+1} y_x - \frac{y_{x+1}}{x+2} + \frac{y_x}{x-1} = 0
```

```
(%i3) solve_rec(%, y[x], y[3]=5)$
```

```
(%i4) ratsimp(minfactorial(factcomb(%)));
```

$$y_x = -\frac{30x^3 - 30x^2}{5x^6 - 3x^5 - 25x^4 + 15x^3 + 20x^2 - 12x - 1584}$$

```
(%o4) y_x = -\frac{30x^3 - 30x^2}{5x^6 - 3x^5 - 25x^4 + 15x^3 + 20x^2 - 12x - 1584}
```

See also: `solve_rec_rat`, `simplify_products`, and `product_use_gamma`.

### **solve\_rec\_rat** (*eqn*, *var*, [*init*])

Function

Solves for rational solutions to linear recurrences. See `solve_rec` for description of arguments.

To use this function first load the `solve_rec` package with `load(solve_rec);`.

Example:

```
(%i1) (x+4)*a[x+3] + (x+3)*a[x+2] - x*a[x+1] + (x^2-1)*a[x];
```

$$(x+4)a_{x+3} + (x+3)a_{x+2} - xa_{x+1} + (x^2-1)a_x$$

```
(%o1) (x + 4) a_{x+3} + (x + 3) a_{x+2} - x a_{x+1} + (x^2 - 1) a_x
```

```
(%i2) solve_rec_rat(%, (x+2)/(x+1), a[x]);
```

$$a_x = \frac{1}{x(x-1)(x+1)}$$

```
(%o2) a_x = \frac{1}{x(x-1)(x+1)}
```

See also: `solve_rec`.

**product\_use\_gamma**

Option variable

Default value: `true`

When simplifying products, `solve_rec` introduces gamma function into the expression if `product_use_gamma` is true.

See also: `simplify_products`, `solve_rec`.

**summand\_to\_rec** (*summand*, *k*, *n*)

Function

**summand\_to\_rec** (*summand*, [*k*, *lo*, *hi*], *n*)

Function

Returns the recurrence satisfied by the sum

```

 hi
 ====
 \
 > summand
 /
 ====
 k = lo

```

where *summand* is hypergeometrical in *k* and *n*. If *lo* and *hi* are omitted, they are assumed to be *lo* = `-inf` and *hi* = `inf`.

To use this function first load the `simplify_sum` package with `load(simplify_sum)`.

Example:

```

(%i1) load("simplify_sum")$
(%i2) summand: binom(n,k);
(%o2) binomial(n, k)
(%i3) summand_to_rec(summand,k,n);
(%o3)
 2 sm - sm = 0
 n n + 1
(%i7) summand: binom(n, k)/(k+1);
(%o7)
 binomial(n, k)

 k + 1
(%i8) summand_to_rec(summand, [k, 0, n], n);
(%o8)
 2 (n + 1) sm - (n + 2) sm = - 1
 n n + 1

```

## 76 stats

### 76.1 Introduction to stats

Package **stats** contains a set of classical statistical inference and hypothesis testing procedures.

All these functions return an **inference\_result** Maxima object which contains the necessary results for population inferences and decision making.

Global variable **stats\_numer** controls whether results are given in floating point or symbolic and rational format; its default value is **true** and results are returned in floating point format.

Package **descriptive** contains some utilities to manipulate data structures (lists and matrices); for example, to extract subsamples. It also contains some examples on how to use package **numericalio** to read data from plain text files. See **descriptive** and **numericalio** for more details.

Package **stats** loads packages **descriptive**, **distrib** and **inference\_result**.

For comments, bugs or suggestions, please contact the author at  
'mario AT edu DOT xunta DOT es'.

### 76.2 Functions and Variables for inference\_result

**inference\_result** (*title, values, numbers*) Function

Constructs an **inference\_result** object of the type returned by the stats functions. Argument *title* is a string with the name of the procedure; *values* is a list with elements of the form **symbol = value** and *numbers* is a list with positive integer numbers ranging from one to **length(values)**, indicating which values will be shown by default.

Example:

This is a simple example showing results concerning a rectangle. The title of this object is the string "Rectangle", it stores five results, named 'base', 'height', 'diagonal', 'area', and 'perimeter', but only the first, second, fifth, and fourth will be displayed. The 'diagonal' is stored in this object, but it is not displayed; to access its value, make use of function **take\_inference**.

```
(%i1) load(inference_result)$
(%i2) b: 3$ h: 2$
(%i3) inference_result("Rectangle",
 ['base=b,
 'height=h,
 'diagonal=sqrt(b^2+h^2),
 'area=b*h,
 'perimeter=2*(b+h)],
 [1,2,5,4]);
| Rectangle
|
| base = 3
|
| height = 2
|
| perimeter = 10
|
| area = 6
(%i4) take_inference('diagonal,%);
(%o4) sqrt(13)
```

See also **take\_inference**.

**inferencep** (*obj*) Function  
 Returns **true** or **false**, depending on whether *obj* is an **inference\_result** object or not.

**items\_inference** (*obj*) Function  
 Returns a list with the names of the items stored in *obj*, which must be an **inference\_result** object.

Example:

The **inference\_result** object stores two values, named 'pi and 'e, but only the second is displayed. The **items\_inference** function returns the names of all items, no matter they are displayed or not.

```
(%i1) load(inference_result)$
(%i2) inference_result("Hi", ['pi=%pi, 'e=%e], [2]);
 | Hi
(%o2) |
 | e = %e
(%i3) items_inference(%);
(%o3) [pi, e]
```

**take\_inference** (*n*, *obj*) Function

**take\_inference** (*name*, *obj*) Function

**take\_inference** (*list*, *obj*) Function

Returns the *n*-th value stored in *obj* if *n* is a positive integer, or the item named *name* if this is the name of an item. If the first argument is a list of numbers and/or symbols, function **take\_inference** returns a list with the corresponding results.

Example:

Given an **inference\_result** object, function **take\_inference** is called in order to extract some information stored in it.

```
(%i1) load(inference_result)$
(%i2) b: 3$ h: 2$
(%i3) sol: inference_result("Rectangle",
 ['base=b,
 'height=h,
 'diagonal=sqrt(b^2+h^2),
 'area=b*h,
 'perimeter=2*(b+h)],
 [1,2,5,4]);
 | Rectangle
 |
 | base = 3
(%o3) |
 | height = 2
 |
 | perimeter = 10
 |
 | area = 6
(%i4) take_inference('base,sol);
(%o4) 3
(%i5) take_inference(5,sol);
(%o5) 10
(%i6) take_inference([1,'diagonal],sol);
(%o6) [3, sqrt(13)]
(%i7) take_inference(items_inference(sol),sol);
(%o7) [3, 2, sqrt(13), 6, 10]
```

See also **inference\_result** and **take\_inference**.



```

|
| distribution = [student_t, 9]
|
| p_value = .7845100411786889

```

This time Maxima performs an asymptotic test, based on the *Central Limit Theorem*. The null hypothesis is  $H_0 : equal(mean, 50)$  against the two sided alternative  $H_1 : notequal(mean, 50)$ ; according to the results, the  $p$ -value is very small,  $H_0$  should be rejected in favor of the alternative  $H_1$ . Note that, as indicated by the `Method` component, this procedure should be applied to large samples.

```

(%i1) load("stats")$
(%i2) test_mean([36,118,52,87,35,256,56,178,57,57,89,34,25,98,35,
 98,41,45,198,54,79,63,35,45,44,75,42,75,45,45,
 45,51,123,54,151],
 'asymptotic=true,'mean=50);
|
| MEAN TEST
|
| mean_estimate = 74.88571428571429
|
| conf_level = 0.95
|
| conf_interval = [57.72848600856194, 92.04294256286663]
|
(%o2) | method = Large sample z-test. Unknown variance.
|
| hypotheses = H0: mean = 50 , H1: mean # 50
|
| statistic = 2.842831192874313
|
| distribution = [normal, 0, 1]
|
| p_value = .004471474652002261

```

|                                                                   |          |
|-------------------------------------------------------------------|----------|
| <b>test_means_difference</b> ( $x1$ , $x2$ )                      | Function |
| <b>test_means_difference</b> ( $x1$ , $x2$ , <i>options ...</i> ) | Function |

This is the difference of means  $t$ -test for two samples. Arguments  $x1$  and  $x2$  are lists or column matrices containing two independent samples. In case of different unknown variances (see options `'dev1`, `'dev2` and `'varequal` below), the degrees of freedom are computed by means of the Welch approximation. It also performs an asymptotic test based on the *Central Limit Theorem* if option `'asymptotic` is set to `true`.

Options:

- 
- `'alternative`, default `'twosided`, is the alternative hypothesis; valid values are: `'twosided`, `'greater` and `'less`.
- `'dev1`, default `'unknown`, this is the value of the standard deviation of the  $x1$  sample when it is known; valid values are: `'unknown` or a positive expression.
- `'dev2`, default `'unknown`, this is the value of the standard deviation of the  $x2$  sample when it is known; valid values are: `'unknown` or a positive expression.
- `'varequal`, default `false`, whether variances should be considered to be equal or not; this option takes effect only when `'dev1` and/or `'dev2` are `'unknown`.
- `'conflvel`, default `95/100`, confidence level for the confidence interval; it must be an expression which takes a value in  $(0,1)$ .
- `'asymptotic`, default `false`, indicates whether it performs an exact  $t$ -test or an asymptotic one based on the *Central Limit Theorem*; valid values are `true` and `false`.

The output of function `test_means_difference` is an `inference_result` Maxima object showing the following results:

1. 'diff\_estimate: the difference of means estimate.
2. 'conf\_level: confidence level selected by the user.
3. 'conf\_interval: confidence interval for the difference of means.
4. 'method: inference procedure.
5. 'hypotheses: null and alternative hypotheses to be tested.
6. 'statistic: value of the sample statistic used for testing the null hypothesis.
7. 'distribution: distribution of the sample statistic, together with its parameter(s).
8. 'p\_value:  $p$ -value of the test.

Examples:

The equality of means is tested with two small samples  $x$  and  $y$ , against the alternative  $H_1 : m_1 > m_2$ , being  $m_1$  and  $m_2$  the populations means; variances are unknown and supposed to be different.

```
(%i1) load("stats")$
(%i2) x: [20.4,62.5,61.3,44.2,11.1,23.7]$
(%i3) y: [1.2,6.9,38.7,20.4,17.2]$
(%i4) test_means_difference(x,y,'alternative='greater');
 DIFFERENCE OF MEANS TEST
 diff_estimate = 20.319999999999999
 conf_level = 0.95
 conf_interval = [- .04597417812882298, inf]
(%o4) method = Exact t-test. Welch approx.
 hypotheses = H0: mean1 = mean2 , H1: mean1 > mean2
 statistic = 1.838004300728477
 distribution = [student_t, 8.62758740184604]
 p_value = .05032746527991905
```

The same test as before, but now variances are supposed to be equal.

```
(%i1) load("stats")$
(%i2) x: [20.4,62.5,61.3,44.2,11.1,23.7]$
(%i3) y: matrix([1.2],[6.9],[38.7],[20.4],[17.2])$
(%i4) test_means_difference(x,y,'alternative='greater',
 'varequal=true);
 DIFFERENCE OF MEANS TEST
 diff_estimate = 20.319999999999999
 conf_level = 0.95
 conf_interval = [- .7722627696897568, inf]
(%o4) method = Exact t-test. Unknown equal variances
 hypotheses = H0: mean1 = mean2 , H1: mean1 > mean2
 statistic = 1.765996124515009
 distribution = [student_t, 9]
```

```
|
| p_value = .05560320992529344
```

**test\_variance** (*x*)

Function

**test\_variance** (*x, options, ...*)

Function

This is the variance  $\chi^2$ -test. Argument *x* is a list or a column matrix containing a one dimensional sample taken from a normal population.

Options:

- 'mean, default 'unknown, is the population's mean, when it is known.
- 'alternative, default 'twosided, is the alternative hypothesis; valid values are: 'twosided, 'greater and 'less.
- 'variance, default 1, this is the variance value (positive) to be checked.
- 'conlevel, default 95/100, confidence level for the confidence interval; it must be an expression which takes a value in (0,1).

The output of function **test\_variance** is an **inference\_result** Maxima object showing the following results:

1. 'var\_estimate: the sample variance.
2. 'conf\_level: confidence level selected by the user.
3. 'conf\_interval: confidence interval for the population variance.
4. 'method: inference procedure.
5. 'hypotheses: null and alternative hypotheses to be tested.
6. 'statistic: value of the sample statistic used for testing the null hypothesis.
7. 'distribution: distribution of the sample statistic, together with its parameter.
8. 'p\_value: *p*-value of the test.

Examples:

It is tested whether the variance of a population with unknown mean is equal to or greater than 200.

```
(%i1) load("stats")$
(%i2) x: [203,229,215,220,223,233,208,228,209]$
(%i3) test_variance(x,'alternative='greater','variance=200);
|
| VARIANCE TEST
|
| var_estimate = 110.75
|
| conf_level = 0.95
|
| conf_interval = [57.13433376937479, inf]
(%o3) | method = Variance Chi-square test. Unknown mean.
|
| hypotheses = H0: var = 200 , H1: var > 200
|
| statistic = 4.43
|
| distribution = [chi2, 8]
|
| p_value = .8163948512777689
```

**test\_variance\_ratio** (*x1, x2*)

Function

**test\_variance\_ratio** (*x1, x2, options ...*)

Function

This is the variance ratio *F*-test for two normal populations. Arguments *x1* and *x2* are lists or column matrices containing two independent samples.

Options:



- 'alternative, default 'twosided, is the alternative hypothesis; valid values are: 'twosided, 'greater and 'less.
- 'mean1, default 'unknown, when it is known, this is the mean of the population from which x1 was taken.
- 'mean2, default 'unknown, when it is known, this is the mean of the population from which x2 was taken.
- 'conflvel, default 95/100, confidence level for the confidence interval of the ratio; it must be an expression which takes a value in (0,1).

The output of function `test_variance_ratio` is an `inference_result` Maxima object showing the following results:

1. 'ratio\_estimate: the sample variance ratio.
2. 'conf\_level: confidence level selected by the user.
3. 'conf\_interval: confidence interval for the variance ratio.
4. 'method: inference procedure.
5. 'hypotheses: null and alternative hypotheses to be tested.
6. 'statistic: value of the sample statistic used for testing the null hypothesis.
7. 'distribution: distribution of the sample statistic, together with its parameters.
8. 'p\_value:  $p$ -value of the test.

Examples:

The equality of the variances of two normal populations is checked against the alternative that the first is greater than the second.

```
(%i1) load("stats")$
(%i2) x: [20.4,62.5,61.3,44.2,11.1,23.7]$
(%i3) y: [1.2,6.9,38.7,20.4,17.2]$
(%i4) test_variance_ratio(x,y,'alternative='greater);
|
| VARIANCE RATIO TEST
|
| ratio_estimate = 2.316933391522034
|
| conf_level = 0.95
|
| conf_interval = [.3703504689507268, inf]
|
(%o4) | method = Variance ratio F-test. Unknown means.
|
| hypotheses = H0: var1 = var2 , H1: var1 > var2
|
| statistic = 2.316933391522034
|
| distribution = [f, 5, 4]
|
| p_value = .2179269692254457
```

**test\_proportion** ( $x, n$ )

Function

**test\_proportion** ( $x, n, options \dots$ )

Function

Inferences on a proportion. Argument  $x$  is the number of successes in  $n$  trials in a Bernoulli experiment with unknown probability.

Options:

- 'proportion, default 1/2, is the value of the proportion to be checked.
- 'alternative, default 'twosided, is the alternative hypothesis; valid values are: 'twosided, 'greater and 'less.
- 'conflvel, default 95/100, confidence level for the confidence interval; it must be an expression which takes a value in (0,1).

- 'asymptotic, default **false**, indicates whether it performs an exact test based on the binomial distribution, or an asymptotic one based on the *Central Limit Theorem*; valid values are **true** and **false**.
- 'correct, default **true**, indicates whether Yates correction is applied or not.

The output of function `test_proportion` is an `inference_result` Maxima object showing the following results:

1. 'sample\_proportion: the sample proportion.
2. 'conf\_level: confidence level selected by the user.
3. 'conf\_interval: Wilson confidence interval for the proportion.
4. 'method: inference procedure.
5. 'hypotheses: null and alternative hypotheses to be tested.
6. 'statistic: value of the sample statistic used for testing the null hypothesis.
7. 'distribution: distribution of the sample statistic, together with its parameters.
8. 'p\_value:  $p$ -value of the test.

Examples:

Performs an exact test. The null hypothesis is  $H_0 : p = 1/2$  against the one sided alternative  $H_1 : p < 1/2$ .

```
(%i1) load("stats")$
(%i2) test_proportion(45, 103, alternative = less);
 PROPORTION TEST
 sample_proportion = .4368932038834951
 conf_level = 0.95
 conf_interval = [0, 0.522714149150231]
(%o2) method = Exact binomial test.
 hypotheses = H0: p = 0.5 , H1: p < 0.5
 statistic = 45
 distribution = [binomial, 103, 0.5]
 p_value = .1184509388901454
```

A two sided asymptotic test. Confidence level is 99/100.

```
(%i1) load("stats")$
(%i2) fpprintprec:7$
(%i3) test_proportion(45, 103,
 conflevel = 99/100, asymptotic=true);
 PROPORTION TEST
 sample_proportion = .43689
 conf_level = 0.99
 conf_interval = [.31422, .56749]
(%o3) method = Asymptotic test with Yates correction.
 hypotheses = H0: p = 0.5 , H1: p # 0.5
 statistic = .43689
```

```

|
| distribution = [normal, 0.5, .048872]
|
| p_value = .19662

```

**test\_proportions\_difference** (*x1*, *n1*, *x2*, *n2*)

Function

**test\_proportions\_difference** (*x1*, *n1*, *x2*, *n2*, *options* ...)

Function

Inferences on the difference of two proportions. Argument *x1* is the number of successes in *n1* trials in a Bernoulli experiment in the first population, and *x2* and *n2* are the corresponding values in the second population. Samples are independent and the test is asymptotic.

Options:

- 'alternative, default 'twosided, is the alternative hypothesis; valid values are: 'twosided ( $p1 \neq p2$ ), 'greater ( $p1 > p2$ ) and 'less ( $p1 < p2$ ).
- 'conlevel, default 95/100, confidence level for the confidence interval; it must be an expression which takes a value in (0,1).
- 'correct, default true, indicates whether Yates correction is applied or not.

The output of function **test\_proportions\_difference** is an **inference\_result** Maxima object showing the following results:

1. 'proportions: list with the two sample proportions.
2. 'conf\_level: confidence level selected by the user.
3. 'conf\_interval: Confidence interval for the difference of proportions  $p1 - p2$ .
4. 'method: inference procedure and warning message in case of any of the samples sizes is less than 10.
5. 'hypotheses: null and alternative hypotheses to be tested.
6. 'statistic: value of the sample statistic used for testing the null hypothesis.
7. 'distribution: distribution of the sample statistic, together with its parameters.
8. 'p\_value: *p*-value of the test.

Examples:

A machine produced 10 defective articles in a batch of 250. After some maintenance work, it produces 4 defective in a batch of 150. In order to know if the machine has improved, we test the null hypothesis  $H0:p1=p2$ , against the alternative  $H0:p1>p2$ , where  $p1$  and  $p2$  are the probabilities for one produced article to be defective before and after maintenance. According to the *p* value, there is not enough evidence to accept the alternative.

```

(%i1) load("stats")$
(%i2) fpprintprec:7$
(%i3) test_proportions_difference(10, 250, 4, 150,
 alternative = greater);
|
| DIFFERENCE OF PROPORTIONS TEST
|
| proportions = [0.04, .02666667]
|
| conf_level = 0.95
|
| conf_interval = [- .02172761, 1]
|
(%o3) | method = Asymptotic test. Yates correction.
|
| hypotheses = H0: p1 = p2 , H1: p1 > p2
|
| statistic = .01333333
|
| distribution = [normal, 0, .01898069]
|

```

```
| p_value = .2411936
```

Exact standard deviation of the asymptotic normal distribution when the data are unknown.

```
(%i1) load("stats")$
(%i2) stats_numer: false$
(%i3) sol: test_proportions_difference(x1,n1,x2,n2)$
(%i4) last(take_inference('distribution,sol));
 1 1 x2 + x1
 (--- + ---) (x2 + x1) (1 - ----)
 n2 n1 n2 + n1
(%o4) sqrt(-----)
 n2 + n1
```

**test\_sign** (*x*) Function

**test\_sign** (*x, options ...*) Function

This is the non parametric sign test for the median of a continuous population. Argument *x* is a list or a column matrix containing a one dimensional sample.

Options:

- 'alternative, default 'twosided, is the alternative hypothesis; valid values are: 'twosided, 'greater and 'less.
- 'median, default 0, is the median value to be checked.

The output of function **test\_sign** is an **inference\_result** Maxima object showing the following results:

1. 'med\_estimate: the sample median.
2. 'method: inference procedure.
3. 'hypotheses: null and alternative hypotheses to be tested.
4. 'statistic: value of the sample statistic used for testing the null hypothesis.
5. 'distribution: distribution of the sample statistic, together with its parameter(s).
6. 'p\_value: *p*-value of the test.

Examples:

Checks whether the population from which the sample was taken has median 6, against the alternative  $H_1 : median > 6$ .

```
(%i1) load("stats")$
(%i2) x: [2,0.1,7,1.8,4,2.3,5.6,7.4,5.1,6.1,6]$
(%i3) test_sign(x,'median=6,'alternative='greater);
|
| SIGN TEST
|
| med_estimate = 5.1
|
| method = Non parametric sign test.
|
(%o3) | hypotheses = H0: median = 6 , H1: median > 6
|
| statistic = 7
|
| distribution = [binomial, 10, 0.5]
|
| p_value = .054687499999999989
```

**test\_signed\_rank** (*x*) Function

**test\_signed\_rank** (*x, options ...*) Function

This is the Wilcoxon signed rank test to make inferences about the median of a continuous population. Argument *x* is a list or a column matrix containing a one dimensional sample.





**test\_normality** (x)

Function

Shapiro-Wilk test for normality. Argument *x* is a list of numbers, and sample size must be greater than 2 and less or equal than 5000, otherwise, function **test\_normality** signals an error message.

Reference:

[1] Algorithm AS R94, Applied Statistics (1995), vol.44, no.4, 547-551

The output of function **test\_normality** is an **inference\_result** Maxima object with the following results:

1. 'statistic: value of the *W* statistic.
2. 'p\_value: *p*-value under normal assumption.

Examples:

Checks for the normality of a population, based on a sample of size 9.

```
(%i1) load("stats")$
(%i2) x: [12,15,17,38,42,10,23,35,28]$
(%i3) test_normality(x);
|
| SHAPIRO - WILK TEST
|
(%o3) | statistic = .9251055695162436
|
| p_value = .4361763918860381
```

**linear\_regression** (x)

Function

**linear\_regression** (x option)

Function

Multivariate linear regression,  $y_i = b_0 + b_1 * x_{1i} + b_2 * x_{2i} + \dots + b_k * x_{ki} + u_i$ , where  $u_i$  are  $N(0, \sigma^2)$  independent random variables. Argument *x* must be a matrix with more than one column. The last column is considered as the responses ( $y_i$ ).

Option:

- 'conflevel, default 95/100, confidence level for the confidence intervals; it must be an expression which takes a value in (0,1).

The output of function **linear\_regression** is an **inference\_result** Maxima object with the following results:

1. 'b\_estimation: regression coefficients estimates.
2. 'b\_covariances: covariance matrix of the regression coefficients estimates.
3. b\_conf\_int: confidence intervals of the regression coefficients.
4. b\_statistics: statistics for testing coefficient.
5. b\_p\_values: *p*-values for coefficient tests.
6. b\_distribution: probability distribution for coefficient tests.
7. v\_estimation: unbiased variance estimator.
8. v\_conf\_int: variance confidence interval.
9. v\_distribution: probability distribution for variance test.
10. residuals: residuals.
11. adc: adjusted determination coefficient.
12. aic: Akaike's information criterion.
13. bic: Bayes's information criterion.

Only items 1, 4, 5, 6, 7, 8, 9 and 11 above, in this order, are shown by default. The rest remain hidden until the user makes use of functions **items\_inference** and **take\_inference**.

Example:

Fitting a linear model to a trivariate sample. The last column is considered as the responses ( $y_i$ ).

```

(%i2) load("stats")$
(%i3) X:matrix(
 [58,111,64],[84,131,78],[78,158,83],
 [81,147,88],[82,121,89],[102,165,99],
 [85,174,101],[102,169,102])$
(%i4) fpprintprec: 4$
(%i5) res: linear_regression(X);
 | LINEAR REGRESSION MODEL
 |
 | b_estimation = [9.054, .5203, .2397]
 |
 | b_statistics = [.6051, 2.246, 1.74]
 |
 | b_p_values = [.5715, .07466, .1423]
(%o5) |
 | b_distribution = [student_t, 5]
 |
 | v_estimation = 35.27
 |
 | v_conf_int = [13.74, 212.2]
 |
 | v_distribution = [chi2, 5]
 |
 | adc = .7922
(%i6) items_inference(res);
(%o6) [b_estimation, b_covariances, b_conf_int, b_statistics,
b_p_values, b_distribution, v_estimation, v_conf_int,
v_distribution, residuals, adc, aic, bic]
(%i7) take_inference('b_covariances, res);
 [223.9 - 1.12 - .8532]
 [
(%o7) [- 1.12 .05367 - .02305]
 [
 [- .8532 - .02305 .01898]
(%i8) take_inference('bic, res);
(%o8) 30.98
(%i9) load("draw")$
(%i10) draw2d(
 points_joined = true,
 grid = true,
 points(take_inference('residuals, res)))$

```

## 76.4 Functions and Variables for special distributions

**pdf\_signed\_rank** ( $x, n$ ) Function  
 Probability density function of the exact distribution of the signed rank statistic. Argument  $x$  is a real number and  $n$  a positive integer.  
 See also `test_signed_rank`.

**cdf\_signed\_rank** ( $x, n$ ) Function  
 Cumulative density function of the exact distribution of the signed rank statistic. Argument  $x$  is a real number and  $n$  a positive integer.  
 See also `test_signed_rank`.



**pdf\_rank\_sum** ( $x$ ,  $n$ ,  $m$ )

Function

Probability density function of the exact distribution of the rank sum statistic. Argument  $x$  is a real number and  $n$  and  $m$  are both positive integers.

See also `test_rank_sum`.

**cdf\_rank\_sum** ( $x$ ,  $n$ ,  $m$ )

Function

Cumulative density function of the exact distribution of the rank sum statistic. Argument  $x$  is a real number and  $n$  and  $m$  are both positive integers.

See also `test_rank_sum`.



## 77 stirling

### 77.1 Functions and Variables for stirling

**stirling** (*z,n*)

Function

**stirling** (*z,n,pred*)

Function

Replace **gamma**(*x*) with the  $O(1/x^{2n-1})$  Stirling formula. when *n* isn't a nonnegative integer, signal an error. With the optional third argument **pred**, the Stirling formula is applied only when **pred** is true.

Reference: Abramowitz & Stegun, "Handbook of mathematical functions", 6.1.40.

Examples:

```
(%i1) load (stirling)$

(%i2) stirling(gamma(%alpha+x)/gamma(x),1);
 1/2 - x x + %alpha - 1/2
(%o2) x (x + %alpha)
 1 1
 ---- - ---- - %alpha
 12 (x + %alpha) 12 x
 %e

(%i3) taylor(%,x,inf,1);
 %alpha 2 %alpha
 %alpha x %alpha - x %alpha
(%o3)/T/ x + ----- + . . .
 2 x

(%i4) map('factor,%);
 %alpha (%alpha - 1) %alpha x
(%o4) x + -----
 2
 %alpha - 1
```

The function **stirling** knows the difference between the variable 'gamma' and the function gamma:

```
(%i5) stirling(gamma + gamma(x),0);
 x - 1/2 - x
(%o5) gamma + sqrt(2) sqrt(%pi) x %e
(%i6) stirling(gamma(y) + gamma(x),0);
 y - 1/2 - y
(%o6) sqrt(2) sqrt(%pi) y %e
 x - 1/2 - x
 + sqrt(2) sqrt(%pi) x %e
```

To apply the Stirling formula only to terms that involve the variable *k*, use an optional third argument; for example

```
(%i7) makegamma(pochhammer(a,k)/pochhammer(b,k));
(%o7) (gamma(b)*gamma(k+a))/(gamma(a)*gamma(k+b))
(%i8) stirling(%,1, lambda([s], not(freeof(k,s))));
(%o8) (%e^(b-a)*gamma(b)*(k+a)^(k+a-1/2)*(k+b)^(-k-b+1/2))/gamma(a)
```

The terms **gamma**(*a*) and **gamma**(*b*) are free of *k*, so the Stirling formula was not applied to these two terms.

To use this function write first **load("stirling")**.



## 78 stringproc

### 78.1 Introduction to string processing

`stringproc.lisp` enlarges Maximas capabilities of working with strings and adds some useful functions for file in/output.

For questions and bugs please mail to `van.nek at arcor.de`.

In Maxima a string is easily constructed by typing "text". `stringp` tests for strings.

```
(%i1) m: "text";
(%o1) text
(%i2) stringp(m);
(%o2) true
```

Characters are represented as strings of length 1. These are not Lisp characters. Tests can be done with `charp` (respectively `lcharp` and conversion from Lisp to Maxima characters with `cunlisp`).

```
(%i1) c: "e";
(%o1) e
(%i2) [charp(c),lcharp(c)];
(%o2) [true, false]
(%i3) supcase(c);
(%o3) E
(%i4) charp(%);
(%o4) true
```

All functions in `stringproc.lisp` that return characters, return Maxima-characters. Due to the fact, that the introduced characters are strings of length 1, you can use a lot of string functions also for characters. As seen, `supcase` is one example.

It is important to know, that the first character in a Maxima-string is at position 1. This is designed due to the fact that the first element in a Maxima-list is at position 1 too. See definitions of `charat` and `charlist` for examples.

In applications string-functions are often used when working with files. You will find some useful stream- and print-functions in `stringproc.lisp`. The following example shows some of the here introduced functions at work.

Example:

`openw` returns an output stream to a file, `printf` then allows formatted writing to this file. See `printf` for details.

```
(%i1) s: openw("E:/file.txt");
(%o1) #<output stream E:/file.txt>
(%i2) for n:0 thru 10 do printf(s, "~d ", fib(n));
(%o2) done
(%i3) printf(s, "%~d ~f ~a ~a ~f ~e ~a~%",
 42,1.234,sqrt(2),%pi,1.0e-2,1.0e-2,1.0b-2);
(%o3) false
(%i4) close(s);
(%o4) true
```

After closing the stream you can open it again, this time with input direction. `readline` returns the entire line as one string. The `stringproc` package now offers a lot of functions for manipulating strings. Tokenizing can be done by `split` or `tokens`.

```
(%i5) s: openr("E:/file.txt");
(%o5) #<input stream E:/file.txt>
(%i6) readline(s);
(%o6) 0 1 1 2 3 5 8 13 21 34 55
(%i7) line: readline(s);
(%o7) 42 1.234 sqrt(2) %pi 0.01 1.0E-2 1.0b-2
```

```
(%i8) list: tokens(line);
(%o8) [42, 1.234, sqrt(2), %pi, 0.01, 1.0E-2, 1.0b-2]
(%i9) map(parse_string, list);
(%o9) [42, 1.234, sqrt(2), %pi, 0.01, 0.01, 1.0b-2]
(%i10) float(%);
(%o10) [42.0, 1.234, 1.414213562373095, 3.141592653589793, 0.01,
0.01, 0.01]

(%i11) readline(s);
(%o11) false
(%i12) close(s)$
```

`readline` returns `false` when the end of file occurs.

## 78.2 Functions and Variables for input and output

Example:

```
(%i1) s: openw("E:/file.txt");
(%o1) #<output stream E:/file.txt>
(%i2) control:
"~2tAn atom: ~2t~a~%~2tand a list: ~2t~{~r ~}~%~2t\
and an integer: ~2t~d~%"$
(%i3) printf(s,control, 'true,[1,2,3],42)$
(%o3) false
(%i4) close(s);
(%o4) true
(%i5) s: openr("E:/file.txt");
(%o5) #<input stream E:/file.txt>
(%i6) while stringp(tmp:readline(s)) do print(tmp)$
An atom: true
and a list: one two three
and an integer: 42
(%i7) close(s)$
```

**close** (*stream*) Function  
Closes *stream* and returns `true` if *stream* had been open.

**length** (*stream*) Function  
Returns the number of elements in *stream*.

**fposition** (*stream*) Function  
**fposition** (*stream*, *pos*) Function  
Returns the current position in *stream*, if *pos* is not used. If *pos* is used, **fposition** sets the position in *stream*. *pos* has to be a positive number, the first element in *stream* is in position 1.

**freshline** () Function  
**freshline** (*stream*) Function  
Writes a new line (to *stream*), if the position is not at the beginning of a line. See also `newline`.

**newline** () Function  
**newline** (*stream*) Function  
Writes a new line (to *stream*). See `sprint` for an example of using `newline()`. Note that there are some cases, where `newline()` does not work as expected.

**opena** (*file*) Function  
Returns an output stream to *file*. If an existing file is opened, **opena** appends elements at the end of file.

**openr** (*file*) Function  
 Returns an input stream to *file*. If *file* does not exist, it will be created.

**openw** (*file*) Function  
 Returns an output stream to *file*. If *file* does not exist, it will be created. If an existing file is opened, **openw** destructively modifies *file*.

**printf** (*dest*, *string*) Function

**printf** (*dest*, *string*, *expr\_1*, ..., *expr\_n*) Function

Makes the Common Lisp function **FORMAT** available in Maxima. (From gcl.info: "format produces formatted output by outputting the characters of control-string *string* and observing that a tilde introduces a directive. The character after the tilde, possibly preceded by prefix parameters and modifiers, specifies what kind of formatting is desired. Most directives use one or more elements of *args* to create their output.")

The following description and the examples may give an idea of using **printf**. See a Lisp reference for more information.

|     |                                                 |
|-----|-------------------------------------------------|
| ~%  | new line                                        |
| ~&  | fresh line                                      |
| ~t  | tab                                             |
| ~\$ | monetary                                        |
| ~d  | decimal integer                                 |
| ~b  | binary integer                                  |
| ~o  | octal integer                                   |
| ~x  | hexadecimal integer                             |
| ~br | base-b integer                                  |
| ~r  | spell an integer                                |
| ~p  | plural                                          |
| ~f  | floating point                                  |
| ~e  | scientific notation                             |
| ~g  | ~f or ~e, depending upon magnitude              |
| ~h  | bigfloat                                        |
| ~a  | uses Maxima function string                     |
| ~s  | like ~a, but output enclosed in "double quotes" |
| ~~  | ~                                               |
| ~<  | justification, ~> terminates                    |
| ~(  | case conversion, ~) terminates                  |
| ~[  | selection, ~] terminates                        |
| ~{  | iteration, ~} terminates                        |

Note that the selection directive ~[ is zero-indexed. Also note that the directive ~\* is not supported.

```
(%i1) printf(false, "~a ~a ~4f ~a ~@r",
 "String",sym,bound,sqrt(12),144), bound = 1.234;
(%o1)
 String sym 1.23 2*sqrt(3) CXLIV
(%i2) printf(false,"~{~a ~}",["one",2,"THREE"]);
(%o2)
 one 2 THREE
(%i3) printf(true,"~{~{~9,1f ~}~%~}",mat),
 mat = args(matrix([1.1,2,3.33],[4,5,6],[7,8.88,9]))$
 1.1 2.0 3.3
 4.0 5.0 6.0
 7.0 8.9 9.0
(%i4) control: "~:(~r~) bird~p ~[is~;are~] singing."$
(%i5) printf(false,control, n,n,if n=1 then 0 else 1), n=2;
(%o5)
 Two birds are singing.
```

If *dest* is a stream or **true**, then **printf** returns **false**. Otherwise, **printf** returns a string containing the output.

**readline** (*stream*) Function  
 Returns a string containing the characters from the current position in *stream* up to the end of the line or *false* if the end of the file is encountered.

**sprint** (*expr\_1*, ..., *expr\_n*) Function  
 Evaluates and displays its arguments one after the other 'on a line' starting at the leftmost position. The numbers are printed with the '-' right next to the number, and it disregards line length. **newline()**, which will be autoloaded from **stringproc.lisp** might be useful, if you wish to place intermediate line breaking.

Example:

```
(%i1) for n:0 thru 19 do sprint(fib(n))$
0 1 1 2 3 5 8 13 21 34 55 89 144 233 377 610 987 1597 2584 4181
(%i2) for n:0 thru 22 do (
 sprint(fib(n)), if mod(n,10)=9 then newline())$
0 1 1 2 3 5 8 13 21 34
55 89 144 233 377 610 987 1597 2584 4181
6765 10946 17711
```

## 78.3 Functions and Variables for characters

**alphacharp** (*char*) Function  
 Returns **true** if *char* is an alphabetic character.

**alphanumericp** (*char*) Function  
 Returns **true** if *char* is an alphabetic character or a digit.

**ascii** (*int*) Function  
 Returns the character corresponding to the ASCII number *int*. ( -1 < int < 256 )

```
(%i1) for n from 0 thru 255 do (
 tmp: ascii(n), if alphacharp(tmp) then sprint(tmp),
 if n=96 then newline())$
A B C D E F G H I J K L M N O P Q R S T U V W X Y Z
a b c d e f g h i j k l m n o p q r s t u v w x y z
```

**cequal** (*char\_1*, *char\_2*) Function  
 Returns **true** if *char\_1* and *char\_2* are the same.

**cequalignore** (*char\_1*, *char\_2*) Function  
 Like **cequal** but ignores case.

**cgreaterp** (*char\_1*, *char\_2*) Function  
 Returns **true** if the ASCII number of *char\_1* is greater than the number of *char\_2*.

**cgreaterpignore** (*char\_1*, *char\_2*) Function  
 Like **cgreaterp** but ignores case.

**charp** (*obj*) Function  
 Returns **true** if *obj* is a Maxima-character. See introduction for example.

**cint** (*char*) Function  
 Returns the ASCII number of *char*.

**clessp** (*char\_1*, *char\_2*) Function  
 Returns **true** if the ASCII number of *char\_1* is less than the number of *char\_2*.



|                                                                                                                                                                                                                                                                                                   |          |
|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|
| <b>clesspignore</b> ( <i>char_1</i> , <i>char_2</i> )                                                                                                                                                                                                                                             | Function |
| Like <b>clessp</b> but ignores case.                                                                                                                                                                                                                                                              |          |
| <b>constituent</b> ( <i>char</i> )                                                                                                                                                                                                                                                                | Function |
| Returns <b>true</b> if <i>char</i> is a graphic character and not the space character. A graphic character is a character one can see, plus the space character. ( <b>constituent</b> is defined by Paul Graham, ANSI Common Lisp, 1996, page 67.)                                                |          |
| <pre>(%i1) for n from 0 thru 255 do ( tmp: ascii(n), if constituent(tmp) then sprint(tmp) )\$ ! " # % ' ( ) * + , - . / 0 1 2 3 4 5 6 7 8 9 : ; &lt; = &gt; ? @ A B C D E F G H I J K L M N O P Q R S T U V W X Y Z [ \ ] ^ _ ` a b c d e f g h i j k l m n o p q r s t u v w x y z {   } ~</pre> |          |
| <b>cunlisp</b> ( <i>lisp_char</i> )                                                                                                                                                                                                                                                               | Function |
| Converts a Lisp-character into a Maxima-character. (You won't need it.)                                                                                                                                                                                                                           |          |
| <b>digitcharp</b> ( <i>char</i> )                                                                                                                                                                                                                                                                 | Function |
| Returns <b>true</b> if <i>char</i> is a digit.                                                                                                                                                                                                                                                    |          |
| <b>lcharp</b> ( <i>obj</i> )                                                                                                                                                                                                                                                                      | Function |
| Returns <b>true</b> if <i>obj</i> is a Lisp-character. (You won't need it.)                                                                                                                                                                                                                       |          |
| <b>lowercasep</b> ( <i>char</i> )                                                                                                                                                                                                                                                                 | Function |
| Returns <b>true</b> if <i>char</i> is a lowercase character.                                                                                                                                                                                                                                      |          |
| <b>newline</b>                                                                                                                                                                                                                                                                                    | Variable |
| The newline character.                                                                                                                                                                                                                                                                            |          |
| <b>space</b>                                                                                                                                                                                                                                                                                      | Variable |
| The space character.                                                                                                                                                                                                                                                                              |          |
| <b>tab</b>                                                                                                                                                                                                                                                                                        | Variable |
| The tab character.                                                                                                                                                                                                                                                                                |          |
| <b>uppercasep</b> ( <i>char</i> )                                                                                                                                                                                                                                                                 | Function |
| Returns <b>true</b> if <i>char</i> is an uppercase character.                                                                                                                                                                                                                                     |          |

## 78.4 Functions and Variables for strings

|                                                                                                                           |          |
|---------------------------------------------------------------------------------------------------------------------------|----------|
| <b>stringp</b> ( <i>obj</i> )                                                                                             | Function |
| Returns <b>true</b> if <i>obj</i> is a string. See introduction for example.                                              |          |
| <b>charat</b> ( <i>string</i> , <i>n</i> )                                                                                | Function |
| Returns the <i>n</i> -th character of <i>string</i> . The first character in <i>string</i> is returned with <i>n</i> = 1. |          |
| <pre>(%i1) charat("Lisp",1); (%o1) L</pre>                                                                                |          |
| <b>charlist</b> ( <i>string</i> )                                                                                         | Function |
| Returns the list of all characters in <i>string</i> .                                                                     |          |
| <pre>(%i1) charlist("Lisp"); (%o1) [L, i, s, p] (%i2) %1; (%o2) L</pre>                                                   |          |

**eval\_string** (*str*) Function

Parse the string *str* as a Maxima expression and evaluate it. The string *str* may or may not have a terminator (dollar sign \$ or semicolon ;). Only the first expression is parsed and evaluated, if there is more than one.

Complain if *str* is not a string.

Examples:

```
(%i1) eval_string ("foo: 42; bar: foo^2 + baz");
(%o1) 42
(%i2) eval_string ("(foo: 42, bar: foo^2 + baz)");
(%o2) baz + 1764
```

See also `parse_string`.

**parse\_string** (*str*) Function

Parse the string *str* as a Maxima expression (do not evaluate it). The string *str* may or may not have a terminator (dollar sign \$ or semicolon ;). Only the first expression is parsed, if there is more than one.

Complain if *str* is not a string.

Examples:

```
(%i1) parse_string ("foo: 42; bar: foo^2 + baz");
(%o1) foo : 42
(%i2) parse_string ("(foo: 42, bar: foo^2 + baz)");
(%o2) (foo : 42, bar : foo^2 + baz)
```

See also `eval_string`.

**scopy** (*string*) Function

Returns a copy of *string* as a new string.

**sdowncase** (*string*) Function

**sdowncase** (*string*, *start*) Function

**sdowncase** (*string*, *start*, *end*) Function

Like `supcase`, but uppercase characters are converted to lowercase.

**sequal** (*string\_1*, *string\_2*) Function

Returns `true` if *string\_1* and *string\_2* are the same length and contain the same characters.

**sequalignore** (*string\_1*, *string\_2*) Function

Like `sequal` but ignores case.

**sexplode** (*string*) Function

`sexplode` is an alias for function `charlist`.

**simplode** (*list*) Function

**simplode** (*list*, *delim*) Function

`simplode` takes a list of expressions and concatenates them into a string. If no delimiter *delim* is specified, `simplode` uses no delimiter. *delim* can be any string.

```
(%i1) simplode(["xx[" , 3, "]" : " , expand((x+y)^3)]);
(%o1) xx[3]:y^3+3*x*y^2+3*x^2*y+x^3
(%i2) simplode(sexplode("stars")," * ");
(%o2) s * t * a * r * s
(%i3) simplode(["One","more","coffee."]," ");
(%o3) One more coffee.
```

- sinsert** (*seq, string, pos*) Function  
 Returns a string that is a concatenation of **substring** (*string*, 1, *pos* - 1), the string *seq* and **substring** (*string*, *pos*). Note that the first character in *string* is in position 1.
- ```
(%i1) s: "A submarine."$
(%i2) concat( substring(s,1,3),"yellow ",substring(s,3) );
(%o2)
      A yellow submarine.
(%i3) sinsert("hollow ",s,3);
(%o3)
      A hollow submarine.
```
- sinvertcase** (*string*) Function
sinvertcase (*string, start*) Function
sinvertcase (*string, start, end*) Function
 Returns *string* except that each character from position *start* to *end* is inverted. If *end* is not given, all characters from *start* to the end of *string* are replaced.
- ```
(%i1) sinvertcase("sInvertCase");
(%o1)
 SiNVERTcASE
```
- slength** (*string*) Function  
 Returns the number of characters in *string*.
- smake** (*num, char*) Function  
 Returns a new string with a number of *num* characters *char*.
- ```
(%i1) smake(3,"w");
(%o1)
      www
```
- smismatch** (*string-1, string-2*) Function
smismatch (*string-1, string-2, test*) Function
 Returns the position of the first character of *string-1* at which *string-1* and *string-2* differ or false. Default test function for matching is **sequal**. If **smismatch** should ignore case, use **sequalignore** as test.
- ```
(%i1) smismatch("seven","seventh");
(%o1)
 6
```
- split** (*string*) Function  
**split** (*string, delim*) Function  
**split** (*string, delim, multiple*) Function  
 Returns the list of all tokens in *string*. Each token is an unparsed string. **split** uses *delim* as delimiter. If *delim* is not given, the space character is the default delimiter. *multiple* is a boolean variable with **true** by default. Multiple delimiters are read as one. This is useful if tabs are saved as multiple space characters. If *multiple* is set to **false**, each delimiter is noted.
- ```
(%i1) split("1.2  2.3  3.4  4.5");
(%o1)
      [1.2, 2.3, 3.4, 4.5]
(%i2) split("first;;third;fourth",";",false);
(%o2)
      [first, , third, fourth]
```
- sposition** (*char, string*) Function
 Returns the position of the first character in *string* which matches *char*. The first character in *string* is in position 1. For matching characters ignoring case see **ssearch**.
- sremove** (*seq, string*) Function
sremove (*seq, string, test*) Function
sremove (*seq, string, test, start*) Function
sremove (*seq, string, test, start, end*) Function
 Returns a string like *string* but without all substrings matching *seq*. Default test function for matching is **sequal**. If **sremove** should ignore case while searching for *seq*, use **sequalignore** as test. Use *start* and *end* to limit searching. Note that the first character in *string* is in position 1.

```
(%i1) sremove("n't","I don't like coffee.");
(%o1)          I do like coffee.
(%i2) sremove ("D0 ",%, 'sequalignore);
(%o2)          I like coffee.
```

sremovefirst (*seq, string*) Function
sremovefirst (*seq, string, test*) Function
sremovefirst (*seq, string, test, start*) Function
sremovefirst (*seq, string, test, start, end*) Function

Like **sremove** except that only the first substring that matches **seq** is removed.

sreverse (*string*) Function
Returns a string with all the characters of *string* in reverse order.

ssearch (*seq, string*) Function
ssearch (*seq, string, test*) Function
ssearch (*seq, string, test, start*) Function
ssearch (*seq, string, test, start, end*) Function

Returns the position of the first substring of *string* that matches the string *seq*. Default test function for matching is **sequal**. If **ssearch** should ignore case, use **sequalignore** as test. Use *start* and *end* to limit searching. Note that the first character in *string* is in position 1.

```
(%i1) ssearch("~s","~{~S ~}~%", 'sequalignore);
(%o1)                                     4
```

ssort (*string*) Function
ssort (*string, test*) Function

Returns a string that contains all characters from *string* in an order such there are no two successive characters *c* and *d* such that **test** (*c, d*) is **false** and **test** (*d, c*) is **true**. Default test function for sorting is **clessp**. The set of test functions is {**clessp**, **clesspignore**, **cgreaterp**, **cgreaterpignore**, **cequal**, **cequalignore**}.

```
(%i1) ssort("I don't like Mondays.");
(%o1)          '.IMaddeiklnnoosty
(%i2) ssort("I don't like Mondays.", 'cgreaterpignore);
(%o2)          ytsoonMlkIiedda.'
```

ssubst (*new, old, string*) Function
ssubst (*new, old, string, test*) Function
ssubst (*new, old, string, test, start*) Function
ssubst (*new, old, string, test, start, end*) Function

Returns a string like *string* except that all substrings matching *old* are replaced by *new*. *old* and *new* need not to be of the same length. Default test function for matching is **sequal**. If **ssubst** should ignore case while searching for *old*, use **sequalignore** as test. Use *start* and *end* to limit searching. Note that the first character in *string* is in position 1.

```
(%i1) ssubst("like","hate","I hate Thai food. I hate green tea.");
(%o1)          I like Thai food. I like green tea.
(%i2) ssubst("Indian","thai",%, 'sequalignore,8,12);
(%o2)          I like Indian food. I like green tea.
```

ssubstfirst (*new, old, string*) Function
ssubstfirst (*new, old, string, test*) Function
ssubstfirst (*new, old, string, test, start*) Function
ssubstfirst (*new, old, string, test, start, end*) Function

Like **subst** except that only the first substring that matches *old* is replaced.

strim (*seq, string*) Function
 Returns a string like *string*, but with all characters that appear in *seq* removed from both ends.

```
(%i1) "/* comment */"$
(%i2) strim(" /*",%);
(%o2)
comment
(%i3) slength(%);
(%o3) 7
```

striml (*seq, string*) Function
 Like **strim** except that only the left end of *string* is trimmed.

strimr (*seq, string*) Function
 Like **strim** except that only the right end of *string* is trimmed.

substring (*string, start*) Function

substring (*string, start, end*) Function

Returns the substring of *string* beginning at position *start* and ending at position *end*. The character at position *end* is not included. If *end* is not given, the substring contains the rest of the string. Note that the first character in *string* is in position 1.

```
(%i1) substring("substring",4);
(%o1)
string
(%i2) substring(%,4,6);
(%o2)
in
```

supcase (*string*) Function

supcase (*string, start*) Function

supcase (*string, start, end*) Function

Returns *string* except that lowercase characters from position *start* to *end* are replaced by the corresponding uppercase ones. If *end* is not given, all lowercase characters from *start* to the end of *string* are replaced.

```
(%i1) supcase("english",1,2);
(%o1)
English
```

tokens (*string*) Function

tokens (*string, test*) Function

Returns a list of tokens, which have been extracted from *string*. The tokens are substrings whose characters satisfy a certain test function. If *test* is not given, *constituent* is used as the default test. {*constituent*, *alphacharp*, *digitcharp*, *lowercasep*, *uppercasep*, *charp*, *characterp*, *alphanumericp*} is the set of test functions. (The Lisp-version of **tokens** is written by Paul Graham. ANSI Common Lisp, 1996, page 67.)

```
(%i1) tokens("24 October 2005");
(%o1) [24, October, 2005]
(%i2) tokens("05-10-24",'digitcharp);
(%o2) [05, 10, 24]
(%i3) map(parse_string,%);
(%o3) [5, 10, 24]
```


79 to_poly_solve

79.1 Functions and Variables for to_poly_solve

The packages `to_poly` and `to_poly_solve` are experimental; the specifications of the functions in these packages might change or some of the functions in these packages might be merged into other Maxima functions.

Barton Willis (Professor of Mathematics, University of Nebraska at Kearney) wrote the `to_poly` and `to_poly_solve` packages and the English language user documentation for these packages.

`%and` Operator

The operator `%and` is a simplifying nonshort-circuited logical conjunction. Maxima simplifies an `%and` expression to either true, false, or a logically equivalent, but simplified, expression. The operator `%and` is associative, commutative, and idempotent. Thus when `%and` returns a noun form, the arguments of `%and` form a non-redundant sorted list; for example

```
(%i1) a %and (a %and b);
(%o1)                                a %and b
```

If one argument to a conjunction is the *explicit* negation of another argument, `%and` returns false:

```
(%i2) a %and (not a);
(%o2)                                false
```

If any member of the conjunction is false, the conjunction simplifies to false even if other members are manifestly non-boolean; for example

```
(%i3) 42 %and false;
(%o3)                                false
```

Any argument of an `%and` expression that is an inequation (that is, an inequality or equation), is simplified using the Fourier elimination package. The Fourier elimination simplifier has a pre-processor that converts some, but not all, nonlinear inequations into linear inequations; for example the Fourier elimination code simplifies `abs(x) + 1 > 0` to true, so

```
(%i4) (x < 1) %and (abs(x) + 1 > 0);
(%o4)                                x < 1
```

Notes

- The option variable `prederror` does *not* alter the simplification `%and` expressions.
- To avoid operator precedence errors, compound expressions involving the operators `%and`, `%or`, and `not` should be fully parenthesized.
- The Maxima operators `and` and `or` are both short-circuited. Thus `and` isn't associative or commutative.

Limitations The conjunction `%and` simplifies inequations *locally, not globally*. This means that conjunctions such as

```
(%i5) (x < 1) %and (x > 1);
(%o5)                                (x > 1) %and (x < 1)
```

do *not* simplify to false. Also, the Fourier elimination code *ignores* the fact database;

```
(%i6) assume(x > 5);
(%o6)                                [x > 5]
(%i7) (x > 1) %and (x > 2);
(%o7)                                (x > 1) %and (x > 2)
```

Finally, nonlinear inequations that aren't easily converted into an equivalent linear inequation aren't simplified.

There is no support for distributing `%and` over `%or`; neither is there support for distributing a logical negation over `%and`.

To use 'load(to_poly_solve)'

Related functions %or, %if, and, or, not

Status The operator %and is experimental; the specifications of this function might change and its functionality might be merged into other Maxima functions.

%if (*bool*, *a*, *b*) Operator

The operator %if is a simplifying conditional. The *conditional bool* should be boolean-valued. When the conditional is true, return the second argument; when the conditional is false, return the third; in all other cases, return a noun form.

Maxima inequations (either an inequality or an equality) are *not* boolean-valued; for example, Maxima does *not* simplify $5 < 6$ to true, and it does not simplify $5 = 6$ to false; however, in the context of a conditional to an %if statement, Maxima *automatically* attempts to determine the truth value of an inequation. Examples:

```
(%i1) f : %if(x # 1, 2, 8);
(%o1)                                     %if(x - 1 # 0, 2, 8)
(%i2) [subst(x = -1,f), subst(x=1,f)];
(%o2)                                     [2, 8]
```

If the conditional involves an inequation, Maxima simplifies it using the Fourier elimination package.

Notes

- If the conditional is manifestly non-boolean, Maxima returns a noun form:

```
(%i3) %if(42,1,2);
(%o3)                                     %if(42, 1, 2)
```

- The Maxima operator if is nary, the operator %if *isn't* nary.

Limitations The Fourier elimination code only simplifies nonlinear inequations that are readily convertible to an equivalent linear inequation.

To use: 'load(to_poly_solve)'

Status: The operator %if is experimental; its specifications might change and its functionality might be merged into other Maxima functions.

%or Operator

The operator %or is a simplifying nonshort-circuited logical disjunction. Maxima simplifies an %or expression to either true, false, or a logically equivalent, but simplified, expression. The operator %or is associative, commutative, and idempotent. Thus when %or returns a noun form, the arguments of %or form a non-redundant sorted list; for example

```
(%i1) a %or (a %or b);
(%o1)                                     a %or b
```

If one member of the disjunction is the *explicit* the negation of another member, %or returns true:

```
(%i2) a %or (not a);
(%o2)                                     true
```

If any member of the disjunction is true, the disjunction simplifies to true even if other members of the disjunction are manifestly non-boolean; for example

```
(%i3) 42 %or true;
(%o3)                                     true
```

Any argument of an %or expression that is an inequation (that is, an inequality or equation), is simplified using the Fourier elimination package. The Fourier elimination code simplifies $\text{abs}(x) + 1 > 0$ to true, so we have

```
(%i4) (x < 1) %or (abs(x) + 1 > 0);
(%o4)                                     true
```

Notes

- The option variable **prederror** does *not* alter the simplification of %or expressions.

- You should parenthesize compound expressions involving the operators `%and`, `%or`, and `not`; the binding powers of these operators might not match your expectations.
- The Maxima operators `and` and `or` are both short-circuited. Thus `or` isn't associative or commutative.

Limitations The conjunction `%or` simplifies inequations *locally, not globally*. This means that conjunctions such as

```
(%i1) (x < 1) %or (x >= 1);
(%o1) (x > 1) %or (x >= 1)
```

do *not* simplify to true. Further, the Fourier elimination code ignores the fact database;

```
(%i2) assume(x > 5);
(%o2)                                     [x > 5]
(%i3) (x > 1) %and (x > 2);
(%o3)                                     (x > 1) %and (x > 2)
```

Finally, nonlinear inequations that aren't easily converted into an equivalent linear inequation aren't simplified.

The algorithm that looks for terms that cannot both be false is weak; also there is no support for distributing `%or` over `%and`; neither is there support for distributing a logical negation over `%or`.

To use 'load(to_poly_solve)'

Related functions `%or`, `%if`, `and`, `or`, `not`

Status The operator `%or` is experimental; the specifications of this function might change and its functionality might be merged into other Maxima functions.

complex_number_p (x) Function

The predicate `complex_number_p` returns true if its argument is either `a + %i * b`, `a`, `%i b`, or `%i`, where `a` and `b` are either rational or floating point numbers (including big floating point); for all other inputs, `complex_number_p` returns false; for example

```
(%i1) map('complex_number_p,[2/3, 2 + 1.5 * %i, %i]);
(%o1)                                     [true, true, true]
(%i2) complex_number_p((2+%i)/(5-%i));
(%o2)                                     false
(%i3) complex_number_p(cos(5 - 2 * %i));
(%o3)                                     false
```

Related functions `isreal_p`

To use 'load(to_poly_solve)'

Status The operator `complex_number_p` is experimental; its specifications might change and its functionality might be merged into other Maxima functions.

compose_functions (l) Function

The function call `compose_functions(l)` returns a lambda form that is the *composition* of the functions in the list `l`. The functions are applied from *right* to *left*; for example

```
(%i1) compose_functions([cos, exp]);
(%o1)                                     %g151
lambda([%g151], cos(%e      ))
(%i2) %(x);
(%o2)                                     x
cos(%e )
```

When the function list is empty, return the identity function:

```
(%i3) compose_functions([]);
(%o3)                                     lambda([%g152], %g152)
(%i4) %(x);
(%o4)                                     x
```

Notes

- When Maxima determines that a list member isn't a symbol or a lambda form, `funmake` (*not* `compose_functions`) signals an error:

```
(%i5) compose_functions([a < b]);

funmake: first argument must be a symbol, subscripted symbol,
string, or lambda expression; found: a < b
#0: compose_functions(l=[a < b])(to_poly_solve.mac line 40)
-- an error. To debug this try: debugmode(true);
```

- To avoid name conflicts, the independent variable is determined by the function `new_variable`.

```
(%i6) compose_functions([%g0]);
(%o6)          lambda([%g154], %g0(%g154))
(%i7) compose_functions([%g0]);
(%o7)          lambda([%g155], %g0(%g155))
```

Although the independent variables are different, Maxima is able to deduce that these lambda forms are semantically equal:

```
(%i8) is(equal(%o6,%o7));
(%o8)                                     true
```

To use 'load(to_poly_solve)'

Status The function `compose_functions` is experimental; its specifications might change and its functionality might be merged into other Maxima functions.

dfloat (*x*) Function

The function `dfloat` is similar to `float`, but the function `dfloat` applies `rectform` when `float` fails to evaluate to an IEEE double floating point number; thus

```
(%i1) float(4.5^(1 + %i));
                                     %i + 1
(%o1)                                     4.5
(%i2) dfloat(4.5^(1 + %i));
(%o2) 4.48998802962884 %i + .3000124893895671
```

Notes

- The rectangular form of an expression might be poorly suited for numerical evaluation—for example, the rectangular form might needlessly involve the difference of floating point numbers (subtractive cancellation).
- The identifier `float` is both an option variable (default value false) and a function name.

Related functions `float`, `bfloat`

To use 'load(to_poly_solve)'

Status The function `dfloat` is experimental; its specifications might change and its functionality might be merged into other Maxima functions.

elim (*l*, *x*) Function

The function `elim` eliminates the variables in the set or list *x* from the equations in the set or list *l*. Each member of *x* must be a symbol; the members of *l* can either be equations, or expressions that are assumed to equal zero.

The function `elim` returns a list of two lists; the first is the list of expressions with the variables eliminated; the second is the list of pivots; thus, the second list is a list of expressions that `elim` used to eliminate the variables.

Here is an example of eliminating between linear equations:

```
(%i1) elim(set(x + y + z = 1, x - y - z = 8, x - z = 1),
          set(x,y));
(%o1) [[2 z - 7], [y + 7, z - x + 1]]
```

Eliminating *x* and *y* yields the single equation $2z - 7 = 0$; the equations $y + 7 = 0$ and $z - z + 1 = 1$ were used as pivots. Eliminating all three variables from these equations, triangularizes the linear system:

```
(%i2) elim(set(x + y + z = 1, x - y - z = 8, x - z = 1),
          set(x,y,z));
```

```
(%o2)      [[], [2 z - 7, y + 7, z - x + 1]]
```

Of course, the equations needn't be linear:

```
(%i3) elim(set(x^2 - 2 * y^3 = 1, x - y = 5), [x,y]);
```

```
(%o3)      [[], [2 y^3 - y^2 - 10 y - 24, y - x + 5]]
```

The user doesn't control the order the variables are eliminated. Instead, the algorithm uses a heuristic to *attempt* to choose the best pivot and the best elimination order.

Notes

- Unlike the related function `eliminate`, the function `elim` does *not* invoke `solve` when the number of equations equals the number of variables.
- The function `elim` works by applying resultants; the option variable `resultant` determines which algorithm Maxima uses. Using `sqfr`, Maxima factors each resultant and suppresses multiple zeros.
- The `elim` will triangularize a nonlinear set of polynomial equations; the solution set of the triangularized set *can* be larger than that solution set of the untriangularized set. Thus, the triangularized equations can have *spurious* solutions.

Related functions `elim_allbut`, `eliminate_using`, `eliminate`

Option variables `resultant`

To use 'load(to_poly)'

Status The function `elim` is experimental; its specifications might change and its functionality might be merged into other Maxima functions.

elim_allbut (*l*, *x*) Function

This function is similar to `elim`, except that it eliminates all the variables in the list of equations *l* *except* for those variables that in in the list *x*

```
(%i1) elim_allbut([x+y = 1, x - 5*y = 1],[]);
```

```
(%o1)      [[], [y, y + x - 1]]
```

```
(%i2) elim_allbut([x+y = 1, x - 5*y = 1],[x]);
```

```
(%o2)      [[x - 1], [y + x - 1]]
```

To use 'load(to_poly)'

Option variables `resultant`

Related functions `elim`, `eliminate_using`, `eliminate`

Status The function `elim_allbut` is experimental; its specifications might change and its functionality might be merged into other Maxima functions.

eliminate_using (*l*, *e*, *x*) Function

Using *e* as the pivot, eliminate the symbol *x* from the list or set of equations in *l*. The function `eliminate_using` returns a set.

```
(%i1) eq : [x^2 - y^2 - z^3, x*y - z^2 - 5, x - y + z];
```

```
(%o1)      [- z^3 - y^2 + x, - z^2 + x y - 5, z - y + x]
```

```
(%i2) eliminate_using(eq,first(eq),z);
```

```
(%o2) {y^3 + (1 - 3 x) y^2 + 3 x^2 y - x^3 - x^2,
      y^4 - x^4 y^2 + 13 x^3 y^2 - 75 x^2 y^2 + x^4 + 125}
```

```
(%i3) eliminate_using(eq,second(eq),z);
```

```
(%o3) {y^2 - 3 x y + x^2 + 5, y^4 - x^4 y^2 + 13 x^3 y^2 - 75 x^2 y^2 + x^4 + 125}
```

```
(%i4) eliminate_using(eq, third(eq),z);
```

```
(%o4) {y2 - 3 x y + x2 + 5, y3 + (1 - 3 x) y2 + 3 x2 y - x3 - x2}
```

Option variables *resultant*

Related functions *elim, eliminate, elim_allbut*

To use 'load(to_poly)'

Status The function `eliminate_using` is experimental; its specifications might change and its functionality might be merged into other Maxima functions.

fourier_elim ([eq1, eq2, ...], [var1, var, ...]) Function

Fourier elimination is the analog of Gauss elimination for linear inequations (equations or inequalities). The function call `fourier_elim([eq1, eq2, ...], [var1, var2, ...])` does Fourier elimination on a list of linear inequations [eq1, eq2, ...] with respect to the variables [var1, var2, ...]; for example

```
(%i1) fourier_elim([y-x < 5, x - y < 7, 10 < y],[x,y]);
(%o1) [y - 5 < x, x < y + 7, 10 < y]
(%i2) fourier_elim([y-x < 5, x - y < 7, 10 < y],[y,x]);
(%o2) [max(10, x - 7) < y, y < x + 5, 5 < x]
```

Eliminating first with respect to x and second with respect to y yields lower and upper bounds for x that depend on y , and lower and upper bounds for y that are numbers. Eliminating in the other order gives x dependent lower and upper bounds for y , and numerical lower and upper bounds for x .

When necessary, `fourier_elim` returns a *disjunction* of lists of inequations:

```
(%i3) fourier_elim([x # 6],[x]);
(%o3) [x < 6] or [6 < x]
```

When the solution set is empty, `fourier_elim` returns `emptyset`, and when the solution set is all reals, `fourier_elim` returns `universalset`; for example

```
(%i4) fourier_elim([x < 1, x > 1],[x]);
(%o4) emptyset
(%i5) fourier_elim([minf < x, x < inf],[x]);
(%o5) universalset
```

For nonlinear inequations, `fourier_elim` returns a (somewhat) simplified list of inequations:

```
(%i6) fourier_elim([x^3 - 1 > 0],[x]);
(%o6) [1 < x, x2 + x + 1 > 0] or [x < 1, -(x2 + x + 1) > 0]
(%i7) fourier_elim([cos(x) < 1/2],[x]);
(%o7) [1 - 2 cos(x) > 0]
```

Instead of a list of inequations, the first argument to `fourier_elim` may be a logical disjunction or conjunction:

```
(%i8) fourier_elim((x + y < 5) and (x - y > 8),[x,y]);
(%o8) [y + 8 < x, x < 5 - y, y < -3 - 2]
(%i9) fourier_elim(((x + y < 5) and x < 1) or (x - y > 8),[x,y]);
(%o9) [y + 8 < x] or [x < min(1, 5 - y)]
```

The function `fourier_elim` supports the inequation operators `<`, `<=`, `>`, `>=`, `#`, and `=`.

The Fourier elimination code has a preprocessor that converts some nonlinear inequations that involve the absolute value, minimum, and maximum functions into linear inequations. Additionally, the preprocessor handles some expressions that are the product or quotient of linear terms:

```
(%i10) fourier_elim([max(x,y) > 6, x # 8, abs(y-1) > 12],[x,y]);
(%o10) [6 < x, x < 8, y < - 11] or [8 < x, y < - 11]
or [x < 8, 13 < y] or [x = y, 13 < y] or [8 < x, x < y, 13 < y]
or [y < x, 13 < y]
```

```
(%i11) fourier_elim([(x+6)/(x-9) <= 6],[x]);
(%o11)      [x = 12] or [12 < x] or [x < 9]
(%i12) fourier_elim([x^2 - 1 # 0],[x]);
(%o12)      [- 1 < x, x < 1] or [1 < x] or [x < - 1]
```

To use 'load(fourier_elim)'

isreal_p (e)

Function

The predicate `isreal_p` returns true when Maxima is able to determine that `e` is real-valued on the *entire* real line; it returns false when Maxima is able to determine that `e` *isn't* real-valued on some nonempty subset of the real line; and it returns a noun form for all other cases.

```
(%i1) map('isreal_p, [-1, 0, %i, %pi]);
(%o1)      [true, true, false, true]
```

Maxima variables are assumed to be real; thus

```
(%i2) isreal_p(x);
(%o2)      true
```

The function `isreal_p` examines the fact database:

```
(%i3) declare(z,complex)$

(%i4) isreal_p(z);
(%o4)      isreal_p(z)
```

Limitations Too often, `isreal_p` returns a noun form when it should be able to return false; a simple example: the logarithm function isn't real-valued on the entire real line, so `isreal_p(log(x))` should return false; however

```
(%i5) isreal_p(log(x));
(%o5)      isreal_p(log(x))
```

To use 'load(to_poly_solve)'

Related functions `complex_number_p`

Status The function `real_p` is experimental; its specifications might change and its functionality might be merged into other Maxima functions.

new_variable (type)

Function

Return a unique symbol of the form `%[z,n,r,c,g]k`, where `k` is an integer. The allowed values for `type` are *integer*, *natural_number*, *real*, *natural_number*, and *general*. (By natural number, we mean the *nonnegative integers*; thus zero is a natural number. Some, but not all, definitions of natural number *exclude* zero.)

When `type` isn't one of the allowed values, `type` defaults to *general*. For integers, natural numbers, and complex numbers, Maxima automatically appends this information to the fact database.

```
(%i1) map('new_variable,
        ['integer, 'natural_number, 'real, 'complex, 'general]);
(%o1)      [%z144, %n145, %r146, %c147, %g148]
(%i2) nicedummies(%);
(%o2)      [%z0, %n0, %r0, %c0, %g0]
(%i3) featurep(%z0, 'integer);
(%o3)      true
(%i4) featurep(%n0, 'integer);
(%o4)      true
(%i5) is(%n0 >= 0);
(%o5)      true
(%i6) featurep(%c0, 'complex);
(%o6)      true
```

Note Generally, the argument to `new_variable` should be quoted. The quote will protect against errors similar to

```
(%i7) integer : 12$

(%i8) new_variable(integer);
(%o8)                                     %g149
(%i9) new_variable('integer);
(%o9)                                     %z150
```

Related functions *nicedummies*

To use 'load(to_poly_solve)'

Status The function `new_variable` is experimental; its specifications might change and its functionality might be merged into other Maxima functions.

nicedummies

Function

Starting with zero, the function `nicedummies` re-indexes the variables in an expression that were introduced by `new_variable`;

```
(%i1) new_variable('integer) + 52 * new_variable('integer);
(%o1)                                     52 %z136 + %z135
(%i2) new_variable('integer) - new_variable('integer);
(%o2)                                     %z137 - %z138
(%i3) nice_dummies(%);
(%o3)                                     %z0 - %z1
```

Related functions *new_variable*

To use 'load(to_poly_solve)'

Status The function `nicedummies` is experimental; its specifications might change and its functionality might be merged into other Maxima functions.

parg (x)

Function

The function `parg` is a simplifying version of the complex argument function `carg`; thus

```
(%i1) map('parg, [1, 1+%i, %i, -1 + %i, -1]);
(%o1)                                     %pi %pi 3 %pi
[0, ---, ---, ----, %pi]
      4    2    4
```

Generally, for a non-constant input, `parg` returns a noun form; thus

```
(%i2) parg(x + %i * sqrt(x));
(%o2)                                     parg(x + %i sqrt(x))
```

When `sign` can determine that the input is a positive or negative real number, `parg` will return a non-noun form for a non-constant input. Here are two examples:

```
(%i3) parg(abs(x));
(%o3) 0
(%i4) parg(-x^2-1);
(%o4)                                     %pi
```

Note The `sign` function mostly ignores the variables that are declared to be complex (`declare(x, complex)`); for variables that are declared to be complex, the `parg` can return incorrect values; for example

```
(%i1) declare(x, complex)$

(%i2) parg(x^2 + 1);
(%o2) 0
```

Related function *carg, isreal_p*

To use 'load(to_poly_solve)'

Status The function `parg` is experimental; its specifications might change and its functionality might be merged into other Maxima functions.

real_imagpart_to_conjugate (e)

Function

The function `real_imagpart_to_conjugate` replaces all occurrences of `realpart` and `imagpart` to algebraically equivalent expressions involving the `conjugate`.

```
(%i1) declare(x, complex)$

(%i2) real_imagpart_to_conjugate(realpart(x) + imagpart(x) = 3);
      conjugate(x) + x  %i (x - conjugate(x))
(%o2)  ----- - ----- = 3
          2              2
```

To use 'load(to_poly_solve)'

Status The function `real_imagpart_to_conjugate` is experimental; its specifications might change and its functionality might be merged into other Maxima functions.

rectform_log_if_constant (e)

Function

The function `rectform_log_if_constant` converts all terms of the form `log(c)` to `rectform(log(c))`, where `c` is either a declared constant expression or explicitly declared constant

```
(%i1) rectform_log_if_constant(log(1-%i) - log(x - %i));
      log(2)  %i %pi
(%o1)  - log(x - %i) + ----- - -----
                      2      4

(%i2) declare(a,constant, b,constant)$

(%i3) rectform_log_if_constant(log(a + %i*b));
      2      2
      log(b  + a )
(%o3)  ----- + %i atan2(b, a)
          2
```

To use 'load(to_poly_solve)'

Status The function `rectform_log_if_constant` is experimental; the specifications of this function might change and its functionality might be merged into other Maxima functions.

simp_inequality (e)

Function

The function `simp_inequality` applies some simplifications to conjunctions and disjunctions of inequations.

Limitations The function `simp_inequality` is limited in at least two ways; first, the simplifications are local; thus

```
(%i1) simp_inequality((x > minf) %and (x < 0));
(%o1) (x>1) %and (x<1)
```

And second, `simp_inequality` doesn't consult the fact database:

```
(%i2) assume(x > 0)$

(%i3) simp_inequality(x > 0);
(%o3) x > 0
```

To use 'load(fourier_elim)'

Status The function `simp_inequality` is experimental; its specifications might change and its functionality might be merged into other Maxima functions.

standardize_inverse_trig (e)

Function

This function applies the identities `cot(x) = atan(1/x)`, `acsc(x) = asin(1/x)`, and similarly for `asec`, `acoth`, `acsch` and `asech` to an expression. See Abramowitz and Stegun, Eqs. 4.4.6 through 4.4.8 and 4.6.4 through 4.6.6.

To use 'load(to_poly_solve)'

Status The function `standardize_inverse_trig` is experimental; its specifications might change and its functionality might be merged into other Maxima functions.

subst_parallel (*l*, *e*)

Function

When *l* is a single equation or a list of equations, substitute the right hand side of each equation for the left hand side. The substitutions are made in parallel; for example

```
(%i1) load(to_poly_solve)$

(%i2) subst_parallel([x=y,y=x], [x,y]);
(%o2) [y, x]
```

Compare this to substitutions made serially:

```
(%i3) subst([x=y,y=x], [x,y]);
(%o3) [x, x]
```

The function **subst_parallel** is similar to **sublis** except that **subst_parallel** allows for substitution of nonatoms; for example

```
(%i4) subst_parallel([x^2 = a, y = b], x^2 * y);
(%o4) a b
(%i5) sublis([x^2 = a, y = b], x^2 * y);
```

2

```
sublis: left-hand side of equation must be a symbol; found: x
-- an error. To debug this try: debugmode(true);
```

The substitutions made by **subst_parallel** are literal, not semantic; thus **subst_parallel** *does not* recognize that $x * y$ is a subexpression of $x^2 * y$

```
(%i6) subst_parallel([x * y = a], x^2 * y);
(%o6) x y
```

The function **subst_parallel** completes all substitutions *before* simplifications. This allows for substitutions into conditional expressions where errors might occur if the simplifications were made earlier:

```
(%i7) subst_parallel([x = 0], %if(x < 1, 5, log(x)));
(%o7) 5
(%i8) subst([x = 0], %if(x < 1, 5, log(x)));
```

```
log: encountered log(0).
```

```
-- an error. To debug this try: debugmode(true);
```

Related functions *subst*, *sublis*, *ratsubst*

To use 'load(to_poly_solve_extra.lisp)'

Status The function **subst_parallel** is experimental; the specifications of this function might change might change and its functionality might be merged into other Maxima functions.

to_poly (*e*, *l*)

Function

The function **to_poly** attempts to convert the equation *e* into a polynomial system along with inequality constraints; the solutions to the polynomial system that satisfy the constraints are solutions to the equation *e*. Informally, **to_poly** attempts to polynomialize the equation *e*; an example might clarify:

```
(%i1) load(to_poly_solve)$

(%i2) to_poly(sqrt(x) = 3, [x]);
(%o2) [[%g130 - 3, x = %g130^2],
      [%pi <= parg(%g130), parg(%g130) <= %pi], []]
```

The conditions $-\pi/2 < \text{parg}(\%g130), \text{parg}(\%g130) \leq \pi/2$ tell us that $\%g130$ is in the range of the square root function. When this is true, the solution set to $\text{sqrt}(x) = 3$ is the same as the solution set to $\%g130 - 3, x = \%g130^2$.

To polynomialize trigonometric expressions, it is necessary to introduce a non algebraic substitution; these non algebraic substitutions are returned in the third list returned by `to_poly`; for example

```
(%i3) to_poly(cos(x), [x]);
                2                                %i x
(%o3)  [[%g131 + 1], [2 %g131 # 0], [%g131 = %e    ]]
```

Constant terms aren't polynomialized unless the number one is a member of the variable list; for example

```
(%i4) to_poly(x = sqrt(5), [x]);
(%o4)  [[x - sqrt(5)], [], []]
(%i5) to_poly(x = sqrt(5), [1, x]);
                2
(%o5)  [[x - %g132, 5 = %g132 ],
        %pi
        [- --- < parg(%g132), parg(%g132) <= ---], []]
        2                                2
```

To generate a polynomial with $\sqrt{5} + \sqrt{7}$ as one of its roots, use the commands

```
(%i6) first(elim_allbut(first(to_poly(x = sqrt(5) + sqrt(7),
                                [1, x])), [x]));
                4      2
(%o6)  [x - 24 x + 4]
```

Related functions *to_poly_solve*

To use 'load(to_poly)'

Status: The function `to_poly` is experimental; its specifications might change and its functionality might be merged into other Maxima functions.

to_poly_solve (*e*, *l*, [*options*]) Function

The function `to_poly_solve` tries to solve the equations *e* for the variables *l*. The equation(s) *e* can either be a single expression or a set or list of expressions; similarly, *l* can either be a single symbol or a list of set of symbols. When a member of *e* isn't explicitly an equation, for example $x^2 - 1$, the solver assumes that the expression vanishes.

The basic strategy of `to_poly_solve` is use `to_poly` to convert the input into a polynomial form and call `algsys` on the polynomial system. Thus user options that affect `algsys`, especially `algexact`, also affect `to_poly_solve`. The default for `algexact` is false, but for `to_poly_solve`, generally `algexact` should be true. The function `to_poly_solve` does not locally set `algexact` to true because this would make it impossible to find approximate solutions when the `algsys` is unable to determine an exact solution.

When `to_poly_solve` is able to determine the solution set, each member of the solution set is a list in a %union object:

```
(%i1) load(to_poly_solve)$

(%i2) to_poly_solve(x*(x-1) = 0, x);
(%o2) %union([x = 0], [x = 1])
```

When `to_poly_solve` is *unable* to determine the solution set, a %solve nounform is returned (in this case, a warning is printed)

```
(%i3) to_poly_solve(x^k + 2*x + 1 = 0, x);
```

```
Nonalgebraic argument given to 'to_poly'
unable to solve
```

```
                k
(%o3) %solve([x + 2 x + 1 = 0], [x])
```

Substitution into a %solve nounform can sometimes result in the solution

```
(%i4) subst(k = 2, %);
(%o4) %union([x = - 1])
```

Especially for trigonometric equations, the solver sometimes needs to introduce an arbitrary integer. These arbitrary integers have the form %zXXX, where XXX is an integer; for example

```
(%i5) to_poly_solve(sin(x) = 0, x);
(%o5) %union([x = 2 %pi %z33 + %pi], [x = 2 %pi %z35])
```

To re-index these variables to zero, use `nicedummies`:

```
(%i6) niceDummies(%);
(%o6) %union([x = 2 %pi %z0 + %pi], [x = 2 %pi %z1])
```

Occasionally, the solver introduces an arbitrary complex number of the form %cXXX or an arbitrary real number of the form %rXXX. The function `nicedummies` will re-index these identifiers to zero.

The solution set sometimes involves simplifying versions of various of logical operators including %and, %or, or %if for conjunction, disjunction, and implication, respectively; for example

```
(%i7) sol : to_poly_solve(abs(x) = a, x);
(%o7) %union(%if(isnonnegative_p(a), [x = - a], %union()),
             %if(isnonnegative_p(a), [x = a], %union()))
(%i8) subst(a = 42, sol);
(%o8) %union([x = - 42], [x = 42])
(%i9) subst(a = -42, sol);
(%o9) %union()
```

The empty set is represented by %union.

The function `to_poly_solve` is able to solve some, but not all, equations involving rational powers, some nonrational powers, absolute values, trigonometric functions, and minimum and maximum. Also, some it can solve some equations that are solvable in terms of the Lambert W function; some examples:

```
(%i1) load(to_poly_solve)$

(%i2) to_poly_solve(set(max(x,y) = 5, x+y = 2), set(x,y));
(%o2) %union([x = - 3, y = 5], [x = 5, y = - 3])
(%i3) to_poly_solve(abs(1-abs(1-x)) = 10,x);
(%o3) %union([x = - 10], [x = 12])
(%i4) to_poly_solve(set(sqrt(x) + sqrt(y) = 5, x + y = 10),
                    set(x,y));
(%o4) %union([x = -  $\frac{5^{3/2} \sqrt{-10}}{2}$ , y =  $\frac{5^{3/2} \sqrt{10}}{2}$ ],
              [x =  $\frac{5^{3/2} \sqrt{10}}{2}$ , y =  $-\frac{5^{3/2} \sqrt{-10}}{2}$ ])
(%i5) to_poly_solve(cos(x) * sin(x) = 1/2,x,
                    'simpfuncs = ['expand, 'nicedummies]);
(%o5) %union([x = %pi %z0 +  $\frac{\pi}{4}$ ])
(%i6) to_poly_solve(x^(2*a) + x^a + 1,x);
(%o6) %union([x =  $\frac{(\sqrt{3} \sqrt{-1})^{1/a} e^{2 \pi i \sqrt{81} a}}{2^{1/a}}$ ],
```

$$[x = \frac{(-\sqrt{3})^i - 1}{\frac{1/a}{2}} \frac{e^{2i\pi/z83}}{a}}]$$

```
(%i7) to_poly_solve(x * exp(x) = a, x);
(%o7) %union([x = lambert_w(a)])
```

For *linear* inequalities, `to_poly_solve` automatically does Fourier elimination:

```
(%i8) to_poly_solve([x + y < 1, x - y >= 8], [x,y]);
(%o8) %union([x = y + 8, y < -7/2],
             [y + 8 < x, x < 1 - y, y < -7/2])
```

Each optional argument to `to_poly_solve` must be an equation; generally, the order of these options does not matter.

- `simpfuncs = 1`, where `1` is a list of functions. Apply the composition of the members of `1` to each solution.

```
(%i1) to_poly_solve(x^2=%i,x);
(%o1) %union([x = -(-1)^(1/4)], [x = (-1)^(1/4)])
(%i2) to_poly_solve(x^2=%i,x, 'simpfuncs = ['rectform]);
(%o2) %union([x = -sqrt(2)/sqrt(2) - sqrt(2)/sqrt(2)], [x = sqrt(2)/sqrt(2) + sqrt(2)/sqrt(2)])
```

Sometimes additional simplification can revert a simplification; for example

```
(%i3) to_poly_solve(x^2=1,x);
(%o3) %union([x = -1], [x = 1])
(%i4) to_poly_solve(x^2= 1,x, 'simpfuncs = [polarform]);
(%o4) %union([x = 1], [x = e^(i*pi)])
```

Maxima doesn't try to check that each member of the function list `1` is purely a simplification; thus

```
(%i5) to_poly_solve(x^2 = %i,x, 'simpfuncs = [lambda([s],s^2)]);
(%o5) %union([x = %i])
```

To convert each solution to a double float, use `simpfunc = ['dfloat]`:

```
(%i6) to_poly_solve(x^3 + x + 1 = 0,x,
                  'simpfuncs = ['dfloat]), algexact : true;
(%o6) %union([x = -.6823278038280178],
             [x = .3411639019140089 - 1.161541399997251 %i],
             [x = 1.161541399997251 %i + .3411639019140089])
```

- `use_grobner = true` With this option, the function `poly_reduced_grobner` is applied to the equations before attempting their solution. Primarily, this option provides a workaround for weakness in the function `algsys`. Here is an example of such a workaround:

```
(%i7) to_poly_solve([x^2+y^2=2^2,(x-1)^2+(y-1)^2=2^2],[x,y],
                  'use_grobner = true);
(%o7) %union([x = -sqrt(7)/2 - 1, y = sqrt(7)/2],
             [x = sqrt(7)/2 + 1, y = -sqrt(7)/2])
```

```

                                [x = -----, y = - -----])
                                2                2
(%i8) to_poly_solve([x^2+y^2=2^2, (x-1)^2+(y-1)^2=2^2], [x,y]);
(%o8)                                %union()
• maxdepth = k, where k is a positive integer. This function controls the maximum
  recursion depth for the solver. The default value for maxdepth is five. When the
  recursions depth is exceeded, the solver signals an error:
  (%i9) to_poly_solve(cos(x) = x, x, 'maxdepth = 2);

  Unable to solve
  Unable to solve
  (%o9)                                %solve([cos(x) = x], [x], maxdepth = 2)
• parameters = l, where l is a list of symbols. The solver attempts to return a solution
  that is valid for all members of the list l; for example:
  (%i10) to_poly_solve(a * x = x, x);
  (%o10)                                %union([x = 0])
  (%i11) to_poly_solve(a * x = x, x, 'parameters = [a]);
  (%o11) %union(%if(a - 1 = 0, [x = %c111], %union()),
                                %if(a - 1 # 0, [x = 0], %union()))

```

In (%o2), the solver introduced a dummy variable; to re-index the these dummy variables, use the function `nicedummies`:

```

(%i12) nice_dummies(%);
(%o12) %union(%if(a - 1 = 0, [x = %c0], %union()),
                                %if(a - 1 # 0, [x = 0], %union()))

```

The `to_poly_solve` uses data stored in the hashed array `one_to_one_reduce` to solve equations of the form $f(a) = f(b)$. The assignment `one_to_one_reduce['f,'f] : lambda([a,b], a=b)` tells `to_poly_solve` that the solution set of $f(a) = f(b)$ equals the solution set of $a = b$; for example

```

(%i13) one_to_one_reduce['f,'f] : lambda([a,b], a=b)$

(%i14) to_poly_solve(f(x^2-1) = f(0), x);
(%o14)                                %union([x = - 1], [x = 1])

```

More generally, the assignment `one_to_one_reduce['f,'g] : lambda([a,b], w(a, b) = 0)` tells `to_poly_solve` that the solution set of $f(a) = f(b)$ equals the solution set of $w(a, b) = 0$; for example

```

(%i15) one_to_one_reduce['f,'g] : lambda([a,b], a = 1 + b/2)$

(%i16) to_poly_solve(f(x) - g(x), x);
(%o16)                                %union([x = 2])

```

Additionally, the function `to_poly_solve` uses data stored in the hashed array `function_inverse` to solve equations of the form $f(a) = b$. The assignment `function_inverse['f] : lambda([s], g(s))` informs `to_poly_solve` that the solution set to $f(x) = b$ equals the solution set to $x = g(b)$; two examples:

```

(%i17) function_inverse['Q] : lambda([s], P(s))$

(%i18) to_poly_solve(Q(x-1) = 2009, x);
(%o18)                                %union([x = P(2009) + 1])
(%i19) function_inverse['G] : lambda([s], s+new_variable(integer));
(%o19)                                lambda([s], s + new_variable(integer))
(%i20) to_poly_solve(G(x - a) = b, x);
(%o20)                                %union([x = b + a + %z125])

```

Notes

The solve variables needn't be symbols; when `fullratsubst` is able to appropriately make substitutions, the solve variables can be nonsymbols:

```
(%i1) to_poly_solve([x^2 + y^2 + x * y = 5, x * y = 8],
                    [x^2 + y^2, x * y]);
```

```
(%o1) %union([x y = 8, y^2 + x^2 = - 3])
```

For equations that involve complex conjugates, the solver automatically appends the conjugate equations; for example

```
(%i1) declare(x,complex)$
```

```
(%i2) to_poly_solve(x + (5 + %i) * conjugate(x) = 1, x);
```

```
(%o2) %union([x = - ----])
                25 %i - 125
```

```
(%i3) declare(y,complex)$
```

```
(%i4) to_poly_solve(set(conjugate(x) - y = 42 + %i,
                        x + conjugate(y) = 0), set(x,y));
```

```
(%o4) %union([x = - ----, y = - ----])
                2                2
```

For an equation that involves the absolute value function, the `to_poly_solve` consults the fact database to decide if the argument to the absolute value is complex valued. When

```
(%i1) to_poly_solve(abs(x) = 6, x);
```

```
(%o1) %union([x = - 6], [x = 6])
```

```
(%i2) declare(z,complex)$
```

```
(%i3) to_poly_solve(abs(z) = 6, z);
```

```
(%o3) %union(%if((%c11 # 0) %and (%c11 conjugate(%c11) - 36 =
                                0), [z = %c11], %union()))
```

This is the only situation that the solver consults the fact database. If a solve variable is declared to be an integer, for example, `to_poly_solve` ignores this declaration.

Relevant option variables *algexact, resultant, algebraic*

Related functions *to_poly*

To use 'load(to_poly_solve)'

Status: The function `to_poly_solve` is experimental; its specifications might change and its functionality might be merged into other Maxima functions.

80 unit

80.1 Introduction to Units

The *unit* package enables the user to convert between arbitrary units and work with dimensions in equations. The functioning of this package is radically different from the original Maxima units package - whereas the original was a basic list of definitions, this package uses rulesets to allow the user to chose, on a per dimension basis, what unit final answers should be rendered in. It will separate units instead of intermixing them in the display, allowing the user to readily identify the units associated with a particular answer. It will allow a user to simplify an expression to its fundamental Base Units, as well as providing fine control over simplifying to derived units. Dimensional analysis is possible, and a variety of tools are available to manage conversion and simplification options. In addition to customizable automatic conversion, *units* also provides a traditional manual conversion option.

Note - when unit conversions are inexact Maxima will make approximations resulting in fractions. This is a consequence of the techniques used to simplify units. The messages warning of this type of substitution are disabled by default in the case of units (normally they are on) since this situation occurs frequently and the warnings clutter the output. (The existing state of ratprint is restored after unit conversions, so user changes to that setting will be preserved otherwise.) If the user needs this information for units, they can set *unitverbose:on* to reactivate the printing of warnings from the unit conversion process.

unit is included in Maxima in the share/contrib/unit directory. It obeys normal Maxima package loading conventions:

```
(%i1) load("unit")$
*****
*                               Units version 0.50                               *
*          Definitions based on the NIST Reference on                               *
*          Constants, Units, and Uncertainty                                       *
*          Conversion factors from various sources including                       *
*          NIST and the GNU units package                                         *
*****

Redefining necessary functions...
WARNING: DEFUN/DEFMACRO: redefining function TOPLEVEL-MACSYMA-EVAL ...
WARNING: DEFUN/DEFMACRO: redefining function MSETCHK ...
WARNING: DEFUN/DEFMACRO: redefining function KILL1 ...
WARNING: DEFUN/DEFMACRO: redefining function NFORMAT ...
Initializing unit arrays...
Done.
```

The WARNING messages are expected and not a cause for concern - they indicate the *unit* package is redefining functions already defined in Maxima proper. This is necessary in order to properly handle units. The user should be aware that if other changes have been made to these functions by other packages those changes will be overwritten by this loading process.

The *unit.mac* file also loads a lisp file *unit-functions.lisp* which contains the lisp functions needed for the package.

Clifford Yapp is the primary author. He has received valuable assistance from Barton Willis of the University of Nebraska at Kearney (UNK), Robert Dodier, and other intrepid folk of the Maxima mailing list.

There are probably lots of bugs. Let me know. *float* and *numer* don't do what is expected.

TODO : dimension functionality, handling of temperature, showabbr and friends. Show examples with addition of quantities containing units.

80.2 Functions and Variables for Units

setunits (*list*)

Function

By default, the *unit* package does not use any derived dimensions, but will convert all units to the seven fundamental dimensions using MKS units.

```
(%i2) N;
(%o2) 
$$\frac{\text{kg m}}{\text{s}^2}$$

(%i3) dyn;
(%o3) 
$$\frac{1}{100000} \frac{\text{kg m}}{\text{s}^2}$$

(%i4) g;
(%o4) 
$$\frac{1}{1000} (\text{kg})$$

(%i5) centigram*inch/minutes^2;
(%o5) 
$$\frac{127}{1800000000000} \frac{\text{kg m}}{\text{s}^2}$$

```

In some cases this is the desired behavior. If the user wishes to use other units, this is achieved with the **setunits** command:

```
(%i6) setunits([centigram,inch,minute]);
(%o6) done
(%i7) N;
(%o7) 
$$\frac{1800000000000}{127} \frac{\%in \text{ cg}}{\%min^2}$$

(%i8) dyn;
(%o8) 
$$\frac{18000000}{127} \frac{\%in \text{ cg}}{\%min^2}$$

(%i9) g;
(%o9) (100) (cg)
(%i10) centigram*inch/minutes^2;
(%o10) 
$$\frac{\%in \text{ cg}}{\%min^2}$$

```

The setting of units is quite flexible. For example, if we want to get back to kilograms, meters, and seconds as defaults for those dimensions we can do:

```
(%i11) setunits([kg,m,s]);
(%o11) done
(%i12) centigram*inch/minutes^2;
(%o12) 
$$\frac{127}{1800000000000} \frac{\text{kg m}}{\text{s}^2}$$

```

Derived units are also handled by this command:


```
(%i17) setunits(N);
(%o17) done
(%i18) N;
(%o18) N
(%i19) dyn;
(%o19) 
$$\frac{1}{100000} \text{ (N)}$$

(%i20) kg*m/s^2;
(%o20) N
(%i21) centigram*inch/minutes^2;
(%o21) 
$$\frac{127}{1800000000000} \text{ (N)}$$

```

Notice that the *unit* package recognized the non MKS combination of mass, length, and inverse time squared as a force, and converted it to Newtons. This is how Maxima works in general. If, for example, we prefer dyne to Newtons, we simply do the following:

```
(%i22) setunits(dyn);
(%o22) done
(%i23) kg*m/s^2;
(%o23) (100000) (dyn)
(%i24) centigram*inch/minutes^2;
(%o24) 
$$\frac{127}{18000000} \text{ (dyn)}$$

```

To discontinue simplifying to any force, we use the `uforget` command:

```
(%i26) uforget(dyn);
(%o26) false
(%i27) kg*m/s^2;
(%o27) 
$$\frac{\text{kg m}}{\text{s}^2}$$

(%i28) centigram*inch/minutes^2;
(%o28) 
$$\frac{127}{1800000000000} \frac{\text{kg m}}{\text{s}^2}$$

```

This would have worked equally well with `uforget(N)` or `uforget(%force)`. See also `uforget`. To use this function write first `load("unit")`.

uforget (*list*)

Function

By default, the *unit* package converts all units to the seven fundamental dimensions using MKS units. This behavior can be changed with the `setunits` command. After that, the user can restore the default behavior for a particular dimension by means of the `uforget` command:

```
(%i13) setunits([centigram,inch,minute]);
(%o13) done
(%i14) centigram*inch/minutes^2;
(%o14) 
$$\frac{\text{\%in cg}}{\text{\%min}^2}$$

(%i15) uforget([cg,\%in,\%min]);
(%o15) [false, false, false]
```

```
(%i16) centigram*inch/minutes^2;

(%o16)          127      kg m
      (-----) (----)
      1800000000000      2
                      s
```

`uforget` operates on dimensions, not units, so any unit of a particular dimension will work. The dimension itself is also a legal argument.

See also `setunits`. To use this function write first `load("unit")`.

convert (*expr*, *list*) Function

When resetting the global environment is overkill, there is the `convert` command, which allows one time conversions. It can accept either a single argument or a list of units to use in conversion. When a convert operation is done, the normal global evaluation system is bypassed, in order to avoid the desired result being converted again. As a consequence, for inexact calculations "rat" warnings will be visible if the global environment controlling this behavior (`ratprint`) is true. This is also useful for spot-checking the accuracy of a global conversion. Another feature is `convert` will allow a user to do Base Dimension conversions even if the global environment is set to simplify to a Derived Dimension.

```
(%i2) kg*m/s^2;

(%o2)          kg m
      ----
      2
      s

(%i3) convert(kg*m/s^2,[g,km,s]);

(%o3)          g km
      ----
      2
      s

(%i4) convert(kg*m/s^2,[g,inch,minute]);

'rat' replaced 39.37007874015748 by 5000/127 = 39.37007874015748
(%o4)          18000000000      %in g
      (-----) (-----)
      127      2
                      %min

(%i5) convert(kg*m/s^2,[N]);
(%o5)          N

(%i6) convert(kg*m^2/s^2,[N]);
(%o6)          m N

(%i7) setunits([N,J]);
(%o7)          done

(%i8) convert(kg*m^2/s^2,[N]);
(%o8)          m N

(%i9) convert(kg*m^2/s^2,[N,inch]);

'rat' replaced 39.37007874015748 by 5000/127 = 39.37007874015748
(%o9)          5000
      (----) (%in N)
      127

(%i10) convert(kg*m^2/s^2,[J]);
(%o10)          J

(%i11) kg*m^2/s^2;
(%o11)          J

(%i12) setunits([g,inch,s]);
(%o12)          done
```

```

(%i13) kg*m/s^2;
(%o13)
N
(%i14) uforget(N);
(%o14)
false
(%i15) kg*m/s^2;
(%o15)
5000000 %in g
(-----) (-----)
127      2
s

(%i16) convert(kg*m/s^2,[g,inch,s]);

'rat' replaced 39.37007874015748 by 5000/127 = 39.37007874015748
(%o16)
5000000 %in g
(-----) (-----)
127      2
s

```

See also `setunits` and `uforget`. To use this function write first `load("unit")`.

userunits

Optional variable

Default value: none

If a user wishes to have a default unit behavior other than that described, they can make use of *maxima-init.mac* and the *userunits* variable. The *unit* package will check on startup to see if this variable has been assigned a list. If it has, it will use `setunits` on that list and take the units from that list to be defaults. `uforget` will revert to the behavior defined by `userunits` over its own defaults. For example, if we have a *maxima-init.mac* file containing:

```
userunits : [N,J];
```

we would see the following behavior:

```

(%i1) load("unit")$
*****
*                               Units version 0.50                               *
*          Definitions based on the NIST Reference on                               *
*          Constants, Units, and Uncertainty                                       *
*          Conversion factors from various sources including                       *
*          NIST and the GNU units package                                           *
*****

Redefining necessary functions...
WARNING: DEFUN/DEFMACRO: redefining function
TOPLEVEL-MACSYMA-EVAL ...
WARNING: DEFUN/DEFMACRO: redefining function MSETCHK ...
WARNING: DEFUN/DEFMACRO: redefining function KILL1 ...
WARNING: DEFUN/DEFMACRO: redefining function NFORMAT ...
Initializing unit arrays...
Done.
User defaults found...
User defaults initialized.
(%i2) kg*m/s^2;
(%o2)
N
(%i3) kg*m^2/s^2;
(%o3)
J
(%i4) kg*m^3/s^2;
(%o4)
J m
(%i5) kg*m*km/s^2;
(%o5)
(1000) (J)

```

```

(%i6) setunits([dyn,eV]);
(%o6) done
(%i7) kg*m/s^2;
(%o7) (100000) (dyn)
(%i8) kg*m^2/s^2;
(%o8) (6241509596477042688) (eV)
(%i9) kg*m^3/s^2;
(%o9) (6241509596477042688) (eV m)
(%i10) kg*m*km/s^2;
(%o10) (6241509596477042688000) (eV)
(%i11) uforget([dyn,eV]);
(%o11) [false, false]
(%i12) kg*m/s^2;
(%o12) N
(%i13) kg*m^2/s^2;
(%o13) J
(%i14) kg*m^3/s^2;
(%o14) J m
(%i15) kg*m*km/s^2;
(%o15) (1000) (J)

```

Without `userunits`, the initial inputs would have been converted to MKS, and `uforget` would have resulted in a return to MKS rules. Instead, the user preferences are respected in both cases. Notice these can still be overridden if desired. To completely eliminate this simplification - i.e. to have the user defaults reset to factory defaults - the `dontusedimension` command can be used. `uforget` can restore user settings again, but only if `usedimension` frees it for use. Alternately, `kill(userunits)` will completely remove all knowledge of the user defaults from the session. Here are some examples of how these various options work.

```

(%i2) kg*m/s^2;
(%o2) N
(%i3) kg*m^2/s^2;
(%o3) J
(%i4) setunits([dyn,eV]);
(%o4) done
(%i5) kg*m/s^2;
(%o5) (100000) (dyn)
(%i6) kg*m^2/s^2;
(%o6) (6241509596477042688) (eV)
(%i7) uforget([dyn,eV]);
(%o7) [false, false]
(%i8) kg*m/s^2;
(%o8) N
(%i9) kg*m^2/s^2;
(%o9) J
(%i10) dontusedimension(N);
(%o10) [%force]
(%i11) dontusedimension(J);
(%o11) [%energy, %force]
(%i12) kg*m/s^2;
(%o12) kg m
-----
2
s

```

```

(%i13) kg*m^2/s^2;

                                     2
                                   kg m
(%o13) -----
                                     2
                                     s

(%i14) setunits([dyn,eV]);
(%o14) done
(%i15) kg*m/s^2;
                                   kg m
(%o15) -----
                                     2
                                     s

(%i16) kg*m^2/s^2;
                                     2
                                   kg m
(%o16) -----
                                     2
                                     s

(%i17) uforget([dyn,eV]);
(%o17) [false, false]
(%i18) kg*m/s^2;
                                   kg m
(%o18) -----
                                     2
                                     s

(%i19) kg*m^2/s^2;
                                     2
                                   kg m
(%o19) -----
                                     2
                                     s

(%i20) usedimension(N);
Done. To have Maxima simplify to this dimension, use
setunits([unit]) to select a unit.
(%o20) true
(%i21) usedimension(J);
Done. To have Maxima simplify to this dimension, use
setunits([unit]) to select a unit.
(%o21) true
(%i22) kg*m/s^2;
                                   kg m
(%o22) -----
                                     2
                                     s

(%i23) kg*m^2/s^2;
                                     2
                                   kg m
(%o23) -----
                                     2
                                     s

(%i24) setunits([dyn,eV]);
(%o24) done
(%i25) kg*m/s^2;
(%o25) (100000) (dyn)

```

```

(%i26) kg*m^2/s^2;
(%o26) (6241509596477042688) (eV)
(%i27) uforget([dyn,eV]);
(%o27) [false, false]
(%i28) kg*m/s^2;
(%o28) N
(%i29) kg*m^2/s^2;
(%o29) J
(%i30) kill(usersetunits);
(%o30) done
(%i31) uforget([dyn,eV]);
(%o31) [false, false]
(%i32) kg*m/s^2;
(%o32)
      kg m
      ----
      2
      s

(%i33) kg*m^2/s^2;
(%o33)
      2
      kg m
      ----
      2
      s

```

Unfortunately this wide variety of options is a little confusing at first, but once the user grows used to them they should find they have very full control over their working environment.

metricexpandall (x)

Function

Rebuilds global unit lists automatically creating all desired metric units. *x* is a numerical argument which is used to specify how many metric prefixes the user wishes defined. The arguments are as follows, with each higher number defining all lower numbers' units:

- 0 - none. Only base units
- 1 - kilo, centi, milli
- (default) 2 - giga, mega, kilo, hecto, deka, deci, centi, milli, micro, nano
- 3 - peta, tera, giga, mega, kilo, hecto, deka, deci, centi, milli, micro, nano, pico, femto
- 4 - all

Normally, Maxima will not define the full expansion since this results in a very large number of units, but **metricexpandall** can be used to rebuild the list in a more or less complete fashion. The relevant variable in the *unit.mac* file is *%unitexpand*.

%unitexpand

Variable

Default value: 2

This is the value supplied to **metricexpandall** during the initial loading of *unit*.

81 zeilberger

81.1 Introduction to zeilberger

`zeilberger` is a implementation of Zeilberger's algorithm for definite hypergeometric summation, and also Gosper's algorithm for indefinite hypergeometric summation.

`zeilberger` makes use of the "filtering" optimization method developed by Axel Riese.

`zeilberger` was developed by Fabrizio Caruso.

`load (zeilberger)` loads this package.

81.1.0.1 The indefinite summation problem

`zeilberger` implements Gosper's algorithm for indefinite hypergeometric summation. Given a hypergeometric term F_k in k we want to find its hypergeometric anti-difference, that is, a hypergeometric term f_k such that

$$F_k = f_{k+1} - f_k.$$

81.1.0.2 The definite summation problem

`zeilberger` implements Zeilberger's algorithm for definite hypergeometric summation. Given a proper hypergeometric term (in n and k) $F_{n,k}$ and a positive integer d we want to find a d -th order linear recurrence with polynomial coefficients (in n) for $F_{n,k}$ and a rational function R in n and k such that

$$a_0 F_{n,k} + \dots + a_d F_{n,k+d}, \quad k = \Delta_K (R(n, k) F_{n,k}),$$

where Δ_k is the k -forward difference operator, i.e., $\Delta_k(t_k) \equiv t_{k+1} - t_k$.

81.1.1 Verbosity levels

There are also verbose versions of the commands which are called by adding one of the following prefixes:

Summary Just a summary at the end is shown

Verbose Some information in the intermediate steps

VeryVerbose
 More information

Extra Even more information including information on the linear system in Zeilberger's algorithm

For example:
`GosperVerbose`, `parGosperVeryVerbose`, `ZeilbergerExtra`, `AntiDifferenceSummary`.

81.2 Functions and Variables for zeilberger

AntiDifference	(F_k, k)	Function
Returns the hypergeometric anti-difference of F_k , if it exists.		
Otherwise AntiDifference returns <code>no_hyp_antidifference</code> .		

Gosper	(F_k, k)	Function
Returns the rational certificate $R(k)$ for F_k , that is, a rational function such that $F_k = R(k+1) F_{k+1} - R(k) F_k$, if it exists. Otherwise, Gosper returns <code>no_hyp_sol</code> .		

GosperSum (F_k, k, a, b)

Function

Returns the summation of F_k from $k = a$ to $k = b$ if F_k has a hypergeometric anti-difference. Otherwise, **GosperSum** returns **nongosper_summable**.

Examples:

```
(%i1) load (zeilberger)$
(%i2) GosperSum ((-1)^k*k / (4*k^2 - 1), k, 1, n);
Dependent equations eliminated: (1)
              3      n + 1
      (n + -) (- 1)
              2
(%o2)  - ---- - -
              2      4
      2 (4 (n + 1) - 1)
(%i3) GosperSum (1 / (4*k^2 - 1), k, 1, n);
              3
      - n - -
              2      1
(%o3)  ----- + -
              2      2
      4 (n + 1) - 1
(%i4) GosperSum (x^k, k, 1, n);
      n + 1
      x      x
      ----- - -----
      x - 1   x - 1
(%i5) GosperSum ((-1)^k*a! / (k!*(a - k)!), k, 1, n);
              n + 1
      a! (n + 1) (- 1)      a!
(%o5)  - ---- - ----
      a (- n + a - 1)! (n + 1)!   a (a - 1)!
(%i6) GosperSum (k*k!, k, 1, n);
Dependent equations eliminated: (1)
              (n + 1)! - 1
(%o6)  GosperSum ((k + 1)*k! / (k + 1)!, k, 1, n);
              (n + 1) (n + 2) (n + 1)!
(%o7)  ----- - 1
              (n + 2)!
(%i8) GosperSum (1 / ((a - k)!*k!), k, 1, n);
(%o8)  NON_GOSPER_SUMMABLE
```

parGosper ($F_{n,k}, k, n, d$)

Function

Attempts to find a d -th order recurrence for $F_{n,k}$.

The algorithm yields a sequence $[s_1, s_2, \dots, s_m]$ of solutions. Each solution has the form

$$[R(n, k), [a_0, a_1, \dots, a_d]].$$

parGosper returns **[]** if it fails to find a recurrence.

Zeilberger ($F_{n,k}, k, n$)

Function

Attempts to compute the indefinite hypergeometric summation of $F_{n,k}$.

Zeilberger first invokes **Gosper**, and if that fails to find a solution, then invokes **parGosper** with order 1, 2, 3, ..., up to **MAX_ORD**. If **Zeilberger** finds a solution before reaching **MAX_ORD**, it stops and returns the solution.

The algorithms yields a sequence $[s_1, s_2, \dots, s_m]$ of solutions. Each solution has the form

$$[R(n, k), [a_0, a_1, \dots, a_d]].$$

`Zeilberger` returns `[]` if it fails to find a solution.

`Zeilberger` invokes `Gosper` only if `Gosper_in_Zeilberger` is `true`.

81.3 General global variables

MAX_ORD

Global variable

Default value: 5

`MAX_ORD` is the maximum recurrence order attempted by `Zeilberger`.

simplified_output

Global variable

Default value: `false`

When `simplified_output` is `true`, functions in the `zeilberger` package attempt further simplification of the solution.

linear_solver

Global variable

Default value: `linsolve`

`linear_solver` names the solver which is used to solve the system of equations in `Zeilberger`'s algorithm.

warnings

Global variable

Default value: `true`

When `warnings` is `true`, functions in the `zeilberger` package print warning messages during execution.

Gosper_in_Zeilberger

Global variable

Default value: `true`

When `Gosper_in_Zeilberger` is `true`, the `Zeilberger` function calls `Gosper` before calling `parGosper`. Otherwise, `Zeilberger` goes immediately to `parGosper`.

trivial_solutions

Global variable

Default value: `true`

When `trivial_solutions` is `true`, `Zeilberger` returns solutions which have certificate equal to zero, or all coefficients equal to zero.

81.4 Variables related to the modular test

mod_test

Global variable

Default value: `false`

When `mod_test` is `true`, `parGosper` executes a modular test for discarding systems with no solutions.

modular_linear_solver

Global variable

Default value: `linsolve`

`modular_linear_solver` names the linear solver used by the modular test in `parGosper`.

ev_point

Global variable

Default value: `big_primes[10]`

`ev_point` is the value at which the variable n is evaluated when executing the modular test in `parGosper`.

mod_big_prime

Global variable

Default value: `big_primes[1]`

`mod_big_prime` is the modulus used by the modular test in `parGosper`.

mod_threshold

Global variable

Default value: 4

`mod_threshold` is the greatest order for which the modular test in `parGosper` is attempted.

82 Indices

Appendix A Function and Variable Index

!		/	
! (Operator)	121	/ (Operator)	81
!! (Operator)	120		
#		:	
# (Operator)	85	: (Operator)	87
		:: (Operator)	88
		::= (Operator)	88
		:= (Operator)	89
%		<	
% (System variable)	12	< (Operator)	84
%% (System variable)	12	<= (Operator)	84
%and (Operator)	817		
%c (Variable)	508	=	
%e (Constant)	37	= (Operator)	86
%e_to_numlog (Option variable)	122	>	
%edispflag (Option variable)	19	> (Operator)	84
%emode (Option variable)	122	>= (Operator)	84
%enumer (Option variable)	123		
%f (Function)	222	?	
%gamma (Constant)	37	? (Special symbol)	13
%i (Constant)	37	?? (Special symbol)	13
%iargs (Option variable)	126		
%if (Operator)	818	@	
%k1 (Variable)	508	@ (Operator)	58
%k2 (Variable)	508		
%m (Function)	222	[
%or (Operator)	818	[(Operator)	40
%phi (Constant)	37		
%pi (Constant)	38]	
%piargs (Option variable)	126] (Operator)	40
%rnum_list (System variable)	261	^	
%s (Function)	209	^ (Operator)	81
%th (Function)	13	^^ (Operator)	83
%unitexpand (Variable)	840		
%w (Function)	222	-	
,		- (System variable)	11
,		-- (System variable)	11
, (Operator)	95	‘	
,, (Operator)	96	‘ (Operator)	644
		“ (Operator)	645
*		\	
* (Operator)	81	\	35
** (Operator)	83		
+			
+ (Operator)	81		
-			
- (Operator)	81		
.			
. (Operator)	83		

(Operator)	335
~	
~ (Operator)	334
A	
abasep (Function)	363
abs (Function)	115
absboxchar (Option variable)	19
absint (Function)	286
absolute_real_time (Function)	411
acos (Function)	127
acosh (Function)	127
acot (Function)	127
acoth (Function)	127
acsc (Function)	127
acsch (Function)	127
activate (Function)	141
activecontexts (System variable)	141
adapt_depth (Graphic option)	577
adapt_depth (Plot option)	165
add_edge (Function)	685
add_edges (Function)	685
add_vertex (Function)	685
add_vertices (Function)	685
addcol (Function)	290
additive (Property)	105
addmatrices (Function)	724
addrow (Function)	290
adim (Variable)	363
adjacency_matrix (Function)	672
adjoin (Function)	434
adjoint (Function)	290
af (Function)	363
aform (Variable)	363
agd (Function)	781
airy_ai (Function)	210
airy_bi (Function)	210
airy_dai (Function)	210
airy_dbi (Function)	210
alg_type (Function)	363
algebraic (Option variable)	185
algepsilon (Option variable)	261
algexact (Option variable)	261
algsys (Function)	261
alias (Function)	61
aliases (System variable)	61
all_dotsimp_denoms (Option variable)	310
allbut (Keyword)	61
allocation (Graphic option)	577
allroots (Function)	263
allsym (Option variable)	322
alphabetic (Property)	133
alphacharp (Function)	810
alphanumericp (Function)	810
amortization (Function)	658
and (Operator)	84
annuity_fv (Function)	658
annuity_pv (Function)	657
antid (Function)	233
antidiff (Function)	233
AntiDifference (Function)	841
antisymmetric (Property)	105
append (Function)	40
appendfile (Function)	173
apply (Function)	457
apply1 (Function)	417
apply2 (Function)	417
applyb1 (Function)	417
apropos (Function)	7
args (Function)	62
arit_amortization (Function)	658
arithmetic (Function)	780
arithsum (Function)	780
array (Function)	49
arrayapply (Function)	49
arrayinfo (Function)	49
arraymake (Function)	50
arrays (System variable)	51
arraysetapply (Function)	52
ascii (Function)	810
asec (Function)	127
asech (Function)	127
asin (Function)	127
asinh (Function)	127
askexp (System variable)	413
askinteger (Function)	141
asksign (Function)	141
assoc (Function)	41
assoc_legendre_p (Function)	761
assoc_legendre_q (Function)	761
assume (Function)	141
assume_external_byte_order (Function)	751
assume_pos (Option variable)	142
assume_pos_pred (Option variable)	142
assumescalar (Option variable)	142
asymbol (Variable)	363
asympa (Function)	495
at (Function)	234
atan (Function)	127
atan2 (Function)	127
atanh (Function)	128
atensimp (Function)	362
atom (Function)	62
atomgrad (Property)	235
atrig1 (Package)	128
atvalue (Function)	235
augcoefmatrix (Function)	290
augmented_lagrangian_method (Function)	497
av (Function)	363
average_degree (Function)	672
axes (Plot option)	165
axis_3d (Graphic option)	578
axis_bottom (Graphic option)	578
axis_left (Graphic option)	578
axis_right (Graphic option)	578
axis_top (Graphic option)	579
azimuth (Plot option)	165

B

background_color (Graphic option)	579
backslash	35
backsubst (Option variable)	264
backtrace (Function)	478
bars (Graphic object)	608
barsplot (Function)	527
barsplot_description (Function)	527
bashindices (Function)	365
batch (Function)	173
batchload (Function)	174
bc2 (Function)	277
bdvac (Function)	352
belln (Function)	435
benefit_cost (Function)	660
berlefact (Option variable)	185
bern (Function)	381
bernpoly (Function)	381
bernstein_approx (Function)	500
bernstein_expand (Function)	500
bernstein_explicit (Variable)	499
bernstein_poly (Function)	499
bessel_i (Function)	208
bessel_j (Function)	207
bessel_k (Function)	208
bessel_y (Function)	208
besslelexpand (Option variable)	209
beta (Function)	213
beta_args_sum_to_integer (Option variable) ...	219
beta_expand (Option variable)	219
beta_incomplete (Function)	214
beta_incomplete_generalized (Function)	217
beta_incomplete_regularized (Function)	216
bezout (Function)	185
bf_find_root (Function)	284
bf_fmin_cobyla (Function)	504
bfallroots (Function)	263, 264
bffac (Function)	210
bffhzeta (Function)	381
bfloat (Function)	29
bfloatp (Function)	29
bfpai (Function)	210
bfpai0 (Function)	210
bftorat (Option variable)	29
bft trunc (Option variable)	29
bifzeta (Function)	381
biconnected_components (Function)	672
bimetric (Function)	352
bindtest (Property)	133
binomial (Function)	120
bipartition (Function)	673
block (Function)	458
blockmatrixp (Function)	724
bode_gain (Function)	501
bode_phase (Function)	501
border (Graphic option)	579
bothcoef (Function)	186
boundaries_array (Global variable)	622
box (Function)	62
box (Plot option)	166
boxchar (Option variable)	62
boxplot (Function)	529
boxplot_description (Function)	529
break (Function)	458
breakup (Option variable)	264
bug_report (Function)	5
build_info (Function)	5

buildq (Function)	454
burn (Function)	381

C

cabs (Function)	118
canform (Function)	322
canten (Function)	321
cardinality (Function)	435
carg (Function)	119
cartan (Function)	236
cartesian_product (Function)	435
catch (Function)	458
cauchy_matrix (Function)	290
cauchysum (Option variable)	368
cbffac (Function)	210
cbrange (Graphic option)	579
cbtics (Graphic option)	580
cdf_bernoulli (Function)	568
cdf_beta (Function)	556
cdf_binomial (Function)	566
cdf_cauchy (Function)	563
cdf_chi2 (Function)	548
cdf_continuous_uniform (Function)	557
cdf_discrete_uniform (Function)	570
cdf_exp (Function)	552
cdf_f (Function)	551
cdf_gamma (Function)	555
cdf_general_finite_discrete (Function)	565
cdf_geometric (Function)	569
cdf_gumbel (Function)	564
cdf_hypergeometric (Function)	571
cdf_laplace (Function)	563
cdf_logistic (Function)	558
cdf_lognormal (Function)	554
cdf_negative_binomial (Function)	572
cdf_noncentral_chi2 (Function)	550
cdf_noncentral_student_t (Function)	547
cdf_normal (Function)	545
cdf_pareto (Function)	559
cdf_poisson (Function)	567
cdf_rank_sum (Function)	803
cdf_rayleigh (Function)	560
cdf_signed_rank (Function)	802
cdf_student_t (Function)	546
cdf_weibull (Function)	559
cdisplay (Function)	353
ceiling (Function)	116
central_moment (Function)	518
cequal (Function)	810
cequalignore (Function)	810
cf (Function)	382
cfdisrep (Function)	383
cfexpand (Function)	383
cflength (Option variable)	383
cframe_flag (Option variable)	357
cgeodesic (Function)	352
cgreaterp (Function)	810
cgreaterpignore (Function)	810
changename (Function)	314
changevar (Function)	243
chaosgame (Function)	631
charat (Function)	811
charfun (Function)	146
charfun2 (Function)	702
charlist (Function)	811
charp (Function)	810

charpoly (Function)	290
chebyshev_t (Function)	761
chebyshev_u (Function)	761
check_overlaps (Function)	310
checkdiv (Function)	352
chinese (Function)	382
cholesky (Function)	725
christof (Function)	343
chromatic_index (Function)	673
chromatic_number (Function)	673
cint (Function)	810
circulant_graph (Function)	668
clear_edge_weight (Function)	673
clear_rules (Function)	428
clear_vertex_label (Function)	673
clebsch_graph (Function)	668
clessp (Function)	810
clesspignore (Function)	811
close (Function)	808
closefile (Function)	174
cmetric (Function)	341
cnonmet_flag (Option variable)	357
coeff (Function)	186
coefmatrix (Function)	291
cograd (Function)	351
col (Function)	291
collapse (Function)	63
collectterms (Function)	778
color (Graphic option)	580
color (Plot option)	166
colorbox (Graphic option)	581
colorbox (Plot option)	166
columnop (Function)	725
columns (Graphic option)	581
columnspace (Function)	725
columnswap (Function)	725
columnvector (Function)	291
combination (Function)	781
combine (Function)	105
commutative (Property)	105
comp2pui (Function)	393
compare (Function)	146
compfile (Function)	459
compile (Function)	459
compile_file (Function)	475
complement_graph (Function)	668
complete_bipartite_graph (Function)	668
complete_graph (Function)	668
complex (Property)	140
complex_number_p (Function)	819
components (Function)	317
compose_functions (Function)	819
concan (Function)	321
concat (Function)	35
conjugate (Function)	119
commetderiv (Function)	325
connect_vertices (Function)	685
connected_components (Function)	673
cons (Function)	41
constant (Property)	133
constantp (Function)	134
constituent (Function)	811
constvalue (Function)	648
cont2part (Function)	396
content (Function)	187
context (Option variable)	143
contexts (Option variable)	144

continuous_freq (Function)	512
contortion (Function)	350
contour (Graphic option)	581
contour_levels (Graphic option)	582
contour_plot (Function)	152
contract (Function)	316, 396
contract_edge (Function)	686
contragrad (Function)	351
contrib_ode (Function)	507
convert (Function)	836
coord (Function)	325
copy (Function)	725
copy_graph (Function)	668
copylist (Function)	41
copymatrix (Function)	292
cor (Function)	524
cos (Function)	128
cosh (Function)	128
cosnpiflag (Option variable)	286
cot (Function)	128
coth (Function)	128
cov (Function)	523
cov1 (Function)	523
covdiff (Function)	327
covect (Function)	291
covers (Function)	781
create_graph (Function)	667
create_list (Function)	41
csc (Function)	128
csch (Function)	128
csetup (Function)	340
cspline (Function)	703, 704
ct_coords (Option variable)	359
ct_coordsys (Function)	341
ctaylor (Function)	345
ctaypov (Option variable)	357
ctaypt (Option variable)	357
ctayswitch (Option variable)	357
ctayvar (Option variable)	357
ctorsion_flag (Option variable)	357
ctransform (Function)	350
ctranspose (Function)	725
ctrgsimp (Option variable)	357
cube_graph (Function)	669
cuboctahedron_graph (Function)	669
cunlisp (Function)	811
current_let_rule_package (Option variable)	417
cv (Function)	518
cycle_digraph (Function)	668
cycle_graph (Function)	668
cylindrical (Graphic object)	608

D

data_file_name (Graphic option)	582
days360 (Function)	657
dblrint (Function)	244
deactivate (Function)	144
debugmode (Option variable)	491
declare (Function)	134
declare_constvalue (Function)	648
declare_dimensions (Function)	651
declare_fundamental_dimensions (Function)	651
declare_fundamental_units (Function)	652
declare_qty (Function)	649
declare_translated (Function)	475
declare_unit_conversion (Function)	650

declare_units (Function)	648
declare_weights (Function)	309
decreasing (Property)	135
decsym (Function)	322
default_let_rule_package (Option variable) ..	418
defcon (Function)	316
define (Function)	459
define_variable (Function)	460
defint (Function)	244
defmatch (Function)	418
defrule (Function)	419
defstruct (Function)	57
deftaylor (Function)	369
degree_sequence (Function)	674
del (Function)	236
delay (Graphic option)	582
delete (Function)	41
deleten (Function)	357
delta (Function)	236
demo (Function)	7
demoivre (Function)	106
demoivre (Option variable)	106
denom (Function)	187
dependencies (System variable)	236
depends (Function)	237
derivabbrev (Option variable)	237
derivdegree (Function)	237
derivlist (Function)	238
derivsubst (Option variable)	238
describe (Function)	8
desolve (Function)	277
determinant (Function)	292
detout (Option variable)	292
dfloat (Function)	820
dgauss_a (Function)	508
dgauss_b (Function)	508
dgeev (Function)	707
dgemm (Function)	711
dgeqrf (Function)	708
dgesv (Function)	708
dgesvd (Function)	709
diag (Function)	535
diag_matrix (Function)	725
diagmatrix (Function)	292
diagmatrixp (Function)	353
diagrametric (Option variable)	357
diameter (Function)	674
diff (Function)	238, 323
diff (Special symbol)	239
digitcharp (Function)	811
dim (Option variable)	357
dimacs_export (Function)	687
dimacs_import (Function)	687
dimension (Function)	265
dimensionless (Function)	653
dimensions (Function)	652
dimensions (Graphic option)	583
dimensions_as_list (Function)	652
direct (Function)	397
discrete_freq (Function)	513
disjoin (Function)	435
disjointp (Function)	436
disolate (Function)	63
disp (Function)	19
dispcon (Function)	314
dispflag (Option variable)	265
dispform (Function)	63

dispfun (Function)	462
dispJordan (Function)	536
display (Function)	20
display_format_internal (Option variable) ..	20
display2d (Option variable)	20
disprule (Function)	419
dispterms (Function)	21
distrib (Function)	106
distribute_over (Option variable)	106
divide (Function)	187
divisors (Function)	436
divsum (Function)	384
dkummer_m (Function)	509
dkummer_u (Function)	509
dlange (Function)	711
do (Special operator)	479
doallmxops (Option variable)	293
dodecahedron_graph (Function)	669
domain (Option variable)	107
domxexpt (Option variable)	293
dommxops (Option variable)	293
domxnctimes (Option variable)	293
dontfactor (Option variable)	293
doscmxops (Option variable)	293
doscmxplus (Option variable)	294
dot0nscsimp (Option variable)	294
dot0simp (Option variable)	294
dot1simp (Option variable)	294
dotassoc (Option variable)	294
dotconstrules (Option variable)	294
dotdistrib (Option variable)	294
dotexptsimp (Option variable)	294
dotident (Option variable)	294
dotproduct (Function)	726
dotscrules (Option variable)	294
dotsimp (Function)	309
dpart (Function)	64
draw (Function)	575
draw_file (Function)	576
draw_graph (Function)	687
draw_graph_program (Option variable) ..	689
draw_realpart (Graphic option)	583
draw2d (Function)	576
draw3d (Function)	576
drawdf (Function)	627
dscalar (Function)	239, 352

E

echelon (Function)	295
edge_color (draw_graph option)	690
edge_coloring (draw_graph option)	690
edge_coloring (Function)	674
edge_connectivity (Function)	674
edge_partition (draw_graph option)	690
edge_type (draw_graph option)	690
edge_width (draw_graph option)	690
edges (Function)	674
eigens_by_jacobi (Function)	726
eigenvalues (Function)	295
eigenvectors (Function)	295
eighth (Function)	42
einstein (Function)	344
eivals (Function)	295
eivects (Function)	295
elapsed_real_time (Function)	411
elapsed_run_time (Function)	411

ele2comp (Function)	393
ele2polynome (Function)	400
ele2pui (Function)	393
elem (Function)	393
elementp (Function)	436
elevation (Plot option)	166
elevation_grid (Graphic object)	609
elim (Function)	820
elim_allbut (Function)	821
eliminate (Function)	188
eliminate_using (Function)	821
ellipse (Graphic object)	609
elliptic_e (Function)	230
elliptic_ec (Function)	230
elliptic_eu (Function)	230
elliptic_f (Function)	230
elliptic_kc (Function)	230
elliptic_pi (Function)	230
ematrix (Function)	297
empty_graph (Function)	669
emptyp (Function)	437
endcons (Function)	42
enhanced3d (Graphic option)	584
entermatrix (Function)	297
entertensor (Function)	314
entier (Function)	117
epsilon_lp (Option variable)	775
equal (Function)	147
equalp (Function)	286
equiv_classes (Function)	437
erf (Function)	221
erf_generalized (Function)	221
erf_representation (Option variable)	221
erfc (Function)	221
erfflag (Option variable)	244
erfi (Function)	221
errcatch (Function)	481
error (Function)	481
error (System variable)	481
error_size (Option variable)	482
error_syms (Option variable)	482
error_type (Graphic option)	585
errormsg (Function)	482
errormsg (Option variable)	482
errors (Graphic object)	609
euler (Function)	384
ev (Function)	98
ev_point (Global variable)	843
eval (Special symbol)	100
eval_string (Function)	812
even (Property)	136
evenfun (Property)	107
evenp (Function)	30
every (Function)	437
evflag (Property)	100
evfun (Property)	101
evolution (Function)	631
evolution2d (Function)	631
evundiff (Function)	324
example (Function)	9
exp (Function)	123
expand (Function)	107
expandwrt (Function)	108
expandwrt_denom (Option variable)	109
expandwrt_factored (Function)	109
expintegral_chi (Function)	221
expintegral_ci (Function)	220

expintegral_e (Function)	220
expintegral_e1 (Function)	220
expintegral_ei (Function)	220
expintegral_li (Function)	220
expintegral_shi (Function)	221
expintegral_si (Function)	220
expintexpand (Option variable)	221
expintrep (Option variable)	221
explicit (Graphic object)	610
explode (Function)	396
expon (Option variable)	109
exponentialize (Function)	109
exponentialize (Option variable)	109
expop (Option variable)	109
express (Function)	239
expt (Special symbol)	21
exptdispflag (Option variable)	21
exptisolate (Option variable)	64
exptsbst (Option variable)	64
exsec (Function)	781
extdiff (Function)	335
extract_linear_equations (Function)	310
extremal_subset (Function)	438
ezgcd (Function)	188

F

f90 (Function)	655
facexpand (Option variable)	188
facsum (Function)	777
facsum_combine (Global variable)	778
factcomb (Function)	120
factlim (Option variable)	122
factor (Function)	189
factorfacsum (Function)	778
factorflag (Option variable)	191
factorial (Function)	121
factorial_expand (Option variable)	122
factorout (Function)	191
factors_only (Option variable)	384
factorsum (Function)	191
facts (Function)	144
false (Constant)	37
fast_central_elements (Function)	310
fast_linsolve (Function)	309
fasttimes (Function)	191
fb (Variable)	359
feature (Property)	136
featurep (Function)	136
features (Declaration)	136
fernfalse (Function)	661
fft (Function)	282
fib (Function)	384
fibtophi (Function)	384
fifth (Function)	42
file_name (draw_graph option)	691
file_name (Graphic option)	586
file_output_append (Option variable)	174
file_search (Function)	175
file_search_demo (Option variable)	175
file_search_lisp (Option variable)	175
file_search_maxima (Option variable)	175
file_search_tests (Option variable)	175
file_search_usage (Option variable)	175
file_type (Function)	176
file_type_lisp (Option variable)	176
file_type_maxima (Option variable)	176

filename_merge (Function).....	174
fill_color (Graphic option).....	586
fill_density (Graphic option).....	586
fillarray (Function).....	52
filled_func (Graphic option).....	586
find_root (Function).....	284
find_root_abs (Option variable).....	284
find_root_error (Option variable).....	284
find_root_rel (Option variable).....	284
findde (Function).....	350
first (Function).....	42
fix (Function).....	117
fixed_vertices (draw_graph option).....	691
flatten (Function).....	438
flength (Function).....	808
flipflag (Option variable).....	316
float (Function).....	30
float2bf (Option variable).....	30
floatnump (Function).....	30
floor (Function).....	117
flower_snark (Function).....	669
flush (Function).....	324
flushderiv (Function).....	327
flushd (Function).....	324
flushnd (Function).....	325
fmin_cobyla (Function).....	503
font (Graphic option).....	587
font_size (Graphic option).....	588
for (Special operator).....	483
forget (Function).....	144
fortindent (Option variable).....	183
fortran (Function).....	183
fortspaces (Option variable).....	184
fourcos (Function).....	287
fourexpend (Function).....	286
fourier (Function).....	286
fourier_elim (Function).....	822
fourint (Function).....	287
fourintcos (Function).....	287
fourintsin (Function).....	287
foursimp (Function).....	286
foursin (Function).....	287
fourth (Function).....	42
fposition (Function).....	808
fpprec (Option variable).....	30
fpprintprec (Option variable).....	30
frame_bracket (Function).....	347
freeof (Function).....	64
freshline (Function).....	808
fresnel_c (Function).....	221
fresnel_s (Function).....	221
from_adjacency_matrix (Function).....	669
frucht_graph (Function).....	669
full_listify (Function).....	439
fullmap (Function).....	463
fullmapl (Function).....	463
fullratsimp (Function).....	191
fullratsubst (Function).....	192
fullsetify (Function).....	439
funcsolve (Function).....	265
functions (System variable).....	463
fundamental_dimensions (Global variable).....	651
fundamental_units (Function).....	653
fundef (Function).....	464
funmake (Function).....	464
funp (Function).....	286
fv (Function).....	657

G

gamma (Function).....	210
gamma_expand (Option variable).....	212
gamma_greek (Function).....	212
gamma_incomplete (Function).....	212
gamma_incomplete_generalized (Function).....	212
gamma_incomplete_regularized (Function).....	212
gammalim (Option variable).....	212
gauss_a (Function).....	508
gauss_b (Function).....	508
gaussprob (Function).....	780
gcd (Function).....	193
gcdex (Function).....	193
gcddivide (Function).....	779
gcfac (Function).....	783
gcfactor (Function).....	194
gd (Function).....	780
gdet (System variable).....	358
gen_laguerre (Function).....	761
generalized_lambert_w (Function).....	225
genfact (Function).....	122
genindex (Option variable).....	413
genmatrix (Function).....	298
gensumnum (Option variable).....	413
gensym (Function).....	413
geo_amortization (Function).....	659
geo_annuity_fv (Function).....	658
geo_annuity_pv (Function).....	658
geomap (Graphic object).....	624
geometric (Function).....	780
geometric_mean (Function).....	521
geosum (Function).....	780
get (Function).....	137
get_edge_weight (Function).....	674
get_lu_factors (Function).....	727
get_pixel (Function).....	620
get_plot_option (Function).....	153
get_tex_environment (Function).....	182
get_tex_environment_default (Function).....	183
get_vertex_label (Function).....	675
gfactor (Function).....	194
gfactorsum (Function).....	194
ggf (Function).....	665
GGFCFMAX (Option variable).....	665
GGFINFINITY (Option variable).....	665
girth (Function).....	676
global_variances (Function).....	523
globalsolve (Option variable).....	266
gnuplot_close (Function).....	170
gnuplot_curve_styles (Plot option).....	170
gnuplot_curve_titles (Plot option).....	170
gnuplot_default_term_command (Plot option) ..	170
gnuplot_dumb_term_command (Plot option).....	170
gnuplot_file_name (Graphic option).....	588
gnuplot_out_file (Plot option).....	170
gnuplot_pm3d (Plot option).....	170
gnuplot_preamble (Plot option).....	170
gnuplot_ps_term_command (Plot option).....	170
gnuplot_replot (Function).....	171
gnuplot_reset (Function).....	171
gnuplot_restart (Function).....	170
gnuplot_start (Function).....	170
gnuplot_term (Plot option).....	169
go (Function).....	483
Gosper (Function).....	841
Gosper_in_Zeilberger (Global variable).....	843
GosperSum (Function).....	842

<code>gr2d</code> (Scene constructor)	575
<code>gr3d</code> (Scene constructor)	575
<code>gradef</code> (Function)	240
<code>gradefs</code> (System variable)	240
<code>gramschmidt</code> (Function)	299
<code>graph_center</code> (Function)	675
<code>graph_charpoly</code> (Function)	675
<code>graph_eigenvalues</code> (Function)	675
<code>graph_flow</code> (Function)	657
<code>graph_order</code> (Function)	675
<code>graph_periphery</code> (Function)	675
<code>graph_product</code> (Function)	669
<code>graph_size</code> (Function)	675
<code>graph_union</code> (Function)	669
<code>graph6_decode</code> (Function)	687
<code>graph6_encode</code> (Function)	687
<code>graph6_export</code> (Function)	687
<code>graph6_import</code> (Function)	687
<code>great_rhombicosidodecahedron_graph</code> (Function)	669
<code>great_rhombicuboctahedron_graph</code> (Function) ..	669
<code>grid</code> (Graphic option)	588
<code>grid</code> (Plot option)	166
<code>grid_graph</code> (Function)	669
<code>grind</code> (Function)	22
<code>grind</code> (Option variable)	22
<code>groebner_basis</code> (Function)	309
<code>grotzsch_graph</code> (Function)	669

H

<code>halfangles</code> (Option variable)	128
<code>hamilton_cycle</code> (Function)	676
<code>hamilton_path</code> (Function)	676
<code>hankel</code> (Function)	727
<code>hankel_1</code> (Function)	208
<code>hankel_2</code> (Function)	209
<code>harmonic</code> (Function)	780
<code>harmonic_mean</code> (Function)	521
<code>hav</code> (Function)	781
<code>head_angle</code> (draw_graph option)	691
<code>head_angle</code> (Graphic option)	588
<code>head_both</code> (Graphic option)	589
<code>head_length</code> (draw_graph option)	691
<code>head_length</code> (Graphic option)	589
<code>head_type</code> (Graphic option)	589
<code>heawood_graph</code> (Function)	669
<code>hermite</code> (Function)	761
<code>hessian</code> (Function)	727
<code>hgfred</code> (Function)	224
<code>hilbert_matrix</code> (Function)	727
<code>hilbertmap</code> (Function)	663
<code>hipow</code> (Function)	194
<code>histogram</code> (Function)	530
<code>histogram_description</code> (Function)	530
<code>hodge</code> (Function)	335
<code>horner</code> (Function)	283, 284
<code>hypergeometric</code> (Function)	222
<code>hypergeometric_representation</code> (Option variable)	221

I

<code>ibase</code> (Option variable)	23
<code>ic_convert</code> (Function)	337
<code>ic1</code> (Function)	278
<code>ic2</code> (Function)	278
<code>icc1</code> (Variable)	330
<code>icc2</code> (Variable)	330
<code>ichr1</code> (Function)	327
<code>ichr2</code> (Function)	327
<code>icosahedron_graph</code> (Function)	669
<code>icosidodecahedron_graph</code> (Function)	670
<code>icounter</code> (Option variable)	319
<code>icurvature</code> (Function)	327
<code>ident</code> (Function)	299
<code>identfor</code> (Function)	727
<code>identity</code> (Function)	439
<code>idiff</code> (Function)	323
<code>idim</code> (Function)	327
<code>idummy</code> (Function)	319
<code>idummyx</code> (Option variable)	319
<code>ieqn</code> (Function)	267
<code>ieqnprint</code> (Option variable)	267
<code>if</code> (Special operator)	483
<code>ifactors</code> (Function)	385
<code>ifb</code> (Variable)	330
<code>ifc1</code> (Variable)	331
<code>ifc2</code> (Variable)	331
<code>ifg</code> (Variable)	331
<code>ifgi</code> (Variable)	331
<code>ifr</code> (Variable)	331
<code>iframe_bracket_form</code> (Option variable)	331
<code>iframes</code> (Function)	330
<code>ifri</code> (Variable)	331
<code>ifs</code> (Function)	632
<code>igcdex</code> (Function)	385
<code>igeodesic_coords</code> (Function)	328
<code>igeowedge_flag</code> (Option variable)	336
<code>ikt1</code> (Variable)	332
<code>ikt2</code> (Variable)	332
<code>ilt</code> (Function)	244
<code>image</code> (Graphic object)	611
<code>imaginary</code> (Property)	140
<code>imagpart</code> (Function)	120
<code>imetric</code> (Function)	327
<code>imetric</code> (System variable)	327
<code>implicit</code> (Graphic object)	612
<code>implicit_derivative</code> (Function)	699
<code>implicit_plot</code> (Function)	153
<code>in_neighbors</code> (Function)	676
<code>inchar</code> (Option variable)	13
<code>increasing</code> (Property)	135
<code>ind</code> (Constant)	37
<code>indexed_tensor</code> (Function)	317
<code>indices</code> (Function)	315
<code>induced_subgraph</code> (Function)	670
<code>inf</code> (Constant)	37
<code>inference_result</code> (Function)	789
<code>inferencecp</code> (Function)	790
<code>infeval</code> (Option variable)	103
<code>infinity</code> (Constant)	37
<code>infix</code> (Function)	90
<code>inflag</code> (Option variable)	65
<code>infolists</code> (System variable)	14
<code>init_atensor</code> (Function)	362
<code>init_ctensor</code> (Function)	343
<code>inm</code> (Variable)	332
<code>inmc1</code> (Variable)	332

inmc2 (Variable)	332
innerproduct (Function)	299
inpart (Function)	66
inprod (Function)	299
inrt (Function)	385
intanalysis (Option variable)	245
integer (Property)	137
integer_partitions (Function)	440
interp (Function)	30
integervalued (Property)	138
integrate (Function)	246
integrate_use_rootsof (Option variable)	249
integration_constant (System variable)	248
integration_constant_counter (System variable)	248
intersect (Function)	440
intersection (Function)	440
intervalp (Function)	762
intfaclim (Option variable)	194
intpois (Function)	378
intosum (Function)	365
inv_mod (Function)	385
invariant1 (Function)	352
invariant2 (Function)	352
inverse_fft (Function)	281
inverse_jacobi_cd (Function)	229
inverse_jacobi_cn (Function)	229
inverse_jacobi_cs (Function)	229
inverse_jacobi_dc (Function)	229
inverse_jacobi_dn (Function)	229
inverse_jacobi_ds (Function)	229
inverse_jacobi_nc (Function)	229
inverse_jacobi_nd (Function)	229
inverse_jacobi_ns (Function)	229
inverse_jacobi_sc (Function)	229
inverse_jacobi_sd (Function)	229
inverse_jacobi_sn (Function)	229
invert (Function)	300
invert_by_lu (Function)	728
ip_grid (Graphic option)	590
ip_grid_in (Graphic option)	590
irr (Function)	660
irrational (Property)	140
is (Function)	144
is_biconnected (Function)	676
is_bipartite (Function)	677
is_connected (Function)	677
is_digraph (Function)	677
is_edge_in_graph (Function)	677
is_graph (Function)	677
is_graph_or_digraph (Function)	678
is_isomorphic (Function)	678
is_planar (Function)	678
is_sconnected (Function)	678
is_tree (Function)	678
is_vertex_in_graph (Function)	678
ishow (Function)	315
isolate (Function)	66
isolate_wrt_times (Option variable)	66
isomorphism (Function)	676
isqrt (Function)	385
isreal_p (Function)	823
items_inference (Function)	790
itr (Variable)	332

J

jacobi (Function)	386
jacobi_cd (Function)	228
jacobi_cn (Function)	228
jacobi_cs (Function)	228
jacobi_dc (Function)	229
jacobi_dn (Function)	228
jacobi_ds (Function)	229
jacobi_nc (Function)	228
jacobi_nd (Function)	229
jacobi_ns (Function)	228
jacobi_p (Function)	762
jacobi_sc (Function)	228
jacobi_sd (Function)	228
jacobi_sn (Function)	228
jacobian (Function)	728
JF (Function)	535
join (Function)	43
jordan (Function)	535
julia (Function)	632
julia_parameter (Optional variable)	662
julia_set (Function)	662
julia_sin (Function)	662

K

kdels (Function)	319
kdelta (Function)	319
keepfloat (Option variable)	195
key (Graphic option)	590
kill (Function)	14
killcontext (Function)	145
kinvariant (Variable)	359
kostka (Function)	400
kron_delta (Function)	441
kroncker_product (Function)	728
kt (Variable)	359
kummer_m (Function)	508
kummer_u (Function)	508
kurtosis (Function)	521
kurtosis_bernoulli (Function)	569
kurtosis_beta (Function)	557
kurtosis_binomial (Function)	567
kurtosis_chi2 (Function)	550
kurtosis_continuous_uniform (Function)	558
kurtosis_discrete_uniform (Function)	570
kurtosis_exp (Function)	554
kurtosis_f (Function)	552
kurtosis_gamma (Function)	556
kurtosis_general_finite_discrete (Function)	566
kurtosis_geometric (Function)	570
kurtosis_gumbel (Function)	564
kurtosis_hypergeometric (Function)	571
kurtosis_laplace (Function)	563
kurtosis_logistic (Function)	558
kurtosis_lognormal (Function)	555
kurtosis_negative_binomial (Function)	572
kurtosis_noncentral_chi2 (Function)	551
kurtosis_noncentral_student_t (Function)	548
kurtosis_normal (Function)	545
kurtosis_pareto (Function)	559
kurtosis_poisson (Function)	567
kurtosis_rayleigh (Function)	562
kurtosis_student_t (Function)	546
kurtosis_weibull (Function)	560

L

label (Graphic object)	612	list_nc_monomials (Function)	310
label_alignment (draw_graph option)	689	listarith (Option variable)	43
label_alignment (Graphic option)	590	listarray (Function)	53
label_orientation (Graphic option)	591	listconstvars (Option variable)	67
labels (Function)	15	listdummyvars (Option variable)	67
labels (System variable)	15	listify (Function)	441
lagrange (Function)	701	listoftens (Function)	314
laguerre (Function)	762	listofvars (Function)	67
lambda (Function)	466	listp (Function)	43, 728
lambert_w (Function)	225	lmax (Function)	117
laplace (Function)	241	lmin (Function)	117
laplacian_matrix (Function)	679	lmxchar (Option variable)	300
lassociative (Property)	109	load (Function)	176
last (Function)	43	load_pathname (System variable)	176
lbfgs (Function)	715	loadfile (Function)	177
lbfgs_n corrections (Variable)	719	loadprint (Option variable)	177
lbfgs_nfeval_max (Variable)	719	local (Function)	467
lc_l (Function)	321	locate_matrix_entry (Function)	728
lc_u (Function)	321	log (Function)	124
lc2kdt (Function)	320	log_gamma (Function)	211
lcharp (Function)	811	logabs (Option variable)	124
lcm (Function)	386	logand (Function)	779
ldefint (Function)	250	logarc (Function)	124
ldisp (Function)	24	logarc (Option variable)	124
ldisplay (Function)	24	logcb (Graphic option)	592
leftjust (Option variable)	25	logconcoeffp (Option variable)	124
legend (Plot option)	166	logcontract (Function)	125
legendre_p (Function)	762	logexpand (Option variable)	125
legendre_q (Function)	762	lognegint (Option variable)	125
leinstein (Function)	344	logor (Function)	779
length (Function)	43	logsimp (Option variable)	125
let (Function)	420	logx (Graphic option)	592
let_rule_packages (Option variable)	422	logx (Plot option)	166
letrat (Option variable)	421	logxor (Function)	779
letrules (Function)	421	logy (Graphic option)	592
letsimp (Function)	421	logy (Plot option)	166
levi_civita (Function)	320	logz (Graphic option)	592
lfg (Variable)	358	lopow (Function)	195
lfreeof (Function)	67	lorentz_gauge (Function)	328
lg (Variable)	358	lowercasep (Function)	811
lgtreillis (Function)	400	lpart (Function)	67
lhospitallim (Option variable)	231	lratsubst (Function)	195
lhs (Function)	267	lreduce (Function)	441
li (Function)	123	lriem (Variable)	358
liediff (Function)	323	lriemann (Function)	344
limit (Function)	231	lsquares_estimates (Function)	735
limsubst (Option variable)	231	lsquares_estimates_approximate (Function)	737
Lindstedt (Function)	721	lsquares_estimates_exact (Function)	736
line_graph (Function)	670	lsquares_mse (Function)	738
line_type (Graphic option)	591	lsquares_residual_mse (Function)	739
line_width (Graphic option)	591	lsquares_residuals (Function)	739
linear (Function)	779	lsum (Function)	365
linear (Property)	109	ltreillis (Function)	400
linear_program (Function)	775	lu_backsub (Function)	728
linear_regression (Function)	801	lu_factor (Function)	729
linear_solver (Global variable)	843		
linearinterpol (Function)	702		
linechar (Option variable)	15		
linel (Option variable)	25		
linenum (System variable)	16		
linsolve (Function)	268		
linsolve_params (Option variable)	269		
linsolvewarn (Option variable)	269		
lispdisp (Option variable)	25		
list_correlations (Function)	525		
list_matrix_entries (Function)	300		

M

m1pbranch (Option variable)	31
macroexpand (Function)	455
macroexpand1 (Function)	456
macroexpansion (Option variable)	468
macros (Global variable)	456
mainvar (Property)	67
make_array (Function)	54
make_graph (Function)	670
make_level_picture (Function)	620
make_poly_continent (Function)	622
make_poly_country (Function)	622
make_polygon (Function)	622
make_random_state (Function)	132
make_rgb_picture (Function)	621
make_transform (Function)	154
makebox (Function)	325
makefact (Function)	220
makegamma (Function)	213
makelist (Function)	43
makeOrders (Function)	745
makeset (Function)	442
mandelbrot (Function)	632
mandelbrot_set (Function)	662
manual_demo (Option variable)	9
map (Function)	484
mapatom (Function)	484
maperror (Option variable)	484
maplist (Function)	485
mapprint (Option variable)	485
mat_cond (Function)	730
mat_fullunblocker (Function)	730
mat_function (Function)	537
mat_norm (Function)	730
mat_trace (Function)	731
mat_unblocker (Function)	731
matchdeclare (Function)	422
matchfix (Function)	92
matrix (Function)	300
matrix_element_add (Option variable)	302
matrix_element_mult (Option variable)	303
matrix_element_transpose (Option variable)	303
matrix_size (Function)	730
matrixmap (Function)	302
matrixp (Function)	302, 730
mattrace (Function)	304
max (Function)	117
max_clique (Function)	679
max_degree (Function)	679
max_flow (Function)	679
max_independent_set (Function)	680
max_matching (Function)	680
MAX_ORD (Global variable)	843
maxapplydepth (Option variable)	424
maxapplyheight (Option variable)	424
maxima_tempdir (System variable)	409
maxima_userdir (System variable)	409
maximize_lp (Function)	775
maxnegex (Option variable)	110
maxposex (Option variable)	110
maxpsifracdenom (Option variable)	220
maxpsifracnum (Option variable)	220
maxpsinegint (Option variable)	220
maxpsiposint (Option variable)	219
maxtayorder (Option variable)	369
maybe (Function)	145
mean (Function)	516
mean_bernoulli (Function)	568
mean_beta (Function)	557
mean_binomial (Function)	566
mean_chi2 (Function)	549
mean_continuous_uniform (Function)	557
mean_deviation (Function)	520
mean_discrete_uniform (Function)	570
mean_exp (Function)	553
mean_f (Function)	551
mean_gamma (Function)	556
mean_general_finite_discrete (Function)	565
mean_geometric (Function)	569
mean_gumbel (Function)	564
mean_hypergeometric (Function)	571
mean_laplace (Function)	563
mean_logistic (Function)	558
mean_lognormal (Function)	555
mean_negative_binomial (Function)	572
mean_noncentral_chi2 (Function)	550
mean_noncentral_student_t (Function)	547
mean_normal (Function)	545
mean_pareto (Function)	559
mean_poisson (Function)	567
mean_rayleigh (Function)	561
mean_student_t (Function)	546
mean_weibull (Function)	559
median (Function)	519
median_deviation (Function)	520
member (Function)	44
mesh (Graphic object)	613
mesh_lines_color (Plot option)	167
method (System variable)	508
metricexpandall (Function)	840
min (Function)	118
min_degree (Function)	680
min_edge_cut (Function)	680
min_vertex_cover (Function)	680
min_vertex_cut (Function)	680
minf (Constant)	37
minfactorial (Function)	122
minimalPoly (Function)	537
minimize_lp (Function)	775
minimum_spanning_tree (Function)	680
minor (Function)	304
minpack_lsquares (Function)	743
minpack_solve (Function)	743
mnewton (Function)	747
mod (Function)	386
mod_big_prime (Global variable)	843
mod_test (Global variable)	843
mod_threshold (Global variable)	844
mode_check_errorp (Option variable)	470
mode_check_warnp (Option variable)	470
mode_checkp (Option variable)	470
mode_declare (Function)	470
mode_identity (Function)	471
ModeMatrix (Function)	537
modular_linear_solver (Global variable)	843
modulus (Option variable)	195
moebius (Function)	442
mon2schur (Function)	394
mono (Function)	310
monomial_dimensions (Function)	310
multi_elem (Function)	394
multi_orbit (Function)	398
multi_pui (Function)	394
multibernstein_poly (Function)	499

multinomial (Function).....	406
multinomial_coeff (Function).....	443
multiplicative (Property).....	110
multiplicities (System variable).....	269
multiplot_mode (Function).....	576
multsym (Function).....	399
multthru (Function).....	110
mycielski_graph (Function).....	670
myoptions (System variable).....	16

N

nary (Function).....	93
nary (Property).....	111
natural_unit (Function).....	654
nc_degree (Function).....	309
ncexpt (Special symbol).....	21
ncharpoly (Function).....	304
negative_picture (Function).....	621
negdistrib (Option variable).....	111
negsumdispflag (Option variable).....	26
neighbors (Function).....	681
new (Function).....	58
new_graph (Function).....	670
new_variable (Function).....	823
newcontext (Function).....	146
newdet (Function).....	305
newline (Function).....	808
newline (Variable).....	811
newton (Function).....	285
newtonepsilon (Option variable).....	747
newtonmaxiter (Option variable).....	747
next_prime (Function).....	386
nextlayerfactor (Global variable).....	778
nicedummies (Function).....	824
niceindices (Function).....	370
niceindicespref (Option variable).....	370
ninth (Function).....	44
nm (Variable).....	359
nmc (Variable).....	359
noeval (Special symbol).....	103
nofix (Function).....	93
nolabels (Option variable).....	16
nonarray (Property).....	138
noncentral_moment (Function).....	517
nonnegative_lp (Option variable).....	776
noninteger (Property).....	137
nonmetricity (Function).....	350
nonnegintegrp (Function).....	31
nonscalar (Property).....	138
nonscalarp (Function).....	138
nonzeroandfreeof (Function).....	779
not (Operator).....	85
notequal (Function).....	148
noun (Property).....	68
noundisp (Option variable).....	68
nounify (Function).....	68
nouns (Special symbol).....	103
np (Variable).....	359
npi (Variable).....	359
nptetrad (Function).....	347
npv (Function).....	660
nroots (Function).....	269
nterms (Function).....	68
ntermst (Function).....	353
nthroot (Function).....	269
nticks (Graphic option).....	592

nticks (Plot option).....	167
ntrig (Package).....	129
nullity (Function).....	731
nullspace (Function).....	731
num (Function).....	196
num_distinct_partitions (Function).....	443
num_partitions (Function).....	443
numbered_boundaries (Function).....	622
numberp (Function).....	31
numer (Option variable).....	31
numer_pbranch (Option variable).....	32
numerval (Function).....	32
numfactor (Function).....	220
nusum (Function).....	370
nzeta (Function).....	225
nzetai (Function).....	225
nzetar (Function).....	225

O

obase (Option variable).....	26
odd (Property).....	136
odd_girth (Function).....	681
oddfun (Property).....	107
oddp (Function).....	32
ode_check (Function).....	507
ode2 (Function).....	278
odelin (Function).....	507
op (Function).....	68
opena (Function).....	808
opena_binary (Function).....	751
openr (Function).....	809
openr_binary (Function).....	751
openw (Function).....	809
openw_binary (Function).....	751
operatorp (Function).....	69
opproperties (System variable).....	111
opsubst (Function).....	753
opsubst (Option variable).....	69
optimize (Function).....	69
optimprefix (Option variable).....	69
optionset (Option variable).....	16
or (Operator).....	85
orbit (Function).....	399
orbits (Function).....	632
ordergreat (Function).....	69
ordergreatp (Function).....	70
orderless (Function).....	69
orderlessp (Function).....	70
orthogonal_complement (Function).....	731
orthopoly_recur (Function).....	762
orthopoly_returns_intervals (Variable).....	762
orthopoly_weight (Function).....	762
out_neighbors (Function).....	681
outative (Property).....	112
outchar (Option variable).....	16
outermap (Function).....	486
outofpois (Function).....	378

P

packagefile (Option variable).....	414
pade (Function).....	371
palette (Graphic option).....	593
palette (Plot option).....	167
parabolic_cylinder_d (Function).....	223
parametric (Graphic object).....	614
parametric_surface (Graphic object).....	614
parg (Function).....	824
parGosper (Function).....	842
parse_string (Function).....	812
part (Function).....	71
part2cont (Function).....	397
partfrac (Function).....	386
partition (Function).....	71
partition_set (Function).....	444
partpol (Function).....	397
partswitch (Option variable).....	71
path_digraph (Function).....	670
path_graph (Function).....	671
pathname_directory (Function).....	177
pathname_name (Function).....	177
pathname_type (Function).....	177
pdf_bernoulli (Function).....	568
pdf_beta (Function).....	556
pdf_binomial (Function).....	566
pdf_cauchy (Function).....	563
pdf_chi2 (Function).....	548
pdf_continuous_uniform (Function).....	557
pdf_discrete_uniform (Function).....	570
pdf_exp (Function).....	552
pdf_f (Function).....	551
pdf_gamma (Function).....	555
pdf_general_finite_discrete (Function).....	565
pdf_geometric (Function).....	569
pdf_gumbel (Function).....	564
pdf_hypergeometric (Function).....	571
pdf_laplace (Function).....	562
pdf_logistic (Function).....	558
pdf_lognormal (Function).....	554
pdf_negative_binomial (Function).....	572
pdf_noncentral_chi2 (Function).....	550
pdf_noncentral_student_t (Function).....	547
pdf_normal (Function).....	545
pdf_pareto (Function).....	558
pdf_poisson (Function).....	567
pdf_rank_sum (Function).....	802
pdf_rayleigh (Function).....	560
pdf_signed_rank (Function).....	802
pdf_student_t (Function).....	546
pdf_weibull (Function).....	559
pearson_skewness (Function).....	522
permanent (Function).....	305
permut (Function).....	406
permutation (Function).....	781
permutations (Function).....	444
petersen_graph (Function).....	671
petrov (Function).....	348
pfeformat (Option variable).....	26
pickupart (Function).....	71
picture_equalp (Function).....	621
picturep (Function).....	621
piece (System variable).....	73
piechart (Function).....	531
piechart_description (Function).....	531
planar_embedding (Function).....	681
playback (Function).....	17
plog (Function).....	125
plot_format (Plot option).....	167
plot_options (System variable).....	164
plot_realpart (Plot option).....	167
plot2d (Function).....	154
plot3d (Function).....	159
plotdf (Function).....	765
plsquares (Function).....	740
pochhammer (Function).....	763
pochhammer_max_index (Variable).....	763
point_size (Graphic option).....	594
point_type (Graphic option).....	594
point_type (Plot option).....	167
points (Graphic object).....	615
points_joined (Graphic option).....	595
poisdiff (Function).....	378
poisexpt (Function).....	378
poisint (Function).....	378
poislim (Option variable).....	379
poismap (Function).....	379
poisplus (Function).....	379
poissimp (Function).....	379
poisson (Special symbol).....	379
poissubst (Function).....	379
poistimes (Function).....	379
poistrim (Function).....	379
polar (Graphic object).....	617
polar_to_xy (System function).....	154
polarform (Function).....	120
polarorect (Function).....	281
poly_add (Function).....	694
poly_buchberger (Function).....	696
poly_buchberger_criterion (Function).....	696
poly_coefficient_ring (Option variable).....	694
poly_colon_ideal (Function).....	697
poly_content (Function).....	696
poly_depends_p (Function).....	697
poly_elimination_ideal (Function).....	697
poly_elimination_order (Option variable).....	694
poly_exact_divide (Function).....	696
poly_expand (Function).....	695
poly_expt (Function).....	696
poly_gcd (Function).....	697
poly_grobner (Function).....	697
poly_grobner_algorithm (Option variable).....	694
poly_grobner_debug (Option variable).....	694
poly_grobner_equal (Function).....	697
poly_grobner_member (Function).....	698
poly_grobner_subsetp (Function).....	698
poly_ideal_intersection (Function).....	697
poly_ideal_polysaturation (Function).....	698
poly_ideal_polysaturation1 (Function).....	698
poly_ideal_saturation (Function).....	698
poly_ideal_saturation1 (Function).....	698
poly_lcm (Function).....	697
poly_minimization (Function).....	697
poly_monomial_order (Option variable).....	693
poly_multiply (Function).....	695
poly_normal_form (Function).....	696
poly_normalize (Function).....	695
poly_normalize_list (Function).....	697
poly_polysaturation_extension (Function).....	698
poly_primary_elimination_order (Option variable).....	694
poly_primitive_part (Function).....	695
poly_pseudo_divide (Function).....	696
poly_reduced_grobner (Function).....	697

poly_reduction (Function).....	696
poly_return_term_list (Option variable).....	694
poly_s_polynomial (Function).....	695
poly_saturation_extension (Function).....	698
poly_secondary_elimination_order (Option variable).....	694
poly_subtract (Function).....	695
poly_top_reduction_only (Option variable)....	694
polydecomp (Function).....	196
polyfactor (Option variable).....	269
polygon (Graphic object).....	617
polymod (Function).....	197
polynome2ele (Function).....	401
polynomialp (Function).....	731
polytocompanion (Function).....	732
pop (Function).....	44
posfun (Property).....	138
postfix (Function).....	93
potential (Function).....	250
power_mod (Function).....	387
powerdisp (Option variable).....	27
powers (Function).....	197
powerseries (Function).....	372
powerset (Function).....	444
pred (Special symbol).....	103
prederror (Option variable).....	485
prefix (Function).....	94
prev_prime (Function).....	387
primep (Function).....	387
primep_number_of_tests (Option variable)....	387
principal_components (Function).....	526
print (Function).....	27
print_graph (Function).....	681
printf (Function).....	809
printfile (Function).....	177
printpois (Function).....	379
printprops (Function).....	138
prodrac (Function).....	401
product (Function).....	365
product_use_gamma (Option variable).....	788
program (draw_graph option).....	691
programmode (Option variable).....	270
prompt (Option variable).....	17
properties (Function).....	138
proportional_axes (Graphic option).....	595
props (System variable).....	139
propvars (Function).....	139
psexpand (Option variable).....	373
psfile (Plot option).....	168
psi (Function).....	219, 348
psubst (Function).....	73
ptriangularize (Function).....	732
pui (Function).....	395
pui_direct (Function).....	399
pui2comp (Function).....	395
pui2ele (Function).....	395
pui2polynome (Function).....	401
puireduc (Function).....	395
push (Function).....	45
put (Function).....	139
pv (Function).....	657

Q

qput (Function).....	139
qrangle (Function).....	520
qty (Function).....	649
quad_control (Function).....	260
quad_qag (Function).....	252
quad_qagi (Function).....	254
quad_qagp (Function).....	259
quad_qags (Function).....	253
quad_qawc (Function).....	255
quad_qawf (Function).....	256
quad_qawo (Function).....	257
quad_qaws (Function).....	258
quadrilateral (Graphic object).....	618
quantile (Function).....	519
quantile_bernoulli (Function).....	568
quantile_beta (Function).....	556
quantile_binomial (Function).....	566
quantile_cauchy (Function).....	563
quantile_chi2 (Function).....	549
quantile_continuous_uniform (Function).....	557
quantile_discrete_uniform (Function).....	570
quantile_exp (Function).....	553
quantile_f (Function).....	551
quantile_gamma (Function).....	556
quantile_general_finite_discrete (Function)	565
quantile_geometric (Function).....	569
quantile_gumbel (Function).....	564
quantile_hypergeometric (Function).....	571
quantile_laplace (Function).....	563
quantile_logistic (Function).....	558
quantile_lognormal (Function).....	555
quantile_negative_binomial (Function).....	572
quantile_noncentral_chi2 (Function).....	550
quantile_noncentral_student_t (Function)....	547
quantile_normal (Function).....	545
quantile_pareto (Function).....	559
quantile_poisson (Function).....	567
quantile_rayleigh (Function).....	560
quantile_student_t (Function).....	546
quantile_weibull (Function).....	559
quantile_skewness (Function).....	522
quit (Function).....	17
qunit (Function).....	387
quotient (Function).....	197

R

radcan (Function).....	112
radexpand (Option variable).....	112
radius (Function).....	682
radsubstflag (Option variable).....	202
random (Function).....	132
random_bernoulli (Function).....	569
random_beta (Function).....	557
random_binomial (Function).....	567
random_bipartite_graph (Function).....	671
random_cauchy (Function).....	563
random_chi2 (Function).....	550
random_continuous_uniform (Function).....	558
random_digraph (Function).....	671
random_discrete_uniform (Function).....	571
random_exp (Function).....	554
random_f (Function).....	552
random_gamma (Function).....	556
random_general_finite_discrete (Function)...	566

random_geometric (Function).....	570	read_xpm (Function).....	621
random_graph (Function).....	671	readline (Function).....	810
random_graph1 (Function).....	671	readonly (Function).....	18
random_gumbel (Function).....	564	real (Property).....	140
random_hypergeometric (Function).....	572	real_imagpart_to_conjugate (Function).....	825
random_laplace (Function).....	563	realonly (Option variable).....	270
random_logistic (Function).....	558	realpart (Function).....	120
random_lognormal (Function).....	555	realroots (Function).....	270
random_negative_binomial (Function).....	572	rearray (Function).....	55
random_network (Function).....	671	rectangle (Graphic object).....	618
random_noncentral_chi2 (Function).....	551	rectform (Function).....	120
random_noncentral_student_t (Function).....	548	rectform_log_if_constant (Function).....	825
random_normal (Function).....	545	recttopolar (Function).....	281
random_pareto (Function).....	559	rediff (Function).....	323
random_permutation (Function).....	445	redraw (draw_graph option).....	690
random_poisson (Function).....	568	reduce_consts (Function).....	782
random_rayleigh (Function).....	562	reduce_order (Function).....	785
random_regular_graph (Function).....	671	refcheck (Option variable).....	491
random_student_t (Function).....	546	region (Graphic object).....	618
random_tournament (Function).....	671	region_boundaries (Function).....	623
random_tree (Function).....	671	region_boundaries_plus (Function).....	623
random_weibull (Function).....	560	rem (Function).....	140
range (Function).....	519	remainder (Function).....	204
rank (Function).....	305, 732	remarray (Function).....	55
rassociative (Property).....	113	rembox (Function).....	73
rat (Function).....	197	remcomps (Function).....	318
ratalgdenom (Option variable).....	198	remcon (Function).....	316
ratchristof (Option variable).....	358	remcoord (Function).....	325
ratcoef (Function).....	198	remfun (Function).....	286
ratdenom (Function).....	198	remfunction (Function).....	471
ratdenomdivide (Option variable).....	198	remlet (Function).....	424
ratdiff (Function).....	199	remove (Function).....	140
ratdisrep (Function).....	200	remove_constvalue (Function).....	648
rateinstein (Option variable).....	358	remove_dimensions (Function).....	651
ratepsilon (Option variable).....	32	remove_edge (Function).....	686
ratexpand (Function).....	200	remove_fundamental_dimensions (Function).....	651
ratexpand (Option variable).....	200	remove_fundamental_units (Function).....	652
ratfac (Option variable).....	201	remove_vertex (Function).....	686
ratinterpol (Function).....	705	rempart (Function).....	778
rational (Function).....	779	remrule (Function).....	424
rational (Property).....	140	remsym (Function).....	322
rationalize (Function).....	32	remvalue (Function).....	414
ratmx (Option variable).....	305	rename (Function).....	315
ratnumer (Function).....	201	reset (Function).....	18
ratnump (Function).....	33	residue (Function).....	250
ratp (Function).....	201	resolvante (Function).....	401
ratprint (Option variable).....	201	resolvante_alternee1 (Function).....	404
ratriemann (Option variable).....	358	resolvante_bipartite (Function).....	405
ratsimp (Function).....	201	resolvante_diedrale (Function).....	405
ratsimpexpons (Option variable).....	202	resolvante_klein (Function).....	405
ratsubst (Function).....	202	resolvante_klein3 (Function).....	405
ratvars (Function).....	203	resolvante_produit_sym (Function).....	405
ratvars (System variable).....	203	resolvante_unitaire (Function).....	406
ratvarswitch (Option variable).....	203	resolvante_vierer (Function).....	406
ratweight (Function).....	204	rest (Function).....	45
ratweights (System variable).....	204	resultant (Function).....	205
ratweyl (Option variable).....	358	resultant (Option variable).....	205
ratwtlvl (Option variable).....	204	return (Function).....	485
read (Function).....	17	reveal (Function).....	74
read_array (Function).....	750	reverse (Function).....	45
read_binary_array (Function).....	751	revert (Function).....	373
read_binary_list (Function).....	751	revert2 (Function).....	373
read_binary_matrix (Function).....	751	rgb2level (Function).....	621
read_hashed_array (Function).....	750	rhs (Function).....	270
read_list (Function).....	750	ric (Variable).....	358
read_matrix (Function).....	750	ricci (Function).....	343
read_nested_list (Function).....	750	riem (Variable).....	358

riemann (Function)	344
rinvariant (Function)	345
risch (Function)	251
rk (Function)	633
rmxchar (Option variable)	305
rncombine (Function)	414
romberg (Function)	771
rombergabs (Option variable)	772
rombergit (Option variable)	772
rombergmin (Option variable)	772
rombertol (Option variable)	772
room (Function)	410
rootsconmode (Option variable)	271
rootscontract (Function)	271
rootsepsilon (Option variable)	272
round (Function)	118
row (Function)	305
rowop (Function)	732
rowswap (Function)	732
rreduce (Function)	445
run_testsuite (Function)	5
run_viewer (Plot option)	168

S

save (Function)	177
savedef (Option variable)	471
savefactors (Option variable)	205
saving (Function)	659
scalar (Property)	140
scalarmatrixp (Option variable)	305
scalarp (Function)	140
scaled_bessel_i (Function)	209
scaled_bessel_i0 (Function)	209
scaled_bessel_i1 (Function)	209
scalefactors (Function)	305
scanmap (Function)	485
scatterplot (Function)	532
scatterplot_description (Function)	532
schur2comp (Function)	396
sconcat (Function)	36
scopy (Function)	812
scsimp (Function)	113
scurvature (Function)	344
sdowncase (Function)	812
sec (Function)	129
sech (Function)	129
second (Function)	45
sequal (Function)	812
sequalignore (Function)	812
set_draw_defaults (Function)	577
set_edge_weight (Function)	682
set_partitions (Function)	447
set_plot_option (Function)	164
set_random_state (Function)	132
set_tex_environment (Function)	182
set_tex_environment_default (Function)	183
set_up_dot_simplifications (Function)	309
set_vertex_label (Function)	682
setcheck (Option variable)	491
setcheckbreak (Option variable)	491
setdifference (Function)	446
setelmx (Function)	306
setequalp (Function)	446
setify (Function)	446
setp (Function)	446
setunits (Function)	834

setup_autoload (Function)	414
setval (System variable)	492
seventh (Function)	45
sexplode (Function)	812
sf (Function)	363
shortest_path (Function)	682
shortest_weighted_path (Function)	683
show (Function)	316
show_edge_color (draw_graph option)	690
show_edge_type (draw_graph option)	690
show_edge_width (draw_graph option)	690
show_edges (draw_graph option)	690
show_id (draw_graph option)	689
show_label (draw_graph option)	689
show_vertex_color (draw_graph option)	690
show_vertex_size (draw_graph option)	690
show_vertex_type (draw_graph option)	690
show_vertices (draw_graph option)	689
show_weight (draw_graph option)	689
showcomps (Function)	318
showratvars (Function)	205
showtime (Option variable)	18
sierpinski (Function)	661
sierpinski (Function)	663
sign (Function)	146
signum (Function)	118
similaritytransform (Function)	306
simp (Option variable)	113
simp_inequality (Function)	825
simplified_output (Global variable)	843
simplify_products (Option variable)	786
simplify_sum (Function)	786
simplode (Function)	812
simpmetderiv (Function)	325
simpsum (Option variable)	366
simtran (Function)	306
sin (Function)	129
sinh (Function)	129
sinnpiflag (Option variable)	286
sinset (Function)	813
sinvertcase (Function)	813
sixth (Function)	45
skewness (Function)	522
skewness_bernoulli (Function)	569
skewness_beta (Function)	557
skewness_binomial (Function)	567
skewness_chi2 (Function)	549
skewness_continuous_uniform (Function)	557
skewness_discrete_uniform (Function)	570
skewness_exp (Function)	554
skewness_f (Function)	552
skewness_gamma (Function)	556
skewness_general_finite_discrete (Function)	566
skewness_geometric (Function)	570
skewness_gumbel (Function)	564
skewness_hypergeometric (Function)	571
skewness_laplace (Function)	563
skewness_logistic (Function)	558
skewness_lognormal (Function)	555
skewness_negative_binomial (Function)	572
skewness_noncentral_chi2 (Function)	551
skewness_noncentral_student_t (Function)	548
skewness_normal (Function)	545
skewness_pareto (Function)	559
skewness_poisson (Function)	567
skewness_rayleigh (Function)	562

skewness_student_t (Function).....	546	std_binomial (Function).....	566
skewness_weibull (Function).....	560	std_chi2 (Function).....	549
slength (Function).....	813	std_continuous_uniform (Function).....	557
smake (Function).....	813	std_discrete_uniform (Function).....	570
small_rhombicosidodecahedron_graph (Function)	671	std_exp (Function).....	553
small_rhombicuboctahedron_graph (Function) ..	671	std_f (Function).....	552
smax (Function).....	519	std_gamma (Function).....	556
smin (Function).....	518	std_general_finite_discrete (Function).....	565
smismatch (Function).....	813	std_geometric (Function).....	570
snowmap (Function).....	663	std_gumbel (Function).....	564
snub_cube_graph (Function).....	671	std_hypergeometric (Function).....	571
snub_dodecahedron_graph (Function).....	671	std_laplace (Function).....	563
solve (Function).....	272	std_logistic (Function).....	558
solve_rec (Function).....	786	std_lognormal (Function).....	555
solve_rec_rat (Function).....	787	std_negative_binomial (Function).....	572
solvedecomposes (Option variable).....	274	std_noncentral_chi2 (Function).....	551
solveexplicit (Option variable).....	275	std_noncentral_student_t (Function).....	548
solvefactors (Option variable).....	275	std_normal (Function).....	545
solvenullwarn (Option variable).....	275	std_pareto (Function).....	559
solveradcan (Option variable).....	275	std_poisson (Function).....	567
solvetrigrwarn (Option variable).....	275	std_rayleigh (Function).....	561
some (Function).....	447	std_student_t (Function).....	546
somrac (Function).....	401	std_weibull (Function).....	560
sort (Function).....	46	std1 (Function).....	517
space (Variable).....	811	stemplot (Function).....	533
sparse (Option variable).....	306	stirling (Function).....	805
sparse6_decode (Function).....	687	stirling1 (Function).....	448
sparse6_encode (Function).....	687	stirling2 (Function).....	449
sparse6_export (Function).....	687	strim (Function).....	815
sparse6_import (Function).....	687	strim1 (Function).....	815
specint (Function).....	223	strimr (Function).....	815
spherical (Graphic object).....	619	string (Function).....	36
spherical_bessel_j (Function).....	763	stringdisp (Option variable).....	36
spherical_bessel_y (Function).....	763	stringout (Function).....	178
spherical_hankel1 (Function).....	763	stringp (Function).....	811
spherical_hankel2 (Function).....	764	strong_components (Function).....	683
spherical_harmonic (Function).....	764	structures (Global variable).....	57
spherical_to_xyz (System function).....	165	struve_h (Function).....	222
splice (Function).....	456	struve_l (Function).....	222
split (Function).....	813	style (Plot option).....	168
sposition (Function).....	813	sublis (Function).....	75
spring_embedding_depth (draw_graph option) ..	691	sublis_apply_lambda (Option variable).....	75
sprint (Function).....	810	sublist (Function).....	47
sqfr (Function).....	205	sublist_indices (Function).....	47
sqrt (Function).....	125	submatrix (Function).....	306
sqrtdenest (Function).....	783	subnumsimp (Option variable).....	75
sqrtdispflag (Option variable).....	28	subnsample (Function).....	513
sremove (Function).....	813	subset (Function).....	450
sremovefirst (Function).....	814	subsetp (Function).....	450
sreverse (Function).....	814	subst (Function).....	76
ssearch (Function).....	814	subst_parallel (Function).....	826
ssort (Function).....	814	substinpart (Function).....	76
sstatus (Function).....	410	substpart (Function).....	77
ssubst (Function).....	814	substring (Function).....	815
ssubstfirst (Function).....	814	subvar (Function).....	55
staircase (Function).....	633	subvarp (Function).....	55
standardize (Function).....	513	sum (Function).....	366
standardize_inverse_trig (Function).....	825	sumcontract (Function).....	368
stardisp (Option variable).....	28	sumexpand (Option variable).....	368
starplot (Function).....	532	summand_to_rec (Function).....	788
starplot_description (Function).....	532	sumsplitfact (Option variable).....	122
stats_numer (Option variable).....	791	supcase (Function).....	815
status (Function).....	410	supcontext (Function).....	146
std (Function).....	517	surface_hide (Graphic option).....	596
std_bernoulli (Function).....	568	symbolp (Function).....	78
std_beta (Function).....	557	symmdifference (Function).....	450
		symmetric (Property).....	113

symmetricp (Function) 353
 system (Function) 410

T

t (Plot option) 168
 tab (Variable) 811
 take_channel (Function) 621
 take_inference (Function) 790
 tan (Function) 129
 tanh (Function) 129
 taylor (Function) 374
 taylor_logexpand (Option variable) 377
 taylor_order_coefficients (Option variable) .. 377
 taylor_simplifier (Function) 377
 taylor_truncate_polynomials (Option variable)
 377
 taylordepth (Option variable) 376
 taylorinfo (Function) 376
 taylorp (Function) 377
 taytorat (Function) 377
 tcl_output (Function) 415
 tcontract (Function) 397
 tellrat (Function) 206
 tellsimp (Function) 425
 tellsimpafter (Function) 426
 tensorkill (System variable) 359
 tentex (Function) 336
 tenth (Function) 48
 terminal (draw_graph option) 691
 terminal (Graphic option) 596
 test_mean (Function) 791
 test_means_difference (Function) 792
 test_normality (Function) 800
 test_proportion (Function) 795
 test_proportions_difference (Function) 797
 test_rank_sum (Function) 800
 test_sign (Function) 798
 test_signed_rank (Function) 798
 test_variance (Function) 794
 test_variance_ratio (Function) 794
 testsuite_files (Option variable) 5
 tex (Function) 179
 tex1 (Function) 180
 texput (Function) 180
 third (Function) 48
 throw (Function) 486
 time (Function) 410
 timedate (Function) 411
 timer (Function) 492
 timer_devalue (Option variable) 492
 timer_info (Function) 492
 title (Graphic option) 597
 tldfint (Function) 251
 tlimit (Function) 231
 tlimswitch (Option variable) 232
 to_lisp (Function) 18
 to_poly (Function) 826
 to_poly_solve (Function) 827
 todd_coxeter (Function) 407
 toeplitz (Function) 732
 tokens (Function) 815
 topological_sort (Function) 683
 totaldisrep (Function) 206
 totalfourier (Function) 287
 totient (Function) 387
 tpartpol (Function) 397

tr (Variable) 359
 tr_array_as_ref (Option variable) 473
 tr_bound_function_apply (Option variable) ... 473
 tr_file_tty_messagesp (Option variable) 473
 tr_float_can_branch_complex (Option variable)
 473
 tr_function_call_default (Option variable) ... 474
 tr_numer (Option variable) 474
 tr_optimize_max_loop (Option variable) 474
 tr_semicompile (Option variable) 474
 tr_state_vars (System variable) 474
 tr_warn_bad_function_calls (Option variable)
 474
 tr_warn_fexpr (Option variable) 474
 tr_warn_meval (Option variable) 474
 tr_warn_mode (Option variable) 475
 tr_warn_undeclared (Option variable) 475
 tr_warn_undefined_variable (Option variable)
 475
 tr_warnings_get (Function) 474
 trace (Function) 493
 trace_options (Function) 493
 tracematrix (Function) 779
 tranform_sample (Function) 515
 transcompile (Option variable) 471
 transform (Graphic option) 597
 transform_xy (Plot option) 168
 translate (Function) 472
 translate_file (Function) 472
 transparent (Graphic option) 598
 transpose (Function) 306
 transrun (Option variable) 473
 tree_reduce (Function) 450
 treefalse (Function) 661
 treillis (Function) 400
 treinat (Function) 400
 triangle (Graphic object) 619
 triangularize (Function) 306
 trigexpand (Function) 129
 trigexpandplus (Option variable) 130
 trigexpandtimes (Option variable) 130
 triginverses (Option variable) 130
 trigrat (Function) 131
 trigreduce (Function) 130
 trigsig (Option variable) 130
 trigsimp (Function) 130
 trivial_solutions (Global variable) 843
 true (Constant) 38
 trunc (Function) 377
 truncated_cube_graph (Function) 671
 truncated_dodecahedron_graph (Function) 672
 truncated_icosahedron_graph (Function) 672
 truncated_tetrahedron_graph (Function) 672
 ttyoff (Option variable) 28
 tube (Graphic object) 619
 tube_extremes (Graphic option) 598
 tutte_graph (Function) 672

U

ueivects (Function)	307
ufg (Variable)	358
uforget (Function)	835
ug (Variable)	358
ultraspherical (Function)	764
und (Constant)	38
underlying_graph (Function)	672
undiff (Function)	324
union (Function)	451
unique (Function)	48
unit_step (Function)	764
unit_vectors (Graphic option)	598
uniteigenvectors (Function)	307
unitp (Function)	650
units (Function)	648
unitvector (Function)	307
unknown (Function)	148
unless (Special operator)	486
unorder (Function)	78
unsum (Function)	378
untellrat (Function)	206
untimer (Function)	492
untrace (Function)	494
uppercasep (Function)	811
uric (Variable)	358
uricci (Function)	344
uriem (Variable)	358
uriemann (Function)	344
use_fast_arrays (Option variable)	55
user_preamble (Graphic option)	598
usersetunits (Optional variable)	837
uvect (Function)	307

V

values (System variable)	19
vandermonde_matrix (Function)	733
var (Function)	516
var_bernoulli (Function)	568
var_beta (Function)	557
var_binomial (Function)	566
var_chi2 (Function)	549
var_continuous_uniform (Function)	557
var_discrete_uniform (Function)	570
var_exp (Function)	553
var_f (Function)	552
var_gamma (Function)	556
var_general_finite_discrete (Function)	565
var_geometric (Function)	570
var_gumbel (Function)	564
var_hypergeometric (Function)	571
var_laplace (Function)	563
var_logistic (Function)	558
var_lognormal (Function)	555
var_negative_binomial (Function)	572
var_noncentral_chi2 (Function)	551
var_noncentral_student_t (Function)	547
var_normal (Function)	545
var_pareto (Function)	559
var_poisson (Function)	567
var_rayleigh (Function)	561
var_student_t (Function)	546
var_weibull (Function)	559
var1 (Function)	517
vect_cross (Option variable)	308
vector (Graphic object)	620

vectorpotential (Function)	307
vectorsimp (Function)	307
verbify (Function)	78
verbose (Option variable)	378
vers (Function)	781
vertex_color (draw_graph option)	689
vertex_coloring (draw_graph option)	690
vertex_coloring (Function)	684
vertex_connectivity (Function)	683
vertex_degree (Function)	683
vertex_distance (Function)	683
vertex_eccentricity (Function)	684
vertex_in_degree (Function)	684
vertex_out_degree (Function)	684
vertex_partition (draw_graph option)	690
vertex_size (draw_graph option)	689
vertex_type (draw_graph option)	689
vertices (Function)	684
vertices_to_cycle (Function)	691
vertices_to_path (Function)	691
view (Graphic option)	599

W

warnings (Global variable)	843
weyl (Function)	345
weyl (Variable)	359
wheel_graph (Function)	672
while (Special operator)	486
wiener_index (Function)	685
wired_surface (Graphic option)	599
with_stdout (Function)	179
write_binary_data (Function)	752
write_data (Function)	751
writefile (Function)	179
wronskian (Function)	779

X

x (Plot option)	168
x_voxel (Graphic option)	599
xaxis (Graphic option)	599
xaxis_color (Graphic option)	600
xaxis_secondary (Graphic option)	600
xaxis_type (Graphic option)	600
xaxis_width (Graphic option)	600
xlabel (Graphic option)	601
xlabel (Plot option)	169
xrange (Graphic option)	601
xrange_secondary (Graphic option)	601
xreduce (Function)	451
xthru (Function)	113
xtics (Graphic option)	601
xtics_axis (Graphic option)	602
xtics_rotate (Graphic option)	602
xtics_rotate_secondary (Graphic option)	602
xtics_secondary (Graphic option)	602
xtics_secondary_axis (Graphic option)	602
xu_grid (Graphic option)	602
xy_file (Graphic option)	603
xyplane (Graphic option)	603

Y

y (Plot option).....	169
y_voxel (Graphic option).....	603
yaxis (Graphic option).....	603
yaxis_color (Graphic option).....	603
yaxis_secondary (Graphic option).....	604
yaxis_type (Graphic option).....	604
yaxis_width (Graphic option).....	604
ylabel (Graphic option).....	604
ylabel (Plot option).....	169
yrange (Graphic option).....	605
yrange_secondary (Graphic option).....	605
yticks (Graphic option).....	605
yticks_axis (Graphic option).....	605
yticks_rotate (Graphic option).....	605
yticks_rotate_secondary (Graphic option).....	605
yticks_secondary (Graphic option).....	606
yticks_secondary_axis (Graphic option).....	606
yv_grid (Graphic option).....	606

Z

z (Plot option).....	169
z_voxel (Graphic option).....	606
zaxis (Graphic option).....	606
zaxis_color (Graphic option).....	606

zaxis_type (Graphic option).....	607
zaxis_width (Graphic option).....	607
Zeilberger (Function).....	842
zeroa (Constant).....	38
zerob (Constant).....	39
zerobern (Option variable).....	387
zeroequiv (Function).....	148
zerofor (Function).....	733
zeromatrix (Function).....	308
zeromatrixp (Function).....	733
zeta (Function).....	388
zeta%pi (Option variable).....	388
zlabel (Graphic option).....	607
zlabel (Plot option).....	169
zlange (Function).....	711
zn_log (Function).....	388
zn_order (Function).....	389
zn_primroot (Function).....	390
zn_primroot_limit (Option variable).....	391
zn_primroot_p (Function).....	391
zn_primroot_pretest (Option variable).....	391
zn_primroot_verbose (Option variable).....	391
zrange (Graphic option).....	607
ztics (Graphic option).....	608
zticks_axis (Graphic option).....	608
zticks_rotate (Graphic option).....	608